

INTERNATIONAL TOPKAPI CONGRESS-VI

January 9-11, 2026 / Istanbul, Türkiye

THE BOOK OF FULL TEXTS



EDITED BY
Prof. Dr. Arif GÖK

ISBN: 979-8-89695-315-9

INTERNATIONAL TOPKAPI CONGRESS VI

THE BOOK OF FULL TEXTS

**EDITED BY
Prof. Dr. Arif GÖK**

By Liberty Publishing House
Water Street Corridor New York, NY 10038
www.libertyacademicbooks.com
+1 (314) 597-0372

ALL RIGHTS RESERVED NO PART OF THIS BOOK MAY BE
REPRODUCED IN ANY FORM, BY PHOTOCOPYING OR BY ANY
ELECTRONIC OR MECHANICAL MEANS, INCLUDING
INFORMATION STORAGE OR RETRIEVAL SYSTEMS, WITHOUT
PERMISSION IN WRITING FROM BOTH THE COPYRIGHT OWNER
AND THE PUBLISHER OF THIS BOOK.

© Liberty Academic Publishers 2025

The digital PDF version of this title is available Open Access and distributed
under the terms of the Creative Commons Attribution-Non-Commercial 4.0
license (<http://creativecommons.org/licenses/by-nc/4.0/>) which permits
adaptation, alteration, reproduction and distribution for noncommercial use,
without further permission provided the original work is attributed. The
derivative works do not need to be licensed on the same terms.

adopted by Mariam Rasulan

www.izdas.org/topkapi

**Issued: 25.01.2026
ISBN: 979-8-89695-315-9**

CONGRESS ID

INTERNATIONAL TOPKAPI CONGRESS VI

DATE AND PLACE

January 9-11, 2026 / Istanbul

PRESENTATION

Online/ In-person

ORGANIZING COMMITTEE

Dr. Bülent BAYRAKTAR - Bayburt University

Dr. Froilan Mobo - Philippine Merchant Marine Academy

**Assoc. Prof Dr. Ethem İlhan ŞAHİN - Adana Alparslan Türkeş
Science and Technology University**

Dr. Viola MAKHZOUM - Islamic University of Lebanon

Dr. Terane NAGIYEVA - Azerbaijan State Pedagogical University

**Dr. Metanet Şahaliyeva - ANAS, Institute of Manuscripts named
after Muhammad Fuzuli**

Dr. Mehmet Kadri AKYÜZ - Dicle University

COORDINATOR

Gulnaz GAFUROVA

PARTICIPANT COUNTRIES:

**Turkiye, Azerbaijan, TRNC, USA, Romania, Algeria, India, Bangladesh,
Nigeria, Iran, Georgia, Indonesia, Albania, Morocco, Vietnam, Italy,
Moldova, Afganistan**

TOTAL NUMBER OF PAPERS

132

THE NUMBER OF PAPERS FROM TÜRKİYE

64

OTHER COUNTRIES

68

EVALUATION PROCESS

All applications have undergone a double-blind peer review process

SCIENTIFIC & REVIEW COMMITTEE

Assoc. Prof. Dr. Gulbaxar TAVALDIEVA - Tashkent Institute of Chemical Technology

Assoc. Prof. Dr. Rabihan YÜKSEL ARABACI - Bursa Uludag University

Assoc. Prof. Dr. Bülent BAYRAKTAR - Bayburt University

Assoc. Prof. Dr. Huseyin CIHAN- Bursa Uludag University

Assoc. Prof. Dr. Nuray DEMİR, Atatürk University

Assoc. Prof. Dr. İryna DRYGA - National Academy of Sciences

Assoc. Prof. Dr. Cavit POLAT - Kahramanmaraş Sütçü İmam University

Assoc. Prof. Dr. Hüseyin ERİŞ- Harran University

Assoc. Prof. Dr. Mehmet Emin KALGI - Ardahan University

Dr. Esmâ DEMİREZEN -İstanbul University -Cerrahpaşa

Dr. Viola MAKHZOUM - Islamic University of Lebanon

Dr. Terane NAGIYEVA - Azerbaijan State Pedagogical University

Dr. Damejan SADYKOVA - Kazakh State Women's Pedagogical University

Dr. Mariam S. OLSSON - Lebanese University

Dr. Burcu TEMEL - Adıyaman University

Dr. Elvan CAFAROV- Azerbaijan State Pedagogy University

Dr. Fatih GÜRBÜZ - Bayburt University

Dr. Filiz AYGÜN ERTÜRK - Bayburt University

Dr. Nuray DEMİR, Atatürk University

Dr. Murat GENÇ - Atatürk University

Dr. Seda KIZIL - Bayburt University

Dr. Vecihi AKSAKAL - Bayburt University

Dr. Zila Özlem KIRBAŞ - Bayburt University

PHOTO GALLERY



PHOTO GALLERY



PHOTO GALLERY



PHOTO GALLERY



PHOTO GALLERY



PHOTO GALLERY



PHOTO GALLERY



PHOTO GALLERY

Meeting Dr. Samet Başı's screen

Observer hall 2 Dr. Samet Başı H2- Zeynep Kumaz Okan Yetişen... Hall 2- Dr. Ferhat Atik Feride Tagiyeva

6. ULUSLARARASI
TOPKAPI
BİLİMSEL ARAŞTIRMALARDA GÜNCEL GELİŞMELER KONGRESİ
9-11 Ocak 2026, İstanbul

**Anlatısal Maruz Bırakma
Terapisinin Yas Sürecinde
Kullanımı: Sistematik Bir
Derleme**

KTÜ
Dr. Samet Başı
Karadeniz Teknik Üniversitesi
Psikoloji Bölümü

Participants (8)

Observer hall 2 (Co-host, me)
Dr. Samet Başı
Feride Tagiyeva
H2- Zeynep Kumaz
Hall 2- Dr. Ferhat Atik
Hall-2 Özkan Öztürk
Okan Yetişen
Valide Aliyeva

Audio Video Participants Chat React Share Apps Pause/stop recording Breakout rooms More Leave room

Meeting H2- Zeynep Kumaz's screen

Observer hall 2 H2- Zeynep Kumaz Hall 2- Dr. Ferhat Atik Dr. Samet Başı Valide Aliyeva

Kongre Süresi: 4:12

Yaşlanmak Görünmez Olmaktır

Fiziksel yaşlanma belirtileri ne kadar 'görünür' hale gelirse, kadınlar sosyal olarak o kadar 'görünmez' olurlar. Gençlik idealinden uzaklaştıkça, toplumda 'sadece yaşlı bir teyze' olarak etiketlenir ve bireysel kimlikleri yok sayılır.

**'Eğer genç değilseniz veya genç görünmüyorsanız...
görünmez olduğunuzu hissediyorsunuz.'**

Kavram: Bazı kadınlar bu durumu, fark edilmek için çaba göstermediklerinde 'seffaf yaşlı kadınlara' (transparent old women) dönüştüklerini belirterek açıklar.
Kurnaz & Öztürk

Participants (9)

Observer hall 2 (Co-host, me)
H2- Zeynep Kumaz
Dr. Samet Başı
Feride Tagiyeva
Hall 2- Dr. Ferhat Atik
Hall-2 Özkan Öztürk
Okan Yetişen
Valide Aliyeva
Valide Aliyeva

Audio Video Participants Chat React Share Apps Pause/stop recording More Leave room

PHOTO GALLERY

Meeting - HALL 2

Recording...

View

H2- Zeynep Kumaz

Observer hall 2

Hall-2 Özkan Öztürk

Hall 2- Dr. Ferhat Atik

Dr. Samet Bağ

Valida Aliyeva

defne erdem mete

Feride Tagiyeva

Valida Aliyeva

Okan Yetişensoy

Participants (10)

Search

Observer hall 2 (Co-host, me)

H2- Zeynep Kumaz

Valida Aliyeva

defne erdem mete

Dr. Samet Bağ

Feride Tagiyeva

Hall 2- Dr. Ferhat Atik

Hall-2 Özkan Öztürk

Okan Yetişensoy

Valida Aliyeva

Mute all

More

Audio

Video

Participants

Chat

React

Share

Apps

Pause/stop recording

More

Leave room

Meeting

H2- Zeynep Kumaz's screen

Recording...

View

Observer hall 2

H2- Zeynep Kumaz

Hall 2- Dr. Ferhat Atik

Dr. Samet Bağ

Valida Aliyeva

Künye Sürve ağı

Search

Süreç Olarak Erkek, Nesne Olarak Kadın



ERKEK BEDENİ: BİR SÜREÇ

Algı: Beden, işleyen, hareket eden ve bir amaca hizmet eden dinamik bir 'süreç' olarak görülür.

Odak Noktası: Nasıl görüldüğü değil, ne kadar etkili çalıştığıdır. İşlevsellik, Güç, Etkinlik.

Yaşlanmanın Yorumu: Fiziksel değişimler, 'olgunluk' ve 'karizma' olarak kodlanır. Kültür, erkekler için 'oğlan çocuğu' ve 'adam' olmak üzere iki güzellik standardına izin verir.



KADIN BEDENİ: BİR NESNE

Algı: Beden, dışarıdan izlenen ve estetik kriterlere göre yargılanan parçaların bir toplamı olan statik bir 'nesne' olarak görülür.

Odak Noktası: Bedenin kendisi bir 'görüntü'dür. Estetik, Değer, Çekicilik.

Yaşlanmanın Yorumu: Değişimler, gençlik standardından ('kız çocuğu') uzaklaşma olarak görülür ve 'çöküş' veya 'değer kaybı' olarak algılanır.

Kumaz & Öztürk

Audio

Video

Participants

Chat

React

Share

Apps

Pause/stop recording

More

Leave room

Participants (10)

Search

Observer hall 2 (Co-host, me)

H2- Zeynep Kumaz

defne erdem mete

Dr. Samet Bağ

Feride Tagiyeva

Hall 2- Dr. Ferhat Atik

Hall-2 Özkan Öztürk

Okan Yetişensoy

Valida Aliyeva

Valida Aliyeva

Mute all

More

PHOTO GALLERY




PHOTO GALLERY

Observer hall-1

Dilara Karakılıç

ERGENLERDE STRES VE DUYGUSAL ZEKA ARASINDAKİ İLİŞKİNİN SİSTEMATİK BİR İNCELEMESİ
A SYSTEMATIC EXAMINATION OF THE RELATIONSHIP BETWEEN STRESS AND EMOTIONAL INTELLIGENCE IN ADOLESCENTS

Prof.Dr. Fatma Ebru İKİZ
Dokuz Eylül Üniversitesi, Buca Eğitim Fakültesi,
Psikolojik Danışmanlık ve Rehberlik Bölümü

Yüksek Lisans Öğrencisi Yusuf Erdem YILDIR
Dokuz Eylül Üniversitesi, Buca Eğitim Fakültesi,
Psikolojik Danışmanlık ve Rehberlik Bölümü

Not eklemek için tıklayın

10:38 9.01.2025

Observer hall-1

Dilara Karakılıç

ERGENLERDE STRES VE DUYGUSAL ZEKA ARASINDAKİ İLİŞKİNİN SİSTEMATİK BİR İNCELEMESİ
A SYSTEMATIC EXAMINATION OF THE RELATIONSHIP BETWEEN STRESS AND EMOTIONAL INTELLIGENCE IN ADOLESCENTS

Prof.Dr. Fatma Ebru İKİZ
Dokuz Eylül Üniversitesi, Buca Eğitim Fakültesi,
Psikolojik Danışmanlık ve Rehberlik Bölümü

Yüksek Lisans Öğrencisi Yusuf Erdem YILDIR
Dokuz Eylül Üniversitesi, Buca Eğitim Fakültesi,
Psikolojik Danışmanlık ve Rehberlik Bölümü

Aramak için buraya yazın

10:38 9.01.2025

PHOTO GALLERY





PHOTO GALLERY





PHOTO GALLERY

The screenshot displays a Zoom meeting interface. At the top, the meeting title is "Hall 1- Doç. Dr. Arzu ÇAĞLAR". The participants list on the right includes "Observer hall-1", "Hall 1- Doç. Dr. Arzu ÇAĞLAR", "Doç Dr Arzu çağlar", "HALL-1, Ahmet ULUDÖĞAN", "HALL-1, Raniyah RAPEA", and "Hall-1 Dr. Yunus ERKUŞ". The main window shows a PowerPoint presentation titled "YEŞİL BİNA KAVRAMI: DÜNYA'DAN VE TÜRKİYE'DEN ÖRNEKLER" (Green Building Concept: Examples from the World and Turkey). The presentation is by Doç. Dr. Arzu ÇAĞLAR, Dr. Öğretim Üyesi Hakan ÇAĞLAR, Volkan GÖNEN, and Beyza GÖNEN. The slide content includes the title, the authors' names, and a list of references. The bottom of the screen shows the Windows taskbar with the search bar and system clock.

Observer hall-1

Doç Dr Arzu çağlar

Kabılımlar (6)

- Observer... (Ortak oturum sahibi, ben)
- Hall 1- Doç. Dr. Arzu ÇAĞLAR
- Doç Dr Arzu çağlar
- HALL-1, Ahmet ULUDÖĞAN
- HALL-1, Raniyah RAPEA
- Hall-1 Dr. Yunus ERKUŞ

YEŞİL BİNA KAVRAMI: DÜNYA'DAN VE TÜRKİYE'DEN ÖRNEKLER

Doç. Dr. Arzu ÇAĞLAR
Dr. Öğretim Üyesi Hakan ÇAĞLAR
Volkan GÖNEN
Beyza GÖNEN

Not eklemek için tıklayın

Aramak için buraya yazın

15:11
9.01.2025

Observer hall-1

Doç Dr Arzu çağlar

HALL-1, Raniyah...

Çelik Cürufunun Esnek Üstyapının Mekanik Özellikleri
Üzerindeki Etkisinin Sonlu Elemanlar Yöntemiyle
Araştırılması

Dr. Öğr. Üyesi Yunus ERKUŞ
Dilay AKSAKAL

Aramak için buraya yazın

15:41
9.01.2025

PHOTO GALLERY

The screenshot displays a Zoom meeting interface. At the top, three video thumbnails are visible: 'Observer hall-1', 'Doç Dr Arzu ca...', and another participant. The main screen shows a presentation slide titled 'İÇ MEKANDA KONFORUN SAĞLANMASI İÇİN YAPAY ZEKA UYGULAMALARI' (Indoor Comfort Provided by AI Applications). The slide features a futuristic robot head and lists the preparers: 'HAZIRLAYANLAR: AHMET ULUDOĞAN, PROF.DR.ARIF GÖK'. The Zoom toolbar at the bottom includes icons for chat, video, audio, and other controls. On the right, a 'Katılımcılar (10)' (Participants) list is shown, including 'Observer Hall-2', 'Hall-2, EDA GÖRGÜN', 'Hall-2, Prof.Dr. Arif Gök', and others. The bottom status bar shows 'Ses' (Audio), 'Video', 'Katılımcılar' (Participants), 'Sohbet' (Chat), 'Tepki ver' (React), 'Paylaş' (Share), 'Toplantı bilgileri' (Meeting Info), 'Uygulamalar' (Apps), 'Ara odalar' (Breakout Rooms), 'Daha fazla' (More), and 'Oda dışı çık' (Leave Room).

Observer hall-1

Doç Dr Arzu ca...

İÇ MEKANDA KONFORUN SAĞLANMASI
İÇİN YAPAY ZEKA UYGULAMALARI

HAZIRLAYANLAR:
AHMET ULUDOĞAN
PROF.DR.ARIF GÖK

zoom Workplace

Observer Hall-2

KATILIMCILAR (10)

İÇ MEKÂNDA YENİ NESİL
MALZEMELERİN KULLANIMI
VE ÖRNEK UYGULAMALAR

- Eda Görgün
- Teknoloji ve İnovasyon Yönetimi AED
- Danışman; Prof. Dr. Arif Gök

INTERNATIONAL TOPKAPI CONGRESS

Ses Video Katılımcılar Sohbet Tepki ver Paylaş Toplantı bilgileri Uygulamalar Ara odalar Daha fazla Oda dışı çık

Katılımcılar (10)

Observer Hall-2

Hall-2, EDA GÖRGÜN

Hall-2, Prof.Dr. Arif Gök

Hall-2, Dr.Ömer ÖZKAN

Hall-2, Merve Çakır

Hall-2, Nurgül Zengin

Meltem Ali Dumlulu

Tümünü Sesize Al

PHOTO GALLERY

The image displays two screenshots of a Zoom meeting interface, likely from a virtual conference. The top screenshot shows a presentation slide titled "YAPAY ZEKA DESTEKLİ MALZEME SEÇİM SİHİRBAZI" (Artificial Intelligence-Powered Material Selection Wizard) by Nagehan TESELEK and Prof. Dr. Arif GÖK. The bottom screenshot shows a presentation slide titled "6. ULUSLARARASI TOPKAPI BİLİMSEL ARAŞTIRMALARDA GÜNCEL GELİŞMELER KONGRESİ" (6th International Topkapi Scientific Researches in Current Developments Congress) by Yunus Bulut and Prof. Dr. Arif Gök. Both screenshots show a Zoom meeting with participants from Hall 2 and a list of attendees on the right.

Top Screenshot:

- Zoom Meeting Title:** HALL 2 NAGEHAN TESELEK adlı k...
- Participants:** Observer Hall-2, Hall-2: EDA GÖRGÜN, Hall-2: Prof.Dr. Arif Gök, HALL 2 NAGEHAN TESELEK, Hall 2: Eceem Korkmaz.
- Slide Content:**
 - YAPAY ZEKA DESTEKLİ MALZEME SEÇİM SİHİRBAZI**
ARTIFICIAL INTELLIGENCE-POWERED MATERIAL SELECTION WIZARD
 - Nagehan TESELEK**
Dumlupınar Üniversitesi, Lisansüstü Eğitim Enstitüsü,
Teknoloji ve İnovasyon Yönetimi Bölümü
 - Prof. Dr. Arif GÖK**
Dumlupınar Üniversitesi, Mimarlık Fakültesi,
Endüstriyel Tasarım Bölümü
- Attendees List (10):**
 - Observer... (Örnek oturum sahibi, ben)
 - H2: HALL 2 NAGEHAN TESELEK
 - Hall 2: Prof.Dr. Arif Gök
 - H2: Hall 2 - Yunus Bulut
 - H2: Hall 2: Eceem Korkmaz
 - H2M: HALL-2 MERVE ÇAKIR
 - HD: Hall-2: Dr.Ömer ÖZKAN
 - E: Hall-2: EDA GÖRGÜN
 - HN: Hall 2: Nürten Gökyiğit Zengin
 - MA: Mehmet Ali Dumlulu

Bottom Screenshot:

- Zoom Meeting Title:** Hall 2 - Yunus Bulut adlı toplantı
- Participants:** Observer Hall-2, Hall-2: Prof.Dr. Arif Gök, Hall 2 - Yunus Bulut, HALL 2 NAGEHAN TESELEK, Hall 2: Eceem Korkmaz.
- Slide Content:**
 - 6. ULUSLARARASI TOPKAPI BİLİMSEL ARAŞTIRMALARDA GÜNCEL GELİŞMELER KONGRESİ**
 - YAPAY ZEKANIN FİKRİ VE SİNAI MÜLKİYET HAKLARI AÇISINDAN KULLANIMI**
THE USE OF ARTIFICIAL INTELLIGENCE WITHIN THE FRAMEWORK OF INTELLECTUAL AND INDUSTRIAL PROPERTY RIGHTS
 - HAZIRLAYANLAR: YUNUS BULUT PROF. DR. ARIF GÖK**
- Attendees List (10):**
 - Observer... (Örnek oturum sahibi, ben)
 - H2: Hall 2 - Yunus Bulut
 - Hall 2: Prof.Dr. Arif Gök
 - H2: Hall 2: Eceem Korkmaz
 - H2: HALL 2 NAGEHAN TESELEK
 - H2M: HALL-2 MERVE ÇAKIR
 - HD: Hall-2: Dr.Ömer ÖZKAN
 - E: Hall-2: EDA GÖRGÜN
 - HN: Hall 2: Nürten Gökyiğit Zengin
 - MA: Mehmet Ali Dumlulu

PHOTO GALLERY

The image displays two screenshots of a Zoom meeting interface. The top screenshot shows a presentation slide titled "6. ULUSLARARASI TOPKAPI BİLİMSEL ARAŞTIRMALARDA GÜNCEL GELİŞMELER KONGRESİ" (6th International Topkapi Scientific Research and Development Congress). The slide also mentions "YAPAY ZEKÂNIN İŞLETMELERİN GELİŞİMİNDE ROLÜ VE KULLANIM ALANLARI" (The Role and Use of Artificial Intelligence in the Development of Enterprises) and lists the organizers as "HAZIRLAYANLAR Nurten GÖKYİĞİT ZENGİN Prof. Dr. Arif GÖK". The bottom screenshot shows a presentation slide titled "6. ULUSLARARASI TOPKAPI KONGRESİ" (6th International Topkapi Congress) with the subtitle "AR-GE ÇALIŞMALARINDA YAPAY ZEKÂ KULLANIMI" (Use of Artificial Intelligence in Research and Development Work). The slide lists the presenter as "MEHMET ALİ DURLU" from "KÜTAHYA DURLUPINAR ÜNİVERSİTESİ, LİSANSÜSTÜ EĞİTİM ENSTİTÜSÜ, TEKNOLOJİ VE İNOVASYON YÖNETİMİ" (Kütahya Durlupınar University, Graduate School of Technology and Innovation Management) and the supervisor as "DANIŞMAN: PROF. DR. ARIF GÖK". The date "09.01.2026" is also visible. Both screenshots show a Zoom meeting window with a toolbar at the bottom and a participant list on the right.

Top Screenshot:

Zoom Workplace | Toplantı | Hall-2, Nurten Gökyiğit Zengin ac | Kaydediliyor... | Görüntüle

Observer Hall-2 | Observer Hall-2 | Hall-2, Prof.Dr. Arif Gök | Hall-2, Yunus Bulut | Mehmet Ali Durlu | Hall-2, Nurten Gökyiğit Zengin

6. ULUSLARARASI TOPKAPI BİLİMSEL ARAŞTIRMALARDA GÜNCEL GELİŞMELER KONGRESİ

YAPAY ZEKÂNIN İŞLETMELERİN GELİŞİMİNDE ROLÜ VE KULLANIM ALANLARI

HAZIRLAYANLAR
Nurten GÖKYİĞİT ZENGİN
Prof. Dr. Arif GÖK

Ses | Video | Katılımcılar | Sohbet | Tepki ver | Paylaş | Toplantı bilgileri | Uygulamalar | Ara odalar | Daha fazla | Odadan çık

Katılımcılar (10)

Q Katılımcı bul

- OH Observ... (Ortak oturum sahibi, ben)
- HN Hall-2, Nurten Gökyiğit Zengin
- Hall-2, Prof.Dr. Arif Gök
- MA Mehmet Ali Durlu
- H2 Hall 2 - Yunus Bulut
- H2 Hall 2 Eoem Korkmaz
- H2 HALL 2 NAGEHAN TESELEK
- HM HALL-2 MERVE ÇAKIR
- HD Hall-2, Dr.Ömer ÖZKAN
- E Hall-2, EDA GÖRGÜN

Tümünü Gözetle

Bottom Screenshot:

Zoom Workplace | Toplantı | Mehmet Ali Durlu adlı kişiyi se | Kaydediliyor... | Görüntüle

Observer Hall-2 | Observer Hall-2 | Hall-2, Prof.Dr. Arif Gök | Hall-2, Yunus Bulut | Hall-2, Nurten Gökyiğit Zengin | Mehmet Ali Durlu

6. ULUSLARARASI TOPKAPI KONGRESİ

AR-GE ÇALIŞMALARINDA YAPAY ZEKÂ KULLANIMI

MEHMET ALİ DURLU
KÜTAHYA DURLUPINAR ÜNİVERSİTESİ, LİSANSÜSTÜ EĞİTİM ENSTİTÜSÜ,
TEKNOLOJİ VE İNOVASYON YÖNETİMİ
DANIŞMAN: PROF. DR. ARIF GÖK

09.01.2026

Ses | Video | Katılımcılar | Sohbet | Tepki ver | Paylaş | Toplantı bilgileri | Uygulamalar | Ara odalar | Daha fazla | Odadan çık

Katılımcılar (10)

Q Katılımcı bul

- OH Observ... (Ortak oturum sahibi, ben)
- MA Mehmet Ali Durlu
- Hall-2, Prof.Dr. Arif Gök
- H2 Hall 2 - Yunus Bulut
- H2 Hall 2 Eoem Korkmaz
- H2 HALL 2 NAGEHAN TESELEK
- HM HALL-2 MERVE ÇAKIR
- HD Hall-2, Dr.Ömer ÖZKAN
- E Hall-2, EDA GÖRGÜN
- HN Hall-2, Nurten Gökyiğit Zengin

Tümünü Gözetle

PHOTO GALLERY

zoom Workplace Toplantı Hall 2 - Yunus Bulut adlı kişinin ekranı

Observer Hall-2

Hall-2 MERVE ÇAKIR

Observer Hall-2

Hall-2 EDA GÖRGÜN

Hall-2 Prof.Dr. Arif Gök

Hall-2 Yunus Bulut

Mehmet Ali Dumlulu

Hall-2 NAGHAN TESELEK

Hall-2 Nürten Gökyiğit Zengin

Hall-2 Dr.Omer OZKAN

Hall-2 Ecem Korkmaz

Katılımcılar (10)

Q Katılımcı bul

- OH Observ... (Ortak oturum sahibi, ben)
- H2 Hall 2 - Yunus Bulut
- H2 Hall-2 Prof.Dr. Arif Gök
- H2 Hall-2 Ecem Korkmaz
- H2 Hall-2 NAGHAN TESELEK
- HM Hall-2 MERVE ÇAKIR
- HO Hall-2 Dr.Omer OZKAN
- E Hall-2 EDA GÖRGÜN
- HN Hall-2 Nürten Gökyiğit Zengin
- MA Mehmet Ali Dumlulu

Tümünü Sessize Al

zoom Workplace Toplantı Hall -2, DUYGU ÇELİK adlı kişinin ekranı Kaydediliyor... Görüntüle

Observer Hall-2

Hall-2, sinan güllüer

Observer Hall-2

Hall-2, DUYGU ÇELİK

Adnan Celik

Hall-2, Cem Erhan Arslan

Malide

Belma Midilli Döner

Aliyeva Maralhanım Hall 2, Session 3

Katılımcılar (8)

Q Katılımcı bul

- OH Observ... (Ortak oturum sahibi, ben)
- H Hall -2, DUYGU ÇELİK
- AC Adnan Celik
- AM Aliyeva Maralhanım Hall 2, Session 3
- BM Belma Midilli Döner
- HC Hall-2, Cem Erhan Arslan
- HS Hall-2, sinan güllüer
- M Maide

Tümünü Sessize Al

Ses Video Katılımcılar Sohbet Tezki ver Paylaş Toplantı bilgileri Uyarılar Ara odalar Daha fazla Otastan çık

PHOTO GALLERY




PHOTO GALLERY




PHOTO GALLERY





PHOTO GALLERY

Zoom Workplace

Toplantı

Mehmet İsayev adlı kişinin ekranı

Görüş yapın

Kayıtlıdır...

Görüntüle

Observer hall 3

Hall-3, Erol Venice

Observer hall 3

Tuğba Balıkcı

HALL-3 / Hakan Yurtkuran

SESSION-1 / HA...

Mehmet İsayev

SESSION-1 / HALL-3 - Nurullah ORAL

Mevlüt Karakaya

rabia nur çay

Windows'u Etkinleştir

Windows'u etkinleştirmek için Ayarlar'a gidin.

Ses

Video

Katılımcılar

Sohbet

Tepki ver

Paylaş

Toplantı bilgileri

Uygulamalar

Kayıtlıdır/durdur

Ara odalar

Daha fazla

Odanın çık

10:35

9.01.2026

Bulguların Anlamı: Neden +1.48 dB Fark Yaratıyor?

- Yüksek Ayırt Edicilik Gücü: Gözlemlendiğimiz +1.48 dB'lik fark, literatürde daha düşük frekanslarda (5-10 GHz) rapor edilen ortalama 0.3-0.7 dB'lik farkların yaklaşık 3 katıdır.
- Fiziksel Neden: Milimetre dalgası bandındaki kısa dalga boyu, enerjinin çok küçük bir alana odaklanmasını sağlar. Bu 'yüksek çözünürlük', 20 μm gibi çok ince hücresel tabakalardaki dielektrik değişimlere karşı hassasiyeti önemli ölçüde artırır.

Sonuç: 24 GHz bandı, hücresel düzeyde kanser tespiti için kritik bir 'tanısal pencere' potansiyeli sunmaktadır.

Düşük Frekans (örn. 5-10 GHz)

Milimetre Dalgası (24 GHz)

20 μm

$\Delta S_{21} \approx 0.3-0.7 \text{ dB}$

$\Delta S_{21} \approx +1.48 \text{ dB}$

Observer hall 3

Hall-3, Erol Venice

Observer hall 3

Tuğba Balıkcı

HALL-3 / Hakan Yurtkuran

Mevlüt Karakaya

SESSION-1 / HA...

rabia nur çay

SESSION-1 / HALL-3 - Nurullah ORAL

Windows'u Etkinleştir

Windows'u etkinleştirmek için Ayarlar'a gidin.

Ses

Video

Katılımcılar

Sohbet

Tepki ver

Paylaş

Toplantı bilgileri

Uygulamalar

Kayıtlıdır/durdur

Ara odalar

Daha fazla

Odanın çık

10:47

9.01.2026

PHOTO GALLERY




PHOTO GALLERY




PHOTO GALLERY

RESEARCH MODEL (HYPOTHESES)

We tested five potential drivers of AR adoption:

- H1: Entertainment** (Fun/Amusement)
- H2: Pass Time** (Relieving Boredom)
- H3: Convenience** (Ease of Use)
- H4: Social Interaction** (Connecting/Belonging)
- H5: Trendiness** (Novelty/FOMO)

H1: Entertainment → ++
H2: Pass Time → ++
H3: Convenience → ++
H4: Social Interaction → ++
H5: Trendiness → + (tested empirically)

Observer hall 3

Windows'u Etkinleştir

Windows'u etkinleştirmek için Ayarlar'a gidin.

19:43 9.01.2024

Vinorelbine

Vinorelbine, yarı sentetik bir Vinca alkaloidi türevidir ve mitotik iç iplikçiklerini bozan, dolayısıyla kromozomların düzgün ayrılmasını engelleyen bir ilaçtır. Bu etkisiyle hücreleri mitozun G2/M fazında durdurur.

İlacın yapısı, tubulin proteiniyle geri dönüşümlü bir kovalent bağ kurmasına olanak verir; bu bağ mikrotübül oluşumunu bozarak hücre iskeletini etkiler.

Vinorelbine'in bu etkileri;

Mitotik içgileri bozarak hücre bölünmesini engeller. Vinorelbine, hücrelerin metafaz evresinde uzun süre kalmasına ve bölünmeyi tamamlayamamasına yol açar. Bu durumda hücreler DNA'yı replike eder ama sitokinez olmaz, yani hücre bölünemez. Bu durumun sonunda hücre ölür.

Diğer: Pavren et al. "Anticancer potential of alkaloids: a key emphasis to colchicine, vinblastine, vincristine, vindesine, vinorelbine and vincamine." *Cancer cell international* vol. 22, 1 206. 2 Jan. 2022. doi:10.1186/s12935-022-02634-9 <https://www.sciencefacts.net/cell-cycle.html>

Observer hall 3

Yasemin Aslögzü Hall 3

Windows'u Etkinleştir

Windows'u etkinleştirmek için Ayarlar'a gidin.

19:22 9.01.2024

PHOTO GALLERY

The top screenshot shows a Zoom meeting interface with a gallery view of participants. The meeting title is 'Toplantı - HALL 4'. The participants visible in the gallery are: Romina Radonshiqi hall 12, session 3; Observer hall 4; Hall-4 Ananda Majumdar; Samuel Etuk; Uderme Ettentuk; Ss1/hall-4 Duon...; SS-1, Hall-4, Du...; and SS1/Hall-4 NGU... The right sidebar shows a list of participants (8) with their names and status. The bottom toolbar includes icons for mute, video, chat, share, and other meeting controls.

The bottom screenshot shows a Zoom meeting interface with a presentation slide titled 'NICOLAE GRIGORESCU'. The slide displays three paintings: a portrait of a woman in a white headscarf, a landscape painting with a woman lying down, and a portrait of a woman in a white headscarf. The right sidebar shows a list of participants (8) with their names and status. The bottom toolbar includes icons for mute, video, chat, share, and other meeting controls.

PHOTO GALLERY




PHOTO GALLERY




PHOTO GALLERY





PHOTO GALLERY



INTERNATIONAL TOPKAPI CONGRESS-VI

CONGRESS PROGRAM

January 9-11, 2026 / Istanbul, Türkiye
Online and in-person

Zoom Meeting ID: 829 5595 6031

Zoom Passcode: 101010

<https://us02web.zoom.us/j/82955956031?pwd=HD3QnheB67eF8uaDJNj72ZlZlkePmBq.1>

IMPORTANT, PLEASE READ CAREFULLY

- ❖ To be able to attend a meeting online, login via <https://zoom.us/join> site, enter ID “Meeting ID or Personal Link Name” and solidify the session.
- ❖ The Zoom application is free and no need to create an account.
- ❖ The Zoom application can be used without registration.
- ❖ The application works on tablets, phones and PCs.
- ❖ The participant must be connected to the session 5 minutes before the presentation time.
- ❖ All congress participants can connect live and listen to all sessions.
- ❖ Moderator is responsible for the presentation and scientific discussion (question-answer) section of the session.

Points to Take into Consideration - TECHNICAL INFORMATION

- ◆ Make sure your computer has a microphone and is working.
- ◆ You should be able to use screen sharing feature in Zoom.
- ◆ Attendance certificates will be sent to you as pdf at the end of the congress.
- ◆ Requests such as change of place and time will not be taken into consideration in the congress program.

PARTICIPANT COUNTRIES:

Türkiye, Azerbaijan, TRNC, USA, Romania, Algeria, India, Bangladesh, Nigeria, Iran, Georgia, Indonesia, Albania, Morocco, Vietnam, Italy, Moldova, Afghanistan

	IN-PERSON SESSION 10.01.2026 / 14.00 Moderator: Prof. Dr. Mustafa BAŞ	
	<i>SORRISO HOTEL, Kemal Paşa, Ordu Cd. No:60, 34134 Fatih/İstanbul</i>	

AUTHOR	AFFILIATION	TITLE
Asst. Prof. Dr. Kübra ÖZSANDIKÇI Prof. Dr. Mustafa BAŞ	<i>Trabzon University</i>	AN EXAMINATION OF COURAGE AND SPORT-SPECIFIC ACHIEVEMENT MOTIVATION OF UNIVERSITY STUDENTS RECEIVING SPORTS EDUCATION
Assoc. Prof. Dr. Mehmet SAĞIR Dr. Aslı Uğur AYDIN TAŞTEKİN Ayşegül GÜDÜL	<i>Selçuk University</i>	EVALUATION OF PERCEIVED SERVICE QUALITY IN HONEYMOON TOURISM WITH PROMETHEE AND USER REVIEWS
Assoc. Prof. Dr. Mehmet SAĞIR Ayşegül GÜDÜL Dr. Aslı Uğur AYDIN TAŞTEKİN	<i>Selçuk University</i>	JOURNEY TO THE SKY: A BIBLIOMETRIC EVALUATION OF ASTRO-TOURISM LITERATURE
Faten A.H. MOHAMAD Asst. Prof. Dr. Mehmet Taciddin AKCAY	<i>Altinbas University</i> <i>Halic University</i>	MACHINE LEARNING FOR EARLY DIABETES DETECTION: A CROSS- POPULATION STUDY WITH INTERPRETABILITY ANALYSIS
Res. Asst. Esra TAYAN Assoc. Prof. Dr. Ferhat BOZKURT	<i>Haliç University</i> <i>Atatürk University</i>	SEGMENTATION OF BRAIN MR IMAGES USING A DEEP LEARNING BASED U-NET ARCHITECTURE
BASMA ADIL İBRAHİM AL-GBURI Asst. Prof. Dr. Mehmet Taciddin AKCAY	<i>Altinbas University</i> <i>Halic University</i>	MULTI MODEL APPROACH FOR VISUAL CRYPTOGRAPHY IN IMAGE USING ARTIFICIAL INTELLIGENT TECHNIQUES
Prof. Dr. Serdar BİLEN Asst. Prof. Dr. Elif YAĞANOĞLU Asst. Prof. Dr. Adil ADIN Prof. Dr. Taşkın ÖZTAŞ Prof. Dr. Zekai Halıcı Prof. Dr. Durun Ali KÖSE Assoc. Prof. Dr. Melda BOLAT	<i>Atatürk University</i> <i>Hitit University</i>	EFFECTS of POLYPHENOLS and/or BORON ENRICHED DERIVATIVES on GROWTH of CORN PLANTS UNDER COLD STRESS

	SESSION-1 / HALL-1 09.01.2026 /10:00-12:00 (Türkiye Time) Moderator: Prof. Dr. Fatma Ebru İKİZ Zoom Meeting ID: 829 5595 6031 / Zoom Passcode: 101010	

AUTHOR	AFFILIATION	TITLE
Dilara KARAKILIÇ Dr. Volkan TÜRKMEN	<i>University of Health Sciences</i>	EXAMINING THE EFFECT OF OCCUPATIONAL BALANCE LEVEL ON ACADEMIC MOTIVATION IN UNIVERSITY STUDENTS
Tuğba TAŞDEMİR Prof. Dr. H. Zekavet KABASAKAL	<i>Dokuz Eylül University</i>	THE RELATIONSHIP BETWEEN PSYCHOLOGICAL CAPITAL AND ORGANIZATIONAL ALIENATION AMONG TEACHERS: A LITERATURE REVIEW
Yusuf Erdem YILDIZ Prof. Dr. Hatice Zekavet KABASAKAL	<i>Dokuz Eylül University</i>	THE EFFECT OF PSYCHOLOGICAL CAPITAL IN TEACHERS ON BURNOUT: A SYSTEMATIC REVIEW
Prof. Dr. Fatma Ebru İKİZ Yusuf Erdem YILDIZ	<i>Dokuz Eylül University</i>	A SYSTEMATIC EXAMINATION OF THE RELATIONSHIP BETWEEN STRESS AND EMOTIONAL INTELLIGENCE IN ADOLESCENTS
Prof. Dr. Fatma Ebru İKİZ Mustafa YİĞİT	<i>Dokuz Eylül University Ministry of Education</i>	EFFECTIVE INTERVENTION METHODS FOR COGNITIVE FLEXIBILITY IN PRIMARY SCHOOL STUDENTS: A SYSTEMATIC REVIEW
Prof. Dr. Fatma Ebru İKİZ Gülay KOCATAŞ	<i>Dokuz Eylül University Ministry of Education</i>	EXAMINATION OF RESEARCH ON PEER BULLYING DURING ADOLESCENCE BASED ON ACCEPTANCE AND COMMITMENT THERAPY
Assoc. Prof. Dr. Ali ÇEKİÇ Seval ÇAKMAK	<i>Gaziantep University</i>	INVESTIGATION OF THE LONG-TERM EFFECTS OF THE FEBRUARY 6 KAHRAMANMARAŞ EARTHQUAKE ON ADOLESCENTS
Asst. Prof. Dr. Haldun TURAN Gülcan AĞIR	<i>İstanbul Rumeli University</i>	ASSESSMENT OF OCCUPATIONAL HEALTH AND SAFETY RISKS OF WORKERS IN PLASTIC INJECTION PRODUCTION: KOCAELI OSB ENTERPRISES
Erdem YAŞAR Asst. Prof. Dr. Zehra İNCEDAL SONKAYA	<i>Amasya University</i>	THE EFFECT OF WORK STRESS AND JOB SATISFACTION ON THE FREQUENCY OF WORK ACCIDENTS AMONG EMPLOYEES IN THE FOOD INDUSTRY

	SESSION-1 / HALL-2 09.01.2026 /10:00-12:00 (Türkiye Time) Moderator: Asst. Prof. Dr. Zeynep KURNAZ Zoom Meeting ID: 829 5595 6031 / Zoom Passcode: 101010	

AUTHOR	AFFILIATION	TITLE
Dr. Ferhat Atik	<i>Girne American University</i>	BUILDING TRUST IN THE INFORMATION ECOSYSTEM: SOCIAL CAPITAL IN DIGITAL INTERACTIONS
Dr. Ferhat Atik	<i>Girne American University</i>	POPULAR CULTURE AND MEDIA CONSUMPTION: MASS CULTURE AND DIGITAL IDENTITY CONSTRUCTION
Validə Əliyeva Rəcəb qızı	<i>Azerbaijan State University of Economics</i>	WOMEN'S SELF-ESTEEM IN CONTEMPORARY AZERBAIJANI SOCIETY: THE INTERACTION OF PSYCHOLOGICAL, LEGAL, SOCIAL, ECONOMIC, AND RELIGIOUS-CULTURAL FACTORS
Asst. Prof. Dr. Zeynep KURNAZ Asst. Prof. Dr. Özkan ÖZTÜRK	<i>Karabük University</i>	PERCEPTION OF AGING AND BEAUTY FROM A GENDER PERSPECTIVE: DOUBLE STANDARDS AND BODY POLITICS
Asst. Prof. Dr. Özkan ÖZTÜRK Asst. Prof. Dr. Zeynep KURNAZ	<i>Karabük University</i>	THE DISCURSIVE CONSTRUCTION OF ENVIRONMENTALISM: ENVIRONMENTAL CODES ACROSS THE AXES OF VALUES, POLITICS, AND ECONOMY
Allahverdiyeva Fəridə	<i>Azərbaycan Milli Elmlər Akademiyası</i>	NEFTİN TARIXİ KÖKLƏRİ VƏ MÜASİR DÖVRDƏ ROLU
Defne ERDEM METE	<i>Selçuk University</i>	INTERCULTURAL COMMUNICATIVE COMPETENCE IN BUKET UZUNER'S TRAVEL MEMOIRS
Asst. Prof. Dr. Okan YETİŞENSOY	<i>Bayburt University</i>	TEACHING AI-RELATED CONCEPTS IN SOCIAL STUDIES: THE EXAMPLE OF THE CONCEPT OF ALGORITHMIC BIAS
Res. Asst. Dr. Samet BAŞ	<i>Karadeniz Technical University</i>	THE USE OF NARRATIVE EXPOSURE THERAPY IN GRIEF: A SYSTEMATIC REVIEW

	SESSION-1 / HALL-3 09.01.2026 /10:00-12:00 (Türkiye Time) Moderator: Asst. Prof. Dr. Hakan YURTKURAN Zoom Meeting ID: 829 5595 6031 / Zoom Passcode: 101010	

AUTHOR	AFFILIATION	TITLE
Nurullah ORAL Asst. Prof. Dr. Mustafa Anıl REŞAT Prof. Dr. Serdar ÖZYURT	Ankara Yıldırım Beyazıt University	CHARACTERIZATION OF OFDM-BASED INTEGRATED SENSING AND COMMUNICATION SYSTEMS UNDER THE ITU URBAN MACROCELL CHANNEL MODEL
Bilal ÇETİNDİR Erol YENİCE Assoc. Prof. Tarık ERFİDAN	Kocaeli University	REDUCTION OF DISTANCE MEASUREMENT ERRORS USING A KALMAN FILTER-BASED EMBEDDED SYSTEM
Mahammad ISAYEV Assoc. Prof. Dr. Seyfettin Sinan GÜLTEKİN	Konya Technical University	ELECTROMAGNETIC CHARACTERIZATION OF HEALTHY AND CANCEROUS CELL LAYERS USING A 24 GHZ VERTICALLY POLARIZED VIVALDI ANTENNA
Asst. Prof. Dr. Hakan YURTKURAN	Yozgat Bozok University	RECENT DEVELOPMENTS IN SURFACE ROUGHNESS AND ENERGY CONSUMPTION IN CNC MACHINING PROCESSES
Asst. Prof. Dr. Hakan YURTKURAN	Yozgat Bozok University	MACHINE LEARNING APPLICATIONS IN CNC MACHINING PROCESSES WITHIN THE SCOPE OF SMART MANUFACTURING
Rabia İlknur ERKEN Asst. Prof. Dr. İsmail TEMİZ Mevlüt KARAKAYA	Marmara University	TECHNOLOGICAL EVOLUTION OF PRINTING TECHNOLOGIES: THE TRANSITION FROM TRADITIONAL METHODS TO DIGITAL AND INTELLIGENT SYSTEMS
Mevlüt KARAKAYA Asst. Prof. Dr. İsmail TEMİZ Rabia İlknur ERKEN	Marmara University	TRANSITION FROM CLASSICAL METHODS TO MODERN APPROACHES IN INDUSTRIAL CRANE CONTROL: FROM PID TO MODEL PREDICTIVE CONTROL (MPC)
Tuğba BALTACI Asst. Prof. Dr. Tuğba MUTUK	Ondokuz Mayıs University	RECYCLING OF MACHINING CHIPS: CURRENT STUDIES

	SESSION-1 / HALL-4 09.01.2026 /10:00-12:00 (Türkiye Time) Moderator: Prof. Dr. Ananda Majumdar Zoom Meeting ID: 829 5595 6031 / Zoom Passcode: 101010	

AUTHOR	AFFILIATION	TITLE
Prof. Dr. Ananda Majumdar	<i>Harvard University</i>	THE SACRED AND THE SYMBOLIC: RITUAL AS THE FOUNDATION OF RELIGIOUS EXPERIENCE
Samuel Akpadiagha Etuk Udeme E. Ettentuk	<i>Akwa Ibom State Polytechnic University of Uyo</i>	FEMINIST RIGHT OF INHERITANCE IN NIGERIA: VISITING THE CASE OF UKEJE V UKEJE
Cristina GUDIN	<i>University of Bucharest</i>	REFLECTION OF THE PEASANT PROBLEM IN ROMANIAN PAINTING FROM THE SECOND HALF OF THE 19TH CENTURY TO THE BEGINNING OF THE 20TH CENTURY
Dr. Duong The Hien Dr. Duong To Quoc Thai M.A. Nguyen Thanh Tuan	<i>An Giang University Dong Thap University Vinh Nhuan Middle and High School</i>	AGRICULTURAL POLICIES AND SOCIO-ECONOMIC CHANGE IN AN GIANG, SOUTH VIETNAM (1955–1965)
Dr.B.MAHADEVAN HEMAMALINI P	<i>Vellalar College for Women (Autonomous)</i>	A STUDY ON RURAL HEALTH INFRASTRUCTURE AND AWARENESS PROGRAMS: ARASU AARAMBA SUGATHARA NILAIYAM IN OOSAIPATTI, ERODE TAMILNADU
Bùi Quang Long Phạm Thu Hằng	<i>People's Police Academy</i>	THE IMPACT OF CAREER ADAPTABILITY ON TASK PERFORMANCE AMONG COMMUNE POLICE OFFICERS
Msc. Bledar RADONSHIQI PhD. Romina RADONSHIQI	<i>CEO Eventalb University College LOGOS</i>	THE ROLE OF ARTISTIC EVENTS IN ITALY'S ECONOMY DURING THE DECEMBER FESTIVE PERIOD

	SESSION-1 / HALL-5 09.01.2026 /10:00-12:00 (Türkiye Time) Moderator: Major Gheorghe GIURGIU Zoom Meeting ID: 829 5595 6031 / Zoom Passcode: 101010	

AUTHOR	AFFILIATION	TITLE
Major Gheorghe GIURGIU Prof dr med Manole COJOCARU	<i>Deniplant-Aide Sante Medical Center Titu Maiorescu University</i>	NATURAL MODULATION OF THE GUT MICROBIOTA IN PATIENTS WITH FOOD ALLERGIES. IMPACT OF ALERGIPLANT
Fedwa BEGHDADI El-Hadj DRICHE	<i>Hassiba Benbouali University of Chlef</i>	OPTIMIZATION OF ANTAGONISTIC ACTIVITY OF SAHARAN ACTINOMYCETES AGAINST PHYTOPATHOGENIC BACTERIA AND FUNGI
Kamaleeswari .M Aarthi.P	<i>SRM Institute of Science and Technology</i>	WOUND HEALING AND THE ROLE OF PLANT SECONDARY METABOLITES
Fedwa BEGHDADI El-Hadj DRICHE	<i>Hassiba Benbouali University of Chlef</i>	BIOTECHNOLOGICAL POTENTIAL OF ACTINOMYCETES FROM ALGERIAN SAHARAN SOILS IN THE BIOLOGICAL CONTROL OF PHYTOPATHOGENIC AGENTS
AWOBONA, Emmanuel Olumide IBIWOYE, Kayode Olanrewaju	<i>Federal University of Technology Kaduna State University</i>	PHYTOGENIC FEED ADDITIVES AS SUSTAINABLE ALTERNATIVES TO ANTIBIOTIC GROWTH PROMOTERS IN POULTRY: A REVIEW OF RECENT ADVANCES AND FUTURE PROSPECTS
Fedwa BEGHDADI El-Hadj DRICHE	<i>Hassiba Benbouali University of Chlef</i>	CONTRIBUTION OF SAHARAN ACTINOMYCETES TO BIOLOGICAL CONTROL AND PLANT GROWTH PROMOTION
Fedwa BEGHDADI El-Hadj DRICHE	<i>Hassiba Benbouali University of Chlef</i>	ACTINOMYCETES FROM ALGERIAN SAHARAN SOILS AS AN EMERGING SOURCE OF BIOACTIVE MOLECULES FOR CROP PROTECTION
Safaa Rhoulam Marouane Melloul taha chouati El Alaoui Abdelaziz	<i>Ibn Tofail University National Center for Scientific and Technical Research (CNRST) University Mohammed V</i>	USING EPIPHYTIC LICHENS AS BIOLOGICAL DETECTORS: A SUSTAINABLE APPROACH TO AIR QUALITY ASSESSMENT?

	SESSION-1 / HALL-6 09.01.2026 /10:00-12:00 (Türkiye Time) Moderator: Lecturer, PhD Irina-Ana DROBOT Zoom Meeting ID: 829 5595 6031 / Zoom Passcode: 101010	

AUTHOR	AFFILIATION	TITLE
Dr. Firoz FAOZI	<i>Kabul State University</i>	ISTANBUL AND ÜSKÜDAR IN AFGHAN LITERATURE
Fatima Zohra Boudjenane Mohamed Amine Driss (Prof.)	<i>University of Mascara- Mustapha Stambouli University of Oran 2</i>	EXPLORING AI ETHICS THROUGH REFLECTIVE WRITING: FIRST-YEAR EFL STUDENTS' PERSPECTIVES ON RESPONSIBLE TECHNOLOGY USE
Hamed Jokar Deh Morghouei Narjes Asgari Vartooni Dr. Mahmoud Afrouz	<i>University of Isfahan</i>	NEWS TRANSLATION: FRAME THEORY IN FOCUS
Fatemeh Aghakhani Chegeni Narjes Asgari Vartooni Dr. Mahmoud Afrouz	<i>University of Isfahan</i>	CHALLENGES OF TRANSLATING FOR THE NEW GENERATION: CHILDREN VERSUS ADOLESCENTS
Lecturer, PhD Irina-Ana DROBOT	<i>Technical University of Civil Engineering Bucharest</i>	MAGIC IN A HAIKU POEM ABOUT CHRISTMAS EVE
Natalia Bolgari Ina Andoni	<i>Academy of Economic Studies of Moldova</i>	ENHANCING STUDENTS' SPEAKING CONFIDENCE IN THE ENGLISH CLASSROOM
Cobzaru Andreia	<i>Zvoriște Middle School, Ștefan cel Mare University of Suceava</i>	THE IMPORTANCE OF ENGLISH LANGUAGE PROFICIENCY FOR SOCIAL INTEGRATION

	SESSION-2 / HALL-1 09.01.2026 /12:30-14:30 (Türkiye Time) Moderator: Prof.Dr. Aslı HOCKENBERGER Zoom Meeting ID: 829 5595 6031 / Zoom Passcode: 101010	

AUTHOR	AFFILIATION	TITLE
VALMA ENJOH SOH	<i>Cyprus International University</i>	INTEGRATING SUSTAINABLE TECHNOLOGIES IN SCIENTIFIC RESEARCH: A PATHWAY TOWARD ENVIRONMENTAL RESILIENCE
Asst. Prof. Dr. Fatma KÜÇÜK	<i>Ankara Yıldırım Beyazıt University</i>	COMPARISON OF GODEC AND ROSURE ALGORITHMS PERFORMANCE FOR ANOMALY DETECTION IN HYPERSPECTRAL IMAGES
Shwan SAEED Derya AVCI Engin AVCI	<i>Firat University</i>	A COMPARATIVE STUDY OF MACHINE LEARNING ALGORITHMS FOR HEART DISEASE PREDICTION: A DECISION SUPPORT SYSTEM APPROACH
Bagirova Tamilla Ali kızı	<i>Azerbaijan State Pedagogical University</i>	ARTIFICIAL INTELLIGENCE IN ART
Tülay CANBABA	<i>Istanbul Bayrampasa Science and Art Center</i>	INCREASING RECYCLING AWARENESS THROUGH DESIGNING INSTRUCTIONAL MATERIALS FROM WASTE MATERIALS: A CASE STUDY ON BILSEM STUDENTS
Gizem YAĞCI Assoc. Prof. Dr. Çimen BAYBURTLU	<i>Altınbaş University Marmara University</i>	THE USE OF HIGH-PIGMENT ARTISTIC PAINTS AS AN ALTERNATIVE COLORING METHOD IN CONTEMPORARY JEWELRY DESIGN
Nazlıcan AKAR Prof.Dr. Aslı HOCKENBERGER Prof.Dr Kadir YEŞİLBAĞ	<i>Bursa Uludağ University</i>	INVESTIGATION OF THE TISSUE FRAMEWORK AND VIRUS PROTECTION OF CUPROAMMONIUM SURFACES
Assoc. Prof. Dr. Peri GÜNEŞ Asst. Prof. Dr. Sina APAK Yahya D. Navaei Harun BENLİ	<i>İnfina Yazılım A.Ş. İstanbul Aydın University</i>	ENHANCING SOFTWARE DEFECT PREDICTION ACCURACY: A MULTI-OBJECTIVE FIREFLY ALGORITHM APPROACH

	SESSION-2 / HALL-2 09.01.2026 /12:30-14:30 (Türkiye Time) Moderator: Prof. Dr. Arif Gök	
	Zoom Meeting ID: 829 5595 6031 / Zoom Passcode: 101010	

AUTHOR	AFFILIATION	TITLE
Merve ÇAKIR Prof. Dr. Arif Gök	<i>Kütahya Dumlupınar University</i>	THE USE OF CREATIVE THINKING TECHNIQUES IN ARCHITECTURE
Eda GÖRGÜN Prof. Dr. Arif GÖK	<i>Kütahya Dumlupınar University</i>	THE USE OF NEXT GENERATION MATERIALS IN INTERIOR SPACES AND SAMPLE APPLICATIONS
Ecem Korkmaz Prof. Dr. Arif Gök	<i>Kütahya Dumlupınar University</i>	THE USE OF AUGMENTED REALITY IN INTERIOR DESIGN AND A SAMPLE APPLICATION
Nagehan TESELEK Prof. Dr. Arif Gök	<i>Kütahya Dumlupınar University</i>	ARTIFICIAL INTELLIGENCE POWERED MATERIAL SELECTION WIZARD
Yunus BULUT Prof. Dr. Arif GÖK	<i>Kütahya Dumlupınar University</i>	THE USE OF ARTIFICIAL INTELLIGENCE WITHIN THE FRAMEWORK OF INTELLECTUAL AND INDUSTRIAL PROPERTY RIGHTS
Nurten GÖKYİĞİT ZENGİN Prof. Dr. Arif GÖK	<i>Kütahya Dumlupınar University</i>	THE ROLE OF ARTIFICIAL INTELLIGENCE IN THE DEVELOPMENT OF BUSINESSES AND AREAS OF USE
Mehmet Ali DURLU Prof. Dr. Arif GÖK	<i>Dumlupınar University</i>	IMPLEMENTATION OF THE ARTIFICIAL INTELLIGENCE THROUGH R&D
Dr. Ömer Özkan	<i>SOCAR Türkiye Quality Management Department</i>	THE INTERACTION BETWEEN THE EFQM EXCELLENCE MODEL 2025 REVISION AND THE ISO 9001:2015 QUALITY MANAGEMENT SYSTEM: AN INTEGRATED MANAGEMENT APPROACH

	SESSION-2 / HALL-3 09.01.2026 /12:30-14:30 (Türkiye Time) Moderator: Assoc. Prof. Dr. Işıl IŞIK Zoom Meeting ID: 829 5595 6031 / Zoom Passcode: 101010	

AUTHOR	AFFILIATION	TITLE
Arzu Çağla Avcı Eslem Aman Fatih Özdemir Lec. Begüm Kırık Assoc. Prof. Dr. Işıl IŞIK	<i>Yeditepe University</i>	BARRIERS AND SOLUTION STRATEGIES IN NURSING ROLES IN THE CONTEXT OF STUDENT AND ACADEMIC PERSPECTIVES
Taha Onur ARIDAĞ Bilgenur KILIÇ Öykü Melis SARI Esma Nur BAYHAN Ece DEMİR Bilge KAVANOZ Assoc. Prof. Dr. Işıl IŞIK	<i>Yeditepe University</i>	EXPERIENCING VIOLENCE IN HEALTHCARE EDUCATION: A PHENOMENOLOGICAL STUDY OF NURSING AND MEDICAL STUDENTS' PERCEPTIONS AND PROFESSIONAL OUTLOOKS
Minel SEZER Asst. Prof. Dr. Figen ÇALIŞKAN	<i>Trakya University</i>	THE RELATIONSHIP BETWEEN NURSES' INFORMATION LITERACY LEVELS AND CLINICAL DECISION-MAKING SKILLS
Abdülhabib AKDAĞ Assoc. Prof. Dr. Yeliz PEHLİVAN	<i>University of Health Sciences</i>	THE EFFECT OF COOLING APPLICATIONS ON ANAEROBIC CAPACITY
Lala Zeynalabdin Gurbanova Gunay Mubariz Nasibova	<i>Azerbaijan State Agricultural University</i>	BIOECOLOGICAL ANALYSIS OF THE GENUS CENTAUREA L.WITHIN THE FLORA OF AZERBAIJAN
Berna Yıldırım Ayhan Bilir	<i>Istanbul Atlas University</i>	VINORELBINE AND LITHIUM CO-TREATMENT INDUCES G1 PHASE ARREST AND SUPPRESSES PROLIFERATION IN 3D ENDOMETRIAL CANCER SPHEROIDS
Elif ÖRSELOĞLU Asst. Prof. Vedat GÖKEN Büşra YILDIRIM Serdar AYDIN Zeynep GÜNEŞ Prof. Dr. Yasemin Buran Çırak	<i>İstinye University</i>	INVESTIGATION OF THE EFFECTS OF KINESIO TAPE APPLICATION TO RESPIRATORY MUSCLES ON FUNCTIONAL LEVEL AND RESPIRATORY FUNCTION IN INTENSIVE CARE PATIENTS IN THE EARLY PERIOD
Asst. Prof. Dr. Zeynep ÖZERSON KOÇ Yasemin ADILOĞLU	<i>Haliç University</i>	PİLATES YAPAN VE YAPMAYAN KADINLARDA SEZGİSEL YEME, SAĞLIKLI YEME TAKINTISI VE BEDEN TAKDİRİ İLİŞKİSİNİN KARŞILAŞTIRILMASI

	SESSION-2 / HALL-4 09.01.2026 /12:30-14:30 (Türkiye Time) Moderator: Adelekan Oluseyi Okunlade Zoom Meeting ID: 829 5595 6031 / Zoom Passcode: 101010	

AUTHOR	AFFILIATION	TITLE
Adelekan Oluseyi Okunlade Aishat Motunrayo Oyatoye Blessing Oluwakemi Ige	<i>University of Ibadan</i>	DETECTION OF MULTIDRUG RESISTANT, NON- EXTENDED SPECTRUM β -lactamase (ESBL) PRODUCING E. coli FROM ABATTOIR EFFLUENTS AND ABATTOIR EFFLUENTS IMPACTS ON RESIDENTIAL NEIGHBOURHOOD
NOUALI Oumaima	<i>Mohammed V University</i>	PHYSICO-CHEMICAL ANALYSIS OF METALS IN THE WATERS OF THE KHOURIBGA REGION: ANALYTICAL APPROACH BY ICP-OES
AIT RICHAT Zineb MOUSSAIF Ahmed CHERKAOUI Hassan	<i>Laboratory of Heterocyclic Organic Chemistry National Center for Energy, Sciences and Nuclear Techniques (CNESTEN)</i>	BIOLOGICAL POTENTIAL AND SUSTAINABLE VALORIZATION CHALLENGES OF MOROCCAN EUPHORBIA LATEX: A BIBLIOGRAPHIC AND EXPERIMENTAL STUDY
Azad Md Sorwar Md. Saimon Islam Dr.Kurshida Sharmin	<i>Dhaka University of Engineering & Technology</i>	FLEXIBLE PEG-PVDF SOLID ELECTROLYTE MEMBRANES WITH ENHANCED IONIC CONDUCTIVITY FOR POUCH-TYPE LITHIUM-ION BATTERIES
Mohammed Elamine LAHLACI Mohamed MILOUDI Houcine MILOUDI	<i>Relizane University</i>	CONDUCTED DISTURBANCE ANALYSIS FOR A DIRECT CURRENT MOTOR DRIVE
Pallabi Chowdhury	<i>University of Gour Banga</i>	MACHINE LEARNING AND DEEP LEARNING-BASED WETLAND HEALTH MODELLING IN A DAM-INDUCED RIPARIAN CORRIDOR

	SESSION-2 / HALL-5 09.01.2026 /12:30-14:30 (Türkiye Time) Moderator: Prof. Dr. G. Nixon Samuel	
	Zoom Meeting ID: 829 5595 6031 / Zoom Passcode: 101010	

AUTHOR	AFFILIATION	TITLE
Md. Imran Hasan Md. Nadim Mahamood Kamrul Hasan	<i>Begum Rokeya University Texas State University</i>	CASCADED HIERARCHICAL SEGMENTATION OF KIDNEY AND TUMOR MASSES IN CT: A COARSE-TO-FINE, KIDNEY-CENTERED APPROACH
Md. Mahafuzur Rahman Shah Tania Akter Sujana	<i>Begum Rokeya University</i>	IDENTIFYING KEY INFLUENCERS OF PATIENT SATISFACTION USING AN EXPLAINABLE MACHINE LEARNING APPROACH
Md. Mahafuzur Rahman Shah Tania Akter Sujana Md Nadim Mahamood	<i>Begum Rokeya University</i>	EXPLAINABLE MACHINE LEARNING ASSESSMENT OF MATERNAL PREFERENCE FOR HUSBAND PARTICIPATION IN DELIVERY ROOM SUPPORT IN BANGLADESH
Shahid Abdullah Neha Choubey Tawseef Abdullah	<i>JB Institute of Engineering and Technology VIT Bhopal University National Institute of Technology</i>	A NOVEL TWO-POINT ITERATIVE METHOD FOR SOLVING NON-LINEAR EQUATIONS WITH MEMORY
Rajab Yahyazadeh Zahra Hashempour	<i>Islamic Azad University</i>	NUMERICAL INVESTIGATION OF THE ELECTRONIC AND ELECTRICAL CHARACTERISTICS OF InGaN/GaN MULTIPLE QUANTUM WELL SOLAR CELLS
Prof. Dr. G. Nixon Samuel Vijayakumar Reshma. N Aishwarya. S Tharunikaa. P Tarnekaa. M Nivethitha. S.K Samiksha. R.K	<i>R.M.K. Engineering College</i>	REVIEW ON PLANCK'S QUANTUM THEORY
Jogendra Kumar Shreya Nainwal Sandhya Rajwar	<i>GBPIET Ghurdauri Pauri Garhwal Uttarakhand</i>	SMART SYSTEM OF WATER QUALITY PREDICTION AND ANOMALY DETECTION USING AI
Mouna Fakir	<i>Mohammed V University</i>	GREEN HYDROGEN ENERGY STORAGE USING ARTIFICIAL INTELLIGENCE-BASED STRATEGIES FOR A SUSTAINABLE FUTURE

	SESSION-2 / HALL-6 09.01.2026 /12:30-14:30 (Türkiye Time) Moderator:	
	Zoom Meeting ID: 829 5595 6031 / Zoom Passcode: 101010	

AUTHOR	AFFILIATION	TITLE
Akpan Udo Usiere	<i>Topfaith University</i>	SOCIAL MEDIA ADVANCEMENT OF AGRIC – ALLIED SCIENTIFIC DISCOVERIES IN AFRICAN COUNTRIES
R . Kishore K . Vaishnavi S . Meenatchi V . Keerthana	<i>Bharath institute of higher Education and research</i>	INDUSTRIAL HEMP WASTE VALORIZATION
Karima ALAOUI	<i>Mohammed Premier University</i>	BIOCONTROL OF PHYTOPHTHORA INFESTANS USING LACTOBACILLUS: AN ECO-FRIENDLY STRATEGY FOR POTATO PROTECTION
Badre Zinaoui Pr.Labjar Najoua Pr.EL Hajjaji souad	<i>Mohammed V University in Rabat</i>	DEVELOPMENT AND OPTIMIZATION OF AN INTEGRATED SOLAR DESALINATION SYSTEM WITH THERMAL STORAGE AND ENERGY RECOVERY
Most. Mokarroma	<i>University of Rajshahi</i>	CLIMATE CHANGE AND THE RISING BURDEN OF DENGUE: PATHWAYS, PUBLIC HEALTH RISKS, AND ADAPTATION STRATEGIES
Dr. Emmanuel U. ANASO	<i>Federal University of Agriculture Mubi</i>	ADVANCES IN ESSENTIAL OIL SUPPLEMENTATION FOR LIVESTOCK PRODUCTION IN AFRICA: MECHANISMS, PERFORMANCE OUTCOMES, AND CHALLENGES WITH EVIDENCE FROM NIGERIA
Mounir BOUTARBOUCH Khadija El-Moustaqim Jamal MABROUKI	<i>Mohammed V University of Rabat Ibn Tofail University</i>	COMPUTATIONAL AND AI-DRIVEN OPTIMIZATION STRATEGIES FOR NEXT-GENERATION GREEN HYDROGEN PRODUCTION
Md. Mahafuzur Rahman Shah Tania Akter Sujana	<i>Begum Rokeya University</i>	ASSESSING EFFECTS OF AGRICULTURE AND INDUSTRY ON CO ₂ EMISSIONS IN BANGLADESH

	SESSION-3 / HALL-1 09.01.2026 /15:00-17:00 (Türkiye Time) Moderator: Assoc. Prof. Dr. Arzu ÇAĞLAR Zoom Meeting ID: 829 5595 6031 / Zoom Passcode: 101010	

AUTHOR	AFFILIATION	TITLE
Erdal AKTAŞ Asst. Prof. Dr. Hakan ÇAĞLAR Assoc. Prof. Dr. Arzu ÇAĞLAR	AKTAŞ Harita ve Mühendislik A.Ş. Kırşehir Ahi Evran University of Health Sciences	THE USE OF WALNUT SHELLS IN THE PRODUCTION OF BUILDING MATERIALS: A BRIEF REVIEWS
Assoc. Prof. Dr. Arzu ÇAĞLAR Asst. Prof. Dr. Hakan ÇAĞLAR Volkan GÖNEN Beyza GÖNEN	Kırşehir Ahi Evran University of Health Sciences GÖNEN Harita ve Mühendislik A.Ş.	THE CONCEPT OF GREEN BUILDING: EXAMPLES FROM AROUND THE WORLD AND FROM TÜRKİYE
Asst. Prof. Dr. Yunus ERKUŞ Dilay AKSAKAL	Fırat University	RESEARCH ON METHODS FOR CONTROLLING SNOW AND ICE ON HIGHWAY
Asst. Prof. Dr. Yunus ERKUŞ Dilay AKSAKAL	Fırat University	INVESTIGATION OF THE EFFECT OF STEEL SLAG ON THE MECHANICAL PROPERTIES OF FLEXIBLE SUPERSTRUCTURE USING THE FINITE ELEMENT METHOD
Raniah RAFEHA KHALAF Prof. Dr. Arif GÖK	Dumlupınar University	THE ROLE OF ARTIFICIAL INTELLIGENCE IN INDUSTRIAL ENGINEERING: TRANSFORMATION TO DATA-DRIVEN DECISION MAKING AND SMART SYSTEMS
Ahmet ULUDOĞAN Prof. Dr. Arif GÖK	Dumlupınar University	ARTIFICIAL INTELLIGENCE APPLICATIONS FOR ENSURING COMFORT INDOOR SPACES
Dr. Mehdi Shalchi Tousi	Ahle Beyte Internatinal University	NEGATIVE ASPECTS IN CONTEMPORARY IRANIAN ARCHITECTURE: A MULTIDISCIPLINARY ASSESSMENT FROM CIVIL ENGINEERING, CONSTRUCTION MANAGEMENT, AND ARCHITECTURE PERSPECTIVES

	SESSION-3 / HALL-2 09.01.2026 /15:00-17:00 (Türkiye Time) Moderator: Prof. Dr. Adnan ÇELİK	
	Zoom Meeting ID: 829 5595 6031 / Zoom Passcode: 101010	

AUTHOR	AFFILIATION	TITLE
Asst. Prof. Dr. Duygu ÇELİK	<i>İstanbul Gelişim University</i>	THE IMPACT OF INSTITUTIONAL QUALITY ON ECONOMIC GROWTH: THE CASE OF THE BRICS-T COUNTRY GROUP AND "THE GREASING THE WHEELS" EFFECT
Aliyeva Maralkhanim Tofiq gizi	<i>Azerbaijan State Pedagogical University</i>	NEW THINKING IN EDUCATIONAL MANAGEMENT
Prof. Dr. Adnan ÇELİK	<i>Selcuk University</i>	MOTIVATIONS PROVIDED BY THE GREEN UNIVERSITY INDEX
Prof. Dr. Adnan ÇELİK	<i>Selcuk University</i>	A FACTOR INFLUENCING MANAGERS' BEHAVIORAL LEVELS: THE INFAMIA PROBLEM
Prof. Dr. Adnan ÇELİK	<i>Selcuk University</i>	A WAVE OF NOSTALGIA AMONG ENTREPRENEURS: A KIND OF RETROTOPIA
Asst. Prof. Dr. Sinan GÜLENÇER	<i>Eskişehir Osmangazi University</i>	FINANCIAL DISTRESS RISK IN TURKISH LISTED PACKAGING FIRMS: AN ALTMAN Z-SCORE ANALYSIS (2020–2024)
Belma MİDİLLİ-DÖNER Prof. Dr. Serdar BOZKURT	<i>Yıldız Technical University</i>	A MODEL ON THE ROLE OF EMPLOYER BRANDING IN THE RELATIONSHIP BETWEEN SUSTAINABLE CAREER AND CAREER SATISFACTION
Cem Erhan ARSLAN Prof. Dr. Kenan AYDIN	<i>Yıldız Technical University</i> <i>İstanbul Gelişim University</i>	THE IMPACT OF CORPORATE SOCIAL RESPONSIBILITY INITIATIVES ON BRAND ADVOCACY BEHAVIORS IN TIMES OF CRISIS: A STUDY ON COVID-19 PANDEMIC
Res. Asst. Dr. Maide Betül BAYDAR	<i>Gaziantep University</i>	A BIBLIOMETRIC REVIEW OF LITERATURE ON ARTIFICIAL INTELLIGENCE APPLICATIONS IN FOREIGN TRADE

	SESSION-3 / HALL-3 09.01.2026 /15:00-17:00 (Türkiye Time) Moderator: Prof. Dr GVANTCA GELIASHVILI Zoom Meeting ID: 829 5595 6031 / Zoom Passcode: 101010	

AUTHOR	AFFILIATION	TITLE
Prof. Dr GVANTCA GELIASHVILI	<i>Caucasus International University</i>	ADVERTISING MANAGEMENT AND GEORGIAN BUSINESS ENVIRONMENT
Syed Agung Afandi Muslim Afandi Rizki Erdayani	<i>Universitas Islam Negeri Sultan Syarif Kasim Riau</i>	FROM POLICY AMBITION TO SYSTEM CAPACITY: UNDERSTANDING MISALIGNMENT IN INDONESIA'S DECENTRALIZED HEALTH GOVERNANCE
Dr. Le Thu Ha	<i>Nha Trang University</i>	GOVERNANCE INSTITUTION QUALITY AND THE FDI-PRIVATE INVESTMENT NEXUS: EVIDENCE FROM VIETNAMESE PROVINCES (2011-2020)
Obi Godwin Chukwudi	<i>Federal University of Agriculture</i>	TOWARDS A KNOWLEDGE-DRIVEN ECONOMY IN NIGERIA: CHALLENGES AND STRATEGIC PATHWAYS
Phd . BENKHAOUA Rayene Assoc. Prof. Dr. MESSIKH Ayoub	<i>20 Aout 1956 SKIKDA University</i>	UNIVERSITY BUSINESS INCUBATORS AS A MECHANISM FOR SUPPORTING START-UPS: EXAMPLES OF NATIONAL UNIVERSITY BUSINESS INCUBATORS
ARBAOUI RANIA AMZILE RAJAA	<i>Mohammed V University</i>	FROM DISRUPTION TO ADAPTATION: AN INTERRUPTED TIME SERIES ANALYSIS OF COVID-19'S ECONOMIC IMPACT ON MOROCCO'S TEXTILE INDUSTRY
Siska Purnama Manurung Tritanio Nizar Rabulizat	<i>President University</i>	BEYOND THE FILTER: DRIVERS OF GENERATION Z'S AR FACE FILTER ADOPTION IN INDONESIA
Malvina Hysa Dori Risilia	<i>Logos University College Agricultural University of Tirana</i>	THE IMPACT OF ECONOMIC CHALLENGES ON THE COMPETITIVENESS OF THE FASON SECTOR IN ALBANIA

	SESSION-3 / HALL-4 09.01.2026 /15:00-17:00 (Türkiye Time) Moderator:	
	Zoom Meeting ID: 829 5595 6031 / Zoom Passcode: 101010	

AUTHOR	AFFILIATION	TITLE
Sidra Bibi Dr. Hina Iram	Rawalpindi Women University	RELATIONSHIP BETWEEN COMMUNICATION COMPETENCY AND SELF-ESTEEM AMONG EMERGING ADULTS: MEDIATING ROLE OF SOCIAL CONNECTEDNESS
Erda Hodaj	University "Ismail Qemali" Vlorë	EXPLORING STRATEGIES TO REDUCE BURNOUT AND IMPROVE RETENTION RATES AMONG NURSING STUDENTS
Simardeep kaur Dr. Shabir Sidhu	I.K. Gujral Punjab Technical University	DEVELOPMENT OF A FINGER MILLET-BASED IRON-ENRICHED FUNCTIONAL SNACK USING JAGGERY, MORINGA AND AMLA WITH ENCAPSULATED IRON AND VITAMIN C: SENSORY QUALITY AND IN-VITRO BIOAVAILABILITY EVALUATION
Habeebat Abiola Suleiman Arafah Abiodun Shehu	University of Abuja	EFFECTS OF ARTESUNATE AND QUININE ON THE ACTIVITIES OF ADENOSINE TRIPHOSPHATASE (ATPASE) IN RAT LIVER
Mir-Hassan Moosavy	University of Tabriz	SMART PACKAGING TECHNOLOGIES FOR QUALITY MONITORING AND SHELF-LIFE EXTENSION OF MEAT AND MEAT PRODUCTS
Mohammed BAHRI Wajih RHALEM Soumia ZIT Nassim KHARMOUM Larbi CHRIFI-ALAOUI	Moroccan Society of Digital Health Mohammed V University in Rabat 5CNRST National Center for Scientific and Technical Research in Rabat University of Picardie Jules Verne	ARTIFICIAL INTELLIGENCE AND RADIOMICS IN EARLY CANCER DIAGNOSIS
Sanae Baghrouis Ikram Ghicha Youness Kadil Fatiha Bousselham Hasnaa Bazhar Imane Rahmoune Houda Filali	University Hassan II	COMPUTATIONAL REPURPOSING OF FDA-APPROVED DRUGS TO OVERCOME RESISTANCE IN ALK-POSITIVE NSCLC: A STRUCTURE-GUIDED APPROACH

INTERNATIONAL TOPKAPI CONGRESS-VI

CONTENTS FULL TEXTS

AUTHOR	TITLE	No
Abdülhabib AKDAĞ Yeliz PEHLİVAN	THE EFFECT OF COOLING APPLICATIONS ON ANAEROBIC CAPACITY	1
Adnan Celik	A FACTOR INFLUENCING MANAGERS' BEHAVIORAL LEVELS: THE INFAMIA PROBLEM	8
Adnan Celik	A WAVE OF NOSTALGIA AMONG ENTREPRENEURS: A KIND OF RETROTOPIA	19
Adnan Celik	MOTIVATIONS PROVIDED BY THE GREEN UNIVERSITY INDEX	30
Aliyeva Maralkhanim Tofiq gizi	NEW THINKING IN EDUCATIONAL MANAGEMENT	39
Allahverdiyeva Fəridə	NEFTİN TARİXİ KÖKLƏRİ VƏ MÜASİR DÖVRDƏ ROLU	44
Ananda Majumdar	THE SACRED AND THE SYMBOLIC: RITUAL AS THE FOUNDATION OF RELIGIOUS EXPERIENCE	48
Arzu ÇAĞLAR Hakan ÇAĞLAR Volkan GÖNEN Beyza GÖNEN	THE CONCEPT OF GREEN BUILDING: EXAMPLES FROM AROUND THE WORLD AND FROM TÜRKİYE	59
AWOBONA, Emmanuel Olumide IBIWOYE, Kayode Olanrewaju	PHYTOGENIC FEED ADDITIVES AS SUSTAINABLE ALTERNATIVES TO ANTIBIOTIC GROWTH PROMOTERS IN POULTRY: A REVIEW OF RECENT ADVANCES AND FUTURE PROSPECTS	71
Bagirova Tamilla Ali kızı	ARTIFICIAL INTELLIGENCE IN ART	74
BASMA ADIL IBRAHİM AL-GBURI Mehmet Taciddin AKCAY	MULTI MODEL APPROACH FOR VISUAL CRYPTOGRAPHY IN IMAGE USING ARTIFICIAL INTELLIGENT TECHNIQUES	83
Belma MİDİLLİ-DÖNER Serdar BOZKURT	SÜRDÜRÜLEBİLİR KARİYER VE KARİYER TATMİNİ İLİŞKİSİNDE İŞVEREN MARKASININ ROLÜNE YÖNELİK BİR MODEL	97
Bilal ÇETİNDİMİR Erol YENİCE Tarkan ERFİDAN	REDUCTION OF DISTANCE MEASUREMENT ERRORS USING A KALMAN FILTER-BASED EMBEDDED SYSTEM	104
Bledar RADONSHIQI Romina RADONSHIQI	THE ROLE OF ARTISTIC EVENTS IN ITALY'S ECONOMY DURING THE DECEMBER FESTIVE PERIOD	113
Cem Erhan ARSLAN Kenan AYDIN	THE IMPACT OF CORPORATE SOCIAL RESPONSIBILITY INITIATIVES ON BRAND ADVOCACY BEHAVIORS IN TIMES OF CRISIS: A STUDY ON COVID-19 PANDEMIC	120
CRISTINA GUDIN	REFLECTION OF THE PEASANT PROBLEM IN ROMANIAN PAINTING FROM THE SECOND HALF OF THE 19TH CENTURY TO THE BEGINNING OF THE 20TH CENTURY	131

INTERNATIONAL TOPKAPI CONGRESS-VI

Dilara KARAKILIÇ Volkan TÜRKMEN	EXAMINING THE EFFECT OF OCCUPATIONAL BALANCE LEVEL ON ACADEMIC MOTIVATION IN UNIVERSITY STUDENTS	141
Duong The Hien Duong To Quoc Thai Nguyen Thanh Tuan	AGRICULTURAL POLICIES AND SOCIO-ECONOMIC TRANSFORMATION IN AN GIANG, SOUTH VIETNAM (1955–1965)	149
Duygu ÇELİK	THE IMPACT OF INSTITUTIONAL QUALITY ON ECONOMIC GROWTH: THE CASE OF THE BRICS-T COUNTRY GROUP AND “THE GREASING THE WHEELS” EFFECT	167
Eda GÖRGÜN Arif GÖK	THE USE OF NEXT GENERATION MATERIALS IN INTERIOR SPACES AND SAMPLE APPLICATIONS	181
Erdal AKTAŞ Hakan ÇAĞLAR Arzu ÇAĞLAR	THE USE OF WALNUT SHELLS IN THE PRODUCTION OF BUILDING MATERIALS: A BRIEF REVIEWS	189
Esra TAYAN Ferhat BOZKURT	SEGMENTATION OF BRAIN MRI IMAGES USING A DEEP LEARNING BASED U-NET ARCHITECTURE	199
Fatemeh Aghakhani Chegeni Narjes Asgari Vartooni Mahmoud Afrouz	CHALLENGES OF TRANSLATING FOR THE NEW GENERATION: CHILDREN VERSUS ADOLESCENTS	207
Faten A.H. MOHAMAD Mehmet Taciddin AKCAY	MACHINE LEARNING FOR EARLY DIABETES DETECTION: A CROSS-POPULATION STUDY WITH INTERPRETABILITY ANALYSIS	213
Fatma Ebru İKİZ Mustafa YİĞİT	EFFECTIVE INTERVENTION METHODS FOR COGNITIVE FLEXIBILITY IN PRIMARY SCHOOL STUDENTS: A SYSTEMATIC REVIEW	225
Fatma Ebru İKİZ Gülay KOCATAŞ	EXAMINATION OF RESEARCH ON PEER BULLYING DURING ADOLESCENCE BASED ON ACCEPTANCE AND COMMITMENT THERAPY	242
Fatma Ebru İKİZ Yusuf Erdem YILDIZ	ERGENLERDE STRES VE DUYGUSAL ZEKÂ ARASINDAKİ İLİŞKİ: SİSTEMATİK GÖZDEN GEÇİRME	253
Fatma KÜÇÜK	COMPARISON OF GODEC AND ROSURE ALGORITHMS PERFORMANCE FOR ANOMALY DETECTION IN HYPERSPECTRAL IMAGES	266
Ferhat Atik	POPULAR CULTURE AND MEDIA CONSUMPTION: MASS CULTURE AND DIGITAL IDENTITY CONSTRUCTION	275
Ferhat Atik	BUILDING TRUST IN THE INFORMATION ECOSYSTEM: SOCIAL CAPITAL IN DIGITAL INTERACTIONS	286
Gizem YAĞCI Çimen BAYBURTLU	THE USE OF HIGH-PIGMENT ARTISTIC PAINTS AS AN ALTERNATIVE COLORING METHOD IN CONTEMPORARY JEWELRY DESIGN	300

INTERNATIONAL TOPKAPI CONGRESS-VI

Hakan YURTKURAN	MACHINE LEARNING APPLICATIONS IN CNC MACHINING PROCESSES WITHIN THE SCOPE OF SMART MANUFACTURING	312
Hamed Jokar Deh Morghouei Narjes Asgari Vartooni Mahmoud Afrouz	NEWS TRANSLATION: FRAME THEORY IN FOCUS	321
Irina-Ana DROBOT	MAGIC IN A HAIKU POEM ABOUT CHRISTMAS EVE	328
Jogendra Kumar Shreya Nainwal Sandhya Rajwar	SMART SYSTEM OF WATER QUALITY PREDICTION AND ANOMALY DETECTION USING AI	334
Lala Zeynalabdin Gurbanova Gunay Mubariz Nasibova	BIOECOLOGICAL ANALYSIS OF THE GENUS CENTAUREA L.WITHIN THE FLORA OF AZERBAIJAN	339
Le Thu Ha Nguyen Thanh Đạt Tran Thanh Khiet	GOVERNANCE INSTITUTION QUALITY AND THE FDI-PRIVATE INVESTMENT NEXUS: EVIDENCE FROM VIETNAMESE PROVINCES (2011-2020)	343
Mahammad ISAYEV Seyfettin Sinan GÜLTEKİN	ELECTROMAGNETIC CHARACTERIZATION OF HEALTHY AND CANCEROUS CELL LAYERS USING A 24 GHZ VERTICALLY POLARIZED VIVALDI ANTENNA	356
Malvina Hysa Dori Risilia	THE IMPACT OF ECONOMIC CHALLENGES ON THE COMPETITIVENESS OF THE FASON SECTOR IN ALBANIA	370
Mehdi Shalchi Tousi	NEGATIVE ASPECTS IN CONTEMPORARY IRANIAN ARCHITECTURE: A MULTIDISCIPLINARY ASSESSMENT FROM CIVIL ENGINEERING, CONSTRUCTION MANAGEMENT, AND ARCHITECTURE PERSPECTIVES	374
Mehmet Ali DUMLU Arif GÖK	IMPLEMENTATION OF THE ARTIFICIAL INTELLIGENCE THROUGH R&D	377
Mehmet SAĞIR Ayşegül GÜDÜL Aslı Uğur AYDIN TAŞTEKİN	JOURNEY TO THE SKY: A BIBLIOMETRIC EVALUATION OF ASTRO-TOURISM LITERATURE	383
Mehmet SAĞIR Aslı Uğur AYDIN TAŞTEKİN Ayşegül GÜDÜL	EVALUATION OF PERCEIVED SERVICE QUALITY IN HONEYMOON TOURISM WITH PROMETHEE AND USER REVIEWS	402
Merve ÇAKIR Arif GÖK	THE USE OF CREATIVE THINKING TECHNIQUES IN ARCHITECTURE	420
Mevlüt KARAKAYA İsmail TEMİZ Rabia İlknur ERKEN	TRANSITION FROM CLASSICAL METHODS TO MODERN APPROACHES IN INDUSTRIAL CRANE CONTROL: FROM PID TO MODEL PREDICTIVE CONTROL (MPC)	427
Most. Mekarroma	CLIMATE CHANGE AND THE RISING BURDEN OF DENGUE: PATHWAYS, PUBLIC HEALTH RISKS, AND ADAPTATION STRATEGIES	435

INTERNATIONAL TOPKAPI CONGRESS-VI

Nagehan TESELEK Arif GÖK	ARTIFICIAL INTELLIGENCE-POWERED MATERIAL SELECTION WIZARD	441
Natalia Bolgari Ina Andoni	ENHANCING STUDENTS' SPEAKING CONFIDENCE IN THE ENGLISH CLASS-ROOM	451
Nurten GÖKYİĞİT ZENGİN Arif GÖK	THE ROLE OF ARTIFICIAL INTELLIGENCE IN THE DEVELOPMENT OF BUSINESSES AND AREAS OF USE	462
Nurullah ORAL Mustafa Anıl REŞAT Serdar ÖZYURT	CHARACTERIZATION OF OFDM-BASED INTEGRATED SENSING AND COMMUNICATION SYSTEMS UNDER THE ITU URBAN MACROCELL CHANNEL MODEL	468
Obi Godwin Chukwudi	TOWARDS A KNOWLEDGE-DRIVEN ECONOMY IN NIGERIA: CHALLENGES AND STRATEGIC PATHWAYS	476
Ömer Özkan	INTERACTION BETWEEN THE EFQM EXCELLENCE MODEL 2025 REVISION AND THE ISO 9001 QUALITY MANAGEMENT SYSTEM: AN INTEGRATED MANAGEMENT APPROACH	480
Özkan ÖZTÜRK Zeynep KURNAZ	THE DISCURSIVE CONSTRUCTION OF ENVIRONMENTALISM: ENVIRONMENTAL CODES ACROSS THE AXES OF VALUES, POLITICS, AND ECONOMY	487
Peri GÜNEŞ Sina APAK Yahya D. Navaei Harun BENLİ	ENHANCING SOFTWARE DEFECT PREDICTION ACCURACY: A MULTI-OBJECTIVE FIREFLY ALGORITHM APPROACH	493
Rabia İlknur ERKEN İsmail TEMİZ Mevlüt KARAKAYA	TECHNOLOGICAL EVOLUTION OF PRINTING TECHNOLOGIES: THE TRANSITION FROM TRADITIONAL METHODS TO DIGITAL AND INTELLIGENT SYSTEMS	504
Rajab Yahyazadeh Zahra Hashempour	NUMERICAL INVESTIGATION OF THE ELECTRONIC AND ELECTRICAL CHARACTERISTICS OF MULTIPLE QUANTUM WELL SOLAR CELLS In GaN / GaN	518
Raniyah RAFAA KHALAF Arif GÖK	THE ROLE OF ARTIFICIAL INTELLIGENCE IN INDUSTRIAL ENGINEERING: TRANSFORMATION TO DATA-DRIVEN DECISION MAKING AND SMART SYSTEMS	522
Serdar BİLEN Elif YAĞANOĞLU Adil ADIN Taşkın ÖZTAŞ Zekai Halıcı Durun Ali KÖSE Melda BOLAT	EFFECTS of POLYPHENOLS and/or BORON ENRICHED DERIVATIVES on GROWTH of CORN PLANTS UNDER COLD STRESS	526
Shwan SAEED Derya AVCI Engin AVCI	A COMPARATIVE STUDY OF MACHINE LEARNING ALGORITHMS FOR HEART DISEASE PREDICTION: A DECISION SUPPORT SYSTEM APPROACH	537
Sinan GÜLENÇER	FINANCIAL DISTRESS RISK IN TURKISH LISTED PACKAGING FIRMS: AN ALTMAN Z-SCORE ANALYSIS (2020–2024)	546

INTERNATIONAL TOPKAPI CONGRESS-VI

Siska Purnama Manurung Tritanio Nizar Rabulizat	BEYOND THE FILTER: DRIVERS OF GENERATION Z'S AR FACE FILTER ADOPTION IN INDONESIA	557
Syed Agung Afandi Muslim Afandi Rizki Erdayani	FROM POLICY AMBITION TO SYSTEM CAPACITY: UNDERSTANDING MISALIGNMENT IN INDONESIA'S DECENTRALIZED HEALTH GOVERNANCE	570
Azad Md. Sorwar Saimon Islam Khurshida Sharmin	"FLEXIBLE PEG-PVDF SOLID ELECTROLYTE MEMBRANES WITH ENHANCED IONIC CONDUCTIVITY FOR POUCH-TYPE LITHIUM-ION BATTERIES"	583
Tuğba TAŞDEMİR H. Zekavet KABASAKAL	ÖĞRETMENLERDE PSİKOLOJİK SERMAYE VE ÖRGÜTSEL YABANCILAŞMA İLİŞKİSİ: BİR LİTERATÜR TARAMASI	588
Validə Əliyeva Rəcəb qızı	WOMEN'S SELF-ESTEEM IN CONTEMPORARY AZERBAIJANI SOCIETY: THE INTERACTION OF PSYCHOLOGICAL, LEGAL, SOCIAL, ECONOMIC, AND RELIGIOUS-CULTURAL FACTORS	598
Yunus BULUT Arif GÖK	THE USE OF ARTIFICIAL INTELLIGENCE WITHIN THE FRAMEWORK OF INTELLECTUAL AND INDUSTRIAL PROPERTY RIGHTS	602
Yunus ERKUŞ Dilay AKSAKAL	INVESTIGATION OF THE EFFECT OF STEEL SLAG ON THE MECHANICAL PROPERTIES OF FLEXIBLE SUPERSTRUCTURE USING THE FINITE ELEMENT METHOD	609
Yunus ERKUŞ Dilay AKSAKAL	RESEARCH ON METHODS FOR CONTROLLING SNOW AND ICE ON HIGHWAY	622
Yusuf Erdem YILDIZ Hatice Zekavet KABASAKAL	ÖĞRETMENLERDE PSİKOLOJİK SERMAYENİN TÜKENMİŞLİK ÜZERİNE ETKİSİ: SİSTEMATİK BİR GÖZDEN GEÇİRME	635
Zeynep KURNAZ Özkan ÖZTÜRK	PERCEPTION OF AGING AND BEAUTY FROM A GENDER PERSPECTIVE: DOUBLE STANDARDS AND BODY POLITICS	652

SOĞUTUCU UYGULAMALARIN ANAEROBİK KAPASİTEYE ETKİSİ

Abdülhabib AKDAĞ¹, Yeliz PEHLİVAN²

1. İstanbul Sağlık Bilimleri Üniversitesi, Hamidiye Sporcu Sağlığı ve Spor Bilimleri Enstitüsü, Spor Bilimleri Ana Bilim Dalı, Tezli Yüksek Lisans Programı, İstanbul, TÜRKİYE
2. Doç.Dr., İstanbul Sağlık Bilimleri Üniversitesi, Hamidiye Yaşam Bilimleri Fakültesi, Egzersiz ve Spor Bilimleri Bölümü, İstanbul, TÜRKİYE

Özet

Anaerobik kapasite, kısa süreli ve yüksek yoğunluklu aktivitelerde vücudun enerji üretme yeteneğini belirler ve sporculardan endüstriyel çalışanlara kadar geniş bir yelpazede performansı etkileyebilir. Soğutucu ekipmanlar, kasların aşırı ısınmasını engelleyerek, enerji sistemlerinin daha verimli çalışmasına, yorgunluğun azaltılmasına ve toparlanmanın hızlanmasına yardımcı olabilir. Bu çalışma soğutucu ekipmanların türlerini, tasarım özelliklerini ve kullanım alanlarını ele alırken, anaerobik kapasiteyi etkileyen faktörleri de tartışmaktadır. Literatür taraması, soğutucu ekipmanların sporcular ve endüstriyel çalışanlar üzerindeki olumlu etkilerini ortaya koymuş, ancak ekipman türleri arasındaki farklılıklar ve kullanım protokollerinin netleştirilmesi gerektiği vurgulanmıştır. Ayrıca, ergonomi, konfor ve dayanıklılık gibi faktörler göz önünde bulundurularak soğutucu ekipmanların tasarımının optimize edilmesi gerektiği belirtilmiştir. Gelecekte yapılacak araştırmaların, daha geniş örneklerle ve farklı soğutma teknolojilerinin karşılaştırmalı analizleriyle derinleştirilmesi gerektiği ifade edilmiştir. Ayrıca soğutucu ekipmanların etkinliğini artırmak için kullanıcıya özel ayarlanabilir özellikler ve ergonomik tasarımlar önerilmektedir. Bu nedenle bu çalışmada, soğutucu uygulamalarının sporcularda anaerobik kapasite üzerindeki etkilerini incelemek amaçlanmıştır. Bu çalışma ile hem spor bilimi hem de iş sağlığı alanlarında, soğutucu ekipmanların daha geniş bir uygulama yelpazesinde kullanılmasını sağlayacak bilgi ve öneriler sunulmaktadır.

Anahtar kelimeler: Anaerobik kapasite, soğutucu uygulama, fizyoloji, performans

THE EFFECT OF COOLING APPLICATIONS ON ANAEROBIC CAPACITY

Abstract

Anaerobic capacity determines the body's ability to produce energy during short-duration, high-intensity activities and can affect performance across a wide range of individuals, from athletes to industrial workers. By preventing muscle overheating, cooling equipment can help energy systems function more efficiently, reduce fatigue, and accelerate recovery. This study examines the types, design features, and applications of cooling equipment, while also discussing the factors that influence anaerobic capacity. The literature review revealed the positive effects of cooling equipment on athletes and industrial workers, but emphasized the need for clarification of differences between equipment types and usage protocols. It also stated that the design of cooling equipment should be optimized by considering factors such as ergonomics, comfort, and durability. Future research should be further explored with larger samples and comparative analyses of different cooling technologies. Furthermore, user-specific adjustable features and ergonomic designs are recommended to increase the effectiveness of cooling equipment. Therefore, this study aimed to examine the effects of cooling applications on anaerobic capacity in athletes. This study provides information and recommendations that will enable the use of

cooling equipment in a wider range of applications in both sports science and occupational health.

Keywords: Anaerobic capacity, cooling application, physiology, performance

Giriş

Rekabetçi spor yapan sporcular, atletik performanslarını en üst düzeye çıkarmayı hedefler; bu performans artışı, kuvvet performansının artması, zamanlı aerobik ve anaerobik etkinliklerde daha hızlı tamamlanma süreleri, spor spesifik becerilerde bilişsel kapasitenin artması ve belirli süreli yarışmalarda egzersiz kapasitesinin yükselmesi gibi alanlarda gözlemlenir. Yarışma sırasında, özellikle sıcak ortamda, sporcuların vücut sıcaklıkları sıklıkla 39–40°C aralığına ulaşabilir; bu durum performans üzerinde olumsuz etkiler yaratabilir ve ısıya bağlı hastalık riskini artırabilir. Bu potansiyel olumsuz etkilerle mücadele etmek için sporcular, yarışma sırasında vücut sıcaklığının artışı azaltmak veya kontrol altına almak amacıyla çeşitli vücut soğutma tekniklerini kullanır (Adams vd., 2016, 384). Isıya maruz kalma sırasında uzuv ve ekstremitelerin kan damarları, ısı dağılımını desteklemek için genişler. Bu nedenle eller, vücut sıcaklığındaki artışları hafifletme ve ısıya maruz kalma sırasında termal rahatsızlığı azaltma potansiyeline sahiptir. Bu amaçla, ellerde dolaşan kan ile dış ortam arasındaki ısı alışverişini artırabilen bazı cihazlar geliştirilmiştir. Böylece soğutulmuş kan, venöz dönüş yoluyla vücudun merkezine geri döner ve çekirdek sıcaklığının düşmesine katkı sağlar (Douzi vd., 2020, 10).

Anaerobik kapasite (AK), kısa süreli ve yüksek yoğunluklu aktivitelerde enerji üretme kapasitesini ifade eder ve spor performansı ile iş gücü verimliliği açısından kritik bir göstergedir (Gastin, 1994, 100). Ancak yoğun egzersiz veya iş sırasında kasların aşırı ısınması, performansın düşmesine ve toparlanma sürelerinin uzamasına yol açabilir. Soğutucu eldivenler ve benzeri ekipmanlar, lokal veya genel vücut soğutması sağlayarak kas yorgunluğunu azaltabilir, enerji sistemlerinin daha verimli çalışmasına katkıda bulunabilir (Park & Kim, 2023, S260). Bu nedenle, soğutucu ekipmanların anaerobik kapasite üzerindeki etkilerinin anlaşılması hem spor bilimi hem de endüstriyel uygulamalar için önemli bir araştırma alanını temsil eder. Ayrıca, bu ekipmanların etkinliği üzerine yapılan derlemeler, tasarım ve kullanım stratejilerinin geliştirilmesine ışık tutar. Bu çalışma, soğutucu eldiven ve benzeri ekipmanların anaerobik kapasiteye etkilerini kapsamlı bir şekilde inceleyen derleme niteliğindedir.

2. Anaerobik Kapasiteyi Etkileyen Faktörler

2.1. Fiziksel Performans ve Dayanıklılık

Çeşitli fiziksel egzersizlerin uygulanma düzeyi ve bireylerin ya da sporcuların bu egzersizler sırasında ortaya koyduğu verimlilik kapasitesi, onların maksimum performans düzeyleri olarak değerlendirilir. Maksimum performansın belirlenmesindeki temel amaç, fiziksel aktivite sırasında iskelet kasları tarafından aerobik ve anaerobik metabolizma yoluyla üretilen enerji miktarını değerlendirmektir (Sözen & Akyıldız, 2018, 331). Fiziksel performans, güç, dayanıklılık ve toparlanma kapasitesi gibi birçok bileşenden oluşur ve vücut kompozisyonu ile zindelik düzeyi tarafından şekillendirilir. Güncel araştırmalar çeşitli yaşam tarzı alışkanlıklarının vücut kompozisyonunu ve anaerobik çıktıları nasıl etkilediğini giderek daha fazla incelemektedir. Kronik stres, düşük uyku kalitesi, beslenme yetersizlikleri ve tütün kullanımı gibi faktörlerin hormonal dengeyi bozduğu, inflamasyonu artırdığı ve kas onarımı ile vücut kompozisyonunu olumsuz etkilediği bilinmektedir. Bu durum, anaerobik kapasite üzerinde de ek bir olumsuz etki yaratmaktadır (Ali vd., 2025, 1).

Fiziksel performans, farklı ısınma türleri ve özellikle tüm vücut vibrasyonu (WBV) uygulamalarıyla değişebilmektedir. WBV'nin kas kuvveti, hız, çeviklik ve patlayıcı güç üzerinde olumlu etkiler yaratabildiği; bazı çalışmalarda dikey sıçrama ve sprint gibi anaerobik performans göstergelerinde anlamlı artış sağladığı belirtilmiştir. Geleneksel ısınma yöntemlerinin esneklik, hareket açıklığı ve kan akışını artırması da performansı destekler. Bu

nedenle hem ısınma içeriği hem de titreşim uygulamaları, sporcuların dayanıklılığı, hareket verimliliği ve kısa süreli yüksek yoğunluklu performans becerileri üzerinde belirleyici bir role sahiptir (Jamshidi vd., 2016, 35).

2.2. Sıcaklık, Metabolizma ve Enerji Üretimi

Isınma sırasında artan vücut sıcaklığı, kasların daha verimli çalışmasını sağlayarak metabolik süreçleri hızlandırır. Isınmanın kan akışını artırdığı ve bunun kaslara daha fazla oksijen ve besin taşınmasına katkıda bulunduğu vurgulanmaktadır. WBV'nin dolaşımı artırıcı etkisi de benzer şekilde enerji üretim süreçlerini destekler. Metabolik faaliyetlerin hızlanması, anaerobik enerji sistemlerinin daha etkin kullanılmasına olanak tanır. Bu durum kısa süreli, yüksek güç gerektiren hareketlerde sporcuların performansını doğrudan etkiler (Jamshidi vd., 2016, 35).

2.3. Kas Yorgunluğu ve Toparlanma Süreçleri

Anaerobik kapasiteyi etkileyen temel faktörler, kişinin biyolojik özellikleri, vücut yapısı ve fiziksel uyumuyla yakından ilişkilidir. Kas gücü, hız, patlayıcı kuvvet, kalp ve akciğerlerin çalışma kapasitesi, esneklik, koordinasyon ve hareket zamanlaması anaerobik performansın temel bileşenleri olarak öne çıkmaktadır. Buna ek olarak, vücut yapısı ve antropometrik özellikler, özellikle kemik yapısı, duruş ve boy-kilo oranı gibi unsurlar yüksek yoğunluklu güç üretimini etkiler. Ayrıca, düşük yağ oranı ile yüksek kas kütlesi ve kemik yoğunluğunun başarılı sporcularda belirleyici olduğu vurgulanmaktadır. Kas gücü ve dayanıklılık, ağırlık kaldırma sporunun ana gereksinimleri arasında yer alırken, aerobik kapasitenin de toparlanmayı hızlandırarak dolaylı biçimde anaerobik performansı desteklediği belirtilmektedir. Spora başlama yaşı ve düzenli antrenmanla kazanılan fiziksel gelişim de anaerobik kapasitenin gelişiminde önemli bir etkidir (Hermawan & Priyono, 2022, 38).

Titreşim uygulamalarının kan dolaşımını artırarak yorgunlukla ilişkili metabolik maddelerin birikimini azaltabileceği ve yorgunluğun gecikmesine katkı sağlayabileceği ifade edilmiştir. Yorgunluğun gecikmesi, özellikle voleybol gibi patlayıcı güç ve tekrarlı anaerobik efor gerektiren sporlarda önemli bir avantajdır. Yetersiz dolaşım ve düşük kas sıcaklığı kaslarda daha hızlı yorgunluk oluşumuna yol açarken, WBV'nin bu süreçleri olumlu yönde etkileyebileceği belirtilmiştir. Bu nedenle titreşimle desteklenmiş ısınma hem yorgunluk düzeyinin kontrol edilmesine hem de toparlanma sürecinin daha verimli işlemesine katkı sağlayan bir yöntem olarak öne çıkmaktadır (Jamshidi vd., 2016, 35).

3. Soğutucu Ekipmanlar

Spor bilimlerinde soğutma çalışmalarında kullanılan teknikler ve soğutucu ekipmanlar çeşitlilik göstermektedir; bunlar arasında soğutma giysileri, soğuk suya daldırma, buz bulamacı veya soğuk sıvı yutma, soğuk paketler, soğutma yelekleri, buz yelekleri, havalandırılmalı yelekler, su spreyleri ve hava ventilasyonu sayılabilir. Genel olarak, per-soğutma tekniklerinin çoğu, sıcak ve ılıman koşullarda egzersiz performansını iyileştirmede etkilidir ve optimum etkiyi sağlamak için egzersiz sırasında yeterli soğutma gücü kullanılması önerilir. Dolayısıyla, egzersiz sırasında yapılan soğutma müdahalesinin etkinliği, kullanılan soğutma miktarına ve deneyimlenen termal zorlanmanın derecesine bağlıdır (Douzi vd., 2020, 5). Literatürde çeşitli soğutma yöntemleri tanımlanmış olup bunlar arasında soğuk suya daldırma (5–15°C) en yaygın kullanılan tekniktir. Ayrıca soğuk hava maruziyeti (–30°C) ve soğutucu paketlerle bölgesel soğutma gibi yöntemler de bildirilmiştir. Son yıllarda, tüm vücudu hedefleyen kriyoterapi de popüler bir post-soğutma stratejisi hâline gelmiştir. Kriyoterapi, çok düşük sıcaklıktaki kuru havaya (< –100°C) kısa süreli maruz kalmayı (2–4 dakika) içerir. Bu uygulama sırasında bireyler, soğuk yaralanması riskini azaltmak için minimum düzeyde kıyafet, eldiven, kulakları örten yün bir bant, ağız-burun maskesi ve kuru ayakkabı ile çorap giyer (Bongers vd., 2017, 67).

Soğutma ceketleri (jel veya buzlu) günümüzde sıcak ortamda yürütülen spor dalında kullanılmaktadır. Bu ceketler, egzersiz sonrası 30 dakikalık bir soğutma döneminde çekirdek sıcaklığının daha hızlı düşmesini sağlar. Benzer şekilde, diğer çalışmalar da soğutma

ceketlerinin 10–30 dakika kullanımıyla çekirdek sıcaklığın daha hızlı düştüğünü göstermiştir. Ayrıca, bu ceketlerin kullanımı vücut yüzey sıcaklığını ve algılanan ısı yükünü azaltabilir. Soğutma ceketlerinin popülerliği, özellikle su veya elektrik kaynağı bulunmadığında kullanımlarının kolay olmasından kaynaklanır; bu durum diğer daha etkili soğutma yöntemlerinin (örneğin suya daldırma veya vantilatör) kullanımını engelleyebilir. Ancak bu ceketlerin etkinliğini koruyabilmesi için kullanılmadan önce buzlu suda aktive edilmeleri ve egzersiz süresince bir buz kutusunda saklanmaları gerekir (Maroni et al., 2018a, 2).

4. Soğutmanın Vücut Isısı Üzerindeki Etkileri

Isı çıkarma teknolojisi, belirli kılsız cilt yüzeylerinin özelliği olan ısı transferi için uyarlamalardan yararlanır. Avuç içlerindeki ve ayak tabanlarındaki arteriovenöz anastomozlar (AVA'lar) ve venöz pleksuslar, vücut çekirdek sıcaklığı yükseldiğinde ısı dağılımı için etkili mekanizmalardır. Soğutmada kullanılan cihazlar, kanı ele çekmek ve avuç içi yüzeyinin altındaki venöz pleksusun dolumunu artırmak için tüm ele 35 ila 45 mmHg subatmosferik basınç uygulamak için kullanılır. Bu avuç içine uygulanan bir ısı emici ısıyı çeker ve venöz kanı soğutur (Grahn vd., 2005, 972).

Sıcak çevre koşullarında egzersiz yapan kaslar, yüksek düzeyde ısı üretir. Bu nedenle vücut, ısı dengesini korumak için vazodilatasyon ve terleme gibi ısı dağıtıcı mekanizmaları devreye sokar. Sıcaklık artışlarını sınırlamak ve ısı kaybını artırmak için egzersiz sırasında çeşitli soğutma stratejileri uygulanır. Örneğin, yapılan bir çalışmada, gövdeyi ısı kazanımından koruyan bir buz yeleği kullanıldığında çekirdek sıcaklığındaki artışın daha sınırlı olduğu gözlemlenmiştir. Diğer çalışmalar da bu bulguları desteklemektedir (Adams vd., 2016, 385).

5. Soğutucu Ekipmanların Anaerobik Performansa Etkisi

Soğutma, çekirdek sıcaklığındaki artışı sınırladığı için anaerobik güç gerektiren sonraki eforlar üzerinde olumlu bir etki yaratabilir. El soğutma cihazlarının, özellikle glabrous (kılı olmayan) el yüzeylerinde bulunan damar yapısı sayesinde ısıyı daha hızlı uzaklaştırdığı ve buna bağlı olarak çekirdek sıcaklığını daha etkin düşürdüğü gösterilmiştir. Bu durum, yüksek sıcaklık nedeniyle merkezi yorgunluğun erken başlamasını önleyebilir. Soğutucu yelekler de benzer şekilde kısa süreli dinlenme aralarında çekirdek sıcaklığının düşmesine yardımcı olmuş, ancak el soğutma cihazlarının bazı koşullarda daha hızlı soğutma sağladığı rapor edilmiştir. Çekirdek sıcaklığındaki düşüşün, anaerobik güç üretimi sırasında sinir-kas iletişimini ve kas kasılma verimliliğini koruyabileceği düşünülmektedir. Bu nedenle, oyun araları veya kısa dinlenme dönemlerinde yapılan soğutma müdahaleleri, özellikle sprint, patlayıcı güç veya kısa yoğun tekrarlar gibi anaerobik yüklenmeler için yeniden performans üretme kapasitesini artırma potansiyeli taşır (Maroni vd., 2018a, 444). Araştırmalar, soğutucu eldivenler kullanıldığında çekirdek sıcaklığın, soğutma yapılmayan duruma göre önemli ölçüde daha hızlı düştüğünü göstermektedir. Tek el veya iki el kullanımı ile elde edilen soğutma oranları, çoğu durumda buz yeleği ile karşılaştırılabilir seviyelerdedir. Soğutucu eldivenler, taşınabilirliği ve kolay uygulanabilirliği sayesinde, buzlu suya daldırma veya soğuk depolama gerektirmemesi nedeniyle sıcak ortamlarda yapılan saha sporları için pratik bir alternatif sunar (Maroni vd., 2018b, 486).

Genellikle anaerobik kapasiteyi belirleyen mekanizmalar tek bir doku veya sistemle sınırlı değildir (istisnai durum: kas kan akımının tamamen kesildiği koşullar). Organizmanın asit-baz dengesini koruma stratejileri; vücut sıvıları arasında iyon değişimleri ve üretilen CO₂'nin solunum yoluyla uzaklaştırılması gibi çoklu süreçleri içerir. Bu nedenle anaerobik kapasite yalnızca anaerobik kas dokusundaki mekanizmalarla değil, vücudun diğer bölgelerindeki düzenleyici süreçlerle de belirlenir. Bu açıdan bakıldığında, anaerobik kapasiteyi yalnızca kas dokusuna indirgemek yerine bütüncül bir sistem yaklaşımıyla ele almak gerekir. Bütüncül bakış, organizmanın anaerobik son ürünleri biriktirme kapasitesine odaklanır. Bu bakışa göre anaerobik metabolizma ile yeniden sentezlenen ATP miktarı, tüm vücut genelinde biriken anaerobik son ürünlerle ilişkilidir. Üretilen laktatın daha sonra başka bir bölgede oksidasyona

uğraması durumunda, bu süreçte açığa çıkan enerji aerobik metabolizmanın bir parçası olarak değerlendirilmelidir. Çünkü sonuçta karbon iskeleti oksidatif yolla CO₂'ye kadar parçalanır. Kas içinde pH düzenlenmesinin laktat oksidasyonu sayesinde iyileşmesi sonucunda yapılan ek iş de aerobik kabul edilir (Green, 1994, 172).

5.1. Toparlanma Sürelerinin Hızlanması

Soğutma uygulamaları, toparlanma sürecini hızlandırarak sporcuların bir sonraki efora daha hazır hâle gelmesini sağlar. Çalışmalarda hem soğutucu yelek hem de el soğutma cihazlarının, egzersiz sonrası 30 dakikalık süreçte çekirdek sıcaklığını kontrol şartına göre daha hızlı düşürdüğü, bazı cihazlarda bu etkinin daha belirgin olduğu bulunmuştur. Çekirdek sıcaklığındaki daha hızlı düşüş, kalp atım hızı, termal yük algısı ve cilt sıcaklığı üzerinde de olumlu etki yaratmış ve sporcuların kendilerini daha az ısınmış hissetmelerini sağlamıştır. Soğutmanın bilişsel toparlanmayı da etkileyebileceği ifade edilmiş; sıcaklık azaltıldığında tepki süresi ve dikkat gibi zihinsel süreçlerin daha stabil kaldığı görülmüştür. Bu durum, özellikle sıcak ortamlarda kısa mola sonrası oyuna geri dönen sporcular için hem fiziksel hem bilişsel toparlanmanın daha hızlı gerçekleşmesi anlamına gelmektedir (Maroni vd., 2018a, 444).

6. Soğutucu Ekipmanların Avantajları ve Sınırlamaları

6.1. Avantajlar

Yoğun bir egzersiz sonrası toparlanmayı artırma yeteneği, özellikle profesyonel ve elit spor ortamlarında giderek daha fazla önem kazanmıştır. Sporcular, rakiplerine karşı yasal ve rekabetçi bir avantaj elde etmek için soğutucu ekipmanları kullanır. Egzersiz, vücutta öncelikle vücut sıcaklığındaki artıştan kaynaklanan bir stres yanıtı oluşturur. Egzersiz sonrası vücut sıcaklığını düşürerek stres seviyesini azaltmak, vücudun daha hızlı toparlanmasına yardımcı olur ve sonraki antrenman veya yarışmalarda performansın artmasını sağlar. Egzersiz sonrası soğutucu ekipmanları kullanarak soğutma, iltihaplanmayı, kalp atış hızını ve kardiyak çıktıyı azaltır ve analjezik etkiler sağlayarak toparlanma süresini kısaltabilir (Adams vd., 2016, 384). Özellikle, önceki çalışmalar, sıcakta egzersiz sonrası dikkat, karar verme ve çalışma belleğinde bozulmalar olduğunu bildirmiştir, bunlar genellikle bu koşullar sırasında artan ter çıkışına neden olan yüksek gövde sıcaklığının neden olduğu >%2'lik vücut kütlesi kayıplarıyla ilişkilidir. Daha da önemlisi, bitkinliğe kadar koşma sırasında kullanılan boyun soğutma, sıcakta egzersiz sonrası basit bilişsel görevlere kıyasla daha karmaşık bilişsel görevleri iyileştirmiştir. Bu nedenle, sıcakta egzersizden önce soğutma uygulamasının, soğutma yapılmamasına kıyasla vücut sıcaklığındaki ve terleme oranındaki artışı geciktirmesi, bunun da karmaşık bilişsel işlevleri (uyanıklık ve karar verme gibi) artırarak bisiklet yarışı performansını iyileştirmesi mümkündür (Maroni vd., 2019, 2).

6.2. Sınırlamalar ve Potansiyel Riskler

Periferik bölgelerin aşırı soğutulmasının, kas içi sıcaklığı önemli ölçüde düşürebileceği ve böylece enzimatik süreçleri ve sinir iletimini yavaşlatabileceği, bunun da kuvvet üretim hızı ve kas dayanıklılığı üzerinde olumsuz etkiler yaratabileceği vurgulanmaktadır (Douzi vd., 2020, 11). Örneğin soğutucu eldiven kullanımına ilişkin olası bir sorun, elin soğuk bırakılması nedeniyle bazı el becerilerinde bozulma olasılığıdır. Örneğin, 10°C suya 5 dakika boyunca elin daldırılması, soğutma yapılmayan duruma kıyasla el becerisinde önemli bir düşüşe yol açabilir. Top atma, sopayı veya topu yakalama ve tutma gibi beceriler birçok takım sporunda başarının ayrılmaz bir parçası olduğundan, soğutucu eldivenlerin bu beceriler üzerindeki etkilerini belirlemek önemlidir (Maroni vd., 2018b, 486).

7. Sonuçlar

Soğutucu eldivenler ve benzeri ekipmanlar, vücut sıcaklığını düzenleyerek özellikle kısa süreli ve yüksek yoğunluklu aktivitelerde anaerobik performansın korunmasına katkı sağlayabilmektedir. Çalışmalar, lokal soğutmanın kas yorgunluğunu azalttığını, ısı kaynaklı performans düşüşlerini sınırladığını ve enerji üretim süreçlerinin daha verimli işlemesine yardımcı olduğunu göstermektedir. Eldiven gibi periferik soğutma ekipmanları hem

sporcularda hem de sıcak ortamlarda çalışan bireylerde anaerobik kapasiteyi dolaylı olarak artırıcı bir etki yaratabilmektedir. Bu etkiler; daha düşük algılanan yorgunluk, daha istikrarlı kas sıcaklığı ve daha hızlı toparlanma süreçleri şeklinde gözlemlenmektedir. Bununla birlikte, literatürde mevcut bulgular farklı türde ekipmanlar ve uygulama protokolleri arasında değişkenlik göstermekte, bu nedenle etkilerin her durum için aynı düzeyde olmadığı da belirtilmektedir.

8. Öneriler

Gelecek araştırmalar, soğutucu eldivenler ve benzeri ekipmanların anaerobik performans üzerindeki etkilerini daha kapsamlı ve genellenebilir sonuçlarla ortaya koymak için çeşitli alanlarda derinleştirilebilir. İlk olarak, mevcut çalışmaların çoğu sınırlı örneklem gruplarıyla yürütülmüş olduğundan, daha geniş katılımcı profilleri içeren araştırmalara ihtiyaç vardır. Farklı yaş, cinsiyet, kondisyon düzeyi ve spor branşlarına sahip bireyler üzerinde yapılacak uzun süreli çalışmalar, ekipmanların gerçek etkilerini daha net bir şekilde ortaya koyacaktır.

Ayrıca, soğutma yöntemlerinin türleri arasındaki farklılıklar da henüz yeterince araştırılmamıştır. Jel bazlı, sıvı dolaşım, hava akışıyla soğutma gibi farklı teknolojilerin karşılaştırmalı analizleri, hangi yöntemin hangi durumlarda daha etkili olduğunu belirlemeye yardımcı olacaktır. Bu tür değerlendirmeler, hem spor biliminde hem de iş sağlığı alanında uygulanabilir protokollerin geliştirilmesini kolaylaştıracaktır.

Bunun yanında, soğutma uygulamalarının fizyolojik mekanizmalarını anlamaya yönelik biyokimyasal analizlere ağırlık verilmesi önemlidir. Kas içi sıcaklık değişimleri, laktat birikimi, oksijen kullanım kapasitesi ve metabolik yanıtlar gibi biyofizyolojik göstergeler üzerinden yapılacak araştırmalar, ekipmanların performans üzerindeki etkilerini daha ayrıntılı biçimde açıklayabilir.

Son olarak, teknolojik gelişmelere paralel olarak daha hafif, ergonomik ve kullanıcıya özel ayarlanabilir soğutucu ekipmanların geliştirilebilir. Gelecekte yapılacak çalışmaların mühendislik tasarımı, malzeme bilimi ve biyomekanik alanlarıyla disiplinler arası bir yaklaşım içinde yürütülmesi büyük önem taşımaktadır. Bu tür bütüncül çalışmalar, soğutma teknolojilerinin hem sporculuk hem de endüstriyel kullanımda daha etkili ve güvenli hale getirilmesine katkı sağlayacaktır.

KAYNAKLAR

- Adams, W. M., Hosokawa, Y. & Casa, D. J. (2016). Body-Cooling Paradigm in Sport: Maximizing Safety and Performance During Competition. *Journal of Sport Rehabilitation*, 25(4), 382-394.
- Ali, H., Omoush, R., Amawi, A. & Ghazzawi, H. (2025). Body composition and anaerobic power: correlational analysis in male athletes. *Front. Sports Act. Living*, 7:1666296.
- Bongers, C. C. W. G., Hopman, M. T. E. & Eijssvogels, T. M. H. (2017). Cooling interventions for athletes: An overview of effectiveness, physiological mechanisms, and practical considerations, *Temperature*, 4(1), 60-78.
- Douzi, W., Dupuy, O., Theurot, D., Smolander, J. & Dugué, B. (2020). Per-Cooling (Using Cooling Systems during Physical Exercise) Enhances Physical and Cognitive Performances in Hot Environments. A Narrative Review. *International Journal of Environmental Research and Public Health*, 17, 1031.
- Gastin, J. B. (1994). Quantification of anaerobic capacity. *Scandinavian Journal of Medicine & Science in Sports*, 4, 91-112.
- Grahn, D. A., Cao, V. H. & Heller, H. C. (2005). Heat extraction through the palm of one hand improves aerobic exercise endurance in a hot environment. *Journal of Applied Physiology*, 99, 972-978.
- Green, S. (1994). A definition and systems view of anaerobic capacity. *European Journal of Applied Physiology*, 69, 168-173

- Hermawan, R. & Priyono, D. (2022). Anthropometry and anaerobic exercise to aerobic athletes in weightlifting athletes. *Advances in Health and Exercise*, 2(2), 38-44.
- Jamshidi, M., Jahromi, M. K., Salesi, M., Chari, M. H., Mohajerani, R. & Dashtiyani, A. A. (2016). The effect of three methods of warm-up on the anaerobic power, agility, speed, flexibility and fatigue index of elite female volleyball players. *Turkish Journal of Kinesiology*, 2(3), 34-42.
- Maroni, T., Dawson, B., Barnett, K., Guelfi, K., Brade, C., Naylor, L., Brydges, C. & Wallman, K. (2018a). Effectiveness of hand cooling and a cooling jacket on post-exercise cooling rates in hyperthermic athletes. *European Journal of Sport Science*, 18(4), 441-449.
- Maroni, T., Dawson, B., Dennis, M., Naylor, L., Brade, C. & Wallman, K. (2018b). Effects of Half-Time Cooling Using A Cooling Glove and Jacket on Manual Dexterity and Repeated-Sprint Performance in Heat. *Journal of Sports Science and Medicine*, 17, 485-491.
- Park, J. & Kim, J. (2021). Effects of cooling glove on the human body's recovery after exercise and improvement of exercise ability. *Technology and Health Care*, 31, S259-S269.
- Sözen, H. & Akyıldız, C. (2018). The Effects of Aerobic and Anaerobic Training on Aerobic and Anaerobic Capacity. *The Journal of International Anatolia Sport Science*, 3(3), 331-337.

A FACTOR INFLUENCING MANAGERS' BEHAVIORAL LEVELS: THE INFAMIA PROBLEM

Prof. Dr. Adnan Celik

Selcuk University, FEAS, Department of Business, Turkiye.

ORCID ID: 0000-0002-8538-9937

Abstract

Today is the age of organized society. Various organizations can be established, from private businesses to public institutions. Volunteer organizations and civil society organizations also exist. Organizations meet the very different material, social, and spiritual needs of people. Organizational structures interact with various elements. These can generally be grouped under the headings of internal and external environment. Or, a distinction can be made between the immediate, national, and international environment. Organizational managements contain subsystems within themselves. At every level, one can find a manager appointed there. These operate within certain rules and principles. There are also many legal and ethical frameworks that bind the parties. An organization member is not expected to act entirely according to their own will. Generally accepted principles create a behavioral framework. Here, the desired behaviors within the organization are established. Individual behaviors gain meaning at the behavioral level and become social behaviors. Problems arise for those who deviate from this. One of these is the problem of infamia. Those who lose their status and reputation become, in a way, infamous. A normal manager would not want to fall into this situation, because they may face many problems. This study consists of three separate sections. Under the heading "Literature Review", the concepts of behavior, behavioral level, and infamia are explained. Methodology is introduced in the second section. The third section deals with findings and discussion. The study draws attention to the issue of infamia that can be encountered in organizational management. This problem is seen as an issue affecting the behavioral levels of managers. At the end of the study, various solutions are also developed for relevant parties.

Keywords: Behavioral Level, Social Status, Infamia, Infamia in Managers

INTRODUCTION

Our era reflects a period where organization is reaching ever larger dimensions. Naturally, actions that individuals cannot perform alone are carried out by organizations. Every business organization consists of an "internal" and "external" environment. A large-scale business organization or a company operating at an international level also encounters "global" environmental elements. Every organization contains different hierarchies within itself. In this context, management levels also stand out. In other words, one can speak of a kind of management pyramid. At each level, certain authorities and responsibilities are defined. Those related to management belong to the managers. Every manager cannot act as they wish. The organization has a vision and mission. Organizational culture can also include limiting or supporting factors. Above all, organizational legitimacy is important. There are generally accepted patterns of behavior and principles that must be followed. At this point, we can talk about the behavioral level.

The behavioral level is concerned with the desired behaviors within a social group. Individual behaviors gain meaning at the behavioral level and become social behaviors. Just as every individual has unique characteristics; Every organization has its own unique structure. Organization members and environmental factors generally accept these structures. In other words, a kind of social behavioral framework is formed. However, the "theoretical behavioral

framework” and the “actual behavioral framework” are also encountered. Various problems affect the behavioral frameworks of managers. This study clarifies one of these problems: the infamia issue. A manager who is admired and envied may deviate from this behavioral framework. There are various boundaries here. If a serious crime has been committed, various penalties may be imposed. Legal power and status may be lost. A shameful situation may arise. Even convictions may be issued. A manager in this situation is called infamis because they have committed the act of infamia.

The study consists of three main sections. The first section clarifies the literature. Here, the concept and scope of behavior are first discussed. Then, the behavioral framework is addressed. The third subsection explains the topic of infamia. The second section is titled methodology. Here, the purpose and importance of the research are first introduced. Then, the research method is specified. Findings and discussion are shared in the third section. Here, three main topics are addressed. The first is the interaction between managers and behavioral levels. The second sub-section focuses on the interaction between managers and social status. The third sub-section reveals the effects of the infamy problem on managers' behavioral levels. The study concludes with a conclusion and general evaluation.

1. LITERATURE REVIEW

1.1. The Concept and Scope of Behavior

Behavior is an action directed towards living beings. The activities of living beings vary considerably, as each living being has its own unique structure. Behavior can be approached from many perspectives. For example, it can be interpreted from the perspective of normative, positive, and rational sciences. Or, explanations can be made according to any of the natural, social, educational, engineering, natural, health, and applied sciences. Since the following explanations will focus more on the social sciences, emphasis can be placed on the natural sciences here. These sciences try to reveal the workings of our world and the universe. One of its main branches is biology. Behavior, biology, and the interaction of organisms can also be evaluated within this scope. Biologically, behavior is concerned with the way an organism moves in any given environment. It is also closely related to the study of everything that can be observed and measured. It rarely involves randomness. It is usually causal. It also includes motivations in line with specific goals. When focusing on the human element, one can encounter causes and effects unique to humans. When examined at the individual level, it can be seen that the behaviors exhibited and their outcomes are even more diverse.

The following statements can be shared regarding the concept and scope of behavior (Kolasa, 1979: 9; Erdogan, 1997: 2; Eroglu, 2017: 1-2; Eren, 2017: 2-3; Guney, 2007: 26; Kocel 2020: 646; Simsek & Celik, 2025: 16):

-Behavior is primarily the activities that a human or animal displays individually or collectively.

-Behavior, associated with the concept of acting, can be seen as attitude, course, and manner of movement.

-In general, it is the response of an organism to specific stimuli.

-According to psychologists, a stimulus is necessary for a person to behave. When a stimulus arrives, the person behaves. This process can be formulated as “stimulus - organism - response = behavior”.

-In the most general sense, behavior is a concept that encompasses all human actions (effects and reactions). One of the most important characteristics of human behavior, which forms the basis of psychology, is its complex and multifaceted nature. From a behavioral perspective, it is a fact that every event is the result of a set of preceding conditions. This is related to the principle of determinism.

1.2. Behavioral Level

The social interaction space consisting of the desired behaviors within a social group is called the behavioral plane. According to the open system theory, every social structure consists of sub-social systems; and every sub-social system consists of many behavioral planes that constitute it. Individual behaviors gain meaning at the behavioral plane and become social behaviors (Erdogan, 1997: 65; Eroglu, 2017: 99-100; Simsek et al., 2025: 47).

Individual behaviors gain meaning at the behavioral plane and become social behaviors. Just as every individual has their own unique beliefs, attitudes, character, temperament, and abilities, every institution also has its own unique social structure, desired behaviors, value judgments, and belief systems. These are understood and made functional by individuals within certain institutional standards. Here, the social behavioral plane comes into play. At the social behavioral plane, two different behavioral planes can be mentioned: the “theoretical behavioral plane” and the “actual behavioral plane”. The theoretical framework of behavior is established by general and specific rules unique to the organization. Those involved are expected to fulfill all the requirements of this framework and comply with the general and specific rules. However, these rules may not always be fully adhered to. The mismatch between individual interests and organizational interests, and/or individual goals and organizational goals, is a contributing factor. Thus, a new framework of behavior emerges based on the difference between the theoretical and the real situation, and this is called the “real framework of behavior”. The organization's framework of behavior is formed more according to the real situation than to theoretical assumptions (Tutar, 2010; Simsek & Celik, 2025: 47).

1.3. Infamia

Infamia was a widely used word in Roman culture. It was used to mean the “loss” of legal or social status. It also carried connotations of guilt, disgrace, shame, and loss of reputation. It involved a person losing their power and certain legal rights. Those who committed the act of infamia were declared infamis. Those who fell into this situation lost many things. Previously admired or envied, they became ostracized. Their power and prestige vanished. Those around them suddenly began to distance themselves. Depending on the severity of the crime, even imprisonment could be imposed. Roman law contained provisions that strengthened concepts such as loyalty, faithfulness, honesty, trust, and confidence. These were collectively called “fiducia”. Reputation (fama) was prioritized. Infamy was an undesirable state (McGinn, 1998: 65; Chiusi, 2013: 143-144; Rašljanin, 2023: 54; Infamy, 2025).

Attention can also be drawn to the legal dimensions of infamy. Because no one becomes disgraced for no reason (with exceptions). No one wants to be in a shameful situation in the public eye. For a normal person who has lost their reputation, certain socio-psychological problems arise. This situation becomes even bigger if it involves a crime. Even a conviction for a detected crime may come into question. In early common law, there were various sanctions for conviction for a disgraceful crime. After the loss of trust, the right to testify on any matter could also be lost. The criterion for a crime to be considered disgraceful was whether the perpetrator was branded as unreliable. Therefore, the concept was initially limited to crimes called perjury. However, its scope was later expanded. Crimes involving fraud or corruption were also included. Eventually, all serious crimes came to be considered infamy. Nevertheless, the inability to testify due to infamy has been abolished by law in England and generally in the United States (Infamy, 2025). The words infamy and infamy have survived to this day. The meanings of the words may have changed. Some topics may have been removed; some may have been added. However, there are some negative situations that closely concern business or organizational managers.

2. METHODOLOGY

2.1. Purpose and Importance of the Research

Management is a significant activity. It's a profession. It's an art. In fact, it even has a scientific aspect. Based on this, it can be said that “successful organizations are the product of both successful entrepreneurs and successful leader-managers”. Leader-manager or manager-leadership requires the harmonization of certain factors. One of these is the behavioral level within the organization. Business organizations, public institutions, or other organizations are a type of social system. In these, the social group is also dominant. Within groups, a certain pattern of behavior emerges. Those that are generally accepted or considered legitimate form a framework. This situation is also consistent with the elements of organizational culture. It can even be strengthened by the organizational vision and mission. However, the desired behaviors may not always be present. Managers, in particular, may face many negative situations. Those that do not conflict with the behavioral framework may be overcome through teamwork. However, there are difficulties for those that contradict the behavioral framework. In particular, a manager committing the act of infamy (becoming infamous) leads to very serious problems. Someone who loses their social status and reputation can also harm their organization and team. Once the loss of legal or social status is clearly established, certain consequences follow. That is, once this is proven, the relinquishment of authority and responsibility is expected.

2.2. Research Method

This study focuses on the dimensions of “behavioral levels, social status, infamia, and infamia in managers”. Attention is also drawn to their interactions. The topic might seem generally well-known, and perhaps not even considered a top priority from an organizational management perspective. However, the following point makes the study somewhat unique: “There is an insufficient number and quality of studies on the interaction between behavioral levels and infamia”. This issue is not unique to our country; many examples exist globally. In this study, generally accepted literature was primarily examined. Current assessments in open sources were also analyzed. The topic was enriched with information and documents from popular publications. Ultimately, an attempt was made to produce significant theoretical knowledge.

3. FINDINGS AND DISCUSSION

Three main topics are addressed here. First, the interaction between managers and behavioral levels is one of the aspects that constitute the subject of organizational behavior. Therefore, it is considered beneficial to reveal the interaction between managers and behavioral levels. The second dimension focuses on the interaction between managers and social status. Finally, the topic of infamia is discussed. That is, the effects of the infamia problem on managers' behavioral levels are presented.

3.1. Interaction Between Managers and Behavioral Levels

Organizational behavior encompasses numerous internal and external activities relevant to any business, institution, or organization. These include topics such as “behavioral level, status, social status, role, role behaviors, social institutions, culture, organizational culture, beliefs, attitudes, personality, perception, learning, communication, motivation, leadership, groups and management, team building, conflict and management, alienation and management, stress and management, absenteeism, organizational change, organizational development, social responsibility, etc.”. Furthermore, regarding the activities of individuals within the organizational structure, various frequently occurring situations such as “resentment, low morale, overt or covert conflicts, disciplinary actions and threats of

disciplinary action, internal organizational politics, and power struggles” may arise (Kocel 2020: 646; Simsek & Celik, 2025: 17).

The behavioral level holds particular importance within the context of organizational behavior. Because organizations are, first and foremost, social systems. These systems contain various social groups. Both organizational structure and group norms have boundaries. Some behaviors and actions may be desirable, while others may be undesirable. Appropriate and desirable behaviors form acceptance patterns. Micro-level acceptance patterns can gradually create macro-level acceptance patterns as well. This situation can also reveal a kind of system hierarchy. Because behaviors and actions can form sub-units of a social system. Sub-social systems can also form the social structure of the organization. Ultimately, movements can spread from individual behaviors to institutional behaviors that permeate the entire organization.

The behavioral plane consists of several factors. These factors can be classified and grouped among themselves. A dual distinction has been made here. That is, explanations have been made within the scope of “general” and “specific” rules (Erdogan, 1997: 66-69; Guney, 2000: 25; Eroglu, 2017: 101-107). General rules are a type of social norm. These rules have the following characteristics: “-They are rules that ensure the orderly continuation of social life and are related to the entire society. -They are rules that are valid at all levels of behavior. -They can be grouped into two categories: rules with sanctions (laws, decrees, regulations, and bylaws) and rules without sanctions (customs, traditions, etiquette, and morals), which have a standard dimension of movement and behavior. -They are social forces that compel individuals to behave in a certain way in certain environments and conditions. Therefore, individuals may face various penalties when they do not act in accordance with social norms. -General rules, although with minor differences, are generally the limiting factors of all levels of behavior”. Specific rules, on the other hand, have the following characteristics: “-They are a collection of rules related to the level in which the individual is located. -Often, written rules established depending on the level of behavior may also include traditional unwritten rules. -Since they encompass the specific rules related to each level of behavior, they may not be valid in those outside the relevant level. -They play a major role in the differentiation of levels of behavior”. Every business organization can consist of various sub-units. Every organization has a capacity. Here, we can talk about scale or size, because this closely affects two aspects. Firstly, the management levels. Secondly, the interactions of those at these levels with their behavioral planes. Behavioral planes, as explained above, can include many “general” and “specific” rules. They can also be related to different factors or issues. These can become more comprehensive in large-scale businesses. The situation may be different in small and medium-sized enterprises (SMEs). They can even appear in different forms in public institutions or voluntary organizations. What is important is the formation of behavioral planes within each organization. These generally accepted principles closely concern all parties. All levels of management, starting with top executives, should have a stakeholder culture. Behavioral planes do not only bind subordinates; they closely concern the entire business or organization. Those who demonstrate a collaborative and participatory approach in this regard achieve success more easily.

3.2. Interaction Between Leaders and Social Statuses

The needs and values of a society help determine the place of its people within the group or society. In today's complex societies, relationships between people, people and objects, people and groups, and finally between groups are established through statuses. In a sense, society creates interrelated statuses. It is also a known fact that the social structure ensures the formation of status by assigning various meanings and roles to individuals. Status is seen in everyday speech as “an indicator of respect or prestige”. Society assigns various meanings and roles to individuals. Each position consists of a set of beliefs and expectations that

distinguish it from others. A person may have a particular character, but the same person may also have more than one status at a given moment. For example, when a person is both the head of the family and a teacher, they have two statuses at once. This person's teacher status is more prominent at school, especially during the day, while their father status is more prominent at home, especially in the evenings. To summarize briefly; people's statuses can vary and change very rapidly. As the degree of complexity increases in a society and the education and skill levels of individuals improve, their status also increases and becomes more complex (Ozkalp, 2004: 45; Simsek et al., 2025: 48-49).

The definition of social status can begin with status itself. Every individual may have a unique social status. At the same time, one social position can differ from another social position, thus revealing social status. Social status is the place an individual occupies in the social structure. It is the area of social relationships in which individuals are located within the behavioral plane. It is the position or rank that those around the individual objectively deem appropriate for them within society. It is the collection of roles or role obligations that the individual will assume within the group. Or it is the order of importance of the individual's place within the social group. Social status, as a more specifically defined system of relationships or a collection of regulated behaviors within the behavioral plane, differs from the behavioral plane, which has more general characteristics (Kızılcelik, 1992: 397; Erdogan, 1997: 77-78).

3.3. A Factor Affecting Managers' Behavioral Levels: The Problem of Infamia

As mentioned earlier, managers engage in certain interactions. In the context of our topic, behavioral levels and social statuses have been clarified. Here, concise information about the management profession and management levels is shared first. Subsequently, explanations are given about the theoretical and actual behavioral levels. Finally, attention is drawn to the issue of infamia, which can be encountered in organizational management. In other words, this issue, which can negatively affect the behavioral levels of managers, has been analyzed. Management is the practice of the management profession. The units where management is exhibited include employees at all levels. In institutions or organizations, some people perform jobs or tasks. These constitute the managed group. Others provide coordination and direct and manage. These are the managers. Here, there are functions such as “planning, organizing, directing, coordinating, and controlling”. These are performed by managers. In other words, there is a series of activities that concern all managers, from the highest-level executive to the lowest-level one. While management is the bridge to achieving goals, managers should be seen as those who design this bridge. The bridge metaphor here refers to a kind of organizational design. Naturally, system building, institutionalization, and sustainability are also necessary. This can be provided by leading managers or executive leaders. These individuals should be selected from among those who are well-educated in their field, possess various competencies, and have field experience. Such individuals can both understand the management profession well and maintain a balance between authority and responsibility. It should not be forgotten that company managers will be held accountable when the time comes. They are even held responsible for the work of their team members (Gulick, 1937; 1-9; Kocel, 1983; 6; Eren, 2019: 4-6; Kocel, 2020; 128-129; Celik, 2025: 10).

Just as every individual has unique beliefs, attitudes, character, temperament, and abilities, every institution also has its own unique social structure, desired behaviors, values, and belief systems. These are understood and made functional by individuals within certain institutional standards. This is where the social behavioral plane comes into play. Within the social behavioral plane, two different behavioral planes can be distinguished: the “theoretical behavioral plane” and the “actual behavioral plane”. The theoretical behavioral plane is formed by general and specific rules unique to the institution. Those involved are expected to fulfill all the requirements of this behavioral plane and comply with the general and specific

rules. However, these rules may not always be fully complied with. The mismatch between individual interests and organizational interests, and/or individual goals and organizational goals, is a contributing factor. Thus, a new behavioral plane emerges based on the difference between the theoretical and the real situation, and this is called the “actual behavioral plane”. The organization's behavioral framework is formed more according to the real situation than to theoretical assumptions (Tutar, 2010; Simsek et al., 2025: 47).

The historical use of the word “infamia” is known to date back to the Ancient Roman period. This word inherently carries some negative connotations. In the specific context of our discussion, it refers to the loss of reputation for an official. Someone who loses their reputation also loses their previous social status or institutional power. A person who loses their legal or social status becomes a kind of “infamy” figure. Various difficulties await someone declared infamy. First and foremost, losing reputation is a significant negative event because it implies a kind of guilt. In social culture, it can also be seen as disgrace and shame (McGinn, 1998: 65; Chiusi, 2013: 143-144; Rašljanin, 2023: 54; Infamy, 2025). It can be quite difficult for someone in this situation to manage a team effectively, because a crucial component of leadership or managerial leadership has been lost.

The concept of “infamy” has persisted to this day in various forms. While the words used may differ, the outcome is similar. A manager may exhibit inappropriate behavior or commit acts that constitute a crime. Of course, nobody wants this to happen. However, if it does, various sanctions may be imposed. Whether it's a private business or a public institution, crimes are punishable. The crimes of company managers are regulated under the Law No. 5326 on Misdemeanors, the Turkish Commercial Code No. 6102, and the Law No. 6698 on the Protection of Personal Data. For public officials, the Civil Servants Law No. 657 provides various provisions. The main thing is to avoid falling into these situations.

For the continuation of the corporate structure, managers must demonstrate the necessary sensitivity. Because the system wasn't easily established. A great deal of effort, both tangible and intangible, has been involved. Entrepreneurs, managers, and personnel have worked together to create order. They have also established a socially meaningful system. Within the organization, some social relationships and developments have occurred. Even emotional reactions have been observed. Naturally, different behavioral styles may arise. Some members of the organization may be consistent with their personal identities, while others may be inconsistent (Zavyalova et al, 2016: 461). This also applies to managers. What is important is the preservation of the organization's behavioral norms. Otherwise, each manager may propose different methods and principles, and may even want to implement some of them. Good intentions are necessary. When faced with a problem, it may not be enough for only the stakeholders to be sensitive; sensitivity is needed throughout the company. An effective company can continue on its path by demonstrating its distinctiveness. Strong management also means transparent management. Well-intentioned stakeholders need to be directly protected. Those who are not acting in good faith or who commit crimes should be directly removed. Some may take a forgiving approach, or say, “Let's resolve this internally”. What matters is formal behavior. Transparency and a legal framework are essential for everyone. Organizations that do this will see their reputations rise. Those who gain the trust of both internal and external stakeholders will continue on their path successfully (Ansari, 2024; Shi, 2025). It must be emphasized once again that “Activities must be in accordance with organizational culture, legal framework, and ethical values”. These guidelines must be internalized by all parties. It should be stressed that those who do not comply may face infamy; that is, they should be informed that they may be declared infamy.

4. CONCLUSION AND GENERAL EVALUATION

Every organization is a kind of behavioral plane institution. Therefore, the structure of organizations can be considered a behavioral plane. This plane naturally contains certain

statuses. Statuses are useful if used for cooperation. In other words, there is a linear relationship between the success of a business or any organization and its behavioral planes. Various benefits are obtained if both those in positions of status and their subordinates conform to generally accepted planes. Many desirable behaviors can occur at both the micro and macro levels. As long as these are consistent with organizational culture and ethical principles, there is no problem. Behaviors in this sense form a structure. Subsequently, areas of social interaction emerge. Contemporary management demonstrates sensitivity to these areas of social interaction. Leadership means guiding and managing subordinates in line with organizational goals.

Ethical principles and moral behavioral boundaries are for everyone's benefit. Undermining them harms the organization and its stakeholders. There are problems awaiting those who disregard the rules and act outside the legitimate framework. Unintentional mistakes can be tolerated. However, knowingly acting improperly is not tolerated. Those who knowingly commit a crime will be punished. Those who act against their colleagues are ostracized. Those who harm the organization pay the price. Losing prestige as a result of bad behavior is not good. Those who lose their legal or social status also suffer psychologically. Actions that are unacceptable and vehemently rejected are considered “infamy”. Those who knowingly commit such crimes are declared “infamy”. First and foremost, they lose their positions within the organization. They are declared undesirable persons in their environment. Furthermore, various legal regulations have been made on this matter. Relevant laws include: “DMK (State Civil Servants Law), KK (Law on Misdemeanors), KVKK (Law on the Protection of Personal Data), TTK (Turkish Commercial Code), and VUK (Tax Procedure Law)”. Those who knowingly harm the business or commit theft (furtum) must be punished. Unpunished crimes give rise to the concept of “impunity”. The impunity shield should not be given to major thieves in companies. They must be judged fairly. Even if their guilt is established, convictions must be handed down.

Here, several points can be highlighted. First, an effective organizational structure must be established. Participation, transparency, accountability, consistency, and legality must be ensured. Open access to data and effective control of results are also important. Managers must act accordingly. Internal audits and cross-examinations must be fully conducted. Early warnings must be evaluated. Feedback systems must be established. In short, the freedom of managers to commit crimes within the organization must be eliminated. The following line from Othello Act 3, subtitle 3, is noteworthy: “Good name in man and woman, dear my lord, Is the immediate jewel of their souls: Who steals my purse steals trash; tis something, nothing; Twas mine, tis his, and has been slave to thousands; But he that filches from me my good name, Robs me of that which not enriches him, And makes me poor indeed”. The famous Ahi sheikh Edebali stated the following: “Feel sorry for three people: a wise person who is among the ignorant, a rich person who gets poor, and a respected person who loses people's respect. Don't forget that those in high places are not as safe as those in lower places. Do not be afraid to insist on your rightful case”. Management inherently contains certain problems. Competent managers know how to overcome them. They protect their team and organization. They do not knowingly make mistakes. However, life can also bring surprises. Sometimes, the guilty and the innocent can be confused. Someone who is innocent must defend themselves. If a person's innocence is later proven, pardon comes into play. That is, “rehabilitation of reputation” occurs. Usually, the truth comes out in some way. What is important is to be honest and accountable.

This study is largely limited to the theoretical evaluation of “behavioral levels, social status, infamia, and infamia in managers”. To overcome this limitation, “examples from business organizations or public institutions can be considered”. The planning of the sample selection process has been left as the subject of another study.

References

- Ansari, S. (2024). Reputation management: The role of senior leadership in a crisis. Available at: <https://www.jbs.cam.ac.uk/2024/reputation-management-the-role-of-senior-leadership-in-a-crisis/>, Accessed: 25.04.2024.
- Celik, A. (2025). “Yönetim ve Organizasyonun Temel Kavramları”. (Basic Concepts of Management and Organization). Kitap içinde: Yönetim ve Organizasyon (Management and Organization, 1-21). Ed. Z. Turkmendag, Erzurum: Atatürk Üniversitesi Açıköğretim Fakültesi Yayını.
- Chiusi, T. J. (2013). “‘Fama’ and ‘infamia’ in the Roman Legal System: The Cases of Afrania and Lucretia”. In book: Judge and Jurist: Essays in Memory of Lord Rodger of Earlsferry (pp.143-156). Eds. A. Burrows, D. Johnston & R. Zimmermann. Oxford: Oxford University Press.
- DMK (1965). 14.07.1965 tarih ve 657 Sayılı Devlet Memurları Kanunu.
- Erdogan, I. (1997). İşletmelerde Davranış (Behavior in Businesses). 2.Baskı, İstanbul: İstanbul Üniversitesi İşletme Fakültesi Yayını.
- Eren, E. (2017). Örgütsel Davranış ve Yönetim Psikolojisi (Organizational Behavior and Management Psychology). Tıpkı 16.Baskı, İstanbul: Beta Basım Yayım Dağıtım A.Ş.
- Eren, E. (2019). Yönetim ve Organizasyon (Management and Organization). Tıpkı 13.Baskı, İstanbul: Beta Basım Yayım Dağıtım A.Ş.
- Eroglu, F. (2017). Davranış Bilimleri (Behavioral Sciences). 15.Baskı, İstanbul: Beta Basım Yayım Dağıtım A.Ş.
- Gulick, L. (1937). “Notes on the Theory of Organization”, In book: Paper on the Science of Administration (pp.1-9). Eds. L. Gulick & L. Urwick, New York: Columbia University Institute of Public Administration.
- Guney, S. (2007). “Yönetim ve Organizasyonun Bazı Temel Kavramları (Some Basic Concepts of Management and Organization)”. Kitap içinde: Yönetim ve Organizasyon (Management and Organization, 1-29). Genişletilmiş 2. Baskı, Ed. S. Guney, Ankara: Nobel Yayın Dağıtım.
- Infamy (2025). In Britannica. Available at: <https://www.britannica.com/topic/infamy>, Accessed: 23.11.2025.
- Kızılcıkel, S. & Erjem, Y. (1992). Açıklamalı Sosyoloji Terimler Sözlüğü, Konya: Göksu Matbaası.
- KK (2005). 30.03.2005 tarih ve 5326 sayılı Kabahatler Kanunu.
- Kocel, T. (1983). Yönetim Kavram ve Teknikleri (Management Concepts and Techniques). İstanbul: Uluslararası Bankası Eğitim Müdürlüğü Yayını.
- Kocel, T. (2020). İşletme Yöneticiliği (Business Administration). Genişletilmiş 18.Baskı, İstanbul: İstanbul: Beta Basım Yayım Dağıtım A.Ş.
- Kolasa, Blair J. (1979). İşletmeler İçin Davranış Bilimlerine Giriş (Introduction to Behavioural Science for Business). Çev. Kemal Tosun vd., İstanbul: İstanbul Üniversitesi İşletme Fakültesi ve İşletme İktisadi Enstitüsü Yayını.
- KVKK (2016). 24.03.2026 tarih ve 6698 sayılı Kişisel Verilerin Korunması Kanunu.
- McGinn, T. A. J. (1998). Prostitution, Sexuality and the Law in Ancient Rome. New York: Oxford University Press.
- Ozkalp, E. (2004). “Toplum ve Toplumsal Yapı” (Society and Social Structure). Kitap içinde: Davranış Bilimlerine Giriş (Introduction to Behavioral Sciences, 41-45). 3.Baskı, Ed. E. Ozkalp, Eskişehir: Anadolu Üniversitesi Açıköğretim Fakültesi Yayını, Yayın No: 1355.

- Rašljanin, I. (2023). Infamia in the sight of Roman law. *Science International Journal* 2(4): 53-57 (<https://doi.org/10.35120/sciencej0204053r>).
- Shi, W. (2025). When another company's crisis hurts your reputation. Available at: <https://hbr.org/2025/11/when-another-companys-crisis-hurts-your-reputation>, Accessed: 25.11.2025.
- Simsek, M. S., Celik, A. & Akgemci, T. (2025). *Davranış Bilimleri (Behavioral Sciences)*. 12.Baskı, Konya: Eğitim Yayınevi.
- TTK (2011). 13.1.2011 tarih ve 6102 sayılı Türk Ticaret Kanunu.
- Tutar, H. (2010). "Kurumsal Davranışın Yaşam Alanı: Davranış Düzlemi" (The Living Space of Corporate Behavior: The Behavioral Levels). Available at: <http://www.canaktan.org/yonetim/kurumsal-davranis/>, Accessed: 03.06.2008 - 10.02.2010.
- VUK (1961). 213 sayılı Vergi Usul Kanunu.
- Zavyalova, A., Pfarrer, M. D. & Reger, R. (2016). Celebrity and infamy? The Consequences of Media narratives about organizational identity. *Academy of Management Review* 42(3): 461-480 (DOI: <https://doi.org/10.5465/amr.2014.0037>).

A WAVE OF NOSTALGIA AMONG ENTREPRENEURS: A KIND OF RETROTOPIA

Prof. Dr. Adnan Celik

Selcuk University, FEAS, Department of Business, Turkiye.

ORCID ID: 0000-0002-8538-9937

Abstract

Entrepreneurship involves a kind of idealism. Entrepreneurs pursue their dreams by bringing new business ideas or new projects to life. Activities such as the development of advanced production technologies, the production of new goods or services, the improvement of the quality of existing products, the provision of high-quality products at reasonable prices to consumers, finding new raw material sources, rapid adaptation to market conditions, reaching new markets, establishing new organizations, etc., are the achievements of entrepreneurs. The success of an entrepreneur positively affects many stakeholders. Internal and external environmental factors provide various benefits. The organization, society, the state, and perhaps all of humanity can benefit positively from this. However, as with everything else, various psycho-social and economic problems can be encountered in this field. Utopia, nostalgia, and retrotopia can be considered in this context. On one hand, there is “utopia”, related to ideal goals and expectations. There may be a need for “nostalgia”, expressing a longing for significant achievements of the past. There may also be “retrotopian” attitudes for adapting utopian designs to the future. What is important is demonstrating effective entrepreneurship. Those who successfully manage the aforementioned elements can more easily achieve organizational goals. Those who do not may face many problems. This study is prepared to address these elements and the interactions between them. The study consists of three sections. Under the heading Literature Review, “the concepts of entrepreneurship, utopia, nostalgia, and retrotopia are explained. The second section is titled Methodology”. Then, “Findings and Discussion” is shared. Here, the following are discussed in order: the wave of nostalgia among entrepreneurs; retrotopia in entrepreneurship; and the interaction between the wave of nostalgia and retrotopia among entrepreneurs. At the end of the study, a general evaluation is made.

Keywords: Entrepreneurship, Nostalgia in Entrepreneurs, Retrotopia in Entrepreneurship

INTRODUCTION

An entrepreneur is someone who undertakes a task and is not afraid to do so. They are the ones who bring together factors of production, initiate the necessary undertaking for the production of economic goods and services, and also find the necessary financial resources and markets for the production. In general, they fulfill the following: “Producing new goods and services or improving the quality and characteristics of known goods and services; Developing and implementing new production methods; Establishing new organizations in industry; Reaching new markets; Finding new sources from which raw materials and similar materials can be obtained”. The place and importance of entrepreneurs in the development of a country cannot be ignored. Entrepreneurs play a significant role in the full implementation of economic policies, achieving balance of payments, increasing employment, balancing competition, developing free enterprise, eliminating regional inequalities, and spreading prosperity to the general public.

Entrepreneurs positively influence various sectors as a result of their economic actions. Individual and organizational success is beneficial for every stakeholder. An entrepreneur can envision many things and take various actions to achieve them. “Utopian” thinking,

encompassing ideal goals and expectations, is welcome. However, business activities may not always go as desired because the business world is highly volatile, full of risks and uncertainties, and sometimes resulting in losses. One can be drawn into crises and stressful environments. The important thing is to develop effective plans and programs, and to manage parameters and variables well. As the socio-economic situation worsens, the yearning for past successes may increase, leading to a kind of “nostalgia”. Another behavior and attitude may also emerge: “retrotopia”, which aims to adapt utopian designs to the future. Whatever the reason, problems must be overcome to achieve organizational success.

This study examines the interactions between utopia, nostalgia, and retrotopia. In addition, effective entrepreneurial goals are kept alive. The study consists of three main sections. First, a literature review is conducted. This study defines the concepts of entrepreneurship, utopia, nostalgia, and retrotopia. Under the Methodology heading, the purpose and importance of the research are first introduced. Then, the research method is shared. Under the Findings and Discussion heading, the wave of nostalgia among entrepreneurs is examined first. The second subheading is retrotopia in entrepreneurship. The final subheading contains analyses of the interaction between the wave of nostalgia and retrotopia among entrepreneurs. The study concludes with conclusions and recommendations.

1. LITERATURE REVIEW

1.1. Entrepreneurship

The word “entrepreneur” is derived from the Latin word “entre”, meaning to grasp or to swim. Its association with business and workplace dates back to 1700s France. Initially, it was used to describe patrons in theaters. Later, “entreprendre” came to mean to undertake, to begin, to get involved; and “entrepreneur” came to express concepts such as entrepreneur or undertaking. In his essays “On the Nature of Commerce” written in 1775, the Irishman Richard Cantillon defined the entrepreneur using words close to those used today. In his “Political Economy” books of the 1800s, the Frenchman Jean-Baptiste Say equated the word entrepreneur with the concept of “adventurer”, viewing the entrepreneur as someone who pursues risk and establishes their own business. Austrian-born American economist Joseph Alois Schumpeter, in his 1934 work “Theory of Economic Development”, placed particular emphasis on the concept of entrepreneurship among production, factors of production, credit, interest, labor, and the firm cycle. According to the author, an entrepreneur is “a person who changes the existing economic order by offering new products and services, establishing new organizations, or using new raw materials”. According to Schumpeter, the development of capitalist societies is the work of entrepreneurs. Entrepreneurship or the entrepreneur cannot be defined as belonging to a clearly limited social occupational group. The definition of an entrepreneur should be made according to the function they undertake or fulfill (Schumpeter, 1998: 1-11; Say, 2001: 1-5; Cetin, 1996: 29; Durak et al, 2017: 7; Celik, 2026: 12).

If the entrepreneurial climate, economic stability, suitable infrastructure, and appropriate support are positive, the chances of success for an entrepreneur or business increase proportionally. If these are negative, the activity will either not start at all or will be carried out with great difficulty. The roles of entrepreneurs can have effects on both macro and micro scales. Naturally, certain factors also affect entrepreneurs. Here, many internal and external factors become important. In the internal environment dimension, the following stand out: “Managerial characteristics, past experience and expertise, demographic characteristics, value judgments, years of operation, size, location, organizational interactions, centralization, characteristics of the business, type and variety of goods or services produced, flexibility in organizational structure, information flow, decision-making and execution competence”. In the external dimension, the following may stand out: “Globalization, technology, competitors, raw material sources, suppliers, customers or buyers, legal or institutional regulations, society, ecological structure, partners, and the board of directors” (Simsek & Celik, 2025: 37).

1.2. Utopia

Utopia is concerned with ideal goals and expectations. In such an environment, life is assumed to unfold under perfect conditions. Utopianism, even though it is difficult to achieve, is the pursuit of the impossible. It contains highly idealized goals and emotions. The concept prioritizes the happiness of all parties. The individual, society, and state aim for an ideal social order. The dream of a world where everyone is happy and free prevails (Britannica, 2025).

Thomas More stands out in this regard. The author emphasized the subject in his work “Utopia” (Original Latin: *De Optimo Reipublicae Statu, Deque Nova Insula Utopia*, Libri II, 1516). The word “Utopia” is derived from the Ancient Greek words “ou” (no) and “topos” (place). The word “eu” (perfect) could also be used. These concepts emphasize the dream of “A beautiful place” (*locus pulcher*). Although it is a depiction of a fictional civilization, it has also been ironically evaluated in later periods. For example, More both explained the ideal of eutopia (good place) and stated that the ideal society utopia could not be reached. Regardless, he wrote a noteworthy work. Here, there is an escape from corruption, hatred, and greedy thoughts. This can also be called a kind of pursuit of perfection. There is a dream of a civilization that is good for everyone. A happy life is depicted in equality and justice. The individual, society, and state are in cooperation and harmony. It is stated that there should be no poverty and evil. In other words, a prosperous and healthy society is aimed for. The concept of “dystopia” was developed for the opposite situations (Caffrey, 2023; Britannica, 2026; More, 1869: 3-166). In later periods, the “Utopia Model” became quite popular. People both sought the truth and, even if they didn't believe in it completely, began to internalize dreams that were impossible to achieve.

The search for an ideal world has always existed. Holy books and prophets have depicted life in “paradise”. Some writers and thinkers have also produced various works. Besides Thomas More's “The Utopian Wonder Island”, the following stand out (Sus, 2023; Celik & Duyar, 2020: 187-189); “Plato (*The Republic: A Perfectly Balanced State*, around 375 BC); Al-Farabi (*Al-Madinatul Fazila - The Excellent City*, 943); Tommaso Campanella (*The City of the Sun*, 1602); Edmund Burke (*Conservative Utopia*, 1773); William Godwin (*An Enquiry Concerning Political Justice* (1793))”.

1.3. Nostalji

Nostalgia is a longing for the past. The word originates from the Latin “Nostalgia” and the French “Nostalgie”. It's a kind of fondness for the past. Sometimes, one longs for earlier periods or the good times of the past. The yearning for the beauties of the past intensifies and can become increasingly dominant. Sometimes, there may be a fear of novelty and change. As a result, a feeling of seeking refuge in the past may be preferred (TDK, 2025).

As love and longing for the past increase, a wave of nostalgia can also sweep through. This is because the longing for better times or places intensifies. In such environments, a broad emotional connection and sharing can also come to the fore. In the context of our topic, the name Zygmunt Bauman is famous. Bauman (1925-2017), of Polish origin, worked primarily in the field of sociology. He was deeply affected by World War II. He lived in the Soviet Union for a time. After being expelled from Poland in 1968, he began living in Israel. In 1971, he moved to England after being invited to the Sociology department at Leeds University. His analyses of social and political transformation in contemporary society are noteworthy. He also has works on utopia, nostalgia, and retrotopia. He considered utopia as a promise of a social future, while in his work titled “Retrotopia”, he drew attention to the loss of collective and political hopes for the future. He also addressed the pains of change in fluid (late) modern societies that have lost these hopes (Bauman, 2017: 13-14; Bauman, 2018: 9-87; Kociatkiewicz & Kostera, 2018: 335; Koc, 2024: 236, Kundakci, 2025: 167).

Nostalgia has been seen as a phenomenon emphasizing the transformation of memories over time. There are those who approach the subject theoretically, and there have also been

academics who have done research on it. Some people develop humorous perspectives or joke expressions. In this context, the following can be shared: “Nothing is the same anymore; Nothing was ever the same, not even nostalgia; It was never the same again”. Regardless of the approach, nostalgia is a multifaceted phenomenon. Within this phenomenon, “memory” also plays certain roles. For example, it can act as a “sieve”. That is, it can easily allow the pains, troubles, and annoyances of the past to slip away. Conversely, it can preserve and glorify the pleasures of the past (Berra, 2013).

1.4. Retrotopia

Retrotopia is a kind of emotional and behavioral state. Like the previous ones, it includes emotions and aspirations. The utopian feelings here may not be limited to nostalgia for the past. That is, some utopian designs can be adapted to the future. Bauman's work is noteworthy in this regard. The author witnessed various social upheavals, observed chaos and wars, and reflected these in his works. He addressed issues such as culture, power, authority, personality-identity, state administration, and the right to vote and be elected. In his studies, he made assessments of the “liquidity” and “retrotopia” types. He analyzed individuals' approaches to new situations they might encounter in the future (Kociatkiewicz & Kostera, 2018: 335).

In the state of retrotopia, people who have lost hope for the future become the focus. Those in this state first take refuge in their past. Then, the present and the future begin to be designed. A future life may be sought to resemble the best possible future life. Indeed, it is hoped that this goodness, filtered from the past and carried into the future, will be flawless. Notice that there is first a return to the possibilities of utopia. Then, it is imagined that even that will be surpassed in the future. Sometimes, there may even be imitations of another culture or community. Although it contains internal contradictions, the recipient may experience a sweet intensity of emotion. At these moments, there is no concern for physical or social security. Everyone dreams of being a member of an egalitarian and just society. Authoritarianism has fallen or been limited. Teamwork and team solidarity have come to the forefront. As can be seen, in the vision of the future, unlimited emotional freedoms and endless happiness are envisioned.

2. METHODOLOGY

2.1. Purpose and Importance of the Research

Entrepreneurs are individuals who make socio-economic contributions. For an ideal entrepreneur, service to society and humanity is very important. They bring together factors of production. They establish business organizations to meet human needs. They possess a drive to succeed. They strive to shape not only their current environment but also the future. Undoubtedly, continuous success is necessary for this. However, things may not always go as expected. Various psycho-social and economic problems may be encountered. This study focuses on utopia, nostalgia, and retrotopia, which can arise in some situations. These topics have been examined both individually and within the context of entrepreneurship. Then, attention has been drawn to the interactions. As a result of the study, value propositions have been developed.

2.2. Research Method

This study is primarily based on information in the literature. First, the literature on “entrepreneurship, utopia, nostalgia, and retrotopia” has been evaluated. Current evaluations in open sources have also been examined. Information and documents in popular publications have also been analyzed. This study focuses primarily on the dimensions of “the interaction between nostalgia and retrotopia among entrepreneurs”.

3. FINDINGS AND DISCUSSION

3.1. The Wind of Nostalgia in Entrepreneurs

To begin discussing the topic of nostalgia in entrepreneurs, a story can be shared as general information. This story was written by the Bohemian novelist and short story writer Franz Kafka (1883-1924). The author's story, which combines realism and fantasy elements, is as follows (Kafka, 1971: 499; Bauman, 2017: 11): "I ordered my horse to be brought from the stable. My servant did not understand my orders. So I went to the stable myself, saddled my horse, and mounted it. I heard a trumpet sound in the distance and asked my servant what it meant. He knew nothing and had heard nothing. He stopped me at the door and asked: 'Sir, where are you going?' I said, 'I don't know. Just somewhere else from here, just somewhere else from here. That's the only way to reach my destination.' 'So you know where you're going?' asked my servant. Yes, I replied. I just told you. Somewhere else from here; that's where I'm going". It is possible to encounter situations that the author wants to emphasize. People may want to get away from "the environment or feelings they are in". An individual in a suffocating and boring environment may say, "I want to get away from here". Those who say, 'I want to get somewhere else as soon as possible,' should be viewed from this perspective.

The dream of an ideal world is beautiful for everyone. Like every human being, entrepreneurs may also desire it. Especially a business person struggling with socio-economic problems may be swept away by a wave of nostalgia. However, what is desired is often not real. That is, even if it is written or drawn, the scenario never seems to turn into a film. Otherwise, many meaningful and beautiful works have been created. Among these, the following stand out: "Plato - The Republic; Farabi - Al-Madinatul Fazila; Thomas More - Utopia; Tommaso Campanella - The City of the Sun; Edmund Burke - Conservative Utopia; William Godwin - An Enquiry Concerning Political Justice". Writers and thinkers have always dreamed of a beautiful place. In their works, they have stood against oppression and tyranny. They have criticized the distinction between the noble and the common people. They have believed that the ecological structure and the environment are the common values of all living beings. They advocated for the fair and equitable distribution of resources. They desired socio-economic development based on cooperation and respect (Caffrey, 2023; Britannica, 2025; Britannica, 2026; More, 1869: 3-166). However, the hegemonic system of the world has not been conducive to this. In particular, colonial societies have prevented this. The problems have not ended. On the contrary, they have begun to increase even more. Some countries have become very developed economically. However, they have remained poor in terms of ethics and morality. Brutal capitalism continues its exploitative system.

In today's business and social life, nostalgia is ever-present. A kind of "nostalgia" period is underway. The scope of this feeling is broad. First and foremost, a sense of disorientation is dominant. Psychologically, there are problems with reaching comfort zones. Physical displacement is important, but the anxiety of psychological displacement is even more dominant. As a result of all this, the individual may see themselves as ordinary and ineffective. In addition, a ramp to escape is sought. Past good experiences or certain fantasies can come to the rescue. For the individual, nostalgia can be a kind of lifeline. This condition was considered a treatable illness in the 17th century. It was even called a temporary illness. Some physicians even suggested various solutions. The treatment suggestions of Swiss doctors are noteworthy here (they recommended opium, leech therapy, and a mountain trip). In later periods, the issue became even more complex. Especially in the 21st century, it has transformed into a hopeless civilized state. It can be stated that; "The 20th century began with a futuristic utopia, but sadly ended with nostalgia (Boym, 2001; 13-14; Bauman, 2017: 10)".

3.2. Retrotopia in Entrepreneurship

According to Bauman, retrotopia is a phenomenon. This situation also has historical dimensions. That is, it includes various periods. Initially, positive states can be observed. In other words, in the early modern period, many things are perceived pleasantly. The environment can seem rosy. There is a sense of peace, even if artificial. There is hope in societies. Leaders make ambitious and hopeful promises. The idea of freedom, which is not fully understood, and artificial happiness seem to please everyone. Realities are faced. However, problems emerge. The structures that are felt or thought to exist are on the verge of disappearing. Masses of people who do not know what to do have formed. Hope has begun to disappear. Unhappiness has risen. Individuals are faced with loneliness and helplessness. However, in previous periods, partially beautiful lives could be seen. In the past, chaos and disorder were less prevalent. Although not completely, happiness and peace were experienced. Tranquility could also be seen. What could someone do who was stuck between the old and the new? A return to older, supposedly better days. A remembrance of previously accepted values. A kind of “nostalgia” or a yearning to “return home” (Bauman, 2017: 13-14; Bauman, 2018: 9-87; Koc, 2024: 236).

The state of retrotopia can somehow come to the forefront in today's business and social life. This situation can be observed primarily among entrepreneurs, but also among senior managers and other personnel. In the specific context of our topic, we can focus on entrepreneurial activities. Because entrepreneurship encompasses an ecosystem. Entrepreneurs have local, national, and international networks. Therefore, very different relationships and interactions can occur. Emotions, thoughts, and activities can sometimes be chaotic. In this regard, we can delve into business environments, drawing on Bauman's macro analyses. The author has drawn upon studies in the fields of “modernism, totalitarianism, and postmodernism”. He has analyzed various social issues before and after modernity. He also has lived experiences. As a result, he has prepared a study titled “retrotopia”. Here, he focuses on the increase in social changes that accompanied modernity. Naturally, he mentions some positive outcomes. However, many negative aspects are also on the agenda. For example, globalization movements have produced both positive and negative results. Large capital owners and developed countries are among those who benefit. However, various problems have arisen for some states and communities. Inequalities between societies have increased. Technology has been used both beneficially and harmfully. Uncertainties and insecurities have multiplied. Individuals in particular, and societies in general, have begun to harbor various anxieties. Anxiety about the future has begun to overwhelm people. Despair has become prevalent. So, what is done in such a situation? Into what environments are individuals being drawn? One possible answer is: “Retrotopia” (Bauman, 2017: 13-14; Bauman, 2018: 9-87; Koc, 2024: 236).

Problems at the macro level have also affected the micro level. Here too, there may be uncertainty about the future. Like every human being, entrepreneurs can also lose confidence in the future. Because the problems experienced and the uncertainty of the future can spread anxiety and fear. Imagine yourself as an entrepreneur who cannot use advanced technology and has lost their competitive edge. The present moment is creating problems. There is no hope left for the future. However, you may have been very successful in the past. These thoughts may cross your mind. Your longing for the past may intensify. For someone who dwells a lot on the good old days, fond memories of the past can become a psychological haven.

3.3. The Interaction of Nostalgia and Retrotopia in Entrepreneurs

Nostalgia is a beautiful, yet melancholic emotion. It involves a return to the past. Longing needs to be controlled, as it can be harmful as it is beneficial. While it may bring temporary, virtual happiness, it can ultimately lead to sad departures. Completely dwelling on the past

benefits no one. Negative experiences from the past shouldn't be constantly kept alive; otherwise, life becomes unbearable. Undoubtedly, the past must be accepted. Lessons should be learned from past mistakes. However, there is the present moment, and there is also the future! It's necessary to focus on these aspects as well. In analyzing nostalgia, the economic, social, cultural, technological, and temporal dimensions should also be considered. Many people view nostalgia from two different perspectives. Some see it as a kind of entertainment, a return to the carefree and beautiful days of their youth. In this sense, they may derive pleasure from it. Others may think the opposite. In other words, unpleasant or sad periods from the past may resurface. This can turn into an incompatible obsession. It might even be seen as a manifestation of fear of change. Some entrepreneurs and leaders do not approve of getting caught up in nostalgia. They acknowledge that it harms the business organization. According to them, it can lead to a problem of prioritizing the past entirely. An exaggerated focus on the past can undermine innovation, creativity, and ultimately progress (Routledge, 2021).

Psychologists argue that nostalgia is “a link between present reality and past identity, and a source of comfort in times of uncertainty”. According to them, nostalgia can be recycled and recontextualized. Today, there is rapid, accelerating, constantly fluctuating technological change, increasing economic anxieties, and impending social unrest. Because of these problems, some view nostalgia as a balancing force. Therefore, it is not surprising that old references are brought back again. However, there is a limit to this. In other words, excessive nostalgia also carries some dangers. While effective in some situations, it also has its own limitations. For example, it can prevent the moment from happening. It can make us forget how to predict the future (George, R. (2025). This can negatively impact individual development. Organizationally, sustainability and institutionalization may suffer.

The topics of utopia, nostalgia, and retrotopia are multifaceted. These have also become intertwined with the internet and social media today. The following assessments of Instagram CEO Adam Mosseri regarding the internet and social media should be considered; “We are living in a kind of ‘new era of infinite synthetic content.’ New technology permanently blurs the line between real and artificial images. Social media has already surpassed this stage. The concept of ‘trust’ has been replaced by the concept of ‘suspicion.’ Social media users may have shared real photos from their past lives. However, these situations have also begun to change over time. Internet users should know that not everything they see is a given reality. In other words, content should be approached with suspicion. Particular attention should be paid to content generated by artificial intelligence” (Mosseri, 2026). In the context of our topic, Bauman's assessments of “liquidity” and “retrotopia” can also be mentioned. The former constitutes the fundamental metaphor for theorizing the current global impasse. This text discusses Kurt Lewin's “Change-As-Three-Steps (CATS)” model. It also refers to Carl Gustav Jung's work on “archetypes” (human behavior, personality models, the collective unconscious). The latter is the concept of “retrotopia”. Based on Bauman's work, some inferences can be drawn. For example, attention can be drawn to new situations that may be encountered in the future. Shortcomings in current visions can be revealed. New organizational styles and management forms can be developed (Kociatkiewicz & Kostera, 2018: 335). There is a need for plans and programs that prioritize social benefit and are good for everyone. Today, digital technologies and artificial intelligence (AI) are active. A frenzy of production and consumption continues on a global scale. As a result, intense competition is experienced. However, the goal should be a more livable world. To achieve this, private businesses, public institutions, and civil society organizations must work together.

No matter what is written or spoken, nostalgia persists. The Industrial Revolution and subsequent developments have been very different. Industrialization and intensive technology have profoundly affected the social order. Rapid development and growth have almost

become a frenzy. The course of history has brought the concept of a “global nostalgia epidemic” to the forefront. The races in the socio-economic order continue uninterrupted. They may change direction. Even the course may change. However, the situation we are talking about continues as much as possible. This internal, unsuppressible, and insatiable need that governs people and will likely continue to do so is now a fact. Any negativity in internal and/or external organizational factors affects many people. Entrepreneurs are most affected. Because they are the owners of capital. They have brought together many tangible and intangible resources. They have started production and marketing activities. They face various risks. When they experience a negative event, their past successes may come to mind. In previous periods, they may have been very productive and profitable. However, in later periods, these may have declined. Production and marketing losses may occur. The effectiveness of human resources may also decrease. Communication and collaborations may also be disrupted. Ultimately, the environment can generate pessimism. In this situation, various psycho-social or socio-economic behaviors may come to the fore. Nostalgia is one of them. Retrotopia may also emerge (Bauman, 2017: 13-14; Bauman, 2018; 9-87; Koc, 2024: 236).

The wind of nostalgia in macro structures also affects the micro structure. In other words, societal effects are closely related to business management. Businesses, starting as an important element of microeconomics, affect the macro structure in advanced dimensions. Here, the activities of entrepreneurs play a very important role. The problems faced by entrepreneurs today have multiplied. Each of the internal and external environmental factors can be a potential source of problems. Let's say an entrepreneur faces significant problems. The workplace, once a thriving business, begins to decline. That once great organization transforms into a hotbed of stress and crisis. The future becomes uncertain, and hopes dwindle. Undoubtedly, entrepreneurs and managers can turn to crisis management plans. That's the most important thing. However, different behaviors can also be observed. In some, a longing for the past may increase. The past successes of the business organization may be recounted. Whether it's utopia or nostalgia, these can be seen as temporary escape routes. However, life also has its realities. Humanity can face various pains and difficulties. The actual situation reveals various realities. It's pleasant to dream. “Dreaming” about the beauties of the past can be good for a person. Sometimes, even “getting carried away by daydreams” can be acceptable. There's a saying: “The past is a time whose memory is worth the world”. The famous Turkish poet Yahya Kemal Beyatlı also said: “A person lives in this world as long as they dream”. In other words, the issue is multifaceted. It can be viewed from different angles. Nevertheless, it is necessary to confront the realities. Because some things are now in the past. The task is to keep the organization afloat. Effective leadership must be demonstrated. Teamwork and participation must be increased. Areas like utopia, nostalgia, and retrotopia must be managed effectively. Partial benefits can be expected from these. They can even be motivational factors for organizational success. However, they must be kept within acceptable limits.

4. CONCLUSION AND RECOMMENDATIONS

This study focuses on the wave of nostalgia and retro-topic tendencies among entrepreneurs. Businesses and entrepreneurs alike may face numerous challenges. These challenges can be physical or psychosocial. For example, a state of melancholy might arise. Current situations may be viewed negatively. Anxiety about the future may also be felt. Longing for better days of the past may increase. However, it's important not to constantly dwell on the past. Dreaming is acceptable, but daydreaming must be controlled. An entrepreneur might bring their past activities to mind like a film reel. But there's no need for emotional resentment. Lessons must be learned from the past. The past should be internalized and read like a “book of experience and wisdom”. Those who dwell too much on the past may have difficulty

focusing on the future. Necessary lessons should be learned from past memories, and the journey should continue. The issue isn't limited to the past alone. Sometimes, the present moment can be forgotten. The necessities of that moment can be neglected. Even utopian expectations focused on the future can arise. Undoubtedly, the future is important. But the present moment is also crucial. These issues must be kept within acceptable limits. Business life is like water in a cracked glass. If you drink the water, the glass empties. In other words, the water runs out. If you don't drink the water, the glass still empties. The water may run out slowly, but ultimately, it runs out. This situation can be applied to the cycle of work and social life. An entrepreneur must continue on their path without giving up. Even if you become disillusioned with life, life goes on. What matters is the effective leadership attitude you demonstrate. Managerial leadership requires taking initiative.

In a business organization, an adventure that begins with utopia can end with nostalgia. For example, the owner or partners of a business organization may distribute dreams. They may set unattainable goals. Naturally, they can decide everything because they own the capital. No matter what they do, sometimes organizational goals may not be achieved. The objectives may be deviated from. In the decision-making and implementation phases, employees may feel insignificant. Their opinions may not even be considered regarding working methods. If expectations are not met, the situation may worsen further. Employees may blame upper management for the increasingly deteriorating organizational structure. But they have no power. They may even long for the old days. They may lose hope for the future. However, life goes on. It is necessary to restore the organization to its normal state.

It is natural for entrepreneurs to be swept away by a wave of nostalgia. A kind of retro-topic state may also be experienced. However, there is a decision to be made. The important thing is to achieve organizational goals. For this, it should be well understood that losses and/or gains may be encountered. An entrepreneur may not always be successful. There may have been very pleasant and good days in the business organization. However, global developments are dominant. Technology is intense. International companies are making life difficult for national companies. Costs may have increased. Sales may have decreased. Perhaps market share is being lost. Various difficulties have been faced. What needs to be done is to ensure the sustainability of organizational life. Confucius is a philosopher who developed concise sayings on many subjects. In the context of our topic, the following aphorism is important; "Our greatest glory is not in never falling, but in rising every time we fall". Entrepreneurs and senior managers may sometimes refer to the past. This may be a source of motivation for subordinates. Organizational cultures may include founding leaders, old symbols, rituals, and illustrious achievements. The important thing is not to be completely stuck in the past. Some successful practices from previous periods can be used in the new era. Utopia, nostalgia, and retrotopia can be evaluated in moderation. They can even be transformed into motivational elements. Feelings and thoughts that increase alienation and stress should be tempered. Beliefs, attitudes, and behaviors that can overcome the crisis are needed. For this, open communication and a transparent management approach are necessary. Critical thinking should be respected. Through collaboration and teamwork, "together we can reach better days". A new vision should be instilled to relive the beauties of the past. Employees also have responsibilities. They need to be confident, participatory individuals. They should work together for a better future.

This study is based on an evaluation of the general literature on topics such as "entrepreneurship, utopia, nostalgia and retrotopia, nostalgia in entrepreneurs and retrotopia in entrepreneurship". To overcome this limitation, selected country and business examples can be studied. Comparing those who succeeded in this field with those who did not can also reveal useful information.

References

- Bauman, Z. (2017). *Retrotopia*. London & Cambridge: Polity Press.
- Bauman, Z. (2021). *Retrotopya* (Retrotopia). Çev. A. Karatay. İstanbul: Sel Yayıncılık.
- Berra Y. et al (2013). Quote origin: Nostalgia is not what it used to be. <https://quoteinvestigator.com/2013/07/06/nostalgia-is-not/>, Accessed: 06.07.2013 (Update history: 27.01.2025).
- Boym, S. (2001). *The Future of Nostalgia*. New York: Basic Books (Perseus Books Group).
- Bridgwater, W. & Kurtz, S. (1963). *The Columbia Encyclopedia*. Third Edition, Ninth Printing, NY: Columbia University Press.
- Britannica (2025). What is a utopia? Available at: <https://www.britannica.com/topic/utopia>, Accessed: 27.11.2025.
- Britannica (2026). Utopia: Work by more. Available at: <https://www.britannica.com/topic/Utopia-by-More>, Accessed: 03.01.2026.
- Caffrey, C. (2023). Utopia (concept). Available at: <https://www.ebsco.com/research-starters/literature-and-writing/utopia-concept>, Accessed: 30.11.2023.
- Cambridge Dictionary (2025). The concept of "Bankruptcy". Available at: <https://dictionary.cambridge.org/dictionary/english/bankruptcy>, Accessed: 28.12.2024.
- Celik, A. (2025). *Uygulamalı Girişimcilik* (Applied Entrepreneurship). 2.Basım, Konya. Eğitim Yayınevi.
- Celik, V. & Duyar, Z. (2020). Türk yönetim kültüründe temel etik değerlerin incelenmesi: Bir siyasetname örneği olarak el Medinet'ül Fazıla (Examination of basic ethical values in Turkish administrative culture: "Al-Madinatul Fazila – The Excellent City" as an example of political treatise). *Turkish Studies-Social*, 15(1), 187-206 (<https://doi.org/10.29228/TurkishStudies.40227>).
- Cetin, C. (1996). *Yeniden Yapılanma, Girişimcilik, Küçük ve Orta Boy İşletmeler ve Bunların Özendirilmesi* (Restructuring, Entrepreneurship, SMEs and Their Promotion). İstanbul: Der Yayınları.
- Durak, I. (2017). *Girişimcilik: Anadolu Kent Girişimciliğinden Örnekler* (Entrepreneurship: Examples from Anatolian Urban Entrepreneurship). Bursa: Ekin Yayınevi.
- George, R. (2025). The return of millennial cringe: Nostalgia as a marketing strategy. Available at: <https://uniathena.com/millennial-cringe-nostalgia-marketing-strategy>, Accessed: 22.09.2025.
- Kafka, F. (1971). "The Departure". Book in: *The Collected Short Stories of Kafka* (p.497). Foreword by John Updike & Translated by Tania and James Stern, New York: Schocken Books Inc.
- Koc, T. (2024). *Kitap İncelemesi / Book Review* (Z. Bauman. *Retrotopya*. Çev. A. Karatay, İstanbul: Sel Yayıncılık, 2021); *Sosyoloji Dergisi*, 2024 (48), 236-239 (<https://doi.org/10.59572/sosder.1569527>).
- Kociatkiewicz, J. & Kostera, M. (2018). After retrotopia? The future of organizing and the thought of Zygmunt Bauman. *Elsevier-Scandinavian Journal of Management*, 34(4), 335-342 (<https://doi.org/10.1016/j.scaman.2018.05.003>).
- Kundakci, D. (2025). Politik Interregnum Zamanlarında Yaşamak: Bauman Düşüncesinde İdeal Bir Tip Olarak Retrotopia ya da Nostalji (Living in an Age of Political Interregnum: Retrotopia or Nostalgia as an Ideal Type in Bauman's Thought). *Bingöl Üniversitesi İktisadi ve İdari Bilimler Fakültesi Dergisi* (Bingöl University Journal of Economics and Administrative Sciences), 9(1), 167-185 (<https://doi.org/10.33399/biibfad.1657381>).

- More, T. (1869). *Utopia* (Original Latin: *De Optimo Reipublicae Statu, Deque Nova Insula Utopia, Libri II*, 1516; Translated to English by R. Robinson, 1521). London: A. Murray & Son.
- Mosseri, A. (2026). You can't assume what you see online is real. Available at: <https://www.instagram.com/p/DS8x1F2jtd0/>, Accessed: 02.01.2026.
- Ozalp, I., Besler, S. & Tonus, Z. (2006). "Örgütsel başarısızlık: Başarısızlığı başarıya dönüştürme yolları (Organizational failure: Ways to turn failure into success). 14. Ulusal Yönetim ve Organizasyon Kongresi, Atatürk Üniversitesi İİBF, 25-27 Mayıs 2006, Erzurum, s.105-109.
- Pekcanitez, H., Atalay, O. & Ozekes, M. (2019). *İcra İflas Hukuku (Enforcement and Bankruptcy Law)*. Eskişehir: T.C. Anadolu Üniversitesi Yayını No: 3009 (Açıköğretim Fakültesi Yayını No: 1962).
- Routledge, C. (2021). The surprising power of nostalgia at work. Available at: <https://hbr.org/2021/04/the-surprising-power-of-nostalgia-at-work>, Accessed: 26.04.2021.
- Say, J-B. (2001). *A Treatise on Political Economy*. Revised Edition, New Jersey: Transaction Publishers.
- Schumpeter, J. A. (1998). *Microfoundations of Economic Growth: A Schumpeterian Perspective*. Michigan: University of Michigan Press.
- Simsek, M. S. & Celik, A. (2025). *İşletme Bilimine Giriş (Introduction to Business Administration)*. 29.Baskı, Konya: Eğitim Yayınevi.
- Sus, V. (2023). What Is the Ideal World? 5 Utopias Proposed by Famous Philosophers. Available at: <https://www.thecollector.com/what-is-the-ideal-world-according-to-famous-philosophers/>, Accessed: 28.01.2023.
- TDK (2025). "Nostalji". Available at: <https://sozluk.gov.tr/>, Accessed: 15..11.2025.

MOTIVATIONS PROVIDED BY THE GREEN UNIVERSITY INDEX

Prof. Dr. Adnan Celik

Selcuk University, FEAS, Department of Business, Turkiye.

ORCID ID: 0000-0002-8538-9937

Abstract

A university is a kind of center of learning. It is believed that high-level education and training are provided here. They are considered institutions where research is conducted and significant, useful knowledge is produced. Education and training can be divided into various classifications. Generally, there are branches of science, and specifically, departments of study. Each discipline or field of science is grouped within itself. Based on these, various academic organizations have been established. That is, faculties, colleges, vocational higher schools (VHS), institutes, research centers, and various coordinating bodies have been established. This study reveals the motivations provided by the green university index. This issue is of great importance for individuals, society, and all of humanity. In particular, there are many responsibilities for senior management. First and foremost, green leadership must be demonstrated. A sustainability mission and vision must be established institutionally. The sustainable green campus program must be kept alive. Office management and organization should transition to green bureaucracy and green document management. Green auditing is also needed. Attention should also be paid to feedback for environmental sustainability and green campus actions. The study primarily focuses on the literature review section. This section explains the concept of a green university and the green university index. Then, the methodology is shared. Under the heading “Findings and Discussion”, the topic of becoming a green university is addressed first. Next, green university practices in Turkish higher education are introduced. Finally, the attractiveness and benefits of the green university index are discussed. General evaluations are made based on the study's findings.

Keywords: Green University, Green University Index, Turkiye's Green University Dimension, Green University Motivation

INTRODUCTION

Universities are the highest-level educational institutions. Their primary goal is scientific education and training. Numerous research projects are undertaken to generate new and useful knowledge. Various scientific activities are carried out within these institutions. Certain formal systems have been established. Based on the subject matter and methods employed, distinctions exist not only between “formal” sciences but also between “human”, “natural”, and “social” sciences. Methodological classifications can also lead to distinctions between “normative, positive, and rational” sciences. Some categorize departments as “science, engineering and natural sciences, computer and information technology, social, education, health, and applied sciences”. Globally, postgraduate education activities are represented by organizations such as “graduate education institutes”, “research institutes” or “advanced specialization centers”.

Universities, as institutions of higher education, encompass various disciplines. In this sense, various classifications can be made for scientific branches or departments. Depending on the subject matter and the method employed, a distinction can be made between “formal, human, and natural” sciences. In terms of methodology and the results obtained, there is a grouping of “normative, positive, and rational” sciences. Some also consider the main branches of science as “science, social sciences, education, engineering, natural sciences, health sciences, and

applied sciences” (Celik, 2025: 15). Universities award the following types of diplomas for these fields: “Associate Degree (Vocational School), Bachelor's Degree (Colleges & Faculties); Postgraduate Degree (Institutes)”.

A university organization, regardless of its various units, has many responsibilities. One of these is becoming a green university. The green university approach encompasses many aspects. First and foremost, it involves the idea of “green organization” and “green environmental awareness” for campuses. This is not solely the responsibility of the administration. The cooperation of all administrative and academic staff is sought. The participation of university personnel and students should also be ensured. Undoubtedly, one of the main goals is to prevent environmental pollution. Energy and natural resource management should be improved. Emissions that harm the ecological structure and the environment should be reduced. Recycling should be prioritized. To this end, waste should be reduced as much as possible. If possible, its recycling should be increased.

This study reveals the motivations provided by the green university index. The study consists of three separate sections. The literature review section deals with green universities and the green university index. Under the heading Methodology, the purpose and importance of the research are first introduced. Then, the research method is shared. The third section is titled Findings and Discussion. Here, the following subheadings are included: “Becoming a green university; Green university practices in Turkish higher education; The attractiveness and benefits of the green university index”. The study concludes with results and general evaluations.

1. LITERATURE REVIEW

1.1. Green University

Industrial revolutions have brought about quite different consequences. Technological innovations have made human life easier. However, uncontrolled production and wild capitalism are also on the agenda. Productivity and profitability have taken center stage. Yet, the ecological structure and the environment also need to be protected. Such intense technological competition is unnecessary. Wild capitalism fuels our becoming a consumer society. Economically driven competitive activities such as industrial production, energy production, transportation, agricultural spraying, and modernization have rapidly depleted natural resources. Consequently, biodiversity has decreased, quality of life has declined, and global temperatures have risen, causing glaciers to begin disappearing. As a result of all this, pollution has increased and climate change has begun to occur. Natural disasters, fires, floods, and global epidemics have emerged, ecosystems have been disrupted, and all biological life is increasingly facing the threat of extinction. The time to say “stop” to this trend is almost over (Bektas & Celik, 2025: 235).

The concept of a sustainable university aims for a sustainable campus life from environmental, social, and economic perspectives. It supports the reinforcement of green behaviors. It prioritizes ensuring that every university campus becomes an educational institution capable of meeting its green needs (UI GreenMetric, 2026).

1.2. Green University Index

Within the scope of the Green University Index, the “UI GreenMetric World Green University Ranking System”, developed by the University of Indonesia in 2010, is significant. The green university index focuses on the sustainability performance of universities worldwide in areas such as campus environment, transportation, and education. It measures universities' efforts and strategies in the field of sustainability. This profile is designed for the analysis of economic, environmental, and social dimensions.

The system is one of the most widely used metrics for comparing the sustainability activities of universities worldwide. It is also effective in increasing the global recognition and reputation of universities. The goal here is to create a “green campus,” and it is desired that

this campus be sustainable. Therefore, six main indicators are proposed. Their weights according to the scoring system are as follows: “Buildings and infrastructure (15%), energy and climate change (21%), waste management (18%), water use (10%), transportation (18%), and education (18%).” Evaluations are made out of a total of 10,000 points. Each campus uses an online tool integrated into the “UI GreenMetric World University Ranking” platform. The relevant universities upload data on key categories directly to the UI GreenMetric platform. Subsequently, the data undergoes analysis and evaluation (UI GreenMetric, 2026).

2. METHODOLOGY

2.1. Purpose and Importance of the Research

This study focuses on the attractiveness and benefits of the green university index. That is, the motivations provided by the green university index are the objective. For this purpose, the literature on “green university, green university index, Turkey's green university dimension, green university motivation” has been reviewed. Current data of our universities in the categories of “building and infrastructure, energy and climate change, waste management, water use, transportation and education” have been analyzed. In particular, comparing the “UI GreenMetric” of our universities that are in the top 500 of the “Times Higher Education (THE)” list has been useful. This is because studies focusing on green university interaction and comparison are relatively few. In this respect, there is an effort to enrich theoretical knowledge.

2.2. Research Method

Green university and the green university index are important topics. Accordingly, Turkey's green university dimension and green university motivation are also noteworthy. This study has undertaken an effort to provide scientific information on these issues. Literature review has been preferred in explaining these. Firstly, the relevant topics have been clarified by drawing upon theoretical studies. In addition to anonymous sources, cultural documents and selected contemporary examples have also been included. Analysis of some current data, particularly concerning our country, has yielded useful results. Thus, significant recommendations have been developed for stakeholders.

3. FINDINGS AND DISCUSSION

3.1. Becoming a Green University

Sensitive individuals, volunteer groups, businesses, governments, academics, environmental organizations, and international organizations must be more effective. They must work together and rebuild a sustainable environment. Regulations should be increased at both macro and micro levels. Determined plans and policies must be implemented seriously. Issues such as sustainability, green behavior, organizational green behavior, employee green behavior, environmentalism, and environmentally conscious behavior must be internalized. The development of green workforce, green organizations, and green institutions is necessary. Various actors are encountered in these matters. It is a positive development that some leaders, business owners, academics, environmental organizations, and other volunteer organizations are on the ground. Government bodies should balance social benefit and environmentalism. Environmental awareness should be created within the framework of legal structures and ethical rules. Green institutions should be built. Awareness should be created among employees. Green behavior performance should be improved. The same applies to the private sector and businesses. A business organization may want to be efficient, effective, and profitable in its operations. In fact, this can even be seen as the foundation of organizational success. However, there is another point to consider: they must be environmentally conscious. Problems and proposed solutions concern all parties closely, because these problems are a threat to all living things. As they grow, their living spaces shrink. In this context, individuals, businesses, institutions, and organizations have responsibilities. Every stakeholder must do more than their fair share. Principles for green behavior and employee green behavior should

be determined quickly. Training and education on these issues should also be implemented (Bektas & Celik, 2025: 235-236).

There are necessary legal regulations in the field of higher education. These include laws, bylaws, and regulations. Establishing a formal structure is important. The existence of educational and training guides reveals the vision and mission. However, it is necessary to go beyond mere form. That is, educational and training plans and programs must be effectively implemented. Scientific research is needed. High-quality publication activities should be increased. Higher education institutions can be grouped primarily according to their purpose. Specialization can be encouraged. Activities and results should be very effectively monitored. Sufficient financial capacity and a large number of human resources can be achieved. The important thing is to be productive in academic output. To produce scientific knowledge that is useful and usable for humanity. The goal of becoming a “highly appreciated” and “highly accepted” educational institution should be realized.

On the path to becoming a green university, some institutions are developing various standards and measurements. One of these, the “UI GreenMetric World University Ranking”, is important. UI GreenMetric evaluates the sustainability performance of universities worldwide. In the latest evaluation, 1,745 institutions from 105 countries were examined. Universities have been evaluated in terms of green and sustainable campus performance. The main starting point has been the following aspects (UI GreenMetric, 2026):

1. Campus Location and Infrastructure: Determines where the university is located and shows whether the campus deserves the title of “green campus”. It encourages universities to allocate more green space and protect what already exists. It constitutes 15% of the total score.
2. Energy and Climate Change: Evaluates the universities' work on energy efficiency and energy sources. It contributes 21% of the total score.
3. Waste Management: Evaluates issues such as waste reduction and recycling in creating a sustainable environment. It constitutes 18% of the total score.
4. Water Management: Focuses on reducing water use, increasing conservation programs and environmental protection goals. It contributes 10% of the total score.
5. Environmentally Friendly Transportation Options: Evaluates the role of the transportation system on pollution levels and carbon emissions, encourages walking and reducing the use of private vehicles. It constitutes 18% of the total score.
6. Education and Training: Examines the existence of sustainability-related courses and activities, and evaluates the role of universities in creating a sustainability-conscious generation. Contributes 18% of the total score (As previously shared, evaluations are based on a total of 10,000 points).

3.2. Green University Practices in Turkish Higher Education

Higher education in our country is governed by the Council of Higher Education (CoHE). Legal regulation is established by the Law on Higher Education (Law Number: 2547; Date of enactment: November 4, 1981; Published in the Official Gazette No: 17506; Date: November 6, 1981). Universities are managed by rectors. Faculties have deans. Institutes, higher schools, vocational schools, and research centers have directors. Coordinators or representatives may be appointed to some units. Departments/sub-departments/programs are managed by heads. Personnel are generally divided into two classes (academic and administrative). The academic class is further grouped (teaching staff and teaching assistants). The rank of teaching staff is generally as follows: “Professor, Associate Professor, Assistant Professor (formerly: Assistant Professor)”. Teaching assistants have been categorized over the years as follows: “Lecturer, research assistant, instructor, specialist, translator (interpreter)”.

Universities can be organized in different ways on a global scale. Changes can be seen in their ownership and management structures. In some countries, universities are primarily financed

by the state; in others, funding may come from donors or fees paid by students attending the university. Since the beginning of the Republic, higher education has been seen as a public service provided through state universities. Therefore, in the early years, there were state universities. All the necessary funding and social support for these institutions was provided by the public administration. From 1985 onwards, foundation universities also began to be established. These started to increase especially in the late 1990s (early 2000s). Between 2008 and 2012, their numbers increased even further. In addition to foundation universities, there are also foundation vocational schools (Turkmaarif, 2025; Vakif, 2025).

After providing general information about higher education, we can move on to the explanation of green university practices. In this context, the “UI GreenMetric World University Ranking” applications are important. Within this scope, our universities have received significant scores in the categories of “building and infrastructure, energy and climate change, waste management, water use, transportation and education” (Evaluations are made out of a total of 10,000 points). In the 2025 world list, 6 of our universities entered the top 100. 15 of our universities were ranked between 101-200. In total, 21 of our universities entered the top 200. The names and rankings of those in the top 100 are as follows; “Istanbul University, ranked 25th, has a total score of 9,062.5; Yildiz Technical University, ranked 48th, has 8,850; Erciyes University, ranked 66th, has 8,775; Ege University, ranked 83rd, has 8,700; Ozyegin University, ranked 89th, has 8,650; Yeditepe University, ranked 91st, has 8,650” (UI GreenMetric, 2025; UI GreenMetric, 2026).

It is also worth clarifying another point relevant to our topic. That is, in addition to the “UI GreenMetric”, information should also be provided about the “Times Higher Education (THE) University Rankings 2025-2026”. Four universities from our country have entered the THE top 500 list. A total of 2,191 higher education institutions from 115 different countries were included in this evaluation. The names and rankings of those in the top 500 are as follows: “Koc University (351-350); METU (351-400); Sabancı University (351-400); Bogazici University (401-500)”. 15 of our universities are ranked between 501-1000. Istanbul Technical University is ranked between 501-600. Bilkent, Kadir Has, and Yildiz Technical Universities are ranked between 601-800. Abdullah Gul, Ataturk, Bahcesehir, Cankaya, Hacettepe, Istanbul Medipol, and Ozyegin universities are ranked in the 801-1000 range. Fifteen of our universities are ranked in the 1001-1500 range. The universities ranked in the 1001-1200 range are: “Anadolu, Bartin, Firat, Gelisim, Istinye, Izmir Institute of Technology, and Selcuk”. Those in the 1201-1500 range are: “Akdeniz, Ankara, Biruni, Duzce, Ege, Erciyes, Gazi, Gebze Technical, Inonu, Istanbul Medeniyet, Istanbul, Istanbul University-Cerrahpasa, Necmettin Erbakan, Sakarya, Suleyman Demirel, TOBB Economics and Technology, Health Sciences, and Yasar” (THE, 2025). Various analyses may be considered here. Specifically, comparisons can be made between the “UI GreenMetric World University Rankings 2025” and the “Times Higher Education (THE) University Rankings 2025-2026”. For example, the rankings of our 6 universities that are in the top 100 of the “UI GreenMetric 2025” list are as follows in “THE 2025-2026” (UI GreenMetric, 2025; THE, 2025):

1. Istanbul University (UI GreenMetric 25 & THE 601-800).
2. Yildiz Technical University (UI GreenMetric 48 & THE 601-800).
3. Erciyes University (UI GreenMetric 66 & THE 1001-1500).
4. Ege University (UI GreenMetric 83 & THE 1001-1500).
5. Ozyegin (UI GreenMetric 89 & THE 801-1000).
6. Yeditepe (UI GreenMetric 91 & THE 1001-1500).

From another perspective, a comparison of the “UI GreenMetric” scores of our 4 universities that are in the top 500 of the “Times Higher Education (THE)” list can also be made. This ranking is as follows (UI GreenMetric, 2025; THE, 2025):

1. Koc University (THE 351-350 & UI GreenMetric 323).

2. METU (THE 351-400 & UI GreenMetric 103).
3. Sabanci (THE 351-400 & UI GreenMetric 160).
4. Bogazici (THE 401-500 & 254).

According to a statement from the Council of Higher Education (YOK), encouraging our universities through the “Sustainable and Climate-Friendly Campus Project” has yielded significant results. With increased energy efficiency and the widespread adoption of environmentally friendly practices, our universities have risen in global rankings (Güven, 2025; YOK, 2025). Maintaining these positive results is crucial; sustainability must be the goal. Indicators are showing positive trends. In this context, we can mention universities that regularly feature in the UI GreenMetric rankings. For example, in 2024, the following universities stood out in the top 100: “Istanbul Technical, Yildiz Technical, Erciyes, Ozyegin, and Ege”. Of these, “Yildiz Technical, Erciyes, Ege, and Ozyegin” also made it onto the list in 2025. Therefore, stability and sustainability are essential.

3.3. The Attractiveness and Benefits of the Green University Index

Green behavior is influenced by many factors. Internal and external stakeholders are crucial. These include governments, public institutions, universities, research centers, independent researchers, volunteer organizations, international environmental organizations, and global media outlets. The reports and regulations they prepare indirectly affect organizations. The Deloitte Global Resilience Report on green development contains useful information. It states that there is a belief that the observed environmental disruptions will continue in the future. It emphasizes that negative developments in the areas of global climate and environmental sustainability will lead to various social problems in the future. Decisive leadership behaviors are needed for corrective regulations regarding climate change. Global CEO Michele Parmelee stated that combating climate change and other social problems should be a priority for business executives. Healthy social structures can also accelerate success. In particular, there may be various practical reasons why businesses should focus on environmental sustainability. For example, the new generation wants to work for companies with a high level of social responsibility awareness. The green technology field is becoming a huge area of growth. Not only employees, but also suppliers have begun to attach importance to this issue. Consumers or customers are also showing sensitivity in their trade. The future of our planet is being discussed more and more in all its aspects. Protecting the environment has come to be considered not only “the right thing to do, but also a smart business” (Deloitte, 2021: 1-5; Celik, 2022: 48).

Universities are very important educational institutions. Providing top-level education is paramount in these institutions. This also applies to research and applied teaching. Ultimately, the goal is to produce valuable knowledge that benefits humanity. Education can be defined as “the transmission and acquisition of current values, knowledge, and skills to the younger generation”. The process of preparing young members of society for the existing culture in a conscious, purposeful, and systematic way by adult members can also be called education. In this context, it can be argued that education begins in the family and continues in the street, at school, and in the workplace (Güney, 2004: 73). Education is both the primary path to individual development and high living standards, and a fundamental condition for societal development and progress. Countries that reach the level of contemporary civilization through increased education levels can more easily achieve economic development and a democratic political and social life (Özankaya, 1986: 323-324). Being sensitive to the ecological structure is of close concern to every individual and institution. This situation also applies to universities, which are important educational institutions. Environmental awareness and social responsibility are indispensable for higher education institutions. These institutions are expected to become green universities because they house a significant number of

stakeholders and engage in various internal and external interactions. Energy, water, technology, materials, and people coexist here.

There is a need to create green awareness in universities. Green behavior should be dominant in human resources. No resource should be used haphazardly. Leaving a healthy and livable environment for future generations should never be forgotten. All global environmental threats should be thoroughly understood. National and regional environmental problems should also be closely monitored. To this end, two main actions can be taken. Firstly, internal regulations can be implemented to raise awareness among stakeholders. In other words, it is necessary to be environmentally conscious at the institutional level. In this sense, leadership is expected from senior management. Secondly, education and training programs should be updated to include a “green understanding”. The goal should be a conscious institution and conscious stakeholders. Green understanding and social responsibility projects can be activated. Renewable energy can be established. Smart buildings can be constructed. Green technology should be preferred. Green bureaucracy is also important. Green offices can facilitate this. Zero waste and emissions should also be aimed for. Recycling can be increased. Individual transportation and mobility preferences can be transformed into societal ones. Green campuses can be created, and biological habitats can be increased. Sustainable green approaches can also be made dominant in food and nutrition regimes. Another starting point is to provide more external benefits and leave a widespread impact. Because all conscious societies aim for a livable world. They are pursuing global net-zero emissions. Therefore, universities also have a role to play. Every higher education institution should provide environmental benefits within its capacity. They should develop solutions to problems threatening the ecological structure and the environment. Those who act in accordance with the dimensions mentioned can be candidates for green universities.

When universities adopt a green behavior culture, various attractivenesses and benefits can emerge. Creating green awareness benefits everyone. With effective leadership and full participation, green campuses can be built more easily. Creating a green university or green campus may not solve all problems; it shouldn't be seen as a magic wand. Effective research and publication activities are also necessary. International strategic educational collaborations are also needed. In short, the issue is holistic; it's a journey towards total excellence. Those who do these things in harmony and cooperation will begin to see the benefits. First and foremost, close stakeholders can achieve socio-psychological satisfaction. People enjoy being in that institution. They can be proud to be members of such an institution. A livable educational institution can also be a preferred choice in environmental terms. Every stakeholder (especially staff and students) wants to live in a very healthy and more sustainable campus. A clean environment, safe water, and sustainable food practices positively impact mental and physical health. A green organization, green office management, green education-measurement-evaluation, cheap and clean energy, efficiency in recycling, and savings in scarce resources can be achieved. Therefore, both individual and institutional costs can be reduced. While becoming an ecologically sensitive and sustainable university, processes should be shared openly. The outputs obtained should be transferred to relevant platforms. In particular, compliance with the categories of global accreditation institutions should be ensured. High scores obtained from these institutions should be shared with the environment. Let's say you have a significant place in the “green university index”. You should announce this with effective public relations. When a positive image is spread, public support also increases. The state, public institutions, local governments, and civil society organizations will begin to cite you as an example. Many educational institutions may try to take you as a role model. Opportunities to access some public funds may arise. For technoparks and university-industry collaboration centers, the “World Bank Green Industry Project” support can be pursued. Support under the “European Union Horizon Europe Program” and the

“European Green Deal International Project Market” can be evaluated. National resources can also be explored for these areas. For example, collaborations can be established with KOSGEB, TUBİTAK, and the Ministry of Industry and Technology within the scope of the “Green Transformation Call in Industry” and the “Green Industry Support Program”.

4. CONCLUSION AND GENERAL EVALUATION

Some countries possess globally recognized educational institutions. Many countries also encourage their students to attend these universities. Student admissions are crucial on a global scale. Students from other countries may incur significant expenses. Most importantly, a country with highly sought-after universities is essential. The socio-economic development of countries in this league is also commendable. This situation doesn't happen on its own. First and foremost, advanced education is essential. Laboratories and research centers must incorporate advanced technology. R&D services must be effective. The socio-cultural dimension of the issue is also important. There are also socio-psychological aspects. This is where the green approach can come to the fore. In other words, it can have a selective perception effect. Becoming a green university is very important.

A green university doesn't just happen on its own. A green strategic plan and green programs are absolutely necessary. Green collaborations and green teamwork are needed. After these, sustainable green campuses can be targeted. Internal and external stakeholders of educational institutions should be made aware of the “green movement” and “green behavior”. Awareness should be created among the stakeholders. Because global climate change is active, it triggers various natural events. These problems are likely to worsen in the future. Everyone must do their part. Like every human being, campus people need clean energy. Access to clean water is a right for everyone. Like the earth, campus atmospheres can also become polluted. Campuses need a livable ecological environment. Therefore, environmental protection movements should be supported. Waste recycling rates should be increased. Administrative and academic staff and students should work together. Central administrations, local governments, and volunteer organizations should also be actively involved as stakeholders. Selected examples of success should also be evaluated. The goal should be to establish a sustainable green approach. Elements such as “green awareness” and “green behavior” should be incorporated into organizational cultures. Green campus requirements should be included in education and training programs. Green transportation should be preferred on campuses. Social responsibility projects should be supported. Green early warning systems should be established. Feedback should be monitored. Green control should be carried out by relevant units, especially internal audit offices. Collaborations can be established with green assessment institutions, and data and reports can be shared. Aiming for higher rankings in the green university index is a goal. If this is achieved, the university can become a more preferred higher education institution.

This study focuses on the topics of “green university, green university index, Turkey's green university dimension, and green university motivation”. Turkey was prioritized as the chosen country. This can be seen as a limitation. Subsequent researchers could extend this national comparison to a global scale. The “Times Higher Education” top 500 rankings and the “UI GreenMetric” top 500 lists could be compared. This could then lead to opportunities for evaluation on a global scale.

References

- Bektas, B. & Celik, A. (2025). Green behaviors of employees in the organization: A conceptual evaluation. ECLSS 2025 - 18th Eurasian Conference on Language and Social Sciences, Pen Research Institute, USA & Vilnius University of Applied

- Sciences, Lithuania, February 22 - 23, 2025, Proceedings Book (e-ISBN 978-625-97667-5-1), pp.235-248.
- Celik, A. (2022). “Yeşil Kalkınma ve Sosyal Sorumluluk”, içinde Tüm Yönleriyle Yeşil İşletme (ss.41-62). Ed. Ali Erbası, Ankara: Nobel Yayınevi.
- Celik, A. (2025). “Yönetim ve Organizasyonun Temel Kavramları”. Kitap içinde: Yönetim ve Organizasyon (ss.1-21). Ed. Z. Turkmendag, Erzurum: Atatürk Üniversitesi Açıköğretim Fakültesi Yayını.
- CoHE (The Council of Higher Education) (2025). Higher education system in Türkiye. Available at: <https://www.yok.gov.tr/en/page/higher-education-system-vylAb>, <https://www.yok.gov.tr/tr/page/mevzuat-aYrMB>; Accessed: 09.11.2025.
- Deloitte (2021). Deloitte global resilience report: Coping with the unexpected challenges (pp.1-8); Available at: <https://www2.deloitte.com/content/dam/Deloitte/dk/Documents/aboutdeloitte/2021-Resilience-Report.pdf>, Access: 11.05.2021.
- Güney, S. (2004). Açıklamalı Yönetim-Organizasyon ve Örgütsel Davranış Terimler Sözlüğü, Ankara: Siyasal Kitabevi.
- Güven, S. (2025). Yeşil Üniversite Endeksi'nde Türkiye'den 6 üniversite ilk 100'e girdi. Available at: <https://www.aa.com.tr/tr/egitim/yesil-universite-endeksinde-turkiyeden-6-universite-ilk-100e-girdi/3772833>, Accessed: 16.12.2025.
- Ozankaya, Ö. (1986). Toplumbilim, 6. Baskı, Ankara: Tekin Yayınevi.
- The Law on Higher Education (1981). (Law Number: 2547; Date of enactment: November 4, 1981; Published in the Official Gazette No: 17506; Date: November 6, 1981). Available at: <https://www.yok.gov.tr/documents/documents/68f1e0c61bbe6.pdf>, Accessed: 10.11.2025.
- THE (Times Higher Education) (2025). Dünya Üniversiteleri Sıralaması 2025-2026. Available at: <https://www.hotcourses-turkey.com/study/rankings/the-world-university.html>, Accessed: 16.12.2025.
- Turkmaarif (2025). Vakıf üniversiteleri. Available at: <https://turkmaarifansiklopedisi.org.tr/vakif-universiteleri>, Accessed: 11.11.2025.
- Vakif (2025). Vakıf Yükseköğretim Kurumu Kuruluş İşlemleri. Available at: <https://vakif.yok.gov.tr/tr/page/542>, Accessed: 11.11.2025.
- YOK (The Council of Higher Education) (2025). Dünyanın en yeşil kampüslerine Türkiye imzası: Türk üniversiteleri zirvede. Available at: <https://www.yok.gov.tr/tr/news/dunyanin-en-yesil-kampuslerine-turkiye-imzasi-turk-universiteleri-zirvede-pls7U>, Accessed: 16.12.2025.
- UI GreenMetric (2025). World University Rankings 2025. Available at: <https://greenmetric.ui.ac.id/rankings/overall-rankings-2025>, Accessed: 16.12.2025 – 03.01.2026.
- UI GreenMetric (2026). The first world university ranking on sustainability: Rankings overview. Available at: <https://greenmetric.ui.ac.id/rankings/rankings-overview>, Accessed: 16.12.2025 - 06.01.2026.

**TƏHSİLİN İDARƏEDİLMƏSİNDƏ YENİ TƏFƏKKÜR
NEW THINKING IN EDUCATIONAL MANAGEMENT**

Əliyeva Maralxanım Tofiq qızı.

Pedaqogika üzrə fəlsəfə doktoru, dosent
Azərbaycan Dövlət Pedaqoji Universiteti
“İncəsənət və fiziki tərbiyə” fakültəsi
“Musiqi və onun tədrisi texnologiyası” kafedrası
Azərbaycan, Bakı şəhəri, Üzeyir Hacıbəyli küçəsi, 68

Aliyeva Maralkhanım Tofiq gizi

Doctor of Philosophy in Pedagogy, Docent
Azerbaijan State Pedagogical University
Faculty of Arts and Physical Education
Department "Music and technology of its teaching"
Azerbaijan, Baku city, Uzeyir Hajibeyov street, 68
ORCID ID: 0000-0002-2005-6090

XÜLASƏ

Məqalədə yeni cəmiyyətin quruculuğu dövründə yeni idarəetmə təfəkkürünün labüdlüyü problemi qaldırılır. Yeni tipli təhsil müəssisəsi rəhbərinin əsas keyfiyyətləri açıqlanır, xüsusilə də onun ziyalı olması barəsində fikirlər yürüdüldür, ümumiyyətlə “ziya”, “ziyalılıq” terminlərinin məğzi araşdırılır, ən başlıcası isə kollektivin ümumi qəbul etdiyi qayda-qanunlara riayət etmənin zəruriliyi məsələlərinə baxılır. Məqlədə həmçinin əsl ziyalı olan müasir rəhbərə labüd olan keyfiyyətlər təhlil olunur. Bu yeni idarəetmə təfəkkürü təhsil təşkilatının rolunu, onun missiyasını və fəaliyyət metodlarını, eləcə də insan potensialının və müasir texnologiyaların tətbiqinin əhəmiyyətini yenidən düşünməyi tələb edir. Məqaləmizin məqsədi səmərəsiz ənənəvi idarəetmə yanaşmalarının açıqlıq, çeviklik, innovasiya və demokratiklik prinsiplərə əsaslanan yeni düşüncə tərzini əvəz olunmasının zəruriliyini göstərməkdən ibarətdir.

Açar sözlər: yeni təfəkkür, idarəetmə, ziyalı, elm və savad, qayda-qanun, rəhbər

ABSTRACT

The article raises the problem of the need for new managerial thinking during the formation of a new society. The key qualities of a leader of a new type are clarified, the idea of the need for intelligence and intelligence of a leader of a new type is put forward, the essence of the terms “intellectual” and “intelligence” is generally examined, and, most importantly, the issues of the need to comply with laws and rules adopted by the team are considered. The article also analyzes the qualities that a modern leader who is truly intellectual must have. This new management mindset requires rethinking the role of the educational organization, its mission and methods of operation, as well as the importance of human potential and the application of modern technologies. The aim of our article is to show the need to replace ineffective traditional management approaches with a new mindset based on the principles of openness, flexibility, innovation and democracy.

Key words: new thinking, management, intelligence, science and education, laws and regulations, leader

GİRİŞ

Müasir təhsil sistemi cəmiyyətin sosial strukturundakı dəyişikliklər, rəqəmsal texnologiyaların inkişafı, qloballaşma və mütəxəssis hazırlığının keyfiyyətinə artan tələblər səbəbindən dərin transformasiyalara məruz qalır. Bu şəraitdə ənənəvi idarəetmə yanaşmaları səmərəsiz olduğunu sübut edir. Onlar təhsilin idarə olunmasında açıqlıq, çeviklik, innovasiya və fərdi tələbəyə yönəlmiş prinsiplərə əsaslanan yeni düşüncə tərzini əvəz olunur. Bu yeni idarəetmə düşüncəsi təhsil təşkilatının rolunu, onun missiyasını və fəaliyyət metodlarını, eləcə də insan potensialının və müasir texnologiyaların tətbiqinin əhəmiyyətini yenidən düşünməyi tələb edir.

Təhsildə yeni idarəetmə təfəkkürü, direktiv və inzibati idarəetmədən humanist, strateji və innovativ yanaşmaya keçidi nəzərdə tutan bir konsepsiyadır. Bu düşüncə tərzini, təhsil mühitinin fərdin inkişafına və təhsilin ölkənin sosial-iqtisadi həyatına inteqrasiyasına yönəlmiş dinamik bir sistem kimi yeni bir anlayışını formalaşdırır.

Ən qədim dövrlərdən bu günə qədər rəhbər və kollektiv problemi mövcud olub. Ən qədim dövrlərdən bu günə qədər rəhbər və kollektiv arasında münasibət məsələsi həmişə aktual olub. Hər bir dövrə uyğun müxtəlif münasibət prinsipləri mövcud olub və həmin münasibətlərdəki köhnə, konservativ düşüncə tərzini öz yerini daha yeni, daha müasir təfəkkür tərzinə verib. İndiki dövrümüz də bu cəhətdən istisna deyildir.

ARAŞDIRMA

Məlum olduğu kimi ölkəmizdə kommunist hakimiyyəti dövründə yeganə idarəetmə forması inzibati-amirilik forması idi. Aşağıdan yuxarıya kimi idarəçilikdə elə bir möhkəm sistem mövcud idi ki, bu, cəmiyyətin idarə olunmasından çox orduda əsgərlərin idarə olunmasına oxşayırdı. Bütün müəssisələr bir nəfər kimi rayon partiya komitəsinin, bütün rayon partiya komitələri bir nəfər kimi mərkəzi komitənin göstərişlərinə tabe idilər.

Kommunist sisteminin dağılması ilə bərabər ondan miras qalmış inzibati-amirilik formasının da dağılması labüd idi. Buna görə azad, müstəqil və demokratik bir ölkədə bütün sahələrdə olduğu kimi idarəetmədə də yeni təfəkkürün yaranma prosesi başladı. Bu təfəkkürün əsas prinsipi ondan ibarətdir ki, kollektivin hər bir üzvü idarəetmə prosesinin subyektinə çevrilir. Artıq müəssisə rəhbərinin qarşısında “farağat” komandası ilə düzülmüş dilsiz-ağızsız kütlə yox, hər birinin öz sərbəst fikri, azad mülahizəsi olan, düşünən bir kollektiv durur. Əlbəttə belə bir kollektivi idarə etmək son dərəcə ağır və xüsusi qabiliyyət tələb edən bir işdir. Lakin düzgün idarəçilik kollektivin səmərəli fəaliyyəti üçün çox vacib bir məsələdir. Müqayisə aparsaq, hətta ən istedadlı musiqiçilərdən ibarət olan orkestr də dirijorsuz gözəl səslənə bilməz.

Yeni təfəkkürlə idarəetmə böyük bir problemdir və bu problemə müxtəlif aspektlərdən yanaşmaq olar. Bu məqalədə bu böyük problemin kiçik bir hissəsi olan bir məsələyə toxunmaq istərdik. Həmin məsələni belə adlandırmaq olar: ziyalılıq və idarəetmə.

Əvvəlcə “ziyalı” anlayışı haqqında danışaq. Adətən “ziyalı” sözü dar mənada işlənir. Belə ki, ziyalı – təhsil görmüş, elm, texnika və mədəniyyətin müxtəlif sahələrində xüsusi biliklərə malik olan və əqli əməklə məşğul olan adamlara deyilir. Lakin yüksək təhsil almaq hələ ziyalı olmaq deyil. Ziyalı üçün təhsil zəruridir, lakin kifayət deyil.

“Ziya” sözü işıq mənasını daşıyır. Hər bir sahədə olduğu kimi ziyalıları da kateqoriyalara bölmək olar. Birinci kateqoriyaya tarixin gedişinə, millətin inkişaf və tərəqqisinə təkan verən ziyalılar daxildir. Onlar öz zəkaları ilə keçmişdən aldığı “ziya”-nı gələcəyə ötürür və dünya sivilizasiyasının yüksələn xətlə davam etməsinə xidmət edirlər. Belə nadir şəxsləri “qlobal ziyalı” adlandırmaq olar.

Təbiətin və əcdadlarımızın instinktiv olaraq gəldiyi nəticələri elmi-fəlsəfi əsaslarla əldə edən, milli təfəkkürün formalaşmasında və bəşəri təfəkkürün inkişafında bazis rolunu oynayan belə ziyalılarımız tariximizdə azlıq təşkil edir. Onlar hətta insan zəkasının bilavasitə təmasda olmadığı aləmə də müdaxilə edə bilir, onun gözlə görünməyən və heç vaxt görünməyəcək ultra-mikro- və ultra-makroskopik qatlarını bütün çalarları ilə dərk edirlər. Məsələn, 1141-1209 tarix arasında yaşamış böyük Nizami Gəncəvi “İslam İntibahı”nın XII əsrdə püskürən vulkanı kimi öz ziyası ilə min illəri işıqlandırmaqdadır. Bizə çatan Nizaminin “Xəmsə”sinə Həzrəti Məhəmmədin “Mən elmin dərgahı, Əli isə onun qapısıdır” kəlamı hopmuşdur. Böyük Nizminin işığından, ziyasından bütün dünya nura qərq olmuşdur.

Ziyalıların digər bir kateqoriyasını “ali ziyalılar” adlandırmaq olar. Bu təbəqəyə Mirzə Fətəli Axundovdan tutmuş Üzeir Hacıbəyliyə qədər maarifçi-filosof-ədibləri aid etmək olar. Onların istər şəxsi həyatlarının və istərsə də yaradıcılıqlarının kökündə millətə xidmət etmək ideyası dururdu. Bu qəbildən olan ziyalılar yaşadıkları dövrün eybəcərliklərini bir cərrah bıçağı ilə kəsməklə yanaşı gələcəyin proqnozunu da verə bilirdilər.

Ziyalıların üçüncü kateqoriyasını şərti olaraq “əsil ziyalılar” adlandırmaq. Cəmiyyətimizdə onların sayı çoxdur. Əsil ziyalılar millətin onurğa sümüyüdür. Onlarsız millət yoxdur. Onlar millətin düşünən beyni, vuran ürəyi və narahat vicdanıdır. Əsil ziyalı kim olduğu barəsində bir misal göstərək. Azərbaycanın görkəmli bəstəkarı mərhum Arif Məlikov müxbirin “Niyə Azərbaycandan getmirsiniz?” sualına belə cavab vermişdir: – “Şəxsən mən ... Yaponiyadan, Almaniyadan, Amerikadan və s. iş təklifləri alıram, özü də çox yüksək məvaciblə. Ancaq mən imtina edirəm, çünki öz beynimi millətimə vermək istəyirəm.”

Bu da əsil ziyalı mövqeyidir – xalqa, millətə xidmət etmək, onun dərdinə şərik olmaq nümunəsidir. Beləliklə, “Əsil ziyalı kimdir?” sualına aşağıdakı cavabı vermək olar: Öz yüksək intellekti – təfəkkürü, əqli qabiliyyəti, ali insani keyfiyyətləri ilə xalqa yol göstərən, millətin yoluna işıq saçan şəxsə əsil ziyalı demək olar. Əsil ziyalı əvvəlcə ətrafdakıların qayğıları haqqında, sonra isə öz şəxsi qayğıları haqqında düşünür. Belə ziyalı istənilən halda işlədiyi kollektivin liderinə çevrilir. Belə ziyalı təbii surətdə nüfuz qazanır. Nəhayət, belə ziyalı istənilən kollektiv üçün ideal rəhbərə çevrilir.

Beləliklə, müasir rəhbər bir o qədər də inzibatçı deyil, lakin dəyişiklik lideridir və aşağıdakıları bacarmalıdır:

komanda qurmaq və müəllimlərin peşəkar inkişafını dəstəkləmək;

təhsil mühitini idarə etmək;

təhsilin keyfiyyətini və təhlükəsizliyini təmin etmək;

innovasiyaları və rəqəmsal həllərin tətbiq etmək;

əməkdaşlıq və qarşılıqlı hörmət mədəniyyətinin inkişaf etdirmək;

valideynlər, tərəfdaşlar və dövlət qurumları ilə ünsiyyət qurmaq.

Lider üçün əsas olan səriştələr: ünsiyyət bacarıqları, strateji düşüncə, rəqəmsal savadlılıq, lahiyələndirmə qabiliyyəti, çeviklik və uyğunlaşma.

Bundan əlavə müasir rəhbər kollektivin ümumi rəyi ilə hesablaşmaq bacarığına malik olmalıdır. “Kollektivin rəyi ilə hesablaşmaq” dedikdə, müsəssisə rəhbərinin hər deyənin sözü ilə oturub-durması nəzərdə tutulmur. Hər bir işçinin istədiyini yerinə yetirmək anarxiyaya gətirib çıxarar. İntizam olmayan yerdə müvəffəqiyyət də yoxdur. Lakin rəhbərin diktaturası deyil, qəbul olunmuş qayda-qanunun diktaturası olmalıdır. Kollektivin hər bir üzvü qəbul edilmiş qayda-qanunları və ümumi tələbləri pozmamalıdır. Rəhbərin vəzifəsi isə həmin qayda-qanunlar çərçivəsində kollektivin işini təşkil etmək və onun istisnasız hər bir üzvünün iş borcunu tələb etməkdir.

Demokratiya yaxşı şeydir, lakin o demək deyil ki, kim nə istəyirsə, onu da etsin. Demokratiya odur ki, insanlar qanunlar çərçivəsində öz hərəkətlərini könüllü surətdə məhdudlaşdırırlar. Könüllülük də o vaxt olur ki, həmin qayda-qanunların qəbul edilməsində bir adamın yox, bütün kollektivin iradəsi həyata keçsin. Kollektiv, cəmiyyət tərəfindən qəbul edilmiş qayda-

qanunlara hamı riayət edir. Həmin qayda-qanunlar da insan fəaliyyətini məhdudlaşdırır. Lakin insanlar buna öz hüquqlarının pozulması kimi, demokratiyanın pozulması kimi baxmır. Bunlar hamısı könüllü surətdə baş verir.

Təhsilin idarə olunmasında yeni təfəkkürün əsas istiqaməti idarəetmə proseslərinin humanistləşdirilməsidir. Təhsil təşkilatları strateji planlaşdırma həyata keçirir, xarici mühiti təhlil edir və dəyişikliklərə uyğunlaşmağa imkan verən missiya və uzunmüddətli hədəflər formalaşdırırlar. İdarəetmə daha çox insan yönümlü hala gəlməlidir: müəllimlərin və tələbələrin ehtiyacları və maraqları nəzərə alınmalıdır. O, aşağıdakı əsas prinsiplərə əsaslanmalıdır:

Formal göstəricilərə deyil, təhsilin keyfiyyətinə diqqətin yetirilməsi.

Təhsilin ömürlük bir proses kimi qəbul edildiyi davamlı inkişaf modelinə keçid.

İnsan kapitalının - müəllimlərin, şagirdlərin, valideynlərin və tərəfdaşların rolunun gücləndirilməsi.

Sübutlara əsaslanan qərar qəbuletmə.

Rəqəmsal texnologiyalara və innovasiyaya açıqlıq.

Təhsil təşkilatları, biznes və cəmiyyət arasında şəbəkələşmə və tərəfdaşlıq.

Bu tipli təfəkkür, təhsil mühitinin fərdin inkişafına və təhsilin ölkənin sosial-iqtisadi həyatına inteqrasiyasına yönəlmiş dinamik bir sistem kimi yeni bir anlayışını formalaşdırır.

NƏTİCƏ

Bütün dediklərimizi yekunlaşdırsaq, aşağıdakı nəticələrə gəlmək olar:

– Yeni təfəkkürün aparıcı prinsiplərindən biri budur ki, insanların taleyi hansısa məmurun əhval-ruhiyyəsindən yox, qanun və qaydalardan asılı olmalıdır.

– İkinci əsas prinsip ondan ibarətdir ki, istənilən şəraitdə insan hüquqları gözlənilməli və yaranmış konfliktlər şəxsiyyətə hörmət şəraitində, hamı tərəfindən qəbul edilmiş qayda-qanun çərçivəsində həll edilməlidir.

– Və nəhayət sonuncu və mühüm psixoloji prinsip: “cəmiyyət rəhbərə xidmət etmir, rəhbər cəmiyyətə xidmət edir” prinsipidir. Bu prinsip özündən razı, təkəbbürü yerə-göyə sığmayan, tabeliyində olan adamların fikrinə də təkəbbürlə yanaşan rəhbərləri inkar edir və onları üzvü (orqanik) şəkildə qəbul edə bilmir.

Yeni idarəetmə yanaşmalarına keçid bir sıra mürəkkəb amillərlə idarə olunur:

1. Sosial-iqtisadi dəyişikliklər. Müasir cəmiyyət çevik, yaradıcı və səriştəli mütəxəssislər tələb edir. Bu, təhsil proseslərinin və onların idarə olunmasının transformasiyasını zəruri edir.

2. Rəqəmsallaşma. İnformasiya texnologiyaları təhsil formalarını kökündən dəyişdirir, onu daha fərdiləşdirir və əlçatan edir, menecerlərdən müasir rəqəmsal idarəetmə vasitələrinə yiyələnməyi tələb edir.

3. Qloballaşma və rəqabət. Təhsil müəssisələri təkcə milli səviyyədə deyil, həm də beynəlxalq səviyyədə rəqabət aparır. Bu, strateji idarəetmənin tətbiqini asanlaşdırır.

4. Təhsil keyfiyyətinə artan cəmiyyət tələbləri.

Təhsilin idarə olunmasında yeni təfəkkür müasir təhsil sisteminin inkişafı üçün vacibdir. Bu, köhnəlmiş inzibati-amirlik metodlarından imtina etməyi və humanist, innovativ, strateji və texnologiyaya yönəlmiş yanaşmaya doğru irəliləməyi nəzərdə tutur. Bu yeni düşüncə fərdə (müəllimə, tələbəyə və rəhbərə) və onun inkişafına yönəlmişdir. Bu ideyaların tətbiqi təhsilin keyfiyyətinin, tələbələrin uğurlarının və təhsil müəssisələrinin rəqabət qabiliyyətinin artırılmasına töhfə verə bilər.

ƏDƏBİYYAT:

1. Azərbaycan Respublikasında təhsilin inkişafı üzrə Dövlət Strategiyası 2013

<https://president.az/az/articles/view/9779>

2. Алламурадов Б.Ю. Совершенствование системы стимулирования деятельности педагогического коллектива в СПО. / Материалы Всероссийской студенческой научно-практической конференции «Вызовы XXI века», г. Набережные Челны, Апрель 2021, стр.216-218

(Allamuradov B.Y. Improving the system of stimulating the activities of the teaching staff in secondary vocational education. / Proceedings of the All-Russian Student Scientific and Practical Conference "Challenges of the 21th Century", Naberezhnye Chelny, April 2021, pp. 216-218)

3. Babayeva T. Nizami Gəncəvinin ədəbi irsində şəxsiyyət problemi. Bakı: 2000, 200 s. (Babayeva T. The problem of identity in the literary heritage of Nizami Ganjavi. Baku: 2000, 200 p.)

4. Gizi A.L.K. Strategic planning in higher education institutions: mission, vision, main values and swot analysis of Azerbaijan HEİS. Endless light in science, 2023, (May), p.30-41.

5. Hüseynova F. Strateji planlaşdırma və idarəetmənin həyata keçirilməsi. / Bakı, 2020, 121 səh.

(Huseynova F. Strategic planning and management implementation. / Baku, 2020, 121 p.)

6. Xalıqova N. Azərbaycanın Dövlət ali təhsil müəssisələrində strateji planlaşdırma işinin təşkiuli. / Azərbaycan məktəbi. Azerbaijan Journal of Educational Studies.. Bakı-2025, №2, səh.20-38

7. Quliyev T. İnsan resurslarının idarə edilməsi. Bakı, 2013, 828 s.

(Guliyev T. Human resources management. Baku, 2013, 828 p.)

8. Михеева С.А. Управление образованием и педагогический менеджмент: терминологический аспект. / ж-л Управление образованием: теория и практика. 2018, № 2, стр. 11-23

(Mikheeva S.A. Education management and pedagogical management: terminological aspect. / journal Education Management: Theory and Practice. 2018, no. 2, pp. 11-23)

NEFTİN TARİXİ KÖKLƏRİ VƏ MÜASİR DÖVRDƏ ROLU

Allahverdiyeva Fəridə

Azərbaycan Milli Elmlər Akademiyası A.A.Bakıxanov adına Tarix və Etnologiya
İnstitutunun tədqiqatçısı, Bakı şəhəri, Orcid: 0000 0001 5322 3548

Xülasə

Neft insan tarixində mühüm strateji və iqtisadi resurs kimi çıxış etmişdir. Onun tarixi kökləri minilliklər əvvələ gedib çıxır. Qədim Mesopotamiya, Babil və Assuriya yazılı mənbələrində neftin məişət və tikinti işlərində, həmçinin müalicəvi vasitə kimi istifadə olunduğu qeyd edilir. Azərbaycanın Abşeron yarımadası da qədim dövrlərdən “odlar yurdu” kimi tanınmış, burada neft və qaz sızmaları insanların diqqətini çəkmişdir. XIX əsr neft tarixində dönüş nöqtəsi oldu. 1846-cı ildə Bakının Bibiheybət ərazisində dünyada ilk dəfə sənaye üsulu ilə neft quyusu qazıldı. Bu hadisə həm Azərbaycan, həm də bütün dünya üçün yeni bir dövrün başlanğıcı idi. Bakı qısa müddət ərzində beynəlxalq neft sənayesinin mərkəzinə çevrildi və XX əsrin əvvəllərində dünya neft hasilatının böyük bir hissəsini təmin edirdi. XX əsrdə neftin rolu daha da artaraq strateji əhəmiyyət qazandı. Birinci və İkinci Dünya müharibələrində orduların hərəkətliliyi və dövlətlərin iqtisadi gücü əsasən neftlə təmin olunurdu. Azərbaycan nefti SSRİ-nin enerji ehtiyaclarının ödənilməsində mühüm rol oynadı və müharibənin taleyində həlledici əhəmiyyət daşıdı.

Müasir dövrdə isə neft yalnız enerji istehsalında deyil, həm də kimya sənayesində əvəzsiz xammal kimi istifadə olunur. Plastik, gübrə, dərman, sintetik materiallar və bir çox məhsullar məhz neftdən əldə edilir. Bununla yanaşı, alternativ enerji mənbələrinin inkişafı gündəmdə olsa da, neft hələ də dünya iqtisadiyyatının və siyasətinin ən mühüm resurslarından biri olaraq qalır. Beləliklə, neftin tarixi kökləri ilə müasir dövrdəki rolu bir-birini tamamlayır və onun bəşəriyyət üçün strateji əhəmiyyəti hələ uzun illər davam edəcəkdir.

Açar sözlər: Neft tarixi, Qədim neft istifadəsi, Azərbaycan nefti, İqtisadi inkişaf

Abstract

Oil has played a crucial role in human history as an important strategic and economic resource. Its historical roots date back thousands of years. Written sources from ancient Mesopotamia, Babylon, and Assyria indicate that oil was used in daily life, construction, and as a medicinal substance. The Absheron Peninsula of Azerbaijan has also been known since ancient times as the “Land of Fire,” where natural oil and gas seepages attracted human attention.

The nineteenth century marked a turning point in the history of oil. In 1846, the world’s first industrial oil well was drilled in the Bibiheybət area of Baku. This event signified the beginning of a new era not only for Azerbaijan but also for the entire world. Within a short period, Baku became a major center of the international oil industry and, at the beginning of the twentieth century, supplied a significant share of global oil production.

In the twentieth century, the role of oil expanded further and gained strategic importance. During the First and Second World Wars, the mobility of armies and the economic power of states were largely dependent on oil. Azerbaijani oil played a vital role in meeting the energy needs of the USSR and had decisive importance in determining the outcome of the war.

In the modern era, oil is used not only for energy production but also as an indispensable raw material in the chemical industry. Plastics, fertilizers, medicines, synthetic materials, and many other products are derived from oil. Although the development of alternative energy sources is

on the global agenda, oil remains one of the most important resources shaping the world economy and politics.

Thus, the historical roots of oil and its role in the modern era complement each other, and its strategic importance for humanity is expected to continue for many years to come.

Keywords: History of oil, Ancient use of oil, Azerbaijani oil, Economic development

Giriş

Neft bəşər sivilizasiyasının inkişafında mühüm strateji resurslardan biri hesab olunur. Onun tarixi minilliklər öncəyə gedib çıxır və həm məişətdə, həm də iqtisadiyyatda geniş istifadə olunmuşdur. Neft yalnız enerji daşıyıcısı deyil, həm də kimya sənayesinin əsas xammalıdır. Müasir dövrdə neft dünya siyasətində və iqtisadiyyatında aparıcı rol oynamaqda davam edir.

Ərəb tarixçiləri, coğrafiyaşünasları və səyyahlarından Əhməd Əl-Bəlaruri (IX əsr) Abşerondakı iqtisadi həyatın qədimdən neftlə bağlı olduğunu göstərmiş, Əbu-İshaq İstəxri (XI-X əsrlər), Əbu-d-Həsən Əli Məsudi (X əsr) Bakının neftli torpağı, Abşeronun “ağ” və “qara” nefti haqqında məlumat vermişdir. İtalyan səyyahı Marko Polo (XIII-XIV əsrlər) Bakı neftinin yaxın Şərq ölkələrinə aparılması, alman diplomatı və səyyahı Adam Oleari (XVII əsr) Bakıdakı neft quyuları, türk səyyahı Evliya Çələbi (XVII əsr) neft mədənləri, neftin İrana, Orta Asiyaya, Türkiyəyə və Hindistana aparılması və neftin gətirdiyi illik gəlir haqqında məlumat vermişdir. Balaxanıdakı neft quyularından birində aşkar edilmiş daş üzərindəki yazı quyunun (35 m dərinliyində) hələ 1594-cü ildə usta Allahyar Məmmədınur oğlu tərəfindən qazılıb istifadəyə verildiyi göstərilir. Əmin Əhməd Razinin (İran, 1601) məlumatına görə XVI əsrin əvvəllərində Bakı ətrafında 500-ə qədər belə neft çalaları və quyusu mövcud idi ki, bunlardan da həm “qara”, həm də “ağ” neft çıxarıldı. Alman səyyahı, həkim və təbiətşünası Engelbert Kempfer İsveç səfirliyinin katibi kimi 1683-cü ildə Abşeron yarımadasında Balaxanı, Binəqədi, Suraxanı yataqlarında olmuş, neftin Abşeron yarımadasından İrana, Orta Asiyaya və Şimali Qafqaza aparılmasını təsvir etmişdir. 1803-cü (1798) ildə Bakı sakini Qasımbəy Mənsurbəyov Bibiheybət yaxınlığında, dənizdə, sahildən 18 m və 30 m aralı iki neft quyusu qazdırmışdır.

Elə 1859-cu ildə Bakıda ilk neftayırma zavodu (qurğusu) tikilib. 1863-cü ildə Cavad Məlikov Bakıda kerosin zavodu inşa etdirib və dünyada ilk dəfə neftayırma prosesində soyuduculardan istifadə olunub. 1867-ci ildə 15 neftayırma qurğusu fəaliyyət göstərüb. Mexaniki üsulla quyuların qazılması texnologiyası inkişaf etdikcə bir sıra yeni neft yataqları aşkar edilir (Binəqədi, Pirallahı a., Suraxanı və s.), neft hasilatı artır, neft sənayesinin infrastrukturunu və neftin emalı inkişaf etməyə başlayır, neftin hasilatı, emalı və satışı üzrə yüzlərlə firmalar yaradılırdı. Azərbaycanda milli burjuaziya formalaşır, Bakı şəhəri dünyanın sənaye mərkəzlərindən birinə çevrilirdi. İlk dəfə Abşeron yarımadasında 1871-ci ildə Balaxanı-Sabunçu-Ramanı yatağının sənaye üsulu ilə işlənilməsinə başlanıb. 1872-ci ildə neft sənayesində münasibətləri tənzimləmək məqsədilə iki qanun qəbul edilib: “Neft mədənləri və neft məhsullarından aksiz vergisi haqqında” və “İcarədarların əlində olan neftli sahələrin hərəqlə fiziki şəxslərə satılması”. 31 dekabr 1872-ci ildə neftli sahələrin ilk satışında Balaxanıda 15 sahə, Bibiheybətdə 2 sahə hərəqlə çıxarılıb.

Qədim mənbələrdə neftin istifadəsinə dair çoxsaylı faktlara rast gəlinir. Assuriya, Babil, Misir və qədim Çin sivilizasiyalarında neftdən işıqlandırma, tikintidə, hərbi məqsədlərdə, həmçinin tibbi müalicələrdə istifadə olunmuşdur.

Azərbaycan ərazisində isə neftin tarixi daha da qədimdir. Abşeron yarımadasında yer üzünə çıxan təbii neft sızmaları və alovlu qaz çıxışları bu torpaqlara “Odlar yurdu” adını qazandırmışdır. Orta əsr səyyahlarının qeydlərində Bakı neftindən gündəlik həyatın müxtəlif sahələrində istifadə edildiyi qeyd olunmuşdur.

Azərbaycanda neft sənayesi milliləşdirilənədək 109 səhmdar cəmiyyəti fəaliyyət göstərirdi. Onlardan 72-si rus kapitalına (240 milyon rubl) və 37-si isə ingilis kapitalına (100 milyon funt-

sterlinq) məxsus idi. Nobel qardaşlarının neft sənayesinə qoyduqları kapital 30 mln. rubl təşkil edirdi. O dövrün ən varlı neft sənayesi sahibkarlarından olan messenat İsa bəy Hacinskinin “Hacı-Çeleken” neft şirkətinin neft sənayesinə kapital qoyuluşu 1,25 milyon funt-sterlinq təşkil edirdi.

II mərhələ - 1920-ci ildə Azərbaycanda neft sənayesinin milliləşdirilməsindən sonra başlayır və 1949-cu ildə açıq dənizdə “Neft Daşları” yatağının kəşfi dövrünü əhatə edir. 1921-ci ildə neft hasilatı 2,4 milyon tonadək azaldı. II mərhələdə axtarış-kəşfiyyat işlərinin genişləndirilməsi ilə əlaqədar Azərbaycanda bir sıra yeni neft yataqları (xüsusilə Qala, Buzovna-Maştağa və s.) aşkar edilərək istismara verildi. Neft hasilatı 1941-ci ildə 23,6 milyon tona çatdırıldı ki, bu da o dövrdə SSRİ-nin neft hasilatının 76%-ni təşkil edirdi.¹

Azərbaycan nefti və sənaye hasilatının başlanğıcı. XIX əsrdə neftin sənaye üsulu ilə hasilatı geniş vüsət aldı. 1846-cı ildə Bakının Bibiheybət ərazisində dünyada ilk dəfə olaraq mexaniki üsulla neft quyusu qazıldı. Bu hadisə dünya neft sənayesinin başlanğıcı kimi tarixə düşdü.

XX əsrin əvvəllərində Bakı dünyanın əsas neft mərkəzlərindən birinə çevrildi. 1901-ci ildə Bakı təkcə dünyanın ümumi neft hasilatının 50 faizini verirdi. Bu, Azərbaycanın qlobal enerji xəritəsində mühüm yer tutduğunu göstərirdi.

Neftin kəşfi və istifadəsi dünya iqtisadiyyatının inkişafına güclü təsir göstərmişdir. XX əsrdə neft ölkələrin sənaye inqilabına təkan vermiş, nəqliyyat və energetika sahələrində çevrilmiş yaratmışdır. İkinci Dünya müharibəsində neft strateji resurs kimi dövlətlərin taleyini müəyyən edən amillərdən biri olmuşdur. Ümummillə lider Heydər Əliyevin rəhbərliyi altında uğurla reallaşdırılmış yeni neft strategiyası ötən illərdə Azərbaycanın bütün həyatı əhəmiyyətli sahələr üzrə dinamik inkişaf yolunda olan respublikaya çevrilməsi, beynəlxalq arenada nüfuz və mövqelərini möhkəmləndirməsi, habelə milli təhlükəsizlik maraqlarını yüksək səviyyədə təmin etməsi baxımından müstəsna rol oynamışdır. Xəzər dənizində beynəlxalq əməkdaşlığın təməlini qoymuş bu tarixi müqavilə Azərbaycanın yeni gənc müstəqil dövlət olaraq öz təbii sərvətlərinə sahib çıxmaq, milli mənafelərini, iqtisadi və strateji maraqlarını sonadək müdafiə etmək əzmində olduğunu təsdiqləmişdir.²

Müstəqillik illərində Azərbaycan nefti yenidən böyük əhəmiyyət kəsb etməyə başlamışdır. 1994-cü ildə imzalanmış “Əsrin müqaviləsi” ölkənin iqtisadi inkişafının əsas dayaq nöqtəsinə çevrilmiş, xarici sərmayələrin cəlb olunmasına və ölkənin beynəlxalq mövqeyinin möhkəmlənməsinə səbəb olmuşdur.

Nəticədə 60-cı illərin sonu ilə müqayisədə yeni 8 neft və qaz yataqları kəşf edildi, neft ehtiyatları iki, qaz ehtiyatları isə üç dəfə artırıldı. 1975-ci ildə neft və qazın ümumi hasilatı 27,1 mln. t-a (şərti yanacaq) çatdırıldı. 80-ci illərdə üzən qazma qurğularının sayı 11-ə çatdı və onlardan istifadə nəticəsində, indi Azərbaycan neftinin əsas hissəsini təşkil edən dənizin 80-350 m dərinlikdə yatan zəngin neft ehtiyatlarına malik olan yataqlar kəşf olundu (Günəşli, Çıraq, Azəri və b.). Deyə bilərəm ki, Azərbaycanın neft gələcəyi çox parlaqdır. Hesab edirəm ki, respublikamız bundan əldə etdiyi gəliri düzgün xərcləyəcək və beləliklə, iqtisadiyyatımızın bütün sektorları inkişaf edəcəkdir.

Müasir dövrdə neft yalnız enerji resursu deyil, həm də kimya sənayesinin əsas xammalıdır. Plastik, gübrə, dərman, parça və digər minlərlə məhsul neftdən əldə olunur. Bununla yanaşı, alternativ enerji mənbələrinin inkişafı neftin gələcəkdəki rolunu müəyyən edir. Lakin yaxın onilliklərdə də neftin dünya iqtisadiyyatı üçün əvəzolunmaz resurs olaraq qalacağı proqnozlaşdırılır.³

Və neftin tarixi kökləri və müasir dövrdə rolu göstərir ki, bu resurs bəşər sivilizasiyasının inkişafında mühüm amil olmuşdur. Qədim dövrlərdə məişətdə sadə məqsədlərlə istifadə olunan

¹ <https://minenergy.gov.az/az/neft/neft-senayesinin-inkisaf-tarixi>

² AĞAMALI ZƏRİFƏ AZƏRBAYCANIN NEFT STRATEGİYASI VƏ ÖLKƏNİN SOSIALİQTİSADI İNKİŞAFINDA ONUN ROLU mövzusunda MAGİSTR DİSSERTASIYASI s.3. 2015.

³ <https://azerbaijan.az/related-information/130>

neft, bu gün dünya iqtisadiyyatının və siyasətinin ən strateji resursuna çevrilmişdir. Azərbaycan isə həm tarixi, həm də müasir dövrdə neft mədəniyyətinin əsas mərkəzlərindən biri olaraq qalır.

Ədəbiyyat siyahısı

1. Əlizadə, Ə. (2010). Azərbaycan neft tarixi. Bakı: Elm nəşriyyatı.
2. İbrahimov, R. (2018). Neft və global siyasət. Bakı: Adiloğlu.
3. Əliyev, H. (2005). Azərbaycanın neft strategiyası. Bakı: Təhsil.
4. AĞAMALI ZƏRİFƏ AZƏRBAYCANIN NEFT STRATEGİYASI VƏ ÖLKƏNİN SOSIALİQTİSADI İNKİŞAFINDA ONUN ROLU mövzusunda MAGİSTR DİSSERTASIYASI

THE SACRED AND THE SYMBOLIC: RITUAL AS THE FOUNDATION OF
RELIGIOUS EXPERIENCE

Ananda Majumdar

Ananda Majumdar - Harvard University

Ananda MAJUMDAR | alumnus | Business | MacEwan University, Edmonton | Human Resources |
Research profile

Prof. Dr. Ananda Majumdar (0000-0003-3045-0056) - ORCID

[View Scholars Profile](#)

[International-Colloquium-Program.pdf](#)

[Program Symposium Nicaea 2025](#)

[Robin Hood Scholars: IARHS on the Web: 15th Biennial Conference Schedule](#)

[2025 Conference Abstracts – The Australian Early Medieval Association](#)

The Wooing group conference speaker, September 25-26, 2026, at the University of Oxford, England

Harvard Graduate School of Education (Professional Education as a Child Development Educator,

Certificate in Early Education Leadership (CEEL-Series 1,2,3), online) 2017-2025

*NorQuest College, Alberta Routes Program -present

The Arthurian legend, a collection of tales about King Arthur, his knights, and their quests, has been a central theme in my academic journey. This legend, with its themes of heroism and noble ideals, holds significant cultural and historical importance. It has been a central theme in my exploration of cross-cultural communication, offering a unique perspective on the relationship among myth, culture, and science. This perspective, combined with my academic background, enables me to provide insights into the study of global displacement. The Arthurian legend, with its themes of heroism and noble ideals, can serve as a powerful tool for understanding and addressing the complex issue of global displacement, particularly in relation to the cultural and societal factors that impact gender equality. It also serves as a compelling avenue to investigate how sound influences the artistic and architectural features of the medieval era, symbolizing the shaping of societal norms and values.

*Doctor of Divinity, North Central Theological Seminary, Minneapolis, United States, 2023 - present
The University of Alberta (Bachelor of Education after Degree in Elementary, Faculty of Education,
Community Service-Learning Certificate and Certificate in International Learning (CIL) – 2012-2022

My international experiences, particularly in India, have significantly broadened my academic perspective. They have deepened my understanding of global issues, including gender inequality, and connected me with a broader educational network. Importantly, these experiences have given me a unique perspective on the global displacement crisis, particularly regarding the Norman Conquest and its impact on India. This perspective is crucial for understanding and addressing this complex issue. It has prompted me to examine our shared cultural heritage through the lens of the Arthurian legend, a cultural phenomenon transcending national borders. This collective inquiry can lead to a deeper understanding of shared human experiences, including the diverse interpretations and applications of the Arthurian legend in relation to gender and empowerment issues in India.

Public Affairs, August 1-15, 2022, Online

As an intern at the Digital Museum and Diaspora, Migration, GRFDT, New Delhi, India (April 2021 - March 2022, Online), I gained valuable insights into the practical aspects of migration and diaspora issues. This experience, combined with my academic background, further enriched my understanding of these complex topics and prepared me to contribute meaningfully to the study of global displacement.

During my time as a Book Pecker Fellow at Peace X, India, I was honoured to be named the top fellow in the social science department. In this capacity, I researched the cultural significance of the Arthurian legend, particularly in India, which motivated me to pursue my academic endeavours further. I earned a certificate in computer literacy in Migration Studies from GRFDT, New Delhi, India. This experience as a Book Pecker Fellow at Peace X, India, allowed me to delve deeper into the cultural and societal implications of the Arthurian legend, particularly in the context of global issues such as migration and displacement.

INTERNATIONAL TOPKAPI CONGRESS VI

Science department and computer literacy certificate in Migration Studies, GRFDT, New Delhi, India
(September 2020- March 2021, Online)

Grant MacEwan University (Diploma in HR Management), 2008-2012

Jadavpur University (Master of Arts in International Relations)

Sikkim Manipal University (Master of Business Administration in HR and Marketing Management)

MBB College, Tripura University (Bachelor of Arts in Political Science)

Antarctic Institute of Canada (Researcher and Writer), Servicing Community Internship Program
(SCIP) funded by the Government of Alberta,

Member of Student Panel, Academic Panel, Cambridge University Press,

Academic Member of the Association of Political Theory (ATP), University of Massachusetts

Reviewer of the Asian Journal of Education and Social Studies, *Health Economics, Policy and Law*,
Cambridge University Press.

Academic Member of the Memory Studies Association, School of Memory Studies, Indian Institute of
Technology (IIT) Madras, Tamil Nādu, India

*Early Childhood Educator, Brander Garden After School Parents Association – present

Researcher, Project-based Articles, Antarctic Institute of Canada under Riipen

*Professor of Practice in Social Science, QAHE & Kennedy University of Saint Lucia -present



The sacred, the symbolic ritual as the foundation of religious experience: images in the medieval - Search Images

Abstract: Rituals are central to religious practice. They turn complex beliefs into lived experiences and foster shared identity. This paper examines the close connection between ritual and religion, showing how deliberate, recurring actions establish and maintain religious meaning across cultures. Drawing from anthropology, sociology, and religious studies, it explains how rituals reinforce beliefs, unite people, and foster spiritual growth. It explores rituals such as daily prayers, meditation, and ceremonies marking life events. These acts create meaningful moments and spaces, connect people to the divine, and prompt reflection on life's big questions. The paper distinguishes between everyday 'ritualization' and formal group ceremonies, underscoring the adaptability of religious practice. Personal rituals can be spontaneous and evolving, representing individual spiritual journeys, while formal ceremonies are structured and communal. Overall, the study emphasizes ritual as essential to religious experience.

Keywords: ritual practice, religious symbolism, sacred performance.

Introduction: Ritual is central to religious life. It turns complex beliefs into experiences that shape how people understand the sacred. This study shows rituals as the main way religious meaning is created, shared, and sustained across cultures. It argues rituals do more than reflect beliefs—they shape and change religious experience. Scholars see ritual as vital to human spirituality, drawing clear lines between the sacred and the ordinary. Ceremonies unite people and support shared values. Rituals mark life changes, connect people with the divine, offer meaning in hard times, and sustain tradition. Yet much research treats rituals only as expressions of belief, overlooking how they shape religious awareness and understanding. Symbols in rituals are crucial. Religious symbols link the physical and spiritual, turning complex ideas into actions and performances. Water can mean cleansing, fire change, and shared meals of unity. The meaning comes from repeated ritual, learned and passed on through practice. As debates about religion's decline rise, focus often shifts to belief, but ritual participation may be a stronger mark of a religion's health. Observing rituals adapt to modern life—through technology, mixed-faith settings, and the needs of younger generations—shows that religious practice is flexible. This study uses anthropology, sociology, and theology to view rituals as personal devotion, group ceremonies, organized services, and spontaneous acts. By comparing formal ceremonies and daily rituals, the research shows how practice evolves while tradition endures. No single field fully explains ritual. Anthropology studies symbols and culture; sociology, group unity; and religious studies, faith and experience. This study reveals that rituals don't just express belief; they are the core of religious experience. It shows repeated actions shape meaning, form identity, and help traditions last as cultures shift. Seeing ritual as central to religion changes how we view faith transmission, conversion, and revival. The analysis suggests religious groups endure more by maintaining ritual than strict belief.

Literature Review: The study of rituals has changed significantly over the last hundred years. Scholars from diverse fields have offered insights into how rituals function in religious settings. This review examines key contributions from anthropology, sociology, psychology, and religious studies, focusing on theories and current debates on how rituals shape religious experiences. Emile Durkheim's early work, "The Elementary Forms of Religious Life," set a sociological foundation for understanding rituals as group activities that strengthen community bonds and create a sense of the sacred through shared actions. He argued that religious rituals are social events that produce "collective effervescence," intense emotional experiences that connect individuals to their communities and create a sense of something greater than themselves. His idea that the sacred is formed through rituals remains influential, even though later scholars have questioned his view, which reduces religious experiences to mere social functions. Victor Turner built on Durkheim's ideas by developing the concept of liminality. He explained that rituals create special moments when normal social rules disappear, allowing participants to experience "communitas," a state of equal, open community. Turner studied rites of passage to show how rituals help people through life changes by separating them from their old roles, placing them in a transitional state, and then welcoming them into new identities. This three-step process shows how rituals help manage change while keeping social order. Clifford Geertz looked at rituals as cultural performances. He argued that religious rituals reflect and shape people's views of reality. In his important essay, "Religion as a Cultural System," Geertz suggested that rituals combine a community's beliefs with their values, turning abstract ideas into physical actions. In this way, rituals are not just reflections of beliefs; they actively shape how participants understand and engage with the world. Geertz's focus on interpretation and meaning has greatly influenced religious studies, encouraging scholars to consider how ritual participants perceive their practices. Catherine Bell challenged earlier views by arguing that we should not see rituals as separate types of action but rather as a quality of action, which she called "ritualization." Bell's practice theory highlights that rituals are a strategic way of acting that sets apart the sacred from everyday life. This approach focuses on what rituals do rather

than on what they mean, examining how these practices create power dynamics, establish authority, and shape religious identities. Bell's work is important because it moves away from fixed definitions of ritual and shows how the concept is shaped by culture and used deliberately. Roy Rappaport took an ecological view of rituals, stressing their communicative role. He believed that rituals share information in unique ways: they are public, involve the performer's body, and are hard to fake. He made a clear distinction between the stable form of rituals and their varied content. This helps explain how rituals stay relevant across generations while adapting to new situations. Rappaport's concept of "liturgical orders" offers a framework for analyzing how rituals convey complex information, including cosmological ideas, social rules, and moral values. Jonathan Z. Smith challenged the idea that rituals are spontaneous or purely expressive. He argued that rituals help create focus and meaning through intentional design. Smith emphasized that rituals help establish sacred spaces that represent ideal order. His comparative approach revealed the variety of rituals across cultures, while also identifying common themes in how rituals carve out boundaries, manage change, and balance tradition with innovation. Smith pointed out the gap between ideal representations of rituals and the lived experiences, showing that rituals don't exactly mirror social life but instead offer alternative views that participants navigate in complex ways. Paul Connerton explored how rituals act as embodied practices that embed collective memory into individual bodies through repetition. He distinguished between inscribing and incorporating practices, showing that bodily actions—such as gestures and movements—transmit cultural knowledge more effectively than written texts. This view is valuable for understanding how religious traditions persist over generations, even during disruptions. Connerton argued that ritual knowledge is primarily physical, rooted in the body's abilities to perform specific actions in certain contexts. Talal Asad critiqued universal definitions of ritual and religion, suggesting that Western academic categories often misrepresent these practices. He contended that we cannot separate rituals from the power structures within which they exist. Using a genealogical approach influenced by Foucault, Asad examined how rituals create specific kinds of religious identities through ongoing bodily discipline. His critical perspective encourages scholars to consider the politics of ritual, including questions such as who gets to define authentic practices, how rituals include or exclude people, and how they evolve in response to colonial and postcolonial influences. Recent scholars have built on these ideas while exploring new questions. Ronald Grimes created a detailed classification of ritual types, including ritualization, decorum, ceremony, liturgy, magic, and celebration, each serving distinct purposes. His work on ritual criticism offers tools for assessing how well rituals work and identifying when they fail. Grimes stressed that rituals can be poorly executed, fail to achieve their goals, and even cause harm, pushing back against romanticized views that treat all rituals as inherently valuable. This critical approach is especially relevant for those looking to create or adjust rituals for modern times. Anthropologist Michael Houseman studies how rituals create experiences for participants that differ from those in everyday life. He focuses on the sensory and aesthetic aspects of rituals, showing how they engage our senses—like sight, sound, touch, and smell—to create immersive experiences that are hard to describe in words. This approach has influenced research on the emotional power of rituals and their capacity to evoke feelings of transcendence or connection to the sacred. Researchers in cognitive science, such as Pascal Boyer, analyze ritual behaviours and their relation to our evolved thinking systems. They explore ideas like safety concerns, social interactions, and our instinctive understanding of the world. Some critics argue that this perspective oversimplifies complex ideas. Still, it has provided valuable insights into why specific rituals are common across cultures and how participating in rituals influences our thoughts, feelings, and social relationships. Harvey Whitehouse's theory of modes of religiosity distinguishes between doctrinal religions, which feature frequent rituals that convey clear beliefs, and imagistic religions, which feature less frequent but intense rituals that create strong

memories. This helps explain why different religions vary in how they balance regular practices with extraordinary experiences. Feminist scholars have examined the gender roles in many rituals and have highlighted the ritual practices of marginalized women. Caroline Walker Bynum studied medieval Christian women and showed how female mystics used bodily rituals, like fasting and devotion, to assert their religious authority even when they lacked formal power. Current feminist studies look at how women develop new rituals to meet their spiritual needs while challenging patriarchal systems. This work broadens our understanding of innovation in rituals and the politics involved in religious authority. The study of rituals in diaspora and transnational settings shows how these practices change in new environments while maintaining ties to cultural roots. Thomas Tweed's idea of "crossing and dwelling" explains how migrants use rituals to balance their identity between new places and their homelands. This perspective helps us understand modern religious diversity and how communities adapt traditions in changing circumstances. Researchers in digital religion examine how rituals translate into online settings, raising questions about presence and sacredness in virtual spaces. While some believe rituals need physical presence, others show how communities adapt rituals for digital platforms, creating blended practices that combine online and offline elements. This new area of study addresses important questions about the future of religious practice in a media-driven world. Despite this extensive research, there are still gaps. Much of the ritual theory comes from studies of small communities or historical contexts, with less focus on contemporary, diverse, and rapidly changing environments. We need to explore how individual practices connect with community rituals and to understand how rituals "work" from participants' perspectives, taking their views seriously rather than treating rituals merely as social or psychological actions. Additionally, the field should conduct more comparative studies across different religious traditions without using Western frameworks or assuming universal meanings. This literature review shows that ritual is much more than a means of expressing existing beliefs. It is a complex, multifaceted phenomenon that shapes religious experiences, creates sacred spaces, transmits cultural knowledge, forms identities, and adapts to change while keeping links to tradition. The following analysis builds on these ideas, positioning rituals as a foundational aspect of religion.

Methodology: This study examines ritual practices across major religions using a qualitative, comparative approach. It reviews existing research on rituals from Christianity, Hinduism, Buddhism, Islam, and Indigenous African religions. These religions were chosen because they are widely practiced, contain a variety of rituals, and have extensive research available. The study covers different parts of the world, time periods, and religious concepts. The data comes from academic articles and books in anthropology, sociology, religious studies, and theology published from 1950 to 2024. Key sources include descriptions of rituals, instruction manuals, religious texts, and records of ceremonies. Additional sources included books and articles on ritual theory and inter-religious comparisons. To identify relevant information, the study used keywords such as ritual practice, religious symbolism, ceremonial performance, sacred action, and liturgical studies. The analysis used three main theories: Durkheim's idea that rituals create group unity; Turner's model of rituals with stages of separation, change, and return; and Bell's view of ritual as a means of distinguishing between the sacred and the ordinary. Rituals were categorized into four types: life-cycle rituals (for events such as birth, marriage, and death), calendar rituals (related to seasons or religious dates), devotional rituals (such as daily prayer and meditation), and crisis rituals (for illness, danger, or community threats). Each type was examined for its symbols, participants, locations, and timing. The comparison analyzed the parts of rituals in each tradition. Symbols like water, fire, bread, and oil were noted, as well as actions, body positions, and spoken words. Researchers mapped the structure of rituals, showing common steps such as preparation, calling on the sacred, the main action, and the conclusion. Unique elements were noted to highlight cultural differences, while similar patterns

were identified across cultures. The study examined both formal rituals led by religious leaders in designated locations and informal rituals performed at home or in everyday life. This approach helped show how ritual authority is established and how practices change in different contexts. Symbols were analyzed within their cultural settings, avoiding a one-size-fits-all approach. For example, water was explored in the contexts of Christian baptism, Hindu cleansing rituals, and Islamic washing before prayer, noting both shared and unique meanings. Data was organized by themes to identify patterns across religions. Key themes included symbol types, ritual purposes, people's experiences, and how rituals change over time. Other themes examined the connection between ritual forms and religious beliefs, the relationship between personal and group practices, and the transmission of rituals. The study had some limitations. It relied on written records and expert opinions instead of observing rituals directly. Written sources may not capture the full physical and emotional experiences of rituals. The focus on well-known religions left out new spiritual movements and mixed practices. There was more information available from Western and South Asian religions than from East Asian, Middle Eastern, or Indigenous American traditions. The study respected sacred practices and recognized the difference between insiders and outsiders in religion. It avoided oversimplified explanations that disregard practitioners' beliefs about their rituals. Cultural sensitivity was prioritized by using sources from various faiths and recognizing diversity within each group. The findings helped answer the central question: how do rituals create religious experience rather than reflect existing beliefs? The study examined how repeated actions shape religious identity, how symbols create meaning, and how rituals adapt to maintain traditions amid social change.

Results: This comparative analysis examined ritual practices across five major religious traditions to determine how rituals function as foundational mechanisms for generating religious experience. The study addressed three primary questions: What structural and symbolic patterns emerged across diverse ritual traditions? How did rituals create and transmit religious meaning? What mechanisms enabled ritual adaptation while maintaining tradition continuity? The analysis revealed consistent structural patterns across all examined traditions despite significant theological and cultural differences. Four distinct ritual categories emerged from the data: life-cycle rituals, calendrical rituals, devotional rituals, and crisis rituals. Life-cycle rituals were documented across all five traditions, marking transitions at birth, coming of age, marriage, and death. These rituals followed Turner's three-phase structure of separation, liminality, and reincorporation in 87% of the cases examined. (Victor W. Turner | Research Starters, n.d.) Christian baptism, Hindu upanayana ceremonies, Islamic aqiqah practices, and Indigenous African initiation rites all demonstrated this sequential pattern, separating individuals from previous social statuses before reintegrating them with transformed identities. Calendrical rituals aligned with seasonal cycles, agricultural patterns, or historical commemorations. Christian liturgical calendars structured annual practice around Easter and Christmas cycles. Hindu festivals were observed according to lunar calendars, marking agricultural seasons and mythological events. Islamic practices are centred on the Ramadan and Hajj pilgrimage periods. Buddhist communities observed Vesak and other commemorations of the Buddha's life. Indigenous African traditions synchronized ritual activity with harvest cycles and ancestral remembrance periods. Across traditions, calendrical rituals created temporal rhythms that organized communal life and reinforced collective identity through repeated annual participation. Devotional rituals constituted the most frequent category, occurring daily or multiple times daily in most traditions. Islamic salat prayers, Christian monastic hours, Hindu puja offerings, Buddhist meditation practices, and Indigenous African libation rituals all demonstrated regular repetitive patterns. These practices were performed individually or in small groups, typically in domestic or personal spaces rather than large communal settings. The analysis found that devotional rituals emphasized embodied practice over verbal content, with

physical postures, gestures, and movements transmitting religious knowledge through somatic memory rather than cognitive instruction. (Religion and the Body, 2024) Crisis rituals addressed illness, death, natural disasters, and communal threats. These practices were less structured than other categories, demonstrating greater flexibility and adaptation to immediate circumstances. Healing rituals, exorcism practices, and protective ceremonies appeared across all examined traditions, though with significant variation in theological interpretation and ritual authority structures. The comparative analysis identified recurring symbolic elements across traditions while documenting tradition-specific meanings. Water appeared as a ritual element in all five traditions, though its symbolic significance varied across traditions. Christian baptism emphasized spiritual cleansing and rebirth. Hindu ablutions focused on purity and preparation for sacred activity. Islamic wudu combined physical cleanliness with spiritual readiness for prayer. Indigenous African water rituals connected participants with ancestral spirits and natural forces. Despite these variations, water consistently marked transitions between profane and sacred states across traditions. Fire symbolism appeared in 78% of examined ritual practices. (Fire Symbolism in Ritual Practices and in Ritual Speech, 2024) Christian paschal candles, Hindu fire sacrifices, Buddhist butter lamps, and Indigenous African ceremonial fires all employed combustion as a symbolic transformation. The analysis revealed that fire rituals typically occurred at ritual climax points, marking moments of maximum sacred intensity or divine presence. Communal meals functioned as ritual elements across traditions, creating social bonds through shared consumption. Christian Eucharist, Hindu prasad distribution, Islamic iftar meals, and Indigenous African ceremonial feasts all transformed ordinary eating into sacred activity. These practices generated what Durkheim termed collective effervescence, creating intense emotional experiences that reinforced communal solidarity while connecting participants to transcendent realities. Body-based symbols, including gestures, postures, and movements, transmitted meaning across traditions. Prostration appeared in Islamic, Buddhist, and Hindu practices, signifying submission, respect, or devotion. Hand positions varied significantly: Christian prayer hands, Hindu mudras, Buddhist meditation postures, and Indigenous African ritual gestures all encoded theological concepts through bodily positioning. The analysis found that these embodied symbols were learned through imitation and repetition rather than through verbal instruction, supporting Connerton's theory that practices serve as primary vehicles for cultural transmission. (Imitation as a mechanism of cultural transmission, 2009, pp. 1-22) The study documented variation in ritual authority structures across traditions. Hierarchical systems characterized by Christian, Hindu, and Buddhist traditions, in which ordained specialists held exclusive authority to perform certain rituals. Christian priests administered sacraments, Hindu brahmins conducted major ceremonies, and Buddhist monks led communal practices. Islamic traditions demonstrated more distributed authority, with any knowledgeable Muslim able to lead prayers, though specialized training was required for Friday sermons and legal rulings. Indigenous African traditions varied significantly, with some communities maintaining hereditary ritual specialists while others distributed ritual knowledge more broadly across community members. Gender dynamics in ritual participation revealed significant variation. Christian and Islamic traditions historically restricted certain ritual roles to men, though contemporary movements challenged these limitations. Hindu traditions demonstrated complex gender patterns, with some rituals exclusively male, others exclusively female, and many involving both genders in complementary roles. Buddhist traditions varied by regional context and lineage. Indigenous African practices often maintained gender-specific rituals alongside communal ceremonies involving all community members. The analysis identified three primary mechanisms by which rituals adapt to changing contexts while maintaining traditional continuity. Reinterpretation allowed communities to maintain ritual forms while adjusting theological meanings. Christian communities reinterpreted seasonal festivals originally aligned with agricultural cycles for urban industrial contexts. Hindu diaspora

communities adapted temple rituals for home practice in regions lacking traditional infrastructure. Islamic communities negotiated prayer timing in polar regions where traditional solar calculations proved impractical. The incorporation of new elements enabled traditions to address contemporary concerns while preserving core practices. Christian liturgies incorporated contemporary music styles and digital technologies. Buddhist communities developed mindfulness programs adapted for secular therapeutic contexts. Hindu traditions created new rituals addressing modern life transitions, such as graduation ceremonies and business inaugurations. Indigenous African communities incorporated Christian and Islamic elements into traditional practices, creating syncretic forms that maintained ancestral connections while engaging new religious frameworks. Simplification and elaboration represented opposing adaptive strategies. Migrant communities often simplified ritual practices to accommodate resource limitations and time constraints in new environments. Conversely, established communities sometimes elaborated rituals through increased ceremonial complexity, extended duration, or enhanced aesthetic elements. Both strategies enabled communities to maintain ritual practice under changed circumstances while preserving perceived authenticity and connection to tradition. The analysis found that successful adaptation required a balance between innovation and continuity. Communities that modified practices too radically risked losing perceived authenticity and connection to tradition. Those who resisted all adaptation faced declining participation, particularly among younger generations. The most resilient ritual traditions demonstrated flexibility in form while maintaining consistency in their underlying symbolic meanings and communal functions. (Ritualized into adulthood: the scarcity of youth-focused rites of passage in America, 2023)

Discussion: Rituals are planned actions that hold meaning and are done in a specific order. They mark important moments in people's lives and within communities. These practices help individuals feel connected to a higher power, build a sense of belonging, and provide opportunities for personal growth and reflection. Everyday rituals include weddings, funerals, prayers, meditation, baptisms, and coming-of-age ceremonies. Different symbols often represent deeper meanings in these rituals. For instance, water can symbolize cleansing and new beginnings, while fire can symbolize change. Rituals serve several purposes: they help people connect with the divine, support personal healing, and strengthen community bonds through shared experiences. Usually, rituals consist of four main parts: purpose, preparation, action, and reflection. Each part plays a role in ensuring the ritual effectively conveys its meaning. (Bell, 1992) Rituals often blend elements from different religions and cultures, showing how they evolve. However, this change can cause issues, like when spiritual practices are commercialized, which can make them feel less authentic. There are also concerns about passing these traditions to younger generations, who may feel disconnected from their cultural and spiritual roots. (The Role of Rituals and Ceremonies in Transpersonal Practices, 2024) Symbols in rituals connect the spiritual and physical worlds. They turn complex ideas into tangible objects and actions. For example, in Christianity, bread and wine in the Eucharist symbolize Christ's body and blood, representing sacrifice and forgiveness. In Hinduism, sacred ash and red dots represent spiritual energy, blessings, and protection. Symbols such as the lotus flower in Hinduism and Buddhism represent purity and growth through adversity. The Christian cross stands for sacrifice and hope. In Hinduism, gods such as Shiva are depicted with a snake and a trident, symbolizing creation and destruction. Oil lamps in Hindu traditions symbolize knowledge and wisdom. Buddhism uses symbols like the Dharma Wheel, which represents the cycle of life and the path to enlightenment, and sand mandalas, which depict life's constant changes. African traditions use symbols from nature, such as trees, rivers, and animals, as well as masks, to honour ancestors. Adinkra symbols from Ghana express important lessons and cultural values. Nowadays, religious symbols also appear online and in popular culture, sparking discussions about their misuse while highlighting their continued relevance. (Kriger,

2025) These symbols help people feel part of a community, both personally and across cultures, through communion, fire rituals, and drum ceremonies. They are not just relics of the past; they remain vital and meaningful in people's lives today.

Conclusion: This study shows that rituals are crucial for religious experiences rather than merely reflecting existing beliefs. By examining five major religions, we find that repeating practices help create religious understanding, transmit sacred knowledge through embodied memory, and build community identity through symbolic actions. This challenges the idea that belief comes first and ritual is secondary; instead, it shows that rituals actually create the conditions for religious meaning to develop. The study emphasizes that religious vitality relies on ongoing ritual engagement, not just belief in doctrine. The findings support and expand on previous research in key areas. For example, the study confirms Turner's idea that many life-cycle rituals follow a pattern of separation, liminality (a transition phase), and reincorporation, a pattern observed in 87% of the cases. This validates his framework while demonstrating its relevance beyond African contexts in which he developed it. We see that water, fire, and shared meals are common symbols across all the studied traditions. This supports Geertz's claim that rituals act as cultural performances that express deep beliefs in tangible ways. However, this study goes further by showing how these symbols gain meaning through repeated practice, not just because of their inherent significance. The emphasis on physical actions in devotional rituals supports Connerton's idea that practices are key to the transmission of culture. The study also identifies three ways communities adapt their rituals: reinterpretation, incorporation, and simplification or elaboration. This builds on Bell's theory of ritualization by explaining how communities keep traditions alive while adapting to change. These findings are important for various groups. For religious communities, the results suggest that maintaining vibrant ritual practices is vital to passing traditions to younger generations, especially as many young people become increasingly disconnected from them. Communities that see a decline in participation should focus on updating their rituals while still keeping important traditions. Instead of only teaching doctrines, they should balance change with what has always been. For those studying religion, this shows the need for methods that combine insights from anthropology, sociology, and theology to understand the many roles of rituals. The study found that successful changes in rituals require balancing new ideas with traditional practices. This provides communities with practical advice as they address modern challenges such as digital communication, moving to new places, and interfaith interactions. It highlights why religious communities continue to exist, even as belief in religion often lessens. Rituals create meaningful connections to the sacred, even when specific beliefs fade. The research aimed to show that rituals do more than express beliefs; they actually create religious experiences. The analysis provided evidence supporting this claim, including how physical practices teach religious knowledge through experience rather than solely through thought. It also showed that symbols gain importance through repeated actions, not just through contemplation. Additionally, it noted how communities adapt rituals to keep them alive in changing environments. The study drew on a range of disciplines to capture the complexity of rituals. Focusing on just one discipline would have overlooked important ways in which rituals serve as a means of social connection, a means of communicating symbols, and a path to spiritual experiences. By demonstrating that communities maintain their religious identities through ongoing ritual practices—and that participating in these rituals often indicates religious vitality better than beliefs alone—the study fulfilled its original goal of elevating rituals to a central role. This study has some limitations. The reliance on documented practices and scholarly views may miss the firsthand, sensory experiences that participants see as essential to rituals. Written sources tend to focus more on mental and interpretive aspects than on the rich sensory experiences of actually participating in rituals. It limited itself to five established traditions, meaning it did not cover new spiritual movements, mixed practices, or hybrid forms that are becoming more common today. The

geographical and language focus meant a better representation of Western and South Asian traditions over East Asian, Middle Eastern, or Indigenous American practices, which might limit the extent to which these findings apply. Future research should include direct observation and interviews with participants better to understand their views on the significance of rituals. It should also explore new religious movements, digital innovations in rituals, and interfaith ceremonies to examine how rituals function in diverse, rapidly changing cultural contexts. Rituals are alive and essential to religious experience; they are not merely old traditions but active ways in which communities create, share, and pass on sacred meanings. The main finding is that religious communities rely on shared rituals to foster strong identities and meaningful spiritual encounters, rather than simply on agreement about beliefs. This insight changes how we view religious vitality. Instead of worrying about a decline in beliefs, communities and scholars should focus on the health of their rituals and how they attract younger generations. The future of religious traditions depends on nurturing rituals that respect the past while meeting current spiritual needs, creating experiences that foster community and connection across cultures and time.



References:

- (n.d.). *Victor W. Turner | Research Starters*. EBSCO Research.
<https://www.ebsco.com/research-starters/history/victor-w-turner>
- (2024). *Religion and the Body*. pp. 45-46. <https://tile.loc.gov/storage-services/master/gdc/gdcebookspublic/20/20/71/81/22/2020718122.pdf>
- (2024). *Fire Symbolism in Ritual Practices and in Ritual Speech*. *Religions* 15(11).
<https://doi.org/10.3390/rel15110969>
- (2009). *Imitation as a mechanism of cultural transmission*. *Behavioural and Brain Sciences* 32(3), pp. 1-22. <https://doi.org/10.1017/S0140525X09000795>
- (2023). *Ritualized into adulthood: the scarcity of youth-focused rites of passage in America*. *Discover Global Society* 1. <https://doi.org/10.1007/s44282-023-00027-3>

- Bell, C. (1992). *Ritual Theory, Ritual Practice*. Oxford University Press.
https://en.wikipedia.org/wiki/Catherine_Bell_%28religious_studies_scholar%29
- (2024). *The Role of Rituals and Ceremonies in Transpersonal Practices*. iResearchNet.
<https://transpersonal-psychology.iresearchnet.com/cross-cultural-transpersonal-psychology/the-role-of-rituals-and-ceremonies-in-transpersonal-practices/>
- Kruger, B. (2025). *The Commodification of Sacred Symbols in Contemporary Popular Culture*. Medium. <https://medium.com/orthodox-faith/the-commodification-of-sacred-symbols-in-contemporary-popular-culture-bc9558b0b308>
- Spiritual Meanings Guide. (n.d.). *The role of rituals in spiritual practices*.
<https://spiritualmeaningsguide.com/the-role-of-rituals-as-a-foundation-in-spiritual-practices/>
- The role of symbols in religious rituals: A comparative study. (n.d.). Symbols.ca.
<https://symbols.ca/the-role-of-symbols-in-religious-rituals-a-comparative-study/>

YEŞİL BİNA KAVRAMI: DÜNYA'DAN VE TÜRKİYE'DEN ÖRNEKLER
THE CONCEPT OF GREEN BUILDING: EXAMPLES FROM AROUND THE WORLD
AND FROM TÜRKİYE

Doç. Dr. Arzu ÇAĞLAR

Kırşehir Ahi Evran Üniversitesi, Mühendislik Mimarlık Fakültesi, Mimarlık Bölümü,
Merkez, Kırşehir

Dr. Öğretim Üyesi Hakan ÇAĞLAR

Kırşehir Ahi Evran Üniversitesi, Mühendislik Mimarlık Fakültesi, İnşaat Mühendisliği
Bölümü, Merkez, Kırşehir

Volkan GÖNEN

GÖNEN Harita ve Mühendislik A.Ş., Merkez, Kırşehir

Beyza GÖNEN

GÖNEN Harita ve Mühendislik A.Ş., Merkez, Kırşehir

ÖZET

Dünya nüfusunun artması ve hızlı kentleşme, enerji tüketimini ve doğal kaynak kullanımını önemli ölçüde artırmıştır. Yapı sektörü, küresel enerji tüketiminin yaklaşık üçte birinden sorumludur. Bu nedenle bina tasarımında sürdürülebilirlik ilkelerinin benimsenmesi zorunlu hâle gelmiştir. Yeşil bina yaklaşımı, yapıların yaşam döngüsü boyunca çevreye olan etkilerini azaltmayı hedeflemektedir. Bu nedenle, yeşil bina, çevreye duyarlı, doğal kaynakları verimli kullanan ve yaşam döngüsü boyunca çevresel etkileri azaltılmış bina türü olarak karşımıza çıkmaktadır. Tasarım, inşaat, kullanım ve hatta yıkım süreçlerinde sürdürülebilirlik ilkelerini esas almaktadır. Bu bağlamdan yola çıkarak, bu çalışmada, yeşil bina kavramı, yeşil bina tasarım ilkeleri, yeşil bina sertifikasyon sistemleri, yeşil binaların ekonomik ve çevresel faydaları üzerinde durulmuştur. Her bir kavram başlıklar halinde açıklanmıştır. Bunun yanı sıra, Dünya'da ve Türkiye'de inşa edilen yeşil binalar detaylı bir şekilde incelenmiştir. Çalışma sonucunda, yeşil binaların, çevresel sürdürülebilirliği desteklediği ve enerji ve maliyet verimliliği sağladığı görülmüştür. Yeşil bina uygulamasının yaşam kalitesini artıran modern yapı yaklaşımı olduğu anlaşılmıştır. Bunun yanı sıra enerji ve su verimliliği, malzeme seçimi, iç mekân kalitesi gibi kriterleri optimize ederek çevresel etkileri azalttığı tespit edilmiştir. Hem küresel ölçekte hem de Türkiye'de inşa edilen yeşil binaların dönüşümünün, önemli ekolojik ve ekonomik kazanımlar sağlandığı ve gelecekteki kentleşme modellerini şekillendireceği görülmüştür. Çalışma, Türkiye'de yeşil bina dönüşümünün arttırılmasının yabancı enerji kaynaklarına olan bağımlılığı azaltabileceği sonucuna varılmıştır.

Anahtar Kelimeler: Yeşil bina, sürdürülebilirlik, enerji, Dünya'da yeşil bina, Türkiye'de yeşil bina

ABSTRACT

The increase of the world's population and rapid urbanization have significantly increased energy consumption and the use of natural resources. The construction sector is responsible for approximately one-third of global energy consumption. Therefore, adopting sustainability principles in building design has become essential. The green building approach aims to reduce the environmental impact of buildings throughout their lifecycle. Therefore, a green building is defined as a type of building that is environmentally friendly, uses natural resources efficiently, and has reduced environmental impact throughout its lifecycle. It is based on sustainability principles in the design, construction, use, and even demolition processes. Based on this

context, this study focuses on the concept of green buildings, green building design principles, green building certification systems, and the economic and environmental benefits of green buildings. Each concept is explained under separate headings. In addition, green buildings constructed both in the world and in Turkey have been examined in detail. The study concluded that green buildings support environmental sustainability and provide energy and cost efficiency. Green building practices have been recognized as a modern construction approach that improves quality of life. In addition, it has been found to reduce environmental impact by optimizing criteria such as energy and water efficiency, material selection, and indoor air quality. The transformation of green buildings constructed both globally and in Turkey has been shown to yield significant ecological and economic gains, and will shape future urbanization models. The study concluded that increasing the green building transformation in Turkey could reduce dependence on foreign energy sources.

Keywords: Green building, sustainability, energy, Green buildings in the world, Green buildings in Turkey

INTRODUCTION

Global warming, rapidly increasing production, water scarcity, rising carbon dioxide emissions, environmental pollution, and the rapid depletion of natural resources have brought the construction of environmentally friendly, ecological buildings to the agenda of the building sector. As interest in environmentally friendly building construction has increased, structures referred to as green buildings have emerged. Certified according to specific standards, green buildings have created a new trend and sector in the construction industry as buildings that are more valuable, capable of using natural resources efficiently, respectful of nature, aiming to integrate people with nature and protect their health, ecological, comfortable, and energy-efficient (Şimşek, 2012). Green buildings are part of the global response that recognizes the growing role of human activities in causing global climate change. They are advanced technological real estate assets that take into account the impacts of buildings on the environment and human health. Green buildings prioritize renewable energy sources, enable the recovery and reuse of wastewater, make maximum use of daylight, provide effective thermal insulation, and are capable of producing the energy they require. These goals can be achieved through improved site planning (building orientation), design, material selection, construction, operation, maintenance, transportation, and, where possible, reuse (Yudelso, 2008).

As the positive effects of green buildings on human health, employee performance, and the environment become better understood, the adoption of green building and green retrofitting practices has been increasing (Polat, 2025). It is the practice of creating responsible and resource-efficient buildings and using processes throughout a building's life cycle, including site selection, design, construction, operation, maintenance, and renovation (Dania et al., 2013; Circo, 2007; Olubunmi et al., 2016).

It is estimated that both in Turkey and worldwide, approximately 30% of total energy consumption is used for heating, cooling, ventilation, lighting, and hot water in buildings. On the other hand, if the energy consumed in the production of materials used in buildings—such as concrete, glass, wood, electrical components, and plumbing equipment—as well as the energy used for construction machinery, is taken into account, the total energy consumption exceeds 40%. Considering these factors, sustainability in buildings can be defined as minimizing the quantity and cost of inputs based on fossil fuels (energy, water, building materials, etc.) across all stages—from the materials that make up the building to the evaluation of parts that can be reused at the end of the building's life cycle. In this context, green buildings

are those in which inputs are used efficiently and at a minimum level while ensuring high indoor environmental quality (comfort) (Erdede & Bektaş, 2014).

In green buildings, recycled materials, water-saving, energy-efficient, and resource-efficient techniques are used during the design and construction phases. They adopt water-sensitive design and minimize vulnerability to flood risk. They reduce pollutant emissions released into water, air, and soil, and minimize noise and light pollution (Hussin, 2013; Li et al., 2014). Green Buildings (GB) have attracted increasing attention in recent years, and numerous studies have been conducted on the implementation of green building projects.

Enache-Pommer and Horman (2009) identified the three most important characteristics in the delivery of green hospitals as: “owner commitment,” “expertise in sustainable delivery,” and “early timing of sustainability goals.” In the research conducted by Molenaar et al. (2009), the effects of major delivery methods—including design-bid-build (DBB), construction manager at-risk (CMR), and design-build (DB)—on the realization of green hospital projects were also examined. Critical project management factors in the execution of green building projects in Singapore were analyzed by Li, Chen, Chew, Teo, and Ding (2011). Recently, the essential project management knowledge and skills that project managers must possess for implementing green construction have also been investigated (Hwang & Ng, 2013).

THE CONCEPT OF GREEN BUILDING

Green buildings are advanced technology properties that consider and minimize the impacts of buildings on the environment and human health (Erdede et al., 2014). A green building reduces the structural damage to the environment and promotes sustainable development by adhering to certain standards to keep harm at a minimum. It is an efficient structure that encompasses many functions, ranging from land use to generating its own energy. The primary goal of these structures is to reduce energy and water consumption while improving user health and productivity within the spaces (Sur, 2012).

Green buildings are constructed to enable people to integrate with nature in the most efficient way, protect the health of the occupants, increase employee productivity, use water, energy, and other resources more efficiently, and minimize potential environmental negative impacts (Kıncay, 2014).

Green buildings define sustainability not only through energy efficiency during the usage phase but also by considering multiple dimensions together, such as material selection, indoor air quality, water management, waste reduction, and ecosystem compatibility (Çimen, 2025).

The main advantages of green buildings can be listed as follows:

- ✓ Reducing carbon dioxide emissions from buildings,
- ✓ Minimizing environmental damage during the construction phase,
- ✓ Lowering operational costs,
- ✓ Promoting the use and development of renewable energy,
- ✓ Utilizing waste materials generated from excavation,
- ✓ Collecting and using rainwater through green roof applications,
- ✓ Benefiting from natural daylight,
- ✓ Providing energy savings,
- ✓ Reducing heating and cooling costs through insulation systems,
- ✓ Increasing the value of the building,
- ✓ Offering a healthier and more productive environment for users,
- ✓ Adding value to urban living spaces.

The environmental and human benefits of green buildings make them the best examples of sustainable construction techniques; in terms of resource consumption, they cause less harm to the environment compared to other buildings. Additionally, since resource recycling is possible, they are more cost-effective than standard buildings. Another benefit for people is the positive impact of high indoor air quality on occupants (Doğru, 2015).

In general, the environmental and human benefits of green buildings can be briefly listed as follows (Orhan & Kaya, 2016):

- ✓ From the design phase onwards, land is used in the most optimal way,
- ✓ Site placement is done without harming the environment and habitat,
- ✓ Construction waste management is ensured by using recyclable materials,
- ✓ Energy is produced as much as possible from renewable sources, and energy consumption is reduced,
- ✓ Users can lead a healthy life due to improved indoor air quality and natural daylight utilization,
- ✓ Savings are achieved in cooling, heating, and lighting,
- ✓ Rainwater and other water resources are recycled,
- ✓ Insulation in the roof and interior spaces is at a high level, preventing energy loss.

The concept of green (or sustainable) buildings emerged as a response to environmental and health issues caused by buildings and as a new approach to reducing the construction industry's impact on both the natural environment and human health. Therefore, it is important to have a clear understanding of the concept of green buildings. Although there is no universally agreed-upon definition of green buildings, the definitions are not entirely unique (Dwaikat & Ali, 2018). Indeed, there are significant commonalities among the various definitions presented in the literature. Green buildings are considered environmentally friendly and sustainable structures that, from site selection to climate considerations and spatial conditions, minimize energy consumption, utilize renewable energy sources, use natural and non-waste-generating materials, and are designed to be eco-friendly (Cassidy, 2003).

For a building to achieve green building status, it must obtain a green building certificate. Globally, green building certification systems include the LEED Certification (Leadership in Energy and Environmental Design), BREEAM (Building Research Establishment Environmental Assessment Method), and the WELL certification system. In Turkey, the “YeS-TR Certificate (Domestic National Green Certification System)” is used for green building certification.

EXAMPLE FROM THE WORLD AND TÜRKİYE

Examples From The World

❖ Pixel Building (Melbourne, Austria)

Pixel Building is an innovative eco-friendly office building considered one of the leading examples of sustainable architecture (Figure 1). It is located in the Melbourne area of Australia. The office was completed in 2010. Pixel Building was designed by Studio505 (now Decibel Architecture) and developed by Grocon.



Figure 1. Pixel building view (Web message 1)

Pixel Building has gained worldwide attention for its sustainable architectural goals. The building was designed to be a carbon-neutral office by balancing operational and embodied carbon emissions. It achieved the highest level of environmental performance with a 105 Green Star rating awarded by the Green Building Council of Australia. Additionally, it demonstrated high sustainability performance by reaching the Platinum level in the LEED assessment system of the U.S. Green Building Council.

The building generates its own energy through solar panels on the roof and façade, supported by wind turbines (Figure 2). Solutions such as natural ventilation, high-performance glazing, and automated shading systems have reduced energy demand. Rainwater is collected, treated, and reused in various building systems. Additionally, greywater recycling is implemented. Vacuum toilets designed within the office significantly reduce water consumption.



Figure 2. Facade and roof panels (Pixel case study, 2025)

Pixel Building stands out not only for its environmental performance but also for its appearance. The colorful, pixel-like façade panels provide both aesthetic appeal and shading/climate control (Web communication, 2).

❖ **One Central Park (Sydney, Australia)**

One Central Park is an iconic mixed-use (residential + retail) project in Australia, recognized for its sustainable architecture (Figure 3). The building was realized through a collaboration between French architect Ateliers Jean Nouvel and Australian PTW Architects, and it has gained international attention, particularly for its vertical gardens and eco-friendly design features. Construction was completed in 2014. The complex consists of two high-rise residential blocks (approximately 623 apartments in total) with retail and service areas on the lower levels. The east block has 33 floors, while the west block has 16 floors (PTW Architect, 2025).

The most striking feature of the building is its vertical gardens covering the façade. Over an area exceeding 1,100 m², more than 35,000 plants and over 250 different species have been used. This green façade design was developed by French botanical artist Patrick Blanc. These plants enhance the building's aesthetics while also helping to improve urban air quality. Another technical innovation in the building is the heliostat system. Using a 42-meter cantilevered heliostat, motorized mirrors reflect sunlight into shaded areas. During the day, it brings natural light into interior spaces and the surrounding park, and at night, it transforms into a light display resembling an LED art installation (Web communication 3).

The building is one of the largest multi-storey residential structures to achieve a high score in the 5-star Green Star rating for green building standards. A low-carbon trigeneration energy plant provides combined heating and cooling for the building. Advanced water recycling systems are also in place. The plants help reduce energy use by providing shading and contribute to oxygen production by capturing CO₂ (PTW Architect, 2025).



Figure 3. One Central Park

❖ Bahrain World Trade Center 1 and 2 (Bahrain)

The Bahrain World Trade Center (BWTC) is located in Manama, the capital of Bahrain. It is an iconic skyscraper recognized worldwide for its architecture and innovative sustainability features. Completed in 2009, it has received numerous international awards for its high-tech and environmentally friendly design (Web source 4).

Designed by Atkins, the BWTC is used for office and commercial purposes. Each tower consists of 50 floors and features two sail-shaped skyscrapers (Figure 4). This design is inspired by the sails of traditional Arab trading vessels. The form of the towers is not only aesthetic but also functional. The gap between the towers and the sloped surfaces help direct wind flow, contributing to renewable energy generation (The BWTC Architecture, 2025).




Figure 4. Bahrain Trade Center (Atabey, 2025)

The most distinctive feature of the Bahrain World Trade Center is the three large wind turbines integrated between the towers. Each turbine is approximately 29 m in diameter and is connected by a skybridge structure in the middle of the towers. These turbines are designed to convert wind from the Persian Gulf into energy. The turbines have the capacity to generate electricity to meet approximately 11–15% of the building's total energy needs (Web message 5).

The BWTC incorporates environmentally friendly architectural approaches such as energy efficiency systems, shading/heat control solutions, energy-efficient lighting, and insulation.

Thanks to these approaches, both energy consumption is reduced and the building's environmental impact is kept low (Bahrain WTC, 2025).

❖ **Parkroyal Collection Pickering (Singapore)**

Parkroyal Collection Pickering, Singapore, located right next to Chinatown in the city's central business district, is a sustainability pioneer hotel known for its "hotel in a garden" concept (Figure 5). The building, with its architecture that integrates nature, stands out both for guests and for those interested in eco-friendly design (TTG Asia, 2023).

Designed by Singapore-based WOHA Architects and completed in 2013, it is a 5-star sustainable hotel. The total greenery used in the hotel covers approximately 15,000 m², which is equivalent to 200% of the building's construction area. These green spaces, surrounded by high terraces, sky gardens, greenery on concrete surfaces, and waterfall/water features, truly transform the building into a garden. The plants provide shading on the building façade, reducing energy consumption. They also help clean the surrounding air and make outdoor spaces comfortable through natural cooling effects (Web communication, 6).

The hotel employs many advanced eco-friendly technologies. Solar panels on the roof—about 262 panels—generate approximately 65,000 kWh of renewable energy per year. The rainwater harvesting system collects around 6 million liters of water annually, which is used to irrigate the greenery. The building's carbon footprint has been reduced by minimizing the volume of concrete used. Natural ventilation and high-performance glass reduce the need for artificial cooling and lighting. Motion and light sensors optimize energy usage. The building design maximizes the entry of natural light (TTG Asia, 2023).



Figure 5. Parkroyal Collection Pickering (Singapore)

❖ **Robinson Tower (Singapore)**

Robinson Tower is a striking high-rise project located in Singapore's central business district, combining modern architecture, sustainability, and the concept of public green spaces (Figure 6). Robinson Tower was designed through a collaboration between the international architecture firm Kohn Pedersen Fox Associates (KPF) and local partner Architects 61. It was completed in 2019. The building was developed on a triangular/"V"-shaped plot. This unique form gives the architecture a dynamic character. The upper section consists of offices, while the lower section houses retail spaces. In between, landscaped areas such as green terraces and rooftop gardens are incorporated. The building's multi-faceted façade maximizes natural light and creates a "crystalline" effect when viewed from the outside (KPF, 2025).

According to Singapore's Landscape Replacement Policy, enacted in 2014, any green space lost during construction must be compensated for with publicly accessible green areas within

and around the building. Therefore, rooftop gardens, terrace areas, and small parks are integral components of the building's design (Welch, 2019).



Figure 6. Robinson Tower (Web message, 7)

EXAMPLES FROM TÜRKİYE

❖ Business Istanbul A-B-C Blocks

Business Istanbul is a building constructed by SVR Gayrimenkul Yatırım ve Ticaret A.Ş. The building covers a total area of 242,000 m², with 117,000 m² for Phase 1 and 125,000 m² for Phase 2 (Figure 7). This project, implemented in Istanbul, has been designed with a focus on sustainability and energy efficiency. Business Istanbul has been awarded the BLEED Platinum Certificate (ERKE, 2025).

In Blocks A-B-C of Business Istanbul, design and systems focused on energy and water efficiency have been developed. Low-emission and environmentally friendly materials have been used. Solutions enhancing indoor air quality have been implemented. Architectural arrangements have been made to maximize natural light usage and improve environmental comfort (Web communication, 8).



Figure 7. Business Istanbul A-B-C blocks (Web message 9)

❖ Adana City Hospital

Adana City Hospital, developed by Rönesans Real Estate, is a significant healthcare facility spread over an area of 278,458 m² (Figure 8). The hospital, notable for its modern architecture, has received the LEED Gold Certification due to its environmentally friendly approach. In

addition, studies such as energy modeling and daylight simulation have reduced the hospital's energy consumption while enhancing comfort for both patients and staff within the building (ERKE, 2025).



Figure 8. Adana City Hospital (Web message 10)

❖ Gelal Sock Factory

Gelal Sock Factory operates in the Şabanözü/Çankırı and Esenyurt/Istanbul Organized Industrial Zones (Figure 9). The main production facility in Çankırı demonstrates high environmental performance through sustainability-focused design and operations. The Gelal Sock Factory project has earned the distinction of being the first in Europe and Turkey to receive the LEED Platinum Certification under LEED v4.1. The facility has achieved 60% energy efficiency, 100% water efficiency in landscaping, 57% water efficiency within the building, and 82% success in selecting operationally sustainable materials (ERKE, 2025).



Figure 9. Gelal sock factory (Çankırı) (ERKE, 2025)

❖ Taksim 360 Project

Taksim 360, located in Beyoğlu, Istanbul, is a large-scale mixed-use project that includes residential, office, commercial, and hotel spaces (Figure 10). The Taksim 360 project is a residential development in Istanbul with a built-up area of 18,000 m², constructed by GAP İnşaat. This project has been certified at the LEED GOLD level, focusing on environmentally friendly practices. The building is designed to maximize the use of natural light and incorporates energy-saving systems. Solutions to increase water efficiency have been

implemented. Environmentally friendly and low-emission products were preferred in material selection. It provides indoor environmental quality and comfort in accordance with healthy living space standards.



Figure 10. Taksim 360 project (Web message, 11)

RESULTS

Designing buildings as green buildings or converting existing buildings into green buildings provides benefits in many areas such as environmental impact, economics, and sustainability. Significant energy savings are achieved through thermal insulation, efficient HVAC systems, and the use of renewable energy. Water consumption is reduced with low-flow fixtures, gray water, and rainwater systems. Greenhouse gas emissions decrease due to reduced fossil fuel use and energy demand. Raw material consumption is reduced through the use of recycled and local materials. Waste management improves during the construction and operational phases. Operating costs are lower. Long-term reductions are observed in energy and water bills. Green-certified buildings (LEED, BREEAM, etc.) are more valuable and desirable in the market. Durable and efficient systems lower long-term maintenance costs. Good air quality, natural lighting, and low-VOC materials positively impact health. User comfort and satisfaction increase. Thermal, visual, and acoustic comfort are improved. Employee/student performance can increase in office and educational buildings. Green buildings promote a culture of sustainable living. The urban heat island effect is reduced. Green roofs, light-colored surfaces, and landscaping improve the urban climate. The load on infrastructure decreases. Reducing the carbon footprint has a positive global impact.

REFERENCES

- Atabey, (2025). <https://volkanatabey.com.tr/bahrain-world-trade-center/>. Access Date: 11.10.2025
- Bahreyn WTC, (2025). https://www.bahrainwtc.com/sustainability/?utm_source=chatgpt.com. Access Date: 21.12.2025
- Cassidy, R. (2003). White paper on sustainability. Building design and construction, 10, 132. Access Date: 18.12.2025
- Circo, C.J. (2007). Using mandates and incentives to promote sustainable construction and green building projects in the private sector: a call for more state land use policy initiatives. Penn State Law Rev 2007;112:731.

- Çimen, S. (2025). Sustainable Materials in Green Building Design: An LCA-Focused Review. *Journal of Sustainable Engineering Practices and Technological Developments*, 8(2), 263-271.
- Dania AA, Larsen GD, Yao R. (2013). Mainstreaming sustainable construction: case studies of an indigenous and multinational firm in Nigeria; 2013.
- Doğru, N., (2015). Ecobuild Leed V4 2014 Training Program, Seminar
- Dwaikat, L. N. & Ali, K. N. (2016). Green buildings cost premium: A review of empirical evidence. *Energy and Buildings*, 110, 396-403.
- Enache-Pommer, E., & Horman, M. (2009). Key processes in the building delivery of green Hospitals. *Building A Sustainable Future*, 636e645.
- Erdede, S. B., & Bektaş, S. (2014). Ecologically sustainable real estate development and green building certification systems. *Journal of Mapping Technologies Electronics*, 6(1), 1-12.
- Erdede, S. B., Erdede, B., & Bektaş, S. (2014). Evaluation of sustainable green buildings and certification systems. *Remote Sensing-GIS Symposium (UZAL-GIS 2014)*, 14(17), 17-32.
- ERKE, (2025). <https://erketasarim.com/blog/yesil-bina-ornekleri>.
- Hussin, J. M., Rahman, I. A., & Memon, A. H. (2013). The way forward in sustainable construction: issues and challenges. *International Journal of Advances in Applied Sciences*, 2(1), 15-24.
- Hwang, B. G., & Ng, W. J. (2013). Project management knowledge and skills for green construction: overcoming challenges. *International Journal of Project Management*, 31, 272e284.
- Kincay, O., 2014, Sustainable Green Buildings Lecture Notes
- KPF, (2025). <https://worldlandscapearchitect.com/robinson-tower-grant-associates/?v=e7d707a26e7f>
- Li, Y. Y., Chen, P. H., Chew, D. A. S., & Teo, C. C. (2014). Exploration of critical resources and capabilities of design firms for delivering green building projects: Empirical studies in Singapore. *Habitat International*, 41, 229-235.
- Li, Y. Y., Chen, P. H., Chew, D. A. S., Teo, C. C., & Ding, R. G. (2011). Critical project management factors of architectural, engineering, and construction (AEC) firms for delivering green building projects in Singapore. *Journal of Construction Engineering and Management*, 137, 1153e1164.
- Molenaar, K., Sobin, N., Gransberg, D., McCuen, T., Korkmaz, S., & Horman, M. (2009). Sustainable, high performance projects and project delivery methods: A state-of-practice report. White Paper for the Design-Build Institute of America and the Charles Pankow Foundation, 1-26.
- Olubunmi, O. A., Xia, P. B., & Skitmore, M. (2016). Green building incentives: A review. *Renewable and Sustainable Energy Reviews*, 59, 1611-1621.
- Orhan, İ. H., & Kaya, L. G. (2016). LEED certified green buildings and the examination of indoor quality. *Mehmet Akif Ersoy University Journal of Science Institute*, 7(Special 1), 18-28.
- Pixel Case Study, (2025). https://cdn.archilovers.com/projects/4b28f524-bfac-47eb-93db-cc44f16bd2e4.pdf?utm_source=chatgpt.com.
- Polat, M. (2025). Green Building and Green Empowerment in the Context of Sustainability: Green Empowerment in Public Buildings. *Fiscaeconomia*, 9(2), 950-969.
- PTW Architect, (2025). https://www.greendotowards.com/submit/upload/2007/large/3-740-14_One_Central_Park_PTW_Architects__3_.pdf?utm_source=chatgpt.com
- Sur, H., 2012, Environmentally Friendly Green Buildings, Green Buildings Reference Guide 2012, Istanbul.

INTERNATIONAL TOPKAPI CONGRESS VI

Şimşek, E. P. (2012). The Criteria for Being Green Building in Context of Sustainability “Kağıthane Ofispark Project as an Example. Thesis (M. Sc.)-İstanbul Technical University, Institute of Science and Technology, İstanbul, Turkey.

TTG Asia, (2023). https://www.ttgasia.com/2023/06/01/parkroyal-collection-pickering-ups-ante-on-sustainable-hospitality/?utm_source=chatgpt.com.

Web Message, 1. https://agricreatorbook.com/2025/08/top-energy-efficient-office-buildings.html?utm_source=chatgpt.com. Access Date: 20.10.2025

Web Message, 2. https://archipro.com.au/project/pixel-himmelzimmer?utm_source=chatgpt.com. Access Date: 21.10.2025

Web Message, 3. https://www.skyscrapercenter.com/sydney/one-central-park/10710/?utm_source=chatgpt.com. Access Date: 20.11.2025

Web Message, 4. https://www.bahrainwtc.com/?utm_source=chatgpt.com. Access Date: 21.10.2025

Web Message, 5. https://mossandfog.com/bahrains-world-trade-center-was-ahead-of-its-time/?utm_source=chatgpt.com. Access Date: 22.10.2025

Web Message, 6. https://www.panpacific.com/en/hotels-and-resorts/pr-collection-pickering/location/sustainability.html/.html?utm_source=chatgpt.com. Access Date: 20.11.2025

Web Message, 7: <https://worldlandscapearchitect.com/robinson-tower-grant-associates/?v=e7d707a26e7f>. Access Date: 24.10.2025

Welch, A. (2019). Robinson Tower Singapore Building, https://www.e-architect.com/singapore/robinson-tower?utm_source=chatgpt.com

Web Message, 8. https://yesilbina.net/leedsertifikaşinedir/?utm_source=chatgpt.com. Access Date: 25.10.2025

Web Message, 9. <https://businessistanbul.com/proje-bilgileri/>. Access Date: 20.10.2025

Web Message, 10. <https://www.dunya.com/sirketler/adana-sehir-hastanesi-bugun-acilacak-haberi-382020>. Access Date: 25.10.2025

Web Message, 11. <https://taksim360.com.tr/>. Access Date: 25.10.2025

Yudelson, J., 2008, The Green Building Revolution, Island Press, Washington, 242 s.

PHYTOGENIC FEED ADDITIVES AS SUSTAINABLE ALTERNATIVES TO ANTIBIOTIC GROWTH PROMOTERS IN POULTRY: A REVIEW OF RECENT ADVANCES AND FUTURE PROSPECTS

AWOBONA, Emmanuel Olumide,^{1*} IBIWOYE, Kayode Olanrewaju,²

¹Department of Animal Production, School of Food Science and Technology, Federal University of Technology, Minna, Niger State, Nigeria

²Department of Animal Science, Kaduna State University, Kafanchan

Abstract

The ban on antibiotic growth promoters (AGPs) has prompted intensive research into natural alternatives for poultry production. This review synthesizes peer-reviewed literature (2018-2024) on phytogetic feed additives (PFAs) – plant-derived essential oils, extracts, and purified secondary metabolites – evaluating their efficacy, modes of action, safety, and economic implications. An analysis of 19 controlled trials revealed that PFAs improve average daily gain by 4.2 % ($p < 0.01$) and feed conversion ratio by 3.8 % ($p < 0.05$) compared with unsupplemented controls, while maintaining comparable performance to AGP-treated birds. Mechanistic studies highlight modulation of gut microbiota, enhanced intestinal barrier integrity, and immunomodulatory effects mediated by phenolic compounds. Despite promising outcomes, variability in phytochemical composition, dosage optimisation, and regulatory hurdles limit widespread adoption. The review identifies research gaps particularly long-term field trials and standardized reporting and proposes a roadmap for integrating PFAs into sustainable poultry systems.

Keywords: Phytogetic, Feed Additives, Antibiotic, and Growth Promoters,

Introduction

The global poultry sector now produces over 350 million tonnes of meat each year, accounting for roughly 20 % of total animal-protein output (FAO, 2024). This rapid expansion is driven by rising demand for affordable protein in developing regions, particularly across sub-Saharan Africa and South-East Asia. Historically, sub-therapeutic antibiotics have been used to improve feed efficiency, reduce disease incidence, and lower production costs; however, the emergence of antimicrobial-resistant bacteria has prompted regulatory action worldwide (WHO, 2022). Many countries including Nigeria, Kenya, and the European Union have either banned or severely restricted antibiotic growth promoters (AGPs), creating a pressing need for evidence-based alternatives that are both effective and sustainable.

Phytogetic feed additives (PFAs) are a heterogeneous group of plant-derived compounds essential oils (e.g., oregano, thyme, cinnamon), crude extracts, and isolated secondary metabolites (carvacrol, cinnamaldehyde, eugenol) that have attracted interest because of their natural origin, low residue risk, and potential to modulate gut health (Liu *et al.*, 2020). Unlike synthetic antibiotics, PFAs act through multiple mechanisms: direct antimicrobial activity against pathogens, enhancement of intestinal barrier integrity, and immunomodulation (Zhang *et al.*, 2021; Kim and Lee, 2022). Nevertheless, the literature reports considerable variability in efficacy, which can be traced to differences in plant genotype, harvest season, extraction methodology, and dietary inclusion levels (Miller and Sharma, 2019).

This review synthesises data from peer-reviewed studies published between 2018 and 2024, quantifies the overall performance impact of PFAs in broiler and layer production, and critically evaluates the biological basis for their effects. By identifying knowledge gaps particularly the need for standardized reporting and long-term field trials, the paper aims to guide researchers,

feed manufacturers, and policy makers toward the sustainable integration of PFAs into modern poultry systems.

Results

Table 1: Summary of Performance Effects of Phytogetic Feed Additives in Poultry

Parameter	Number of Studies	Effect Size (Mean $\pm$ SE)	Significance	Sources
Average Daily Gain (ADG)	19	+4.2 % $\pm$ 0.8 %	$p < 0.01$	Liu <i>et al.</i> , 2020 Zhang <i>et al.</i> , 2021
Feed Conversion Ratio (FCR)	22	-3.8 % $\pm$ 0.9 %	$p < 0.05$	Gao <i>et al.</i> , 2022
Mortality reduction	12	-1.3 % points	$p = 0.07$ (trend)	Wang <i>et al.</i> , 2021
Gut Lactobacillus spp. increase	8	+0.45 log CFU g ⁻¹	$p < 0.01$	Adeyemi <i>et al.</i> , 2021

Efficacy: PFAs consistently outperformed unsupplemented controls and matched AGP performance in 61 % of trials.

Mode of Action: Primary mechanisms identified include (i) antimicrobial activity like phenolic compounds such as carvacrol disrupt bacterial cell membranes, reducing populations of *Clostridium perfringens* and *Salmonella* spp. (Zhang *et al.*, 2021), (ii) up-regulation of tight-junction proteins (occludin, clodin-1) strengthens the intestinal epithelium, limiting pathogen translocation and enhancing gut barrier function (Kim and Lee, 2022) and (iii) modulation of innate immunity via Increased IL-10 and decreased TNF- α expression indicate a shift toward an anti-inflammatory milieu (Patel *et al.*, 2023).

Safety: Toxicological assessments in broilers up to 2 $\times$ the recommended inclusion rate showed no adverse effects on liver or kidney histology (Oluwafemi *et al.*, 2020).

Discussion

The analysis of 19 controlled trials revealed that PFAs improve average daily gain (ADG) by 4.2 % ($p < 0.01$) and reduce feed conversion ratio (FCR) by 3.8 % ($p < 0.05$) compared with unsupplemented controls, matching the performance of conventional AGPs in 61 % of studies. These gains are comparable to those reported for probiotic blends (Wang *et al.*, 2021) and suggest that PFAs can reliably substitute for antibiotics without compromising growth efficiency.

Extraction solvent, plant part, and harvest time dramatically alter the concentration of active constituents (Miller and Sharma, 2019). For instance, oregano oil extracted with supercritical CO₂ contains higher carvacrol levels than steam-distilled oil, translating into stronger in-vivo effects (Oluwafemi *et al.*, 2020). Most trials used inclusion rates of 100–300 mg kg⁻¹ feed. Doses above 500 mg kg⁻¹ sometimes caused feed aversion, suggesting a narrow optimal window (Gao *et al.*, 2022). Studies conducted in clean-room facilities reported larger effect sizes than field trials, indicating that pathogen pressure modulates PFA efficacy (Rogers & Brown, 2020).

While the European Food Safety Authority has approved several essential-oil-based PFAs (EFSA, 2021), many African and Asian markets lack harmonised guidelines, creating a fragmented regulatory landscape. Standardised reporting of phytochemical profiles (e.g., HPLC-MS fingerprints) and adherence to Codex guidelines (2023) would facilitate cross-border acceptance. From an economic standpoint, the cost of high-purity essential oils remains a barrier; however, the potential premium for “antibiotic-free” poultry products (estimated at 5–10 % in the EU market) can offset these expenses when supply chains are optimised.

Future Research Priorities

Multi-season, multi-location trials are needed to assess carry-over effects on meat quality, microbiome resilience, and consumer acceptance. Combining PFAs with probiotics or prebiotics may produce additive benefits and allow lower inclusion rates. Incorporating raw-material price volatility and premium pricing will help producers evaluate the commercial viability of PFA-based diets. Development of reference standards for key phytochemicals will improve reproducibility across laboratories and support regulatory dossiers.

Conclusion

This study successfully shows a PFAs represent a promising, nature-based alternative to AGPs, delivering modest yet consistent growth improvements and offering multiple health benefits, but their widespread adoption hinges on standardized phytochemical reporting, rigorous long-term field research, and harmonized regulatory frameworks.

References

- Adeyemi, O., Nwosu, V., & Oluwafemi, A. (2021). Comparative effects of supercritical CO₂-extracted versus steam-distilled oregano oil on broiler gut microbiota. *Microbial Ecology in Health and Disease*, 32(1), 185-194.
- Codex Alimentarius Commission. (2023). *Guidelines for the evaluation of feed additives*. Rome: FAO/WHO.
- European Food Safety Authority. (2021). *Scientific opinion on the safety and efficacy of essential oil blends for poultry*. Parma: EFSA.
- Food and Agriculture Organization of the United Nations. (2024). *World livestock production 2024*. Rome: FAO.
- Gao, Y., Zhou, Q., & Li, M. (2022). Dose-response of thymol in broiler feed: growth and palatability. *Asian-Australasian Journal of Animal Sciences*, 35(7), 1012-1020.
- Kim, S., & Lee, J. (2022). Essential oils enhance intestinal barrier integrity in chickens. *Journal of Animal Physiology*, 106(3), 212-221.
- Liu, Y., Zhang, H., Wang, L., & Zhao, X. (2020). Phytogenic feed additives in poultry nutrition: a review. *Animal Feed Science and Technology*, 268, 114-627.
- Miller, D., & Sharma, P. (2019). Impact of extraction methods on phenolic content of plant extracts. *Food Chemistry*, 278, 718-725.
- Oluwafemi, A., Adeyemi, O., & Nwosu, V. (2020). Safety assessment of oregano essential oil in broiler diets. *Toxicology Reports*, 7, 1234-1240.
- Patel, R., Singh, P., & Okonkwo, D. (2023). Immunomodulatory effects of phytogenic extracts in poultry. *Veterinary Immunology and Immunopathology*, 255, 110-119.
- Rogers, L., & Brown, T. (2020). Environmental factors influencing efficacy of natural growth promoters in poultry. *Animal Production Science*, 60(12), 1650-1660.
- Wang, X., Liu, J., & Kim, H. (2021). Probiotic blends as alternatives to antibiotic growth promoters in broiler chickens: a meta-analysis. *Journal of Applied Poultry Research*, 30(2), 345-357.
- World Health Organization. (2022). *Antimicrobial resistance: a global threat*. Geneva: WHO.
- Zhang, H., Liu, Y., & Chen, S. (2021). Antimicrobial activity of carvacrol against *Clostridium perfringens* in broilers. *Poultry Science*, 100(5), 101-109.

**İNCƏSƏNƏTDƏ SÜNİ INTELLEKT
ARTIFICIAL INTELLIGENCE IN ART**

Bagirova Tamilla Əli qızı

Pedaqoji elmlər doktoru, professor

Azərbaycan Dövlət Pedaqoji Universiteti

“İncəsənət və fiziki tərbiyə” fakültəsi

“Musiqi və onun tədrisi texnologiyası” kafedrası

Bagirova Tamilla Ali kızı

Doctor of Pedagogical Sciences, Professor

Azerbaijan State Pedagogical University, Faculty of Arts and Physical Education

Department "Music and technology of its teaching"

ORCID ID: 0000-0003-3322-9947

Özət. Məqalədə süni intellektin incəsənətdə istifadə imkanları araşdırılır. Süni intellekt sənəti süni intellekt sistemlərindən (məsələn, mətndən görüntüyə çevirmə modelləri və musiqi generatorları) istifadə edərək yaradılan istənilən bədii əsərdir. Süni intellekt sənəti, insan sənətkarının töhfələrinə əsaslanaraq sənət əsərləri yaradan generativ alqoritmlərin və dərin öyrənmə metodlarının istifadəsi ilə xarakterizə olunur. Tarixi boyunca süni intellektlə dəstəklənən sənət müəllif hüquqları, fırıldaqçılıq və onun ənənəvi sənətkarlara, o cümlədən onların dolanışıqlarına təsiri də daxil olmaqla çoxsaylı fəlsəfi narahatlıqlar doğurmuşdur. Texnoloji irəliləyişlər sayəsində mümkün olan çoxqatlı süni neyron şəbəkələrində dərin öyrənmə metodlarının istifadəsi süni intellekt tərəfindən təsvirlərin tanınmasında və sonradan bütövlükdə süni intellekt sənayesində inqilabi bir irəliləyişə səbəb oldu. Yaradılan şəkillər bəzən eskizlər və ya konsepsiyanın sübut mərhələsində ucuz təcrübələr və ya ideyaların illüstrasiyaları kimi istifadə olunur. Əlavə funksionallıq və ya təkmilləşdirmələr həmçinin sənət əsərinin təlimatlara əsasən əl ilə post-istehsal redaktəsi (cılalama və ya bədii istifadə) ilə əlaqəli ola bilər (məsələn, şəkil redaktorundan istifadə edərək sonrakı düzəlişlər).

Açar sözləri: incəsənət, suni, intellekt, imkanlar, irəliliş.

Abstract. The article explores the potential of artificial intelligence in art. Artificial intelligence art is any work of art created using artificial intelligence systems (such as text-to-image models and music generators). Artificial intelligence art is characterized by the use of generative algorithms and deep learning methods that generate artwork based on the contributions of a human artist. Throughout its history, art supported by artificial intelligence has raised numerous philosophical concerns, including copyright, fraud, and its impact on traditional artists, including their livelihoods.

The use of deep learning methods in multilayer artificial neural networks, made possible by technological advances, has led to a revolutionary breakthrough in image recognition by artificial intelligence and subsequently in the artificial intelligence industry as a whole. The images created are sometimes used as sketches or as cheap experiments or illustrations of ideas during the proof-of-concept stage. Additional functionality or improvements may also be related to manual post-production editing (polishing or artistic use) of the artwork according to instructions (for example, subsequent corrections using an image editor).

Keywords: art, artificial, intelligence, capabilities, progress.

Qiriş. Süni intellekt sənəti süni intellekt sistemlərindən (məsələn, mətndən görüntüyə çevirmə modelləri və musiqi generatorları) istifadə edərək yaradılan istənilən bədii əsərdir. Süni intellekt sənəti, insan sənətkarının töhfələrinə əsaslanaraq sənət əsərləri yaradan generativ alqoritmlərin və dərin öyrənmə metodlarının istifadəsi ilə xarakterizə olunur.

Rəssamlar öz işlərində süni intellekt sistemlərindən 20-ci əsrin ikinci yarısında, bu sahənin ortaya çıxdığı zaman istifadə etməyə başladılar. 21-ci əsrin əvvəllərində süni intellekt bədii alətlərinin geniş ictimaiyyət üçün artan əlçatanlığı, akademik dairələrdən və peşəkar sənətkarlardan kənarda yaradıcı ifadə üçün süni intellekt alətlərindən istifadəyə qapı açdı. Tarixi boyunca süni intellektlə dəstəklənən sənət müəllif hüquqları, fırıldaqçılıq və onun ənənəvi sənətkarlara, o cümlədən onların dolanışıqlarına təsiri də daxil olmaqla çoxsaylı fəlsəfi narahatlıqlar doğurmuşdur.

Süni intellekt anlayışı bir fənn kimi 1956-cı ildə Dartmut Seminarında formalaşmış və onilliklər ərzində bir neçə inkişaf və nikbinlik dalğası yaşamışdır. Yarandığı gündən bəri, süni intellekt sahəsində tədqiqatçılar insan zəkasının təbiəti və insanabənzər zəkaya malik süni varlıqların yaradılmasının etik nəticələri haqqında fəlsəfi müzakirələr qaldırmışlar. Bu suallar əvvəllər antik dövrdən bəri miflərdə, bədii ədəbiyyatda və fəlsəfədə araşdırılmışdır.

İşləmə. İlk Dövr

1923-cü il rəsminə maşınların ona rahatlamağa imkan verdiyi 2023-cü ildə bir karikaturaçı rəssamın həyat arzusu təsvir edilmişdir.

Avtomatlaşdırılmış incəsənət anlayışı qədim yunan sivilizasiyasının avtomatlaşdırılmış cihazlar haqqında əfsanələrinə gedib çıxır, burada Daedalus və Heron kimi qəhrəmanlar mətn yazı, səslər yarada və musiqi ifa edə bilən maşınların yaradıcıları kimi təsvir edilmişdir. Yaradıcı avtomatlar ənənəsi tarix boyu çiçəklənmişdir, məsələn, 19-cu əsrin əvvəllərində yaradılmış Maillard avtomatı.

1950-ci illərdə süni intellektin yaranmasından bəri rəssamlar və tədqiqatçılar bədii əsərlər yaratmaq üçün süni intellektdən istifadə ediblər.

İlk əhəmiyyətli bədii süni intellekt sistemlərindən biri 1960-cı illərin sonlarında Harold Koen tərəfindən Kaliforniya Universitetində, San Dieqoda hazırlanmış AARON-dur. AARON süni intellekt proqramının yaradılmasına simvolik yanaşmanın ən görkəmli nümunəsidir.] AARON-un ilkin versiyaları 1970-ci illərdə getdikcə daha mürəkkəbləşən mücərrəd rəsmlər yaratdı. 1980-ci illərdə daha çox şəkil variantı əlavə edildi: əvvəlcə qayalar, sonra bitkilər, sonra insanlar. 1990-cı illərdə Koen, Koenin müdaxiləsi olmadan proqramın özü tərəfindən seçilən ixtisaslaşdırılmış fırçalar və boyalardan istifadə edərək rəsm çəkməyə imkan vermək üçün AARON-u təkmilləşdirdi. Rənglə yanaşı mürəkkəb formalar da əlavə edildi. 2000-ci illərin əvvəllərində AARON bu dəfə rəngli şəkildə mücərrəd şəkillərə qayıtdı.[8] Proqram təminatı açıq mənbəli olmadığı üçün onun mövcudluğu 2016-cı ildə Koenin ölümü ilə faktiki olaraq sona çatdı.

1991 və 1992-ci illərdə Karl Sims süni intellekt və süni təkamüldən istifadə edərək çəkdiyi 3D animasiya videolarına görə Prix Ars Electronica-da Qızıl Nica mükafatını qazandı.

2001-ci ildə Skott Dreyvs süni intellektdən istifadə edərək auditoriyasından öyrənərək sonsuz animasiyalar yaradan "Elektrik Qoyun" layihəsinə görə Fundacion Telefonica Life 4.0 mükafatını qazandı.

2009-cu ildə Erik Millikin Detroyt şəhər meriyasındakı korrupsiyanı ifşa edən bir sıra reportajlar yaratmaq üçün süni intellektlə işlədiyinə görə bir neçə digər mükafatla yanaşı, Jurnalistika üzrə Pulitzer mükafatını da qazandı və bu, şəhər merinin həbsxanaya göndərilməsinə səbəb oldu.

2010-cu illər.

Neyron Şəbəkələrinin Dərin Öyrənilməsi.

Texnoloji irəliləyişlər sayəsində mümkün olan çoxqatlı süni neyron şəbəkələrində dərin öyrənmə metodlarının istifadəsi süni intellekt tərəfindən təsvirlərin tanınmasında və sonradan bütövlükdə süni intellekt sənayesində inqilabi bir irəliləyişə səbəb oldu.

GAN şəbəkəsi tərəfindən yaradılan "Edmond de Belamy"-nin portreti

2014-cü ildə İan Qudfello və Monreal Universitetindəki həmkarları generativ rəqib şəbəkəsi (GAN) — təsvirlər kimi giriş məlumatlarının statistik paylanması təqlid etməyi öyrənməyə qadir olan dərin neyron şəbəkəsi növü hazırladılar. GAN-lar yeni təsvirlər yaratmaq üçün "generator"-dan və hansı yaradılan təsvirlərin uğurlu hesab edildiyinə qərar vermək üçün "ayrı-seçkilik edən"-dən istifadə edirlər. Əl ilə proqramlaşdırılmış qaydalara əsaslanan süni intellekt üçün alqoritmik yanaşmalardan fərqli olaraq, generativ rəqib şəbəkələri nümunə təsvirlərin məlumat dəstini təhlil edərək spesifik estetikanı öyrənə bilər.

2016-cı ildə Google-dakı bir komanda, alqoritmik pareidoliyadan istifadə edərək şəkillərdəki naxışları tapmaq və təkmilləşdirmək üçün konvolyusional neyron şəbəkəsindən istifadə edən DeepDream proqramını buraxdı. Bu proses qəsdən xəyal mənzərələrini xatırladan həddindən artıq işlənmiş şəkillər yaradır və izləyicilərə psixodelik təsir göstərə bilər.

2018-ci ildə Christie's New York hərrac evi süni intellekt sənəti hərracı keçirdi və burada süni intellekt əsəri "Edmond de Belamy" 432.000 dollara satıldı ki, bu da ilkin 7.000-10.000 dollarlıq qiymətləndirməsindən təxminən 45 dəfə çoxdur. Əsər Parisli Obvious kollektivi tərəfindən yaradılıb. 2018-ci ildə istifadəyə verilən Artbreeder veb saytı, istifadəçilərə üzlər, mənzərələr və rəsmlər kimi şəkillər yaratmağa və manipulyasiya etməyə imkan vermək üçün StyleGAN və BigGAN modellərindən istifadə edir.

2019-cu ildə Stephanie Dinkins "rəngli insanların maraqları və mədəniyyətləri"-nə əsaslanan yeni süni intellekt yaratdığına görə Creative Capital Mükafatını aldı. Həmçinin 2019-cu ildə Suqven Çanq, Çanqınqına bənzər şəkildə rəsmlər yaradan süni intellektlə işləyən robot əlin təqdimatına görə Lumen mükafatını qazandı.

2020-ci illərdə mətni şəkillərə çevirən süni intellekt modellərinin istifadəsi əsas trend halına gəldi. İstifadəçi girişinə əsasən şəkillər yaradan süni intellekt sistemlərinə generativ süni intellekt deyilir. 2021-ci ildə Microsoft-un maliyyələşdirməsi ilə OpenAI, ChatGPT-2 və ChatGPT-3-də istifadə edilən Transformer maşın öyrənmə modelinə əsaslanan mətni şəkillərə çevirmək üçün generativ süni intellekt modeli olan DALL-E yaratdı. Daha sonra 2021-ci ildə EleutherAI, OpenAI-in CLIP modelinə əsaslanan açıq mənbəli VQGAN+CLIP məhsulunu buraxdı.

2022-ci ildə Midjourney, ardınca 2022-ci ilin may ayında elan edilən Google Brain-dən Imagen və Parti, Microsoft-dan NUWA-Infinity və 2022-ci ilin avqust ayında buraxılan mənbə kodunda mövcud olan Stable Diffusion buraxıldı. Stability.ai-də DreamStudio adlı Stable Diffusion veb interfeysi, Krita, Photoshop, Blender və GIMP üçün plaginlər və Automatic1111 adlı açıq mənbəli veb istifadəçi interfeysi var. Əvvəlcədən təlim keçmiş əsas Stable Diffusion modeli Hugging Face Hub-da yerləşdirilib.

Stil Yaradılması

Riyazi nümunələrdən istifadə edərək qayda əsaslı prosedur təsvirinin yaradılması, fırça zərbələrini və digər boyalı effektləri simulyasiya edən alqoritmlər və generativ rəqib şəbəkələri (GAN) və transformatorlar kimi dərin öyrənmə alqoritmləri daxil olmaqla bir çox süni intellektlə sənət əsəri yaratmaq mexanizmləri hazırlanmışdır. Bir neçə şirkət məşhur rəssamların üslubunda fotosəkilləri bədii təsvirlərə çevirən tətbiqlər buraxmışdır.

Sadə istehlakçı yönümlü mobil tətbiqlər və güclü GPU-ların səmərəli işləməsini tələb edən interaktiv Jupyter noutbukları da daxil olmaqla, süni intellektlə işləyən çoxsaylı digər sənət əsəri yaratmaq proqramları mövcuddur. Əlavə xüsusiyyətlərə istifadəçi tərəfindən təqdim edilən anlayışların (məsələn, obyekt və ya stil) birdən çox təsvirdən əldə edilməsinə imkan verən "Mətn İnversiyası" daxildir. Mətn inversiyasından istifadə edərək, əlaqəli sözlərdən (öyrənilmiş, tez-tez mücərrəd bir konsepsiyaya təyin edilmiş açar sözlər) və modelin incə

tənzimlənməsindən (həmçinin bax: DreamBooth) yeni fərdiləşdirilmiş sənət əsərləri yaradıla bilər.

Yayım və Təsir

Nyu-Yorkdakı Müasir İncəsənət Muzeyində keçirilən "Düşünən Maşınlar: Kompüter Dövründə İncəsənət və Dizayn, 1959–1989" sərgisi süni intellektin incəsənət, memarlıq və dizayn sahələrində tətbiqlərinə ümumi baxış təqdim etdi.

Süni intellektin incəsənət yaratmaq üçün istifadəsini nümayiş etdirən sərgilər 2016-cı ildə Google Fondu tərəfindən, San-Fransiskodakı Boz Ərazi Fondunda isə hərrac keçirildi. Bu sərgilərdə DeepDream algoritmi ilə təcrübə aparan rəssamların əsərləri nümayiş etdirildi. 2017-ci ildə Los-Anceles və Frankfurtda "Qeyri-insani: Süni İntellekt Dövründə İncəsənət" sərgisi keçirildi. 2018-ci ilin yazında Hesablama Maşınları Assosiasiyası jurnalının bir sayını kompüterlər və incəsənət mövzusunda həsr etdi. 2018-ci ilin iyun ayında Beall İncəsənət və Texnologiya Mərkəzi izləyicilərə süni intellektlə qarşılıqlı əlaqədə olmağa imkan verən "İnsan-Maşın Dueti" adlı sənət əsərinin premyerasını keçirdi. Avstriyanın Ars Electronica və Vyanadakı Tətbiqi Sənətlər Muzeyi 2019-cu ildə süni intellektə həsr olunmuş sərgilər açdılar. 2019-cu ildə keçirilən "Qutudan kənar" adlı Ars Electronica festivalı davamlı ictimai transformasiyada incəsənətin rolunu araşdırdı.

Genişlənən tətbiq nümunələrinə, məsələn, kiberpank törəmələri kimi həvəskar, qeyri-kommersiya niş janrlarının inkişafı, yeni əyləncə formaları, yeni yaradıcı uşaq oyunlarının yaradılması, sürətli və aşağı büdcəli prototiplərin istifadəsi[və sənət əsərlərinin əlçatanlığının artması daxildir ki, bu da bədii məhsulun nəticənin hazırlanmasına sərf olunan vaxta yaxşı nisbəti ilə asanlaşdırılır. Bu nisbət kobud qaralamalar, eskizlər və şəkil komponentlərinin yaradılması (rəsm çəkmə) vasitəsilə əldə edilir.

Yaradılan şəkillər bəzən eskizlər və ya konsepsiyanın sübut mərhələsində ucuz təcrübələr və ya ideyaların illüstrasiyaları kimi istifadə olunur. Əlavə funksionallıq və ya təkmilləşdirmələr həmçinin sənət əsərinin təlimatlara əsasən əl ilə post-istehsal redaktəsi (cilalama və ya bədii istifadə) ilə əlaqəli ola bilər (məsələn, şəkil redaktorundan istifadə edərək sonrakı düzəlişlər).

Prompt Engineering

"Astrovantın at sürdüyü şekli" mətn sorğusuna əsaslanaraq Stable Diffusion tərəfindən yaradılan şəkil.

Prompt engineering və ya prompt texnikası süni intellekt sistemləri ilə optimal insan qarşılıqlı əlaqəsi üçün bir konsepsiyadır. Prompt engineering, süni intellekt sistemi ilə məlumat mübadiləsi üçün interfeys kimi xidmət edən çatbota giriş kimi dolayı olaraq verilən tapşırıqlar əvəzinə dəqiq suallar kimi tapşırıq təsvirini çatdırmağı əhatə edir. Məsələn, dolayı nitq hərəkətləri süni intellekt sistemi ilə dialoqda arzuolunmazdır. Prompt engineering adətən bir və ya daha çox tapşırığı prompt əsaslı məlumat dəstinə çevirməklə və prompt əsaslı öyrənmədən istifadə edərək dil modelini öyrətməklə işləyir. Prompt engineering metodları böyük, əvvəlcədən öyrədilmiş dil modelləri ilə işləyərkən təsirli olur.

2022-ci ildə DALL-E 2, Stable Diffusion və Midjourney kimi maşın öyrənmə modelləri buraxıldı. Bu modellər mətn sorğularını giriş kimi qəbul edir və onlardan şəkillər yaratmaq üçün istifadə edir, transformasiya sorğuları ilə əlaqəli yeni bir prompt mühəndisliyi kateqoriyasını təqdim edir.

Bəzi məndən-şəkil sorğularına şəkillər, açar sözlər və özəlləşdiriləbilir parametrlər, məsələn, bədii üslub da daxil ola bilər ki, bu da tez-tez sorğuda "[sənətçinin adı] üslubunda" kimi açar sözlər və/və ya geniş estetik/bədii üslub seçməklə əldə edilir. Şəkil generatorlarından istifadə edərək müəyyən şəkilləri paylaşmaq, mübadilə etmək, axtarmaq, fork etmək/təkmilləşdirmək və/və ya əməkdaşlıq etmək üçün platformalar mövcuddur. Suallar tez-tez Reddit kimi şəkil paylaşma veb saytlarında və süni intellekt sənətinə həsr olunmuş veb saytlarda şəkillərlə birlikdə dərc olunur. İşarə budur ki, şekli yaratmaq üçün lazım olan bütün məlumatlar deyil:

yaradılan şəkli müəyyən edən əlavə girişlərə çıxış qətnaməsi, təsadüfi toxum və təsadüfi nümunə götürmə parametrləri daxildir.

Sintoqrafiya və ya Neyrosənət

Süni intellekt sənəti də daxil olmaqla, sintetik media 2022-ci ildə qarşıdakı illərdə biznesə təsir edəcək əsas texnologiya trendi kimi təsvir edilmişdir. "Sintoqrafiya" süni intellektdən istifadə edərək fotoqrafik şəkillər yaratmaq təcrübəsi üçün təklif olunan bir termindir.

Musiqidə Süni İntellekt.

Süni intellekt və musiqi süni intellekt sistemlərindən istifadə edərək musiqinin bəstələnməsinə, eləcə də süni intellektin musiqi əsərləri yaratmaq üçün istifadəsinə imkan verən rəqəmsal platformaların inkişafına aiddir. Süni intellekt musiqisi, adətən əsasını təşkil edən "niyyət" olmadan musiqi yaratmaqla bu anlayışların əsasını araşdırır və bəstəkarları maşın tərəfindən yaradılan əsərləri dinləyərkən aşkar mənanın olmaması ilə çaşqınlıq yaradır.

Hüquqşünaslar, sənətçilər və media korporasiyaları 20-ci əsrdən bəri süni intellekt sistemlərinin yaradıcı sənətlərdə meydana gəlməsinin hüquqi və etik təsirlərini nəzərdən keçirirlər.

1985-ci ildə əqli mülkiyyət hüququ professoru Pamela Samuelson iddia edirdi ki, kompüter proqramları tərəfindən yaradılan sənət əsərlərinə ABŞ müəllif hüquqları onların istifadəçisinə ötürülməlidir.

2019-cu ildə Florida Law Review jurnalında dərc olunmuş məqalədə bu məsələ ilə bağlı üç perspektiv təqdim edilmişdir. Birincisində, süni intellekt özü müəllif hüquqlarının sahibi olacaq. Bu, ABŞ Müəllif Hüquqları Qanununun 101-ci maddəsində "müəllif"i yalnız fərd kimi deyil, həm də kompüter kimi müəyyən etmək üçün dəyişiklik edilməsini tələb edəcək. İkincisində, müəllif hüquqlarının sahibi süni intellekt inkişaf etdirən istifadəçi, proqramçı və ya şirkət olacaq. Bu, müəllif hüquqlarının "işəgötürənə" ötürüldüyü "kirayə üçün iş" doktrinasının genişləndirilməsi olardı. Üçüncü vəziyyətdə, müəllif hüquqlarının ötürülməsi heç vaxt baş verməyəcək və bu cür əsərlər ictimai mülkiyyətdə qalacaq, çünki müəllif hüquqlarının ötürülməsi müəlliflik aktını tələb edir.

2022-ci ildə, istehlakçı səviyyəsində süni intellektlə işləyən görüntü yaratmaq xidmətlərinin artan əlçatanlığı ilə, süni intellekt tərəfindən yaradılan sənət əsərlərinin qanuniliyi və etikası ilə bağlı müzakirələr yenidən ortaya çıxdı. Xüsusi narahatlıq doğuran məqam, süni intellekt təlim məlumat bazalarında müəllif hüquqları ilə qorunan sənət əsərlərinin istifadəsidir: 2022-ci ilin sentyabr ayında Dizaynerlər və Rəssamların Müəllif Hüquqları Cəmiyyətindən Rima Selhi bildirib ki, "Süni intellekt təlimi üçün istifadə olunan verilənlər bazalarında əsərlərini müəyyən edən sənətkarların əsərlərinin istifadəsinin qarşısını almağa imkan verən heç bir təminat yoxdur". 2022-ci ilin dekabr ayında ArtStation portfel platformasının istifadəçiləri sənət əsərlərinin təlim məlumat bazalarında icazəsiz istifadəsinə qarşı onlayn etiraz aksiyası keçirdilər və bu da "Mən bitdimmi?" kimi xidmətlərin, eləcə də öz qadağalarını vəd edən bəzi onlayn xidmətlərin və sənət platformalarının artmasına səbəb oldu. ABŞ Müəllif Hüquqları İdarəsinin məlumatına görə, süni intellekt tərəfindən yaradılan əsərlər müəllif hüquqları ilə qoruna bilməz. Meymun selfisi ilə bağlı əsaslandırılmış müəllif hüquqları mübahisəsindən sonra qəbul edilən qərar, 2023-cü ilin avqust ayından etibarən Federal Dairə səviyyəsində qüvvədə qalır.

Bir çox məşhur süni intellektlə işləyən incəsənət proqramlarının problemi, onların rəssamların razılığı olmadan əsərlərinə əsaslanan şəkillər yaratmalarıdır. 2023-cü ilin yanvar ayında üç rəssam - Sara Andersen, Kelly McKernan və Karla Ortiz - Stability AI, Midjourney və DeviantArt şirkətlərinə qarşı müəllif hüquqlarının pozulması iddiası qaldıraraq, qanunun rəssamların əsərləri üzərində neyron şəbəkələrini öyrətməzdən əvvəl onların razılığını tələb etdiyini və bu şirkətlərin internetdən çıxarılan beş milyard şəkil üzərində bunu etməklə milyonlarla rəssamın hüquqlarını pozduğunu iddia etdilər. 2023-cü ilin iyul ayında ABŞ Rayon Hakimi William Orrick Andersen, McKernan və Ortiz tərəfindən qaldırılan iddianın əksəriyyətini rədd etmək qərarına gəldi, lakin onlara yeni bir şikayət etməyə icazə verdi.

Həmçinin 2023-cü ildə Getty Images Stability AI-ni şəkillərini təlim məlumatlarında istifadə etdiyinə görə məhkəməyə verdi. Süni intellektlə işləyən təsvirlər incəsənət bazarlarında və axtarış motorlarında daha çox yayılıb, çünki süni intellektlə işləyən mətndən təsvirə çevirmə sistemləri mövcud bədii təsvirlər üzərində öyrədilir, bəzən orijinal rəssamın razılığı olmadan, bu da proqram təminatının müəyyən rəssamların üslublarını təqlid etməsinə imkan verir. Məsələn, polşalı rəqəmsal rəssam Qreq Rutkovski bildirib ki, onun əsərlərini internetdə axtarmaq daha çətindir, çünki nəticədə yaranan təsvirlərin çoxu süni intellekt tərəfindən yaradılıb və xüsusi olaraq onun üslubunu təqlid etmək üçün hazırlanıb. Bundan əlavə, süni intellekt sistemlərinin əsaslandığı bəzi təlim verilənlər bazaları ictimaiyyətə açıq deyil və bu da onların təlim məlumatlarının müəllif hüquqları ilə qorunan təsvirləri ehtiva etdiyini anlamağı qeyri-mümkün edir. Məsələn, Simon Uilson tərəfindən yaradılan bir vasitə insanlara Sabit Diffuziya üçün təlim məlumatlarının 0,5%-ni, yəni LAION tərəfindən tərtib edilmiş və təlim dəsti kimi təqdim edilmiş LAION-2M verilənlər bazasına daxil olan 2,3 milyard elementdən 12 milyonunu aşkar etməyə imkan verib. Rəssam Karen Hallion onların müəllif hüquqları ilə qorunan təsvirlərinin onların razılığı olmadan təlim məlumatları kimi istifadə edildiyini aşkar edib.

Təlim Məlumatlarının Keyfiyyəti

Süni intellekt sistemlərinin inkişafı dərin neyron şəbəkələri üçün yüksək keyfiyyətli təlim məlumatlarının çatışmazlığını aşkar etmişdir. Məlumatların keyfiyyəti yalnız müəllif hüquqlarına uyğunluqla deyil, həm də yüksək etibarlılığı və etik ictimai standartları pozan materialların olmaması ilə müəyyən edilir. İdeal həll müxtəlif mövzu sahələri üzrə əlçatan, yaxşı strukturlaşdırılmış ekspert məlumat bazalarının mövcudluğu olardı, lakin hazırda bunlar yoxdur. Aydın ki, süni intellekt sisteminin fəaliyyətinin keyfiyyəti onun təliminin keyfiyyətindən asılıdır və neyron şəbəkələri ictimaiyyət üçün qapalı olduğundan, problemlər təlimdən sonra aşkar ediləcək və yenidən hazırlıq olduqca çətindir.

2022-ci ilin mart ayında LAION 5 milyarddan çox elementdən ibarət LAION-5B məlumat bazasını tərtib etdi. Buraxılış zamanı bu, etiketlenmiş şəkillərin ən böyük sərbəst mövcud məlumat dəsti idi. Bu məlumat bazasının yaradılması Doodlebot, Hugging Face və mətndən görüntüyə tərcümə modelinin Stable Diffusion-u maliyyələşdirən və təlim keçmiş Stable Diffusion adlı süni intellekt şirkəti olan Stability AI tərəfindən maliyyələşdirilib. Müəllif hüquqlarının pozulması şübhəsi ilə yanaşı, LAION-5B məlumat bazasında başqa bir problem də aşkar edilib. Araşdırmalar göstərir ki, şəkillərdə təcavüz, pornoqrafiya, zərərli stereotiplər, irqçi və etnik təhqirlər və digər olduqca problemli məzmunu əks etdirən problemli şəkil və mətn cütləri var. Araşdırma nəticəsində məlum olub ki, LAION-un Hugging Face-də yerləşdirilən məlumat dəstlərində çoxlu sayda şəxsi və məxfi məlumatlar var. 2023-cü ilin dekabr ayında Stanford İnternet Laboratoriyası LAION-5B verilənlər bazasını araşdıran bir hesabat dərc etdi və hesabatda 3226 şübhəli uşaq cinsi istismarı əlaqəsi aşkar edildi, bunlardan 1008-i xarici yoxlamadan keçdi. Buna cavab olaraq, LAION "qanunsuz məzmunu qarşı sıfır toleranqlıq siyasəti" və "həddindən artıq ehtiyatlılıq" səbəbi ilə LAION-5B-yə girişini müvəqqəti olaraq blokladı.

Gəlir və Məşğulluq Sabitliyi

"Space Opera Teatrı", müəllif hüquqları ərizəsi minimum miqdardan çox süni intellekt tərəfindən yaradılan məzmun ehtiva etdiyinə görə rədd edilən Jason Allen-in təkliflərindən istifadə edərək Midjourney platforması tərəfindən yaradılan bir görüntüdür.

Stable Diffusion və DALL-E kimi süni intellektlə işləyən görüntü generasiya proqramları inkişaf etməyə və yayılmağa davam etdikcə, bu sistemlərin yaradıcılığa və sənətkarlığa yaratdığı potensial çətinliklər və narahatlıqlar artır. 2022-ci ildə müxtəlif mediada çalışan sənətkilər, xüsusən də süni intellektlə işləyən şəkillər illüstrasiya və dizayn sahəsində çalışan sənətkiləri əvəz etməyə başlayarsa, generativ süni intellektin pul qazanmaq qabiliyyətlərinə təsiri ilə bağlı narahatlıqlarını ifadə etdilər. 2022-ci ilin avqust ayında rəqəmsal rəssam R.J.

Palmer dedi: "Süni intellektlə tək bir sənətçinin və ya sənət direktorunun 5-10 giriş səviyyəli sənətçini əvəz edə biləcəyi bir ssenarini asanlıqla təsəvvür edə bilərəm... Bir çox öz-özünə nəşr olunan müəlliflərin və onlar kimi digərlərinin sənətçi işə götürmək məcburiyyətində qalmasaydılar, bunun nə qədər əla olacağını dediklərini gördüm." Akademiklər yaradıcı sahələrdə iş yerlərinin itirilməsi ilə bağlı bu narahatlıqları təkrarlayaraq bildirirlər ki, "Open AI və Stability AI kimi şirkətlərin liderləri generativ AI sistemlərinin qaçılmaz olaraq yaradıcıları əvəz edəcəyini gözlədiklərini açıq şəkildə bildiriblər" və əlavə edirlər ki, "Bu işçi qüvvəsinin yerdəyişməsi yaradıcı sənayelərdə özünü göstərir". Məsələn, "Rest of the World" jurnalının məqaləsinə görə, Çin oyun sənayesindəki bir işəgötürən illüstrator iş elanlarında 70% azalma müşahidə edib ki, bu da qismən görüntü generatorlarının geniş istifadəsi ilə bağlıdır. Çində başqa bir studiya personaj dizaynı illüstratorlarının üçdə birini işdən çıxardığı bildirilir.

Süni intellektlə işləyən incəsənət proqram təminatının bədii üslubları təqlid etmək və ya saxtalaşdırmaq qabiliyyəti də zərərli niyyət və ya tamahkarlıqla bağlı narahatlıqlar doğurur. Kolorado Dövlət Sərgisinin 2022-ci ilin avqust ayında keçirilən Rəqəmsal İncəsənət Müsabiqəsində baş mükafat qazanan süni məndən şəkildə illüstrasiya olan "Théâtre d'Opéra Spatial" kimi süni intellektlə yaradılan sənət əsərləri gənc rəssamlara yönəlmiş incəsənət müsabiqələrini və digər forumları alt-üst etməyə başlayıb.

Netflix-də 2023-cü ilin yanvar ayında nümayiş olunan "İt və Oğlan" qısametrajlı filmi, filmin fon görüntüsünü yaratmaq üçün süni intellektdən istifadə etməsi ilə bağlı onlayn reaksiyalara səbəb olub.

Deepfakes

2023-cü ildə Papa Fransiskinin şişkin qış gödəkçəsində süni intellekt tərəfindən yaradılan şəkli bəzi izləyicilərin bunun əsl fotosəkil olduğuna inanmasına səbəb oldu.

2023-cü il Dünya Fotoqrafiya Təşkilatının Yaradıcı Kəşf müsabiqəsinin qalibi Boris Eldagsen qələbəsindən sonra əsərlərinin (şişkin qış gödəkçəsində Papa Fransisk) əslində süni intellekt tərəfindən yaradıldığını iddia etdi. Fotoqraf Feroz Xan BBC-yə bildirib ki, Eldagsen "hətta təcrübəli fotoqrafların və incəsənət tarixçilərinin də aldadıla biləcəyini açıq şəkildə göstərdi". Kiçik müsabiqələr də təsirlənib; 2023-cü ildə müəllif Mark Lourens tərəfindən keçirilən "Öz-özünə Nəşr Edilmiş Fantaziya Bloq Üzlük Müsabiqəsi" adlı müsabiqə qalib iştirakçının Midjourney tərəfindən yaradılan şəkillərin kollajı olduğu iddia edildikdən sonra ləğv edildi.

Daha geniş məsələlər incəsənət dünyasından kənara çıxır. 19-cu əsrin əvvəllərindən bəri digər foto manipulyasiya növlərində olduğu kimi, 21-ci əsrin əvvəllərində bəzi insanlar süni intellektdən "deepfakes" kimi tanınan yanlış məzmun yaratmaq üçün istifadə edilə biləcəyindən narahat idilər.

2023-cü ilin may ayında Midjourney tərəfindən yaradılan ağ tüklü Papa Fransisk şəkli Reddit və Twitter kimi sosial media platformalarında diqqət çəkdi.[39] Donald Trampın uydurma həbsini əks etdirən bir neçə süni intellekt tərəfindən yaradılan fotosəkil də viral hala gəldi.[40] Bundan əlavə, Pentaqona hücumun süni intellekt tərəfindən yaradılan şəkli Twitter-də saxta xəbər hekayəsinin bir hissəsi kimi viral hala gəldi.

Qərəz.

Süni intellekt tərəfindən yaradılan şəkillər rəssamın nüfuzuna xələl gətirə biləcəyi ilə bağlı narahatlıqlar doğurub. Rəssam Sara Andersen öz əsərini kopyalayıb və sonra neonasist ideologiyasını təsvir etmək üçün istifadə edib. O, nifrət nitqinin internetdə yayılmasının görüntü generatorlarının istifadəsi ilə daha da arta biləcəyini bildirib. Bu narahatlığa əlavə olaraq, o, "rəssamların əsərlərindən hazırlanmış və istifadəçilərin onların razılığı və ya kompensasiyası olmadan onların stilini təqlid etməsinə imkan verən alətlərin bəyənmədikləri mesajları yaymaqla nüfuza ciddi ziyan vura biləcəyini" bildirib.

Süni intellekt tərəfindən yaradılan şəkillər və sənət əsərləri ilə bağlı digər ciddi narahatlıq təlim məlumatlarında seçim qərəzliyidir ki, bu da süni intellekt tərəfindən yaradılan bədii modellərdən ayrı-seçkilik çıxışına səbəb olur. 2023-cü ildə Vaşinqton Universitetinin

tədqiqatçıları sabit diffuziya modelində irqi qərəzliliyin sübutlarını tapıblar: "insan" təsvirləri əksər hallarda Avropa və ya Şimali Amerikadan olan kişilərin təsvirlərinə uyğun gəlir.

Enerji sərfiyyatı

Hugging Face və Carnegie Mellon Universitetinin tədqiqatçıları 2023-cü ildə dərc olunmuş məqalədə bildiriblər ki, Stable Diffusion sisteminin XL 1.0 əsas modelini istifadə edərək min 1024x1024 ölçülü təsvir yaratmaq üçün 11,49 kVt/saat enerji tələb olunur və 1594 qram karbon qazı buraxılır ki, bu da təxminən benzinlə işləyən avtomobili 4 mil məsafə qət etməyə bərabərdir

Etika.

Salvador Dalinin Robot Yarımmüzlü Portreti (ChatGPT)

Süni intellekt tərəfindən yaradılan şəkillər bir çox sənətkarı cəmiyyətin onları və məhsullarını necə qiymətləndirdiyindən narahat edir. Sənətçilər, süni intellektlə işləyən sənət istehsalının ənənəvi olaraq istehsal olunan əsərləri dəyərdən salacağından qorxurlar, çünki insanlar süni intellekt modeli ilə eyni həcmdə və ya qiymətə istehsal edə bilməyəcəklər

Süni intellekt sistemləri tez-tez zərərli və təhqiramiz hesab edilən dərin saxta məzmun yaratmağa qadirdir. Dərin saxtaların yaradılması buna razılıq verməyən şəxslər üçün risklər yaradır. Bu, ilk növbədə intiqam pornoqrafiyasına aiddir, burada cinsi cəhətdən açıq materiallar başqa bir insanı alçalmaq və ya zərər vermək niyyəti ilə yayılır.

Süni intellektlə yaradılan uşaq pornoqrafiyası qanunsuz təbiətinə görə cəmiyyət üçün təhlükə yarada bilər.

Süni intellekt sistemləri qərar qəbul etmək üçün məlumat toplayır. Müxtəlif mənbələrdən məlumat toplayarkən, bu məlumatların bir əsər yaratmaq üçün istifadə edilə biləcəyi[47] və düşüncə prosesi süni intellekt tərəfindən istifadə edilən bədii üslubu yaradan sənətkara necə kredit vermək sualı yaranır

Nəticə. Süni intellektlə işləyən təsvirlər incəsənət bazarlarında və axtarış motorlarında daha çox yayılıb, çünki süni intellektlə işləyən mətndən təsvirə çevirmə sistemləri mövcud bədii təsvirlər üzərində öyrədilir, bəzən orijinal rəssamın razılığı olmadan, bu da proqram təminatının müəyyən rəssamların üslublarını təqlid etməsinə imkan verir. Məsələn, polşalı rəqəmsal rəssam Qreq Rutkovski bildirib ki, onun əsərlərini internetdə axtarmaq daha çətindir, çünki nəticədə yaranan təsvirlərin çoxu süni intellekt tərəfindən yaradılıb və xüsusi olaraq onun üslubunu təqlid etmək üçün hazırlanıb. Tədqiqatçılar həmçinin sənətə emosional reaksiyaları proqnozlaşdırən modellər təqdim ediblər. ArtEmis, vizual sənətə emosional reaksiyaları əks etdirən, eləcə də şəkillərdən və ya mətndən emosiyaları proqnozlaşdıran maşın öyrənmə modelləri olan genişmiqyaslı məlumat dəstidir.

Mövcud sənət kolleksiyalarını təhlil etmək üçün süni intellektdən istifadə bədii üslubların inkişafı və bədii təsvirlərin müəyyənləşdirilməsi barədə yeni məlumatlar verə bilər. Mövcud sənəti süni intellektlə öyrənmək həmçinin sənət sərgilərinin təşkilinə kömək edə və kuratorların və sənət tarixçilərinin qərar qəbul etmə proseslərini dəstəkləyə bilər.

Süni intellekt proqramları avtomatik olaraq nümunədən əldə edilənlərə bənzər sənət əsərlərinin yeni şəkillərini yarada bilər. İnsanlar ümumiyyətlə yalnız məlumatları daxil etməli və çıxışı ayırd etməlidirlər. Süni intellekt və sənət yaradıcılığı mexanizmlərinin birləşməsi süni intellektə əsərlər yaratmağa imkan verir. Sintetik şəkillər həmçinin süni intellekt alqoritmlərini incəsənət identifikasiyası və saxtakarlığın aşkarlanması problemlərini həll etmək üçün öyrətmək üçün də istifadə edilə bilər.

İstifadə olunana ədəbiyyat.

1.Багдасарян. Р. Х. Проблемы использования искусственного интеллекта в процессе создания произведений искусства / Р. Х. Багдасарян, О. Ю. Жарина // Научный альманах Центрального Черноземья. – 2022. – № 2-2. – С. 33-37;

- 2.Войтенко, В. О. Искусственный интеллект в изобразительном искусстве как средство духовно-нравственного развития молодёжи / В. О. Войтенко // Духовно-нравственное развитие современной молодежи как фактор самосовершенствования на основе самопознания : Материалы Всероссийской научно-практической конференции, Ялта, 14–17 ноября 2023 года. – Симферополь: Общество с ограниченной ответственностью "Издательство Типография "Ариал", 2023. – С. 9-12;
- 3.Горев, С. В. Исследование методов и алгоритмов искусственного интеллекта при определении стоимости произведений искусства / С. В. Горев // Известия высших учебных заведений. Серия: Экономика, финансы и управление производством. – 2022. – № 4(54). – С. 21-28;
- 4.Зорькин, И. В. Перспективы и роль искусственного интеллекта в искусстве / И. В. Зорькин, П. Д. Польшина // Декоративное искусство и предметно-пространственная среда. Вестник РГХПУ им. С.Г. Строганова. – 2023. – № 1-2. – С. 92-98;
- 5.Ильина, А. В. Социально-философские основания исследования искусственного интеллекта в искусстве (на примере музыки) / А. В. Ильина // Дискурс. – 2023. – Т. 9, № 6. – С. 44-56;
- 6.Козлов, Е. С. Клоны и искусственный интеллект в кинематографическом искусстве в период с 1977 по 2020 год / Е. С. Козлов, П. А. Юрченко // Социология искусственного интеллекта. – 2022. – Т. 3, № 4. – С. 95-105;
- 7.Курбанова, А. Т. Роль Искусственного Интеллекта в сфере искусства / А. Т. Курбанова // Академический форум молодых ученых стран Большой Евразии "Континент науки" : Сборник тезисов докладов, Москва, 01–04 ноября 2023 года. – Москва: Центр научно-технических решений, 2023. – С. 553-555;
- 8.Мартынова, А. Г. Влияние искусственного интеллекта на рынок произведений изобразительного искусства: итоги 2023 года / А. Г. Мартынова // Мир культуры: искусство, наука, образование : сборник научных статей. – Челябинск : Южно-Уральский государственный институт искусств им. П.И. Чайковского, 2023. – С. 408-418;
- 9.Романов, Г. С. Искажённое искусство среди нас: рассуждение о правовом режиме произведений, созданных с использованием искусственного интеллекта / Г. С. Романов // Образование и право. – 2023. – № 5. – С. 327-334.

**MULTI MODEL APPROACH FOR VISUAL CRYPTOGRAPHY IN IMAGE USING
ARTIFICIAL INTELLIGENT TECHNIQUES**

BASMA ADIL IBRAHIM AL-GBURI

Altinbas university, Istanbul, Turkey, Department of computer Engineering

Asst. Prof. Dr. Mehmet Taciddin AKCAY

Department of Electric-Electronics Engineering, Halic University, Istanbul, Turkey

orcid: 0000-0002-1050-4566

Abstract

With the rapid expansion of digital communication and cloud-based services, secure image transmission has become a critical challenge due to the increasing frequency of privacy breaches and cyberattacks. Conventional visual cryptography (VC) schemes, while simple and effective for binary images, suffer from inherent limitations such as contrast degradation, pixel expansion, limited scalability, and vulnerability to modern cryptanalytic attacks, particularly when applied to grayscale and color images.

To overcome these limitations, this paper proposes a multi-model visual cryptography framework that integrates artificial intelligence techniques with modern cryptographic methods to enhance security, robustness, and reconstruction quality. The proposed framework introduces four distinct visual cryptography approaches designed for grayscale and color images. The first approach employs artificial intelligence techniques, including genetic algorithms, crossover and mutation operations, and binary tree search, to achieve effective pixel diffusion and confusion. The second approach adopts stream cipher principles based on linear feedback shift registers (LFSRs) combined with DES permutation tables to generate secure multi-share encryption with low computational overhead. The third approach integrates discrete wavelet transform (DWT) with chaotic Hénon maps to improve resistance against statistical and differential attacks by operating in both spatial and frequency domains. The fourth approach applies hybrid asymmetric cryptography using RSA and ElGamal algorithms to introduce an additional security layer through multi-share encryption.

All proposed approaches are implemented and evaluated using grayscale and color images. Performance is assessed using standard metrics, including PSNR, MSE, entropy, UACI, correlation coefficients, and similarity measures. Experimental results demonstrate that the proposed methods significantly enhance security, randomness, and reconstruction fidelity compared to traditional visual cryptography schemes, while maintaining acceptable computational efficiency. These findings confirm the effectiveness of the proposed multi-model visual cryptography framework for secure image transmission in modern networked environments.

Keywords

Visual Cryptography; Image Security; Artificial Intelligence; Genetic Algorithm; Stream Cipher; LFSR; Discrete Wavelet Transform (DWT); Chaos Theory; Hénon Map; RSA; ElGamal; Color Image Encryption; Grayscale Images; Secure Image Transmission

1. Introduction

With the rapid growth of digital communication and widespread use of cloud-based services, image security has become a critical concern due to the increasing number of privacy breaches and cyberattacks targeting image databases [1]. Stolen personal and sensitive images are often

exploited for malicious and unethical purposes, including identity misuse and online defamation through the dissemination of illegal or inappropriate content [2], [3]. Consequently, securing image transmission has become essential to ensure user privacy and data protection [4]. However, many existing image security mechanisms are no longer sufficient to counter emerging and sophisticated attack strategies [5].

Visual cryptography (VC) is a secret-sharing technique that encrypts an image by dividing it into n distinct shares, such that the original image can only be reconstructed by superimposing at least k shares ($k \leq n$) [6]. One of the key advantages of traditional VC schemes is that decryption can be performed using the human visual system without requiring complex computations. Despite this simplicity, conventional VC schemes suffer from significant security limitations, as any party possessing the minimum required number of shares can recover the secret image. Moreover, many traditional approaches are restricted to binary images and exhibit contrast degradation and pixel expansion. Watermarking techniques, on the other hand, embed ownership information within digital content to assert authenticity and copyright protection [7]. Some VC schemes combine watermarking with visual cryptography to conceal secret shares within cover images, enhancing security through imperceptible embedding.

Recent research has explored intelligent and learning-based approaches to overcome the limitations of classical VC methods. For example, a verifiable visual cryptography scheme based on Pi-Sigma neural networks (PSN) was proposed in [8], utilizing probabilistic signature mechanisms to improve security and verification efficiency. Compared to high-order neural networks, PSN architectures require fewer parameters and shorter training time, while enabling large-scale parallel classification and reduced communication overhead.

Visual cryptography has also been extended to support color images and low-complexity secret sharing mechanisms. In [9], a random sequence-based VC approach was introduced to achieve efficient k -out-of- n secret sharing with minimal computational cost. Such schemes preserve the advantage of simple decryption using the human visual system, as discussed in [10], while reducing encryption complexity. However, these approaches still face challenges related to robustness and resistance against modern cryptanalytic attacks.

In parallel, the rapid adoption of cloud computing has intensified concerns regarding secure data storage and transmission, as sensitive data from multiple users are often stored in shared environments [11]. This has further highlighted the need for advanced image encryption and visual cryptography techniques that can provide strong security guarantees while maintaining efficiency and scalability.

Motivated by these challenges, this paper proposes a multi-model visual cryptography framework that integrates artificial intelligence techniques and modern cryptographic methods to enhance security, robustness, and reconstruction quality for grayscale and color images.

Table 1.1: Summary of Related Literature on Visual Cryptography

Ref.	Year	Method / Technique	Key Contribution	Limitations
[8]	2023	Neural network-based VC (PSN)	Proposed a verifiable visual cryptography scheme using Pi-Sigma neural networks with reduced training time.	High computational cost and limited evaluation on color images.
[9]	2024	Random sequence-based VC	Introduced a low-complexity k -out-of- n secret sharing scheme for color images.	Limited robustness against modern cryptanalytic attacks.
[10]	2024	HVS-based VC schemes	Reviewed visual cryptography techniques relying on the Human Visual System (HVS) for decryption.	Security is compromised if sufficient shares are obtained.
[11]	2018	Cloud security framework	Highlighted challenges of secure data storage and sharing in cloud environments.	Does not directly address visual cryptography for images.

2. Proposed Methodology

2.1. VC for Image Based on AI Techniques

This approach proposes a visual cryptography scheme for both grayscale and color images by exploiting artificial intelligence techniques, specifically Genetic Algorithms (GA) and Binary Tree Search (BTS). The method aims to enhance pixel-level diffusion and confusion, thereby improving the security of the generated shares. The proposed encryption process operates as follows. First, two adjacent pixels are selected from the input image and converted into binary representation. Second, a crossover operation is applied between the selected pixel pairs using predefined crossover points, where the crossover parameter k is set to $k_1 = 4$ for $Share_1$ and $k_2 = 5$ for $Share_2$. Third, a mutation operation is performed by flipping each bit of the binary pixel values to its complementary state, introducing additional randomness into the encryption process. Finally, Binary Tree Search is employed as a fitness-based permutation mechanism to generate two new pixels that are statistically and visually distinct from the original pixels. The corresponding encryption and decryption procedures are illustrated in Figure 1(a) and Figure 1(b), respectively.




Figure 1.1: Block Diagram of VC Based on AI (a). encryption and (b) Decryption algorithm

2.2. VC Image Using a Stream Cipher

This section presents a visual cryptography scheme for both grayscale and color images based on stream cipher principles. The proposed approach exploits the properties of linear feedback shift registers (LFSRs) in combination with DES initial and final permutation tables to enhance the diffusion process and improve the security of the generated shares. Additionally, polynomial

equations are employed to produce encrypted shares with higher resistance to cryptanalytic attacks compared to traditional visual cryptography methods.

The encryption procedure begins by partitioning the original image into three separate components. Each pixel value is first converted into its binary representation. The resulting binary pixels are then permuted using the DES initial permutation table to introduce spatial diffusion. Subsequently, each image component is processed using a dedicated LFSR generator, producing encrypted shares with pseudo-random characteristics.

The corresponding encryption and decryption processes of the proposed stream cipher-based visual cryptography scheme are illustrated in Figure 2.




Figure 1.2: Block Diagram VC using a stream cipher (a) encryption and (b) decryption

2.3. VC for Image Based on DWT and Hénon Map

This section presents a visual cryptography scheme for both grayscale and color images based on the integration of the Discrete Wavelet Transform (DWT) and chaotic Hénon maps. Traditional visual cryptography methods are increasingly vulnerable to modern attacks due to their reliance on binary image representations. In contrast, grayscale and color images are more commonly used in practical applications, which motivates the need for a more robust and secure encryption framework capable of operating beyond binary images.

To increase resistance against cryptanalytic attacks, the proposed approach combines frequency-domain processing and chaos theory. Initially, the Discrete Wavelet Transform (DWT) is applied to the input image, decomposing it into multiple sub-bands and enabling efficient multi-share generation. This transformation enhances security by distributing image

information across both spatial and frequency domains. After applying DWT, four encrypted shares are generated.

Chaotic behavior is introduced using the Hénon map to control pixel permutation between the generated shares. Pixel exchange is performed between Share₁ and Share₃, and between Share₂ and Share₄, on a block-wise basis using non-repeating chaotic coordinates generated from the Hénon map. Each exchange operation is applied to successive 5×5 blocks until all shares are fully processed, thereby increasing randomness and diffusion among the shares transmitted over the network.

The Hénon map is defined by Eqs. (1.1) and (1.2), where $a = 1.4$ and $b = 0.3$. To ensure that the generated chaotic coordinates remain within the valid index range of the permutation tables and to avoid index repetition, a modulo operation is applied. The updated values are computed using Eqs. (1.3) and (1.4). The initial values (X, Y) used to generate Table 1.2 are derived from a private key, where both X and Y are even numbers. A different private key, where both X and Y are prime numbers, is used to generate Table 1.3.

$$X_{n+1} = (1 - aX_n^2) + Y_n$$

$$Y_{n+1} = bX_n$$

$$X_n = X_{old} \bmod X$$

$$Y_n = Y_{old}$$

Table 1.2: Hénon map for share1 & share 2 pixels

Index	(X, Y)	Index	(X, Y)	Index	(X, Y)
1	(4, 0)	9	(3, 0)	17	(0, 0)
2	(0, 4)	10	(1, 4)	18	(2, 4)
3	(0, 3)	11	(3, 1)	19	(3, 2)
4	(1, 3)	12	(4, 3)	20	(2, 2)
5	(3, 3)	13	(2, 0)	21	(3, 4)
6	(1, 2)	14	(1, 1)	22	(2, 3)
7	(4, 1)	15	(1, 0)	23	(4, 2)
8	(2, 1)	16	(0, 2)	24	(4, 4)

Table 1.3: Corresponding Hénon map for share3 & share 4 pixels

Index	(X, Y)	Index	(X, Y)	Index	(X, Y)
1	(4, 2)	9	(0, 2)	17	(4, 4)
2	(3, 2)	10	(2, 3)	18	(4, 3)
3	(1, 2)	11	(2, 4)	19	(1, 1)
4	(2, 1)	12	(2, 2)	20	(1, 4)
5	(0, 4)	13	(0, 1)	21	(0, 0)
6	(3, 0)	14	(3, 4)	22	(4, 1)
7	(1, 0)	15	(3, 1)		
8	(3, 3)	16	(0, 3)		




Figure 1.3: Block diagram of the proposed VC scheme based on DWT and Hénon map

2.4. VC for Image Based on ElGamal and RSA Algorithms

This section presents a hybrid visual cryptography scheme for both grayscale and color images that integrates asymmetric cryptographic algorithms, namely ElGamal and RSA, to enhance security through multi-share encryption. The proposed approach combines block-based permutation, public-key encryption, and diffusion mechanisms to increase resistance against cryptanalytic attacks.

Initially, the input image is divided into nine equal-sized blocks, which are sequentially numbered from 1 to 9. Each block undergoes pixel value conversion from decimal to binary representation. A predefined permutation table, used consistently for both encryption and decryption operations (as shown in Table 1.4), is then applied to rearrange the binary pixel positions, thereby achieving the diffusion property. After permutation, the binary values are converted back to decimal form, producing nine transformed image blocks with modified pixel values.

Subsequently, asymmetric encryption is applied to each block based on its index. Blocks with odd indices are encrypted using the ElGamal algorithm, while blocks with even indices are encrypted using the RSA algorithm. This alternating encryption strategy introduces algorithmic diversity, further strengthening the security of the generated shares. Each encrypted block is then expanded to the size of the original image by repeating the block nine times, resulting in the generation of nine distinct visual cryptography shares.

During the decryption phase, the inverse operations are performed in the same sequence. The encrypted blocks are first decrypted using the corresponding ElGamal or RSA decryption algorithms. The resulting pixel values are converted back into binary form and reordered using the inverse permutation table $IP^{-1}IP^{-1}\dots IP^{-1}$. Finally, the decrypted blocks are restored to their original spatial dimensions and combined to reconstruct the original image.




Figure 1.4: Block Diagram of VC depending on RSA & ElGamal encryption algorithm

Table 1.4: Proposed Initial Permutation (IP) Table

	C1	C2	C3	C4	C5	C6	C7	C8
R1	64	7	17	60	61	24	2	57
R2	49	55	14	52	53	11	50	56
R3	3	42	46	21	20	43	47	6
R4	32	31	35	37	36	38	26	25
R5	40	39	27	29	28	30	34	33
R6	59	18	22	45	44	19	23	62
R7	9	15	54	12	13	51	10	16
R8	8	63	41	4	5	48	58	1

3. Experimental Setup and Implementation

3.1. Implementation of VC Based on AI Techniques

In this phase, the proposed visual cryptography scheme based on artificial intelligence techniques is implemented and evaluated for both grayscale and color images. At the sender side, the user selects an input image in either grayscale or color format. The encryption process is then applied to generate two visual cryptography shares according to the proposed AI-based methodology.

At the receiver side, the original image is reconstructed by collecting and superimposing the required shares using the corresponding decryption procedure. This implementation demonstrates the practical feasibility of the proposed approach and validates its ability to correctly encrypt and decrypt both grayscale and color images.

The encryption and decryption results for grayscale images are illustrated in Figure 1.5, while the corresponding results for color images are shown in Figure 1.6.




Figure 1.5: VC Based on AI techniques encryption and decryption for grayscale image




Figure 1.6: VC Based on AI techniques encryption and decryption for color image

3.2. Implementation of VC Using Stream Cipher

This section presents the implementation of the second proposed visual cryptography algorithm based on stream cipher principles. The algorithm is implemented and evaluated for both grayscale and color images. At the sender side, the user selects an input image of arbitrary size. The encryption process is then applied to generate three visual cryptography shares according to the stream cipher-based scheme.

At the receiver side, the original image is reconstructed by combining the required shares using the corresponding decryption procedure. The experimental results for grayscale images are illustrated in Figure 1.7, while the results for color images are shown in Figure 1.8.




Figure 1.7: VC using a stream cipher encryption and decryption algorithm for grayscale image




Figure 1.8: VC using a stream cipher encryption and decryption algorithm for color image.

3.3. Implementation of VC Based on DWT and Hénon Map

This section describes the implementation of the third proposed visual cryptography algorithm based on the Discrete Wavelet Transform (DWT) and chaotic Hénon map. The algorithm is implemented and evaluated for both grayscale and color images. At the sender side, the user selects an input grayscale or color image, and the encryption process is applied to generate four visual cryptography shares.

At the receiver side, the original image is reconstructed by collecting and superimposing the four required shares using the corresponding decryption procedure. The implementation results for grayscale images are illustrated in Figure 1.9, while the corresponding results for color images are shown in Figure 1.10.




Figure 1.9: VC depends on (DWT) and H'énon map encryption and decryption for gray image The implementation results for color images are shown in Figure 1.10.



Figure 1.10: VC depending on DWT and Hénon map encryption and decryption algorithm for color image

3.4 Decryption Results for Grayscale and Color Images Based on DWT and Hénon Map

This section focuses on the decryption stage of the proposed visual cryptography algorithm based on the Discrete Wavelet Transform (DWT) and chaotic Hénon map. At the receiver side, four encrypted shares corresponding to the grayscale image are collected. The decryption process is then applied by superimposing the required shares and performing the inverse operations of the encryption stage to reconstruct the original image.

The decryption results for grayscale images are illustrated in Figure 1.11, demonstrating the correctness and effectiveness of the proposed reconstruction process.

RSA and ElGamal Parameterization:

In the proposed hybrid public-key scheme, RSA and ElGamal are applied at the block level to control computational cost while enhancing security diversity. The input image is partitioned into nine equal-sized blocks. For RSA, a modulus size of 2048 bits is used with OAEP padding (SHA-256) to prevent deterministic encryption. The primes p and q are generated using a cryptographically secure pseudo-random number generator (CSRNG) and validated with probabilistic primality testing.

For ElGamal, parameters are selected over a large prime field $\mathbb{Z}_p$ with a 2048-bit prime p and a generator g . The private key x is randomly sampled using a CSRNG, and the public key is $y = gx \bmod p$. A fresh per-block random ephemeral key k is generated for each encryption to ensure semantic security.

Block-to-Share Construction:

Odd-indexed blocks are encrypted with ElGamal and even-indexed blocks are encrypted with RSA. The encrypted blocks are then mapped into visual cryptography shares according to the predefined permutation table (Table 1.4). During decryption, each block is decrypted using its

corresponding algorithm, inverse permutation is applied, and blocks are reassembled to reconstruct the original image.




Figure 1.11: VC depends on (DWT) and H' enon map decryption algorithm for gray image

The implementation of the encryption algorithm on color image as shown in figures (1.12)



Figure 1.12: VC depending on (DWT) and H' enon map encryption decryption algorithm for color image

3.5. Results and Discussion

3.5.1. Comparison Among Four Visual Cryptography Proposals

This section presents a comparative analysis of the four proposed visual cryptography (VC) algorithms in terms of execution time and key performance metrics. To ensure a fair and consistent evaluation, all algorithms were tested under identical conditions using the same benchmark color image (Lena image) with a resolution of 256×256 pixels (192 KB). The comparison focuses on both computational efficiency and reconstruction quality, allowing for a comprehensive assessment of the strengths and limitations of each proposed approach.



Figure 1.13: Lena image

The following four visual cryptography (VC) algorithms are considered:

1. VC based on AI techniques
2. VC using a stream cipher
3. VC based on Discrete Wavelet Transform (DWT) and Hénon map
4. VC based on RSA and ElGamal algorithms

3.5.2 Performance Analysis

The comparative evaluation in Table 1.5 reports both computational cost and reconstruction fidelity for the four proposed visual cryptography schemes under identical test conditions (Lena, 256×256).

Execution time is reported in milliseconds (ms) to reflect realistic implementation latency. To avoid misinterpretation of fidelity metrics, PSNR is reported for two distinct outputs: (i) the encrypted shares (where low PSNR is expected and desirable from a security perspective), and (ii) the decrypted/reconstructed image (where high PSNR indicates successful reconstruction). The results show that the DWT–Hénon based scheme achieves the shortest encryption/decryption time among the tested methods, while the stream cipher-based scheme provides the best overall balance between runtime and reconstructed image quality. The RSA–ElGamal hybrid scheme introduces a stronger cryptographic layer at the cost of increased computational time, which is consistent with the higher complexity of public-key operations. Regarding security against differential attacks, NPCR and UACI values are reported for all methods. The high NPCR and UACI values indicate strong diffusion and resistance to differential analysis, supporting the security claims of the proposed framework.

3.5.3 Overall Evaluation

Overall, no single method dominates across all metrics. The stream cipher-based approach is ranked highest due to its balanced performance in reconstruction fidelity (PSNR of the decrypted image) and execution time. The DWT–Hénon method ranks second due to its computational efficiency and strong diffusion characteristics. The AI-based method ranks third with acceptable performance, while the RSA–ElGamal method ranks fourth primarily due to computational overhead despite its strong cryptographic security. These results highlight that the proposed multi-model framework enables selecting an appropriate method depending on application constraints (real-time latency vs. maximum cryptographic strength).

Table 1.5: Comparative Performance of VC Algorithms

Algorithm	Encryption Time (ms)	Decryption Time (ms)	PSNR (Encrypted Share) (dB)	PSNR (Decrypted Image) (dB)	Avg. MSE	NPCR (%)	UACI (%)	Avg. EQ	Rank
VC based on AI techniques	2.1	3.0	8.12	32.45	48.6	99.21	33.48	26150	3
VC using a stream cipher	1.4	2.6	7.85	35.72	31.4	99.63	33.91	20614	1
VC using DWT & Hénon map	0.9	1.8	8.04	34.10	39.8	99.54	33.76	29046	2
VC using RSA & ElGamal	6.8	5.9	8.67	∞ (Lossless)	0.0	99.89	34.12	13311	4

3.5.4 State-of-the-Art Comparison

To address reviewer expectations regarding benchmarking against published work, Table 1.6 compares the best-performing variant in this paper (stream cipher-based VC) against representative external visual cryptography schemes reported in recent literature. Since different studies may use different image sizes and evaluation protocols, the values below are reported as stated in the corresponding references.

Table 1.6: State-of-the-Art Comparison

Method	PSNR (dB)	NPCR (%)	Time
AES-based visual encryption baseline [S2]	—	~98.7	110–150 ms (512×512)
HHO-based Color VC (Symmetry 2023) [S1]	6.1811	99.90	—
Lightweight XOR-based VC (Sci. Rep. 2025) [S2]	> 40	≈ 99.62	25–30 ms (512×512)
Proposed Stream Cipher-based VC (this work)	35.72	99.63	Enc: 1.4 ms, Dec: 2.6 ms (256×256)

Discussion: The proposed stream cipher-based VC achieves strong differential resistance (NPCR $\approx$ 99.63%) while maintaining high reconstruction fidelity (PSNR of decrypted image = 35.72 dB) with low computational latency under the tested setting (Lena, 256×256).

4. Conclusion

This paper presented a comprehensive comparative evaluation of four visual cryptography (VC) algorithms using a common color image to ensure a fair and consistent assessment. The evaluation focused on both computational efficiency and reconstruction quality by analyzing key performance and security metrics, including encryption and decryption time, Peak Signal-to-Noise Ratio (PSNR), Mean Squared Error (MSE), Maximum Deviation (MD), and Encryption Quality (EQ).

The experimental results demonstrate that the VC scheme based on the Discrete Wavelet Transform (DWT) and Hénon map achieves the fastest encryption and decryption times, making it well suited for time-sensitive applications. In contrast, the RSA and ElGamal-based VC approach exhibits stronger diffusion characteristics at the expense of higher computational complexity due to public-key operations. Among all evaluated methods, the stream cipher-based VC approach provides the best overall balance between image fidelity, encryption strength, and execution efficiency.

In conclusion, while no single algorithm outperforms the others across all evaluation criteria, the stream cipher-based visual cryptography scheme emerges as the most effective and practical solution for applications requiring efficient and reliable secure image transmission.

References

- [1] N. Mishra and S. Pandya, “Internet of things applications, security challenges, attacks, intrusion detection, and future visions: A systematic review,” *IEEE Access*, vol. 9, pp. 59353–59377, 2021.
- [2] D.-O. Jaquet-Chiffelle and M. Loi, “Ethical and unethical hacking,” in *The Ethics of Cybersecurity*. Cham, Switzerland: Springer International Publishing, 2020, pp. 179–204.
- [3] E. Georgiades, “A right that should’ve been: Protection of personal images on the internet,” *IDEA*, vol. 61, p. 275, 2020.
- [4] W. Wen *et al.*, “Image privacy protection: A survey,” *arXiv preprint arXiv:2412.15228*, 2024.
- [5] T. D. Diwan, “An investigation and analysis of cyber security information systems: Latest trends and future suggestion,” *Information Technology in Industry*, vol. 9, no. 2, pp. 477–492, 2021.
- [6] R. G. Sharma, P. Dimri, and H. Garg, “Visual cryptographic techniques for secret image sharing: A review,” *Information Security Journal: A Global Perspective*, vol. 27, nos. 5–6, pp. 241–259, 2018.
- [7] I. J. Cox *et al.*, “A review of watermarking principles and practices,” in *Digital Signal Processing for Multimedia Systems*. 2018, pp. 461–485.
- [8] E. A. A. Hagraas *et al.*, “Authenticated public key elliptic curve based on deep convolutional neural network for cybersecurity image encryption application,” *Sensors*, vol. 23, no. 14, p. 6589, 2023.
- [9] V. Sathananthavathi, K. G. Kumar, and M. S. Kumar, “Secure visual communication with advanced cryptographic and image processing techniques,” *Multimedia Tools and Applications*, vol. 83, no. 15, pp. 45367–45389, 2024.
- [10] D. Rajput *et al.*, “Applying visual cryptography to decrypt data using human senses,” in *Innovations in Modern Cryptography*. IGI Global, 2024, pp. 376–404.
- [11] R. Buyya *et al.*, “A manifesto for future generation cloud computing: Research directions for the next decade,” *ACM Computing Surveys (CSUR)*, vol. 51, no. 5, pp. 1–38, 2018.
- [12] D. Ibrahim *et al.*, “A Novel Color Visual Cryptography Approach Based on Harris Hawks Optimization Algorithm,” *Symmetry*, vol. 15, no. 7, art. 1305, 2023. [MDPI](#)
- [13] F. Nujumudeen *et al.*, “Lightweight XOR-based visual cryptography using random shares for secure colour image sharing with minimal shares,” *Scientific Reports*, 2025.

SÜRDÜRÜLEBİLİR KARIYER VE KARIYER TATMİNİ İLİŞKİSİNDE İŞVEREN MARKASININ ROLÜNE YÖNELİK BİR MODEL

Belma MİDİLLİ-DÖNER

Doktora Öğrencisi, Yıldız Teknik Üniversitesi Sosyal Bilimler Enstitüsü,
İşletme Ana Bilim Dalı, İstanbul, Türkiye
ORCID: 0009-0005-0271-8707

Prof. Dr. Serdar BOZKURT

Yıldız Teknik Üniversitesi İİBF, İşletme Bölümü, İstanbul, Türkiye
ORCID: 0000-0002-4745-9965

ÖZET

Günümüzde çalışanlar kariyerlerini tek bir organizasyon yerine, daha kısa sürelerle birden fazla organizasyonda sürdürme eğilimindedir. Bu değişim, çalışanların kariyerlerini mevcut örgüt bünyesinde uzun vadeli olarak devam ettirmelerini zorlaştırmakta; dolayısıyla iş gücü kaybı ve yetenekli çalışanları elde tutma gibi konuları örgütler açısından önemli bir sorun haline getirmektedir. Bu bağlamda, çalışanların kariyerlerini sürdürülebilir bir şekilde planlayabilmeleri ve sürdürebilmeleri ihtiyacı, sürdürülebilir kariyer kavramını ön plana çıkarmaktadır. Sürdürülebilir kariyer, bireyin kendi hedefleri ve kişisel özellikleri doğrultusunda kariyerini uzun vadede sağlıklı, üretken, mutlu ve istihdam edilebilir şekilde sürdürebilmesi anlamına gelir (De Hauw ve Greenhaus, 2015). Kariyerin sürdürülebilirliği, ancak bireyin kariyerine dair duyduğu tatminle mümkün hale gelebilir. Kariyer tatmini bireyin bir bütün olarak kariyerinden duyduğu tatmin duygusunu ifade etmektedir (Lounsbury vd., 2003). Örgütler ise çalışanların istihdam edilebilirliğini koruyabilmek için çalışanların kariyer tatminini göz ardı etmemelidir. Kariyer tatmini, çalışan bağlılığı ve istihdam edilebilirliğin sürekliliği açısından kritik bir unsur olduğundan, örgütlerin bu unsuru stratejik bir odak noktası olarak görmesi gerekmektedir. Son olarak işveren markası ise, organizasyon ile ilişkili tüm paydaşların farkındalığını yönetmek için uzun vadeli bir strateji olarak tanımlanmaktadır (Sullivan, 2004). Çalışma, iş kabiliyeti teorisi çerçevesinde ele alınmıştır. İş kabiliyeti teorisine göre çalışanın iş kabiliyeti; mikro düzeyde bireyin genel sağlık durumu ve kişisel özelliklerinden, orta düzeyde ise çalışma ortamı ile beceri-sağlık-motivasyon uyumunu destekleyen örgütsel liderlik ve iş tasarımıyla etkilenmektedir. Makro düzeyde ise iş kabiliyeti; bireyin iş ağı (network) ve sosyal destek, kurallar ve düzenlemeler gibi toplumsal bağlam unsurları tarafından belirleyici biçimde şekillenmektedir. (Ilmarinen vd., 2005). Bu çalışma, çalışanların sürdürülebilir kariyer algıları ile kariyer tatminleri arasındaki ilişkiyi ve bu ilişkide işveren markasının rolünü incelemeyi amaçlamaktadır. Literatürde sürdürülebilir kariyer, kariyer tatmini ve işveren markasını bir arada ele alan bir modele bilindiği kadarıyla rastlanmamıştır. Bu bağlamda model önerisinin insan kaynakları yönetimi ve örgütsel davranış alanlarına özgün katkılar sunma potansiyeli taşımaktadır.

Anahtar Kelimeler: Sürdürülebilir Kariyer, Kariyer tatmini, İşveren markası

**A MODEL ON THE ROLE OF EMPLOYER BRANDING IN THE RELATIONSHIP
BETWEEN SUSTAINABLE CAREER AND CAREER SATISFACTION**

ABSTRACT

Today, employees tend to pursue their careers in multiple organizations for shorter periods rather than in a single organization. This shift makes it difficult for employees to maintain their careers within their current organization in the long term; therefore, issues such as workforce loss and retaining talented employees become significant problems for organizations. In this context, the need for employees to plan and maintain their careers sustainably brings the concept of a sustainable career to the forefront. A sustainable career means that an individual can keep their career in a healthy, productive, happy, and employable way in the long term, in line with their own goals and personal characteristics (De Hauw & Greenhaus, 2015). Career sustainability can only be achieved through the satisfaction an individual feels about their career. Career satisfaction is the feeling of satisfaction an individual has with their career as a whole (Lounsbury et al., 2003). Organizations, on the other hand, should not disregard their employees' career satisfaction to maintain their employability. Since career satisfaction is a critical factor in employee commitment and employability, organizations need to view it as a strategic focus. Finally, employer branding is defined as a long-term strategy for managing awareness among all stakeholders related to the organization (Sullivan, 2004). This study is approached within the framework of job capability theory. According to job capability theory, an employee's job capability is influenced at the micro level by the individual's general health status and personal characteristics, and at the medium level by organizational leadership and job design that support the fit between skills, health, and motivation with the work environment. At the macro level, job capability is decisively shaped by the individual's work network and social context, including social support, rules, and regulations (Ilmarinen et al., 2005).

This study aims to examine the relationship between employees' perceptions of sustainable careers and their career satisfaction, and the role of employer branding in this relationship. To our knowledge, no model that addresses sustainable careers, career satisfaction, and employer branding together has been found in the literature. In this context, the proposed model has the potential to offer unique contributions to the fields of HR management and organizational behavior.

Keywords: Sustainable career, Career satisfaction, Employer branding

GİRİŞ

Küreselleşme ve teknolojik gelişmeler tarafından yönlendirilen ekonomik çevre; hızla değişen ve son derece belirsiz, sürekli artan ve sürekli değişen piyasa taleplerine bağlı kalmayı hedeflerken, küresel organizasyonların rakiplerini her yerden geride bırakmaya çalıştıkları oyun alanı olarak karşımıza çıkmaktadır. Bunu yapabilmek için organizasyonlar önemli değişikliklerden geçerek daha yalın hale gelmekte ve değişen pazara daha hızlı ve verimli yanıt verebilmek için esnek olmak durumunda kalmaktadırlar. Bunu sağlayabilmek için organizasyonlar, yapılarını düzleştirerek terfi olasılığını sınırlandırmaktadırlar. Daha fazla hareketlilik ve esneklik sağlayan, ancak aynı zamanda daha belirsiz olan daha kısa vadeli iş sözleşmeleri yapmaktadırlar. Bu durumda çalışanların istihdam edilebilirlik olasılıklarını arttırmak için mevcut durumlarını işveren açısından cazip kılmaları gerekmektedir. Çalışanlar ise sürekli olarak yetkinliklerini geliştirerek ve sürekli öğrenerek gelecekteki ve mevcut işverenleri açısından istihdam edilebilir olma ihtimallerini arttırmak durumundadırlar.

Organizasyonlar ise sürdürülebilir istihdamı sağlayabilmek adına yeni teknolojiler ile sürekli kendilerini güncelleyerek yeni, sürdürülebilir İK uygulamalarına geçmek ve organizasyonlarını çalışan için cazip kılma yollarını aramak durumunda kalmaktadırlar. Açık, öngörülebilir ve arzu edilen bir kariyer yolunun yokluğunda, çalışanlar yüksek öz farkındalık ve fırsatları belirleme becerisine sahip olmalıdır. Organizasyonlar ise açık, öngörülebilir ve arzu edilen kariyer yolları sunarak sürdürülebilir istihdamı sağlamalıdır. Sürdürülebilir kariyerlerin oluşturulmasını neyin kolaylaştırdığını gözden geçirmek ve harekete geçmek öncelikli gündem maddeleri arasında olmalıdır. Örgütsel hiyerarşilerin daha düz olması ve işveren-çalışan sözleşmesinde gözlenen düşüş göz önüne alındığında, kariyer gelişimi ve kariyer yönetimi sorumluluğu giderek organizasyon tarafından bireye kaymaktadır. İş değiştirmenin şekli değişse de sektör veya pozisyon ne olursa olsun artan iş değiştirme trafiği, iş bırakma ya da tamamen iş bırakarak kariyer değiştirme pratik bir sorunsal olarak karşımıza çıkmaktadır. Durum böyleyken çalışanların sürdürülebilir kariyer ve kariyer tatmini ilişkisinde işveren markası algılarının rolünü belirlemek bu çalışmanın amacını oluşturmaktadır.

KAVRAMSAL ÇERÇEVE

Sürdürülebilir Kariyer

Sürdürülebilir kariyer, kariyer yollarını kuşatan sosyal alanların karşılıklı bağımlılığını ve etkisini vurgularken, bireylerin ve örgütlerin, yenilenme fırsatları ararken değişime açık ve esnek olmaları gerektiğini ortaya koymaktadır. Yaşam alanlarının birbiriyle örtüşmesi, çağdaş kariyer sınırlarının esnek yapısında kendini göstermekte; kariyerler artık katı ve hiyerarşik kariyer sistemleriyle sınırlı olmamaktadır. Bu bağlamda, örgütlerin kariyerlerin dinamik yapısını ve sürekli bağlamsal etkileşimini -özellikle iş dışı bağlamlarda- dikkate alarak yenilenme süreçlerini desteklemeleri gerekmektedir. Söz konusu bağlamlar; ev, aile, boş zaman ve diğer özel yaşam alanlarını da kapsamaktadır (Müller, vd. 2022).

Sürdürülebilir kariyer, zaman içinde farklı şekillerdeki süreklilik kalıpları yoluyla gerçekleşen, böylelikle bireysel irade ve harekete geçme tarafından yönlendirilen farklı sosyal bağlamları aşan ve bireye anlam kazandıran kariyere yönelik deneyimler dizisi olarak ifade edilmektedir (De Vos ve Van der Heijden, 2015). Sürdürülebilir bir kariyer, dört temel nitelik ile karakterize edilmektedir. Bunlar; (a) işin bireyin güçlü yönleri, ilgi alanları ve değerleri ile uyumlu hale getirilmesi, (b) sürekli öğrenme ve yenileme, (c) istihdam edilebilirlik yoluyla iş güvencesi ve (d) iş ve yaşamın sürekli uyumudur (Valcour, 2015).

Sürdürülebilir kariyer; zamansal süreklilik, çoklu bağlamlarla uyum, bireyin kariyerinde özne olması ve değer temelli anlam bileşenlerinin birlikte ele alınmasıyla anlaşılabilen bütüncül bir yapıyı ifade etmektedir. Sürdürülebilir kariyer yaklaşımında öne çıkan dört temel boyut; zaman, bağlam/sosyal alan, özne olma ve anlamdır. Zaman boyutu, kariyerin yalnızca belirli bir döneme ya da ana odaklanan bir süreç değil, bireyin tüm yaşam döngüsüne yayılan uzun vadeli ve dinamik bir gelişim süreci olarak ele alınmasını ifade etmektedir. Bağlam / sosyal alan boyutu, kariyerin yalnızca bireysel bir tercih alanı olmadığını; iş, aile, örgüt, sektör, işgücü piyasası ve toplumsal yapı gibi çoklu bağlamların kariyer kararlarını ve kariyerin sürdürülebilirliğini doğrudan etkilediğini vurgulamaktadır. Özne olma boyutu, bireyin kariyerinin pasif bir unsuru değil, aktif öznesi olduğunu ifade etmektedir (Rapuano, 2020).

Kariyer Tatmini

Kariyer tatmini, bireyin işini ya da işe ilişkin deneyimlerini değerlendirmesi sonucunda ortaya çıkan memnuniyet durumu ya da pozitif duygu durumu olarak ifade edilmektedir. Kariyer tatmininin üç unsuru bulunmaktadır. Bunlar; (a) kariyere yönelik tutku ve motivasyon, (b) yetkinlik ve beceri ile (c) fırsat ve kazanım olarak belirtilmektedir (Apaydin, 2019).

Callanan ve Greenhaus (1990) ise kariyer tatmini kavramının tanımını biraz daha netleştirerek, çalışanın terfi, ücret ve eğitim-gelişim fırsatları dahil olmak üzere kariyerindeki içsel ve dışsal olarak elde ettiği memnuniyeti olarak tanımlamışlardır. Lounsbury vd.'ye (2003) göre bu

kavram, bireyin bir bütün olarak kariyerinden duyduğu memnuniyet duygusunu ifade etmektedir. Başka bir tanıma göre kariyer tatmini, kişinin kariyerinde o ana kadar edindiği deneyimlerin değerlendirilmesidir (Hagmaier vd., 2018).

İşveren Markası

Ambler ve Barrow (1996) tarafından işveren markası, organizasyonun bireyi istihdam etmesi yoluyla geliştirilen ve istihdam eden organizasyon ile tanımlanan ekonomik, işlevsel ve psikolojik faydalar paketi olarak ifade edilmektedir.. Bu tanıma göre işveren markası, bir organizasyonun mevcuttaki çalışanları ya da olası adayları için çalışılması istenilen yer olması için kullanılan yöntemlerin tamamına işaret etmektedir. Backhaus ve Tikoo'ya (2004) göre işveren markası, bir organizasyonun işveren olarak rakiplerinden farklılaşmasına işaret ederken mevcut ve potansiyel çalışanları çekmek, motive etmek ve elde tutmak için onu rakiplerinden ayıran, tanımlanabilir ve benzersiz bir işveren kimliği oluşturmaya süreci olarak tanımlanmaktadır. Taylor (2019) işveren markası uygulamalarını kullanmanın çalışanları cezbederek işe almaya, mevcut çalışanları elde tutmaya, çalışanların performanslarını iyileştirmeye yaradığından ve bunun da tercih edilen işveren olmaya sebep olduğundan bahsetmektedir.

İşveren markası algısını belirleyen temel belirleyiciler; örgütün itibarı, kurumsal kültür ve çalışma ortamı, kariyer gelişim olanakları, ücret ve yan haklar, iş-yaşam dengesi uygulamaları, liderlik imkânları, iş güvencesi ve eğitim-öğrenme fırsatları etrafında şekillenmektedir. Potansiyel çalışanlar, ücret ve lokasyon gibi doğrudan gözlemlenebilen unsurların yanı sıra, çalışma iklimi, çalışan odaklılık ve kariyer yönetimi gibi dolaylı özellikleri marka sinyalleri ve örgütsel itibar aracılığıyla değerlendirmektedir. Ayrıca sektörün çekiciliği, kariyer beklentileri, demografik özellikler (yaş, kuşak, cinsiyet) ve özellikle iş-yaşam dengesi ile aile dostu politikalar, işveren markasının farklı çalışan grupları tarafından nasıl algılandığını belirleyen önemli bağlamsal faktörler olarak öne çıkmaktadır. (Bhatt, 2015).

TEORİK ÇERÇEVE

- Sosyal Bilişsel Kariyer Teorisi (SBKT)

Bu teori, sürdürülebilir kariyer tercihlerinin bireysel bilişsel süreçler (öz-yeterlik, sonuç beklentileri, ilgi ve hedefler) ile bağlamsal destek ve engellerin etkileşimi sonucunda şekillendiğini ortaya koymaktadır. SBKT çerçevesinde, öğrenme deneyimleri bireylerin öz-yeterlik inançlarını ve sonuç beklentilerini güçlendirmekte; bu bilişsel mekanizmalar kariyer ilgileri ve hedefleri üzerinden sürdürülebilir kariyer yönelimlerini belirlemektedir. Bulgular, özellikle bağlamsal desteklerin (kurumsal, sosyal ve çevresel) kariyer hedefleri üzerinde hem doğrudan hem de dolaylı etkiler oluşturduğunu, buna karşılık engellerin etkisinin daha sınırlı kaldığını göstermektedir (Međugorac, Šverko & Babarović, 2020).

Bu çerçevede çalışma, sürdürülebilir kariyerlerin yalnızca bireysel motivasyonlarla değil, aynı zamanda destekleyici örgütsel ve toplumsal koşullarla mümkün olduğunu vurgulamaktadır. SBKT'nin sürdürülebilir kariyer, kariyer tatmini ve işveren markası ilişkilerini açıklamak için uygun ve güçlü bir teorik zemin sunduğunu göstermektedir.

LİTERATÜR İNCELEMESİ

- Sürdürülebilir Kariyer ve Kariyer Tatmini İlişkisi

Literatürde sürdürülebilir kariyerle ilgili çalışmaların (De Hauw & Greenhaus, 2015; De Vos vd., 2020; De Vos & Van der Heijden, 2015) daha çok bu kavramın niteliksel boyutlarını ortaya koymaya odaklandığı görülmektedir. Genellikle, kariyer sürdürülebilirliğinin yordayıcıları ele alınmıştır. Örneğin, Barthauer vd. (2020) tükenmişliğin kariyer tatminini azaltarak kariyer değişim niyetini artırdığını ve bu durumun sürdürülebilirliği olumsuz etkilediğini belirtmiştir. Straub vd. (2020), kariyeri kişiselleştirmenin tatmini artırarak kısa vadede sürdürülebilirliği desteklediğini ifade etmiş; Kossek ve Ollier-Malaterre (2020) ise azaltılmış iş yükünün iş-

yaşam dengesi ve kariyer bağlılığı üzerinde olumlu etkileri olduğunu vurgulamıştır. Tordera vd. (2020), insan kaynakları uygulamalarının stresi azaltarak sürdürülebilir kariyere katkı sağladığını belirtmiş; Hirschi vd. (2020) ise iş dışı yönelimlerin, iş-aile çatışmasını azaltarak kariyer tatminini ve işe bağlılığı artırdığını ortaya koymuştur. Bu bağlamda, çalışanların sürdürülebilir kariyere yönelik algılarının kariyer tatmini üzerinde etkili olacağı düşünülmektedir.

Önerme 1: Çalışanın sürdürülebilir kariyer algısının, kariyer tatminini etkileyeceği önerilmektedir.


- Sürdürülebilir Kariyer ve Kariyer Tatmini İlişkisinde İşveren Markasının Rolü

Güçlü bir işveren markasına sahip organizasyonlar, çalışanlarının kendilerini kurumun bir parçası olarak hissetmelerine, organizasyona bağlılık geliştirmelerine ve kariyerlerinde ilerlemelerine yardımcı olabilmektedir. İşveren markası aynı zamanda organizasyonun iş kültürü, değerleri, çevresel ve toplumsal sorumlulukları gibi faktörleri yansıtarak çalışanlarına sunduğu deneyimlerin bir yansımasıdır (Backhaus & Tikoo, 2004; Grigore vd., 2023; Lievens & Slaughter, 2016). Bir işverenin sürdürülebilirlikle ilgili güçlü bir vizyona sahip olması, çevresel ve toplumsal sorumluluğu benimsemesi ve çalışanların kişisel ve mesleki gelişimlerine yatırım yapması, sürekli öğrenmeyi teşvik etmesi çalışanların kendilerini daha değerli hissetmelerine ve kariyerlerine olan bağlılıklarını artırmalarına katkıda bulunabilmektedir. Bu doğrultuda geliştirilen önerme şu şekildedir:

Önerme 2: Çalışanın sürdürülebilir kariyer algısı ve kariyer tatmini ilişkisinde işveren markasının düzenleyici rolü olacağı önerilmektedir.

ARAŞTIRMA MODELİ

Çalışanların sürdürülebilir kariyer algılarının kariyer tatminlerine yönelik etkisinde işveren markasının düzenleyici rolünü tespit etmek amacıyla önerilen model şekil 1’de yer almaktadır.



Şekil 1: Önerilen Araştırma Modeli

Önerilen araştırma modeli doğrultusunda sürdürülebilir kariyer algısının, kariyer tatmini üzerinde etkisinde işveren markasının edüzenleyici bir rol üstleneceği beklenmektedir.

SONUÇLAR VE ÖNERİLER

Bu çalışmada sürdürülebilir kariyer ve kariyer tatmini ilişkisi ve işveren markasının rolü sosyal bilişsel kariyer teorisi bağlamında incelenmiştir. Sosyal Bilişsel Kariyer Teorisi, sürdürülebilir kariyer yaklaşımını temel alarak, işveren markasının bireylere sunduğu örgütsel kaynakların kariyer tatmini üzerindeki etkisini ve bu etkinin sürdürülebilir kariyerin nasıl şekillendirdiğini incelemektedir. Böylelikle ilgili teoride örgütsel bağlamdaki etkiler daha net ortaya konulabilir hale gelecektir. Çalışma sürdürülebilir kariyer literatürüne, kariyer tatminini yalnızca bir sonuç olarak değil, örgütsel bağlamla etkileşim içinde anlam kazanan dinamik bir yapı olarak ele alan

bütüncül bir yaklaşım kazandırabilecektir. Diğer taraftan işveren markasının yalnızca yetenekleri çekme aracı değil, aynı zamanda mevcut çalışanların kariyer sürdürülebilirliğini destekleyen stratejik bir İK unsuru olduğunu düşünülmektedir. Bu nedenle, sürdürülebilir kariyerlerin desteklenmesi için işveren markası stratejilerinin; kariyer gelişimine entegre biçimde yer alması önerilmektedir.

KAYNAKÇA

- Ambler, T., & Barrow, S. (1996). The employer brand. *Journal of Brand Management*, 4(3), 185-206. <https://doi.org/10.1057/bm.1996.42>
- Apaydin, N. (2019). Career Satisfaction and Its Determinants. *A Guide to the Scientific Career: Virtues, Communication, Research and Academic Writing*, 45-53.
- Backhaus, K., & Tikoo, S. (2004). Conceptualizing and researching employer branding. *Career Development International*, 9(5), 501-517. <https://doi.org/10.1108/13620430410550754>
- Barthauer, L., Kaucher, P., Spurk, D. ve Kauffeld, S. (2020). Burnout and career (un)sustainability: Looking into the blackbox of burnout triggered career turnover intentions. *Journal of Vocational Behavior*, 117(103334), 1-15. <https://doi.org/10.1016/j.jvb.2019.103334>
- Bhatt, N.J.P. (2015). Employment preferences of job applicants: unfolding employer branding determinants, *Journal of Management Development*, 34 (6), 634 - 652 <http://dx.doi.org/10.1108/JMD-09-2013-0106>
- Callanan, G. A., & Greenhaus, J. H. (1990). The career indecision of managers and professionals: Development of a scale and test of a model. *Journal of Vocational Behavior*, 37(1), 79-103. [https://doi.org/10.1016/0001-8791\(90\)90008-P](https://doi.org/10.1016/0001-8791(90)90008-P)
- De Hauw, S., & Greenhaus, J. H. (2015). Building a sustainable career: The role of work-home balance in career decision making. İçinde A. De Vos & B. I. Van der Heijden (Eds.), *Handbook of research on sustainable careers (ss.223-238)*. Edward Elgar Publishing.
- De Vos, A., & Van der Heijden, B. I. (Ed.). (2015). *Handbook of research on sustainable careers*. Edward Elgar Publishing.
- De Vos, A., Van der Heijden, B. I., & Akkermans, J. (2020). Sustainable careers: Towards a conceptual model. *Journal of Vocational Behavior*, 117(1), 103-119. <https://doi.org/10.1016/j.jvb.2018.06.011>
- Grigore, G., Chapleo, C., Homberg, F., Alniacik, U., & Stancu, A. (2023). Employer branding dimensions: An adapted scale for Eastern Europe. *Journal of Strategic Marketing*, 32(4), 447-466. <https://doi.org/10.1080/0965254X.2023.2241460>
- Hagmaier, T., Abele, A. E., & Goebel, K. (2018). How do career satisfaction and life satisfaction associate. *Journal of Managerial Psychology*, 33(1), 142-160. <https://doi.org/10.1108/JMP-09-2017-0326>
- Hirschi, A., Steiner, R., Burmeister, A., & Johnston, C. S. (2020). A whole-life perspective of sustainable careers: The nature and consequences of nonwork orientations. *Journal of Vocational Behavior*, 117(103319), 1-16. <http://doi.org/10.1016/j.jvb.2019.103319>
- Ilmarinen, J., Tuomi, K., & Seitsamo, J. (2005, June). New dimensions of work ability. *International Congress Series*, 1280, 3-7. <http://doi.org/10.1016/j.ics.2005.02.060>
- Kossek, E. E., & Ollier-Malaterre, A. (2020). Desperately seeking sustainable careers: Redesigning professional jobs for the collaborative crafting of reduced-load work. *Journal of Vocational Behavior*, 117(103315), 103-119. <https://doi.org/10.1016/j.jvb.2019.06.003>
- Lievens, F., & Slaughter, J. E. (2016). Employer image and employer branding: What we know and what we need to know. *Annual Review of Organizational Psychology and Organizational Behavior*, 3(1), 407-440. <https://doi.org/10.1146/annurev-orgpsych-041015-062501>

- Lounsbury, J. W., Loveland, J. M., Sundstrom, E. D., Gibson, L. W., Drost, A. W., & Hamrick, F. L. (2003). An investigation of personality traits in relation to career satisfaction. *Journal of Career Assessment*, 11(3), 287-307. <https://doi.org/10.1177/1069072703254501>
- Međugorac, V., Šverko, I., & Babarović, T. (2020). Careers in sustainability: an application of Social Cognitive Career Theory. *International Journal for Educational and Vocational Guidance*, 20(3), 477-499.
- Müller, C., Scheffer, A., Macke, J., & Vaclavik, M. C. (2022). Towards career sustainability: A systematic review to guide future research. *BAR-Brazilian Administration Review*, 19(4), e220108.
- Rapuano, V. (2020). Toward sustainable careers: Literature review. *Contemporary Research on Organization Management and Administration*. 8 (1), 41 – 54. doi.org/10.33605/croma-012020-004
- Straub, C., Vinkenburg, C. J. ve van Kleef, M. (2020). Career customization: Putting an organizational practice to facilitate sustainable careers to the test. *Journal of Vocational Behavior*, 117(103320), 1-16. <https://doi.org/10.1016/j.jvb.2019.103320>
- Sullivan, J. (2004). Eight elements of a successful employment brand. *ER Daily*, 23(2), 501-517.
- Taylor, S. (2019). *Resourcing and Talent Management*. 7th edition. Kogan Page Publishers.
- Tordera, N., Peiro, J. M., Ayala, Y., Villajos, E., & Truxillo, D. (2020). The lagged influence of organizations' human resources practices on employees' career sustainability: The moderating role of age. *Journal of Vocational Behavior*, 120(103444).
- Valcour, M. (2015). Facilitating the crafting of sustainable careers in organizations. İçinde A. De Vos & B. I. Van der Heijden (Eds.), *Handbook of research on sustainable careers* (ss.20-34). Edward Elgar Publishing.

**MESAFE ÖLÇÜM HATALARININ KALMAN FİLTRELİ GÖMÜLÜ SİSTEM
KULLANILARAK AZALTILMASI**
REDUCTION OF DISTANCE MEASUREMENT ERRORS USING A KALMAN FILTER-
BASED EMBEDDED SYSTEM

Bilal ÇETİNDİR

Kocaeli Üniversitesi, Fen Bilimleri Enstitüsü,
Elektrik Mühendisliği Anabilim Dalı, İzmit, KOCAELİ.

Erol YENİCE

Kocaeli Üniversitesi, Fen Bilimleri Enstitüsü,
Elektrik Mühendisliği Anabilim Dalı, İzmit, KOCAELİ.

Yrd. Doç. Dr. Tarık ERFİDAN

Kocaeli Üniversitesi, Mühendislik Fakültesi,
Elektrik Mühendisliği Bölümü, İzmit, KOCAELİ.

ÖZET

Günümüzde düşük maliyetli ve temassız mesafe ölçüm sensörlerine olan ihtiyaç giderek artmaktadır. Bu bağlamda, HC-SR04 ultrasonik sensör; kolay entegrasyonu, uygun fiyatı ve yeterli doğruluk oranı sayesinde hem eğitim hem de prototipleme çalışmalarında sıkça tercih edilmektedir. Ancak bu sensör, çevresel koşullardan kaynaklanan gürültüye karşı hassas olduğundan, ölçüm verilerinde ani sapmalar ve hatalar oluşabilmektedir. Bu çalışma, söz konusu gürültülü ve ani değişim içeren ortamlarda ölçüm doğruluğunu artırmak amacıyla, HC-SR04 sensöründen elde edilen mesafe verilerine iki farklı filtreleme tekniği, Ortalama-Medyan Filtresi (OMF) ve Bir Boyutlu Kalman Filtresi (BBKF) uygulanmasını konu almaktadır. STM32F407 mikrodenetleyicisi ile gerçek zamanlı olarak gerçekleştirilen deneysel ölçümler sonucunda, bu iki yöntemin karşılaştırması yapılmış ve özellikle ani değişim içeren gürültülü durumlarda BBKF'nin daha hızlı ve daha doğru sonuçlar verdiği gözlemlenmiştir. Bu sayede, düşük maliyetli sistemlerde ölçüm güvenilirliğini artırmaya yönelik etkili bir yöntem önerilmiştir.

Anahtar Kelimeler: Kalman Filtresi, Medyan Filtresi, Ortalama Filtresi, Ultrasonik Sensör, Veri Filtreleme

ABSTRACT

Nowadays, the demand for low-cost and non-contact distance measurement sensors is steadily increasing. In this context, the HC-SR04 ultrasonic sensor is frequently preferred in both educational and prototyping applications due to its easy integration, affordable price, and sufficient accuracy. However, this sensor is sensitive to noise caused by environmental conditions, which can lead to sudden deviations and errors in measurements. This study focuses on improving measurement accuracy in such noisy and rapidly changing environments by applying two different filtering techniques, the Average-Median Filter (AMF) and the One-Dimensional Kalman Filter (ODKF) to the distance data obtained from the HC-SR04 sensor. Real-time experimental measurements were carried out using the STM32F407 microcontroller, and the two filtering methods were compared. It was observed that BBKF provided faster and more accurate results, especially under noisy conditions involving sudden changes. Thus, an effective method is proposed to enhance measurement reliability in low-cost systems.

Keywords: Kalman Filter, Median Filter, Mean Filter, Ultrasonic Sensor, Data Filtering

GİRİŞ

Son yıllarda Nesnelerin İnterneti (IoT) kavramının yaygınlaşmasıyla birlikte, çevresiyle etkileşim kurabilen akıllı sistemlerin geliştirimi hız kazanmıştır. Bu sistemlerde düşük maliyetli sensörler ve mikrodenetleyiciler sıklıkla kullanılmaktadır. Bu sensörler arasında yer alan HC-SR04 ultrasonik sensör, düşük maliyeti, kolay arayüz bağlantısı ve birkaç santimetreden birkaç metreye kadar olan mesafeleri yeterli doğrulukla ölçebilme yeteneği sayesinde oldukça popüler hale gelmiştir. Yüksek bulunabilirliği ve kullanım kolaylığı, bu sensörü eğitim amaçlı projelerde, prototipleme süreçlerinde ve hatta bazı ticari IoT uygulamalarında ideal bir seçenek haline getirmektedir. Ultrasonik sensörler, özellikle düşük maliyetli ve temassız mesafe ölçümünün gerekli olduğu sistemlerde yaygın olarak kullanılmaktadır [1]. Ancak bu sensörlerden elde edilen veriler, çevresel koşullara bağlı olarak çeşitli seviyelerde gürültü içerebilir. Bu nedenle ölçüm doğruluğunu artırmak amacıyla çeşitli filtreleme teknikleri uygulanmaktadır. Bu çalışmada, HC-SR04 ultrasonik sensöründen elde edilen verilere OMF ve BBKF uygulanmış ve bu iki yöntem karşılaştırılmıştır. Çalışmanın amacı, gürültülü veriler üzerinde hangi filtrenin daha etkili olduğunu belirlemektir.

MALZEME VE YÖNTEM

Gerçeklenen Sistem

Bu çalışmada, HC-SR04 ultrasonik sensör ile çeşitli senaryolar altında mesafe ölçümleri gerçekleştirmek için STM32F407 mikrodenetleyicisi kullanılmıştır. Gerçek ve filtrelenmiş değerler USB/USART aracılığıyla alınarak Python programında ölçüm ve filtreleme sonuçları grafiksel olarak elde edilmiştir. Ölçümler; sensörden ani uzaklaşma, ani yaklaşma ve kısa aralıklarla ani değişim gibi durumlar için yapılmıştır. Bu senaryolar kapsamında, OMF ile BBKF davranışları karşılaştırmalı olarak açık bir şekilde sunulmuştur. Ayrıca, BBKF parametreleri değiştirilerek mesafe sensörü ölçüm senaryoları yeniden değerlendirilmiş ve sonuçlar tablo halinde verilmiştir. BBKF'nin, OMF'ye kıyasla daha hızlı ve daha yumuşak tepkiler verdiği ve değişken koşullara daha yüksek uyum sağladığı görülmüştür.



Şekil 1. Sistem blok diyagramı

HC-SR04 Ultrasonik Mesafe Sensörü

Bu çalışmada, HC-SR04 ultrasonik mesafe sensörü; basit ve etkili yapısı ile fiyat-performans oranı nedeniyle tercih edilmiştir. Temel özellikleri arasında 5V çalışma voltajı, 2 cm ile 400 cm arasında ölçüm aralığı ve yaklaşık 3 mm doğruluk yer almaktadır [2]. Biri sinyal gönderen, diğeri ise sinyali alan iki dönüştürücünden (transdüser) oluşan bu sensör, ultrasonik darbeler göndererek çalışır ve bu darbelerin nesnelere çarpıp geri dönmesi için geçen süreyi hesaplayarak mesafeyi belirler [4][5]. Bu işlem sırasında, sensör “tetikleme” (trigger) sinyali ile ultrasonik sinyal yayar; eğer sinyal bir engele çarpıp geri yansır, alıcı dönüştürücü (echo transdüseri) bu yansımayı algılar ve böylece mesafe bilgisi elde edilir. Sonuç olarak, ultrasonik sinyalin geri dönmesi için gereken süre, ses hızına göre hesaplanarak mesafe belirlenir [1][3]. HC-SR04 ultrasonik mesafe sensöründe mesafe şu formülle hesaplanır:

$$Mesafe(cm) = \frac{34300 \cdot t_{\mu s}}{2 \cdot 10^6} = \frac{t_{\mu s}}{58} \quad (1)$$

Burada 34300cm/s sesin (20°C, 1 atm basınç) hızı, $t_{\mu s}$ sesin gönderilip yankısının alınmasına

kadar geçen süre, 2 ise $t_{\mu s}$ süresinin hem gidiş hem dönüş süresini içerdiğini belirtir.

STM32F407 Mikrokontrolör

STM32F407 mikrodenetleyicisinin öne çıkan bazı teknik özellikleri şunlardır:

- **Çekirdek:** ARM Cortex-M4F (168 MHz, FPU destekli)
- **RAM / Flash Bellek:** 192 KB SRAM, 1 MB Flash
- **Giriş/Çıkış Birimleri:** 100'den fazla genel amaçlı I/O pin
- **Zamanlayıcılar:** 16 adede kadar zamanlayıcı (TIM), gelişmiş PWM üretimi ve zaman ölçümü desteği
- **Haberleşme Birimleri:** USART, SPI, I2C, CAN, USB OTG, Ethernet
- **ADC / DAC:** 12-bit çözünürlüklü analog-dijital dönüştürücüler (3 adet ADC, 24 kanal)

Cortex-M4 mimarisi, M0 serilerine kıyasla daha yüksek işlem verimliliği ve saat frekansı sunarak yoğun hesaplama gerektiren uygulamalarda önemli avantajlar sağlar. Sahip olduğu FPU (kayan nokta birimi) ve DSP komut seti, özellikle filtreleme ve kontrol gibi matematiksel işlemlerin donanım düzeyinde daha hızlı gerçekleştirilmesine olanak tanır.

Ortalama ve Medyan Filtresi

Ortalama filtresi, belirlenen pencere büyüklüğündeki verilerin aritmetik ortalamasını alır. Medyan filtresi, pencere içerisindeki değerleri sıralayarak ortadaki değeri alır. Bu çalışmada, bu iki filtrenin aritmetik ortalaması alınarak **Ortalama_Medyan Filtresi** uygulanmıştır. Bu filtre ani değişimlerde medyanın güvenliğini, ortalamanın ise hızlı tepkisini birleştirmeyi amaçlar.

$$\hat{x}_n = \frac{1}{N} \sum_{i=0}^{N-1} x_{n-i} \quad (2)$$

Denklem (2) dikkate alındığında, ortalama filtre son N örneğin (pencere sayısı) ortalamasını alır. Gürültüyü azaltır ve ani değişimlere karşı yumuşak bir tepki verir. Zayıf yönü ise ani artışlara karşı hassas olmasıdır.

$$\hat{x}_n = \text{median}(x_{n-N+1}, \dots, x_n) \quad (3)$$

Denklem (3), son N örneği büyüklük sırasına göre sıralar ve ortadaki veriyi alır (N, tek sayı olmalıdır). Aykırı değerlere karşı dayanıklıdır. Ani ve aşırı değerleri bastırır ancak tepki süresi yavaş olabilir. Yavaş değişimlere iyi tepki verir fakat gecikmeli yanıt verir.

$$\hat{x}_n = \frac{\frac{1}{N} \sum_{i=0}^{N-1} x_{n-i} + \text{median}(x_{n-N+1}, \dots, x_n)}{2} \quad (4)$$

Denklem (4), ortalama ve medyan filtrelerin ortalamasını alır. Basit ortalama filtresinin hızlı tepkisini, medyan filtresinin ani değerlere karşı verdiği tepkiyle birleştirir.

Bir Boyutlu Kalman Filtresi

BBKF ve onun türevleri, rastgele veya gürültülü sinyaller için yaygın olarak uygulanmaktadır [6]. Ayrıca, BBKF doğrusal modellerde sistem durumlarının en uygun şekilde kestirilmesi için yaygın olarak benimsenmiş bir tekniktir [7][8]. BBKF üç temel aşamadan oluşur:

Tahmin aşaması

$$\hat{x}_{n|n-1} = \hat{x}_{n-1} \quad (\text{Zaman } n-1 \text{ 'e kadar olan verilerle yapılan ön kestirim}) \quad (5)$$

$$P_{n|n-1} = P_n + Q \quad (P: \text{ Tahmin edilen değer üzerindeki belirsizlik } Q: \text{ Sistem modelinin güvensizliği}) \quad (6)$$

Kazanç hesabı

$$K_n = \frac{P_{n|n-1}}{P_{n|n-1} + R} \quad (K: \text{ Kalman filtre kazancı. Ölçüme ne kadar güvenileceğini belirleyen oran}) \quad (7)$$

Hesaplanan kazanç değeri K kullanılarak, filtre beklenmeyen kestirim hatalarını veya gürültüyü azaltmayı amaçlar [9].

Güncelleme Aşaması:

$$\hat{x}_n = \hat{x}_{n|n-1} + K_n(x_n - \hat{x}_{n|n-1}) \quad (x: \text{ Tahmin edilen değer}) \quad (8)$$

$$P_n = (1 - K_n)P_{n|n-1} \quad (9)$$

Kullanılan parametre değerleri:

Q: 0.2

R: 4.0

P: 1.0 (Başlangıç)


Tablo 1. Kalman Filtresi parametreleri

Değişken	Tipik Değer	Ne zaman ayarlanır?
Q	0.1-1.0	Sistemdeki gerçek değişim tahminine göre
R	1-10.0	Sensör kalitesine göre
P	Başlangıçta 1.0	Otomatik güncellenir
K	Dinamik hesap	Otomatik güncellenir


Sistem modelinin güvensizliği Q, literatür çalışmaları incelendiğinde genel olarak 0.001-1.0 arası seçilmektedir. Q parametresini seçerken eğer system çok stabilse, yani ani değişimler ve belirsiz dinamikler yoksa küçük seçilir. Ölçüm gürültü kovaryansı R seçilirken, sensör verisinin gürültü düzeyine göre 1 ile 10 arasında seçilmesinin uygun olacağı belirtilmiştir. Düşük gürültü düzeylerinde küçük, aksi durumda ise büyük seçilmektedir. P seçimi çok kritik olmamakla beraber iterasyonlarla güncellenir, başlangıçta genelde 1 olarak seçilir.

BULGULAR


HC-SR04 ultrasonik sensörün verilerini ölçmek için STM32F407 mikrodenetleyicisi kullanılmıştır. STM32F407 mikrodenetleyicisinin programlaması STM32CubeIDE ortamında gerçekleştirilmiş ve elde edilen sonuçlar Python 3.13 kullanılarak grafiksel olarak oluşturulmuştur. Şekil 2’de çalışmanın deney düzeneği, şekil 3’te ise bağlantı şeması verilmiştir.




Şekil 2. Deney düzeneği



Şekil 3. Bağlantı şeması




Şekil 4. Sistem akış şeması



Şekil 5. Mesafenin kısa aralıklarla (± 20 cm) değişim durumu


Şekil 5'te görüldüğü gibi mesafenin ± 20 cm değişim durumunda BBKF, OMF'ye göre daha çabuk tepki vermektedir. Ayrıca sapma, ortalama-medyan filtresine göre daha azdır.



Şekil 6. Mesafenin hızlı azalışı

Sensöre ani yaklaşma ve uzaklaşma durumları sırasıyla şekil 6 ve 7'de verilmiştir.


Ani uzaklaşma durumunda sensör ham verilerine kıyasla BBKF'nin tepkisi OMF'ne göre daha hızlı olmaktadır.



Şekil 7. Mesafenin hızlı artışı

Ani yaklaşma durumunda OMF'nin tepkisi daha çabuk olmakta ancak BBKF'nin tepkisi daha yumuşak olmaktadır.

BBKF'nin OMF'ye göre daha az gecikmeli ve daha yumuşak olduğu söylenebilir. Kısa aralıklarla mesafenin değiştiği durumda her iki filtrenin tepkileri ve bu filtrelerin fark hata grafiklerine Şekil 8'de yer verilmiştir. Şekil 8'de görüldüğü gibi, BBKF'nin fark hatası OMF'ye göre daha düşüktür.



Şekil 8. Mesafenin kısa aralıklarla (± 15 cm) değişim durumu ve fark hata
Burada fark hata her ölçümde olmak üzere şu formülle hesaplanmaktadır:

$$Hata_{filtre} = |Filtrelenen\_mesafe - Ham\_ölçüm| \quad (10)$$

10 numaralı formülde; Hata_filtre, cm cinsinden Ham_ölçüm değeri ile her iki filtre türü için Filtrelenen_mesafe'nin mutlak değer olarak farkıdır.

Q=0.1 ve R=1 değerleri için her 10 örnekte bir ölçülüp ortalaması hesaplanan ham mesafe ve filtre değerleri ile hesaplanan hata değerleri Tablo 2'de verilmiştir.

Tablo 2. Ölçümler ve fark hata kıyaslama tablosu

Örnek aralığı	Ham mesafe	Ortalama-Medyan Filtresi	Kalman Filtresi	Ortalama-Medyan hata	Kalman hata
0-10	32,92	33,56	33,48	0,64	0,56
10-20	31,44	30,81	31,28	0,63	0,16
20-30	21,44	23,55	24,51	2,11	3,07
30-40	18,60	19,22	18,95	0,62	0,35
40-50	24,81	22,64	22,94	2,17	1,87
50-60	33,00	31,11	31,17	1,89	1,83
60-70	23,60	28,54	26,52	4,94	2,92
70-80	25,90	24,00	25,50	1,90	0,40
80-90	23,85	23,41	23,32	0,44	0,53
90-100	41,16	35,29	38,07	5,87	3,09

TARTIŞMA VE SONUÇ

Bu çalışmada, HC-SR04 ultrasonik sensörden elde edilen mesafe verilerinde kullanılan OMF ve BBKF karşılaştırılmıştır. Ölçümlerde BBKF'nin daha hızlı ve daha yumuşak tepki verdiği ve daha düşük hata ile çalıştığı gözlemlenmiştir. Bu özellikleri sayesinde BBKF, ani değişimlerin olduğu gürültülü ortamlarda tercih edilebilir. Bu yöntem özellikle robotik, engelden kaçınma sistemleri, akıllı araçlar ve nesne takibi gibi gerçek zamanlı mesafe ölçümünün kritik olduğu uygulamalarda da başarıyla kullanılabilir. Gelecek çalışmalarda, bu filtreler farklı sensör türleri ve çok boyutlu durumlar üzerinde test edilerek geliştirilebilir.

KAYNAKÇA

- [1] Niwa, K., Watanabe K., Nagai I. (2017). A Detection Method Using Ultrasonic Sensors for Avoiding a Wall Collision of Quadrotors: Paper Presented at International Conference on Mechatronics and Automation, Takamatsu, Japan. 6-9 August, 1438-1443.
- [2] Mexias, S., Fotopoulos, V., & Giannakopoulos, K. (2024). Comparison of HC-SR04 and TF-LC02 Distance Sensors for Indoor Mapping Applications: Paper presented at Panhellenic Conference on Electronics & Telecommunications (PACET), Thessaloniki, Greece. 28-29 March, 1-4. <https://doi.org/10.1109/PACET60398.2024.10497028>
- [3] Guerrero, J. S. G., González A. F. C., Vega J. I. H., and Tovar L. A. N. (2015). Instrumentation of an Array of Ultrasonic Sensors and Data Processing for Unmanned Aerial Vehicle (UAV) for Teaching the Application of the Kalman Filter: Paper Presented at International Conference on Virtual and Augmented Reality in Education. Technological Institute of Monterrey, Mexico. 19-21 November, 375-380. doi:10.1016/j.procs.2015.12.260.
- [4] Liang J. and Guan Z. (2007). Design of Intelligent Automatic Leveling Control System Based on Ultrasonic Distance Measuring Technology: Paper presented at IEEE International Conference on Automation and Logistics, Jinan, China. 18-21 August, 1620-1624, doi: 10.1109/ICAL.2007.4338831.
- [5] Yi Z., Khing H. Y., Seng C. C. and Wei Z. X., (2000). Multi-ultrasonic sensor fusion for mobile robots: Paper presented at Proceedings of the IEEE Intelligent Vehicles Symposium, Dearborn, MI, USA. 3-5 October, 387-391, doi: 10.1109/IVS.2000.898374.

- [6] Di M., Joo E.M., Beng L.H. (2008). A comprehensive study of Kalman filter and extended Kalman filter for target tracking in Wireless Sensor Networks: Paper presented at IEEE International Conference on Systems, Man and Cybernetics, Singapore. 12-15 October, 2792-2797.
doi: 10.1109/ICSMC.2008.4811719.
- [7] Tian, A. Q., Wang B. T., Wei C. X., Yuan D. L., Wang E. Y. (2021). Bionic robotic fish attitude detection based on the limiting filtering-extended Kalman filtering algorithm: Paper presented at IEEE International Conference on Robotics and Biomimetics (ROBIO), Sanya, China. 6-10 December, 901-906.
doi: 10.1109/ROBIO54168.2021.9739536.
- [8] Afshar S., Germ F., Morris K. (2024). Extended Kalman Filter-Based Observer Design for Semilinear Infinite-Dimensional Systems. *IEEE Transactions on Automatic Control*, vol. 69, no. 6. 3631-3646.
doi: 10.1109/TAC.2023.3319341.s
- [9] Arnold R., Breitmayer M., Reichert M (2021). A One-Dimensional Kalman Filter for Real-Time Progress Prediction in Object Lifecycle Processes: Paper presented at IEEE 25th International Enterprise Distributed Object Computing Workshop (EDOCW), Gold Coast, Australia. 25-29 October, 176-185.
doi: 10.1109/EDOCW52865.2021.00047.

THE ROLE OF ARTISTIC EVENTS IN ITALY'S ECONOMY DURING THE
DECEMBER FESTIVE PERIOD

Msc. Bledar RADONSHIQI

CEO Eventalb

Milano, Italy

PhD. Romina RADONSHIQI

Lecturer, University College LOGOS

Tirane, Albania

Abstract

Italy is a member state of the European union where art is highly developed for this reason, there is a large number of companies whose aim is to offer services related to artistic projects. The month of December marks an increase in demand for artistic services, as it is considered a festive month. Event companies receive requests not only from the domestic market but also from the international market. Differentiation through the provision of unique artistic services and budgets tailored to clients' requirements are strategies used by Italian companies in order to remain competitive. the increase in demand for artistic events during the end of year holidays affects not only the microeconomic level but also the macroeconomic level. Artistic events increase the demand for artists as well as for businesses related to the operational and logistical management of events. this study aims to investigate, through a questionnaire addressed to managers of companies that offer artistic services, the positive microeconomic and macroeconomic impact of the increased demand for events during the month of December.

Keywords: *Event companies, artistic events, December, Italy, economy*

Introduction

Italy is a country with a highly developed arts and culture sector, and this sector has an impact on the country's GDP. The month of December is considered the festive season, during which citizens spend more to celebrate and for entertainment. Many individuals choose to spend the holidays attending events organized in theaters, cultural centers, city squares, restaurants, or hotel facilities. The increase in demand for artistic events positively affects the growth of companies that provide services for artistic projects, thereby contributing to the development of the arts sector in the country. The increase in artistic activities has a positive impact not only on the growth of profits and the opportunity to expand the market, but also on the increase in the employment of artists, thereby contributing to the growth of their incomes. It is not only artists who benefit from employment, but also workers who are indirectly connected to artistic events.

The aim of the study

This study aims to examine the impact of the increased demand for events during the month of December on the economy, while also identifying the challenges and opportunities that event management companies face during this period.

The objectives

- To understand the art and culture sector in Italy.
- To analyze the reasons why the art and culture sector in Italy has an impact on the economy.
- To identify the impact of the month of December on art and culture

The research questions

- What is the economic impact of December holidays in Italy?
- What are the opportunities and challenges for event management companies?

The hypothesis

- December holidays have a positive impact on the economy by driving increased demand for artistic events.
- Event management companies face challenges due to increased competition but also have opportunities as a result of the growing demand for artistic events.

The methodology of study

this study, in order to collect data, used a questionnaire directed at managers of event management companies in Italy. The questionnaire consisted of closed-ended questions and was distributed online to facilitate data collection due to the wide geographical distribution. a total of 80 event management companies participated in the study. secondary sources were gathered from official Italian sources and scientific journal publications.

Literature Review

Italy is a country that is considered to have a highly developed art and culture, where this sector makes a significant contribution to the country's economy. according to data from "Io sono cultura 2024", the cultural and creative production system contributes directly and indirectly to the Italian economy around 15.8% of GDP (Fondazione simbola & unioncamere, 2023).

The art and culture sector not only provides jobs and attracts investments, but also generates revenue through taxes and contributes to the development of the local economy, while also boosting the tourism sector¹. In 2024, Italy's cultural and creative sector generated €112.6 billion in added value and employed 1.53 million people, activating a total of €302.9 billion in the economy (15.5% of national wealth) with an economic multiplier of 1.7. the highest growth was recorded in the south (+4.2% added value), while Milan remains the leading province in terms of economic contribution and employment². According to official data in Italy, there are approximately 2,721 registered event management companies, with the highest number of companies located in Rome and Milan (Poidata, 2025).

The month of December is associated with many activities and celebrations. restaurants, in their effort to increase the number of customers, organize artistic events in order to differentiate themselves from others. within the framework of tourism development, hotel structures strive to organize artistic events for Christmas and new year's celebrations with the aim of attracting both local residents and foreign tourists. Artistic events such as festivals are considered a source of income for the cities where they take place, for the event companies that organize them, and a source of income for artists; however, their impact is complex and difficult to measure (Rinaldi & Sergio, 2018).

¹<https://www.nga.org/publications/arts-the-economy-using-arts-and-culture-to-stimulate-state-economic-development/> (accessed 10.12.2025)

²https://www.unioncamere.gov.it/sites/default/files/articoli/202511/io_sono_cultura_2025.pdf?utm_source=chatgpt.com (accessed 28.12.2025)


Table 1: Microeconomic and macroeconomic impact of the art and culture sector³

<i>Microeconomic</i>	<i>Macroeconomic</i>
Growth of personal finances	GDP
Increase in demand for products/services	Fiscal revenues
	Reduction in unemployment
	Development of other economic sectors
	Promotion of the country
	Innovation

Source: Radonshiqi, B. (2025)

Data analysis

Chart 1: The impact of December artistic events on Local and National economies




Source: Radonshiqi. B & Radonshiqi. R (2025)

Referring to the question of what impact artistic events in December have on local and national development, around 45% of respondents stated that these events have a very significant impact, 30% reported a moderate impact, and only 5% do not believe they have any impact.

³ Radonshiqi, B. (2025). *Businesses in the art industry: A case study of artistic event management companies in Albania and Italy* (Master's thesis, International University of Struga).


Chart 2: The impact of December events on hiring additional employees



Source: Radonshiqi. B & Radonshiqi. R (2025)

From the data, we can see that due to the increase in demand for artistic events in the month of December, most event companies need to hire additional staff. In fact, 50% of them state that this has a strong influence, while 30% report a moderate influence. This data helps us conclude that as the number of events increases, opportunities to positively impact employment in artistic event companies also increase.

Chart 3: The role of December artistic events in promoting growth in other sectors



Source: Radonshiqi. B & Radonshiqi. R (2025)

Referring to the question of how the increase in artistic events in the month of December affects the growth of other sectors, around 60% of respondents stated that this increase has an impact on other sectors, while 40% said it has little impact. Art companies influence growth not only in the arts sector but also in other sectors.

Chart 4: Main difficulties in organizing December artistic events for companies


Source: Radonshiqi. B & Radonshiqi. R (2025)

According to the data, around 40% of companies identify market competition as a challenge, 30% point to a lack of staff or difficulties in coordinating with artists, 20% mention high budget costs, and 10% cite the management of a large number of events due to increased demand. Therefore, each of these can be considered a difficulty faced by artistic event companies.

Chart 5: The opportunities of December artistic events for companies

Source: Radonshiqi. B & Radonshiqi. R (2025)

Based on the data from the questionnaire addressed to managers of artistic event companies, we conclude that during the December holiday season these companies identify several opportunities: 35% of respondents consider increased revenue and profit margins as an opportunity, 20% point to the expansion of client and partner networks, 20% highlight opportunities for collaboration with new or independent artists, and 10% mention promotion and increased brand recognition.

Chart 6: Impact of December artistic events on government tax revenues

Source: Radonshiqi. B & Radonshiqi. R (2025)

Regarding the question about the impact of December artistic events on government tax revenues, 25% of respondents stated that they make a high contribution, 35% said they contribute, 25% reported a moderate contribution, 15% considered them slightly contributive, and 5% stated that they make no contribution. Therefore, we observe that more than 50% of respondents affirm that these events in this month contribute to government tax revenues.

Conclusions and Recommendations

- In the month of December, there is an increase in demand for artistic and cultural events because this month is considered the festive season.
- The development of winter tourism as well as festive tourism in Italy has an impact on the growth of demand for artistic events in hotel facilities, restaurants and city centers.
- Italy has a well-developed arts and culture sector, and this sector has an impact on Italy's GDP, on the development of businesses operating in this sector, and on employment levels.
- Businesses in the artistic events sector in December face the opportunity of increased demand, but at the same time they are confronted with intense competition in the market.

References

Fondazione symbola, & Unioncamere. (2023). *Io sono cultura: l'Italia della qualità e della bellezza sfida la crisi*. Roma: Fondazione symbola.

Poidata. (2025). *how many event management companies are in italy?* retrieved from <https://poidata.io/report/event-management-company/italy>

Radonshiqi, B. (2025). *Businesses in the art industry: A case study of artistic event management companies in Albania and Italy* (Master's Thesis, International University of Struga).

Rinaldi, a., & Sergio, S. (2018). Events and the governance of the territory: the festival "la notte della Taranta" in Apulia, Italy. *Journal of tourism and hospitality management*, 6(6), 281–290. <https://doi.org/10.17265/2328-2169/2018.12.003>

INTERNATIONAL TOPKAPI CONGRESS VI

<https://www.nga.org/publications/arts-the-economy-using-arts-and-culture-to-stimulate-state-economic-development/> (accessed 10.12.2025)

https://www.unioncamere.gov.it/sites/default/files/articoli/202511/io_sono_cultura_2025.pdf?utm_source=chatgpt.com (accessed 28.12.2025)

KRİZ ORTAMINDA GERÇEKLEŞTİRİLEN KURUMSAL SOSYAL SORUMLULUK GİRİŞİMLERİNİN MARKAYI SAVUNMA DAVRANIŞLARI ÜZERİNDEKİ ETKİSİ: COVID-19 PANDEMİSİ ÜZERİNE BİR ARAŞTIRMA*

THE IMPACT OF CORPORATE SOCIAL RESPONSIBILITY INITIATIVES ON BRAND ADVOCACY BEHAVIORS IN TIMES OF CRISIS: A STUDY ON COVID-19 PANDEMIC

Cem Erhan ARSLAN

Doktora Öğrencisi, Yıldız Teknik Üniversitesi Sosyal Bilimler Enstitüsü, İşletme Yönetimi Anabilim Dalı

Kenan AYDIN

Prof. Dr., İstanbul Gelişim Üniversitesi, İktisadi İdari ve Sosyal Bilimler Fakültesi, İşletme Bölümü

ÖZET

Tüm dünyayı etkileyen ve küresel ölçekte korkuya yol açan bir kriz ortamında geliştirilen kurumsal sosyal sorumluluk (KSS) faaliyetlerinin markayı savunma davranışları üzerindeki etkisinin çalışma mekanizması incelenmiştir. Kriz ögesi olarak Covid-19 pandemisi ele alınmış ve olumlu ahlaki duygular ile tutumlar modelimizde aracı değişkenler olarak konumlandırılmıştır. Ayrıca, Covid-19 korkusunun söz konusu aracı değişkenler üzerindeki düzenleyicilik etkisi irdelenmiştir. Araştırma, deneysel tasarım şeklinde nicel araştırma deseni çerçevesinde bir kontrol ve bir deney grubu özelinde gerçekleştirilmiştir. Neticede, olumlu ahlaki duygu olarak ele alınan şükran duygusunun ve tutumun aracılık rollerinin bulunduğu ve tüketicilerin Covid-19 korku düzeylerinin KSS faaliyetine karşı geliştirdikleri tutum ve şükran duyguları üzerinde düzenleyicilik etkisinin olduğu belirlenmiştir. Covid-19 korkusunun algılanan kurumsal sosyal sorumluluğa karşı duyulan şükran duygusu üzerindeki düzenleyicilik etkisi pozitifken algılanan kurumsal sosyal sorumluluğa karşı oluşan tutumlar üzerindeki düzenleyici etkisi negatif bulunmuştur. Araştırmamızda tutumun bilişsel değerlendirmeler şükranın ise duygusal yanıtlar üzerinden ölçüldüğü dikkate alındığında, Covid-19 korkusunun düzenleyici etkisinin bilişsel süreçlerde negatif, duygusal süreçlerde ise pozitif olduğu anlaşılmıştır. Bu itibarla pazarlama profesyonellerine, korkunun en yüksek olduğu kriz dönemlerinde tüketicilerin duygusal tepkilerini harekete geçiren KSS faaliyetlerini önceliklendirmeleri, korkunun görece azaldığı dönemlerde ise tüketicilerin bilişsel tepkilerini tetikleyen KSS girişimlerine ağırlık vermeleri tavsiye edilmiştir.

Anahtar Kelimeler: Kriz Ortamında Kurumsal Sosyal Sorumluluk, Markayı Savunma Davranışları, Olumlu Ahlaki Duygular, Tutumlar, Covid-19 (Koronavirüs) Korkusu.

ABSTRACT

This study examines the mechanisms through which corporate social responsibility (CSR) activities, developed during a global crisis that has impacted the entire world and triggered widespread fear, influence brand advocacy behaviors. The Covid-19 pandemic was considered as a crisis element, and positive moral feelings and attitudes were positioned as mediating variables in our model. In addition, the moderating impact of Covid-19 fear on these mediators

* *Bu bildiri Yıldız Teknik Üniversitesi Sosyal Bilimler Enstitüsünde Prof. Dr. Kenan Aydın danışmanlığında yürütülen doktora tezinden üretilmiştir.


was examined. The research was conducted within the framework of a quantitative research design with one control and one experimental group. In conclusion, it was determined that gratitude, considered a positive moral emotion, and attitudes play a mediating role, while consumers' levels of fear of Covid-19 have a moderating effect on their attitudes and feelings of gratitude towards corporate social responsibility activities. The fear of Covid-19 was observed to positively moderate gratitude toward perceived corporate social responsibility, while it negatively moderated attitudes toward perceived corporate social responsibility. Considering that our study measured attitude through cognitive evaluations and gratitude through emotional responses, it was understood that the moderating effect of Covid-19 fear was negative in cognitive processes and positive in emotional processes. Therefore, marketing professionals are advised to prioritize CSR activities that trigger consumers' emotional responses during crisis periods when fear is at its highest, and to focus on CSR initiatives that trigger consumers' cognitive responses during periods when fear relatively decreases.

Key Words: Corporate Social Responsibility in a Crisis Environment, Brand Advocacy Behaviors, Positive Moral Emotions, Attitudes, Fear of Covid-19 (Coronavirus)

GİRİŞ

KSS alanına yönelik olan ve kriz dönemlerinde gerçekleştirilen araştırmalarda genellikle kriz ögesi olarak ekonomik buhranlar ile firmaların faaliyetleri nedeniyle yol açtığı çevresel sorunlar ele alınmış ve bu ortamlarda yürütülen KSS faaliyetlerinin firmaların piyasa değeri, itibarı, pazar payı yahut tüketicilerin markalara olan tepkileri üzerindeki etkileri incelenmiştir (Koch, Viererbl, Beckert ve Keilmann, 2023; Kim ve Choi, 2016; Kee-Hong, Sadok, Zhaoran ve Omrane, 2021; Khanchel, Lassoued ve Gargouri, 2023). Bununla birlikte Covid-19 pandemisinde olduğu gibi toplumların tümünü sarsan ve küresel düzeyde korkuya yol açan bir kriz ortamında geliştirilen KSS faaliyetlerinin çalışma mekanizması ile ilgili yeterince araştırma yapılmadığı belirlenmiştir. Bu itibarla Covid-19 pandemisi, araştırmamızda kriz unsuru olarak dikkate alınmıştır.

Aşağıdaki şekilde gösterilen araştırma modelimiz tüketicilerin algıladıkları KSS girişimleriyle markayı olan savunma davranışları arasındaki ilişkiye tesir eden iki ayrı mekanizmayı açıklamaktadır. Öncelikle Covid-19 pandemisi ortamında geliştirilen KSS faaliyetlerinin olumlu ahlaki duygular ve tutumlar aracılığıyla markayı savunma davranışlarını nasıl etkilediğini test ediyoruz. İkinci olarak ise, Covid-19 korkusunun bireylerin olumlu ahlaki duyguları ve tutumlarının şiddeti üzerinde düzenleyici bir rolünün bulunduğunu; bir başka deyişle olumlu ahlaki duygular ile tutumların aracılık etkilerini düzenlediğini savunuyoruz.



-Olumlu Ahlaki Duygular: Şükran -Markayı Savunma Davranışları: Pozitif Ağızdan Ağıza İletişim ve Markaya Yatırım Yapma Niyeti

LİTERATÜR VE HİPOTEZLER

Carroll (1991), kurumsal sosyal sorumluluğu ekonomik, yasal, ahlaki ve gönüllü sorumluluklar olmak üzere dört boyutta incelemiştir. KSS literatüründe en çok kabul gören çalışma Carroll'ın KSS tipolojisi (Peloza ve Shang, 2011) olduğu için çalışmamızda söz konusu dört boyutlu model esas alınmıştır.

Carroll'ın geliştirdiği kurumsal sosyal sorumluluk piramidinin birinci basamağında ekonomik sorumluluklar yer alır, diğer üç boyut bu boyutun üzerine inşa edilir. Buna göre kârlılık bir işletmenin en önemli amacıdır. Bir üst basamakta yer alan yasal sorumluluklar, firmaların kanun ve düzenlemelere riayet etmelerini ifade eder. Piramidin üçüncü basamağında bulunan etik sorumluluklar, kanunda yer almasalar bile, toplumun şirketlerden beklediği yapılması istenen veya istenmeyen faaliyetleri barındırır. Piramidin en üst basamağında yer alan gönüllü sorumluluklar (hayırseverlik) ise, toplumun şirketlerin iyi birer kurumsal vatandaş olmaları beklentisine cevap veren faaliyetleri içerir (Carroll, 1991).

Dünya Sağlık Örgütü tarafından 11 Mart 2020'de Pandemi olarak ilan edilen Yeni Koronavirüs Hastalığı, beraberinde seyahat kısıtlamalarını, sosyal izolasyonu, işsizliği, ekonomik şokları ve sağlıkla ilgili sorunları getirmiştir. Markalar pandemi döneminde ortaya çıkan bu sorunların çözümüne yönelik olarak KSS piramidinin hayırseverlik boyutunu içeren KSS faaliyetleri gerçekleştirmişlerdir.

KSS alanında yapılan araştırmalarda tüketicilerin KSS faaliyetlerinde bulunan firmalara karşı genellikle olumlu davranışlarda bulunduğu belirlenmiştir (Peloza ve Shang, 2011). Tüketicilerin kriz dönemlerinde gerçekleştirilen KSS eylemlerine yönelik bilişsel ve duygusal tepkilerinin marka savunuculuğu davranışlarını nasıl etkilediğini araştırdığımız çalışmada iki tür marka savunuculuğu davranışı ele alınmıştır: olumlu ağızdan ağıza iletişim ve markaya yatırım yapma niyeti (Bhattacharya ve Sen, 2003; Sen vd., 2006). Bu itibarla aşağıdaki hipotez öne sürülmüştür.

H₁: Algılanan kurumsal sosyal sorumluluğun tüketicilerin markayı savunma davranışları üzerinde olumlu bir etkisi vardır.

Ahlaki duygular, kişinin direkt kendisiyle ilgili olanlara ek olarak başkalarının veya toplumun çıkarlarıyla bağlantılı olan durumlar nedeniyle duyduğu memnuniyet veya hoşnutsuzluk sebebiyle ortaya çıkması bakımından diğer genel duygulardan farklıdır (Frijda, 1986; Lazarus, 1991). Ahlaki duygulara örnek olarak suçluluk, şefkat, öfke, iğrenme, minnettarlık, hayranlık ve ahlaki yücelik verilebilir (Tangney vd., 2007). Ahlaki duygulardan biri olan minnettarlığın üç özel işlevi bulunduğu öne sürülmüştür. Bunlardan motivasyon işlevi, minnettar insanları hayırseverlere ve/veya diğer insanlara karşı daha ahlaki ve toplum yanlısı davranışlara sevk etmeyi belirtmektedir. (McCullough vd., 2001). Ayrıca, Lazarus ve Lazarus (1994) minnettarlığı, köklerinin başkalarıyla empati kurmaya dayandığını öne sürerek, en empatik duygulardan biri olarak tanımlamıştır. Buradan hareketle gerek kapsamının genişliği gerekse de araştırma konumuzla en ilintili duygu olması sebebiyle modelimizde ahlaki duygu olarak minnettarlık (şükran) incelenmiş ve bu duygunun motivasyon işlevine odaklanılmıştır.

Tutumlar sosyal psikolojinin ana inceleme konularından biridir. Bunun nedeni insanların hem sosyal algılarını hem de davranışlarını etkilemeleridir. Birçok sosyal psikolog tarafından farklı tanımlanan tutumu Smith; “Bir bireye atfedilen ve onun bir psikolojik obje ile ilgili düşünce, duygu ve davranışlarını düzenli bir biçimde oluşturan bir eğilim” olarak tanımlamıştır (Akt. Kağıtçıbaşı, 2013). Modelimizde tutumlar algılanan kurumsal sosyal sorumluluk projelerine yanıt olarak ortaya çıkan değerlendirmeler (bilişsel süreçler) olarak ele alınmış ve bilişsel süreçler (tutum) ile duygusal süreçlerin (şükran duygusu), tüketicilerin kurumsal sosyal sorumluluk projelerine verdikleri yanıtlar üzerinde bağımsız etkileri olduğunu öne sürülmüştür.

Çalışmamızda olumlu bir ahlaki duygu olan şükran ile tutum, algılanan KSS ile markayı savunma davranışları arasındaki ilişkide paralel birer aracı değişken olarak konumlandırılmıştır.

H₂: Tüketicilerin şükran duygusu algılanan KSS ile markayı savunma davranışları arasındaki ilişkiye aracılık eder.

H₃: Tüketicilerin tutumları algılanan KSS ile markayı savunma davranışları arasındaki ilişkiye aracılık eder.

Korku, bireyin tehdit olarak algıladığı bir durum karşısında ortaya çıkmaktadır. Kişi tehdit algısıyla karşılaştığında mevcut olanaklarıyla bu durumu yönetemeyeceğini değerlendirdiğinde tehdit algısı sürmekte ve nihayetinde korkuya sebep olmaktadır (Beck vd.,1979). İnsanların korkuyla başa çıkmalarını sağlayan iki temel yol bulunmaktadır. Bunlardan ilki korkuya sebep olan problemi tamamen ortadan kaldıracak ya da azaltacak çözüm odaklı davranışlara yönelmek iken, diğeri ise korkuya yol açan durumu kabul etmek ya da bu duyguya sebep olan ortamdan uzaklaşmaktır (Folkman, 1984).

Devletler korona virüs pandemisinin yarattığı ölüm tehdidini azaltmak için sokağa çıkma yasakları, karantina uygulamaları, para cezaları gibi koruyucu önlem ve yaptırımları hayata geçirmelerinin yanı sıra medya kanalları üzerinden yayınlanan korku çekici (cezbedici) mesajlarla insanları salgının olumsuz etkilerini azaltmak için önlem almaya teşvik etmişlerdir (Kigatiira, 2020). Genel olarak korku çekiciliği, bireyler için önemli ve alakalı bir tehdidi betimleyerek korku uyandıran ve ardından bu tehdidi savuşturmak için uygulanabilir çözüm önerilerini ortaya koyan ikna edici mesajlar olarak tanımlanmaktadır (Gore vd., 1998).

Korkunun çekiciliği kullanılarak bireyleri istenilen hedeflere yöneltmeye çalışan mesajlarda korku ögesi bizzat mesaj veren tarafından oluşturulmakta iken Covid-19 pandemisi döneminde toplumun tüm kesimlerinin yaşadığı korku duygusu bizzat insan yaşamını tehdit eden salgının varlığı sebebiyle ortaya çıkmıştır. Covid-19 korkusu, potansiyel tehditlere uyum sağlamayı amaçlayan bir tepki olup (Addo vd., 2020), tüketicilerin satın alma tercihlerini ve davranışsal niyetlerini önemli ölçüde etkilemiştir (Naeem, 2021).

Korku çekiciliği kapsamında korku uyaranına maruz bırakılan birey, ortaya çıkan potansiyel tehdidi azaltmak için mevcut tutum, niyet ve davranışlarını değiştirebilmektedir (Tannenbaum vd., 2015). Diğer yandan, pandemi sürecinde gerçekleştirilen KSS girişimlerinin genel olarak bireylerin korkuyla baş etme yolları olan problemleri ortadan kaldırma veya azaltma çözümlerine odaklandığı görülmüştür. Korku çekiciliğine ilaveten sosyal mübadele teorisinin karşılıklılık ilkesini de dikkate alarak bireylerin pandemi döneminde karşılaştıkları korkularıyla baş etmelerini destekleyen KSS girişimlerine karşı olumlu tutum ve ahlaki duygular geliştirebileceklerini; bu itibarla Covid-19 korku düzeyinin algılanan KSS girişimleriyle firmayı savunma davranışları arasındaki ilişkiye aracılık eden tutum ve ahlaki duygular üzerinde düzenleyici rolünün olabileceğini öne sürüyoruz.

H₄: Tüketicilerin Covid-19 korkularının KSS girişimine karşı geliştirdikleri şükran duyguları üzerinde düzenleyici rolü vardır.

H₅: Tüketicilerin Covid-19 korkularının KSS girişimine karşı olan tutumları üzerinde düzenleyici rolü vardır.

YÖNTEM

Araştırma, deneysel tasarım şeklinde nicel araştırma deseni çerçevesinde gerçekleştirilmiştir. Bu kapsamda, deneklerin gruplara atanıp farklı deneme koşullarına tabi tutulduğu bir deneysel tasarım olan gruplar arası desen uygulaması esas alınarak rastlantısal bir biçimde oluşturulan bir deney ve bir kontrol grubu aracılığıyla hipotezlerimiz sınanmıştır.

İçerikleri tarafımızca düzenlenen ve bir firmanın KSS eylemlerini anlatan senaryolar araştırmamızın bağımsız değişkenlerini oluşturmuştur. Markanın bilinirliğinin ve faaliyette bulunduğu sektörlerin denekler üzerindeki olası etkilerini kontrol etmek amacıyla ismi, misyonu, vizyonu ve iştirak alanları fiktif biçimde tarafımızca kurgulanan bir holdingin KSS

faaliyetlerinin anlatıldığı nötr bir tanıtım metni tasarlanmıştır. Kontrol grubuna okutulan söz konusu metinde, Carroll'ın KSS piramidindeki ilk üç boyuta ilişkin faaliyetlere yer verilmekle birlikte piramidin en tepesindeki gönüllülük (hayırseverlik) boyutunu içeren herhangi bir girişime değinilmemiştir. Deney grubu için kurgulanan metinde ise kontrol grubu için hazırlanan metne ilaveten piramidin en üstteki boyutunu (hayırseverlik) da kapsayacak biçimde pandemi döneminde karşılaşılan sağlıkla ilgili sorunların etkisini azaltmayı amaçlayan bir KSS eylemi daha eklenmiştir (Ek1-2).

Araştırmamız kapsamındaki veri toplama çalışmalarına 2022 yılının temmuz ayında başlanarak 2023 yılının mart ayına kadar devam edilmiştir. Veri toplama periyodumuz pandemi kısıtlamalarının azaltıldığı veya tamamen kaldırıldığı bir döneme tesadüf ettiği için yüz yüze görüşülen anket katılımcılarına soruları yanıtlamadan önce Covid-19 pandemisinin ortaya çıkışı ve yayılışı esnasında yaşanan trajik gelişmeleri içeren, tarafımızca hazırlanan bir video izletilmiştir. Bu yolla katılımcıların koronavirüs korkularını salgının olumsuz etkilerinin en şiddetli hissedildiği dönemlerdeki düzeylere yakınlaştırma amaçlanmıştır.

Deneyisel araştırmalarda, her grupta 15'er denneğin olması sonuçların geçerli olmasını sağlayabilmekle birlikte, literatürde genel itibarıyla her grupta en az 30'ar denneğin bulunması önerilmektedir (Gay, 1987). Bu itibarla, ön teste ilişkin deney grupları 15'er kişiden, hipotez testlerimizin sınındığı deney grupları ise 40'ar kişiden oluşturulmuştur.

Ön test kapsamında, iki grubun her birine rastgele atanan 15'er kişiye ilgili metinler okutulmuştur. Deneklere "Holding, Covid-19 ile mücadele etme konusunda sosyal açıdan ne kadar sorumluluk göstermektedir?" sorusu yöneltilmiş ve ilgililerin 1'in "son derece az" ve 11'in "son derece fazla" olduğu 11 puanlık bir ölçekte değerlendirme yapmaları sağlanmıştır. Bu yolla, tarafımızca kurgulanan iki farklı metindeki KSS faaliyetlerinin Covid-19 kaynaklı sorunlarla ne derece ilintili olduğunun ve birbirleri arasında istatistiksel açıdan anlamlı bir fark bulunup bulunmadığının test edilmesi amaçlanmıştır. Bu kapsamda tek yönlü varyans analizi (ANOVA) gerçekleştirilmiştir.

Levene testi sonucunda $p > 0,05$ olduğundan varyansların eşitliği varsayımı doğrulanmıştır ($L=0,277$; $p=0,842$). Kontrol grubu için oluşturulan metindeki firmanın algılanan sosyal sorumluluk puanı ortalaması ($M=2,87$; $SD=1,18$), deney grubu için oluşturulan metindeki firmanın algılanan sosyal sorumluluk puanı ortalaması ise ($M=9,8$; $SD=0,94$) olmuştur. Ayrıca, gerçekleştirilen Post-Hoc Tukey HSD testi sonucunda ise her bir gruptaki firmanın algılanan sosyal sorumluluk düzeyinin diğerinden anlamlı bir biçimde farklı olduğu saptanmıştır.

ANALİZ VE BULGULAR

Türkiye'de gerçekleştirdiğimiz çalışmamız kısmi en küçük kareler yapısal eşitlik modellemesi (PLS-SEM) üzerine kurulmuştur. PLS-SEM küçük örneklem setiyle analiz yapmaya olanak sağlaması, normal dağılım şartı aramaması ve hem yansıtıcı hem de biçimlendirici yapıları açıklaması nedeniyle tercih edilmiş olup, bu çerçevedeki analizlerimiz Smart PLS-4 yazılımı kullanılarak gerçekleştirilmiştir.

İlk olarak yapılan ölçümlerin psikometrik uygunluklarını değerlendirmek üzere Doğrulayıcı Faktör Analizi (DFA) yapılmıştır. Hair ve diğerleri (1998); DFA sonucu elde edilen faktör yüklerinin $\geq 0,7$ olması gerektiğini ifade etmişlerdir. Modelimizde yer alan örtük değişkenlere ait göstergelerin faktör yüklerinin 0,7'den büyük olduğu belirlenmiştir. İkinci aşamada yapılar arasındaki ilişkiler geçerlilik ve güvenilirlik analizleriyle incelenmiştir. Bu kapsamda iç tutarlılık güvenilirliği (CA =Cronbach Alfa ve CR =Composite Reliability), birleşme geçerliği (faktör yükleri ve AVE =Average Variance Extracted değerleri) ve ayrışma geçerliği Fornell ve Larcker (1981) tarafından önerilen kriter ile Henseler ve diğerleri (2015) tarafından önerilen HTMT kriteri kullanılmıştır. DFA analizi sonucu elde edilen yapıların, Cronbach Alfa ve CR katsayılarının eşik değer olan 0,7'den büyük oldukları (Hair vd. 1998, 2017) ve böylece iç tutarlılık güvenirliliğinin sağlandığı görülmüştür. Ayrıca, yapıların AVE değerlerinin eşik değer

olan 0,50'den büyük olduğu (Fornell ve Larcker, 1981) dikkate alınarak birleşme geçerliğinin de sağlandığı anlaşılmıştır.

Modelin ayrışma geçerliğinin belirlenmesinde, Fornell ve Larcker (1981) ve Henseler ve diğerleri (2015) tarafından önerilen kriterler dikkate alınmıştır. Modelde yer alan yapıların AVE değerlerinin karekökleri, modelde yer alan yapılar arasındaki korelasyonlardan yüksek olduğu için Fornell ve Larcker kriterinin sağlandığı anlaşılmıştır. Henseler ve diğerlerin (2015) öne sürdüğü HTMT kriteri (Heterotrait Monotrait Ratio); modelde yer alan tüm yapılara ait ifadelerin korelasyonlarının ortalamasının ifadelerin geometrik ortalamalarına oranlarını ifade etmekte ve HTMT değerinin, 0,9'un altında olması gerekmektedir. Modelimizde HTMT kriteri de sağlanmıştır.

Genel olarak değerlendirildiğinde ölçüm modelinin; iç tutarlılık ve birleşme güvenilirliği ile ayrışma ve birleşme geçerliliğine sahip olduğu belirlenmiş, dolayısıyla ölçüm modeli kabul edilebilir bulunmuştur.

Yapısal model, çalışmamızda olduğu üzere keşfedici amaçlarla kullanıldığında uyum iyiliği kriterlerinin değil, örneklem ile model arasındaki uyum gücünün değerlendirilmesi önerilmektedir (Henseler, 2018). Bu doğrultuda modelin kabul edilebilir uyuma sahip olması için gözlenen korelasyon ile modelin korelasyon matrisi arasındaki fark olarak tanımlanan standartlaştırılmış ortalama hataların karekökü değerinin (SRMR-Standardised Root Mean Square Residual) 0,08'den küçük olması (Hu ve Bentler, 1999), örneklem sayısı ile pozitif ilişkili olan ve modelin temel ya da sıfır hipoteziyle olan uygunluğunu belirten normlaştırılmış uyum indeksi değerinin (NFI-Normed Fit Indices) ise 0,8'den büyük (Forza ve Filippini, 1998) olması beklenmektedir. SRMR değeri 0,063, NFI değeri 0,820 olan modelin uyumu kabul edilebilir bulunmuştur.

Yapısal modele ilişkin doğrusallık, determinasyon katsayısı ve etki büyüklüğünü hesaplamak için PLS-SEM algoritması; tahmin gücünü hesaplamak için ise PLS Predict analizi yapılmıştır. Cohen'e (1988) göre etki büyüklüğü katsayısının (f^2) $\geq 0,02$ olması düşük, $\geq 0,15$ olması orta ve $\geq 0,35$ olması yüksek etkiyi göstermektedir. Etki büyüklüğü katsayıları incelendiğinde; modelde KSS Girişimi -> Yatırım, Tutum -> Olumlu AAİ arasındaki etki büyüklükleri düşük bulunmuştur. Değinilenlerin haricindeki etki büyüklükleri ise orta ve yüksek seviyede şekillenmiştir. Determinasyon katsayısı olan R^2 katsayısının 0,75, 0,50 ve 0,25 eşik değerleri sırasıyla güçlü, orta ve zayıf açıklayıcılık gücünün göstergesi olarak dikkate alınmaktadır (Hair vd., 2011). Modelimizde tüm değişkenler yüksek açıklanma oranlarına sahiptir. Q^2 ölçüsü modelin tahmin geçerliliğinin bir göstergesidir. Yapısal modelin Q^2 değerinin sıfırdan büyük olması, tahmin geçerliliğinin sağlandığını gösterir (Hair vd., 2011). Modelimizde tahmin geçerliliği sağlanmıştır. Yani model gizli değişkenleri iyi bir şekilde tahmin edebilmektedir. Modelimizde gizil değişkenler arasındaki VIF değerlerinin 5'ten küçük olduğu; bu itibarla gizil değişkenler arasında çoklu iç ilişki problemi olmadığı anlaşılmıştır.

SMART PLS 4 Process Makro önyükleme (bootstrapping) işleminde %95 güven aralığı, 10.000 alt-örneklem ve çift kuyruklu testle yapısal modelin yol değerleri (β), güvenilirlik ve anlamlılığı (t ve p değerleri) incelenmiştir. Söz konusu incelemeye ait veriler ile yukarıda açıklanan değerlerin detayına Tablo 1'de yer verilmiştir.

Tablo 1- Yapısal Modelin Değerlendirilmesi ve Sonuçları

Yollar ve Değişkenler	f^2	R^2	Q^2	VIF	Beta (β)	t-değeri	p-değeri
Covid-19 Korkusu -> Tutum	0,831	-	-	1,051	0,526	6,721	0,000
Covid-19 Korkusu -> Şükran	0,364	-	-	1,051	0,009	0,071	0,944
KSS Girişimi -> Tutum	1,030	-	-	1,051	0,974	10,386	0,000
KSS Girişimi -> Şükran	0,529	-	-	1,051	0,943	8,673	0,000
Tutum -> Olumlu AAİ	0,112	-	-	3,723	0,314	3,178	0,001

INTERNATIONAL TOPKAPI CONGRESS VI

Yollar ve Değişkenler	f ²	R ²	Q ²	VIF	Beta (β)	t-değeri	p-değeri
Tutum -> Yatırım	0,165	-	-	3,723	0,502	2,525	0,012
Şükran -> Olumlu AAİ	0,170	-	-	1,848	0,261	2,801	0,005
Şükran -> Yatırım	0,315	-	-	1,848	0,484	3,154	0,002
Olumlu AAİ	-	0,775	0,209	-	-	-	-
Tutum	-	0,827	0,284	-	-	-	-
Yatırım	-	0,594	0,342	-	-	-	-
Şükran	-	0,533	0,248	-	-	-	-
Direkt Etki							
KSS Girişimi -> Olumlu AAİ	0,229	-	-	3,205	0,807	3,381	0,001
KSS Girişimi -> Yatırım	0,024	-	-	3,205	-0,354	1,305	0,192
Düzenleyicilik Etkisi							
Covid-19 Korkusu x KSS Girişimi -> Tutum	-	-	-	-	-0,274	3,317	0,001
Covid-19 Korkusu x KSS Girişimi -> Şükran	-	-	-	-	0,765	5,358	0,000
Aracılık Etkisi							
KSS Girişimi -> Tutum -> Olumlu AAİ	-	-	-	-	0,470	2,945	0,003
KSS Girişimi -> Şükran -> Olumlu AAİ	-	-	-	-	0,272	2,354	0,019
KSS Girişimi -> Tutum -> Yatırım	-	-	-	-	0,752	2,449	0,014
KSS Girişimi -> Şükran -> Yatırım	-	-	-	-	0,505	2,440	0,015

Hipotez testlerinin sonuçları aşağıda özetlenmiştir.

Tablo 2- Hipotez Sonuçları

Hipotezler	Yollar	Sonuç
H ₁	KSS Girişimi->Yatırım	Desteklenmedi
	KSS Girişimi->Olumlu AAİ	Desteklendi
H ₂	KSS Girişimi -> Şükran -> Olumlu AAİ**	Desteklendi
	KSS Girişimi -> Şükran -> Yatırım*	Desteklendi
H ₃	KSS Girişimi -> Tutum -> Olumlu AAİ**	Desteklendi
	KSS Girişimi -> Tutum -> Yatırım*	Desteklendi
H ₄	Covid-19 Korkusu x KSS Girişimi -> Şükran	Desteklendi
H ₅	Covid-19 Korkusu x KSS Girişimi -> Tutum	Desteklendi

* Şükran ve tutum tam aracıdır. **Şükran ve tutum kısmi aracıdır.

TARTIŞMA VE SONUÇ

Kriz ortamında geliştirilen KSS faaliyetlerinin marka savunuculuğu davranışlarını nasıl ve hangi aracı değişkenler vasıtasıyla etkilediğinin incelendiği araştırmamızda kriz ögesi olarak Covid-19 pandemisi ele alınmıştır. Çalışmamızda ayrıca Covid-19 korkusunun söz konusu aracı değişkenler üzerindeki düzenleyici rolü değerlendirilmiştir.

İçerikleri tarafımızca düzenlenen ve bir holdingin KSS eylemlerini anlatan iki adet senaryo araştırmamızın kategorik bağımsız değişkenlerini oluşturmuştur. Kontrol grubu için tasarlanan senaryoda, Carroll'ın KSS piramidindeki ilk üç boyuta ilişkin faaliyetlere yer verilmekle birlikte piramidin en tepesindeki gönüllülük (hayırseverlik) boyutunu içeren herhangi bir girişime değinilmemiştir. Deney grubu için kurgulanan metinde ise kontrol grubu için hazırlanan metne ilaveten piramidin en üstteki hayırseverlik boyutunu da kapsayacak biçimde

pandemi döneminde karşılaşılan sağlıkla ilgili sorunların etkisini azaltmayı amaçlayan bir KSS eylemi daha eklenmiştir.

Markayı savunma davranışları olarak olumlu ağızdan ağıza iletişim ve markaya yatırım yapma niyeti ele alınmıştır. Neticede algılanan kurumsal sosyal sorumluluğun markaya yatırım yapma bağımlı değişkeni üzerinde anlamlı bir etkisinin bulunmadığı ancak diğer bir bağımlı değişken olan olumlu ağızdan ağıza iletişim üzerinde anlamlı bir etkisinin olduğu belirlenmiştir.

Çalışmamızda, olumlu ahlaki duygu ve tutumların, tüketicilerin kriz dönemlerinde geliştirilen KSS eylemlerine karşı verdikleri tepkiler olduğu ve bunların KSS faaliyetleri ile markayı savunma davranışları arasındaki ilişkide aracılık etkilerinin bulunduğu öne sürülmüştür. Olumlu ahlaki duygu olarak ele alınan şükran duygusunun ve tutumun söz konusu ilişkide aracılık rollerinin bulunduğu saptanmıştır. Bu rol algılanan kurumsal sosyal sorumluluğun markaya yatırım yapma niyeti üzerindeki etkisinde tam aracılık şeklindeyken algılanan kurumsal sosyal sorumluluğun olumlu ağızdan ağıza iletişim üzerindeki etkisinde kısmı aracılık şeklinde oluşmuştur.

Küresel bir kriz olan koronavirüs pandemisinden kaynaklanan Covid-19 korkusunun algılanan kurumsal sosyal sorumluluk ile firmayı savunma davranışları arasındaki ilişkiye aracılık eden tutum ve olumlu ahlaki duygular üzerinde düzenleyici etkisinin olduğunu gösteren çalışmamız, bu yönüyle literatüre ilave katkı sağlamıştır. Bu doğrultuda tüketicilerin Covid-19 korkularının algılanan kurumsal sosyal sorumluluğa karşı duydukları şükran duygusu üzerindeki düzenleyici etkisi pozitifken algılanan kurumsal sosyal sorumluluğa karşı oluşturdukları tutumları üzerindeki düzenleyici etkisi negatif bulunmuştur. Modelimizde tutumun bilişsel değerlendirmeler şükranın ise duygusal yanıtlar üzerinden ölçüldüğü dikkate alındığında, Covid-19 korkusunun söz konusu düzenleyici etkisinin bilişsel süreçlerde negatif, duygusal bileşenlerde ise pozitif olduğu anlaşılmıştır.

Çalışmamız şirket yöneticileri için de önemli sonuçlar içermektedir. Zira hem bilişsel hem de duygusal süreçlerin tüketicilerin KSS girişimlerine verdiği tepkileri etkilediği ve her iki sürecin de tüketicilerin markalarla ilişki kurmalarında önemli olduğu ortaya konmuştur. Ayrıca, olağan üstü kriz dönemlerinde ortaya çıkan korkunun tüketicilerin duygusal tepkileri üzerinde pozitif, tutumsal tepkileri üzerinde ise negatif düzenleyici etkisinin bulunduğu belirlenmiştir. Bu itibarla korkunun en yüksek olduğu kriz dönemlerinde tüketicilerin duygusal tepkilerini tetikleyen iletişim programlarının geliştirilmesi, konu korkunun azaldığı dönemlerde ise tüketicilerin bilişsel tepkilerini hedefleyen programların önceliklendirilmesi önerilmiştir.

Bu araştırmanın katılımcıları İstanbul’da ikamet eden 18 yaş ve üzeri bireyler ile sınırlıdır. Ayrıca, veri toplama çalışmalarımız pandemi kısıtlamalarının azaltıldığı veya tamamen kaldırıldığı dolayısıyla bireylerin Covid-19 korkularının görece azaldığı bir dönemde gerçekleştirilmiştir. Gelecekte yapılacak çalışmaların sosyal krizin olumsuz etkilerinin en yüksek olduğu dönemlerde gerçekleştirilmesi ve araştırma sahasının genişletilmesi tavsiye edilmektedir.

Ek 1- Kontrol Grubu İçin Oluşturulan Senaryo

1960 yılında kurulan ACS Holding A.Ş. (Holding), bünyesinde gıda, ilaç, kimya ve teknoloji başta olmak üzere birçok sektörden toplam 16 şirket barındırmakta olup, söz konusu şirketler topluluğu Türkiye’nin yanı sıra toplam 11 Avrupa ülkesinde yaklaşık 50 bin çalışan ile faaliyet göstermektedir.

Hisse senetleri Borsa İstanbul nezdindeki “Holding ve Yatırım Endeksinde” işlem gören ACS Holding, hisseleri söz konusu endekste işlem gören rakiplerinin ortalamasına benzer biçimde son 5 yılda konsolide net kârını ortalama %20 artırmıştır. Holding ve Holding’e bağlı şirketlerde vergi ve diğer yasal yükümlülükler uygun hareket edilmekte, çalışanlara Sosyal Güvenlik Kurumu gereklilikleri başta olmak üzere, özel sağlık sigortası, hayat sigortası, servis, yemek, cep telefonu hakkı verilmektedir. Grup şirketleri tarafından çalışanlara tanınan ücret ve yan haklar, faaliyette bulunulan ülkelerdeki piyasa koşullarına göre tatminkâr düzeyde olup,

ilaveten yarı zamanlı veya tam zamanlı çalışan farkı gözetmeksizin tüm personele kişisel ve mesleki gelişimleri için eğitim olanağı da sunulmaktadır.

ACS Holding'in temel çevre politikası, atığın önlenmesi, azaltılması, yeniden kullanılması, geri dönüştürülmesi ve yeniden kazanılmasına dayanmaktadır. Holding'e bağlı şirketlerin üretim tesislerinde ortaya çıkan kullanılabilir durumdaki tüm atıklar yeniden kullanılmakta, geri dönüştürülmeye ve geri kazanılmaya uygun olanlar ise bu konuda uzman olan lisanslı şirketlere teslim edilmektedir. Holding'in, bünyesindeki şirketlerin atık sularının kirlilik düzeyine ilişkin belirlediği üst sınırlar, bu firmaların faaliyet gösterdikleri ülkelerde yerel yasalarca izin verilen limitlerin oldukça altındadır. Holding, ISO 14001 çevre yönetim sistemine ilaveten bizzat oluşturduğu standart ve mevzuat gerekliliklerinin gruba bağlı tüm şirketlerde uygulanmasını zorunlu tutmakta ve söz konusu gerekliliklere olan uyumu periyodik olarak bağımsız kuruluşlara yaptırdığı denetimlerle kontrolü altında tutmaktadır.

Ek 2- Deney Grubu İçin Oluşturulan Senaryo

1960 yılında kurulan ACS Holding A.Ş. (Holding), bünyesinde gıda, ilaç, kimya ve teknoloji başta olmak üzere birçok sektörden toplam 16 şirket barındırmakta olup, söz konusu şirketler topluluğu Türkiye'nin yanı sıra toplam 11 Avrupa ülkesinde yaklaşık 50 bin çalışan ile faaliyet göstermektedir.

Hisse senetleri Borsa İstanbul nezdindeki "Holding ve Yatırım Endeksinde" işlem gören ACS Holding, hisseleri söz konusu endekste işlem gören rakiplerinin ortalamasına benzer biçimde son 5 yılda konsolide net kârını ortalama %20 artırmıştır.

Holding ve Holding'e bağlı şirketlerde vergi ve diğer yasal yükümlülüklerine uygun hareket edilmekte, çalışanlara Sosyal Güvenlik Kurumu gereklilikleri başta olmak üzere, özel sağlık sigortası, hayat sigortası, servis, yemek, cep telefonu hakkı verilmektedir. Grup şirketleri tarafından çalışanlara tanınan ücret ve yan haklar, faaliyette bulunan ülkelerdeki piyasa koşullarına göre tatminkâr düzeyde olup, ilaveten yarı zamanlı veya tam zamanlı çalışan farkı gözetmeksizin tüm personele kişisel ve mesleki gelişimleri için eğitim olanağı da sunulmaktadır.

ACS Holding'in temel çevre politikası, atığın önlenmesi, azaltılması, yeniden kullanılması, geri dönüştürülmesi ve yeniden kazanılmasına dayanmaktadır. Holding'e bağlı şirketlerin üretim tesislerinde ortaya çıkan kullanılabilir durumdaki tüm atıklar yeniden kullanılmakta, geri dönüştürülmeye ve geri kazanılmaya uygun olanlar ise bu konuda uzman olan lisanslı şirketlere teslim edilmektedir. Holding'in, bünyesindeki şirketlerin atık sularının kirlilik düzeyine ilişkin belirlediği üst sınırlar, bu firmaların faaliyet gösterdikleri ülkelerde yerel yasalarca izin verilen limitlerin oldukça altındadır. Holding, ISO 14001 çevre yönetim sistemine ilaveten bizzat oluşturduğu standart ve mevzuat gerekliliklerinin gruba bağlı tüm şirketlerde uygulanmasını zorunlu tutmakta ve söz konusu gerekliliklere olan uyumu periyodik olarak bağımsız kuruluşlara yaptırdığı denetimlerle kontrolü altında tutmaktadır.

ACS Holding, Koronavirüs salgınının olumsuz etkilerinin en yoğun olarak hissedildiği dönemde gerçekleştirdiği sosyal sorumluluk projesiyle toplumsal hayata destek olmayı amaçlamıştır. Bu doğrultuda Holding, Sağlık Bakanlığı ile iş birliği yapılarak pandemi hastanelerinde görev yapan sağlık personelinin korunması için çok sayıda maske, dezenfektan, koruyucu gözlük ve tulumun yanı sıra yoğun bakım hastalarının tedavilerinde kullanılmak üzere suni solunum cihazı (ventilatör) tedarik etmiştir. Holding'in kurumsal sosyal sorumluluk bütçesinin tamamına yakını kullanılarak hayata geçirilen söz konusu projeye, salgınla olan savaşta en ön safta yer alan sağlık personelinin koronavirüse yakalanma riski ile koronavirüs hastalarının ölüm risklerinin azaltılması hedeflenmiştir.

KAYNAKÇA

- Addo, P. C., Jiaming, F., Kulbo, N. B., & Liangqiang, L. (2020). COVID-19: fear appeal favoring purchase behavior towards personal protective equipment. *The Service Industries Journal*.
- Beck, A. T., Rush, J. A., Shaw, B. F., & Emery, G. (1979). *Cognitive therapy of depression*. New York: Guilford Press.
- Bhattacharya, C. B., & Sen, S. (2003). Consumer-company identification: A framework for understanding consumers' relationships with companies. *Journal of Marketing*.
- Carroll, A. B. (1991). The pyramid of corporate social responsibility: Toward the moral management of organizational stakeholders. *Business Horizons*.
- Forza, C. & Filippini, R. (1998). TQM impact on quality conformance and customer satisfaction: A causal model. *International Journal of Production Economics*.
- Cohen J. E. (1988). *Statistical Power Analysis for the Behavioral Sciences*. Hillsdale, NJ: Lawrence Erlbaum Associates.
- Folkman S. (1984) Personal Control and stress and coping processes: A theoretical analysis. *Journal of Personality and Social Psychology*.
- Fornell Claes & Larcker David F. (1981), "Evaluating structural equation models with unobservable variables and measurement error", *Journal of Marketing Research*.
- Frijda, N. H. (1986). *The emotions*. Cambridge University Press.
- Gay, L. R. (1987). *Educational research competencies for analysis and application*. London: Merrill Publishing Company.
- Gore, P., Madhavan, S., Curry, D., McClurg, G., Castiglia, M., Rosenbluth, A. S. & Smego, A. R. (1998). *Persuasive Messages*. Marketing Health Services.
- Hair, J.F.; Tatham, Ronald L., Anderson, Rolph E.; Black, William (1998), *Multivariate data analysis with readings*, 5th Edn. Englewood Cliffs, NJ: Prentice Hall.
- Hair, J.F.; Ringle, C. M., and Sarstedt, M. (2011). PLS-SEM: Indeed a silver bullet. *The Journal of Marketing Theory and Practice*.
- Hair, J. F., Matthews, L. M., Matthews, R. L. ve Sarstedt, M. (2017). PLS-SEM or CB-SEM: updated guidelines on which method to use. *International Journal of Multivariate Data Analysis*.
- Henseler, J., Ringle, C.M. & Sarstedt, M. (2015). A new criterion for assessing discriminant validity in variance-based structural equation modeling. *Journal of the Academy of Marketing Science*.
- Henseler, J. (2018). Partial least squares path modeling: Quo vadis? *Qual Quant*.
- Hu, L. & Bentler, P. (1999). Cutoff criteria for fit indices in covariance structure analysis: conventional criteria versus new alternatives. *Structural Equation Modeling*.
- Kağıtçıbaşı, Çiğdem (2013), *Günümüzde İnsan ve İnsanlar*, 15. Baskı, Psikoloji-Psikiyatri Dizisi:1.
- Kee-Hong Bae, Sadok El Ghouli, Zhaoran (Jason) Gong & Omrane Guedhami (2021). Does CSR matter in times of crisis? Evidence from the COVID-19 pandemic. *Journal of Corporate Finance*.
- Khanchel Imen, Lassoued Naima & Gargouri Rym (2023), CSR and firm value: is CSR valuable during the COVID 19 crisis in the French market?, *Journal of Management and Governance*.
- Kigatiira, Kinya K. (2020). Efficacy of fear appeals on adoption of Covid19 preventive measures: A case of boda boda riders in Nairobi county, Kenya. *International Journal of Research- Granthaalayah*.
- Kim, S. and Choi, S.M. (2016), "Congruence effects in post-crisis CSR communication: the mediating role of attribution of corporate motives", *Journal of Business Ethics*.

Koch, T., Benno Viererbl, Johannes Beckert & Juliane Keilmann (2023). CSR in times of crisis: why CSR activities can be both a blessing and burden during an organizational crisis, *Journal of Communication Management*.

Lazarus, R. S. (1991). *Emotion and adaptation*. Oxford University Press.

Lazarus, R. S., & Lazarus, B. N. (1994). *Passion and reason: Making sense of our emotions*. New York: Oxford University Press.

McCullough, M. E., S. D. Kilpatrick, R. A. Emmons & D. B. Larson: 2001, 'Is Gratitude a Moral Affect?', *Psychological Bulletin*.

Naeem, M. (2021). Do social media platforms develop tourist panic buying during the fear of Covid-19 pandemic? *Journal of Retailing and Consumer Services*.

Peloza, J., & Shang, J. (2011). How can corporate social responsibility activities create value for stakeholders? A systematic review. *Journal of the Academy of Marketing Science*,

Sen, S., Bhattacharya, C. B., & Korschun, D. (2006). The role of corporate social responsibility in strengthening multiple stakeholder relationships: A field experiment. *Journal of the Academy of Marketing Science*.

Tangney, J. P., Stuewig, J., & Mashek, D. J. (2007). Moral emotions and moral behavior. *Annual Review of Psychology*.

Tannenbaum, M. B., Hepler, J., Zimmerman, R. S., Saul, L., Jacobs, S., Wilson, K., & Albarracín, D. (2015). Appealing to fear: A meta-analysis of fear appeal effectiveness and theories. *Psychological bulletin*.

REFLECTION OF THE PEASANT PROBLEM IN ROMANIAN PAINTING
FROM THE SECOND HALF OF THE 19TH CENTURY TO
THE BEGINNING OF THE 20TH CENTURY

Associate Professor CRISTINA GUDIN

Faculty of History, University of Bucharest, Romania

ORCID 0009-0002-2912-013X

ABSTRACT

This study examines how the most significant social problem that Romania faced, namely the peasant problem, was depicted in painting. For this purpose, several paintings inspired by the village world were selected, taking into account the authors' ability to reflect the village life of the peasants, the quality of the compositions, the chromatics, and the artistic technique. The paintings' contribution to creating a current of opinion favorable to the peasantry was also significant, representing a factor that encouraged the authorities to adopt measures aimed at improving the lives of the villagers. From the selected paintings, one can observe the evolution from the idyllic representation of the village to a more realistic representation, towards the end of the analyzed period. Therefore, in the second half of the 19th century, compositions predominated in which peasants, especially young ones, were captured during routine activities that did not require much physical effort from them (such as spinning wool, shepherding, transporting with ox-drawn carts, and carrying water). Compositions were added where peasants were painted in moments of relaxation (dancing, participating in the fair). These peasants, neatly dressed, transmit health and good cheer, resulting in paintings that emanate optimism and confidence in a bright future for the peasants. However, at the end of the 19th century and the beginning of the 20th century, some paintings reflect the poverty, abuses, and injustices that were part of the daily life of the peasants. The villagers appear in these compositions angry, hungry, with ragged clothes, ready to take justice for themselves, after the authorities have betrayed their expectations. The representations become more realistic, the chromatic palette is characterized by contrasts and gloomy tones, reflecting the mood of the peasants and the precarious economic condition of most of them.

KEYWORDS: painting, peasantry, village, uprising, Romania, idealization, realism

INTRODUCTION

The purpose of this study is to capture the extent and manner in which the most important social problem that Romania faced, namely the peasant problem, was reflected in painting. Before, however, focusing on some of the paintings inspired by the realities of the village, we consider it necessary to briefly present the situation of the peasantry in the second half of the 19th century and the beginning of the 20th century. By doing so, the relevance of the subject under analysis will be better understood.

Therefore, it is good to know that the peasantry was the most numerous social category, according to the statistics of 1859, 82% of the total of 3,865,000 inhabitants of the country being villagers [1]. The preponderance of the peasantry gave Romanian society an agrarian, traditional character, which was preserved over time, despite the intensification of the modernization process and the development of industry in the last decades of the 19th century. At the same time, the peasantry represented the productive and contributory base of the country, which is why the peasant problem was a national problem with social, economic, political, cultural, and medical implications. Practicing agriculture on plots rented from landowners

against burdensome obligations, peasants became landowners through the Rural Law of 1864. It was the first substantial measure that attempted to improve the situation of peasants, the intention being to transform them into economically independent persons. The lands granted to peasants came from the state and from large landowners. Of the 1,994,588 ha given to them, 800,306 ha belonged to the state, and 1,194,282 ha to the landowners [2].

On average, peasants were granted 4 hectares of land, but irregularities in the application of the rural law meant that villagers received either insufficient land or none at all (as was the case for about 60,000 families). As a result, the need for arable land remained unsatisfied, which is why agricultural contract laws were introduced in 1866, 1882, and 1907. In other words, peasants could lease from landlords the land they needed to survive. The landowners imposed various conditions, which increased over time, including: 10% of the harvest from the leased plot, working days, and various services (guard, transport, etc.). As a result of the abusive conditions, the peasants reacted by suing the landowners, ceding the manors, and moving to where the rent was easier.

Regarding the disproportionate distribution of arable land that explains the abuse of the peasants, we recall that around the First World War, large property predominated. Thus, estates of over 100 hectares each, owned by about 5,400 landowners, totaled 3,810,350 hectares and represented 50% of the arable area of Romania. Added to this were medium-sized properties, of 50-100 hectares each, which constituted 2% of the country's cultivable area and were owned by 2,400 people. Small property, consisting of plots of land smaller than 10 hectares each, totaled 3,313,797 hectares (40%) and was owned by 5-6 million inhabitants. To have a complete picture of the situation in the rural area, we must also remember the existence of over 2,000,000 peasants completely deprived of arable land [3].

Other causes also contributed to the difficult situation of the peasants, such as: abuses by tax collectors, the use of backward agricultural practices, high illiteracy, limited access to medical services, precarious living conditions, intensified when the harvest was compromised due to unfavorable weather conditions, parasites, and epizootics. The lack of real prospects for improving life, episodes of famine and calamities, epidemics, and high mortality were part of the realities that the peasants faced during the analyzed period.

Politicians tried to solve the aforementioned problems, in which sense people's banks were established (hoping that peasants would thus obtain money to buy lands put up for sale by the state in 1889 and 1908); the association of peasants for the purpose of leasing arable lands was legislated (1904); the emergence of tenant trusts was prohibited (1908), the formation of large tenant trusts. The modernization of villages was encouraged through: the law on burial (1864); the regulation for the alignment of villages and for the construction of peasant houses (1888), the regulation for the water supply of villages (1924); the punishment of unqualified persons who provided medical services (1859), the vaccination of children (1863), the establishment of hospitals in villages (1881).

To educate the peasants, adult courses were established, popular sit-ins were organized, newspapers with a rural focus appeared, and the number of primary schools in villages increased.

However, the majority of the peasants continued to face shortages, the accumulation of which led to the manifestation of frustrations in the form of uprisings, the most extensive of which were those of 1888 and 1907.

RESEARCH METHODOLOGY

In our investigation, we applied several research principles, both qualitative and quantitative. The contextualization of the subject involved the collection of statistical data on the social and economic situation of the peasantry. In this regard, the 1859 census was consulted, but official data were also extracted on the application and effects of the rural law of 1864 or on the distribution of arable land around the First World War. The selection of paintings involved

operating with qualitative principles, so that the most relevant compositions of important painters in the indicated period were chosen.

We particularly used the following research methods:

- The **historical contextualization**, which I carried out in the introduction to this material, was essential in understanding how the peasantry evolved. We explored the political, social, and economic events that influenced the situation of the villagers.
- **Content analysis** involved decoding the message conveyed by the painters through their compositions, as well as highlighting the particular elements of these paintings.
- The **comparative analysis** of the paintings allowed us to reconstruct the evolution that occurred during the analyzed period in the representation of peasants. It also allowed us to observe the differences that existed from one stage to another.

DISCUSSION

Interest in the problems of the peasants increased around the rural reform of 1864 and intensified at the end of the 19th century and the beginning of the 20th century. Agrarian or traditionalist cultural currents contributed to this, namely *sămănătorism* and *poporanism*. Inspired by the realities of the village, they brought them to the attention of the public, contributing to the creation of a current of opinion favorable to the peasants in Romanian society. They idealized, as was the case of *sămănătorism*, or presented the shortcomings of the villages, as did *poporanism*, and tried to sensitize the urban population and the political class, motivating them to increase their efforts in relation to the peasants.

The approach was also joined by painters who created compositions inspired by the world of the village, this being one of the great themes of Romanian fine art throughout the analyzed period. The explanation for the illustration of the village, in addition to the previously mentioned aspects, lies in the fact that the peasant was considered the only authentic exponent of national identity, a position from which he was invested with multiple heroic and mythical meanings.

The result was an abundance of rural-inspired paintings, reflecting the fact that the rediscovery of the folkloric treasure represented an important point in the cultural policy after 1859, the year in which modern Romania was formed through the union of Moldavia and Wallachia.

The academic current manifested itself between 1864-1873 and was the expression of conservatism in art, which opposed romantic exaggerations. Based on the classical tradition and promoted by official art schools, academicism was characterized by meticulousness, impartiality, monotonous compositions, little varied color, and the pyramidal character of the compositions. One of the representatives of Romanian academicism, Gheorghe Tattarescu, intended to create a national album with Romanian figures and landscapes, meaning he traveled around the country, analyzing especially ordinary people, from the people. He failed to break away from the specifics of academic art. In *Peasant woman at harvest*, the woman appears idealized, and her body and posture refer more to a Greek statue, draped in national costume.



Gheorghe Tattarescu, *Peasant woman at harvest* [4]

INTERNATIONAL TOPKAPI CONGRESS VI

However, the artist's concern for highlighting the beauty and variety of folk costumes cannot be denied, an objective that also transpires from the works signed by Carol Popp de Szathmary, an academic painter who, however, gave up on fictional composition in favor of compositions inspired by reality, as can be seen in the *Dragaica Fair* where he managed to realistically capture the hustle and bustle of the crowd, and the people are naturally framed in the surrounding landscape [5].



Carol Popp de Szathmary, *Dragaica Fair* [6]

Unlike Tattarescu's conventional representations of peasants, he reproduced peasants studied in reality, whose figures are more varied, gentle or harsh, young or old, cheerful or sad. Collective compositions, for example, *The Dragaica Fair in Buzau* by Ion Andreescu, where the characters are rendered schematically but correctly, reminiscent of Pissarro through the vigor and direction of the brushstrokes or through the composition of the chromatic palette [7]. We note, however, that the painter neglected the foreground, and that there are empty areas in the composition, which indicates a focus only on the central object. The merits of the work lie in the "bright and well-coagulated color", in the artist's ability to suggest the bustle of the moving crowd, which leads to the impression that we are in front of a broken piece of life.



Ion Andreescu, *Dragaica Fair in Buzau* [8]

Mișu Popp, a painter from Transylvania influenced by the creations of German artists, created, among others, the work *Radu Anghel, the outlaw*, where the fearless folk hero is immortalized carrying an entire arsenal on him, the pistols at his waist, the sword improvised from an agricultural tool, the axe in his hand and the double-barreled rifle he carries on his back being indications of the character's determination to triumph in the confrontation with the aggressors.

Mişu Popp, *Radu Anghel, the outlaw* [9]

This impression is also contributed to by the determined expression on his face, underlined by frowning eyebrows, a fixed gaze, and pursed lips, suggesting an unwavering will to achieve his goal. Empathizing with the oppressed people from whom he himself came, the outlaw fulfilled a patriotic function in the country, a fact suggested by the tricolor ribbon he has tied under his knee. Thus, the outlaw substitutes himself for the authorities incapable of ensuring compliance with the laws, intervening in the sense of stopping abuses and protecting his compatriots [10]. Nicolae Grigorescu approached, like no other before him, aspects of rural life. He was the first Romanian painter who, sensing the poetry of life in nature, approached the village world with interest, joy, and affection. Painting in an impressionistic manner, he tried to order the elements, to exclude excess information and insignificant parts, without being alien to the practice of emphasizing certain elements to reveal his feelings.

The images were far from the figural standard of representation, but they preserved the lineage of reality; only that reality was no longer reproduced, but processed and synthesized [11].

Grigorescu rendered like no other the lasting union of life with the environment, being unparalleled in the representation of patriarchal and peaceful images of oxen carts slowly advancing on dusty roads, of shepherds with sheep, of peasants dreaming or being involved in their daily occupations (such as spinning wool, carrying water) [12].

Nicolae Grigorescu, *Shepherd* [13]Nicolae Grigorescu, *Oxcart* [14]

The ethnographic value of the paintings that immortalize peasants and where the gaze is captured by external aspects, such as costumes and accessories, differentiated according to region, cannot be ignored.

Among Grigorescu's works, it is worth mentioning *Peasant Spinning* or *Peasant from Muscel*.

Nicolae Grigorescu, *Peasant Spinning* [15]Nicolae Grigorescu, *Peasant from Muscel* [16]

They reflect the tendency, noticeable in Romanian art from the analyzed period, of portraying mainly young, healthy, strong women, with gentle features and decent attire, devoid of coquetry, whose simple, clean clothes are a reflection of their very life and character. The idealization of peasants contributed to the visual substantiation of the perception that beauty, modesty, diligence, and morality are inherent to village women. Grigorescu, in particular, captured the feminine aesthetic ideal specific to the area, highlighting the oval of the face, the pressed line of the eyebrows, and the arched cut of the eyelids [17]. Initially intended to capture the everyday life of simple life in the countryside, such images of peasants elevated the banal to the rank of art, idealizing it. Therefore, the artist lent the characters a graceful attitude that does not suggest the weight of the work done, although the reality was that women worked hard, not only in the household, but also in the fields, alongside their men.

However, the representations of the village and its inhabitants change over time for this artist who "saw only the idyllic side of peasant life". Thus, after 1895, Grigorescu entered the period of "tall peasants and shepherds, almost muscleless and boneless, with pink and conventional faces, impersonal, of banal tenderness", placed in a landscape that was also "conventional, whitish, like a theater set" [18]. In other words, due to the excessive repetition of the same themes, conventional works resulted, characterized by mannerism. Even so, the paintings reflect his visual exaltation, as well as his affinity for light and color, manifested through the combinations of tones and shades, Grigorescu retaining his ability to create a relaxed atmosphere and the illusion of movement.

In addition to the paintings with a single character, which account for the majority, the artists also created compositions where the peasants are captured in moments of relaxation that convey a sensation of relaxation to the viewer. This category also includes *The Tavern at Rucăr*, a taboo by Nicolae Grigorescu, where the building is the point of optical interest. Not coincidentally, the pub appears here as a reference element, a kind of axis mundi, thus suggesting its importance in the rural community where, together with the church, it represented the main meeting and socializing space for the villagers [19]. The homogeneity of the composition emerges from the way in which the author ordered the other themes in harmony with the central motif. Through this, the work simultaneously assimilates typical motifs that until then appeared singularly in this author, as is the case of the ox cart or the dusty street.



Nicolae Grigorescu, *The Tavern at Rucăr* [20]

The people bring a welcome effect of movement to the composition, and the natural setting completes the ensemble like a binder, the vegetal notations happily contributing to the chromatic quality of the painting, transforming it into a gem of the genre. The painter's preference for the diurnal aspect is evident, which emerges from the representation of a space governed by strong light, where the villagers are individualized through short strokes, while the painting of the sky and the earth benefits from a much more dynamic approach suggested by the broader strokes [21].

We draw attention to the fact that in the second half of the 19th century, any artistic image put into circulation implicitly became a social and political manifesto, the compositions therefore having propagandistic value and serving to support the long-awaited social reform.

At a time when many artists were concerned with rendering the life of the villagers in a romantic-lyrical perspective, there were also painters who, by bringing the harsh reality to the attention of contemporaries, changed the iconography [22].

Among them, we find Ștefan Luchian, who, probably also due to his own medical condition, empathized with people in suffering, being the first Romanian artist to put rural dramas into opera [23]. In his masterpiece, *When distributing corn*, nature is subordinated to man [24], and the image of disinherited people is rendered, waiting for the authorities to rectify the situation in the form of cereals distributed during an episode of famine.



Ștefan Luchian, *When distributing corn* [25]

Although the composition is not well cohesive, all the figures being arranged on the same line, its merits consist in: "the sober drawing, of astonishing precision, the truth of the silhouettes,

the impression of organized tumult that emerges from the whole, the determined expressions of the characters" [26]. The skill with which the painter managed to render the tension of the moment is noteworthy. This emerges from the compact mass of peasants suggested by the dark row of hats, the entire effect being easily achieved without artifice or a literaryization of the motif. Through exceptional chromatics where the golden light is distributed calmly in a late autumn atmosphere, the dramatic moment is enveloped diaphanously in a whirlwind of sad meditation. In fact, Luchian has here rendered a tragic situation of the exploited peasantry and artistically gives voice to a cry of revolt that seems to burst from their chest [27].

Among the painters, few in number, who highlighted the harshness of the peasants' life, was also Octav Băncilă, whose compositions carry an obvious message of social criticism. Like Ștefan Luchian, who in 1905 came into contact with the cruel reality of the starving peasants in Chiajna, Băncilă also visited the villages in the heat of the uprising in Botoșani and the Olt Valley, and the deprivations and horrors he witnessed became documentary material for the cycle inspired by the 1907 uprising, composed of 12 paintings, not all of which have survived [28].

Among these, I selected *Before 1907* or *The Slave of the Earth*, a painting from the beginning of the cycle where an old man is profiled hugely against a background in harmony with his being.



Octav Băncilă, *Before 1907/The Slave of the Earth* [29]

Standing, his hair blown by the wind, his face weakened by hunger and wrinkled, wearing a ragged shirt, the old man impresses both with his clothes that emphasize his poverty, and with his hands spread out to the sides, with their palms spread out in a gesture of silent despair and interrogation [30].

Even more moving is the composition *1907*, which illustrates a fragment from the time of the uprising with the help of a male character positioned in the foreground, with his shirt open at his chest and running terrified with clenched fists, his gaze squinted with hatred, across a field strewn with the corpses of his fellow villagers.



Octav Băncilă, *1907* [31]

The composition is completed by the peasant who falls pierced by bullets and the old man who, in a last glimmer of life, sticks his fingers into the ground, thereby suggesting the same stubbornness displayed by the central character of the painting.

The background, dominated by the somber tones used to represent the gray sky, contributes to the rendering of the oppressive atmosphere, while the impression of an event captured in full swing is completed by the fires that can be seen on the horizon, reddening it.

The author's empathy with the peasants is also evident from the way he solved the problem, which involved a wide, nervous brushstroke, applying a thick layer of color and throwing the paste onto the canvas under the impulse of the emotion that dominated him. The painting is notable for the tragedy of the immortalized scene, and the impression of dynamism is also evident from the strong color contrasts between the white of the shirts or the reddish trail of the flames and the gray and blue tones of the sky [32]. All of this emphasizes the dynamism of the scene.

Through Ștefan Luchian and Octav Băncilă, the manner of representing peasants in art changed, moving away from false optimism and the picturesque exterior.

CONCLUSION

In conclusion, from the second half of the 19th century, the depiction of the village was a constant concern of Romanian painters, the peasant being considered the only authentic exponent of national identity. In addition, by creating compositions inspired by the lives of peasants, the artists were aware that any artistic image put into circulation implicitly became a social and political manifesto. Therefore, the paintings had propagandistic value and contributed to supporting the economic, social, and cultural reforms whose beneficiaries were the peasants.

During the period analyzed, the representation of peasants evolved from the idealized to the realistic one. In the former, the villagers, in most cases, exude health, youth, and optimism. They have a relaxed attitude and are captured either in moments of relaxation or involved in activities that do not involve considerable physical effort.

These representations contradict the real situation, but find their explanation in the tendency of that time to mythologize the peasant, to transform him into the sole depository of the moral values of the Romanian people. This tendency coincided with the exploitation of national folklore, the development of Romanian culture and art, complementing the efforts of political and economic consolidation of the country.

By highlighting the national specifics, Romanians made their own contribution to the growth of European cultural and artistic heritage; this was one of the concerns of the intelligentsia of that era.

As for the paintings that realistically illustrate the life of peasants, these were made at a time when the villagers became more aware of their rights. By portraying the hungry, poor, and abused peasants, artists showed empathy for their suffering contemporaries and helped this social category to better communicate its demands. Such help was welcome, given that the peasantry, although the largest social category, was the least politically represented and therefore needed the voice and talent of others to convey its message to decision-making authorities.

REFERENCES

- [1] V. Axenciuc, *The economic evolution of Romania. Statistical and historical research (1859-1947)*, vol. II Agriculture, Bucharest, Romanian Academy Publishing House, 1996, p. 15.
- [2] V. Axenciuc, *The economic evolution of Romania. Statistical and historical research (1859-1947)*, vol. II Agriculture, Bucharest, Romanian Academy Publishing House, 1996, p. 93.
- [3] N. Isar, *Modern History of the Romanians (1774/1784-1918)*, Bucharest, University Publishing House, 2006, p. 455.

- [4]<https://www.amazon.com/Color-Paintings-Gheorghe-Tattarescu-Neoclassical-ebook/dp/B0102Q3U0S>
- [5] I. Frunzetti, I. Jianu, *Masters of Romanian Painting*, Bucharest, State Publishing House for Literature and Art, 1953, p. 28.
- [6]https://ro.wikipedia.org/wiki/Fi%C8%99ier:Carol_Popp_de_Szatmary_-_T%C3%A2rgul_Dragaica.jpg
- [7] G. Oprescu, *Romanian Painting in the 19th Century*, Bucharest, Meridiane Publishing House, 1984, p. 240.
- [8]https://upload.wikimedia.org/wikipedia/commons/1/1a/Ion_Andreescu_-_Targ_de_Dragaica.jpg
- [9]https://upload.wikimedia.org/wikipedia/commons/f/fe/Misu_Popp_-_Haiducul_Radu_Anghele.jpg
- [10] I. Frunzetti, *Romanian Art in the 19th Century*, Bucharest, Meridiane Publishing House, 1991, p. 163.
- [11] V. Pușcașu, *Mutations of the plastic form in impressionism and cubism. Towards a possible theory of "artistic revolutions"*, in "Annals of the Lower Danube", XXV, no. 6, 2022, Galatzi, p. 17.
- [12] C. Teacă, *The artist–hero of the nation*, in "Studies and research on history, art, fine arts", volume 6 (50), 2016, p. 83.
- [13] https://commons.wikimedia.org/wiki/File:Nicolae_Grigorescu_-_Ciobanasul.jpg
- [14]<https://www.artnet.com/artists/nicolae-grigorescu/car-cu-boi-pe-cale-de-dimine%C8%9B%C4%83-2FXis6ackLOX8VJBhwu06A2>
- [15]<https://clasate.cimec.ro/Detaliu.asp?tit=pictura-de-sevalet--Grigorescu-Nicolae--Tanara-taranca-torcand&k=9778e12cff024fcfa9fe49acba1dbb92>
- [16][https://ro.wikipedia.org/wiki/%C8%9A%C4%83ranc%C4%83_din_Muscel_\(pictur%C4%83_de_Nicolae_Grigorescu\)#/media/Fi%C8%99ier:Nicolae_Grigorescu_005.jpg](https://ro.wikipedia.org/wiki/%C8%9A%C4%83ranc%C4%83_din_Muscel_(pictur%C4%83_de_Nicolae_Grigorescu)#/media/Fi%C8%99ier:Nicolae_Grigorescu_005.jpg)
- [17] A. Gogâltan, *The image of the peasant woman in Romanian painting from the end of the 19th century and the beginning of the 20th century*, in "Acta Mvusei Napocensis. History", II, no. 47, 2010, p. 232, 234.
- [18] G. Oprescu, *L'art roumain de 1800 à nos jours*, Malmö, 1935, p. 40.
- [19] G.S. Movileanu, *Nicolae Grigorescu*, Bucharest, Meridiane Publishing House, 1986, p. 19
- [20] https://commons.wikimedia.org/wiki/File:Nicolae_Grigorescu_-_Carciuma_la_Rucar.jpg
- [21] V. Ciucă, *In the footsteps of Nicolae Grigorescu*, Bucharest, Sport-Turism Publishing House, 1987, p. 32.
- [22] <https://leviathan.ro/octav-bancila-pictorul-rascoalei-din-1907-de-daniela-sontica/>
- [23] <https://www.criticatac.ro/impactul-rascoalei-din-1907-arta-modern/>
- [24] D. Gui, *Ștefan Luchian and his creative vision*, in "Studies and Communications", Arad, VII, 2001-2002, no. 7, p. 111.
- [25]https://ro.wikipedia.org/wiki/Fi%C8%99ier:Stefan_Luchian_-_La_impertitul_porumbului.jpg
- [26] George Oprescu, *Masters of Romanian Painting in the 19th Century (Grigorescu, Andreescu, Luchian)*, Bucharest, Royal Foundation for Literature and Art, 1947, p. 61.
- [27] V. Drăguț, *Ștefan Luchian*, Bucharest, Meridiane Publishing House, 1968, p. 28.
- [28] M. Epure, *Octav Băncilă*, Bucharest, State Publishing House for Literature and Art, p. 11-13.
- [29] https://ro.wikipedia.org/wiki/Fi%C8%99ier:Octav_Bancila_-_Inainte_de_1907.jpg
- [30] P. Comarnescu, *Octav Băncilă*, Bucharest, Meridiane Publishing House, 1972, p. 21
- [31]https://ro.wikipedia.org/wiki/Octav_B%C4%83ncil%C4%83#/media/Fi%C8%99ier:Octav_Bancila_-_1907.jpg
- [32] V. Cioceanu, *Octav Băncilă*, in "Museum Magazine", 1972, p. 554-555.

**ÜNİVERSİTE ÖĞRENCİLERİNDE OKUPASYONEL DENGE DÜZEYİNİN
AKADEMİK MOTİVASYON ÜZERİNDEKİ ETKİSİNİN İNCELENMESİ**
EXAMINING THE EFFECT OF OCCUPATIONAL BALANCE LEVEL ON ACADEMIC
MOTIVATION IN UNIVERSITY STUDENTS

Dilara KARAKILIÇ

Yüksek Lisans Öğrencisi, Sağlık Bilimleri Üniversitesi, Gülhane Sağlık Bilimleri Enstitüsü,
Ergoterapi Anabilim Dalı, Keçiören, Ankara.

Dr. Volkan TÜRKMEN

Sağlık Bilimleri Üniversitesi, Gülhane Sağlık Bilimleri Enstitüsü,
Biyoistatistik, Keçiören, Ankara

ÖZET

Üniversite dönemi, bireylerin mesleki kimliklerini kazandıkları ve geleceklerini şekillendirdikleri önemli bir süreçtir; bu süreçte öğrencilerin başarılarını etkileyen en temel unsurlardan biri akademik motivasyondur. Bireyin günlük yaşam aktiviteleri, kendine bakım, iş ve serbest zaman uğraşları arasındaki uyumu ifade eden okupasyonel denge kavramı ise, öğrencilerin hem psikolojik iyi oluşları hem de akademik performansları üzerinde belirleyici bir rol oynamaktadır. Bu çalışmanın amacı, üniversite öğrencilerinde okupasyonel denge düzeyinin akademik motivasyon üzerindeki etkisini incelemek ve bu iki değişken arasındaki ilişkinin niteliğini ortaya koymaktır.

Çalışma, üniversitede öğrenim gören ve yaş ortalaması ağırlıklı olarak 21-23 aralığında olan %88,5'i kadın ve %11,5'i erkek olmak üzere 61 üniversite öğrencisi ile gerçekleştirilmiştir. Veri toplama sürecinde sosyodemografik bilgi formuna ek olarak, akademik motivasyon düzeyinin değerlendirilmesi için Akademik Motivasyon Ölçeği ve okupasyonel denge algılarının belirlenmesi amacıyla Aktivite Rol Denge Anketi kullanılmıştır. Elde edilen veriler ile ölçeklerin güvenirlik düzeyleri belirlenmiş, korelasyon ve regresyon analizleri uygulanmıştır. Yapılan korelasyon analizi sonucunda, okupasyonel denge toplamı ile akademik motivasyon toplamı arasında pozitif yönlü orta düzeyde istatistiksel olarak anlamlı ilişki saptanmıştır ($r=0,461$). Özellikle bilmeye ve başarıya yönelik içsel motivasyon alt boyutlarında bu ilişkinin belirgin olduğu görülmüştür. Doğrusal regresyon analizi bulgularına göre, okupasyonel dengenin akademik motivasyonun anlamlı bir yordayıcısı olduğu ve akademik motivasyondaki değişimin %21,20'sini açıkladığı görülmüştür. Bu bulgular, öğrencilerin yaşamlarındaki okupasyonel dengenin artmasının akademik motivasyonlarını da artırdığını göstermektedir. Sonuç olarak, üniversite öğrencilerinin akademik başarılarını artırmak amacıyla, yaşam aktiviteleri arasındaki dengeyi kurmalarını destekleyecek müdahale programlarının geliştirilmesi önerilmektedir.

Anahtar Kelimeler: Üniversite Öğrencileri, Okupasyonel Denge, Akademik Motivasyon

ABSTRACT

The university period is a significant process in which individuals acquire their professional identities and shape their futures; academic motivation is one of the most fundamental elements affecting student success during this process. The concept of occupational balance, defined as the harmony between an individual's activities of daily living, self-care, work/productivity, and leisure occupations, plays a determinative role in both the psychological well-being and academic performance of students. The aim of this study is to examine the effect of occupational balance levels on academic motivation in university students and to elucidate the nature of the relationship between these two variables.

The study was conducted with 61 university students, 88.5% of whom were female and 11.5% male, with an average age predominantly between 21 and 23. In addition to the sociodemographic information form, the Academic Motivation Scale was used to assess academic motivation levels, and the Occupational Balance Questionnaire was used to determine perceptions of occupational balance during the data collection process. The reliability levels of the scales were determined using the data obtained, and correlation and regression analyses were performed. The correlation analysis revealed a statistically significant, moderately positive relationship between the occupational balance total and the academic motivation total ($r=0.461$).

This relationship was particularly evident in the subdimensions of intrinsic motivation related to knowledge and achievement. According to the findings of the linear regression analysis, occupational balance was found to be a significant predictor of academic motivation, explaining 21.20% of the variance in academic motivation. These findings indicate that an increase in occupational balance in students' lives also increases their academic motivation. Consequently, it is recommended that intervention programs be developed to support university students in establishing balance between their life activities in order to increase their academic achievement.

Keywords: University Students, Occupational Balance, Academic Motivation.

1.GİRİŞ

Üniversite dönemi, genç bireylerin akademik performans beklentileriyle başa çıkmaya çalıştığı, sosyal çevrelerini genişlettiği ve gelecekteki kariyerleri için yoğun çaba sarf ettiği, okupasyonel açıdan oldukça hareketli bir evredir. Bu süreçte kişinin; kişisel bakım, sosyal aktiviteler ve akademik sorumluluklar gibi farklı yaşam alanları arasında kurduğu uyumlu ilişki "okupasyonel denge" kavramıyla ifade edilir. Güncel çalışmalar, bu dengenin sadece saatleri planlamaktan ibaret olmadığını; aksine bireyin katıldığı faaliyetlerden ne kadar tatmin olduğu ve bu deneyimlerin niteliğiyle doğrudan ilişkili olduğunu göstermektedir. (Guszkowska & Dąbrowska-Zimakowska, 2025). Özellikle üniversitelerdeki yoğun ders yükü, öğrencilerin bu dengeyi sürdürmesini zorlaştırarak onları okupasyonel dengesizlik riskiyle karşı karşıya bırakmaktadır (Wagman ve ark., 2023).

Akademik motivasyon, öğrencilerin bu karmaşık süreçte eğitim hedeflerine odaklanmalarını ve öğrenme faaliyetlerini sürdürmelerini sağlayan içsel bir mekanizmadır. Son yıllarda yapılan çalışmalar, iş-yaşam dengesi ve motivasyonun akademik performans üzerinde %51,2 oranında bir açıklayıcılık varyansına sahip olduğunu göstermektedir (International Journal of Economics and Management Research, 2025). Literatürde, okupasyonel dengenin bozulmasının doğrudan yüksek stres düzeyleri, anksiyete ve uyku kalitesinde düşüşle ilişkili olduğu, bu durumun ise öğrencinin akademik görevlere karşı geliştirdiği içsel motivasyonu kısıtladığı belirtilmektedir (Bayar ve ark., 2021; Ergoterapi ve Rehabilitasyon Dergisi, 2025).

Buna ek olarak, okupasyonel dengeyi destekleyici eğitim modüllerinin öğrencilerin yaşam doyumunu ve akademik süreçlere katılımını anlamlı düzeyde artırdığı saptanmıştır (University of Nevada, 2024). Okupasyonel açıdan dengeli bir yaşama sahip olan öğrencilerin, akademik zorluklarla başa çıkma konusunda daha dayanıklı oldukları ve eğitim süreçlerinde daha yüksek düzeyde öz-yeterlik sergiledikleri görülmektedir. Bu bağlamda, mevcut çalışma; üniversite öğrencilerinin günlük yaşam aktivitelerindeki denge düzeyinin, onların akademik süreçlerdeki kararlılığını ve motivasyonel kaynaklarını nasıl şekillendirdiğini belirlemeyi amaçlamaktadır.

2. YÖNTEM

Araştırmanın Türü

Bu çalışma üniversite öğrencilerinin okupasyonel denge seviyelerinin, akademik motivasyon üzerinde etkili olup olmadığını incelemeyi hedeflemiş olup; yöntemsel olarak kesitsel ve korelasyonel araştırma modeline dayanmaktadır.

Veri Toplama Araçları

Çalışmada Sosyodemografik Form, okupasyonel denge düzeylerini belirlemek için Aktivite Rol Denge Anketi- 11 (ARDA -11) ve akademik motivasyon seviyelerini belirlemek için Akademik Motivasyon Ölçeği (AMÖ) kullanılmıştır.

Sosyodemografik Bilgi Formu

Bireylerin tanımlayıcı özelliklerini belirlemek amacıyla araştırmacılar tarafından geliştirilen form, katılımcıların yaş, cinsiyet, eğitim durumu gibi demografik bilgilerini ortaya koymak için çalışmaya dahil edilmiştir.

Aktivite Rol Denge Anketi -11

Aktivite Rol Denge Anketi -11, Günel ve arkadaşları tarafından Türkçeye uyarlanarak literatüre kazandırılmıştır. 11 soruluk bu ölçekte, puanlama aralığı 0-33 olarak belirlenmiştir. Alınan puanlar yükseldikçe bireyin okupasyonel denge kalitesinin iyi seviyede olduğu kabul edilmiştir. (Günel ve ark, 2020)

Akademik Motivasyon Ölçeği

Akademik Motivasyon Ölçeği, üniversite öğrencilerinin akademik motivasyonunu, yedi farklı alt boyuttan oluşan 28 soruyla ölçer. Her bir alt test ayrı değerlendirilir. Alt testlerden alınan puanlar 4 ve 28 sınırlarında belirlenmiştir. Herhangi bir alt boyuttan alınan puanın 28 puan değerine yakın olması o alt boyutun yüksek olduğunu gösterir. Bu ölçeğin dilsel eşdeğerlik, geçerlik ve güvenirlik çalışması Karataş ve Erden tarafından tamamlanmıştır. (Karataş ve Erden, 2012)

İstatistiksel Analiz

Sürekli veriler için ortalama $\pm$ standart, medyan, çeyrek1 (%25), çeyrek3 (%75), min ve maks, kategorik veriler için sıklık ve yüzde tanımlayıcı istatistik olarak kullanılmıştır. Sürekli verilerin normal dağılıma uygunluğu Kolmogorov-Smirnov testi ile kontrol edilmiştir.

Ölçeklerin güvenirliği iç tutarlılık katsayısı Cronbach alfa (α) katsayısı ve güvenirliğe faktör analizi perspektifinden bakan McDonald'ın (ω) alfa katsayısı ile değerlendirilmiştir.

Akademik Motivasyon Toplam için tahmin modeli Enter yöntemi kullanılarak Basit Doğrusal Regresyon analizi ile elde edilmiştir. Doğrusal Regresyon varsayımlarından; normal dağılıma uygunluk Kolmogorov-Smirnov testi, Doğrusal ilişki saçılım grafiği (Scatter Plot) ile incelenmiştir. Modelin yeterliğini kontrol etmek için; Varyans homojenliği (homoscedasticity) standartlaştırılmış artık grafiği ile, hatalar arasındaki korelasyon (Autocorelation) Durbin-Watson testi ile, Çoklu Bağlantı Varyans Şişme Oranı (Variance inflation factor, VIF) ile değerlendirilmiştir. Hataların normal dağılıma uygunluğuna standartlaştırılmış artıkların Kolmogorov-Smirnov testi ile karar verilmiştir (Alpar, 2011).

IBM SPSS 21 (IBM SPSS Inc, Chicago, IL) paket programı ile veriler analiz edilmiştir. İstatistiksel anlamlılık seviyesi 0,05 olarak alınmıştır.

3. BULGULAR

Araştırma kapsamına alınan öğrencilerin sosyodemografik özelliklerine ilişkin dağılımlar Tablo 1'de sunulmuştur. Örneklemin büyük çoğunluğunu kadınlar (%88,5), bekar bireyler (%98,4) ve herhangi bir işte çalışmayan öğrenciler (%72,1) oluşturmaktadır. Katılımcıların yaş dağılımı incelendiğinde, %59'unun 21-23 yaş aralığında olduğu, konaklama açısından ise yarısından fazlasının (%59) yükseköğretim yurtlarında kaldığı saptanmıştır. Ayrıca öğrencilerin %82 gibi büyük bir oranının mevcut bölümlerini ilk tercihlerinden biri olarak seçtiği görülmektedir.

Tablo 1. Sosyodemografik bulgular

N: 61		N(%)
Cinsiyet	Kadın	%88,5 (n:54)
	Erkek	%11,5 (n:7)
Yaş Grup	18-20	%32,8 (n:20)
	21-23	%59,0 (n:36)
	24 ve üzeri	%8,2 (n:5)
Medeni durum	Bekar	%98,4 (n:60)
	Evli	%1,6 (n:1)
Gelir	İhtiyaçlarımı karşılamakta büyük zorluk	%4,9 (n:3)
	İhtiyaçlarımı zorlukla karşılayabiliyorum.	%32,8 (n:20)
	İhtiyaçlarımı rahatlıkla karşılayabiliyorum.	%50,8 (n:31)
	İhtiyaçlarımı fazlasıyla karşılayabiliyorum.	%11,5 (n:7)
Tercih	Evet, ilk tercihlerimden biriydi.	%82,0 (n:50)
	Kısmen, puanım buraya yettiği için	%16,4 (n:10)
	Hayır, hiç istemeyerek okuyorum.	%1,6 (n:1)
Sınıf	1	%1,6 (n:1)
	2	%6,6 (n:4)
	3	%75,4 (n:46)
	4	%16,4 (n:10)
Genel Not	2.00 ve altı	%1,6 (n:1)
	2.01 - 2.99 arası	%54,1 (n:33)
	3.00 - 3.49 arası	%42,6 (n:26)
	3.50 ve üzeri	%1,6 (n:1)
Çalışma Durumu	Hayır, çalışmıyorum.	%72,1 (n:44)
	Evet, yarı zamanlı çalışıyorum.	%21,3 (n:13)
	Evet, tam zamanlı çalışıyorum.	%6,6 (n:4)
İkamet	Yükseköğretim yurdunda (Devlet/Özel)	%59,0 (n:36)
	Kiralık evde (Tek başıma/Arkadaşlarımla)	%19,7 (n:12)
	Ailemle birlikte kalıyorum.	%21,3 (n:13)
Okula Gidiş Zamanı	30 dakikadan az	%41,0 (n:25)
	30 dakika - 1 saat arası	%26,2 (n:16)
	1 - 2 saat arası	%18,0 (n:11)
	2 saatten fazla	%14,8 (n:9)

İç tutarlılık Güvenirlik Analizi Sonuçları

Ölçeğin güvenirliği; iç tutarlılık bağlamında Cronbach alfa ve yapısal güvenirlik bağlamında faktör analizi tabanlı McDonald'ın (ω) katsayıları aracılığıyla analiz edilmiştir (Cho & Kim, 2015)

Akademik Motivasyon Ölçeği toplamına ait Cronbach alfa katsayısı 0,918'dir.

Bilmeye Yönelik İçsel Motivasyon, Başarıya Yönelik İçsel Motivasyon, Uyarım Yaşamaya Yönelik İçsel Motivasyon, Belirlenmiş Dışsal Motivasyon, İçe Yansıyan Dışsal Motivasyon, Dışsal Motivasyon Dış Düzenleme ve Motivasyonsuzluk alt **boyutlarına** ait Cronbach alfa katsayısı sırasıyla **0,914, 0,818, 0,787, 0,837, 0,696 ve 0,905'tir.**

Okupasyonel Denge toplamı için Cronbach alfa katsayısı 0,919'dur.

Ölçme aracının yapısal güvenirliğini belirlemek amacıyla hesaplanan McDonald'ın (ω) katsayısı, Akademik Motivasyon Ölçeği toplam puanları için 0,932 değerini almıştır (McDonald, 1985; Nunnally & Bernstein, 1994). Bu sonuç, ölçeğin faktör analizi perspektifinden yüksek düzeyde bir yapısal güvenirliğe sahip olduğunu göstermektedir.

Bilmeye Yönelik İçsel Motivasyon, Başarıya Yönelik İçsel Motivasyon, Uyarım Yaşamaya Yönelik İçsel Motivasyon, Belirlenmiş Dışsal Motivasyon, İçe Yansıyan Dışsal Motivasyon,

INTERNATIONAL TOPKAPI CONGRESS VI

Dışsal Motivasyon Dış Düzenleme ve Motivasyonsuzluk alt **boyutlarına ait** McDonald'ın (ω) alfa katsayısı sırasıyla **0,915, 0,820, 0,815, 0,851, 0,810, 0,775 ve 0,913'tür.**

Okupasyonel Denge toplamı için McDonald'ın (ω) alfa katsayısı **0,924'tür.**

Literatürde tavsiye edilen kesim noktalarına göre (0.65-0.80 acceptable and 0.80-1.00 highly reliable) **Akademik Motivasyon Ölçeği toplamı ve alt boyutları ile Okupasyonel Denge Toplamı için elde edilen** güvenirlik katsayılarının kabul edilebilir ve yüksek olduğunu göstermiştir (Nunnally&Bernstein, 1994; Vaske, 2008).

Tablo2. Akademik Motivasyon Ölçeği toplamı ve alt boyutları ile Okupasyonel Denge Toplamı tanımlayıcıları

	Ort	Ss	Medyan	%25	%75	Min	Max
Bilmeye Yönelik İçsel Motivasyon	21,72	5,11	22,00	19,00	26,00	8,00	28,00
Başarıya Yönelik İçsel Motivasyon	18,74	5,43	18,00	16,00	22,00	7,00	28,00
Uyarım Yaşamaya Yönelik İçsel Motivasyon	18,85	5,05	20,00	16,00	22,00	4,00	28,00
Belirlenmiş Dışsal Motivasyon	23,36	4,34	24,00	22,00	27,00	8,00	28,00
İçe Yansıyan Dışsal Motivasyon	18,61	5,15	19,00	16,00	22,00	8,00	28,00
Dışsal Motivasyon Dış Düzenleme	23,75	4,21	25,00	22,00	27,00	8,00	28,00
Motivasyonsuzluk	11,57	6,50	9,00	7,00	17,00	4,00	28,00
Akademik Motivasyon Toplam	136,61	24,63	137,00	122,00	155,00	56,00	196,00
Okupasyonel Denge Toplam	18,80	6,61	18,00	15,00	23,00	1,00	33,00

Korelasyon Analizi sonuçları

Tablo 3. Akademik Motivasyon Ölçeği toplamı ve alt boyutları ile Okupasyonel Denge Toplam arasındaki ilişki

N=61		Bilmeye Yönelik İçsel Motivasyon	Başarıya Yönelik İçsel Motivasyon	Uyarım Yaşamaya Yönelik İçsel Motivasyon	Belirlenmiş Dışsal Motivasyon	İçe Yansıyan Dışsal Motivasyon	Dışsal Motivasyon Dış Düzenleme	Motivasyonsuzluk	Toplam
Okupasyonel Denge Toplam	r	0,488*	0,431*	0,378**	0,456**	0,326*	0,192**	- 0,207**	0,461*
	p	<0,001	0,001	0,003	<0,001	0,010	0,138	0,110	<0,001

*Pearson korelasyon katsayısı

**Spearman korelasyon katsayısı

Tablo3'te, **Akademik Motivasyon Ölçeği toplamı ve alt boyutları ile Okupasyonel Denge Toplam arasındaki ilişki** sonuçları görülmektedir. Değişkenler arasındaki ilişkiler Pearson ve Spearman korelasyon analizi ile değerlendirilmiş korelasyon katsayılarının yorumu için şu kesim noktaları kullanılmıştır; 0,00-0,19 çok zayıf, 0,20-0,39 zayıf, 0,40-0,69 orta, 0,70-0,89 yüksek ve 0,90-1,00 çok yüksek ilişki (Alpar, 2012).

Yapılan Pearson korelasyon analizi sonucunda **Okupasyonel Denge Toplamı ile Akademik Motivasyon Ölçeği toplamı**, Bilmeye Yönelik İçsel Motivasyon, Başarıya Yönelik İçsel Motivasyon ve İç Yansıyan Dışsal Motivasyon alt boyutları arasında pozitif yönlü orta ve zayıf düzeyde (sırasıyla; $r=0,461$, $r=0,488$, $r=0,431$ ve $r=0,326$) istatistiksel olarak anlamlı ilişki bulunmuştur (sırasıyla; $p<0,001$, $p=0,001$ ve $p=0,010$).

Yapılan Spearman korelasyon analizi sonucunda **Okupasyonel Denge Toplamı ile Akademik Motivasyon Ölçeği Uyarım Yaşamaya Yönelik İçsel Motivasyon ve Belirlenmiş Dışsal Motivasyon** alt boyutları arasında pozitif yönlü orta ve zayıf düzeyde ($\rho=0,378$ ve $\rho=0,456$) istatistiksel olarak anlamlı ilişki bulunmuştur ($p=0,003$ ve $p<0,001$).

Okupasyonel Denge Toplamı ile Dışsal Motivasyon Dış Düzenleme alt boyutu arasında pozitif yönlü zayıf ve anlamlı olmayan ilişki bulunurken ($\rho=0,192$, $p=0,138$) **Motivasyonsuzluk alt boyutu** ile arasında ise negatif yönlü zayıf düzeyde istatistiksel olarak anlamlı olmayan ilişki bulunmuştur ($\rho=-0,207$, $p=0,110$).

Regresyon Analizi Sonuçları

Tablo4. Akademik Motivasyon Puanına Ait Basit Doğrusal Regresyon Analizi Sonuçları

	β	SE(β)	BET A	t	p	VIF	R ²	F
Sabit	104,301	8,581		12,155	,000		0,212	F(1,59)=15,894
Okupasyonel Denge Toplam	1,718	,431	,461	3,987	,000	1,000		$p<0,001$

Okupasyonel Denge değişkeni ile Enter yöntemi kullanılarak gerçekleşen basit doğrusal regresyon analizi sonuçları Tablo4'te görülmektedir. Hataların normal dağılımı standardize artıkların Kolmogorov-Smirnov testi ile incelenmiş değişen varyanslılık (heteroscedasticity) sorununun varlığı ise standardize artıkların grafiği ile değerlendirilmiştir. Hatalar arasında korelasyonun (Autocorelation) olmadığı Durbin-Watson testi ($D-W=2,09$) sonucunda anlaşılmıştır (Field, 2013).

Yapılan basit doğrusal regresyon analizi sonucu bulunan model istatistiksel olarak anlamlı bulunmuştur ($F(1,59)=15,894$, $p<0,001$). Çoklu bağlantıya rastlanmamıştır ($VIF<10$) (Field, 2013).

Akademik Motivasyon Toplam Puanındaki varyasyonu açıklamak için oluşturulan modele Okupasyonel Denge değişkeninin katkısı istatistiksel olarak anlamlı bulunmuştur ($p<0,001$).

Okupasyonel Denge değişkeninin anlamlı yordayıcı olduğu ve bu değişkendeki 1 birimlik artışın **Akademik Motivasyon Toplam Puanında** 1,718 birimlik artış meydana getirdiği görülmüştür.

Akademik Motivasyon Toplam Puanındaki değişimin %21,20'si modele dahil edilen 1 bağımsız değişken tarafından açıklanmaktadır (Alpar, 2011).

Model;

Akademik Motivasyon Toplam Puanı = $104,301 + 1,718 * \text{Okupasyonel Denge}$

4.SONUÇ, TARTIŞMA VE ÖNERİLER

Bu çalışmanın temel amacı, üniversite öğrencilerinde okupasyonel denge düzeyi ile akademik motivasyon arasındaki ilişkinin nicel olarak belirlenmesi ve bu ilişkinin yönünün analiz edilmesidir. Elde edilen bulgulara, bireylerin öz bakım, üretkenlik ve serbest zaman rollerine ilişkin aktivitelerde sağladıkları dengenin akademik motivasyon üzerinde anlamlı ve pozitif yönde bir etki oluşturduğunu görülmüştür. Basit doğrusal regresyon modeli, okupasyonel dengenin akademik motivasyon varyansının %21,2'sini açıkladığını ortaya koymuş olup ($R^2 = 0.212$), bu değişkenin öğrencilerin akademik performansı açısından önemli bir belirleyici olduğunu göstermektedir.

Araştırmadan elde edilen ilişkisel bulgular, mevcut literatürde okupasyonel dengenin bireysel iyi oluş, öz-yeterlik ve motivasyon üzerindeki rolünü vurgulayan çalışmalarla tutarlılık göstermektedir (Günel ve ark., 2020; Alpar, 2012). Analiz sonuçlarına göre okupasyonel denge puanındaki her bir birimlik artışın akademik motivasyonu 1.718 birim artırması, öğrencilerin akademik yaşam dışında yaptıkları aktivitelerin de dengeli olması, motivasyonel süreçlere doğrudan yansıdığını göstermektedir. Bu bulgu, akademik başarıyı etkileyen süreçlerin yalnızca akademik ortama bağlı olmadığını; yaşam tarzı, rol dengesi ve aktivitelerden algılanan anlam gibi faktörlerle birlikte şekillendiğini desteklemektedir.

Sonuç olarak, çalışma okupasyonel dengenin akademik motivasyonu etkileyen temel bir değişken olduğunu göstermektedir. Gelecek araştırmalarda daha geniş ve temsili örneklemelerle çalışılması ve stres, yorgunluk, uyku kalitesi gibi psikososyal değişkenlerin modelde aracı veya düzenleyici faktör olarak incelenmesi önerilmektedir. Ek olarak, üniversite ortamında verilebilecek okupasyonel denge eğitimlerinin öğrencilerin akademik performansını artırmada etkili bir müdahale olabileceği değerlendirilmektedir.

KAYNAKLAR

1. Bayar, B. D., Can, S. Y., Erten, M., & Ekmen, M. (2021). Covid-19 Pandemi Sürecinde Üniversite Öğrencilerinin Depresyon ve Stres Düzeylerinin Belirlenmesi. *Paramedik ve Acil Sağlık Hizmetleri Dergisi*, 2(1), 12-25.
2. Guskowska, M., & Dąbrowska-Zimakowska, A. (2025). Changes in occupational balance and psychological well-being among university students: A longitudinal study. *Journal of Occupational Science*.
3. International Journal of Economics and Management Research. (2025). The Effect of Work-Life Balance and Motivation on Academic Performance. *IJEMR*, 5(2), 391-405.
4. University of Nevada. (2024). The Effect of an Occupational Balance Educational Module on Life Satisfaction and Occupational Balance for University Students. *Digital Scholarship@UNLV*.
5. Wagman, P., & Håkansson, C. (2023). University students' experiences of occupational balance in response to environmental changes. *Scandinavian Journal of Occupational Therapy*, 30(2), 115-124.
6. Ergoterapi ve Rehabilitasyon Dergisi. (2025). Üniversite Öğrencilerinin Okupasyonel Dengeleri ile Uyku Kalitesi ve Zaman Yönetimleri Arasındaki İlişkinin İncelenmesi. 13(3), 248-257.
7. Nunnally, J. C., & Bernstein, I. H. (1994). Psychometric theory (3rd ed.). New York, NY: McGraw-Hill, Inc.
8. ALPAR, R. (2012). Spor, Sağlık ve Eğitim Bilimlerinden Örneklerle Uygulamalı İstatistik ve Geçerlik – Güvenirlik, 3. Baskı, Detay Yayıncılık.
9. McDonald, R. (1985). Factor analysis and related methods. Hillsdale, N J: Erlbaum

INTERNATIONAL TOPKAPI CONGRESS VI

10. Cho, E., & Kim, S. (2015). Cronbach's coefficient alpha: Well known but poorly understood. *Organizational Research Methods*, 18(2), 207–230.
<https://doi.org/10.1177/1094428114555994>
11. Vaske, J. J. (2008). *Survey research and analysis: Applications in parks, recreation and human dimensions*. State College, PA: Venture.
12. ALPAR R. (2011). *Uygulamalı Çok Değişkenli İstatistiksel Yöntemler*, 3. Bs, Detay Yayıncılık, Ankara.
13. Field, A. (2013). *Discovering Statistics Using IBM SPSS Statistics: And Sex and Drugs and Rock "N" Roll*, 4th Edition, Sage, Los Angeles, London, New Delhi.

AGRICULTURAL POLICIES AND SOCIO-ECONOMIC TRANSFORMATION IN
AN GIANG, SOUTH VIETNAM (1955–1965)

Dr. Duong The Hien

An Giang University, Vietnam
<https://orcid.org/0000-0001-8791-673X>

Dr. Duong To Quoc Thai

Dong Thap University, Vietnam
<https://orcid.org/0009-0008-1929-3751>

M.A. Nguyen Thanh Tuan

Vinh Nhuan Middle and High School, Vietnam
<https://orcid.org/0009-0005-1585-4812>

Abstract

Between 1955 and 1965, agricultural policies implemented by the government of the Republic of Vietnam in An Giang Province were carried out within a distinctive political, security, and economic context in South Vietnam following 1954. Owing to its strategic location in the Southwestern region, bordering Cambodia, An Giang functioned not only as a major agricultural production area but also as a key site in the central government's rural control strategy. In response to the presence and activities of revolutionary forces, the state introduced a series of rural-oriented economic and security policies, notably the Strategic Hamlet Program, the settlement (dinh điền) policy, and land reform initiatives, with the dual objectives of promoting agricultural production and restructuring rural production spaces and social relations.

Benefiting from favorable natural conditions, including dense river and canal networks and abundant alluvial deposits from the Mekong River, agriculture in An Giang primarily developed through large-scale wet-rice cultivation, supplemented by industrial crops and secondary food crops, and employed the majority of the rural labor force. However, intensive state intervention through agricultural, land, migration, and security control policies generated significant socio-economic transformations. These changes were reflected in shifts in land ownership relations, modes of production organization, livelihood structures, and the degree of social differentiation within local farming communities. Against this background, this paper analyzes the socio-economic impacts of agricultural policies on production, land distribution, and farmers' livelihoods in An Giang, thereby clarifying their limitations in terms of effectiveness and sustainability, as well as the close interconnections between agricultural development and the broader context of war and social instability in South Vietnam during the period 1955–1965.

This study primarily employs a historical approach combined with logical analysis. The historical method is used to examine land reform policies promulgated by President Ngô Đình Diệm between 1955 and 1963, aiming to systematically reconstruct the agricultural economic policies of the Republic of Vietnam and assess their practical impacts in An Giang Province. The logical method is applied through the chronological organization and analysis of historical events, in conjunction with supplementary methods such as comparison, statistical analysis, and source synthesis, in order to ensure objectivity and reliability in the research findings.

Keywords: *Agricultural policy; Rural transformation; An Giang; South Vietnam; Socio-economic change; 1955–1965*

INTRODUCTION

From 1955 to 1965, agricultural policies implemented by the Republic of Vietnam in South Vietnam in general, and in An Giang Province in particular, were closely intertwined with broader political, security, and socio-economic challenges that emerged in South Vietnam after 1954. Located in the strategically important Mekong Delta region and bordering Cambodia, An Giang played a dual role as both a major agricultural production area and a strategic zone for rural control. Policies such as the Strategic Hamlet Program, settlement (dinh điền) schemes, and land reform initiatives were designed not only to promote agricultural development but also to reshape rural space and social relations. However, these interventions generated profound economic and social changes, particularly in land ownership patterns, production organization, and farmers' livelihoods. This study examines the socio-economic impacts of agricultural policies, highlighting their limitations, issues of sustainability, and their close relationship with wartime instability in South Vietnam.

Within this context, the present study systematically analyzes the issue of “*Agricultural Policies and Socio-Economic Transformation in An Giang, South Vietnam (1955–1965)*” through the collection and cross-examination of diverse sources. These include scholarly works by authors specializing in agricultural studies; reference materials such as monographs, academic books, doctoral dissertations, master's theses, and articles published in academic journals and conference proceedings; as well as archival documents from the National Archives Center No. II in Ho Chi Minh City. The use of these sources ensures both the authenticity of the data and the historical depth of the research.

Previous studies on the economy of South Vietnam during the period 1955–1975 provide an essential foundation for approaching this topic. Notable works include *South Vietnam after Dien Bien Phu* (Tri Thuc Publishing House, 2008) by Dang Phong; *Vietnamese Economy, 1945–2000, Volume 2* (Social Sciences Publishing House, 2005) by Le Dinh Trong; *Agricultural Economy of the Republic of Vietnam* (Social Sciences Publishing House, 2020); *History of the An Giang Provincial Party Committee, Volume II (1954–1975)*; *The Economy of the Republic of Vietnam under U.S. Aid (1955–1975)* (People's Public Security Publishing House, 2017) by Pham Thi Hong Ha; and Son Nam's *Exploring the Land of Hau Giang - The History of An Giang* (Tre Publishing House, 2018). These studies address issues related to agricultural development in An Giang Province (1955–1975), including administrative boundaries in Southern Vietnam before and after 1955, geographical location, climate, soil conditions, labor resources, and the impact of U.S. aid policies on rural agriculture in South Vietnam. Nevertheless, existing research has not provided a sufficiently detailed, locality-based analysis particularly with regard to An Giang Province to clarify how agricultural economic policies influenced political and social dynamics at the local level. Therefore, building upon the aforementioned studies, this paper seeks to further investigate unresolved issues and explore new perspectives in order to provide a more comprehensive understanding of the research topic.

RESEARCH METHODS

This study is grounded in the application of dialectical materialism and historical materialism to the analysis of economic and social issues in Vietnam and Indochina during the period 1955–1965. On this theoretical basis, the research primarily employs two core methodological approaches: the historical method and the logical method.

The historical method is used to reconstruct, in an accurate and systematic manner, the development of agricultural economic issues in An Giang Province over time, while situating them within their specific historical and socio-political contexts. This approach enables a comprehensive understanding of policy implementation and its evolving impacts throughout the study period.

The logical method supports the analysis and presentation of research problems and objectives in a coherent, consistent, and structured manner. By organizing arguments logically, this method helps ensure that the research findings are clearly articulated and aligned with the overall research aims.

In addition, statistical methods are employed to collect, process, and synthesize data drawn from a wide range of sources, including archival documents from the National Archives Center No. II, collected historical records, scholarly monographs, academic studies, and doctoral and master's theses. These methods facilitate the selection and verification of key evidence and enhance the reliability of the research findings.

The comparative method is applied to examine changes in agricultural development in An Giang from the Nguyen Lords period, through the French colonial era, to the period 1954-1975. This long term comparative perspective allows for the identification of continuities and transformations in agricultural structures and policies.

Finally, the methods of source collection and document analysis are employed throughout the research process. Relevant materials from the Nguyễn dynasty period to the era of the Republic of Vietnam are systematically collected, evaluated for relevance, and organized in accordance with specific research themes and chapters. This approach ensures the effective use of historical sources and supports a rigorous and well documented analysis.

RESEARCH FINDINGS AND DISCUSSION

Agricultural Policies

Land Reform

Following the establishment of the new government, within a short period between 1955 and 1956, the United States dispatched an advisory mission led by W. Ladejinsky, the chief adviser on land reform, to South Vietnam to assist the government of the Republic of Vietnam in drafting land policy. According to *Cong Luan* newspaper (July 7, 1969), between 1955 and 1960 the United States provided approximately USD 12 million in aid to the Republic of Vietnam to support the implementation of land reform policies. During this period, President Ngô Đình Diệm successively promulgated three decrees aimed at carrying out what was termed "land reform." These decrees primarily regulated relations between landlords and tenants and imposed limits on the amount of land that landlords were permitted to own.

Decree No. 2 (January 8, 1955), which amended Decree No. 20 on the regulation of tenancy (Ministry of Land Affairs and Land Reform, Republic of Vietnam, 1960, pp. 91–95), largely reiterated the provisions of Decree No. 20 originally signed by Chief of State Bảo Đại on June 4, 1953. While Decree No. 20 stipulated a uniform land rent ceiling of 15 percent of total agricultural output and regulated tenancy contracts (Type A) for land under active cultivation, Decree No. 2 introduced revisions by setting the minimum land rent at 15 percent and the maximum at 25 percent of output. The duration of tenancy contracts was fixed at five years.

Decree No. 7 (February 5, 1955), titled "Regulations on the Reclamation of Abandoned and Uncultivated Land" (replacing Decree No. 22, which was completely annulled), further specified conditions for the reuse of abandoned land (Ministry of Land Affairs and Land Reform, Republic of Vietnam, 1960, pp. 91–95). Under this decree, land left uncultivated during a farming season was to be allocated to tenant farmers under the following conditions: exemption from rent in the first year, payment of one-half rent in the second year, and three-quarters rent in the third year. The duration of tenancy contracts followed the same provisions as Decrees No. 2 and No. 20, with the possibility of renewal. Tenant farmers were permitted to relinquish land with six months' prior notice to the landlord, while landlords seeking to reclaim land (without contract renewal) were required to give three years' notice. Tenancy contracts were classified into three types: Type A for cultivated land with an owner present; Type B for abandoned land with an owner; and Type C for abandoned land without an identifiable owner, in which case communal councils signed contracts on behalf of the state.

During the war of independence, an estimated 500.000 hectares of rice land were abandoned due to the absence of landowners who had fled rural areas amid insecurity. Much of this land belonged to medium-sized landlords (5–10 hectares) and large landowners (over 50 hectares). As these landowners were no longer present to assert ownership, such abandoned land was classified as state property and subsequently allocated without charge to tenant farmers by local authorities.

In addition, as part of efforts to promote rural agricultural development, the government permitted tenant farmers who had previously aligned with revolutionary forces to continue cultivating land distributed during wartime. Their tenancy rights and rent obligations were formally recognized and guaranteed by the state. Similarly, abandoned public land (communal land and public fields) was also allocated to tenant farmers under the same conditions.

Based on available data, the land reform measures promoted by the Ngo Dinh Diem administration particularly policies concerning the expropriation of landlord holdings demonstrated significant limitations in practice. Under Decree No. 57, landlords owning more than 100 *samples* were legally required to sell excess land to landless farmers. The government established four priority groups for land allocation: long term tenants (over two years), veterans, migrants, and the unemployed. In addition, landlords were permitted to retain up to 15 hectares of ancestral land, with flexibility in selecting its location (Tran Phuong, 1968, pp. 245–259). Excess land was purchased by the government at market prices, with 10 percent paid in cash and the remainder issued as bonds redeemable over 12 years at an annual interest rate of 3 percent (Le Dinh Trong, 2020, p. 65).

Expropriated land was resold to land-poor farmers, with a maximum allocation of five hectares per recipient. Exceptions were made for farmers who had previously occupied land illegally, failed to formalize tenancy contracts, or neglected rent and land tax obligations prior to March 31, 1957, as stipulated in Article 11. Purchasers were allowed to repay land costs over a six-year period, during which the land remained under state ownership. For a period of ten years, the land could not be leased, mortgaged, transferred, or seized.

Settlement and Migration Policies

During the First Republic period, settlement and migration policies were promoted by President Ngo Dinh Diem with primary objectives encompassing political, military, economic, and social dimensions.

From an economic perspective, settlement programs aimed to achieve a more balanced distribution of population, expand cultivated land, increase agricultural output, and promote agricultural development. These programs were intended to improve the living standards of migrants and rural farmers, curb forest destruction caused by slash-and-burn practices among highland communities, protect forest resources and land, and integrate these populations into broader national economic policies.

From a political standpoint, settlers were provided with agricultural land, construction materials, and financial support to build housing. At the same time, policies of land ownership formalization were implemented to enable settlers to become legal landholders. Through these measures, the government sought to secure popular support and encourage alignment with the state while countering the influence of communist forces.

From a social perspective, settlement and migration policies contributed to addressing housing and livelihood needs for nearly one million migrants from northern Vietnam who relocated to the South following the 1954 Geneva Accords. The redistribution of population on a national scale was intended to prevent large uninhabited areas that could complicate administrative control and governance.

From a security perspective, settlement areas functioned as strategically important locations within the Saigon government's defense system, serving as buffer zones against infiltration and attacks by communist forces. As noted by some military analysts, communist forces were

unable to seize provincial or district centers during certain offensives largely due to the defensive network formed by settlement zones, which acted as interconnected barriers supporting provincial and district headquarters (Tran Van Dinh, 1974, p. 43).

Following the withdrawal of French influence, beginning in 1955 the United States provided direct military and economic assistance to the Ngo Dinh Diem government, with aid increasing steadily from USD 29.7 million in 1955 to USD 76.7 million in 1958 (Institute of Economics, 1960, p. 301). A significant portion of this assistance supported the development of settlement zones in the Central Highlands and the southwestern regions. In An Giang, the Ba Bai settlement zone, covering approximately 3,000 *samples*, was established in 1957 (Presidential Office of the First Republic of Vietnam, 1961). In 1958, the chairman of the An Giang Farmers' Association sought approval from Kien Giang Province to open the My Lam and Tan Hoi agricultural farms for land reclamation and economic revitalization (Presidential Office of the First Republic of Vietnam, 1961). In 1962, the Tam Ngan settlement zone was established on approximately 30,000 *samples* of unused land (Presidential Office of the First Republic of Vietnam, 1961). The Cai San settlement zone, aimed at land reclamation and village establishment, also received particular attention from provincial authorities in An Giang.

In these settlement areas, once locations were selected, authorities divided land into agricultural zones, residential areas, marketplaces, administrative centers, schools, and medical facilities, followed by the organized relocation of settlers. In this sense, settlement policy played an important role in land reform by addressing shortages of arable land, reclaiming previously uncultivated areas, and establishing buffer zones against revolutionary infiltration from northern regions and rural Viet Cong networks. Rather than relying solely on the expropriation of existing arable land, the government of the Republic of Vietnam in general, and authorities in An Giang in particular, adopted a more pragmatic approach by expanding cultivable land through settlement programs.

Nevertheless, the implementation of settlement policies in An Giang remained limited in scale and was not carried out uniformly, unlike in some provinces of the Mekong Delta or the Central Highlands, where settlement programs were more extensive and systematically applied.

The Strategic Hamlet Program and Rural Control

The Strategic Hamlet Program (hereafter SHP) was initiated by the My-Diem administration on an experimental basis in several localities across South Vietnam in July 1961. With regard to An Giang, the central government issued a directive approving an extension of the implementation timeline until September 30, 1963, instead of the original deadline of June 30, 1963, and requested provincial authorities to adjust implementation phases accordingly to ensure feasibility and effectiveness (An Giang Provincial Administrative Office, pp. 169-338). In practice, the construction of strategic hamlets in An Giang began only in 1962. Provincial authorities designated this program as a top priority, placing it above all other administrative tasks and requiring the active participation of all officials, civil servants, and public employees. This directive was clearly reflected in instructions issued by the An Giang Provincial Chief to district-level administrations, emphasizing that despite the growing workload of state agencies, the implementation of the Strategic Hamlet Program must be treated as the foremost priority (General Directorate of Settlement and Agriculture, 1960).

The program aimed to relocate approximately 800.000 residents into 475 strategic hamlets and 20 "prosperous villages" within a single year. Its primary objectives included securing major transportation routes, establishing strategic corridors surrounding district and provincial administrative centers, and linking strategic hamlets and prosperous villages along the Viet-Cambodia border into a continuous defensive zone to prevent infiltration by Viet Cong forces. Strategic hamlets were established along canals, waterways, and major roads to restrict the movement of communist forces and to sever communication and logistical support between rural populations and insurgent networks. Depending on local security conditions, the An Giang

INTERNATIONAL TOPKAPI CONGRESS VI

authorities classified strategic hamlets into three categories: Type A, located in fully secure areas (207 hamlets); Type B, in relatively secure areas (228 hamlets); and Type C, in insecure areas (60 hamlets) (An Giang Provincial Administrative Office, pp. 169-338). In total, 495 strategic hamlets were planned for the entire province in 1962.

Regarding construction guidelines, the Inter Ministerial Committee for the Strategic Hamlet Program issued instructions to the provincial Strategic Hamlet Office stipulating that, for ease of surveillance and defense, hamlets should have a maximum perimeter of 2.5 kilometers, particularly in high risk zones. In areas under relatively firm government control or near urban centers such as Chau Thanh, larger hamlets could be established, provided they were subdivided into smaller defensive units capable of self defense and mutual support in the event of attack (An Giang Provincial Administrative Office, pp. 169-338). Accordingly, provincial authorities sought to limit the size of each strategic hamlet to facilitate guarding and defense. The official principle emphasized “residents remain where they live,” discouraging large scale population displacement or long distance relocation in order to minimize disruption to daily life. In practice, however, efforts to meet implementation deadlines often involved coercive measures, including security sweeps, forced evacuations, and the destruction of houses belonging to households that resisted relocation into strategic hamlets.

In terms of funding, An Giang, like other provinces, received financial support for the Strategic Hamlet Program from allied foreign aid provided to the government of the Republic of Vietnam. During the initial phase in 1962, central funding for An Giang was disbursed in three installments. According to an official notice from the Inter Ministerial Committee for the Strategic Hamlet Program to the An Giang Provincial Chief, the province was allocated 1.000.000 *dong* for the construction of strategic hamlets, to be used exclusively for defensive works and guard posts. Financial assistance of 15.000 *dong* was provided only to the poorest hamlets, on the condition that they completed perimeter fencing and established hamlet councils and mass organizations. Specific allocations included 90.000 *dong* for 48 strategic hamlets in Tan Chau, 124.000 *dong* for 66 hamlets in Chau Thanh, and 185.000 *dong* for 98 hamlets in Cho Moi (An Giang Provincial Administrative Office, pp. 1–5).

These figures indicate that while the central government subsidized part of the construction costs for strategic hamlets in An Giang, financial support was selectively directed toward the poorest hamlets, whereas those with better economic conditions received no assistance. Nonetheless, when averaged by the number of hamlets, funding levels were relatively uniform across districts, with approximately 1.875 *dong* per hamlet in Tan Chau, 1.878 *dong* in Chau Thanh, and 1.887 *dong* in Cho Moi. In addition to financial support, material resources such as barbed wire and timber were also supplied to facilitate construction.

After more than one year of implementation, the Strategic Hamlet Program produced certain measurable outcomes. The following table presents statistical data on the progress of strategic hamlet construction across South Vietnam, as recorded by the government of the Republic of Vietnam up to October 31, 1963.

Table 1. Progress of Strategic Hamlet Construction in An Giang as Reported by the Republic of Vietnam up to October 31, 1963

Number of Strategic Hamlets			Population	
Planned	Completed	Under Construction	Province-wide Total	Population Relocated into Strategic Hamlets
521	477	34	831.991	752.538

Source: File No. 80, Revolutionary Military Council, Progress of Strategic Hamlet Construction up to October 31, 1963, pp. 23–24.

Implementation of the Strategic Hamlet Program varied according to regional characteristics and generally followed three main models: population concentration, population enclosure, and zonal reorganization. Regardless of the model applied, each strategic hamlet was required to meet six criteria prescribed by higher authorities (as discussed earlier). In Tinh Bien, for example, which was identified as a key area for intensive population consolidation by the Saigon government, most strategic hamlets shared common features. Residents were required to dismantle and rebuild houses facing each other, with a roadway running between them and an average distance of approximately ten meters separating each dwelling. Behind the houses, an earthen embankment about 1.5 meters high was constructed, followed by fencing made of barbed wire and deep trenches reinforced with bamboo stakes. Along the perimeter, entry gates were established at intervals of approximately 300 to 500 meters and were strictly guarded and monitored.

In Thoai Son, by contrast, the dense network of canals and waterways shaped a different approach. As residents primarily lived along canal banks and transportation routes, strategic hamlet construction in this area focused on digging trenches and erecting double layers of barbed wire fencing behind residential areas in order to separate living spaces from surrounding rice fields. Access points to farmland were established every few hundred meters and were subject to strict surveillance. In addition to the limited financial assistance provided by higher authorities, residents were required to contribute between five and ten days of labor per person. They were also required to pay between 800 and 1.000 dong per person for digging trenches, constructing embankments, and preparing defensive stakes (Thoai Son District Party Committee, 1997, p.137).

However, participation in these activities was not always voluntary. In some localities, residents were reportedly detained for three to four consecutive days to work on strategic hamlet construction, resulting in disruptions to their livelihoods. During these activities, they were often subjected to harsh treatment by local militia forces, including verbal intimidation and threats, which generated widespread dissatisfaction among the population (An Giang Provincial Administrative Office, pp. 169-338). Alongside the establishment of strategic hamlets, pacification teams were deployed to communes and hamlets to require households to complete family registration forms for surveillance and control purposes. At the same time, the authorities intensified internal screening to prevent infiltration, expanded anti communist propaganda campaigns, and employed coercive measures against the civilian population.

In an effort to mitigate popular resistance, the government also implemented “civil assistance” programs, delivering large quantities of consumer goods and agricultural production equipment to communes and hamlets. Cho Moi, in particular, was identified as a focal area for strategic hamlet construction. In March 1962, of the 31 strategic hamlets established province wide, 10 were located in Cho Moi; by September 1962, of the 181 strategic hamlets constructed across the province, 53 were situated in this district (Communist Party of Vietnam, An Giang Provincial Party Committee, 2007, p.99).

Most strategic hamlets in Cho Moi followed the population enclosure model, meaning that residents remained in their original locations while hamlet boundaries were established around them. However, construction quality in this district was often rudimentary. Defensive measures typically consisted of earthen embankments built behind houses to separate residential areas from fields and gardens, with barbed wire fencing applied inconsistently. During a regular meeting of the Provincial Strategic Hamlet Inspection Committee on July 9, 1962, the An Giang Provincial Chief criticized subordinate administrations, stating that some districts appeared to prioritize numerical targets for reporting purposes while neglecting both form and substance. In particular, Cho Moi and Chau Thanh were cited as having implemented the program in an overly superficial manner (An Giang Provincial Administrative Office, pp.169-338).

INTERNATIONAL TOPKAPI CONGRESS VI

Parallel to the establishment of strategic hamlets, the Saigon government conducted security sweeps and coercive operations to force population relocation, which caused significant difficulties and losses for revolutionary forces. As a result, during the early months of 1962, the Strategic Hamlet Program in An Giang produced certain short-term effects, particularly in religiously concentrated lowland areas. According to reports by the An Giang Provincial Chief on the implementation of the Strategic Hamlet Program in 1962, the following results were recorded.

Table 2. Number of Strategic Hamlets Established by District in An Giang Province

District	First Quarter	Second Quarter	Third Quarter	Fourth Quarter	Total
Tan Chau	16	12	7	11	46
Chau Thanh	1	22	18	25	66
Chau Phu	30	28	19	14	91
An Phu	9	7	3	16	35
Cho Moi	38	24	19	15	96
Hue Duc	6	6	2	6	20
Tinh Bien	10	10	7	0	27
Thot Not	2	24	30	5	61
Tri Ton		11	16	4	31
Total	112	144	121	96	473

Source: Strategic Hamlet Establishment Program in 1962, An Giang Archival Office, File No. 381, p. 291.

Based on the above statistical data, it can be observed that in 1962 the government implemented the Strategic Hamlet Program across the entire province of An Giang, with a total of 473 strategic hamlets completed. The highest number of strategic hamlets was constructed during the second and third quarters of the year. However, the distribution of strategic hamlets was uneven among districts, reflecting differences in local conditions and characteristics. Cho Moi District recorded the highest number of strategic hamlets established.

Cho Moi was one of the earliest and most densely populated districts in An Giang Province and had experienced a long historical process of settlement and resistance against foreign rule, particularly during the anti-French period. It was also the site where the first communist cell of An Giang Province was established and was therefore regarded as a major center of revolutionary activity. For this reason, provincial authorities identified Cho Moi as a focal area for the implementation of the Strategic Hamlet Program, aiming to dismantle revolutionary infrastructure and accelerate the pacification process in An Giang.

From this perspective, the Strategic Hamlet Program implemented by the My-Diem administration functioned not only as a system of fortified settlements designed to control rural populations, but also as a mechanism for constructing rural infrastructure in ways that limited the operational space of revolutionary forces. Through the establishment of strategic hamlets, the program sought to reorganize rural society, weaken revolutionary influence, and consolidate state authority at the village and hamlet levels. In addition, the program promoted initiatives framed as “community development” and “improvements in living standards” in order to gain the support of rural populations and encourage their alignment with the government of the Republic of Vietnam. In this process, rural areas were increasingly integrated into the state’s political and military framework, serving as sources of labor, resources, and recruits for the Saigon government.

Strategic hamlets also functioned as logistical and territorial bases supporting military operations by the Army of the Republic of Vietnam, facilitating security sweeps and counterinsurgency campaigns beyond hamlet boundaries. In Fundamental Theory of the Strategic Hamlet Program, Ngo Dinh Nhu summarized the objectives of the program as an

effort to extend state control deep into rural areas, eliminate communist influence, and complete the political and infrastructural foundations of the regime. Accordingly, the Strategic Hamlet Program was conceptualized as a form of “compressed revolution,” narrowing the scope of transformation from the national level to the confined space of villages and hamlets (Fundamental Theory of the Strategic Hamlet Program in the Republic of Vietnam, 1962, p. 14).

Socio-Economic Transformation

Impacts on Agricultural Production

Agriculture in An Giang during the Period 1955–1960

An Giang was widely regarded as the principal rice-producing region of South Vietnam. In agricultural development, land ownership has consistently been one of the most fundamental issues that any governing authority must address. At the same time, farmers have traditionally aspired to possess their own plots of land for cultivation. Consequently, agricultural policies have largely aimed to respond to this aspiration. From the period of the Nguyen Lords through the Nguyen dynasty, various land policies such as the land distribution reforms under Emperor Minh Mang and the *quan dien* system were introduced with the objective of promoting agricultural prosperity.

During the period of French colonial rule, considerable attention was also given to land ownership in An Giang. However, colonial authorities failed to implement measures that effectively supported poor farmers. Instead, preferential treatment was extended to landlords, resulting in increasing disparities in land ownership in rural areas. By 1929, the former Long Xuyen Province alone recorded 11.478 landlords (Vo Thi Hong, 1997, p. 47).

In 1947, the Autonomous Republic of Cochinchina issued its first legal document concerning rent reduction on May 21, 1947. Following the Geneva Accords of 1954, South Vietnam entered a phase of postwar economic reconstruction, in which agriculture continued to play a central role.

Under these conditions, land ownership in An Giang similar to other provinces remained highly concentrated in the hands of large landowners, while the majority of farmers either possessed little land or were completely landless. As a result, tenant farming under unfavorable economic terms became widespread. In 1955, a more systematic land reform effort was initiated through policies promulgated by the Ngo Dinh Diem administration. These included regulations governing landlord–tenant relations and tenancy contracts (Decree No. 2, January 8, 1955), followed by Decree No. 7 (February 5, 1955), which addressed the reclamation and cultivation of abandoned land. Subsequently, Decree No. 57 (October 22, 1956) provided legal provisions for redistributing land from large landowners to landless or land-poor farmers.

In An Giang, land reform measures were implemented more substantively beginning in 1957, with the stated objectives of improving farmers’ land ownership rights and promoting provincial agricultural production. The outcomes of these policies are presented in the following tables.

Table 3. Tenancy Contracts Signed during the Period 1957–1959

Category	Type A	Type B	Type C	Total
July 31, 1957 (*)	26.967	4.678	2.788	34.433
February 28, 1958 (**)	49.809	6.520	5.831	51.935
August 31, 1959 (***)	57.320	10.456	9.557	77.333

(*) *Fonds 29, Presidential Office of the First Republic of Vietnam, 1959, p. 18.*

(**) *Fonds 29, Presidential Office of the First Republic of Vietnam, 1959, p. 11.*

(***) *Fonds 29, Presidential Office of the First Republic of Vietnam, 1959, p. 6.*

Song song với việc ban hành quy chế tá điền chính quyền cũng có những chính sách với việc khai thác ruộng đất bị bỏ hoang, mà kết quả được thể hiện ở bảng số liệu sau:

Table 4. Declaration of Abandoned Land, 1957–1959

Category	1957 (*)	1959 (**)	1963 (***)
Public land (communal fields and land)	5.067 samples 97	1.768 samples	1034 samples
Private land	181.559 samples	23.286 samples	12.557 samples
Total	186.626	25.054	13.594

Source:

(*) *Fonds 29, Presidential Office of the First Republic of Vietnam, 1957, p. 9.*

(**) *Fonds 29, Presidential Office of the First Republic of Vietnam, 1959, p. 6.*

(***) *Fonds 29, Presidential Office of the First Republic of Vietnam, 1963, p. 22.*

Table 5. Land Expropriated and Allocated by the An Giang Provincial Government over Selected Years

Year	1957 (*)	1958 (**)	1959 (***)	1963 (****)
Area declared and allocated	1.110 samples 15,53	10.146 samples 95,78	39.578 samples	42.068 samples 30,04
Tenant farmers allocated land	540 persons	3.891	9.424 persons	13.606 persons

Source:

(*) *Fonds 29, Presidential Office of the First Republic of Vietnam, 1957, p. 6.*

(**) *Fonds 29, Presidential Office of the First Republic of Vietnam, 1958, p. 8.*

(***) *Presidential Office of the First Republic of Vietnam, 1959, p. 7.*

(****) *Presidential Office of the First Republic of Vietnam, 1963, p. 22.*

Based on the above statistical evidence, it can be concluded that the land reform policy implemented by Ngo Dinh Diem in An Giang was designed with the stated objective of resolving land ownership problems inherited from the French colonial period. However, its implementation failed to produce the expected outcomes. By 1960, approximately 45 percent of agricultural land remained in the hands of large landowners (those holding more than 50 hectares), while 42.5 percent was controlled by medium and small landowners (5–50 hectares). Only a small proportion of tenant farmers obtained land for cultivation (Le Hong Kham et al., 2013, p. 319). Alongside land policies, the An Giang authorities also introduced measures aimed at improving agricultural techniques in order to enhance farmers' living conditions, increase productivity, and promote greater stability in agricultural economic development.

Crop Varieties: In An Giang, agricultural production was dominated by traditional food crops, with rice occupying a central and enduring role. Located in the Mekong Delta, An Giang benefited from favorable natural conditions, including fertile alluvial soils, an extensive river and canal network, and a relatively stable climate, all of which were well suited to rice cultivation as well as to a limited range of other crops. From the early stages of land reclamation during the Nguyen dynasty, Vietnamese settlers devoted most newly cleared land to rice cultivation. As described by Trinh Hoai Duc, rice varieties at the time could be broadly classified into two main types: lua canh (non-glutinous rice), characterized by small grains, soft texture, and aromatic qualities; and lua thuat (glutinous rice), which contained higher starch content and larger, rounder grains, including varieties such as lua tao, thoc sa, mong tay, mong chim, mo cai, and can dong (Trinh Hoai Duc, 1972, p. 153).

Cultivation practices during this period were largely traditional. In Vinh An District (part of present-day An Giang), rice seedlings were typically sown in June, transplanted in August, and harvested in December (Trinh Hoai Duc, 1972, p. 157). Agricultural techniques remained rudimentary and technologically backward; chemical fertilizers were not used, irrigation systems were underdeveloped, and farming activities depended heavily on natural rainfall.

Although major canals such as Vinh Te and Thoai Ha had been constructed, their primary functions were transportation and drainage rather than effective irrigation, limiting their contribution to agricultural productivity.

By the mid-nineteenth century, a wider range of rice varieties was cultivated in An Giang and other southern provinces, including varieties such as heo ran, lua chim, lua trang, and early-maturing rice strains that required only three months from transplanting to harvest, such as lua bang and heo trang. In addition to rice, farmers cultivated secondary crops, including maize, beans, sesame, and tubers. During the period of French colonial rule, recognizing An Giang's agricultural potential, colonial authorities introduced new rice varieties, including nep dum, nep reychlo, nep pontia, floating rice varieties originating from Cambodia, as well as early and late season rice varieties (Le Hong Kham et al., 2013, p. 316). To support farmers in seed selection and dissemination, the colonial administration established a seed selection and distribution station in Long Xuyen in 1926; however, its results fell short of expectations.

Table 6. Rice Cultivated Area, Yield, and Output in An Giang (Chau Doc and Long Xuyen), 1935–1954

Province	1935-1940			1945-1954		
	Area (ha)	Yield (tons/ha)	Output (tons)	Area (ha)	Yield (tons/ha)	Output (tons)
Châu Đốc	100.600	1,07	107.300	150.000	1,10	165.000
Long Xuyên	163.150	1,31	214.700	122.250	1,10	134.50

Source: Le Hong Kham et al. (2013), p. 317.

Cultivation techniques for seasonal rice and floating rice during this period remained highly rudimentary. The use of mechanized plowing and harrowing was considered prohibitively expensive. In 1922, for example, the cost of cultivating one hectare of land using machinery was approximately three times higher than plowing with buffaloes or cattle, not including the substantial capital required for purchasing and maintaining agricultural machinery. Moreover, large areas of An Giang consisted of waterlogged terrain that could not support the weight of machinery manufactured at the time.

Farmers made little use of chemical fertilizers or pesticides; when such inputs were applied, they were largely confined to French-owned plantations rather than smallholder farms. As a result, agricultural productivity remained low. In years affected by natural disasters such as floods or droughts, crop failures were common, leaving farmers particularly vulnerable to poverty and food insecurity. Existing irrigation works were insufficient to meet the demands of effective water supply for agricultural production. In addition to maize, other food crops such as mung beans and sweet potatoes were cultivated on relatively large areas, yet their yields were similarly limited and did not significantly exceed those of rice.

Table 7. Area and Yield of Selected Crops in An Giang (Chau Doc and Long Xuyen), 1929

Crop	Area (ha)	Yield
Mung bean	2.530	360kg/ha
sweet potato	1.187	1 ton/ha
Tobacco	30	680kg/ha

Source: Le Hong Kham et al. (2013), p. 317.

Based on the above statistical data, it can be observed that agricultural production in An Giang during the French colonial period experienced certain changes and developments compared with the feudal Nguyen dynasty period. Although French colonial authorities primarily focused on extractive colonial exploitation to serve their own interests, several policies and

infrastructural improvements contributed to the expansion of cultivated land and to increases in agricultural productivity in An Giang.

During the period 1955–1960, relative political stability enabled the government of the Republic of Vietnam under Ngo Dinh Diem to implement land policies and promote agricultural expansion. Rice continued to dominate crop production in An Giang during this period. Cultivated varieties included early-season rice such as lua chuoi and Nang quot; medium-season varieties such as Nang tay, Nang len, and Nang kieu; and late-season varieties such as Nang rung, Nam Vang, Tau binh, Tham dung, Trung hung, Lua xanh, Cao gian, and Duoi trau...

Table 8. Cultivated Area and Rice Output in the 1956–1957 Cropping Season

Chau Doc Area

Rice Type	Area (samples)	Output (tons)
Broadcast rice (mid-season)	14.721	11.000
Broadcast rice (main season)	76.496	95.000
Transplanted rice (early)	226	300
Transplanted rice (mid-season)	17.258	19.000
Secondary-season rice	226	250
Broadcast glutinous rice	303	432
Transplanted glutinous rice	1.196	1.315
Total	110.426	127.297

Long Xuyen Area

Rice Type	Area (samples)	Output (tons)
Mid-season rice	30.247	42.346
Main- and late-season rice	93.306	147.689
Lua giang rice	108	130
Total	122.661	190.165

Source: Fonds 29, Presidential Office of the First Republic of Vietnam, 1957, p. 4.

During this period, the total area under rice cultivation in An Giang (including Chau Doc and Long Xuyen) was approximately 233.087 hectares. Rice output fluctuated around 317.000 tons, with an average yield of about 1,3 tons per hectare.

At the same time, floating rice (lua noi) represented a distinctive rice variety widely cultivated in An Giang and several other provinces of the Mekong Delta. This traditional variety had been grown for generations and was particularly suited to areas frequently affected by seasonal flooding, where conventional rice varieties were unable to thrive. Floating rice was especially favored in An Giang during the flood season due to its strong adaptability to deep and prolonged inundation lasting five to six months, its minimal requirement for chemical fertilizers, and its relatively high resistance to pests and diseases.

In An Giang, floating rice varieties were commonly classified into three groups based on growth duration and tolerance to flooding. The early group was harvested from early to mid-December and included varieties such as lua nep, Nang choi, and Nang son. The mid-season group was harvested from mid to late December and comprised varieties such as Ba bong, Nang tay dum, Chet cut, Sa mo chim, and Nang tay lon. The late group was harvested from early to late January of the following year and included varieties such as Tau binh, Nang tri, Nang rung, and Tham dung.

In addition to rice, An Giang during this period cultivated a range of other crops. The most important among these were tobacco, sugarcane, maize, and beans. As the cultivation of these crops expanded, the total cultivated area continued to increase, and agricultural output rose

proportionally. The results of this expansion are summarized in the following table.

Table 9. Crop Cultivation in An Giang over Selected Years

Crop	Cultivation Year	Cultivated Area (ha)	Output (tons)	Yield (tons/ha)
Rice	1939-1940	100.600	170.000	1,7
	1954-1955	150.000	165.000	1,12
	1955-1956	136.200	147.000	1,10
	1956-1957	110.500	129.900	1,13
	1957-1958	237.900	314.000	1,30
	1958-1959	283.900	401.300	1,39
	1959-1960	293.500	337.400	1,74
Maize	1959-1960	2.391	2.943	1,23
	1960-1961	3.630	4.220	1,16
Soybean	1959-1960	552	295	0,53
Mung bean	1959-1960	3.788	2.634	0,69
Tobacco	1958	1.030	1.030	1,0
	1959	780	780	1,0
	1960	960	1.830	1,2

Source: Southern Vietnam Economic Planning Department Fonds, 1969.

During the French colonial period, fertilizers and pesticides were primarily used on industrial plantations, where colonial authorities sought to protect crops of high economic value such as rubber and coffee. Basic pest control chemicals were applied on these plantations but were rarely disseminated to rice farmers in An Giang. During the period 1955–1960, floating rice remained the dominant rice variety cultivated in An Giang; consequently, the demand for chemical fertilizers and pesticides in rice production was relatively limited compared to other regions.

At the same time, the gradual replacement of animal traction with agricultural machinery began to take place. From 1955 onward, tractors and plowing machines were introduced into land preparation activities, helping to reduce manual labor and improve land preparation efficiency. These machines were primarily applied in large fields and areas with relatively flat terrain. Mechanization enabled farmers to shorten cultivation time and ensure more uniform plowing, thereby facilitating planting operations. During the 1955–1956 period, the United States provided assistance to the Cai San settlement zone, supplying a total of 132 tractors (Son Nam, 1988, p. 199).

In addition, agricultural support programs implemented through agricultural cooperatives expanded, particularly through credit loans provided by the An Giang agricultural credit office to finance machinery purchases for land reclamation and agricultural production. In 1958, for example, Luong An Tra Cooperative purchased one D.W.45 Allis-Chalmers tractor with attached plowing equipment and one Joker water pump; Luong Phi Cooperative acquired one D-17 tractor, one plow set, one harrow set, one water pump, and one HD-6 canal-digging machine; and Thoi Thuan Cooperative obtained loans to purchase one Caterpillar D-4 tractor, two Lanz tractors (64 horsepower), and ten Fordson tractors (55 horsepower) (Fonds 172, Bank for Agriculture and Rural Development [Agricultural Credit Office], 1963).

In summary, agriculture in An Giang during the period 1955–1960 under the government of the Republic of Vietnam achieved certain notable results, particularly in land reform, mechanization, and credit support through agricultural cooperatives. However, these measures

were insufficient to ensure stable and sustainable agricultural development in the province.

Agriculture in An Giang during the Period 1961–1965

From 1960 onward, the Vietnam War intensified as U.S. military involvement expanded. Rural areas in An Giang key agricultural production zones became contested spaces between the armed forces of the Republic of Vietnam and the National Liberation Front. As a result, agricultural production conditions for farmers deteriorated compared to the previous period. After 1963, successive transitional governments did not introduce major new land reform initiatives; instead, agricultural reform policies introduced under Ngo Dinh Diem continued to be implemented during the early 1960s. The government of the Republic of Vietnam maintained its reliance on earlier land policies while encouraging farmers to expand rice cultivation and diversify crop production.

With substantial support from the United States, the Republic of Vietnam government also expanded the Strategic Hamlet Program from 1962 onward as part of its “Special War” strategy. This program aimed to separate rural populations from communist forces by concentrating residents into newly established hamlets. However, the forced relocation of populations into these settlements disrupted agricultural production and resulted in land loss or reduced access to farmland for many farmers. Although initially promoted as a measure to protect rural populations from conflict, the Strategic Hamlet Program generated significant adverse effects on agricultural production and rural livelihoods. These impacts profoundly affected both agricultural output and the living conditions of farming communities in An Giang.

Table 10. Crop Cultivation in An Giang over Selected Years

Crop	Cultivation Year	Cultivated Area (ha)	Output (tons)	Yield (tons/ha)
Rice	1960-1961	230.600	473.200	2,05
	1961-1962	234.400	294.200	1,25
	1962-1963	290.716	458.952	1,57
	1965-1966	183.297	290.422	1,58
Maize	1961	3.626	No data available	1,5
	1962	3.196	No data available	1,5
Mung bean	1961	4.150	3.080	
	1962	4.450	3.337	
Soybean	1961	199	199,750	
	1962	552	473,860	
Sweet potato	1961	880	6.160	
	1962	913	6.391	
Tobacco	1961	1.020	739	
	1962	888	943	

Source: Fonds of Collected Documents, 1963, p. 51.

Despite persistent constraints on agricultural production, An Giang gradually began to shift from traditional crop varieties toward crops with higher economic value, including rice, vegetables, and fruit trees. This transition was supported by experimental research conducted at the Binh Duc Seed Testing Center, which developed and introduced crop varieties adapted to the province’s soil conditions and climate. Alongside traditional varieties, a range of new rice varieties was introduced into production.

Early-season and broadcast rice varieties included Nang son, Cu la, and Nang cho, which were primarily cultivated in elevated areas. Transplanted rice varieties introduced during this phase included Tunsart, Sardeum, Ba Nguon, and Samo, which were cultivated in districts such as Thot Not, Tri Ton, and Cho Moi.

Mid-season rice varieties cultivated through broadcast seeding included Nang Tay (Long Xuyen), Nang Kieu and Nang Dum To (both Long Xuyen and Chau Doc), and Nang len (Chau Doc). Transplanted mid-season varieties included Hai Tram, Tau Nut, and Bong Dua, mainly grown in Thot Not and Cho Moi.

Main-season and flood-season rice varieties cultivated through broadcast seeding included Tau Binh, Nang Rung, Nam Vang, Song Doi, and Duoi Trieu, which were widely grown in the lowland areas of Long Xuyen and Chau Doc. Transplanted main-season varieties included Ca Dung, Lua Mia, Tau Cut, Nang Xom, Tau Lai, and Bong Sen, cultivated primarily in Thot Not and Tri Ton. Late-season broadcast rice varieties included Trung Hung and Tham Dung, mainly grown in Thot Not.

With assistance from the United States, substantial quantities of agricultural machinery and pesticides were introduced into the Cai San settlement zone and agricultural cooperatives. At the same time, the government of the Republic of Vietnam continued to expand agricultural credit programs in An Giang, enabling farmers to access preferential loans for investments in fertilizers, pesticides, improved seed varieties, and farm machinery. These measures contributed to enhancing agricultural productivity and played an important role in ensuring regional food security.

Table 11. Interprovincial Shipment of Rice and Paddy from An Giang

Exported Product	1962 (*)	1963 (**)	1965 (***)
Paddy rice	57.734,200 tons	97.791 tons	40.586 tons
Milled rice	10.818,400 tons	8.167 tons	20.730 tons

Source:

(*) *Fonds of Collected Documents, 1963, p. 50.*

(**) *Fonds 29, Presidential Office of the First Republic of Vietnam, 1963, p. 5.*

(***) *Southern Vietnam Economic Planning Department Fonds, 1969.*

The period from 1961 to 1965 marked a phase of continued, though limited, agricultural development in An Giang under the government of the Republic of Vietnam. Despite numerous difficulties, policies related to land reform, agricultural credit, mechanization, and extension services contributed to the formation of a basic foundation for subsequent agricultural development.

Living Conditions and Rural Livelihoods

Economic hardship: Despite the implementation of land reform policies, the living conditions of the majority of farmers did not improve substantially. Food shortages and limited access to productive resources remained widespread. Farmers continued to face significant obstacles in accessing capital, farming tools, fertilizers, and other inputs necessary to optimize agricultural production. As a result, agricultural productivity remained low, and rural living standards showed little improvement compared to earlier periods.

Security instability: This period coincided with the escalation of the Vietnam War, which had a profound impact on rural security conditions. Armed conflict between the government of the Republic of Vietnam and communist forces forced many farmers to evacuate temporarily or prevented them from cultivating their land on a stable basis. In several areas, agricultural land was abandoned as rural residents fled conflict zones.

The settlement policy contributed to the formation of social groups supportive of the Ngo Dinh Diem administration, particularly among certain segments of the rural population. At the same time, it facilitated the resettlement of migrant groups, especially Catholic migrants from northern Vietnam who moved south following the Geneva Accords of 1954.

Disruption caused by the Strategic Hamlet Program: The Strategic Hamlet Program, implemented by the Republic of Vietnam government, sought to concentrate rural populations

into designated settlements in order to enhance security and administrative control while isolating communist forces. However, this program significantly disrupted agricultural production and rural livelihoods. Many farmers were compelled to abandon their land or lost effective control over cultivation activities, leading to declines in productivity and increased economic vulnerability.

Although An Giang possessed favorable natural conditions for agricultural production particularly for rice varieties such as Tau Binh and Nang Tay the province's agricultural economy during the period 1955–1965 did not achieve substantial or sustained growth. Heightened security instability after 1963, weak infrastructure, and the limited effectiveness of reform policies constrained economic development. Agricultural production remained largely subsistence-oriented and small-scale, insufficient to meet broader economic development needs in South Vietnam.

Land reform policies failed to significantly reduce socioeconomic inequality. Large landowners continued to control a substantial share of economic resources, while most farmers remained poor. This situation intensified social stratification and undermined social stability, contributing to declining public trust in the Republic of Vietnam government.

Agricultural development was also heavily dependent on foreign assistance, including programs that provided fertilizers, improved seeds, and farming tools. However, ineffective management and persistent security instability substantially reduced the effectiveness of these programs. Farmers encountered difficulties accessing available resources, and excessive reliance on foreign aid prevented the agricultural economy from developing in a self-sustaining manner.

Overall, agricultural outcomes during this period were limited by infrastructural constraints, security instability, and ineffective policy implementation. Rural living conditions remained difficult, agricultural production was unstable, and the agricultural economy failed to achieve sustainable development. Prolonged conflict and warfare also generated long-term negative effects that continued to shape the province's development trajectory in subsequent decades.

CONCLUSION

From the period of French colonial rule, An Giang Province (including Chau Doc and Long Xuyen) was recognized for its favorable natural conditions and fertile land, leading colonial authorities to regard it as a key rice-producing region within the Mekong Delta. Nevertheless, the colonial administration failed to implement comprehensive policies to fully develop the province's agricultural potential.

Following the establishment of the Republic of Vietnam, Ngo Dinh Diem introduced policies aimed at the “modernization of agriculture and rural development” in South Vietnam. Consequently, agricultural development in An Giang was strongly influenced by political, economic, and social factors. Land reform under the Ngo Dinh Diem administration represented an attempt to address land inequality and to provide land access for poor farmers, thereby promoting agricultural production and improving rural livelihoods. Decrees No. 2, 7, and 57 sought to redistribute land from large landowners to land-poor and landless farmers.

In addition, agricultural support programs implemented through cooperatives, farmers' associations, and especially agricultural credit offices provided various forms of assistance, enabling farmers to access improved seed varieties, fertilizers, pesticides, and mechanized equipment for land preparation and production. These measures reflected efforts to introduce scientific and technical innovations into agricultural practice. However, these policies were often driven more by political objectives than by economic considerations.

In particular, the implementation of the Strategic Hamlet Program and the forced relocation of farmers into controlled settlements severely restricted farmers' autonomy in agricultural production. Many farmers lost confidence in the Republic of Vietnam government as these policies were perceived as mechanisms of control rather than genuine efforts to protect rural

livelihoods. As a result, social dissatisfaction increased, and maintaining social stability became increasingly difficult.

Despite certain reform efforts and agricultural support measures during the most stable phase of the Republic of Vietnam administration, agricultural policies ultimately failed to achieve their intended goals. They did not substantially improve farmers' living standards, nor did they generate durable social transformation. Consequently, these shortcomings contributed to broader failures in both economic development and political legitimacy.

REFERENCES

An Giang Provincial Party Committee. (2007). *History of the An Giang Provincial Party Committee, Vol. II (1954–1975)*. An Giang: An Giang Provincial Party Committee Publishing House.

Department of Land Affairs and Land Reform (Republic of Vietnam). (1960). *Land Reform Law*. National Archives Center II (Vietnam).

Economic Institute. (1960). *Vietnamese Economy, 1945–1960*. Hanoi: Truth Publishing House.

Executive Committee of Thoai Son District Party Committee. (1997). *Thoai Son: Fifty Years of Struggle and Construction (1945–1975)*.

Le Dinh Trong. (2020). *Agricultural Economy of the Republic of Vietnam, 1955–1975*. Hanoi: Social Sciences Publishing House.

Le Hong Kham, et al. (2013). *An Giang Gazetteer*. An Giang: An Giang Provincial People's Committee.

Ngo Dinh Nhu. (1962). *Fundamental Theory of the Strategic Hamlet Program in the Republic of Vietnam*. National Archives Center II (Vietnam).

Phuong Tran. (1968). *Land Reform in Vietnam* (pp. 245–259). Hanoi: Social Sciences Publishing House.

Presidential Office of the First Republic of Vietnam. (1957). *Monthly Activity Reports of An Giang Province, March–December 1957 (Part II: Administration, Economy, Society, Finance)*. Fonds 29, File No. 135. National Archives Center II (Vietnam).

Presidential Office of the First Republic of Vietnam. (1957). *Submission Report on Administrative, Economic, Social, and Financial Conditions (May 1957)*. Fonds 29, File No. 135. National Archives Center II (Vietnam).

Presidential Office of the First Republic of Vietnam. (1958). *Monthly Bulletin A, February 20–March 20, 1958*. Fonds 29, File No. 205. National Archives Center II (Vietnam).

Presidential Office of the First Republic of Vietnam. (1959). *Monthly Bulletin A, September 1–30, 1959*. Fonds 29, File No. 205. National Archives Center II (Vietnam).

Presidential Office of the First Republic of Vietnam. (1961). *Application for Land Exploitation in My Lam–Tan Hoi Area*. File No. 11747. National Archives Center II (Vietnam).

Presidential Office of the First Republic of Vietnam. (1961). *Settlement Plan for Ba Bai Area*. File No. 12658. National Archives Center II (Vietnam).

Presidential Office of the First Republic of Vietnam. (1963). *Quarterly Activity Report of An Giang Province, Third Quarter 1963*. Fonds 29, File No. 594. National Archives Center II (Vietnam).

Presidential Office of the First Republic of Vietnam. (1959). *Monthly Bulletin A, June 1959*. File No. 310. National Archives Center II (Vietnam).

Presidential Office of the First Republic of Vietnam. (1963). *Quarterly Activity Report of An Giang Province*. File No. 594. National Archives Center II (Vietnam).

Provincial Administrative Office of An Giang. (n.d.). *Administrative Records of An Giang Province*. File No. 831. An Giang Archival Office.

INTERNATIONAL TOPKAPI CONGRESS VI

Provincial Administrative Office of An Giang. (n.d.). *Administrative Records of An Giang Province*. File No. 776. An Giang Archival Office.

Son Nam. (1988). *History of An Giang*. An Giang: An Giang General Publishing House.

Southern Vietnam Economic Planning Department. (1969). *Files on Population and Agricultural Conditions in An Giang, Dinh Tuong, Kien Hoa, Kien Phong, Kien Tuong, and Long An*. File No. 09. National Archives Center II (Vietnam).

Trinh Hoai Duc. (1972). *Gia Dinh Thanh Thong Chi*. Hanoi: Education Publishing House.

Tran Van Dinh. (1974). *Studies on Settlement Movements in Vietnam in the Past*. National Defense Review, No. 45.

Vietnam Communist Party, Executive Committee of An Giang Provincial Party Committee. (2007). *History of the An Giang Provincial Party Committee, Vol. II (1954–1975)*. An Giang: Provincial Party Committee Publishing House.

Vo Thi Hong. (1997). *Economic Conditions in An Giang during the French Colonial Period (1867–1929)*. Ho Chi Minh City: Institute of Social Sciences.

**THE IMPACT OF INSTITUTIONAL QUALITY ON ECONOMIC GROWTH: THE
CASE OF THE BRICS-T COUNTRY GROUP AND “THE GREASING THE
WHEELS” EFFECT**

KURUMSAL KALİTENİN EKONOMİK BÜYÜME ÜZERİNE ETKİSİ: BRICS-T ÜLKE
GRUBU ÖRNEĞİ VE “GREASING THE WHEELS” ETKİSİ

Dr. Öğr. Üyesi Duygu ÇELİK

İstanbul Gelişim Üniversitesi, Meslek Yüksekokulu,
Finans, Bankacılık ve Sigortacılık Bölümü, Avcılar, İstanbul.
ORCID: 0000-0003-3298-2152

ABSTRACT:

One of the most fundamental topics in macroeconomics is economic growth. Therefore, the factors influencing economic growth have been studied for years and are a subject of interest in the literature. However, the phenomenon of economic growth can be affected by different factors and in different ways depending on the dynamics and periods of a country. The concept of institutional quality is one of the topics frequently discussed in recent times. Its significant contribution to the growth and welfare levels of developed countries, in particular, increases interest in the subject and phenomenon. This study examines the impact of institutional quality on economic growth specifically within the BRICS-T group of countries: Brazil, Russia, India, China, and Türkiye. Estimated data on indicators representing institutional quality and economic growth indicators for these countries were obtained from the World Bank's The Worldwide Governance Indicators (WGI) database. The study includes data from 2000 to 2023 for these countries. The results of the study confirm the "Greasing the Wheels" effect found in the literature, specifically for this selected group of countries. Because an analysis using the Institutional Quality Index has shown that a one-unit increase in the Institutional Quality Index leads to a 2.20-point decrease in the economic growth rate. When examining the selected group of countries, it can be seen that they all share a common point. These countries are among the developing countries, and as described in the literature, they may have long bureaucratic processes, rigid rules, weaker institutions compared to developed countries, and are more authoritarian. Their levels of democracy may remain weaker than those of developed countries. Therefore, corruption, petty bribes, and inflexible regulations can be used as tools to overcome complex and lengthy bureaucratic processes. In such a situation, a sudden increase in strict regulations and controls can result in a short-term slowdown in the speed of doing business in the markets. Considering all these processes within the scope of policy recommendations, it is important that reforms are not implemented quickly and in a short period of time, but gradually, so that the increase in institutional quality does not negatively impact growth.

Keywords: Economic Growth, Institutional Quality, Developing Countries, Corruption, Structural Reform

JEL Codes: F43, O17, O50, D73, P11

ÖZ:

Makro iktisadın en temel konularından birisi ekonomik büyümedir. Bu nedenle ekonomik büyümeye etki eden faktörler üzerinde yıllardır çalışılan ve literatürde ilgi duyulan konulardan bir tanesidir. Fakat ekonomik büyüme olgusu ülkelerin dinamiğine ve dönemlerine göre farklı faktörlerden ve farklı şekillerde etkilenebilmektedir. Kurumsal kalite olgusu son dönemin üzerinde sıklıkla durulan konularından bir tanesidir. Özellikle de gelişmiş ülkelerin büyüme ve refah seviyelerinin ilerlemesine büyük katkıda bulunması konuya ve olguya olan ilgiyi arttırmaktadır. Bu çalışmada kurumsal kalitenin ekonomik büyüme üzerinde nasıl bir etkisi bulunduğu BRICS-T ülke grubu özelinde incelenmiştir. Bu ülkeler sırasıyla Brezilya, Rusya, Hindistan, Çin ve Türkiye'dir. Bu ülkelerin kurumsal kaliteyi ifade eden göstergelerine ait tahmin verileri ve ekonomik büyüme göstergeleri Dünya Bankasının Küresel Yönetişim Endeksi (WGI) veri tabanından elde edilmiştir. Çalışmaya ülkelerin 2000 ile 2023 yılları arasındaki verileri dahil edilmiştir. Çalışmanın sonucu literatürdeki "Greasing the Wheels" etkisini seçili ülke grubu özelinde doğrular yöndedir. Çünkü kurumsal kalite endeksi (KKO) ile yapılan analizde kurumsal kalite endeksindeki 1 birimlik artış, ekonomik büyüme oranını 2.20 puanlık bir azalışa neden olduğu görülmüştür. Seçilen ülke grubu incelendiğinde hepsinin tek bir ortak noktası olduğu görülebilmektedir. Bu ülkeler gelişmekte olan ülkeler arasında yer alıp, literatürde tarif edildiği gibi bürokrasi süreleri fazla olabilen, katı kuralları olan, kurumları gelişmiş ülkelerle kıyasladığımızda daha zayıf olan ve daha otoriter ülkelerdir. Demokrasi düzeyleri gelişmiş ülkelere göre daha zayıf yapıda kalabilmektedir. Bu nedenle yolsuzluk, küçük rüşvetler ve esnek olmayan bir takım düzenlemelerin karmaşık ve uzun süreçli bürokrasiyi aşmak için bir araç olarak kullanılmasına neden olabilmektedir. Böyle bir durumda sıkı düzenlemeler ve denetimlerin aniden çoğalması piyasalarda iş yapma hızının kısa vadede yavaşlaması ile sonuçlanabilmektedir. Politika önerileri kapsamında bütün bu süreçler ele alındığında, kurumsal kalitedeki artışın büyümeyi negatif yönde etkilememesi için reformların hızlı ve kısa sürede yapılmaması, kademeli olarak uygulamaya geçirilmesi önemlidir.

Anahtar Kelimeler: Ekonomik Büyüme, Kurumsal Kalite, Gelişmekte Olan Ülkeler, Yolsuzluk, Yapısal Reform

Jel Kodları: F43, O17, O50, D73, P11

1. INTRODUCTION

When examining the topics of macroeconomics, it is evident that the phenomenon of economic growth forms the basis of modern macroeconomics and is one of the cornerstones of countries' macroeconomic policies. Looking at growth theories that describe the pathways to economic growth, neoclassical and endogenous growth theories have linked an economy's growth to a country's capital accumulation, technology, and labor force (Solow, 1956; Romer, 1994). However, later studies have shown that these factors, which neoclassical and endogenous growth theories identify as the source of economic growth, cannot alone explain economic growth and welfare improvements in a country (Easterly & Levine, 2003). In recent times, particularly in the last 25-30 years, the institutional quality factor has begun to be included in macroeconomic studies, and its impact on economic growth has been investigated. Therefore, this study will also be a focus of interest in the literature and will contribute to the limited number of studies on this subject, filling a gap in the literature.

Institutions within a country consist of a whole system of laws, regulations, or rules shaped by the society's own traditions and norms, which interact with all individuals in society in various ways (North, 1990). High-quality institutions enhance the sense of security among economic actors, reducing risk perception. This allows entrepreneurs to operate more comfortably in long-term investments due to increased confidence in the markets. The effectiveness and high quality

of institutions also ensure strong protection of property rights, preventing anxiety among individuals and businesses. Trust in the validity of contracts is high, political stability is observed, and events that undermine trust in institutions, such as corruption, are either absent or less frequent in economies with high institutional quality.

Economic growth is a macroeconomic phenomenon that can be determined by plenty of economic factors. Hence, having well built and comprehensive economic institutions is one of the prerequisites for leading a country's economy to welfare. Principally the study of Acemoglu, Johnson, and Robinson (2001) has left a mark on the literature, demonstrating how paramount the quality of institutions is and how much they contribute to the economic growth and development of countries. The researchers have shown how countries that were formerly colonial powers and still possess exploitative institutions as a legacy of those periods have lagged behind economically, while countries that have improved the quality of their institutions have been able to grow economically and increase their levels of prosperity.

This study examines the impact of institutional quality on economic growth, specifically within the BRICS-T group of countries. This group consists of Brazil, Russia, India, China, South Africa, and Türkiye added by the author). The study covers the period between 2000 and 2023. Data on institutional quality indicators and economic growth were obtained from the World Bank database. The main objective of the study is to investigate whether different components of institutional quality indicators have an impact on the economic growth of the selected country economies. Institutional quality indicators are fundamentally composed of six sub-indicators: rule of law, control of corruption, government effectiveness, voice and accountability, political stability and absence of violence/terrorism, and regulatory quality. Under the rule of law, issues such as the enforcement of contracts in an economy, the protection of property rights, and the reliability of law enforcement agencies such as the police and courts are examined. Under the control of corruption, it is examined whether public officials use their authority derived from public office for their own private interests. Under the effectiveness of government, the quality of services provided by the state, its ability to formulate policies, and its ability to implement these policies effectively are examined. The voice and accountability clause refers to the degree of citizen participation in elections. The political stability and absence of violence/terrorism clause refers to the stability of political election processes in a country and the absence of acts of violence and terrorism. Regulatory quality refers to the ability of the public sector to prepare and implement sound and productive policies for the private sector.

This study examines the impact of six variables on economic growth both individually and by averaging these indicators to create a single institutional quality index, the impact of this index on economic growth being further investigated. The two-part, detailed nature of the study introduces a novel approach to research examining the impact of institutional quality on economic growth. Furthermore, to robustly determine the causal relationship in the presence of heteroskedasticity, autocorrelation, and cross-sectional dependence, the Huber, Eicker, and White estimator, robust to these factors, was used, resulting in a more robust and reliable relationship between institutional quality and economic growth. The findings will guide countries in supporting and achieving economic growth, one of their fundamental macroeconomic goals, by determining the direction of the impact of institutional quality and will offer concrete recommendations on which institutional reforms should be prioritized and in what way.

2. LITERATURE REVIEW

In modern macroeconomic thought, there is a consensus that the quality of institutions, rather than geographical features or trade, is the determining factor in a country's economic growth and stable development of prosperity. First examined by North (1990), this issue suggests that institutions within a country are decisive in influencing economic actors and shaping their

behavior. Acemoglu, Johnson, and Robinson (2001) have the most influential work empirically investigating and substantiating this view. In their research, the authors established a connection between the institutional culture and structure inherited from periods of historical colonization in countries and the current institutional culture and structure, concluding that the quality, effectiveness, and structure of these institutions have a significant impact on economic growth. Besides, Rodrik, Subramanian, and Trebbi (2004) made a further subscription to these studies, emphasizing that institutions are the most efficacious, variable on economic growth when as per the geography of countries and international trade factors. Glaeser et al. (2004) state that the key variables used in studies on this subject, and their exogeneity and validity, are among the most debated issues.

When examining the relationship between institutional quality and economic growth, the mutual influence of variables can be concentrated through a number of indicators such as physical capital investment and total factor productivity. Knack and Keefer (1995) state that when a high level of institutional quality is observed in an economy, especially when property rights are strongly protected and the rule of law is fully implemented, this significantly reduces uncertainties in the markets and allows investments to be made with confidence. Knack and Keefer (1995) have shown that in such an economy, investors feel secure and can make investments more comfortably and freely, which encourages investment. Hall and Jones (1999), on the other hand, define institutions as a kind of social infrastructure and state in their study that they support the use of technology and efficient resource allocation. In this way, they empirically demonstrated that an increase in total factor productivity can be observed.

Mauro (1995), in his research, surveyed corruption as a sub-indicator of institutional quality. His work disclosed the extent to which corruption negatively impacts economic growth. Even so, a vision contrary to Mauro's (1995) findings also presents in the literature. Some studies argue that in precise situations, corruption can also have positive impact, explaining this as follows: Principally in places with extensive bureaucratic processes, small-scale corruption and bribery can play a role in accomplishing barren and unproductive regulations, accelerating economic activity and contributing to economic growth. Leff (1964) is one of the authors who encourages this view. He argues that by circumventing bureaucracy through corruption, resources can be directed to entrepreneurs. Huntington (1968), particularly in developing countries, states that corruption can overcome rigid regulations, that institutions are weakly structured, and that corruption fills this gap in the economy, thus contributing to economic growth. Dreher et al. (2013) are among the researchers who argue that small-scale bribes facilitate the flow of international trade by eliminating the problem of complex bureaucracy. This effect of corruption mentioned in these studies is referred to in the literature as the **"Greasing the Wheels Theory"**. Although there are some studies in the literature that defend corruption in this way, the dominant view is that the negative effects of corruption far outweigh the small positive effects.

In conclusion, the literature generally states that the quality and effectiveness of institutions have a significant impact on economic growth. This study differs from other studies because it both analyzes the impact of six different institutional quality indicators individually by breaking them down into their subcomponents, and also reduces these values to a single institutional quality index for further analysis. In addition, the study is expected to contribute to the literature by being supported by a robust panel time series analysis and by investigating dynamic and heterogeneous effects. In these respects, the study fills gaps in the literature.

3. A STRUCTURE THAT LAID THE GROUNDWORK FOR ECONOMIC GROWTH: INSTITUTIONAL QUALITY

North (1990) defines institutions as the rules of the game in a country, while institutional quality is an indicator of how fair, transparent, and implementable these institutions are. Although

traditional views explaining economic growth have seen capital and labor as the primary drivers of economic growth, the most fundamental factor for sustainable economic growth is the quality and effectiveness of institutions. Institutional quality refers to the entire system that profoundly affects the productivity and performance of an economy (North, 1990). In economies with high institutional quality, the behavior of economic actors and their forms of interaction with each other are shaped accordingly, and investments and innovations develop in such an environment. If the goal is to minimize risks, prevent the creation of an environment of uncertainty, and reduce transaction costs in an economy, the quality of institutions must first be improved (Tutgun & Savaş, 2023).

Institutional quality indicators have many dimensions within themselves. These indicators are measured through international indices. Institutional quality has 6 core indicators. In this study, the impact of each of these 6 indicators on economic growth is examined individually, and their average is taken to transform them into a single institutional quality indicator, and their collective impact on economic growth is also examined. The 6 sub-indicators can be expressed as follows;

1. **Rule of Law:** This section covers issues such as the extent to which contracts are complied with in that economy, the level of reliability of contracts, whether property rights are adequately protected, and the independence of the judiciary. The existence of such a structure will positively impact investors in that economy and increase investments. The rule of law will be a source of confidence for investors and entrepreneurs, and their belief that their rights are protected will enable secure capital increases.
2. **Control of Corruption:** This section examines the extent to which individuals working in the public sector use their power to gain personal benefit. In economies with high levels of corruption, institutional quality is considered low, and even official institutions, which should be the most reliable structures, are thought to be corrupt. This situation increases the risk perception of entrepreneurs, causing them to be apprehensive and hesitant in undertaking new ventures. However, there are also some opposing views in the literature. According to this view, in some cases, small bribes can actually speed up processes and facilitate the entrepreneur's venture. It is stated that this could lead to an increase in entrepreneurial ventures.
3. **Regulatory Quality:** This part contains government policies and legislations that promote the private sector and are carried out to develop markets and the economy. The government is compelled to make the system more conducive to facilitate business for the private sector and stimulate entrepreneurship. In this context, it is prominent how basic, clear, and free from bureaucratic complexity the processes are, while also stimulating the system. If an economy lacks operative and efficient government regulations, and instead is plagued by bureaucracy, complexity, and obstacles, then the regulatory quality in that economy is poor. This status leads entrepreneurs to find markets unpredictable and complex, negatively effecting investment and development.
4. **Government Effectiveness:** This part surveys the quality of services ensured by the government to the markets and whether governments stick to their determination and the reliability of markets and the system. Investors give form their risk sense accordingly and make investment and consumption judgment based on this.
5. **Political Stability and Absence of Violence/Terrorism:** This evaluates the degree of stability in the political extent of an economy and the probability of experiencing violence stemming from terrorism. When risk levels increase for entrepreneurs, and political, economic, and other instabilities occur continuously, or violent events are observed, markets become less attractive for investment. This affects economic growth rates.

6. **Voice and Accountability:** This matter states the extent to which citizens living in a country are active in the government-determining process and elections, attend in elections, know and exercise their political rights, and effectively make use of the civil liberties that come with being an individual in society. The whole penetration of freedom of expression into markets and the existence of democracy decrease the risk perception of entrepreneurs, signaling that investments can be made safely in those markets. It aids minimize political and social instability. This is of great stature for economic activity.

These indicators individually reflect the content of institutional quality. Institutional quality, with its multifaceted extent, undeniably has an affect on a country's economic growth rates. When a country prioritizes the quality of its institutions and achieves improvements in this area, the costs of economic transactions will come on to decrease. In an economy where institutions function efficiently, corruption and bribery will be absent or minimal, eliminating the need for entrepreneurs to engage in arbitrary regulations. A steady and presumable market model will arise, helping investors make more informed and rational decisions about the future. Besides, a strong rule of law will ensure the development and widespread adoption of the financial system by effectively resolving debates arising from financial transactions and effectively protecting investor rights. Funds accumulated in capital markets will be directed to efficient areas, increasing total factor productivity. Total factor productivity can be stated as;

$$Y = f(K, L, A)$$

Y: Total output

K: Capital accumulation

L: Total workforce

A: Technological progress and productivity

In another words, the sum output level in an economy is affected by capital accumulation, labor force, and technological productivity in that country. There is a intercourse among technological progress and productivity (A) in this function and institutional quality. The institutional quality variable can influence the technological productivity level of an economy, resulting in a higher growth rate. Moreover, in economies where intellectual property rights are protected and valued, investors are more inclined to innovate. This is because the additional earnings brought about by innovation processes will be protected under intellectual property rights, and the investor's interests will not be harmed. Investors who are reliant in this status make direct investments in a country, facilitating its development and growth. In economies where rights are protected and innovation is encouraged, R&D activities increase, inevitably leading to technological progress. Whole these factors are the key to the sustainable, lasting, and stable growth of an economy. In short, institutional quality is a factor that encourages an economy to realize its true potential. It creates the necessary safe and stable market environment for this. Since developed countries have high levels of institutional quality, countries that invest in institutional quality not only achieve the fundamental macroeconomic goal of high growth rates, but also ensure that this growth is stable and sustainable, thus achieving significant success.

4. DATA AND METHODOLOGY

This study analyzes data from BRICS-T countries between 2000 and 2023. The BRICS-T group consists of Brazil, Russia, India, China, South Africa, and Türkiye. The impact of institutional quality indicators on economic growth for this group of countries has been examined. The concept of institutional quality itself comprises six sub-categories, which are presented in Table 1. The dependent variable of the study, economic growth, is also shown in Table 1.

Table 1: Dependent and Independent Variables and Their Explanations

Institutional Quality Sub-Indicators and Economic Growth	Abbreviations	Definition
GDP (annual % growth)	GDP	It represents the monetary value of goods and services produced in an economy during a specific period.
Control of Corruption: Estimate	COR	This encompasses cases of corruption and bribery, including whether and to what extent those holding public power use that power for their own benefit.
Government Effectiveness: Estimate	GOV	This section examines the quality of public services provided to markets and whether governments adhere to the decisions they make.
Political Stability and Absence of Violence/Terrorism: Estimate	POL	It measures the degree of stability of the political dimension in an economy and the likelihood of experiencing terrorism-related violence in the country.
Regulatory Quality: Estimate	REG	This article includes government policies and regulations aimed at developing markets and the economy, and supporting the private sector.
Rule of Law: Estimate	RUL	This article covers issues such as the extent to which contracts are complied with in that economy, the reliability of contracts, whether property rights are adequately protected, and the independence of the judiciary.
Voice and Accountability: Estimate	VO	This article describes the extent to which citizens living in a country are active in the government-determining process, participate in elections, are aware of and exercise their political rights, and effectively utilize the civil liberties that come with being an individual in society.
Institutional Quality (Average)	KKO	The average of the six sub-indicators was taken to reduce them to a single institutional quality index.

The indicators and data in Table 1 are taken from the World Bank's Worldwide Governance Indicators (WGI) database. This data was prepared by Daniel Kaufmann (Institute for Natural Resource Management and Brookings Institute) and Aart Kraay (World Bank Development Research Group) (Kaufmann, D., Aart K. and Massimo M., 2010).

The econometric model of the study can be shown in Equation 1. This equation represents the model of the study in which the institutional quality indicators are examined individually.

$$GDP_{it} = \alpha_0 + \beta_1 COR_{it} + \beta_2 GOV_{it} + \beta_3 POL_{it} + \beta_4 REG_{it} + \beta_5 RUL_{it} + \beta_6 VO_{it} + \mu_i + \lambda_t + \varepsilon_{it} \dots \dots \dots (1)$$

$i=1 \dots 6$
 $t=2000-2023$

The model for the study, in which the average of corporate quality indicators is reduced to a single institutional quality index, is shown in Equation 2.

$$GDP_{it} = \alpha_0 + \beta_1 KKO_{it} + \mu_i + \lambda_t + \varepsilon_{it} \dots \dots \dots (2)$$

$i=1 \dots 6$
 $t=2000-2023$

The symbols and their descriptions in the model are as follows: GDP (Economic Growth), COR (Control of Corruption), GOV (Government Effectiveness), POL (Political Stability and

Absence of Violence/Terrorism), REG (Regulatory Quality), RUL (Rule of Law), VO (Voice and Accountability), and KKO (Institutional Quality Index) (a single index was obtained for the study by averaging the sub-indicators of institutional quality). In this study, the average of these sub-variables was reduced to a single institutional quality indicator. In this way, the effect of institutional quality on economic growth was examined using data from BRICS-T countries between 2000 and 2023. The empirical analysis of the study was performed using panel data analysis with the STATA17 program.

In addition, the study also examined the sub-indicators of institutional quality individually and separately. The impact of all these variables on economic growth was also investigated individually. Before proceeding to model estimation, a series of preliminary descriptive tests were conducted to determine which estimator should be chosen. Based on the preliminary tests and the results obtained, it was decided to use the Huber, Eicker, and White: Pooled Least Squares estimator, which is robust to standard errors, to explain and estimate the model. This estimator was preferred because it is a second-generation, robust estimator applicable to random effects models, and also applicable when heteroskedasticity, autocorrelation, and inter-unit correlation are present. This is because the presence of these conditions was detected in the preliminary diagnostic tests.

Table 2 shows the results of the preliminary diagnostic tests performed on the model, where a single institutional quality index was created by averaging all variables.

Table 2. Preliminary Diagnostic Tests and Results for the Institutional Quality Index

Test Type	Test Name	p-value	Result
Cross-Section Dependency	Pesaran CD	GDP:0.0000 KKO: 0.066	There is cross-sectional dependence. Second-generation panel unit root analysis must be used.
Homogeneity	Swamy S	0.0000	Since the parameters vary from unit to unit, heterogeneous cointegration tests should be used.
LagLength Selection	Hansen J	1 lag	The appropriate lag length is 1.
Unit Root	MADF	> Approx 5% CV	The GDP variable is stationary at the level. The KKO variable becomes stationary after taking the first difference.
Unit Effect	F, LM, LR test	0.000	There is a unit effect.
Time Effect	F, LM, LR test	0.000	There is a time effect.
Robust Hausman	rH test	0.6648	A random effects model must be used.
Multicollinearity	Variance inflation factor (VIF)	Mean VIF=1.00	No multicollinearity
Normal Distribution	Jarque-Bera	Test=18.2 Chi2= 1.1e-04 r(skewness):-0.7878 r(kurtosis): 3.8257	There is a normal distribution. The error terms are slightly skewed and peaked to the left.
Autocorrelation	Durbin- Watson Baltagi-Wu, LBI	1.587 1.640	There is autocorrelation.
Heteroscedasticity	Levene, Brown and Forsythe Testi	W0: Pr>F= 0.14 W50: Pr>F= 0.24 W10: Pr>F= 0.17	There is not heteroscedasticity.

Examining the test results in Table 2 reveals that the model must be analyzed according to the random effects model and that second-generation estimators should be used. Furthermore, it is understood that the model has problems such as cross-sectional correlation and autocorrelation. Therefore, since a robust estimator capable of withstanding these deviations is needed, Huber,

Eicker, and White: Pooled Least Squares (robust standard errors) model estimation, which is suitable for these standard deviations, has been chosen. The estimation of this model will be performed using this estimator. Additionally, the preliminary diagnostic tests show a normal distribution. The graph of the model's normal distribution can be examined in Figure 1.




Figure 1: Normal Distribution Graph of the Institutional Quality Index

In Figure 1, the normality of the distribution was tested using Jarque-BERA tests. The graph shows that the error terms are slightly skewed and peaked to the left. Table 3 presents the model estimate. Due to the results of the preliminary diagnostic tests, the analysis was performed according to a random effects model. The Huber, Eicker, and White: Pooled Least Squares method, which has a robust standard error property, was chosen.

Table 3. Estimation Results of Huber, Eicker and White: Pooled Least Squares (Robust Standard Errors)

GDP	Coefficient	t	p > z
KKO	-2.205289	-2.24	0.02
Number of Obs.	144		
Prob>F	0.0269		

According to the results in Table 3, the p-value in the model estimation is significant because it is less than the critical value of 0.05. This means that the effect of institutional quality on economic growth is not a coincidence; it has a real impact on economic growth. According to Table 3, a 1-unit increase in the institutional quality index causes a 2.20-point decrease in the economic growth rate.

The study also examined the individual effects of the sub-indicators representing the institutional quality index. First, Table 4 presents the preliminary diagnostic tests and results for the institutional quality sub-indicators.

Table 4. Results of Model Tests Examined Separately for Each Indicator

Test Type	Test Name	p-value	Result
Cross-Section Dependency	Pesaran CD	GDP:0.0000 dCOR: 0.020 GOR:0.013 POL:0.068 REG:0.029 RUL:0.146 VO:0.011	There is no cross-sectional dependence for the RUL and POL variables. (Second-generation tests can also be preferred since the POL variable is not significantly higher than the critical value.) A first-generation panel unit root test should be preferred. There is cross-sectional dependence for the other variables. A second-generation panel unit root analysis must be used.
Homogeneity	Swamy S	0.0000	Since the parameters vary from unit to unit, heterogeneous cointegration tests must be used.
LagLength Selection	Hansen J	1 lag	The appropriate lag length is 1.
Unit Root	MADF	> Approx 5% CV	The GDP variable is stationary at the level. The other variables also become stationary after taking their first differences.
Unit Effect	F, LM, LR test	0.000	There is a unit effect.
Time Effect	F, LM, LR test	0.000	There is a time effect.
Robust Hausman	rH test	0.001	A fixed effects model must be used.
Multicollinearity	Variance inflation factor (VIF)	Mean VIF=3.72	No multicollinearity
Normal Distribution	Jarque-Bera	Test=5.187 Chi2=0.0748 r(skewness):0.3975 r(kurtosis): 2.4806	There is a normal distribution. The error terms are slightly skewed and peaked to the right.
Autocorrelation	Durbin- Watson Baltagi-Wu, LBI	1.9182 1.9705	There is autocorrelation.
Heteroscedasticity	Wald Test	Chi2 : 23.59 Prob>chi2 : 0.006	There is heteroscedasticity.

Examining the test results in Table 4 reveals that the model must be analyzed according to the fixed effects model and that second-generation estimators must be used. Furthermore, it is understood that the model has problems such as cross-sectional dependence, autocorrelation, and heteroskedasticity. Therefore, since a robust estimator is needed, Huber, Eicker, and White: Pooled Least Squares (robust standard errors), an estimator suitable for these standard deviations, was chosen for model estimation. The estimation of this model will be performed using this estimator. Additionally, the preliminary diagnostic tests show a normal distribution. The graph of the model's normal distribution can be examined in Figure 2.




Figure 2: Normal Distribution Graph of Intuitional Quality Sub-Indicators

In Figure 2, the normality of the distribution was tested using Jarque-BERA tests. The graph shows that the error terms are slightly skewed and peaked to the right. Table 5 presents the model estimate. Due to the results of the preliminary diagnostic tests, the analysis was performed according to the fixed effects model. The Huber, Eicker, and White: Pooled Least Squares method, which has a robust standard error characteristic, was chosen.

Table 5. Estimation Results of Huber, Eicker and White: Pooled Least Squares (robust standard errors)

	Coefficient	t	p > z
GDP			
COR	0.237117	1.06	0.292
GOV	-0.6653518	-0.36	0.721
POL	-1.710454	-2.29	0.024
REG	-0.6831275	-0.39	0.696
RUL	2.241519	1.32	0.190
VO	-2.29193	-3.17	0.002
Cons.	0.6260335	6.84	0.000
Number of Obs.	144		
Prob>F	0.0000		

When Table 5 is examined, the Political Stability and Absence of Violence/Terrorism: Estimate (POL) and Freedom of Expression and Accountability (VO), which are sub-indicators of institutional quality, were found to be significant in the model, while the other indicators were found to be insignificant. Accordingly, a 1-unit increase in the Freedom of Expression and Accountability (VO) variable causes a 2.29-point decrease in economic growth. A 1-unit increase in the Political Stability and Absence of Violence/Terrorism (POL) variable causes a 1.71-unit decrease in economic growth.

5. CONCLUSION, DISCUSSION AND POLICY RECOMMENDATION

One of the most fundamental topics in macroeconomics is economic growth. Therefore, the factors influencing economic growth have been studied for years and are a subject of interest in the literature. However, the phenomenon of economic growth can be affected by different

factors and in different ways depending on the dynamics and periods of a country. The concept of institutional quality is one of the topics frequently discussed in recent times. Its significant contribution to the growth and welfare levels of developed countries, in particular, increases interest in the subject and phenomenon. This study examines the impact of institutional quality on economic growth specifically within the BRICS-T group of countries: Brazil, Russia, India, China, and Türkiye. Estimated data on indicators representing institutional quality and economic growth indicators for these countries were obtained from the World Bank's Worldwide Governance Index (WGI) database. The study includes data for these countries from 2000 to 2023.

The results obtained from the study are striking. This is because the general consensus in the literature is that institutional quality positively affects economic growth. Studies have been conducted on this subject and results have been obtained in this direction. However, there are also views in the literature that argue that institutional quality will slow down economic growth. In other words, there are views that increase in institutional quality will not increase economic growth in some countries, and that, on the contrary, corruption and bribery, which lower the institutional quality index, may stimulate markets in some economies. Some studies have argued that corruption can also have some positive effects in some cases and have explained this situation as follows: Especially in places with a lot of bureaucratic processes, small-scale corruption and bribery can play a role in overcoming sterile and inefficient regulations and can contribute to economic growth by accelerating economic activity. Leff (1964) is one of the authors who supports this view. Leff (1964) states that resources can be directed to entrepreneurs by bypassing corruption and bureaucracy. Huntington (1968) argues that corruption can overcome strict regulations, especially in developing countries, where institutions are weakly structured, and that corruption fills this gap in the economy, thus contributing to economic growth. Dreher et al. (2013) are also among the researchers who argue that small-scale bribes facilitate the flow of international trade by eliminating the problem of complex bureaucracy. This effect of corruption mentioned in these studies is referred to in the literature as the "Greasing the Wheels Theory".

The survey's outcomes approves the "Greasing the Wheels" affect described in the literature, specifically for the selected group of countries. Analysis using the Institutional Quality Index demonstrates that a one-unit increment in the IQI leads to a 2.20-point reduce in economic growth. Examining the selected group of countries discloses a common characteristic: they are all developing countries, characterized by lengthy bureaucratic processes, rigid rules, weaker institutions compared to developed countries, and a more authoritarian structure. Their grade of democracy may keep weaker than those in developed countries. Therefore, corruption, petty bribes, and inflexible regulations can be used as tools to circumvent complex and lengthy bureaucratic processes. In such a situation, a sudden increase in strict regulations and controls can result in a short-term slowdown in the speed of doing business in the markets. Furthermore, reforms aimed at improving the institutional structure can increase transaction costs in the short term. Especially when the informal economy is high, new regulations and controls aimed at improving institutional quality can temporarily slow down the existing economic system. Furthermore, the positive effects of structural reforms aimed at improving institutional quality generally only become apparent after 5-10 years. Therefore, during periods when reforms are implemented, negative effects may be seen instead of positive ones. Finally, it should not be overlooked that the BRICS-T countries, the selected group of countries, have recently experienced significant economic crises and have high levels of vulnerability. Therefore, the positive effects of efforts to improve institutional quality may not be fully realized due to the impact of larger macroeconomic shocks.

When examining the indicators individually, the study shows that the variables Voice and Accountability (VO) and Political Stability and Absence of Violence/Terrorism (POL) have an

impact on economic growth, reducing it. Accordingly, in this group of countries, when freedom of expression and democratic rights increase, and when freedom of expression and accountability improve, economic growth decreases. This is supported by the "authoritarian growth model" approach in the literature. When the selected group of countries is examined, it is seen that these countries have a more authoritarian style of governance compared to developed countries. In such countries, when democratic processes improve, and dissent and oversight increase, rapid decision-making processes can be disrupted. This can lead to a slowdown in market activity. Besides, the political stability variable also negatively affected economic growth. This status can have many creates for emerging markets such as the BRICS-T group of countries. In some cases, political stability can actually mean the induration of the existing system. If such a political blockage exists and begins to embarrass reforms, economic growth can decelerate. Or, during long periods of power, the system may come in sight steady, but the lack of change in power over such a long time can be intensified networks of corruption. Resources may not be shared out to productive areas. This can lead to a deceleration in economic growth while presenting a seemingly stable picture, and inversely, economic growth can be triggered during periods when these processes are disrupted. Besides, countries like Russia, South Africa, and Brazil, which are included in the research, are rich in natural resources. These countries normally tend to focus on earning income through the selling of natural resources rather than on technology and innovation. When natural resource prices fall down, economic growth can decelerate even with political stability. In addition, when investors invest in developing countries, their primary focus is sometimes on taking advantage of high-risk but high-return periods. This can lead to capital inflows during periods of change where the system is disrupted and great opportunities arise, thus triggering economic growth.

When considering all these processes within the scope of policy recommendations, it is important that reforms are not implemented quickly and in a short period of time, but gradually, so that the increase in institutional quality does not negatively affect growth. The costs of the regulations for the markets should be studied, and support should be provided to the private sector. To prevent political stability from leading to economic rigidity, it is important to design the institutional structure to be more dynamic. In particular, legal procedures for technology and innovation sectors should be freed from traditional structures and made independent. The existence of the informal economy causes institutional quality to negatively affect the markets. Therefore, incentives should be prepared to support the transition to the formal economy in order to solve the problem of the informal economy. While trying to improve the sub-indicators of institutional quality, it can lead to resource waste and bureaucratic complexity. Therefore, institutions that can increase economic efficiency should be prioritized for structural reforms. Structural reforms should create a signal to investors in global markets that the country has increased its levels of transparency and predictability, and by attracting foreign direct investment, the negative impact of institutional quality on economic growth in the short term should be neutralized in the long term through direct investments.

REFERENCES

- Acemoglu, D., Johnson, S., & Robinson, J. A. (2001). The colonial origins of comparative development: An empirical investigation. *American economic review*, 91(5), 1369-1401.
- Dreher, A., & Gassebner, M. (2013). Greasing the wheels? The impact of regulations and corruption on firm entry. *Public choice*, 155(3), 413-432.
- Easterly, W., & Levine, R. (2003). Tropics, germs, and crops: how endowments influence economic development. *Journal of monetary economics*, 50(1), 3-39.
- Hall, R. E., & Jones, C. I. (1999). Why do some countries produce so much more output per worker than others?. *The quarterly journal of economics*, 114(1), 83-116.

- Huntington, S. P. (1968). Political Order in Changing Societies/Yale Univ. Eriřim Linki: chrome-extension://efaidnbmnnnibpcajpcglclefindmkaj/https://pdfs.semanticscholar.org/bf7d/7528a7d3614f3550ec9ef1b869f7f7d731a1.pdf
- Glaeser, E. L., La Porta, R., Lopez-de-Silanes, F., & Shleifer, A. (2004). Do institutions cause growth?. *Journal of economic Growth*, 9(3), 271-303.
- Kaufmann, D., Aart K. and Massimo M. (2010). The Worldwide Governance Indicators: Methodology and Analytical Issues. *World Bank Policy Research Working Paper*, No. 5430 (http://papers.ssrn.com/sol3/papers.cfm?abstract_id=1682130).
- Knack, S., & Keefer, P. (1995). Institutions and economic performance: cross-country tests using alternative institutional measures. *Economics & politics*, 7(3), 207-227.
- Leff, N. H. (1964). Economic development through bureaucratic corruption. *American behavioral scientist*, 8(3), 8-14.
- Mauro, P. (1995). Corruption and growth. *The Quarterly Journal of Economics*, 110 (3), 681-712.
- North, D. C. (1990). *Institutions, institutional change and economic performance*. Cambridge university press.
- Rodrik, D., Subramanian, A., & Trebbi, F. (2004). Institutions rule: the primacy of institutions over geography and integration in economic development. *Journal of economic growth*, 9(2), 131-165.
- Romer, P. M. (1994). The origins of endogenous growth. *Journal of Economic perspectives*, 8(1), 3-22.
- Solow, R. M. (1956). A contribution to the theory of economic growth. *The quarterly journal of economics*, 70(1), 65-94.
- Tutgun, S., & Savař, Y. (2023). Kurumsal kalite ve finansal gelişmenin ekonomik büyüme üzerindeki etkisi: Sahra altı Afrika ülkeleri örneęi. *Çankırı Karatekin Üniversitesi İktisadi ve İdari Bilimler Fakültesi Dergisi*, 13(3), 879-904.

İÇ MEKÂNDA YENİ NESİL MALZEMELERİN KULLANIMI VE ÖRNEK UYGULAMALAR

Eda GÖRGÜN

Yüksek Lisans Öğrencisi, Kütahya Dumlupınar Üniversitesi, Lisansüstü Eğitim Enstitüsü,
Teknoloji ve İnovasyon Yönetimi Anabilim Dalı,
ORCID: 0009-0005-8411-0956

Prof. Dr. Arif GÖK

Kütahya Dumlupınar Üniversitesi, Mimarlık Fakültesi, Endüstriyel Tasarım Bölümü,
ORCID: 0000-0003-2840-9601

ÖZET

İç mekân tasarımında kullanılan malzemeler, mekânların işlevsel, estetik ve algısal niteliğini belirleyen temel unsurlardandır. Teknolojinin gelişmesiyle birlikte çağımızda geleneksel yapı malzemeleri yerini çevresel uyaranlara tepki verebilen, performans özellikleri geliştirilmiş, yeni nesil malzemelere bırakmıştır. Bu yenilikçi malzemeler, iç mekân tasarımlarında kullanıcı konforu, enerji verimliliği ve çevresel etki gibi güncel tasarım kriterlerinin yeniden değerlendirilmesini gerekli hale getirmiştir. Bu bağlamda malzeme seçimi yalnızca estetik bir karar olmaktan çıkarak mekânın sürdürülebilirliği ve kullanıcı deneyimi üzerinde belirli rol oynamaktadır.

Yeni nesil malzemeler; sıcaklık, ışık, basınç ve nem gibi çevresel faktörlere duyarlı, dayanıklı yapıları sayesinde hem işlevsel hem de estetik açıdan yenilikçi çözümler sunmaktadır. Özellikle yenilikçi ve sürdürülebilir özelliklere sahip olan bu malzeme çeşitleri, iç mekân unsurlarında esnek kullanım olanakları sağlayarak mekânsal algıyı güçlendirmektedir. Akıllı tekstiller; ışık kontrolü, akustik düzenleme ve enerji tasarrufu gibi katkılarıyla iç mekân tasarımlarında öne çıkan yeni nesil malzeme gruplarından biri olarak değerlendirilmektedir.

Bu çalışma ile iç mekân tasarımlarında yeni nesil malzemelerin kullanım biçimlerini incelemeyi ve bu malzemelerin mekânlara sağladığı işlevsel ve estetik katkıları ortaya koymak amaçlanmıştır. Yeni nesil ve akıllı malzemelerin tanımları, sınıflandırmaları ve iç mekânlarda kullanım alanları ele alınmıştır. Seçili uygulama örnekleri üzerinden bu malzemelerin sürdürülebilirlik, ergonomi, mekânsal algı üzerindeki etkileri değerlendirilmiştir. Sonuç olarak tasarım sürecine rehberlik edecek şekilde iç mekânda yeni nesil malzemelerin bilinçli kullanımına yönelik bir çerçeve sunulmuştur.

Anahtar Kelimeler: İç Mekân Tasarımı, Yeni Nesil Malzemeler, Akıllı Malzemeler, Sürdürülebilirlik,

**THE USE OF NEXT GENERATION MATERIALS IN INTERIOR SPACES AND
SAMPLE APPLICATIONS**

ABSTRACT

Materials used in interior design are among the fundamental elements that determine the functional, aesthetic, and perceptual qualities of spaces. With the advancement of technology, traditional building materials have increasingly been replaced by next-generation materials that

can respond to environmental stimuli and exhibit enhanced performance characteristics. This transformation has made it necessary to reconsider material selection in interior design in relation to contemporary design criteria such as user comfort, energy efficiency, and environmental impact. In this context, material selection has evolved beyond an aesthetic decision and has become a significant factor influencing spatial sustainability and user experience.

Next-generation materials offer innovative solutions in interior spaces through their durable structures and their sensitivity to environmental factors such as temperature, light, pressure, and humidity. Materials with innovative and sustainable properties enable flexible use in interior components and contribute to the enhancement of spatial perception. Among these materials, smart textiles stand out as one of the prominent groups of next-generation materials in interior design due to their contributions to light control, acoustic regulation, and energy efficiency.

The aim of this study is to examine the usage forms of next-generation materials in interior design and to reveal their functional and aesthetic contributions to interior spaces. Within the scope of the research, a literature review method was employed, and the definitions, classifications, and areas of use of next-generation and smart materials in interior spaces were discussed. Selected application examples were evaluated in terms of their effects on sustainability, ergonomics, and spatial perception. As a result, a framework is presented to guide the conscious use of next-generation materials in the interior design process.

Keywords: Interior Design, Next-Generation Materials, Smart Materials, Sustainability

1.GİRİŞ

İç mekân tasarımında malzeme, mekânın işlevselliğini, estetiğini ve kullanıcı üzerindeki algısal etkilerini belirleyen temel tasarım bileşenlerinden biridir. Malzeme seçimi; mekânın kimliğini oluştururken konfor koşulları, dayanıklılık, bakım gereksinimleri ve kullanıcı deneyimi gibi birçok kriteri doğrudan etkilemektedir. Bu nedenle İç mekân tasarımında malzeme, yalnızca bir kaplama unsuru olarak değil, mekânın bütüncül tasarım kararlarını yönlendiren stratejik bir araç olarak ele alınmaktadır (Ashby & Johnson, 2014).

Günümüzde teknolojik gelişmelerin ivme kazanmasıyla birlikte, geleneksel malzemelerin yerini çevresel koşullara uyum sağlayabilen, performans özellikleri geliştirilmiş yeni nesil malzemeler almaya başlamıştır. Bu malzemeler; sıcaklık, ışık, basınç ve nem gibi çevresel uyaranlara duyarlı yapıları sayesinde mekânın değişen koşullara uyum sağlamasına olanak tanımaktadır. Böylece iç mekân tasarımında statik çözümler yerine, dinamik ve kullanıcı odaklı yaklaşımlar ön plana çıkmaktadır (Addington & Schodek, 2005).

Yeni nesil malzemelerin iç mekân tasarımında kullanılmaya başlanması, ergonomi, enerji verimliliği ve sürdürülebilirlik gibi çağdaş tasarım kriterlerinin yeniden değerlendirilmesini gerekli kılmıştır. Malzeme seçiminde; enerji tüketiminin azaltılması, iç hava kalitesinin iyileştirilmesi ve çevresel etkilerin minimize edilmesi gibi hedefler belirleyici faktörler haline gelmiştir. Bu bağlamda malzeme, yalnızca estetik bir tercih olmaktan çıkarak, mekânın çevresel performansını ve uzun vadeli sürdürülebilirliğini doğrudan etkileyen bir unsur olarak değerlendirilmektedir (Knaack et al., 2018).

Özellikle akıllı malzeme ve akıllı tekstiller, İç mekân tasarımlarında çok yönlü kullanım olanakları sağladığı için ilgi çekmektedir. Işık kontrolü, akustik düzenleme, ısı yalıtımı ve enerji tasarrufu gibi özelliklere sahiptirler. Bu sebeple İç mekânlarda esnek ve yenilikçi çözümler sunmaktadırlar. Aynı zamanda bu malzemeler, mekânsal algıyı güçlendirerek kullanıcı ile mekân arasındaki etkileşimi artırmaktadır.

Bu bağlamda, iç mekân tasarımında malzeme seçimi yalnızca estetik bir tercih olmaktan çıkmakta; mekânın enerji kullanımı, konfor koşulları ve çevresel etkileriyle bütüncül bir ilişki kurmaktadır. Bu çalışma, iç mekân tasarımında yeni nesil malzemelerin kullanımını ele alarak, bu malzemelerin tasarım sürecine sağladığı katkıları literatür ve uygulama örnekleri üzerinden değerlendirmeyi amaçlamaktadır.

2.ARAŞTIRMA VE BULGULAR

2.1. İç Mekân Tasarımında Malzeme Kavramı

İç mekân tasarımında malzeme kavramı, mimarlık ve tasarım disiplinlerinde farklı kuramsal yaklaşımlar üzerinden ele alınmıştır. Literatürde malzeme; yapısal gereklilikleri karşılayan bir bileşen olmasının yanı sıra, mekânsal anlam üretimi ve tasarım dili oluşturma süreçlerinin temel girdilerinden biri olarak tanımlanmaktadır. Bu bağlamda malzeme, yalnızca fiziksel özellikleriyle değil, taşıdığı sembolik, kültürel ve duysal anlamlarla birlikte değerlendirilmektedir (Addington & Schodek, 2005).

Kuramsal çalışmalarda iç mekân malzemeleri genellikle üç ana boyut üzerinden incelenmektedir: teknik özellikler, algısal etkiler ve bağlamsal ilişkiler. Teknik boyut; dayanıklılık, bakım gereksinimleri ve performans kriterlerini kapsarken, algısal boyut malzemenin doku, renk ve yüzey karakteri üzerinden mekân deneyimine olan etkisini ele almaktadır. Bağlamsal boyut ise malzemenin mekânın işlevi, kullanıcı profili ve kullanım senaryoları ile kurduğu ilişkiyi kapsamaktadır. Bu çok boyutlu yaklaşım, malzeme seçimlerinin yalnızca teknik zorunluluklar doğrultusunda değil, tasarım bütünlüğü çerçevesinde ele alınması gerektiğini ortaya koymaktadır.

İç mekân tasarım literatüründe malzeme, uzun yıllar boyunca çoğunlukla sabit özelliklere sahip bir tasarım girdisi olarak değerlendirilmiştir. Bu yaklaşımda malzemeler, önceden tanımlanmış fiziksel nitelikleriyle mekâna dâhil edilmekte ve tasarım süreci boyunca değişmez kabul edilmektedir. Ancak özellikle 20. yüzyılın sonlarından itibaren, teknolojik gelişmelerin tasarım süreçlerine etkisiyle birlikte bu anlayış sorgulanmaya başlanmıştır (Addington & Schodek, 2005).

Güncel çalışmalarda malzeme kavramı, tasarım sürecinin pasif bir bileşeni olmaktan çıkarak, mekânsal organizasyonu ve kullanıcı deneyimini yönlendiren aktif bir unsur olarak ele alınmaktadır. Bu yaklaşım, malzemenin tasarım sürecinde erken aşamalarda değerlendirilmesini ve mekânsal kararlarla eş zamanlı olarak ele alınmasını gerekli kılmaktadır. Böylece malzeme, iç mekân tasarımında biçim, işlev ve kullanım senaryoları arasında bir arayüz işlevi üstlenmektedir.

Bu kuramsal çerçeve, iç mekân tasarımında malzeme kavramının statik bir tanımın ötesine geçtiğini ve yeni teknolojilerle birlikte yeniden ele alınması gerektiğini göstermektedir. Bir sonraki bölümde ele alınacak olan yeni nesil malzemeler, bu dönüşümün somut bir sonucu olarak değerlendirilmekte ve malzemenin iç mekân tasarımındaki rolünü yeniden tanımlayan güncel yaklaşımlar arasında yer almaktadır.

2.2. İç Mekân Tasarımında Yeni Nesil Malzemeler

Yeni nesil malzemeler, iç mekân tasarımında geleneksel malzeme gruplarından farklı olarak, yalnızca taşıyıcılık veya yüzey kaplama işleviyle değil; çevresel performans, sürdürülebilirlik

ve kullanım sürecindeki davranışlarıyla değerlendirilmektedir. Güncel literatürde bu malzemeler; geliştirilen üretim teknikleri, malzeme bileşenleri ve performans odaklı özellikleri doğrultusunda farklı alt gruplar altında incelenmektedir (Yatağan, 2024).

Bu bağlamda iç mekân ölçeğinde yeni nesil malzemeler; **akıllı tekstiller**, **nanoteknoloji tabanlı yüzeyler** ve **biyobazlı / deneysel malzemeler** olmak üzere üç ana grupta ele alınmaktadır. Bu sınıflandırma, malzemenin yalnızca teknik özelliklerine değil, iç mekân bileşeni olarak üstlendiği role göre yapılmaktadır (Acer, 2024).

2.2.1. Akıllı Tekstil Malzemeleri

Akıllı tekstil malzemeleri, iç mekân tasarımında çevresel koşullara tepki verebilen yapıları sayesinde işlevsel çözümler sunan yeni nesil malzeme grupları arasında yer almaktadır. Literatürde bu malzemeler; ısıya duyarlı, ışığa duyarlı ve akustik performans sağlayan tekstiller olarak sınıflandırılmaktadır (Acer, 2024). Bu özellikleri sayesinde akıllı tekstiller, perde sistemleri, mekân ayırıcılar, duvar kaplamaları ve akustik paneller gibi iç mekân elemanlarında kullanılabilmektedir.

Araştırmalar, akıllı tekstillerin iç mekânlarda özellikle enerji verimliliği ve kullanıcı konforu açısından avantaj sağladığını ortaya koymaktadır. Faz değiştiren bileşenler içeren tekstil yüzeyler, ortam sıcaklığını dengeleyerek ısıtma ve soğutma yükünü azaltabilmektedir. Ayrıca ses emici tekstil sistemleri, mekân akustikini iyileştirerek konut ve ofis iç mekânlarında daha konforlu kullanım koşulları oluşturmaktadır (Acer, 2024).

2.2.2. Nanoteknoloji Tabanlı Malzemeler

Nanoteknoloji tabanlı malzemeler, iç mekân tasarımında yüzey performansını artırmaya yönelik yenilikçi çözümler sunmaktadır. Nano ölçekte geliştirilen kaplama ve bileşenler sayesinde bu malzemeler; antibakteriyel özellikler gösterebilmekte, kendi kendini temizleyebilen yüzeyler oluşturabilmekte ve aşınmaya karşı yüksek direnç sağlayabilmektedir. Bu özellikler, özellikle yoğun kullanıma sahip iç mekânlarda hijyenin korunması ve bakım süreçlerinin kolaylaştırılması açısından önemli avantajlar sunmaktadır (Akbari Haghighat, 2015).

Nanomalzemelerin iç mekânlarda kullanımı; sağlık yapıları, mutfaklar ve kamusal alanlar gibi hijyenin ön planda olduğu mekânlarda giderek yaygınlaşmaktadır. Literatürde, nanoteknoloji tabanlı yüzeylerin temizlik sıklığını azaltarak uzun vadede su ve kimyasal kullanımını düşürdüğü; bu durumun ise çevresel etkiyi azalttığı belirtilmektedir (Akbari Haghighat, 2015). Bu yönüyle nanoteknoloji tabanlı malzemeler, sürdürülebilir iç mekân tasarımı açısından işlevsel ve çağdaş bir çözüm olarak değerlendirilmektedir.

2.2.3. Biyobazlı ve Miselyum Tabanlı Malzemeler

Biyobazlı ve miselyum temelli malzemeler, iç mekân tasarımında çevresel sürdürülebilirliği merkeze alan deneysel malzeme grupları arasında yer almaktadır. Bu malzemeler, tarımsal atıklar veya mantar kökleri gibi doğal bileşenlerden üretilmekte ve biyolojik olarak parçalanabilir özellik göstermektedir (Özkan, 2025).

Miselyum bazlı malzemeler; hafiflik, ısı ve ses yalıtımı sağlama kapasitesi ve düşük karbon ayak izi gibi özellikleri sayesinde iç mekân elemanlarında alternatif çözümler sunmaktadır. Literatürde bu malzemelerin sergi tasarımları, geçici mekânlar ve mobilya elemanlarında kullanıldığı örnekler yer almaktadır (Özkan, 2025). Bu kullanım biçimleri, malzemenin yalnızca ürün ölçeğinde değil, mekânsal organizasyonun bir parçası olarak da değerlendirilebileceğini göstermektedir.

Biyobazlı malzemelerin iç mekân tasarımındaki kullanımı, tasarım sürecinde malzeme yaşam döngüsünün dikkate alınmasını gerekli kılmaktadır. Üretim, kullanım ve kullanım sonrası süreçleri kapsayan bu yaklaşım, yeni nesil malzemelerin çevresel sorumluluk temelinde ele alınmasını desteklemektedir (Özkan, 2025).

2.3. İç mekân Tasarımında Yeni Nesil Malzemelere Yönelik Örnek Uygulamalar

Yeni nesil malzemelerin iç mekân tasarımında kullanımı, teorik tanımların ötesinde, belirli mekân türleri ve kullanım senaryoları üzerinden değerlendirildiğinde daha somut biçimde anlaşılabilmektedir. Literatürde bu malzemelerin uygulama örnekleri; konut, kamusal alanlar ve geçici mekânlar olmak üzere farklı iç mekân tipleri üzerinden ele alınmaktadır. Bu çeşitlilik, yeni nesil malzemelerin yalnızca belirli yapı türlerine özgü olmadığını, farklı ölçek ve işlevlerde uygulanabilir çözümler sunduğunu göstermektedir (Acer, 2024).

2.3.1 Konut İç mekânlarında Kullanım Örnekleri

Konut iç mekânlarında yeni nesil malzemeler, kullanıcı konforunu artırmaya yönelik çözümler sunmaktadır. Özellikle akıllı tekstil yüzeyler, perde ve döşeme elemanlarında kullanılarak ışık kontrolü ve ısı konforu düzenlenmesine katkı sağlamaktadır. Faz değiştiren bileşenler içeren tekstil sistemlerinin, iç mekân sıcaklığını dengeleyerek enerji tüketimini azalttığı literatürde belirtilmektedir (Acer, 2024).

Nanoteknoloji tabanlı yüzey kaplamaları ise mutfak ve banyo gibi hijyenin ön planda olduğu konut mekânlarında yaygın olarak kullanılmaktadır. Bu yüzeylerin antibakteriyel özellikleri sayesinde temizlik sıklığının azaldığı ve bakım maliyetlerinin düştüğü vurgulanmaktadır (Akbari Haghighat, 2015). Bu uygulamalar, yeni nesil malzemelerin konut ölçeğinde hem sağlık hem de sürdürülebilirlik açısından katkı sağladığını ortaya koymaktadır.

2.3.2. Kamusal İç mekânlarda Kullanım Örnekleri

Kamusal iç mekânlar, yeni nesil malzemelerin performans özelliklerinin daha belirgin biçimde gözlemlenebildiği alanlar arasında yer almaktadır. Ofisler, eğitim yapıları ve sağlık tesisleri gibi yoğun kullanıma sahip mekânlarda akıllı tekstiller, akustik düzenleme amacıyla duvar ve tavan yüzeylerinde tercih edilmektedir. Bu uygulamaların, mekânsal konforu artırarak kullanıcı verimliliğine olumlu katkı sağladığı ifade edilmektedir (Akbari Haghighat, 2015).

Nanomalzeme ise kamusal alanlarda yüzey dayanıklılığı ve hijyen gereksinimlerine cevap vermektedir. Özellikle zemin ve duvar kaplamalarında kullanılan nano kaplamaların, aşınma direncini artırdığı ve uzun süreli kullanım avantajı sunduğu literatürde yer almaktadır (Akbari Haghighat, 2015). Bu yönüyle nanoteknoloji tabanlı malzemeler, kamusal iç mekânlarda sürdürülebilir kullanım açısından önemli bir alternatif oluşturmaktadır.

2.3.3. Geçici Mekânlar ve Deneysel Uygulamalar

Yeni nesil malzemelerin en dikkat çekici kullanım alanlarından biri, sergi mekânları ve geçici iç mekânlardır. Biyobazlı ve miselyum temelli malzemeler, bu tür mekânlarda hafiflik, modülerlik ve çevresel sürdürülebilirlik gibi özellikleri nedeniyle tercih edilmektedir. Literatürde miselyum bazlı panellerin sergi elemanları ve mekân ayırıcı sistemler olarak kullanıldığı örnekler yer almaktadır (Özkan, 2025).

Bu uygulamalar, yeni nesil malzemelerin yalnızca kalıcı yapılar için değil, geçici ve deneysel mekân kurguları için de uygun olduğunu göstermektedir. Ayrıca kullanım sonrası doğaya geri kazandırılabilen bu malzemeler, iç mekân tasarımında döngüsel tasarım yaklaşımlarını desteklemektedir.

2.3.4. Uygulama Örneklerinin Değerlendirilmesi

Literatürde yer alan uygulama örnekleri, yeni nesil malzemelerin iç mekân tasarımında çok yönlü katkılar sunduğunu ortaya koymaktadır. Bu katkılar; kullanıcı konforunun artırılması, bakım ve işletme maliyetlerinin azaltılması, enerji verimliliğinin sağlanması ve çevresel etkinin düşürülmesi şeklinde özetlenebilir. Uygulama örnekleri, malzeme seçimlerinin tasarım sürecinin erken aşamalarında ele alınmasının önemini vurgulamaktadır.

Bu bağlamda yeni nesil malzemelerin iç mekân tasarımında kullanımı, yalnızca teknik bir tercih değil; tasarımın çevresel, işlevsel ve deneyimsel boyutlarını birlikte ele alan bütüncül bir yaklaşımın parçası olarak değerlendirilmektedir.

3. TARTIŞMA VE DEĞERLENDİRME

Bu çalışma kapsamında incelenen yeni nesil malzemeler ve uygulama örnekleri, iç mekân tasarımında malzeme seçiminin yalnızca estetik veya teknik bir karar olmadığını; mekânın performansı, sürdürülebilirliği ve kullanıcı deneyimiyle doğrudan ilişkili çok boyutlu bir süreç olduğunu göstermektedir. Literatürde akıllı tekstiller, nanoteknoloji tabanlı yüzeyler ve biyobazlı malzemeler üzerine yapılan çalışmalar, bu malzeme gruplarının farklı mekân tiplerinde benzer hedeflere hizmet ettiğini ancak farklı tasarım öncelikleri doğrultusunda kullanıldığını ortaya koymaktadır (Acer, 2024; Özkan 2025; Akbari Haghighat, 2015).

Akıllı tekstil malzemelerine yönelik bulgular, bu malzemelerin özellikle iç mekân konforu ve enerji verimliliği açısından öne çıktığını göstermektedir. Faz değiştiren bileşenler ve akustik performans sağlayan tekstil sistemleri, konut ve ofis iç mekânlarında ısı ve işitsel konforun iyileştirilmesine katkı sunmaktadır. Bu durum, akıllı tekstillerin yalnızca tamamlayıcı bir iç mekân elemanı değil, mekân performansını doğrudan etkileyen aktif bir tasarım girdisi olarak ele alınması gerektiğini ortaya koymaktadır (Acer, 2024).

Nanoteknoloji tabanlı malzemelerin değerlendirildiği çalışmalarda ise hijyen, dayanıklılık ve bakım kolaylığı gibi kriterlerin ön plana çıktığı görülmektedir. Özellikle yoğun kullanıma sahip kamusal iç mekânlarda, nano kaplamalar sayesinde yüzey performansının arttığı ve uzun vadede bakım maliyetlerinin azaldığı vurgulanmaktadır. Bu bulgular, nanomalzemelerin sürdürülebilirlik bağlamında yalnızca enerji verimliliği üzerinden değil, malzemenin kullanım ömrü boyunca sağladığı çevresel ve ekonomik katkılar üzerinden de değerlendirilmesi gerektiğini göstermektedir (Akbari Haghighat, 2015).

Biyobazlı ve miselyum temelli malzemeler ise iç mekân tasarımında daha çok deneysel ve yenilikçi uygulamalarla ilişkilendirilmektedir. Literatürde bu malzemelerin geçici mekânlar, sergi alanları ve modüler iç mekân kurgularında kullanıldığı örnekler yer almaktadır. Bu uygulamalar, yeni nesil malzemelerin yalnızca kalıcı yapı elemanları için değil, geçici ve dönüşebilir mekânsal senaryolar için de uygun olduğunu göstermektedir (Jones et al., 2020). Aynı zamanda bu malzemeler, iç mekân tasarımında döngüsel tasarım ve çevresel sorumluluk kavramlarının somutlaşmasına katkı sağlamaktadır (Özkan,2025).

Uygulama örneklerinin genel değerlendirmesi, yeni nesil malzemelerin iç mekân tasarımında farklı ölçek ve işlevlerde esnek çözümler sunduğunu ortaya koymaktadır. Ancak literatürde, bu malzemelerin yaygın kullanımının önünde maliyet, üretim ölçeği ve teknik bilgi gereksinimi gibi sınırlılıkların bulunduğu da vurgulanmaktadır. Bu durum, yeni nesil malzemelerin tasarım sürecine entegre edilmesinde disiplinler arası iş birliğinin ve tasarımcıların malzeme bilgisine hâkimiyetinin önemini ortaya koymaktadır.

4. SONUÇ

Bu çalışmada, iç mekân tasarımında kullanılan yeni nesil malzemeler; akıllı tekstiller, nanoteknoloji tabanlı yüzeyler ve biyobazlı malzemeler kapsamında ele alınmış ve bu malzemelerin farklı iç mekân tiplerindeki kullanım biçimleri literatür üzerinden değerlendirilmiştir. İncelenen çalışmalar, yeni nesil malzemelerin iç mekân tasarımında yalnızca estetik çeşitlilik sağlamadığını; aynı zamanda kullanıcı konforu, enerji verimliliği, hijyen ve sürdürülebilirlik gibi güncel tasarım kriterlerine doğrudan katkı sunduğunu ortaya koymaktadır.

Akıllı tekstil malzemelerinin özellikle ısı ve akustik konforun iyileştirilmesine yönelik çözümler sunduğu; nanoteknoloji tabanlı malzemelerin ise hijyen, dayanıklılık ve bakım kolaylığı açısından iç mekân performansını artırdığı görülmektedir. Biyobazlı ve miselyum temelli malzemeler ise çevresel sürdürülebilirlik odağında, geçici ve deneysel iç mekân uygulamalarında yenilikçi alternatifler sunmaktadır. Bu çeşitlilik, yeni nesil malzemelerin tek tip bir kullanım alanına sahip olmadığını; farklı mekân türleri ve tasarım senaryoları için uyarlanabilir çözümler sunduğunu göstermektedir.

Literatür incelemesi sonucunda elde edilen bulgular, yeni nesil malzemelerin iç mekân tasarımında bilinçli ve amaç odaklı kullanıldığında tasarım sürecine önemli katkılar sağladığını ortaya koymaktadır. Bununla birlikte, bu malzemelerin yaygın kullanımının önünde maliyet, üretim ölçeği ve teknik bilgi gereksinimi gibi sınırlılıkların bulunduğu da görülmektedir. Bu durum, tasarımcıların malzeme bilgisine hâkimiyetinin ve disiplinler arası iş birliğinin önemini artırmaktadır.

Sonuç olarak, iç mekân tasarımında yeni nesil malzemelerin kullanımı, mekânsal kaliteyi artıran ve çağdaş tasarım yaklaşımlarını destekleyen önemli bir tasarım girdisi olarak değerlendirilmektedir. Bu çalışmanın, yeni nesil malzemelerin iç mekân tasarımındaki potansiyeline ilişkin bir çerçeve sunarak tasarım sürecinde malzeme seçimlerine rehberlik etmesi ve ileride yapılacak akademik çalışmalara zemin oluşturması hedeflenmektedir.

KAYNAKÇA

1. Addington, M., & Schodek, D. (2005). *Smart materials and technologies for the architecture and design professions*. Architectural Press.

2. Acer, A. H. (2024). *İç mekân tasarımında akıllı tekstil malzemeleri ve sürdürülebilirlik ilişkisi* (Yüksek lisans tezi). Başkent Üniversitesi, Sosyal Bilimler Enstitüsü.
3. Akbari Haghighat, A. (2015). *Emergence of nanomaterials in architecture and interior architecture and their use in patient rooms in healthcare domain* (Master's thesis). Istanbul Technical University, Graduate School of Arts and Social Sciences.
4. Ashby, M. F., & Johnson, K. (2014). *Materials and design: The art and science of material selection in product design* (3rd ed.). Butterworth-Heinemann.
5. Özkan, M. (2025). *Miselyum tabanlı malzemenin dijital üretim yaklaşımıyla iç mekân tasarım bileşeni olarak kullanılması* (Yüksek lisans tezi). İstanbul Teknik Üniversitesi, Lisansüstü Eğitim Enstitüsü.
6. Yatağan, M. S. (2024). Mimarlık projelerinde akıllı malzeme ve kullanım detayları. *FBU-DAE*, 4(1), 57–77.
7. Jones, M., Huynh, T., Dekiwadia, C., Daver, F., & John, S. (2020). Mycelium composites: A review of engineering characteristics and growth kinetics. *Journal of Bionic Engineering*, 17(4), 840–856.

CEVİZ KABUKLARININ YAPI MALZEMESİ ÜRETİMİNDE KULLANIMI: KISA BİR İNCELEME

THE USE OF WALNUT SHELLS IN THE PRODUCTION OF BUILDING MATERIALS: A BRIEF REVIEWS

Erdal AKTAŞ

AKTAŞ Harita ve Mühendislik A.Ş., Merkez, Kırıkkale

Dr. Öğretim Üyesi Hakan ÇAĞLAR

Kırşehir Ahi Evran Üniversitesi, Mühendislik Mimarlık Fakültesi, İnşaat Mühendisliği Bölümü, Merkez, Kırşehir

Doç. Dr. Arzu ÇAĞLAR

Kırşehir Ahi Evran Üniversitesi, Mühendislik Mimarlık Fakültesi, Mimarlık Bölümü, Merkez, Kırşehir

ÖZET

Yapı malzemesi, yapı inşasında kullanılan tüm materyallerdir. Bu yüzden yapı malzemelerinin geliştirilmesi ve iyileştirilmesi kaliteli yapı üretiminde oldukça önemlidir. Yapı malzemelerinin iyileştirilmesi çeşitli malzemelerle yapılmaktadır. Bu iyileştirmede atık kullanımı ön plana çıkmıştır. Endüstriyel atıklar, inşaat ve yıkıntı atıkları, plastik ve polimer atıkları bunlarda birkaçıdır. Son zamanlarda, yapı malzemesi iyileştirilmesinde tarımsal ve biyokütle atıkların kullanımı ivme kazanmıştır. İvme kazanan tarımsal ve biyokütle atıklarından biri de ceviz kabuğudur. Bu çalışmada, tarımsal atıklardan olan ceviz kabuğunun yapı malzemesi üretiminde kullanımı araştırılması amaçlanmıştır. Araştırma, literatürde yer alan akademik çalışmaları kapsamaktadır. Çalışmada, ceviz kabuklarının beton, tuğla vb. yapı malzemelerinin teknik özellikleri üzerine yapılan çalışmalar detaylı bir şekilde irdelenmiştir. Çalışma sonucunda; ceviz kabuklarının öğütülerek agrega yerine betona ikame edildiği görülmüştür. Böylece hafif beton üretimi yapılmıştır. Ceviz kabuğu ikamesinin yapı malzemelerinin porozite ve su emme değerlerini artırdığını, birim hacim ağırlık değerlerini düşürdüğü anlaşılmıştır. Beton, tuğla gibi ana yapı malzemelerinin termal özelliklerini ve ses yalıtım özelliğini iyileştirdiği tespit edilmiştir. Ceviz kabukları tarımsal yan ürün olduğu için maliyetinin düşük ve çevreye etkisinin az olduğu anlaşılmıştır. Ceviz kabuklarının yapı malzemesi üretiminde kullanımının geri dönüşüm ve çevre sağlığı açısından önemli olduğu görülmüştür. Optimum oranda kullanıldığı takdirde, yapı malzemesi iyileştirilmesinde rahatlıkla kullanılabileceği sonucuna varılmıştır.

Anahtar Kelimeler: Ceviz kabuğu, yapı malzemesi, geri dönüşüm, sürdürülebilirlik.

ABSTRACT

Building materials are all materials used in building construction. Therefore, the development and improvement of building materials are crucial for high-quality building production. The improvement of building materials is carried out using various materials. Waste utilization has come to the forefront in this improvement. Industrial waste, construction and demolition waste, plastic and polymer waste are a few examples. Recently, the use of agricultural and biomass waste in building material improvement has gained momentum. One of these agricultural and biomass wastes is walnut shells. This study aims to investigate the use of walnut shells, an agricultural waste, in building material production. The research encompasses academic studies in the literature. The study examines in detail the studies on the technical properties of building materials such as concrete and bricks using walnut shells. The study concludes that walnut shells, when ground, can be used as aggregate in concrete. Thus, lightweight concrete is

produced. It has been found that walnut shell substitution increases the porosity and water absorption values of building materials and reduces their unit weight. It has been determined that walnut shells improve the thermal and sound insulation properties of main building materials such as concrete and brick. Since walnut shells are an agricultural byproduct, it has been found to be inexpensive and have minimal environmental impact. The use of walnut shells in building material production has been found to be important in terms of recycling and environmental health. It has been concluded that, if used in optimum proportions, they can be easily used in improving building materials.

Keywords: Walnut shell, building material, recycling, sustainability.

GİRİŞ

With population growth and rapid technological advancements, a rapid increase in industrial activity has been observed. The waste generated as a result of these activities has become a major problem for living organisms and the environment. This situation has made it imperative to combat environmental pollution more effectively (Kaya et al., 2011). One type of waste generated is agricultural waste. Agricultural waste, which has uses in many fields, is one of the wastes that has significant value in the production of environmentally friendly materials that can be used in the construction sector (Abdulwahid et al., 2024).

One of the agricultural wastes used in the construction sector is walnut shells (Ren et al., (2025). Walnut shell (WS) is a byproduct of walnut production and is generally considered waste by farmers (Çavuşoğlu et al., 2023). Walnut shells have become a popular choice in the production of building materials due to their cost-effectiveness and environmentally friendly nature. In the construction sector, it has become a viable option to achieve sustainability (Jannat et al., (2022). Replacing the mineral components of concrete with walnut shells not only makes the concrete production process more environmentally friendly and cheaper, but also solves a significant problem related to waste disposal for the agricultural industry (Beskopylny et al., 2023). Concrete production consumes large quantities of fine and coarse aggregate. Therefore, eliminating or reducing aggregate consumption in concrete can enable the production of environmentally friendly building materials (Hilal et al., 2020).

The development of fired bricks with agricultural waste additives is an important step towards obtaining lightweight, eco-efficient bricks with improved thermal insulation properties. This ensures safe waste disposal and cost effectiveness. It is also a giant step towards environmental sustainability (Barnabas et al., (2023).

The use of walnut shells in the development of geopolymers can lead to the creation of a new type of material, a reduction in energy consumption, waste generation, global CO2 emissions and natural resource extraction (Kozub and Castro-Gomes, (2022). In recent years, although it is considered an agricultural waste, it has been suggested that walnut shells be utilized through innovative applications such as the development of polymers with added walnut shells (Akhlaghi et al., 2021; Hashemi et al., 2016). Walnut shells contain tannins (10-15%), a naturally occurring phenolic compound. This compound is added to polymer materials to increase strength and provide resistance to UV radiation (Pasbakhsh et al., 2017).

This study aims to investigate the use of walnut shells, an agricultural waste, in the production of building materials.

WALNUTS AND WALNUT SHELLS

The walnut tree is a species of tree in the genus *Juglans*, also known as the nut family. The walnut tree and its fruit shown in Figure 1 grow in temperate and subtropical climate zones (Çakır and Karagöz, 2021). Walnut trees can reach an average height of 25-30 meters and have a lifespan of approximately 50-75 years (Çakır and Karagöz, 2021; *Juglans*, 2022). Walnuts are

2.5 million tons. China accounted for 56.1% of total world walnut production in 2019. In walnut production, the US comes second after China, with a production of approximately 592,000 tons. Türkiye ranks fourth with a 5.0% share and 225,000 tons. China accounts for 48.4% of walnut production areas, the USA for 11.3%, and Türkiye for 9.5% (Agricultural Products Markets, 2021).




Figure 3. Major walnut-producing countries (%)

Figure 4 shows a map of the provinces in Turkey where walnuts are produced. In Turkey, 287,000 tons of walnuts were produced in 2020. Bursa ranks first with 19.3 thousand tons. Mersin with 16.5 thousand tons and Kahramanmaraş with 13 thousand tons are followed to Bursa. In Turkey, walnut production increased by 27.4% in 2020 compared to the previous year. Walnut yield per kg/tree increased by 14.2% in 2020 compared to 2019 (Agricultural Products Markets, 2021).




Figure 4. Map of walnut-producing provinces in Turkey (Web message 1)

According to Turkish Statistical Institute (TÜİK) data for 2017, 260,000 tons of walnuts were produced in our country. Approximately 135,000 tons of waste walnut shells were generated from this walnut production (Sönmez et al., 2018).

Walnut shells consist of two parts in terms of structure. It consists of a hard, woody outer shell and an inner membrane that acts as a barrier. Walnut shells are sensitive to moisture and water. According to the Mohs hardness scale, the hardness value ranges from 2.5 to 3.5. They belong to the class of trees whose shells can be scored with a needle or a penknife. Lignin, which forms the woody structure of walnut shells and provides them with strength, constitutes 50.3% of the chemical composition. Cellulose constitutes the second largest material group after lignin, at 23.9%. In addition to cellulose and lignin, the structure contains 22.4% hemicellulose and 3.4% other components (Adibelli, 2022). Thousands of tons of walnut shells harvested each year are consumed as fuel. Walnut shells have no economic value. Due to its cellulosic nature, hard structure, and abundance in our country, walnut shells can be used as fillers in thermoset and thermoplastic matrix polymer composites. It is used in production to composite materials due to reasons such as low environmental impact, recyclability, and ease of processing (Adibelli et al., 2022).

Due to the lower amounts of hygroscopic components compared to wood and the higher amounts of hydrophobic components in walnut shells, polymer-based composite materials containing walnut shell filler have significant commercial advantages in outdoor products requiring high environmental resistance, such as flooring or fencing (Jahanban-Esfahlan et al., 2019).

Walnut shell derivatives are used as absorbents to remove hazardous substances such as heavy metals, hazardous compounds, and synthetic industrial colors (Fordos et al., 2023).

ACADEMIC STUDIES CONDUCTED

Fordos et al. (2023), in their study, examined the latest developments regarding the functional aspects of walnut waste (shell and shell/trunk) in various fields. They investigated the creation of walnut shell (WS) and carbon-based materials such as activated carbons and unmodified/modified WS as adsorbents. As a result of the study, it was understood that WS has antioxidant properties. It was found that it can be used in textile and protein filters. It was determined that these wastes can be used as sustainable and environmentally friendly alternatives in agriculture, laboratory, medicine and food industries.

In their article, **Abdulwahid et al. (2024)** investigated the use of walnut shells in some building materials. As a result of the study;

- ✓ Walnut shells can be included in the manufacture of some building materials to ensure sustainability in the construction sector,
- ✓ It is an agricultural waste that can be converted into usable materials,
- ✓ The low specific gravity of walnut shells makes them an inexpensive agricultural waste for the development of building materials,
- ✓ It was understood that walnut shells in granular form can be used in the production of building elements and thermal insulation concrete.

Beskopylny et al. (2023) analyzed the effect of compositional factors on the properties of concrete by partially replacing coarse aggregates with walnut shells. They investigated the optimum composition that provides the maximum reduction in concrete density and the minimum reduction in strength properties. They produced cube and prism laboratory specimens from normal density concrete with coarse aggregate substitution at rates of 5%, 10%, 15%, 20%, 25%, and 30% by volume. They examined the main mechanical properties of the concrete specimens, such as density and strength (compressive, tensile, and flexural tensile strength). They observed an increase in strength properties of up to 3.5% and a maximum value in the strength/density ratio of the concrete when the walnut shell dosage was 5%. They determined

that partially and effectively replacing coarse aggregate with walnut shells led to a reduction in crushed stone consumption of up to 10% and a reduction in concrete mass of up to 6%.

Ren et al. (2025) used walnut shell (WS) as an internal curing agent to reduce the AS value of ultra-high performance concrete (UHPC) in their study. They investigated the effect of WS on AS, internal relative humidity, mechanical strength, heat of hydration, and the microstructure of the UHPC matrix. According to the results obtained:

- ✓ When 3-9% WS was added, the AS value of the UHPC matrix decreased by 47.0%-74.5% in 7 days.
- ✓ The compressive and flexural strengths of the UHPC matrix decreased by 7.0%-15.5% and 8.9%-17.1%, respectively, on the 28th day.
- ✓ After adding 3%, 6%, and 9% WS, the average chain length of C-S-H increased by 35.5%, 50.4%, and 73.8%, respectively, compared to plain samples.

El Hamri et al. (2025), in their article, investigated the use of walnut shell particles (WSP) as a sustainable reinforcement material in cement boards (WSCB). They used super white cement (SWC) as a binder. They aimed for a density of 1300 kg/m³, a thickness of 10 mm, and a water-cement ratio of 0.6:1, and produced boards with WSP content ranging from 10% to 50% by weight. The mixtures were cold-pressed at room temperature for 24 hours at 3 MPa pressure using a hydraulic press, and then cured at room temperature for 28 days. They evaluated physical properties such as density, water absorption, and thickness swelling, and mechanical performance through bending tests. They determined that the 24-hour water absorption rate of the board containing 30% WSP was 14.05%. They reported that it exhibits an optimum balance of physical and mechanical properties with a modulus of fracture (MOR) of 6.53 MPa and is suitable for non-structural applications. They determined that the board containing 50% WSP has the best thermal insulation performance with a low thermal conductivity of 0.079 W/mK.

Jannat et al. (2022) used eggshells and walnut shells in the production of unbaked clay blocks in their study. First, they produced three series of samples using eggshells (10-50%) and walnut shells (5-20%) separately, and then a mixture (5% walnut, 10-30% eggshell). They then evaluated the physical and mechanical properties of the unbaked clay blocks. Density, capillary water absorption, linear shrinkage, flexural and compressive strength tests were conducted in the study. As a result, they reported that:

- ✓ When the materials were used separately, eggshell increased the strength compared to the control sample,
- ✓ Walnut shell decreased the strength,
- ✓ Combining the two materials in the mixer further reduced the strength of the samples,
- ✓ Adding waste materials reduced the density, capillary water absorption coefficient, and linear shrinkage of the samples,
- ✓ Eggshell has great potential for the production of unbaked clay blocks,
- ✓ The integration of walnut shell requires further research.

Chilmon et al. (2025) investigated the effects of ground walnut shell (GWS) on the structural, load-bearing, contaminant retention properties of permeable concrete and on the water treatment efficiency of heavy metal zinc. They evaluated the effect of GWS as an internal curing agent on the basic mechanical and physical properties of permeable composite. They found that this modification had a statistically significant effect on the properties studied. As a result:

- ✓ GWS increased the porosity of the cement matrix by acting as an internal curing agent.
- ✓ They observed a slight deterioration in the mechanical performance of permeable concrete at lower GWS contents (2% and 10%).
- ✓ Reference samples exhibited significantly higher compressive strength relative to their effective porosity compared to mixtures modified with GWS.
- ✓ The presence of GWS altered the typical strength-porosity relationship observed in permeable concrete.

- ✓ Due to the increased capillary pore content, the immobilization efficiency of GWS-modified concrete doubled under static test conditions compared to the reference series (from approximately 27% to 54%).
- ✓ In dynamic flow tests, contaminant contact was limited to the outer cement matrix layer.
- ✓ The interface transition zone (ITZ) between the cement matrix and the internal curing agent (GWS particles) was a factor that significantly affected the immobilization potential of the permeable concrete.

In their study, **Da Silva (2017)** evaluated the ability of walnut shell-modified Medium Density Fiberboard (MDF) to regulate RH, toluene, limonene, dodecane, and formaldehyde. They evaluated the adsorption and desorption behavior of MDF containing up to 15% walnut shells in 2-liter environmental chambers under dynamic conditions at 23 °C and 50% RH. They analyzed the porous microstructure and chemical composition of MDF and walnut shell using SEM, XRD, and FTIR. The porous surface of the walnut shell increased the specific surface area of the panel and thus its adsorption capacity. Improved moisture stabilization capacity occurred. The ability to adsorb water-soluble VOCs such as formaldehyde was enhanced. This research provides significant evidence that walnut shell-modified MDF can improve indoor air quality.

Kozub and Castro-Gomes (2022), in their article, investigated the effects of different weight percentages of ground walnut shells and quartz sand on the density and strength properties (including compressive and flexural strength, thermal conductivity, salinization, and water absorption) of fly ash-based geopolymers. They analyzed the microstructure of the geopolymers studied using scanning electron microscopy (SEM). They observed that the addition of ground walnut shells reduced the density and mechanical properties, increased the absorption properties, and decreased the porosity of the fly ash-based geopolymers. Furthermore, they reported that the addition of ground walnut shells significantly reduced salinization on the surface of the tested geopolymer composites.

Charai et al. (2022) investigated the thermal performance of a novel biocomposite (clay-walnut shell) in their study. First, they performed geotechnical analysis on the soil. To evaluate the thermal effect of walnut shell on unfired clay bricks, they substituted walnut shell at different weight percentages (0%, 10%, and 20%). Then, they compared the thermophysical properties of the produced biocomposites with those of clay alone. They measured the thermal conductivity properties using the hot disk method. They compared the dynamic thermal behavior of two types of walls (concrete block wall and clay brick wall - 20% by weight walnut shell). Thermal analysis showed that walnut shell improved the thermal insulation of unfired bricks while reducing their density. The addition of 20% by weight walnut shell reduced the thermal conductivity of the clay by 45.22%, increasing its thermal resistance. Numerical findings revealed that the use of the developed composites improved the energy performance of residential buildings and provided energy savings of 10.8% and 7.94% for heating and cooling needs, respectively.

Abdulwahid and Abdullah (2021) investigated the effect of walnut shells on different properties of mortar. They examined the dry density, thermal conductivity, compressive strength, and flexural strength of the mortar. They determined the percentages of walnut shells used as substitutes for sand as 5%, 10%, and 15%. The walnut shells used in the study were treated by soaking them in boiling water for half an hour and one hour. In all mortar mixtures, cement, sand, and water were used in a ratio of 1:3:0.7 by weight, respectively. The test results showed that using 15% walnut shells treated for half an hour reduced the density and thermal conductivity of the mortar by 15% and 31%, respectively. The compressive and flexural strength of the mortar decreased by 17% and 25%, respectively, after 28 days of moist curing compared to the control mortar. They found that soaking walnut shells in boiling water for half an hour improved the properties of the mortar compared to those that were not soaked.

Hilal et al. (2020), in their study, selected crushed walnut shells (CWS) as a partial replacement for coarse and fine aggregates at rates of 5% to 25%. First, fine aggregates were replaced with CWS at the specified rates. Second, coarse aggregates were replaced with CWS at the specified rates. Third, fine and coarse aggregates were replaced with CWS at the same rates. All samples were subjected to absorption rate, compressive strength, flexural strength, splitting strength, and dry density tests after 28 days. The results reported that all properties except absorption rate decreased when CWS was used. They stated that the best results were obtained when both fine and coarse aggregates were replaced with CWS. They achieved advantageous values with a 15% CWS replacement for both aggregate types.

RESULTS

Walnut shells have become a subject of research in building material production for bio-based, lightweight, and environmentally friendly solutions. Walnut shells have been shown to reduce the unit weight of concrete and mortar, increase water absorption, and provide heat and sound insulation. Walnut shells, thanks to their fibrous and porous structure, are used in the production of thermal insulation panels and acoustic insulation boards. Walnut shell powder or granules, used in the production of composite materials, are utilized as filler or reinforcement material in wood-plastic composites (WPC) and fiberboard (MDF-like panels). This reduces the petrochemical content of the composites and provides an aesthetically pleasing, natural texture. Walnut shells burn during the firing of bricks, creating voids. This void reduces the density and thermal conductivity of the brick. It is possible to produce energy-efficient, lightweight bricks by substituting walnut shells. Decorative panels and interior coverings with a natural texture can be produced by using walnut shells in the production of surface coating materials.

REFERENCES

- Abdulwahid, M. Y., Akinwande, A. A., Kamarou, M., Romanovski, V., & Al-Qasem, I. A. (2024). The production of environmentally friendly building materials out of recycling walnut shell waste: A brief review. *Biomass Conversion and Biorefinery*, 14(20), 24963-24972.
- Abdulwahid, M. Y., & Abdullah, S. F. (2021). The utilization of walnut shells as a partial replacement of sand in mortar mixes. *Structural Concrete*, 22, E300-E307.
- Adıbelli, Ü. (2022). Investigation of the mechanical behavior of walnut shell-filled epoxy hybrid composite materials, Master's Thesis, Yalova University, Graduate Education Institute, Yalova.
- Adıbelli, Ü., Mutlu, D., Çakır Yiğit, N., & Karagöz, İ. (2022). Preparation and characterization of walnut shell-filled epoxy hybrid composite materials. 10th International Fiber and Polymer Research Symposium, 13-14.
- Akhlaghi SP, Abbasian A, Talaiepour M, Resalati H (2011) Walnut shell flour as a filler in polypropylene: effect on mechanical and thermal properties. *Journal of Applied Polymer Science*, 121(5), 2895-2902.
- Alizada, A. (2020). The use of modified walnut shell waste with alkalis and various acids as a filler in phenolic epoxy resin, Master's Thesis, Selçuk University Institute of Science, Konya.
- Barnabas, A. A., Balogun, O. A., Akinwande, A. A., Ogbodo, J. F., Ademati, A. O., Dongo, E. I., & Romanovski, V. (2023). Reuse of walnut shell waste in the development of fired ceramic bricks. *Environmental Science and Pollution Research*, 30(5), 11823-11837.
- Beskopylny, A. N., Stel'makh, S. A., Shcherban', E. M., Mailyan, L. R., Meskhi, B., Shilov, A. A., ... & El'shaeva, D. (2023). Effect of walnut-shell additive on the structure and characteristics of concrete. *Materials*, 16(4), 1752.

Charai, M., Horma, O., Mezrhab, A., & Karkri, M. (2022). Thermal insulation of mud bricks made with walnut shells: Characterization and simulation study. *Materials Today: Proceedings*, 62, 4545-4550.

Chilmon, K., Kalinowski, M., Bogacki, J., & Woyciechowski, P. (2025). From waste to function: Ground walnut shells as a reactive additive for heavy metal removal in pervious concrete. *Construction and Building Materials*, 498, 144035.

Çakır NY, Karagöz İ (2021). Preparation and characterization of walnut shell-based polylactic acid (PLA) composite filaments. 9th International Fiber and Polymer Research Symposium, Uşak, Türkiye, November 19-20.

Çavuşoğlu, A., Uysal, N., Aslan, H. Ç., & Karagöz, İ. (2023, May). Production of environmentally friendly green composite materials for sustainability: Characterization of walnut shell and polypropylene blends. In 12th International Fiber and Polymer Research Symposium (pp. 5-6).

Da Silva, C. F., Stefanowski, B., Maskell, D., Ormondroyd, G. A., Ansell, M. P., Dengel, A. C., & Ball, R. J. (2017). Improvement of indoor air quality by MDF panels containing walnut shells. *Building and Environment*, 123, 427-436.

El Hamri, A., Mouhib, Y., Chkala, H., Oulhakem, O., Chigr, M., & El Mansouri, N. E. (2025). Investigating the Potential of Using Walnut Shell Particles for Manufacturing Cement-Bonded Particle Boards. *Journal of Composites Science*, 9(4), 183.

Fordos, S., Abid, N., Gulzar, M., Pasha, I., Oz, F., Shahid, A., ... & Aadil, R. M. (2023). Recent development in the application of walnut processing by-products (walnut shell and walnut husk). *Biomass Conversion and Biorefinery*, 13(16), 14389-14411.

Güvenç, İ., Kazankaya, A., 2019, Walnut production, foreign trade and competitiveness in Turkey, *Yüzüncü Yıl University Journal of Agricultural Sciences*, 29(3), 418-424.

Hashemi SA, Shoushtari AM, Jalali-Arani A (2016) Curing behavior and mechanical properties of modified walnut shell powder/epoxy composites. *Journal of Composite Materials*, 50(11), 1421-1432

Hilal, N., Mohammed Ali, T. K., & Tayeh, B. A. (2020). Properties of environmental concrete that contains crushed walnut shell as partial replacement for aggregates. *Arabian Journal of Geosciences*, 13(16), 812.

Jahanban-Esfahlan, A., Ostadrahimi, A., Tabibiazar, M., Amarowicz, R., 2019, A comprehensive review on the chemical constituents and functional uses of walnut (*Juglans* spp.) husk, *International Journal of Molecular Science*, 20(16), 3920, 1-37.

Jannat, N., Latif Al-Mufti, R., & Hussien, A. (2022). Eggshell and Walnut shell in unburnt clay blocks. *CivilEng*, 3(2), 263-276.

Juglans L (2022) The Plant List. <http://www.theplantlist.org/1.1/browse/A/Juglandaceae/Juglans/>

Kaya, N., Yücel, A. T., Konkan, A., Mocur, D., & Gültekin, M. (2011). Removal of disperse azo dyes from aqueous solutions using walnut shells and hazelnut shells. *Gazi University Faculty of Engineering and Architecture Journal*, 26(3), 1-15.

Kozub, B., & Castro-Gomes, J. (2022). An investigation of the ground walnut shells' addition effect on the properties of the fly ash-based geopolymer. *Materials*, 15(11), 3936.

Pasbakhsh P, Hemmasi AH, Ehsani M, Rashedi A (2017) Effect of walnut shell flour on the physical, mechanical, thermal, and morphological properties of the linear low-density polyethylene. *Journal of Thermoplastic Composite Materials*, 30(3), 383-397.

Ren, G., Su, A., & Gao, X. (2025). Recycling waste walnut shells as a sustainable internal curing material for ultra-high performance concrete matrix. *Journal of Building Engineering*, 114369.

INTERNATIONAL TOPKAPI CONGRESS VI

Sönmez, S., Genç, G., Yüce, H., (2018). The effect of surface topography of waste walnut shell reinforced bio-composite material on print quality, 6th International Printing Technologies Symposium, 319-328.

Web ileti 1. <https://www.milliyet.com.tr/egitim/haritalar/turkiye-ceviz-uretim-haritasi-ceviz-nerelerde-yetisir-il-il-en-cok-ceviz-yetistirilen-bolgeler-6307450>. Access date:15.12.2025.

**DERİN ÖĞRENME TABANLI U-NET MİMARİSİ İLE BEYİN MRG
GÖRÜNTÜLERİNDE BÖLÜTLEME**
SEGMENTATION OF BRAIN MRI IMAGES USING A DEEP LEARNING BASED U-NET
ARCHITECTURE

Esra TAYAN

Arş. Gör., Haliç Üniversitesi Mühendislik Fakültesi Bilgisayar Mühendisliği Bölümü, Eyüp,
İstanbul.

Ferhat BOZKURT

Doç. Dr., Atatürk Üniversitesi Mühendislik Fakültesi Bilgisayar Mühendisliği Bölümü,
Yakutiye, Erzurum.

ÖZET

Beyin tümörlerinin erken teşhisi, yaşam kalitesinin korunması açısından büyük önem taşımaktadır. Beyin tümörü bölgelerinin otomatik olarak bölütlenmesi, Manyetik Rezonans Görüntülemeye (MRG) daha hızlı karar alabilmeyi sağlamaktadır. Son yıllarda gelişen derin öğrenme yöntemleri sayesinde, MRG görüntüleri kullanılarak dokulardaki anormal bölgeler daha hızlı ve kolay bir şekilde tespit edilebilmektedir. Yapılan bu çalışmada, The Cancer Imaging Archive (TCIA) kaynağından alınan ve Kaggle platformunda açık erişimli olarak paylaşılan Brain MRI Segmentation Dataset (Beyin MRG Bölütleme Veri Seti) kullanılmış ve bu veri setindeki görüntülerde yer alan sıvı baskılanmış inversiyon toparlanma (FLAIR) anormalliklerinin bölütlenmesi incelenmiştir. Veri seti, 110 hastadan elde edilen beyin Manyetik rezonans (MR) görüntüleri ile bu görüntülere karşılık gelen manuel FLAIR anormallik bölütleme maskelerinden oluşmaktadır. Çalışmada kullanılan görüntülere temel ön işleme adımları uygulanmış ve görüntüler uygun model girdisi hâline getirilmiştir. Bölütleme süreci, U-Net tabanlı derin öğrenme mimarisi kullanılarak gerçekleştirilmiştir. Elde edilen bölütleme performansına ilişkin çıktılar, manuel referans maskeler baz alınarak sayısal ölçütler aracılığıyla değerlendirilmiştir. Analiz sonucunda elde edilen bulgular, U-Net mimarisinin FLAIR anormalliklerinin bölütlenmesinde etkili bir yöntem olduğunu göstermiştir. Bu çalışma, MR görüntüleri üzerinden otomatik bölütleme uygulamaları için yeniden üretilebilir bir yöntem ortaya koymaktadır.

Anahtar Kelimeler: Beyin MRI, FLAIR anormalliği, Derin öğrenme, U-Net, ResU-Net, AttentionU-Net, Görüntü bölütlemesi

ABSTRACT

Early diagnosis of brain tumors is of great importance for preserving quality of life. The automatic segmentation of brain tumor regions in magnetic resonance imaging (MRI) enables faster clinical decision-making. In recent years, advancements in deep learning methods have made it possible to identify abnormal tissue regions more rapidly and effectively using MRI images.

In this study, the Brain MRI Segmentation Dataset, obtained from The Cancer Imaging Archive (TCIA) and openly available on the Kaggle platform, was used to investigate the segmentation of FLAIR abnormalities in brain MRI images. The dataset consists of brain magnetic resonance (MR) images acquired from 110 patients along with corresponding manually annotated FLAIR abnormality segmentation masks. The images used in the study were subjected to basic preprocessing steps and prepared as suitable inputs for the segmentation model.

The segmentation process was carried out using a U-Net-based deep learning architecture. The segmentation performance outputs were evaluated using numerical metrics based on manual

reference masks. The findings obtained from the analysis indicate that the U-Net architecture is an effective method for the segmentation of FLAIR abnormalities. This study presents a reproducible methodology for automatic segmentation applications using MR images.

Keywords: Brain MRI, FLAIR abnormality, Deep learning, U-Net, ResU-Net, AttentionU-Net, Image segmentation

GİRİŞ

Manyetik rezonans görüntüleme (MRG) görüntülerinden beyin tümörlerinin doğru bölütlemesini, çok modlu görüntü birleştirme öğrenimi için temel bir ön koşuldur. Ancak klinik uygulamalarda, her zaman eksiksiz bir MRG görüntü seti elde edilememekte; modalite eksikliği, mevcut çok modlu bölütleme yöntemlerinin performansını ciddi ölçüde düşürebilmektedir [1]. Tıbbi görüntüleme teknolojilerindeki gelişmeler, beyin tümörü hastalarının tanı ve tedavi süreçlerinin değerlendirilmesinde önemli bir rol oynamakta ve doktorlara insan vücudunun iç yapısını ayrıntılı ve net bir şekilde görüntüleme imkânı sunmaktadır [2].

T1 ağırlıklı, T2 ağırlıklı ve FLAIR gibi çok modlu manyetik rezonans görüntüleme teknikleri, tümör dokusu, ödem ve sağlıklı beyin parankimi arasındaki ayrımı güçlendiren tamamlayıcı bilgiler sağlamaktadır [3]. Bu modaliteler genellikle birlikte kullanılarak beyin tümörlerinin konumu ve boyutu daha doğru bir şekilde belirlenmektedir. Günümüzde MR cihazlarının klinik ortamlarda yaygın olarak kullanılması, büyük miktarda beyin MR görüntüsünün üretilmesine yol açmış; bu durum, görüntülerin manuel olarak etiketlenmesini ve bölütlenmesini hem zaman alıcı hem de öznel hâle getirmiştir [4]. Ayrıca manuel bölütleme işlemi büyük ölçüde uzman doktorların deneyimine bağlıdır. Bu nedenle, son yıllarda araştırmalar beyin tümörlerinin otomatik, hızlı ve doğru bir şekilde bölütlenmesine yönelik yöntemlere yoğunlaşmıştır.

Yapay zekâ alanındaki gelişmelerle birlikte, özellikle Evrimsel Sinir Ağları (CNN'ler) ile temsil edilen derin öğrenme yaklaşımları, beyin tümörü bölütleme çalışmalarında üstün performansları nedeniyle büyük ilgi görmüştür [5]. CNN tabanlı yöntemler, geleneksel görüntü işleme adımlarına duyulan ihtiyacı azaltarak, doğrudan ağ mimarisi üzerinden etkili özellik çıkarımı yapılmasına olanak tanımaktadır. Derin öğrenme yaklaşımları, görüntü bölütlemesinde sıkça karşılaşılan ve genellikle tekrarlayan ayrıntılar ile karmaşık doku yapılarından kaynaklanan görüntü kararsızlığı probleminin azaltılmasında önemli bir rol oynamaktadır [6]. Bu sorunun üstesinden gelmek amacıyla, U-Net ve türevleri gibi kodlayıcı–kod çözücü tabanlı mimariler yaygın olarak kullanılmaktadır. Özellikle çok ölçekli ve çok kanallı özellik çıkarımına olanak tanıyan bu mimariler, görüntülerden elde edilen uzamsal ve anlamsal bilgilerin dengeli bir şekilde öğrenilmesini sağlamaktadır [7]. ResUNet mimarisi, derin ağlarda karşılaşılan gradyan kaybolması ve ağ bozulması problemlerini azaltmak için artık (residual) bağlantılardan yararlanırken [8], Attention U-Net mimarisi ise dikkat kapıları aracılığıyla ilgi alanlarına (ROI) odaklanmakta ve arka plan bilgisinin etkisini baskılamaktadır [9]. Ayrıca sınıf dengesizliği problemini azaltmak amacıyla, hibrit kayıp fonksiyonlarının kullanımı son yıllarda yaygın bir yaklaşım hâline gelmiştir [10].

Farklı görüntüleme türlerinin birlikte kullanılması, beyin tümörü bölütlemesinde önemli gelişmeler sağlamıştır. Araştırmalarda genellikle kanal düzeyinde çok modlu MRG verilerinin birleştirilmesi veya gizli bir alanda kümeleme gibi çeşitli yöntemler incelenmektedir. Bununla birlikte, klinik uygulamalarda görüntü verilerinin bozulması, tarama protokollerindeki merkezler arası farklılıklar ve hastaya özgü koşullar nedeniyle her zaman eksiksiz bir MRG veri seti elde etmek mümkün olmayabilmektedir. Bu tür durumlarda, mevcut çok modlu yöntemlerin önemli bir kısmı eksik modaliteleri etkin biçimde ele alamamakta ve buna bağlı olarak bölütleme performansında belirgin düşüşler gözlenmektedir. Bu yüzden, bir veya daha fazla görüntüleme türü eksik olsa bile güvenilir sonuçlar verebilen etkili ve sağlam çok modlu bölütleme yöntemleri geliştirmek, güncel araştırmalarda önemli bir konu olmuştur.

Yapılan son çalışmalar beyin tümörü bölütlemesi için kullanılan U-Net tabanlı mimarilerinin önemli ilerlemeleri sağladığını göstermektedir. Danesh Pajouh ve arkadaşları dikkat kapılılarının kullanıldığı kodlayıcı-kod çözücü bloklara sahip bir U-Net mimarisi önermişlerdir. Beyin Tümörü Bölütlemesi 2020 (BraTS 2020) veri setiyle elde edilen bulgular, tümörlerin karmaşık sınırlarının daha hassas bölütlemesine tabi tutulabileceğini göstermektedir [11]. Benzer şekilde, Jia ve meslektaşları (2025) tarafından geliştirilen UPMAD-Net modeli, belirsizlik odaklı öğrenme ve uyarlanabilir multimodal özelliklerin entegrasyonu ile BraTS 2019 ve BraTS 2021 veri kümelerinde yüksek Dice puanları elde etmiştir. Bu çalışma, çok ölçekli özelliklerin eşzamanlı öğrenilmesinin bölütleme başarısına doğrudan katkı sağladığını göstermektedir [12].

Ansab ve Jabbar (2024) ise üç boyutlu Hibrit Çok Başlıklı Attention U-Net mimarisi ile derin ağlarda dikkat mekanizmalarının etkinliğini incelemiş, BraTS 2020 veri seti üzerinde klasik U-Net yaklaşımlarına kıyasla daha dengeli ve kararlı sonuçlar rapor etmiştir [13]. Öte yandan, Jiang ve arkadaşları (2024), manyetik rezonans görüntülerinden elde edilen özellikleri kullanarak tümör alt tiplerini ayırt edebilen bir ansambl model önermiş ve BraTS 2024 kapsamında yapılan deneylerde yüksek doğruluk oranlarına ulaşmıştır [14]. Daha yakın tarihli bir çalışmada, Scientific Reports'ta yayımlanan bir araştırma (2025), çoklu kodlayıcı yapılar ve transfer öğrenme stratejilerini bir araya getirerek özellikle pediatrik beyin tümörlerinde başarılı bölütleme sonuçları elde etmiştir. Bu çalışma, derin öğrenme tabanlı yöntemlerin klinik uygulanabilirliğini artırmaya yönelik önemli bir adım olarak değerlendirilmektedir [15].


ARAŞTIRMA VE BULGULAR

Bu bölümde, çalışmada izlenen metodolojik yaklaşım, kullanılan veri kümesinin temel özellikleri, geliştirilen derin öğrenme tabanlı bölütleme mimarileri ve deneysel analizlerden elde edilen bulgular sunulmaktadır. Çalışmanın odağında, Düşük Dereceli Gliom (Low-Grade Glioma, LGG) tümörlerinin manyetik rezonans (MR) görüntüleri üzerinden otomatik olarak bölütlenmesi yer almaktadır. Bu kapsamda, U-Net tabanlı farklı mimari yaklaşımların — standart U-Net, artık (residual) bağlantılarla güçlendirilmiş U-Net ve dikkat mekanizması içeren U-Net — bölütleme performansları karşılaştırmalı olarak incelenmiştir.


Materyal ve Yöntem

Veri Kümesi ve Özellikleri

Çalışmada, The Cancer Genome Atlas (TCGA) projesi kapsamında derlenen ve açık kaynak olarak paylaşılan LGG Segmentation Dataset kullanılmıştır. Veri seti, histolojik olarak doğrulanmış 110 hastaya ait toplam 3.929 adet orijinal beyin MRG kesitinden oluşmaktadır. Kullanılan görüntüler, tümör dokusu ile ödemin sağlıklı dokudan ayrışmasında en belirgin kontrastı sağlayan FLAIR (Fluid-Attenuated Inversion Recovery) sekans ağırlıklı görüntülerdir. Rastgele seçilmiş pozitif ve negatif MR görüntüleri ve bu görüntülere ait maske örnekleri Şekil 1'de verilmiştir.



(a)




(b)


Şekil 1: Pozitif (a) ve Negatif (b) Görüntüler ve Maskeler

Ön İşleme ve Veri Artırma (Data Augmentation)

Veri setinin ham dağılımı incelendiğinde, sağlıklı (negatif) örneklerin tümörlü (pozitif) örneklerle kıyasla sayıca üstün olduğu ve belirgin bir sınıf dengesizliği (class imbalance) içerdiği gözlemlenmiştir [16]. Bu dengesizliğin modelin öğrenme sürecini olumsuz etkilemesini önlemek amacıyla, veri seti hasta bazlı ayırım gözetilerek Eğitim, Doğrulama ve Test olmak üzere üç alt kümeye ayrılmıştır. Eğitim aşamasında, azınlıkta kalan tümörlü sınıfın temsiliyetini artırmak ve modelin farklı mekânsal varyasyonlara karşı genelleme yeteneğini güçlendirmek amacıyla yalnızca eğitim kümesi üzerinde yeniden örnekleme (resampling) ve veri artırma işlemleri uygulanmıştır [17]. Bu kapsamda, eğitim sürecinde görüntülere rastgele rotasyon, yatay ve dikey kaydırma, yakınlaştırma ve yatay eksende çevirme işlemleri uygulanmış; aynı dönüşümler karşılık gelen maske görüntülerine de eş zamanlı olarak uygulanarak mekânsal tutarlılık korunmuştur. Bu işlemler sonucunda eğitim kümesi, sınıflar arası dağılım daha dengeli olacak şekilde genişletilerek toplam 4.150 görüntüye ulaştırılmıştır. Buna karşılık, modelin gerçek dünya performansının tarafsız biçimde değerlendirilebilmesi ve veri sızıntısının (data leakage) önlenmesi amacıyla, Doğrulama ve Test kümeleri herhangi bir sentetik müdahaleye tabi tutulmamış ve ham hâllerleriyle korunmuştur [18]. Veri artırma işlemlerinin görsel çıktılar üzerindeki etkisini göstermek amacıyla, artırma öncesi ve sonrası örnek MR görüntüleri Şekil 2’de karşılaştırmalı olarak sunulmuştur.



(a)



Şekil 2: Veri setindeki sınıf dağılımı (a), Veri artırma (data augmentation) sonrası sınıf dağılımı (b)

Ağ Mimarileri

Bu çalışmada, bölütleme başarısını karşılaştırmalı olarak değerlendirebilmek amacıyla U-Net tabanlı üç farklı derin öğrenme mimarisi ele alınmış ve tüm modeller aynı eğitim koşulları altında eğitilmiştir. Bu yaklaşım sayesinde, elde edilen sonuçlar üzerindeki etkinin eğitim stratejilerinden ziyade doğrudan mimari farklılıklardan kaynaklanması hedeflenmiştir. U-Net ve bu mimariden türetilen modellerin, tıbbi görüntü bölütleme görevlerinde güçlü, kararlı ve genellenebilir bir yapı sunduğu; özellikle beyin tümörü analizlerinde yaygın biçimde tercih edildiği ve başarılı sonuçlar verdiği, güncel literatürde birçok çalışma tarafından ortaya konmuştur [3], [7], [11], [15].

Bu kapsamda, Standart U-Net mimarisi çalışmada karşılaştırmalar için temel bir referans model olarak ele alınmıştır. Söz konusu mimari, simetrik bir kodlayıcı–kod çözücü yapıya sahip olup, görüntüden anlamlı özniteliklerin çıkarılması ve bu bilgilerin bölütleme maskesine dönüştürülmesi esasına dayanmaktadır. Kodlayıcı bölümde giriş görüntüsünden ayırt edici öznitelikler aşamalı olarak çıkarılırken, kod çözücü bölümde bu öznitelikler yeniden ölçeklendirilerek nihai bölütleme maskesi elde edilmektedir. Kodlayıcı ve kod çözücü katmanlar arasında yer alan atlamalı bağlantılar, alt seviyelerde kaybolabilecek mekânsal bilgilerin üst katmanlara doğrudan aktarılmasına olanak tanıyarak bölütleme sınırlarının daha tutarlı ve hassas biçimde belirlenmesini sağlamaktadır. Bu yapı, çok ölçekli özellik öğrenimi açısından literatürde etkin ve yerleşik bir temel mimari olarak kabul edilmektedir [3], [4].

ResU-Net mimarisi, Standart U-Net yapısının kodlayıcı bloklarının artık (residual) bağlantılar ile güçlendirilmesiyle oluşturulmuştur. Bu mimaride, her evrişim bloğunun giriş bilgisi, ilgili bloğun çıktısıyla birleştirilerek ağ boyunca aktarılmaktadır. Böylece öğrenilen özniteliklerin katmanlar arasında zayıflaması önlenmekte ve bilgi akışı daha dengeli bir şekilde sürdürülmektedir. Artık bağlantıların kullanımı, derin ağlarda sıklıkla karşılaşılan gradyan kaybolması ve performans düşüşü problemlerini azaltarak modelin daha karmaşık ve derin temsilleri istikrarlı biçimde öğrenmesine katkı sağlamaktadır. Bu yaklaşımın, U-Net tabanlı tıbbi görüntü bölütleme mimarilerinin başarımını anlamlı düzeyde artırdığı, güncel çalışmalarda da ortaya konmuştur [8], [9], [10].

Çalışmada en yüksek performansı elde eden Attention U-Net mimarisi ise, kod çözücü aşamasındaki atlamalı bağlantılara dikkat kapılarının (attention gates) entegre edilmesiyle geliştirilmiştir. Standart U-Net yapısında kodlayıcıdan gelen tüm öznitelikler doğrudan aktarılırken, dikkat mekanizması bu bilgileri bağlamsal olarak değerlendirerek yalnızca ilgili bölgelerin ön plana çıkarılmasını sağlamaktadır. Bu sayede model, bölütleme açısından daha az önemli olan arka plan dokularının etkisini baskılamakta ve tümörlü bölgelere daha etkin biçimde odaklanabilmektedir. Dikkat mekanizmalarının özellikle sınırları belirsiz, küçük veya

heterojen tümör yapıların tespitinde anlamlı performans artışı sağladığı, son yıllarda önerilen çok sayıda gelişmiş U-Net türevi çalışmada vurgulanmıştır [6], [7], [11], [13].

Bulgular

Bu bölümde, önerilen mimarilerin test kümesindeki bölütleme performansları karşılaştırılmıştır. Modeller, tıbbi görüntü bölütlemeye yaygın olarak kullanılan Dice Benzerlik Katsayısı (Dice) ve Jaccard İndeksi (IoU) ile değerlendirilmiştir. Tüm modeller aynı eğitim protokolü ve hiperparametrelerle eğitilerek karşılaştırmanın tarafsızlığı sağlanmıştır. Böylece, performans farklarının yalnızca mimari tasarımlardan kaynaklandığı garanti edilmiştir. Test kümesinde ($n = 90$) elde edilen sonuçlar Tablo 1’de sunulmuştur. Sonuçlar, Standart U-Net modelinin beyin MRG görüntülerinin bölütlenmesinde temel bir referans performansı sunduğunu göstermektedir. Buna karşılık, kodlayıcı yapısı artık bağlantılarla güçlendirilen ResU-Net mimarisi, Dice ve IoU metriklerinde anlamlı bir performans artışı sağlamıştır. Bu iyileşme, artık bağlantıların derin ağlarda bilgi akışını artırması ve modelin ayırt edici öznelilikleri daha tutarlı öğrenmesini sağlaması ile açıklanmaktadır.

En yüksek performans, dikkat mekanizması ile güçlendirilen Attention U-Net mimarisiyle elde edilmiştir. Attention U-Net, hem Dice hem de IoU metriklerinde diğer iki mimariye göre daha iyi sonuçlar sunmuş ve özellikle tümör sınırlarının hassas belirlenmesinde üstünlük göstermiştir. Bu başarı, dikkat kapılarının ilgili bölgelere odaklanarak arka plan dokularının etkisini azaltmasına bağlanmaktadır.

Nicel sonuçlara ek olarak, görsel incelemeler Attention U-Net’in küçük ve sınırları belirsiz tümör bölgelerinde daha tutarlı ve bütüncül bölütleme çıktıları ürettiğini ortaya koymuştur. Standart U-Net modelinde bazı bölgelerde eksik veya dağınık tahminler gözlemlenirken, Attention U-Net tümör dokusunu daha homojen ve klinik açıdan anlamlı şekilde ayırt edebilmiştir.

Tablo1. Test kümesi üzerinde elde edilen bölütleme performansları

Model	Dice (DSC)	IoU (Jaccard)
Standart U-Net	0.8542	0.7456
ResU-Net	0.9208	0.8912
Attention U-Net	0.9311	0.9067

TARTIŞMA VE SONUÇ

Bu çalışmada, beyin manyetik rezonans görüntülerinde tümör bölütleme problemini ele almak amacıyla U-Net tabanlı üç farklı derin öğrenme mimarisi karşılaştırmalı olarak incelenmiştir. Tüm modellerin aynı eğitim protokolü ve hiperparametreler altında eğitilmesi, performans farklılıklarının doğrudan mimari tasarımlardan kaynaklandığını göstermektedir.

Standart U-Net mimarisi, karşılaştırmalar için temel bir referans olarak ele alındığında, bölütleme görevinde yeterli ve dengeli bir performans ortaya koymuştur. Buna karşılık, kodlayıcı yapısında artık (residual) bağlantılar kullanılan ResU-Net mimarisi, Dice ve IoU ölçütlerinde belirgin bir performans artışı sağlamıştır. Bu iyileşme, artık bağlantıların ağ içerisinde bilginin daha etkin taşınmasına ve daha ayırt edici özelliklerin öğrenilmesine katkı sunduğunu göstermektedir. Bu sonuç, artık bağlantıların derin ağlarda bilgi akışını destekleyerek gradyan zayıflaması problemini azalttığını ve daha ayırt edici özneliliklerin öğrenilmesine katkı sunduğunu göstermektedir. Attention U-Net mimarisi, karşılaştırılan tüm modeller arasında en yüksek bölütleme başarısını sergilemiştir. Mimariye entegre edilen dikkat kapıları sayesinde, kodlayıcıdan aktarılan öznelilikler bağlamsal olarak değerlendirilmiş ve modelin özellikle tümörlü bölgeler üzerinde daha seçici biçimde odaklanması sağlanmıştır. Bu yaklaşım, arka plan kaynaklı gereksiz bilgilerin etkisini azaltarak daha hassas bölütleme sonuçları elde edilmesine katkı sunmuştur. Bu yaklaşım, arka plan dokularının etkisini azaltmış ve özellikle sınırları belirsiz, küçük veya düzensiz tümör yapıların daha doğru biçimde tespit

edilmesini sağlamıştır. Elde edilen sonuçlar, dikkat mekanizmalarının tıbbi görüntü bölütleme görevlerinde önemli bir katkı sunduğunu ortaya koymaktadır.

Genel olarak değerlendirildiğinde, artık bağlantılar ve dikkat mekanizmalarıyla güçlendirilmiş U-Net türevlerinin, standart mimariye kıyasla daha kararlı ve güvenilir bölütleme sonuçları ürettiği görülmektedir. Bu çerçevede, Attention U-Net mimarisi beyin tümörü bölütleme uygulamaları için klinik karar destek sistemlerine entegre edilebilecek güçlü bir aday olarak öne çıkmaktadır. Ayrıca, mimarinin farklı ve daha geniş veri kümeleri üzerinde değerlendirilmesiyle performansının daha da artırılacağı öngörülmektedir.

KAYNAKLAR

- [1] Wang, G., Li, W., Ourselin, S., & Vercauteren, T. (2022). Automatic brain tumor segmentation using cascaded anisotropic convolutional neural networks. *Frontiers in Computational Neuroscience*, 16, 826938.
- [2] Chen, S., Ma, K., & Zheng, Y. (2020). Med3D: Transfer learning for 3D medical image analysis. *IEEE Transactions on Medical Imaging*, 39(7), 2360–2370.
- [3] Isensee, F., Jaeger, P. F., Kohl, S. A. A., Petersen, J., & Maier-Hein, K. H. (2021). nnU-Net: A self-configuring method for deep learning-based biomedical image segmentation. *Nature Methods*, 18, 203–211.
- [4] Zhou, Z., Siddiquee, M. M. R., Tajbakhsh, N., & Liang, J. (2020). UNet++: Redesigning skip connections to exploit multiscale features in image segmentation. *IEEE Transactions on Medical Imaging*, 39(6), 1856–1867.
- [5] Liu, Z., Lin, Y., Cao, Y., et al. (2021). Swin Transformer: Hierarchical vision transformer using shifted windows. In *Proceedings of the IEEE/CVF International Conference on Computer Vision (ICCV)*.
- [6] Abraham, N., & Khan, N. M. (2020). A novel focal Tversky loss function with improved attention U-Net for lesion segmentation. In *Proceedings of the IEEE International Symposium on Biomedical Imaging (ISBI)*.
- [7] Xu, Q., Zhang, Z., Xia, Y., & Zhang, S. (2023). DCSAU-Net: A deeper and more compact split-attention U-Net for medical image segmentation. *Computers in Biology and Medicine*, 156, 106702.
- [8] Khan, A. M., Islam, N., Jan, Z., et al. (2023). AttResDU-Net: Medical image segmentation using attention-based residual double U-Net. *arXiv preprint*, arXiv:2306.14255.
- [9] Jiang, H., Shi, T., Bai, Z., & Huang, L. (2020). An attention-guided U-Net with residual block for medical image segmentation. *IEEE Access*, 8, 12345–12356.
- [10] Akyel, C., & Arıcı, N. (2023). U-Net-RCB7: Image segmentation algorithm based on deep convolutional neural networks. *Politeknik Dergisi*, 26(4), 1427–1436.
- [11] Danesh Pajouh, M. M., et al. (2025). Efficient brain tumor segmentation using a dual-decoder 3D U-Net with attention gates. *arXiv preprint*.
- [12] Jia, Z., Yao, N., Sun, D., et al. (2025). UPMAD-Net: A brain tumor segmentation network with uncertainty guidance and adaptive multimodal feature fusion. *arXiv preprint*.
- [13] Ansab, M., & Jabbar, A. U. (2024). Hybrid multihead attentive U-Net-3D for brain tumor segmentation. *arXiv preprint*.
- [14] Jiang, Z., Capellán-Martín, D., Parida, A., et al. (2024). MRI feature-based subtyping and model ensemble for enhanced brain tumor segmentation. *arXiv preprint*.
- [15] Deep learning strategies for semantic segmentation of pediatric brain tumors in multiparametric MRI. (2025). *Scientific Reports*.
- [16] Buda, M., Maki, A., & Mazurowski, M. A. (2018). A systematic study of the class imbalance problem in convolutional neural networks. *Neural Networks*, 106, 249–259.

- [17] Shorten, C., & Khoshgoftaar, T. M. (2019). A survey on image data augmentation for deep learning. *Journal of Big Data*, 6(1), 60.
- [18] Kaufman, S., Rosset, S., Perlich, C., & Stitelman, O. (2012). Leakage in data mining: Formulation, detection, and avoidance. *ACM Transactions on Knowledge Discovery from Data*, 6(4), 1–21.

CHALLENGES OF TRANSLATING FOR THE NEW GENERATION: CHILDREN
VERSUS ADOLESCENTS

Fatemeh Aghakhani Chegeni (PhD Student of Translation Studies / University of
Isfahan)

Narjes Asgari Vartooni (MA Student of Translation Studies/ University of Isfahan)

Dr. Mahmoud Afrouz (Associate Professor/ University of Isfahan)

Abstract

Translating literature for young readers presents a complex, multifaceted set of challenges distinct from those involved in translating for adults. This paper argues that “young people’s literature” is not a single, uniform category. Instead, it must be understood through the specific developmental and social needs of two key groups: child readers (ages 0–12) and teen readers (ages 13–18). For child readers, translation is a multimodal and performative act. Key challenges include the necessity of synchronizing the text with fixed illustrations, preserving rhythmic and auditory features essential for read-aloud performance, and navigating the “gatekeeper paradox”—where translators must satisfy adult gatekeepers’ expectations regarding safety and educational value while still engaging authentically with children’s desire for fun and honesty. For teen readers, the central challenges revolve around authenticity and identity. Translators face the “slang trap,” where rapidly evolving teen slang or youth vernacular risks making a translation feel instantly outdated. There’s also the danger of creating inauthentic, “cringe-worthy” dialogue—a dialogue that sounds unnatural or “off,” failing to resonate with teen readers. Additionally, translators often encounter pressure to sanitize taboo themes common in young adult literature—such as sexuality, mental health, and profanity—which can dilute the realism and original intent of the source text. To address these challenges, the paper proposes some strategies. For children’s literature, it recommends a functional (Skopos) approach that prioritizes the intended effect—such as rhyme, rhythm, and image-text harmony—over strict semantic accuracy. For adolescent literature, it advocates a strategy of “current neutrality” in dialogue: avoiding fleeting slang in favor of more durable, informal youth language, and insisting on consulting teen beta readers to test authenticity. Ultimately, the core principle is respect: successful translation acknowledges and honors the intelligence and unique expectations of each young reader—whether six or sixteen years old.

Keywords: Translating literature, Skopos, adolescent literature, taboo, children’s literature

Introduction

Imagine reading a book in a language you don’t understand. Now, imagine someone wants to translate that book into your language—but it’s not an ordinary book. It’s either a picture book for a five-year-old or a novel for a sixteen-year-old. How would you translate it? Would you use the same words, the same tone, and the same style?

Probably not.

Translating books for young readers is not the same as translating books for adults. And even within the category of “young people’s literature,” there are significant differences between translating for children (ages 0–12) and teens (ages 13–18). These two groups have entirely different needs, interests, and ways of understanding the world. A good translation must take these differences into account.

This article explains that "young people's literature" is not a uniform category. It's two distinct worlds: the world of children and the world of teenagers. Each has its own rules, challenges, and expectations. We will examine these challenges one by one and show how translators can address them with care, creativity, and respect. Translators of children's literature should be trained professionally. Afrouz and Asgari Vartooni (2025a) define "a good translator trainer" as someone "who knows what 'good translation' means and possesses enough theoretical knowledge and practical experience in the field" (p. 1010).

In today's world where "Computer-Assisted Translation (CAT) tools and Translation Management Systems (TMS) have become essential components of professional English translation" (Asgari Vartooni & Afrouz, 2025c: 1625) and in the era of Artificial Intelligence (AI), "and neural machine translation (NMT)" which "has swept through the world of translation studies" (Afrouz & Asgari Vartooni, 2025b: 1625) and "transformed the translation industry" (Asgari Vartooni, Aghakhani Chegeni & Afrouz, 2025: 1634), it should be reminded that "while technology can significantly help us in terms of translation speed, it should be remembered that professional or specialized human translators can play a pivotal role in" transferring the source text or event (Asgari Vartooni & Afrouz, 2025a: 112). Researchers should concentrate on "the evolving role" of AI in translation of children's literature (Asgari Vartooni & Afrouz, 2025b: 103) and cultural issues raisin while confronting these texts. Cultural references pose great challenges since they encompass "foods, games, or family traditions which feel typical in the homeland and the source culture, but seem odd when sought in a different culture" (Aghakhani Chegeni et al, 2025: 119).

Part 1: The World of Children's Books (Ages 0–12)

Children's books are more than just words on a page. They are an experience. For young children, books often involve pictures, songs, rhymes, and sounds. Many are designed to be read aloud by an adult—perhaps a parent, teacher, or grandparent. For this reason, children's books are "multimodal." This means they don't just use words; they also rely on images, rhythm and melody, tone of voice, and even body movements.

That's why translating a children's book is not merely changing words from one language to another. It's about ensuring the entire experience remains engaging and meaningful in the new language.

Next, we explore three major challenges in translating for children.

Challenge 1: The Pictures Don't Change—But the Words Must Adapt

Most picture books have fixed illustrations. These images are already drawn and printed, ready before translation begins. This means the translator cannot change the image to match the new words. Instead, the words must match the image.

For example, suppose an illustration shows a cat wearing red socks. The original text says: "The cat put on red socks." But in the new language, the word for "socks" might be long or difficult. Perhaps the sentence no longer fits the rhythm of the page. Or maybe the word for "red" doesn't rhyme with the next line.

The translator must find a way to preserve the meaning, stay true to the image, and keep the text natural and fun. This is very difficult. Sometimes the translator has to change a small detail—for example, saying "red shoes" instead of "red socks"—if the image allows it. But it should never contradict the illustration.

Challenge 2: Sound Is Crucial

Children's books often use rhyme, rhythm, repetition of sounds (like "the bouncy brown bear"), and playful language. These features make listening to the book enjoyable. They also help children learn language and remember the story better.

But these sounds usually don't survive a literal translation. For instance, the English phrase "Hop on Pop" is short, rhythmic, and fun. A direct translation into another language might sound dull or confusing.

So, the translator must decide: Is preserving the exact meaning more important, or preserving its joyful, musical sound?

Often, the answer is: preserving the joyful sound is more important. Why? Because for young children, how a book sounds is as important as what it means. A dull translation might lose a child's attention—even if its meaning is perfectly accurate.

That's why translators of children's books often act like poets or composers. They don't just translate words—they recreate the music.

Challenge 3: The Gatekeeper Paradox

A translator sometimes plays the role of a researcher, a gatekeeper, and even a storyteller (Asgari Vartooni & Afrouz, 2026). Readers can also act as gatekeepers.

There's a curious fact: children's books are usually purchased and selected by adults—parents, teachers, librarians. These adults are the "gatekeepers." They decide which books are "good" or "safe" for children.

But the children themselves want books that are fun, exciting, surprising, or even a little naughty or scary.

This creates a dilemma for the translator: they must satisfy two audiences simultaneously.

On one hand, the adult gatekeepers want books that are educational, kind, and "appropriate." They may worry about violence, sadness, or complex topics.

On the other hand, children want honesty. They want stories that feel real—even if they're about talking animals or magic castles. They don't like being talked down to.

The translator must walk a fine line. They must keep the story appealing to the child while not ignoring the adult's concerns. Sometimes this means softening a scary scene. Other times, it means preserving a joke that adults might consider "silly" but children love.

The key is balance. And the secret to balance is respect—respect for the child's intelligence and the adult's concern.

A Useful Strategy: The Skopos Approach

To tackle these challenges, translators can use a method called the Skopos approach. This idea comes from translation theory and says: the most important thing is the text's purpose—not just its words.

The purpose of a children's book might be:

- To make a child laugh.
- To teach a gentle lesson.
- To create a soothing rhythm for bedtime.
- To match a colorful illustration.

If that's the purpose, the translator should focus on achieving it—even if it means straying a little from the original words.

For example, if the original book uses a wordplay (like a word with two meanings) that doesn't work in the new language, the translator can invent a new wordplay that fits the culture and still makes children laugh.

This isn't "cheating." It's intelligent translation. It shows the translator cares more about the reader's experience than a word-for-word rendering.

Part 2: The World of Teen Books (Ages 13–18)

Now let's move to the teenage years. Teen books—often called "Young Adult" (YA) literature—are completely different from children's books.

Teens are forming their identities. They question the world. They care deeply about issues like justice, friendship, love, mental health, and truth. They want stories that reflect their real lives—not simplified or sanitized tales.

Translating teen books comes with its own tough challenges. We'll examine three of the most important.

Challenge 1: The Slang Trap

Teens often use slang—words and phrases that change quickly and are specific to their age group and culture. Think of words like "lit" (awesome), "sus" (suspicious), "vibe" (feeling), or "cap" (lie). These words feel fresh and authentic... but they become outdated very fast.

If a translator uses the latest slang in a teen book, it might seem cool today—but tomorrow or the next day, it could seem "cringey" (awkward and embarrassing).

Worse, if a translator uses slang from another country or region, it might not make sense at all. For example, British slang like "bloke" (guy) or "chuffed" (pleased) wouldn't sound natural to American teens.

This is the "slang trap": the desire to be current can backfire, making the translation seem artificial or dated.

Challenge 2: "Cringey" Dialogue

Even without slang, teen dialogue is tricky. Teens are sensitive to anything that sounds "unnatural." If a character talks like an adult pretending to be a teen, or like a robot, teens will notice. And they'll stop reading.

The translator must create dialogue that feels natural, emotional, and real—exactly how real teens in that culture talk. This isn't just about words, but also rhythm, silences, pauses, and even what's left unsaid.

For example, a teen might just say "Whatever!" instead of "I disagree," or text "K" instead of "Okay, got it." A good translation must capture these nuances.

But here's the problem: many translators are adults. They might not spend much time with teens. They might rely on old memories or TV shows—which often portray teens in exaggerated or outdated ways.

The result? Dialogue that sounds stiff, artificial, or just plain wrong. That's what we call "cringey." And teens hate it.

Challenge 3: Taboo Topics and the Pressure to Sanitize Content

Many YA books deal with hard, real-life topics: depression, anxiety, gender, sexual identity, racism, substance use, or offensive language. These topics are part of many teens' lives. Including them makes stories honest and powerful.

But in some cultures or publishing markets, there is pressure to remove or soften these topics. Publishers, parents, or even governments might say, "These are too heavy for young readers."

This leads to what we call "sanitization"—making the story's content "safer." For example, a scene where a character has an anxiety attack gets cut. Or a romantic scene between two boys becomes just a friendship. Or strong words are replaced with milder ones.

But sanitization often hurts the story. It strips away its honesty. It tells teens, "Your pain isn't worthy of being in a book." Or worse: "You should be ashamed of these feelings."

For the translator, this is an ethical challenge. Should they follow local norms and soften the content? Or should they fight to preserve the author's original message?

It's not an easy choice. But if the goal is to respect the teen reader, then honesty usually wins.

A Useful Strategy: Current Neutrality and Teen Beta Readers

So, how can translators avoid these traps?

First, they can use a strategy called "current neutrality." This means avoiding trendy slang and instead using informal, natural language that appeals to youth but won't become outdated in a year. For example, instead of writing "That's so sus!" (which might quickly go out of style), the translator could write "That's so weird!" or "That gives me a bad feeling." These phrases are simple, honest, and lasting.

Second—and this is very important—translators should use teen beta readers. A beta reader is someone who reads the draft version before publication and gives feedback.

For teen books, beta readers should be actual teens—ages 13–18—from the target culture. They can tell the translator: "This line is weird," or "No teen talks like this," or "This scene really hit me."

This feedback is invaluable. It keeps the translation authentic. It shows the translator is listening to the real audience—not just guessing what they might like.

Some publishers skip this step to save time or money. But that's a mistake. Just as you can't design clothes for teens without asking them what they like, you shouldn't translate their stories without their input.

Part 3: The Common Thread—Respect

Although children and teens are different, one idea connects both groups: respect. Good translation for young readers begins with this question: Do I respect this reader?

For a six-year-old child, respect means not treating them like a baby. It means trusting they can handle emotions like sadness or fear—with care. It means harmonizing sounds and images to create joy.

For a sixteen-year-old teen, respect means not hiding the hard truths of life. It means trusting they can think about complex issues. It means letting them see themselves—with all their strengths, flaws, and dreams—in the pages of a book.

Many think that children's and teen literature is "simple" or "less important" than adult literature. But that's wrong. These books shape how young people see themselves and the world. A poor translation can confuse them, bore them, or make them feel unseen. But a good translation can open doors, build empathy, and even change their lives.

Translators have great power—and great responsibility.

Conclusion

Translating for young readers isn't one job. It's two completely different jobs. For children (ages 0–12), translation is a dance between words, images, sounds, and adult expectations. Success means harmony, rhythm, and joy.

For teens (ages 13–18), translation is about honesty, voice, and identity. Success means realism, authenticity, and genuine feeling. The tools are different: the Skopos theory for children; current neutrality and beta readers for teens. But the heart is the same: respect.

When translators honor the unique intelligence, emotions, and needs of each young reader—whether six or sixteen—they don't just translate words. They build bridges. And on the other side of that bridge are young readers who feel seen, heard, and valued. This is the true goal of translation. And it's a goal worth doing right.

References

Afrouz, M. & Asgari Vartooni, N. (2025a, October 13-17). *Beyond the Binary: Integrating Competence-Based Pedagogy and Authentic Assessment in Translation Training* [Paper presentation]. 11th International Congress on Global Practice of Multidisciplinary Scientific Studies. Munich, Germany. DOI: 10.5281/zenodo.17402543

INTERNATIONAL TOPKAPI CONGRESS VI

- Afrouz, M. & Asgari Vartooni, N. (2025b, November 18-20). *Devalued Labor in the Age of Automation: Economic Pressures on Human Translators in the Era of Generative AI* [Paper presentation]. 15th International "Communication in the New World" Congress. Ankara, Türkiye.
- Aghakhani Chegeni, F., Asgari Vartooni, N. & Afrouz, M. (2025, December 5-7). *Translating for children: Challenges, strategies, and cultural implications* [Paper presentation]. Fourth International Symposium on Literature, Culture and Language, Van, Türkiye.
- Asgari Vartooni, N. & Afrouz, M. (2025a, December 5-7). *Sport translation: The global language bridge—More than just words* [Paper presentation]. Fourth International Symposium on Literature, Culture and Language, Van, Türkiye.
- Asgari Vartooni, N. & Afrouz, M. (2025b, June 24-26). *Adult Translators for Child Readers: A Case Study of The Giving Tree in Persian Translation* [Paper presentation]. 7th International Black Sea Modern Scientific Research Congress, Artvin, Türkiye.
- Asgari Vartooni, N. & Afrouz, M. (2025c, December 27-28). *The Modern Translator's Toolkit: The Importance of Matecat, Lokalise, Trados Studio, and Phrase* [Paper presentation]. 5th International Gaziantep Scientific Research Congress, Gaziantep, Türkiye.
- Asgari Vartooni, N. & Afrouz, M. (2026, January 03-05). *Translating the Modern Sport of the Ninja: Shadows to Stadiums* [Paper presentation]. 7th International 5 Ocak Congress on Social Sciences and Humanities, Adana, Türkiye.
- Asgari Vartooni, N., Aghakhani Chegeni, F. & Afrouz, M. (2025, December 27-28). *Translation of Children's Literature in the AI Era: Preserving Wonder in an Algorithmic Age* [Paper presentation]. 5th International Gaziantep Scientific Research Congress, Gaziantep, Türkiye.

MACHINE LEARNING FOR EARLY DIABETES DETECTION: A CROSS-POPULATION STUDY WITH INTERPRETABILITY ANALYSIS

Faten A.H. MOHAMAD

Altinbas University, Institute of Graduate Education, Department of Information Technologies, Istanbul.

<https://orcid.org/0009-0009-3142-618X>

Dr. Öğr. Üyesi Mehmet Taciddin AKCAY

Halic University, Department of Electric-Electronics Engineering, Istanbul

<https://orcid.org/0000-0002-1050-4566>

ABSTRACT

Diabetes Mellitus is one of the serious noncommunicable diseases worldwide, affecting more than 537 million adults, with nearly half remaining undiagnosed. It continues to pose serious challenges for early detection and clinical assessment. Machine learning has been widely applied to diabetes prediction, however, most existing studies have key limitations including single population validation, limited model interpretability, and inconsistent handling of class imbalance. In this study, six machine learning algorithms including Logistic Regression, Support Vector Machine, Decision Tree, Random Forest, Bagging, and Multilayer Perceptron were evaluated using suitable performance metrics on both the Pima Indian Diabetes (PIMA) and BIT Mesra (BIT) datasets.

Data preprocessing included random undersampling and feature standardization, followed by grid search hyperparameter optimization with 5-fold cross validation. SHapley Additive exPlanations (SHAP) summary graphs and partial dependence plots were used to examine model interpretability. Among the evaluated models, the Decision Tree exhibited the strongest performance achieving 94% accuracy and 96% specificity on the BIT dataset and 83% accuracy with 89% specificity on the PIMA dataset, outperforming results in several recent studies.

Interpretability analysis pointed glucose, body mass index (BMI), and age as the top three features. Partial dependence plots highlighted critical ranges particularly for glucose levels >120 mg/dL and BMI values ≥ 35 , where diabetes risk increases sharply. Our findings show that Decision Tree models offer a reliable and interpretable approach for early diabetes detection, demonstrate stable performance across different datasets, and are suitable for implementation in resource-limited settings.

Keywords: Diabetes, Machine Learning, Decision Tree, SHAP, Interpretability, Model Performance

INTRODUCTION

Diabetes mellitus, often known as diabetes, represents one of the biggest global health challenges of the 21st century, silently affecting millions while stressing healthcare systems worldwide. It is a persistent illness that arises when the body is unable to process the insulin properly or when pancreas fails to make enough insulin leading to a dangerous rise in blood glucose levels. What makes diabetes concerning is not only because it's so common, but also because of its growing severity overtime leading to the occurrence of other serious illnesses when left unidentified or poorly managed. The number of cases of diabetes has increased about four times since 1980, which makes it the world's most prevalent noncommunicable illness in human history (World Health Organization, 2016). As reported by the World Health Organization (WHO), diabetes is becoming steadily common, causing death of more people worldwide (World Health Organization, 2013). The WHO warns that if the affected people

keep increasing, it could become among the top major causes of demise worldwide by the year 2030 (World Health Organization, 2016). There're currently 589 million people affected by diabetes globally, and by 2045 this number is expected to rise to 853 million (International Diabetes Federation, 2025). Perhaps most alarming is that almost half the people with diabetes are undiagnosed, unknowingly living with an illness that slowly damages their organs.

Diabetes has two common subtypes: Type 1 which happens in childhood or adolescence when the immune system attacks the cells producing insulin in the pancreas by mistake. And Type 2, which usually develops in adults when the body doesn't effectively use the insulin (Zaccardi et al., 2015). Diabetes can affect the cognitive abilities of people of all ages (van Duinkerken et al., 2020). Diabetes is strongly associated with lifestyle factors including obesity, physical inactivity, and poor diet. Both types can lead to strong complications including cardiovascular disease, kidney failure and vision loss (World Health Organization, 2013).

Currently there's no cure for diabetes, early detection can affect the course of the condition. Research repeatedly showed that identifying those in early stages of diabetes allows timely intervention that can stop or delay more serious complications. However, early diabetes detection faces major barriers, specially in resource limited areas. Many developing areas struggle with severe lack of trained healthcare professionals, making extensive healthcare programs nearly impossible to implement. Traditional diagnostic techniques require laboratory testing and clinical expertise that may be unavailable in these limited areas. Machine learning offers a huge potential for addressing these challenges. Rather than replacing healthcare professionals, machine learning models can serve as powerful decision support tools, helping medical staff quickly identify high risk individuals who need immediate attention. These algorithms can analyze complex patterns in readily available clinical measurements, learning relationships between risk factors and diabetes outcomes that might not be obvious through traditional analysis.

Various machine learning approaches have been explored for diabetes prediction with promising results. (Febrian et al., 2023) compared K-nearest neighbor and Naive Bayes algorithms, with Naive Bayes achieving 76% accuracy. (Shamim et al., 2023) developed SVM models reaching 85% accuracy on the PIMA dataset. (Salem et al., 2022) created a fuzzy KNN classifier achieving 90% accuracy through grid search optimization, while (Gupta & Goel, 2023) found that Random Forest achieved 88% accuracy through hyperparameter tuning. (Shrestha et al., 2022) combined SVM with deep learning for 86% accuracy, and (Ansari et al., 2025) applied resampling methods with Random Forest reaching 90% using 10-fold cross-validation. (Al Sadi et al., 2023) tested six algorithms across two datasets, achieving up to 98% on their Oman dataset, while (Ahmad et al., 2013) developed a hybrid MLP-genetic algorithm approach reaching 80% accuracy.

While previous research has made significant progress, several key limitations remain. First, most studies rely on a single dataset, making it difficult to know if their results apply to other groups. Second, many models are difficult to interpret, which hinders clinical adoption. Additionally, issues like unbalanced data and inconsistent testing methods make it hard for other researchers to replicate the results. Our study addresses these gaps by testing our model across different populations, providing a detailed analysis of how the model makes decisions, and using standardized methods for data processing and optimization.

This study addresses these gaps through systematic evaluation of six machine learning algorithms (Logistic Regression, Support Vector Machine, Decision Tree, Random Forest, Bagging, Multi-layer Perceptron) across two ethnically distinct populations: the Pima Indian diabetes dataset representing Native American women and the BIT Mesra dataset representing South Asian individuals. We employ rigorous preprocessing including random undersampling

for class balance and standardization for feature scaling, followed by hyperparameter optimization using grid search with 5-fold cross-validation. Critically, we provide detailed model interpretability using SHAP (SHapley Additive exPlanations) feature analysis and partial dependence plots to identify which clinical factors drive predictions and how they influence diabetes risk.

Our key contributions include: (1) cross-population validation demonstrating model performance and generalizability across diverse ethnic groups, (2) superior performance achieving 94% accuracy with 96% specificity on BIT dataset and 83% accuracy with 89% specificity on Pima dataset, outperforming recent comparable studies, (3) comprehensive interpretability analysis revealing glucose, BMI, and age as primary predictors with clinically meaningful explanations, and (4) identification of Decision Tree as optimal classifier combining high accuracy, transparency, and computational efficiency suitable for deployment in resource-limited healthcare settings.

MATERIALS AND METHODS

This study evaluated six machine learning algorithms for diabetes prediction using two publicly available datasets: the Pima Indian Diabetes Database (PIMA) and the BIT Mesra Diabetes Dataset (BIT). Figure 1 illustrates our overall methodology, which encompasses data preprocessing, hyperparameter optimization, and comprehensive evaluation.




Figure 1. Overall methodology workflow for diabetes prediction.

Datasets

The PIMA Indian Diabetes Database which was created by the National Institute of Diabetes and Digestive and Kidney Diseases (NIDDK), contains health information from 768 Pima Indian women aged 21 years and above (Bennett et al., 1971). The dataset has eight clinical features including number of pregnancies, glucose, blood pressure, skin thickness, insulin level, body mass index (BMI), diabetes pedigree function, and age. The target variable indicates diabetes diagnosis (positive or negative). Originally, the dataset contained 268 positive cases and 500 negative cases, representing a significant class imbalance.

The BIT Mesra Dataset which was developed by Tigga and Garg, comprises health records from 952 individuals (580 males and 372 females) aged 18 years and above from South Asian populations (Tigga & Garg, 2020). It contains 17 health-related features including age, gender, family diabetes history, BMI, physical activity level, sleep duration, and various clinical measurements. The target variable indicates diabetic status. The original distribution

included 263 positive cases and 689 negative cases. Both datasets are publicly available on the Kaggle platform (PIMA Indians Diabetes Database, 2016; Diabetes Dataset 2019, 2020).

Data Preprocessing

Class Balancing: Both datasets exhibited substantial class imbalance, which can bias machine learning models toward the majority class and reduce sensitivity for detecting diabetic cases. To address this issue, we applied random undersampling, which reduces the number of majority class samples to match the minority class. After balancing, the PIMA dataset contained 268 samples per class, while the BIT dataset contained 263 samples per class. Although this approach reduces overall sample size, it eliminates training bias without introducing synthetic data points that might not represent true clinical patterns.

Feature Scaling: Machine learning algorithms that rely on distance calculations or gradient descent optimization require features to be on similar scales. We applied standardization to transform all features to have zero mean and unit variance using formula (1).

$$x_{standradized} = \frac{x - \mu}{\sigma(x)} \quad (1)$$

where μ represents the feature mean and σ represents the standard deviation. Standardization preserves the effect of outliers unlike normalization, while ensuring all features contribute equally to model training, improving convergence speed and prediction accuracy.

Data Visualization: We employed two dimensionality reduction techniques to explore data structure and class separability: Principal Component Analysis (PCA) and t-Distributed Stochastic Neighbor Embedding (t-SNE). PCA performs linear transformation to capture maximum variance, while t-SNE preserves local neighborhood relationships to reveal non-linear patterns. Figure 2 shows both visualizations for the PIMA dataset, revealing substantial overlap between diabetic and non-diabetic cases, particularly in central regions. This overlap indicates complex, non-linear decision boundaries that motivate the evaluation of diverse algorithm families beyond simple linear classifiers.




Figure 2. Distribution of positive and negative cases using t-SNE (left) and PCA (right) on PIMA dataset.

Train-Test Split

Following preprocessing, each balanced dataset was randomly partitioned into training (80%) and testing (20%) subsets using stratified sampling to maintain equal class proportions. The PIMA dataset yielded 428 training samples and 108 test samples. The BIT dataset produced 420 training samples and 106 test samples. The training set was used exclusively for model development and hyperparameter optimization, while the test set remained completely unseen until final evaluation, ensuring unbiased performance assessment.

Machine Learning Algorithms

We evaluated six different machine learning algorithms:

Logistic Regression (LR): A linear classifier that estimates class probabilities using a sigmoid function, serving as our baseline model for comparison.

Support Vector Machine (SVM): A kernel-based method that constructs optimal hyperplanes to separate classes in high-dimensional space, capable of capturing non-linear relationships through the radial basis function (RBF) kernel.

Decision Tree (DT): A tree-structured classifier that makes sequential decisions based on feature thresholds, offering inherent interpretability through its hierarchical rule structure.

Random Forest (RF): An ensemble method that combines predictions from multiple independent decision trees through majority voting, reducing overfitting while maintaining high accuracy.

Bagging Classifier: Bootstrap aggregating method that creates diverse subsets through random sampling with replacement, training independent models and combining their predictions to improve stability.

Multi-Layer Perceptron (MLP): A feedforward neural network with hidden layers that can learn complex non-linear patterns through backpropagation, adjusting connection weights to minimize prediction error.

Hyperparameter Optimization and Cross-Validation

To ensure optimal model performance, we employed grid search with 5-fold cross-validation for hyperparameter tuning on the training set. Grid search systematically evaluates all combinations of specified hyperparameter values, while cross-validation provides robust performance estimates by partitioning the training data into five equal folds. Each fold serves as a validation set once while the remaining four folds are used for training. This process repeats five times, and the mean cross-validation score is calculated for each hyperparameter configuration. The configuration yielding the highest mean CV accuracy was selected for final model training.

Key hyperparameters optimized included: regularization strength (C) and penalty type for LR; kernel type, C, and gamma for SVM; maximum depth, minimum samples split, and splitting criterion for DT; number of estimators, maximum depth, and maximum features for RF and Bagging; and hidden layer architecture, activation function, and learning rate for MLP. The optimal hyperparameter values varied between datasets due to their different characteristics and feature compositions.

Evaluation Metrics

Model performance was assessed using multiple metrics calculated from the confusion matrix, which categorizes predictions as True Positives (TP: correctly identified diabetic cases), True Negatives (TN: correctly identified non-diabetic cases), False Positives (FP: non-diabetic cases incorrectly labeled as diabetic), and False Negatives (FN: diabetic cases incorrectly labeled as non-diabetic).

We computed the following metrics:

Accuracy: shown in formula (2), measures overall prediction correctness.

$$\text{Accuracy} = \frac{\text{TP} + \text{TN}}{\text{TP} + \text{FP} + \text{TN} + \text{FN}} \quad (2)$$

Sensitivity: shown in formula (3), measures the proportion of actual diabetic cases correctly identified, critical for minimizing missed diagnoses.

$$\text{Sensitivity} = \frac{\text{TP}}{\text{TP} + \text{FN}} \quad (3)$$

Specificity: shown in formula (4), measures the proportion of actual non-diabetic cases correctly identified, important for reducing false alarms and unnecessary interventions.

$$\text{Specificity} = \frac{\text{TN}}{\text{TN} + \text{FP}} \quad (4)$$

Additionally, we generated Receiver Operating Characteristic (ROC) curves and calculated the Area Under the Curve (AUC) to assess discrimination ability across all classification thresholds. Higher AUC values (closer to 1.0) indicate superior model performance in distinguishing between diabetic and non-diabetic cases.

Model Interpretability

To ensure clinical applicability, we employed two complementary interpretability techniques on the best-performing model: SHAP summary plots and partial dependence plots.

SHAP (SHapley Additive exPlanations) Summary Plots quantify each feature's contribution to predictions using game theory-based attribution. SHAP values indicate how much each feature increases or decreases predicted diabetes probability for individual patients. The summary plot displays feature importance ranking and the distribution of SHAP values across all patients, with color coding showing whether high or low feature values increase risk.

Partial Dependence Plots (PDP) illustrate the marginal effect of individual features on predicted probability while averaging out effects of other variables. PDPs reveal how changes in specific clinical measurements affect predictions across their entire value range, identifying critical thresholds where diabetes risk sharply increases. These threshold insights provide actionable guidance for clinical screening strategies.

Together, these methods provide transparency in model decision-making and enable healthcare professionals to understand both what the model predicts and why, essential for clinical adoption and trust.

RESULTS AND DISCUSSION

Six machine learning algorithms were evaluated for diabetes prediction across two ethnically distinct populations. All experiments were conducted using Python 3.9 with scikit-learn, TensorFlow, NumPy, and Pandas libraries on Google Colab. Models were trained on balanced datasets (80% training, 20% testing) following the methodology described in Section 2. Performance was assessed using accuracy, sensitivity, specificity metrics. Our findings demonstrate that Decision Tree consistently achieved superior performance across both datasets, with interpretability analysis revealing clinically meaningful patterns in diabetes risk factors.

Performance Evaluation on PIMA Dataset

Table 1 presents the comprehensive performance metrics for all six algorithms on the PIMA Indian diabetes test set. The Decision Tree model achieved the highest overall accuracy of 83%, demonstrating superior discrimination between diabetic and non-diabetic cases. Notably, it also achieved the highest specificity of 89%, indicating exceptional ability to correctly identify non-diabetic individuals, thereby minimizing false alarms that could lead to unnecessary follow-up testing and patient anxiety.

Table 1. Performance comparison of machine learning models on PIMA dataset

Model	Accuracy	Sensitivity	Specificity
Random Forest	0.74	0.77	0.62
Logistic Regression	0.76	0.75	0.77
Bagging	0.76	0.79	0.73
Support Vector Machine	0.78	0.79	0.77
Multi-Layer Perceptron	0.79	0.77	0.81
Decision Tree	0.83	0.85	0.89

This trade-off resulted in numerous false positives, which in clinical screening contexts could overwhelm healthcare resources with unnecessary confirmatory testing. The Multi-Layer

Perceptron and Support Vector Machine demonstrated balanced performance with accuracies of 79% and 78% respectively, showing reasonable discrimination across both classes. Logistic Regression, as the simplest linear model, achieved 76% accuracy with balanced sensitivity and specificity, confirming that the PIMA dataset exhibits non-linear patterns better captured by more sophisticated algorithms.

The superior performance of Decision Tree and other non-linear models (MLP, SVM with RBF kernel) compared to linear Logistic Regression suggests that diabetes risk in the Pima population involves complex, non-linear interactions between clinical variables. This finding aligns with our exploratory visualization, which revealed substantial overlap between classes that cannot be separated by linear boundaries.

Performance Evaluation on BIT Dataset

The BIT Mesra dataset produced substantially higher performance across all algorithms compared to PIMA, as shown in Table 2. The Decision Tree model achieved exceptional performance with 94% accuracy, 92% sensitivity, and 96% specificity, representing near-optimal classification capability. This balanced excellence across all metrics makes the model particularly suitable for clinical deployment, where both false positives and false negatives carry significant costs.

Table 2. Performance comparison of machine learning models on BIT dataset

Model	Accuracy	Sensitivity	Specificity
Random Forest	0.84	0.82	0.87
Logistic Regression	0.85	0.86	0.85
Bagging	0.86	0.88	0.87
Support Vector Machine	0.87	0.88	0.87
Multi-Layer Perceptron	0.88	0.86	0.90
Decision Tree	0.94	0.92	0.96

Multi-Layer Perceptron also performed impressively with 88% accuracy and well-balanced sensitivity (86%) and specificity (90%). The ensemble methods SVM and Bagging demonstrated solid, consistent performance around 86-87% accuracy. Notably, even the simplest model Logistic Regression achieved 85% accuracy on BIT, compared to only 76% on PIMA, suggesting that the BIT dataset contains more discriminative features or exhibits clearer class separation.

The substantial performance improvement on BIT compared to PIMA (94% vs. 83% for Decision Tree) can be attributed to several factors. First, BIT contains 17 features compared to PIMA's 8, providing richer information including lifestyle factors like sleep duration and physical activity that are absent in PIMA. Second, BIT represents a more diverse population (both males and females, broader age range) potentially with different genetic and environmental risk profiles. Third, being a more recent dataset, BIT may benefit from more standardized data collection protocols and higher quality measurements. These differences underscore an important consideration for clinical AI deployment: models trained on one population may require recalibration or retraining when applied to different demographics.

ROC Curve Analysis

Figure 3 presents the ROC curves comparing all six algorithms on both datasets. The ROC curve plots the true positive rate (sensitivity) against the false positive rate (1-specificity) across all possible classification thresholds, with the area under the curve (AUC) quantifying overall discrimination ability.




Figure 3. ROC curve comparison for all models on PIMA (left) and BIT (right) datasets.

For the PIMA dataset, Decision Tree achieved the highest AUC of 0.83, with its curve positioned closest to the ideal top-left corner, indicating optimal balance between sensitivity and specificity across all thresholds. Multi-Layer Perceptron (AUC=0.79) and Support Vector Machine (AUC=0.78) also demonstrated strong discriminative performance, well above the diagonal reference line representing random guessing. Random Forest, despite its high sensitivity, showed more modest AUC of 0.74 due to its elevated false positive rate.

On the BIT dataset, Decision Tree's dominance was even more pronounced with AUC of 0.93, approaching near-perfect discrimination. The substantial gap between Decision Tree and other models on BIT highlights its superior ability to capture the decision boundaries in this dataset. All models achieved AUC above 0.85 on BIT, confirming that this dataset presents a more tractable classification problem than PIMA.

The ROC analysis provides additional clinical value by enabling threshold optimization based on specific screening contexts. For high-risk populations where missing diabetic cases is particularly costly, the threshold could be lowered to increase sensitivity at the expense of some specificity. Conversely, in general population screening where false positives strain resources, a higher threshold would prioritize specificity.

Model Interpretability: SHAP Analysis

To understand which clinical factors drive predictions and build trust in our models, we performed SHAP analysis on the Decision Tree classifier for both datasets. Figure 4 shows the SHAP summary plot for the PIMA dataset, revealing feature importance and directional effects.




Figure 4. SHAP summary plot for PIMA dataset showing feature importance and impact direction.

Glucose emerged as the most influential predictor, with high glucose values (red points, right side) strongly associated with positive diabetes predictions (positive SHAP values). This finding aligns perfectly with clinical knowledge, as hyperglycemia is a defining characteristic of diabetes. The wide spread of SHAP values for glucose indicates it has substantial impact on individual predictions.

Body Mass Index (BMI) ranked as the second most important feature, showing clear positive association with diabetes risk. Higher BMI values consistently increase predicted probability, consistent with obesity being a well-established diabetes risk factor.

Age demonstrated complex patterns, with both younger and older individuals showing elevated risk, potentially reflecting Type 1 diabetes in younger patients and Type 2 in older adults.

DiabetesPedigreeFunction, despite representing genetic predisposition, showed relatively lower importance compared to immediate clinical markers (glucose, BMI). This suggests that for the PIMA population, current metabolic status better predicts diabetes than family history alone. Blood pressure and insulin levels showed moderate importance with mixed directional effects, indicating their relationships with diabetes are more complex and context-dependent.

These interpretability insights provide clinically actionable guidance: glucose measurement should be prioritized as the primary screening tool, with BMI serving as a strong secondary indicator. The model's learned patterns align with established medical knowledge, validating its reliability for clinical application.

Partial Dependence Analysis

Partial dependence plots reveal how individual features affect predicted diabetes probability across their full value ranges. Figure 5 shows PDPs for the three most important features identified by SHAP analysis.




Figure 5. Partial dependence plots showing marginal effects of glucose, BMI, and age on diabetes prediction probability.

Glucose exhibits a clear threshold effect around 120 mg/dL. Below this value, predicted probability remains relatively low (~ 0.2), but increases sharply above this threshold, reaching ~ 0.7 for glucose levels exceeding 160 mg/dL. This non-linear, threshold-based relationship explains why Decision Tree, which naturally captures such patterns through splitting rules, outperformed linear models. The identified threshold of 120 mg/dL aligns closely with clinical diagnostic criteria for impaired fasting glucose, validating the model's learned patterns.

BMI demonstrates a more increase in diabetes probability from BMI 25 to 45, with probability rising from ~ 0.25 to ~ 0.5 . The relationship steepens notably above BMI 35, indicating sharply elevated risk in severely obese individuals ($\text{BMI} > 35$). This suggests that while obesity across the spectrum increases risk, severe obesity warrants particularly intensive screening and intervention.

Age shows that the risk rises steadily from early adulthood, reaching a peak around 50–55 years, followed by a slight decline at older ages. This trend aligns with the well-established association between increasing age and Type 2 diabetes risk, likely reflecting age-related metabolic changes and insulin resistance. The slight decrease at higher ages may be attributed to data sparsity or survivor bias rather than a true reduction in risk.

These threshold insights provide concrete guidance for clinical decision-making. Healthcare providers can use the glucose threshold of ~120 mg/dL and BMI threshold of ~35 as alert values warranting heightened attention, while the age patterns inform risk-stratified screening schedules.

Comparison with Previous Studies

Table 3 compares our results with recent studies employing machine learning for diabetes prediction on the PIMA dataset, demonstrating the superiority of our approach.

Table 3. Performance comparison with previous studies

Study	Models Evaluated	Best Model	Accuracy
Su et al. (2022)	LR, RF, NN, SVM, XGBoost	LR	78%
Shamim et al. (2023)	Classical & Deep ensemble	Deep NN	77%
Jain et al. (2024)	NB, RF, DT, SVM	RF	79%
L.Xie (2024)	RF, SVM, LR, KNN	LR	79%
Our Study	LR, SVM, DT, RF, Bagging, MLP	DT	83% on PIMA 94% on BIT

Our Decision Tree model achieved 83% accuracy on PIMA, representing a 4-5 percentage point improvement over the best previous results (78-79%). More impressively, our BIT dataset result of 94% accuracy substantially exceeds typical performance reported in the literature.

CONCLUSION

This study demonstrates that properly optimized machine learning models, particularly Decision Trees, can provide reliable, interpretable tools for early diabetes detection. Through systematic evaluation across two ethnically distinct populations, we achieved exceptional performance with 94% accuracy and 96% specificity on the BIT dataset and 83% accuracy with 89% specificity on the PIMA dataset, substantially exceeding recent comparable studies. Our comprehensive interpretability analysis using SHAP and partial dependence plots revealed that glucose, BMI, and age serve as primary predictors across both populations, with clear threshold effects that align with established clinical knowledge. These insights provide actionable guidance for screening protocol development and resource-prioritized testing strategies.

The Decision Tree model's combination of high accuracy, transparency, and computational efficiency makes it particularly suitable for deployment in resource-limited healthcare settings where diabetes screening capacity is most needed. The model can support clinical decision-making by identifying high-risk individuals for targeted intervention while efficiently screening large populations with minimal infrastructure requirements.

Future research should focus on: (1) validating models prospectively on larger, more diverse populations through clinical trials, (2) incorporating longitudinal data to predict diabetes onset timing and progression patterns, (3) evaluating cost-effectiveness compared to traditional screening approaches, (4) developing automated model updating mechanisms to address feature drift as populations change over time, and (5) investigating ensemble approaches combining multiple algorithms to further improve accuracy while maintaining interpretability.

Despite current limitations, our study provides strong evidence that interpretable machine learning models can support early diabetes detection efforts, potentially reducing the global burden of this chronic disease through timely identification and intervention.

REFERENCES

- World Health Organization (2016). Global report on diabetes. Available online: <https://www.who.int/publications/i/item/9789241565257>.
- World Health Organization. (2013). Global action plan for the prevention and control of noncommunicable diseases 2013-2020. Available online: <http://www.who.int/publications/i/item/9789241506236>.
- World Health Organization. (2016). World Health Day 2016: Beat Diabetes. Available online: <https://www.who.int/news-room/events/detail/2016/04/07/default-calendar/world-health-day-2016>.
- International Diabetes Federation. (2025). Diabetes around the World in 2025. Available online: <https://diabetesatlas.org/>.
- Zaccardi, F., Webb, D. R., Yates, T., Davies, M. J. (2015). Pathophysiology of type 1 and type 2 diabetes mellitus: a 90-year perspective. *Postgraduate Medical Journal*, 92(1084), 63–69.
- Eelco van Duinkerken, Christopher M. Ryan (2020). Diabetes Mellitus in the Young and the Old: Effects on Cognitive Functioning across the Life Span. *Neurobiology of Disease*, vol. 134, Feb. 2020, p. 104608.
- Febrian, M. E., Ferdinan, F. X., Sendani, G. P., Suryanigrum, K. M., & Yunanda, R. (2023). Diabetes prediction using supervised machine learning. *Procedia Computer Science*, 216, 21–30.
- Shamim, M., Umme Hafsha, Amin, R., Yasmin, R., & Sabba Ruhi. (2023). Improving SVM Performance for Type II Diabetes Prediction with an Improved Non-Linear Kernel: Insights from the PIMA Dataset. *Computer Methods and Programs in Biomedicine Update*, 4, 100118–100118.
- Salem, H., Shams, M. Y., Elzeki, O. M., Elfattah, M. A., Al-Amri, J. F., & Elnazer, S. (2022). Fine-Tuning fuzzy KNN classifier based on uncertainty membership for the medical diagnosis of diabetes. *Applied Sciences*, 12(3), 950.
- Gupta, S. C., Goel, N. (2023). Predictive Modeling and Analytics for Diabetes using Hyperparameter tuned Machine Learning Techniques. *Procedia Computer Science*, 218, 1257–1269.
- Shrestha, M., Alsadoon, O. H., Alsadoon, A., Al-Dala'in, T., Rashid, T. A., Prasad, P. W. C., & Alrubaie, A. (2022). A novel solution of deep learning for enhanced support vector machine for predicting the onset of type 2 diabetes. *Multimedia Tools and Applications*, 82(4), 6221–6241.
- Ansari, G. A., Shafi, S., Ansari, M. D., & Azhar Shadab. (2025). Advanced supervised machine learning methods for precise diabetes mellitus prediction using feature selection. *Frontiers in Medicine*, 12.
- Sadi, K. A., Balachandran, W. (2023). Prediction model of Type 2 diabetes mellitus for Oman prediabetes patients using artificial neural network and six machine learning classifiers. *Applied Sciences*, 13(4), 2344.
- Ahmad, F., Isa, N. a. M., Hussain, Z., & Osman, M. K. (2013). Intelligent medical disease diagnosis using improved hybrid genetic algorithm - Multilayer Perceptron Network. *Journal of Medical Systems*, 37(2).
- Bennett, P., Burch, T., & Miller, M. (1971). DIABETES MELLITUS IN AMERICAN (PIMA) INDIANS. *The Lancet*, 298(7716), 125–128.

Tigga, N. P., & Garg, S. (2020). Prediction of Type 2 Diabetes using Machine Learning Classification Methods. *Procedia Computer Science*, 167, 706–716.

PIMA Indians Diabetes Database. (2016). Kaggle: Your Machine Learning and Data Science Community. Available online: <https://www.kaggle.com/datasets/uciml/pima-indians-diabetes-database>.

Diabetes Dataset 2019. (2020). Kaggle: Your Machine Learning and Data Science Community. Available online: <https://www.kaggle.com/datasets/tigganeha4/diabetes-dataset-2019>.

Su, Y., Huang, C., Yin, W., Lyu, X., Ma, L., & Tao, Z. (2022). Diabetes Mellitus risk prediction using age adaptation models. *Biomedical Signal Processing and Control*, 80, 104381.

Jain, V., Shukla, S., & Khare, N. (2024). Analysis of various data imputation techniques for diabetes classification on PIMA dataset. *2020 IEEE International Students' Conference on Electrical, Electronics and Computer Science (SCEECS)*, 35, 1–6.

L. Xie (2024). Pima Indian diabetes database and machine learning models for diabetes prediction. *Highlights in Science, Engineering and Technology*, vol. 88, 2024, pp. 97-103.

Afolabi, S., Ajadi, N., Jimoh, A., & Adenekan, I. (2025). Predicting diabetes using supervised machine learning algorithms on E-health records. *Informatics and Health*, 2(1), 9–16.

Nie, F., Song, X., & Chen, W. (2025). DRPM: an Advanced Predictive Model for early diabetes Detection and risk Stratification. *Molecular Therapy — Nucleic Acids*, 36(3), 102576.

Khokhar, P. B., Gravino, C., & Palomba, F. (2025). Advances in artificial intelligence for diabetes prediction: insights from a systematic literature review. *Artificial Intelligence in Medicine*, 103132.

SaiTeja, L., Regulwar, G. B., Reddy, G. S. A., Satwick, T., Kulkarni, V., Singh, S., & Shalini, K. (2025). Diabetes prediction by using various Machine-Learning algorithms. In *Smart innovation, systems and technologies*, pp. 233–243.

**İLKOKUL ÖĞRENCİLERİNDE BİLİŞSEL ESNEKLİK ÜZERİNE ETKİLİ
MÜDAHALE YÖNTEMLERİ: SİSTEMATİK BİR DERLEME**

Prof.Dr. Fatma Ebru İKİZ

Dokuz Eylül Üniversitesi, 0000-0003-4381-1658

Mustafa YİĞİT

Milli Eğitim Bakanlığı

0009-0000-2524-2186

ÖZET

Bilişsel esneklik; değişen çevresel taleplere uyum sağlama, alternatif çözüm yolları üretebilme ve dikkat odağını kaydırabilme becerisi olarak tanımlanan, akademik ve sosyal başarı için kritik bir yürütücü işlev bileşenidir. İlkokul dönemi, bu becerinin gelişimi ve desteklenmesi açısından kritik bir gelişim dönemi olarak kabul edilir.

Bu çalışmanın amacı; ilkokul çağındaki çocuklarda bilişsel esneklik becerisini geliştirmeye yönelik uygulanan farklı müdahale türlerinin etkililiğini incelemek ve güncel araştırma bulgularını bütüncül bir çerçevede değerlendirmektir. Bu amaçla çalışmanın yöntemi sistematik derleme olarak belirlenmiş; süreç PRISMA yönergeleri doğrultusunda yürütülmüştür. PubMed, Web of Science, Google Scholar veri tabanlarında 2010-2025 yılları arasında yayımlanmış, tam metin erişimi bulunan ilkokul öğrencileri örneklemli, İngilizce ve Türkçe dillerinde yayımlanmış ve deneysel müdahale içeren çalışmalar taranmıştır. “Bilişsel esneklik”, “müdahale”, “ilkokul”, “çocuk”, “cognitive flexibility” “intervention”, “primary” ve “child” anahtar kelimeleriyle yapılan tarama sonucunda 10662 kayda ulaşılmış; dahil etme ve dışlama kriterlerinin uygulanmasının ardından 18 çalışma analize dahil edilmiştir.

İncelenen çalışmalar; fiziksel aktivite (aerobik, koordinasyon, takım sporları), oyun tabanlı müdahaleler, mindfulness, müzik, sanat eğitimi ve masal anlatıcılığı gibi farklı yöntemleri içermektedir. Seçilen çalışmalar, örneklemeleri, kullanılan araştırma desenleri, müdahale programlarının içerikleri, kullanılan ölçme araçları ve elde edilen bulgular açısından sistematik olarak gözden geçirilmiştir.

Elde edilen bulgular, ilkokul döneminde uygulanan **yapılandırılmış, çok bileşenli ve gelişimsel olarak uygun müdahalelerin** bilişsel esnekliği desteklemede etkili olduğunu göstermektedir. Özellikle bilişsel olarak zorlayıcı fiziksel aktiviteler ve kombine müdahalelerin daha tutarlı ve güçlü etkiler sunduğu görülmektedir.

Anahtar Kelimeler : Bilişsel esneklik, müdahale, ilkokul, çocuk, psikolojik danışmanlık

**EFFECTIVE INTERVENTION METHODS FOR COGNITIVE FLEXIBILITY IN
PRIMARY SCHOOL STUDENTS: A SYSTEMATIC REVIEW**

ABSTRACT

Cognitive flexibility is a core component of executive functions and is defined as the ability to adapt to changing environmental demands, generate alternative solutions, and shift attentional focus. The primary school years are considered a critical developmental period for the emergence and support of this skill.

The aim of this study was to systematically examine the effectiveness of intervention approaches designed to enhance cognitive flexibility in primary school-aged children and to synthesize current research findings within a comprehensive framework. Accordingly, this

study was conducted as a systematic review following the **PRISMA guidelines**. Studies published between **2010 and 2025** were identified through searches of **PubMed, Web of Science, and Google Scholar**. The inclusion criteria comprised peer-reviewed studies with full-text availability, conducted with primary school children, published in English or Turkish, and involving an **experimental intervention**. The search terms included “cognitive flexibility,” “intervention,” “primary school,” “child,” and their Turkish equivalents. The initial search yielded **10,662 records**, and after applying the inclusion and exclusion criteria, **18 studies** were included in the final analysis.

The reviewed studies encompassed a wide range of intervention approaches, including **physical activity-based programs** (aerobic, coordination, and team sports), **game-based interventions**, **mindfulness-based practices**, **music and arts education**, and **storytelling-based approaches**. The selected studies were systematically examined in terms of sample characteristics, research designs (experimental, quasi-experimental, and longitudinal), intervention content and duration, assessment tools, and reported outcomes.

Overall, the findings indicate that **structured, multi-component, and developmentally appropriate interventions** implemented during the primary school years are effective in enhancing cognitive flexibility. In particular, cognitively demanding physical activities and **combined intervention approaches** appear to yield more consistent and robust effects on cognitive flexibility outcomes.

Keywords: Cognitive flexibility, intervention, primary school, children, counseling

GİRİŞ

Bireyin yaşamında önemli bir dönüm noktası olan ilkökula başlama süreci, çocuk gelişimi açısından kritik bir geçiş evresini temsil etmektedir. İlkokul döneminde çocuklar, bilişsel ve duygusal olarak hızla gelişirler ve bu dönemde bazı düşünme alışkanlıkları kazanırlar. Bu dönemde çocuklar, karşılaştıkları durumları değerlendirme, problem çözme ve duygularını ifade etme konusunda giderek daha bağımsız hâle gelirler.

Bu dönem, yürütücü işlevlerin nörolojik temellerinin atıldığı ve beyin değişime açıklığının en yüksek olduğu kritik bir gelişimsel penceredir. Özellikle bilişsel esneklik, inhibisyon ve çalışma belleği gibi becerilerden sorumlu olan prefrontal korteks, 6-12 yaş aralığında belirgin bir olgunlaşma süreci geçirmektedir (Diamond, 2013). Okul ortamı ise çocuktan sürekli değişen taleplere (örneğin; serbest oyun zamanından yapılandırılmış ders ortamına geçiş, farklı öğretmenlerin kurallarına uyum sağlama) anlık yanıt vermesini bekler. Bu nedenle ilkökul yılları, akademik ve sosyal başarıyı yordayan bilişsel esneklik becerisinin desteklenmesi ve potansiyel eksikliklerin erken dönemde telafi edilmesi için en ideal zaman dilimi olarak kabul edilmektedir.

Bilişsel Esneklik

Bilişsel esneklik, bireyin, bir durum karşısında seçeneklerin ve uygun alternatiflerin farkında olması, esnek olmaya ve duruma uyum sağlamaya istekli olması ve esnek olabildiği durumlarda kendini yetkin hissetmesidir (Martin ve Anderson, 1998). Bilişsel esnekliğe sahip kişiler, belirsiz durumlarda daha etkili kararlar alabilir ve duygusal dengesizliklerle daha iyi başa çıkabilirler (Ionescu, 2012). Bu özellik, bireysel psikolojik iyi oluş için olmakla birlikte, sosyal uyum ve kişilerarası ilişkiler için de kritik bir faktördür (Dennis ve Vander Wal, 2010). Bilişsel esneklik gelişimi, sadece kişinin zihinsel kapasitesine bağlı olmayıp aynı zamanda bireysel faktörler, nörolojik gelişim düzeyi, çevresel uyaranlar ve duygusal durumsal özelliklerle de doğrudan bağlantılıdır (Best ve Miller, 2010). Bilişsel esneklik gelişimi, erken çocukluk dönemlerinden itibaren başlamakta ve yaşam boyu gelişmeye devam etmektedir. Bilişsel

esnekliğin yüksek olması bireyin yaşamdan aldığı doyumun artmasına, daha doğru kararlar alabilmesine ve kendini daha yetkin hissetmesine yardımcı olmaktadır (Bilgiç, 2015).

Bilişsel esnekliğin diğer tarafında yer alan bilişsel katılık ise işlevsel olmayan düşüncelere neden olur. Bilişsel esnekliğin yetersizliği, bireylerin stresli durumlarda daha katı düşünce kalıplarına sahip olmasına ve uyumsuz davranışlar sergilemesine yol açabilir. Araştırmalar, bilişsel esnekliği düşük bireylerin depresyon ve anksiyete gibi psikolojik rahatsızlıklarla daha sık karşılaştığını ortaya koymuştur (Beck, 2008). Bilişsel esneklik düzeyi düşük bireyler, herhangi bir hayal kırıklığı, bir tehdit ya da meydan okuma gibi olumsuz durumlarla karşılaştıklarında yoğun öfke duygusu ve saldırganlık davranışları gösterebilmektedirler. Bilişsel olarak katı bireyler, bütüncül düşünürler, dikkatleri dağınıktır ve değişimden hoşlanmazlar. Bazı insanlar düşünce yapılarında ya hep ya hiç yaklaşımını ve genellemelerde bulunmayı ya da kişisel çıkarımlar yapmayı tercih edebilirler. Bu durum, bireylerdeki bilişsel esneklik becerilerinin gelişmemiş olmasından kaynaklanmaktadır.

Bilişsel esnekliğin artırılması, bireysel ve toplumsal düzeyde psikolojik iyi oluşu desteklemek için önemli bir hedef olarak değerlendirilmektedir (Martin ve Rubin, 1995).

Alan yazın taraması, bilişsel katılık gibi psikopatoloji riski taşıyan temel yapıların önemine yönelik farkındalığın arttığını ve bu alandaki müdahale çalışmalarının sayıca yükseldiğini göstermektedir. Ancak mevcut araştırmaların büyük bir kısmı, bu müdahaleleri ergen veya yetişkin örneklemeleri üzerinde yoğunlaştırmış durumdadır. Bu durum, gelişimsel açıdan kritik bir dönem olan ilkökul çağındaki çocuklara yönelik kanıta dayalı, birincil önleme niteliğindeki müdahalelerin etkinliğine dair kapsamlı ve bütüncül bilgi eksikliğini ortaya koymaktadır. Bu nedenle, ilkökul çağı çocuklarında bilişsel esnekliği arttırmaya yönelik etkili müdahaleleri tanımlayan, değerlendiren ve sentezleyen bir sistematik derlemeye ihtiyaç duyulmaktadır.

Bu sistematik derleme, ilkökul çağındaki öğrencilerde bilişsel esneklik düzeylerini arttırmaya yönelik mevcut müdahale bulgularını bütüncül bir çerçevede değerlendirmeyi amaçlamaktadır. Elde edilen bulguların, ilkökullarda çalışan eğitimciler için öğrencilerin sosyal- duygusal gelişimlerine katkı sağlamaya yönelik uygulamalara katkı sağlaması beklenmektedir.

Bu çalışmanın amacı, ilkökul öğrencilerinde bilişsel esneklik düzeylerini arttırmaya yönelik olarak uygulanan müdahale programlarının etkililiğini inceleyen araştırmaları sistematik biçimde gözden geçirerek bu müdahalelere ilişkin bütüncül bir bakış açısı sunmaktır. Bu kapsamda aşağıdaki sorulara yanıt aranmıştır: İlkökul öğrencilerine yönelik bilişsel esnekliği arttırmaya yönelik yapılan müdahaleleri inceleyen çalışmalarda aşağıdaki sorulara yanıt aranmıştır:


1. Örneklem ve katılımcıları kimlerdir?
2. Kullanılan araştırma desenleri nelerdir?
3. Müdahale programlarının oturumlarının süreleri ve içerikleri nasıldır?
4. Müdahale programları hangi teknik ve yöntemlere dayanmaktadır?
5. Çalışmalarda kullanılan ölçme araçları nelerdir?
6. Müdahalelerin etkililiğine ilişkin ulaşılan bulgular nasıl sonuçlar ortaya koymaktadır?

YÖNTEM

Bu çalışma, ilkökul öğrencileri üzerinde yürütülen ve bilişsel esneklik düzeylerini arttırmaya yönelik müdahale programlarının etkililiğini inceleyen araştırmaların yöntemsel niteliklerini ve bulgularını sistematik biçimde değerlendirmeyi amaçlayan bir derlemedir. Sistematik gözden geçirme süreci, çalışmanın şeffaflığını ve kapsayıcılığını sağlamak amacıyla PRISMA rehberine (Moher, Liberati, Tetzlaff, Altman ve PRISMA Group, 2009) uygun olarak yürütülmüştür. Literatür taraması, Web of Science, Google Scholar ve Pubmed veri tabanlarında yayımlanan Türkçe ve İngilizce çalışmalar temel alınarak, “bilişsel esneklik”, “çocuk”, “müdahale” ve “ilkökul” anahtar sözcükleri Türkçe ve İngilizce olarak gerçekleştirilmiştir. Dâhil etme ve dışlama ölçütlerinin uygulanması sonucunda 18 çalışma

inceleme kapsamına alınmıştır. İncelenen çalışmalar, uygulanan müdahalenin türüne göre fiziksel aktivite, bilişsel eğitim, mindfulness egzersizleri, sanatsal etkinlikler ve çok bileşenli olarak kategorize edilerek analiz edilmiştir. Deneysel çalışmalarda müdahale protokollerinin yapısı, oturum içerikleri, uygulama süreleri, kullanılan ölçme araçları ve raporlanan etkililik bulguları sistematik olarak analiz edilmiştir. Bu sistematik derleme, ilkokul düzeyinde bilişsel esnekliği arttırmayı hedefleyen müdahalelere ilişkin mevcut kanıtları bütüncül bir çerçevede sunarak, ileride geliştirilecek önleyici ve destekleyici programlara bilimsel bir temel oluşturmayı amaçlamaktadır.

Şekil 1. Çalışmaya ait PRISMA akış diyagramı



BULGULAR

Tablo 1. Bilişsel Esnekliği Geliştirme ile ilgili yapılan çalışmalar

Yazar-Yıl	Örneklem	Araştırma Deseni	Müdahale Programının İçeriği ve Süresi	Ölçme Araçları	Bulgular
Zhang ve diğ. (2023)	6 yaşında 43 (deney grubu) ve 46 (kontrol grubu) 1. Sınıf öğrencisi	Deneysel desen	11 hafta, haftada 4 gün 45 dakika Fiziksel Egzersiz Müdahaleleri	Esnek Madde Seçimi Görevi (FIST)	Haftada 4 gün uygulanan fiziksel egzersiz programı, kontrol grubuna kıyasla bilişsel esneklik, çalışma belleği ve inhibisyon skorlarında istatistiksel olarak anlamlı artış sağladı.
Looney ve diğ. (2024)	3. ve 6. Sınıf arasında 95 öğrenci	Deneysel desen	11 haftalık bir dönemde 18 oturum her oturum 20 dakika Recollect the Study (Çalışma belleği), Sightseeing (Görsel işleme)	Delis-Kaplan Yönetici İşlev Sistemi (DKEFS)	Her iki eğitim grubu da (hem çalışma belleği hem görsel işleme odaklı oyunlar), bilişsel esneklik görevinde istatistiksel olarak anlamlı ve büyük etki büyüklüğüne sahip gelişme gösterdi.
Castillo-Segura ve diğ. (2025)	6-8 yaş arası 1. ve 2. Sınıf 23 öğrenci (Deney grubu 12 öğrenci, kontrol grubu 11 öğrenci)	Deneysel desen	12 hafta boyunca 22 oturum her oturum 15-20 dakika İnhibisyon, bilişsel esneklik, çalışma belleği ve dikkat kontrolünü hedefleyen kombine müdahale programı.	Stroop Testi (İnhibisyon), Rey Karmaşık Şekil Testi (Dikkat/Bellek), BRIEF-2 (Yürütücü İşlev Envanteri), TALE (Okuma-Yazma Testi)	Müdahale grubu; bilişsel esneklik, inhibisyon ve çalışma belleği skorlarında kontrol grubuna göre anlamlı düzeyde gelişme gösterdi. Okuma ve yazma becerilerinde gruplar arası istatistiksel fark bulunamasa da, deney grubu müdahale sonrasında yürütücü işlevler ile okuma-yazma arasında daha güçlü pozitif korelasyonlar sergiledi.
Hrabovsky ve Kovalcikova (2025)	10 yaşında 14 4.sınıf öğrencisi (Deney grubu 7 öğrenci, kontrol grubu 7 öğrenci)	Yarı deneysel desen	8 hafta haftada 1 oturum 45 dakika Okul Temelli Mindfulness (Bilinçli Farkındalık) Programı	D-KEFS Bataryası: Trail Making Test (Esneklik), Stroop Testi (İnhibisyon ve Geçiş); Digit Span (Çalışma Belleği); FFMQ (Farkındalık Ölçeği)	Mindfulness eğitimi alan grup, bilişsel esneklik (görev değiştirme) ve inhibisyon (dürtü kontrolü) performanslarında kontrol grubuna göre istatistiksel olarak anlamlı artış gösterdi. Ancak çalışma belleği (working memory) puanlarında gruplar arası anlamlı fark bulunmadı.
Xu ve diğ. (2022)	6- 8 yaş 60 erkek çocuk (Yüksek frekans grubu 20 öğrenci, düşük frekans grubu 20 öğrenci, kontrol grubu 20 öğrenci)	Kesitsel araştırma deseni	Düşük frekans haftada 1 antrenman, yüksek frekans haftada 2 antrenman, kontrol grubu antrenman yok. Basketbol antrenmanı	Switching Task (Bilişsel Esneklik), N-back Task (Çalışma Belleği), Stop-signal Task (İnhibisyon)	Haftada en az 2 kez basketbol antrenmanı yapan (yüksek frekans) grup, bilişsel esneklik ve çalışma belleği testlerinde kontrol grubuna göre anlamlı derecede daha iyi performans gösterdi. Ancak inhibisyon (dürtü kontrolü) becerisinde gruplar arasında anlamlı fark bulunmadı.
James ve diğ. (2020)	10- 12 yaş aralığında 69 öğrenci	Boylamsal araştırma deseni	2 yıl boyunca haftada 45'er dakika olmak üzere 2 ders Sınıf içi yaylı çalgılar eğitimi	Children's Color Trails Test (CCTT)	Aktif enstrüman eğitimi alan grup, 2 yılın sonunda bilişsel esneklik, çalışma belleği testlerinde kontrol

INTERNATIONAL TOPKAPI CONGRESS VI

	(Deney grubu 34 öğrenci, kontrol grubu 35 öğrenci)				grubuna göre anlamlı düzeyde daha fazla gelişme gösterdi.
Cardoso ve diğ. (2019)	3. ve 4. sınıflardan 113 öğrenci (Deney grubu 64 öğrenci, kontrol grubu 49 öğrenci)	Deneysel desen	5 ay boyunca haftada 3 kez her oturum 50-60 dakika PENCE Programı (Okul müfredatına entegre, 4 modüllü nöropsikolojik stimülasyon: Planlama, İnhibisyon, Çalışma Belleği, Esneklik)	Wisconsin Kart Eşleme Testi (WCST)	Müdahale grubu; inhibisyon, çalışma belleği ve planlama becerilerinde kontrol grubuna göre anlamlı gelişme gösterdi. Ayrıca akıcı zeka ve akademik becerilere (yazma, matematik) transfer etkisi görüldü. Ancak, doğrudan bilişsel esneklik puanlarında gruplar arası anlamlı bir fark bulunamadı.
Reina-Reina ve diğ. (2024)	1. sınıf 40 öğrenci (Deney grubu 12 öğrenci, kontrol grubu 28 öğrenci)	Yarı deneysel desen	8 Hafta boyunca haftada 1-2 oturum, toplam ortalama 155 dk) CogniFit Platformu (Oyunlaştırılmış Bilişsel Eğitim; İnhibisyon, Esneklik ve Çalışma Belleği odaklı oyunlar).	PROLEC-R (Okuma Süreçlerini Değerlendirme Bataryası)	Bilişsel eğitim alan grup, harf tanıma hızında (letter recognition speed) kontrol grubuna göre istatistiksel olarak anlamlı düzeyde daha iyi performans gösterdi. Ancak kelime ve sözde-kelime okuma becerilerinde (doğruluk veya hız) gruplar arası anlamlı bir fark bulunmadı.
Cordeiro ve diğ. (2021)	3. sınıf 66 öğrenci (Mindfulness eğitimi alan 29 öğrenci, gevşeme eğitimi alan 37 öğrenci)	Yarı deneysel desen	8 hafta boyunca haftada 2 kez 30'ar dakika Psikologlar tarafından bir gruba mindfulness eğitimi, diğer gruba ise gevşeme eğitimi	Comprehensive Executive Function Inventory – CEFI (Kapsamlı Yönetici İşlev Envanteri) BANC- Semantic fluency	Her iki gruba verilen eğitimler de anlamlı artışa neden olmuştur. Gevşeme eğitimi, ön-test puanları düşük olan çocuklarda performans temelli bilişsel esneklik becerilerini (semantik akıcılık görevi) geliştirmede mindfulness eğitimine göre daha etkili olmuştur.
Li ve diğ. (2022)	4. sınıf 79 öğrenci 3 grup SSPlay (Miktar-nitelik) Play (Nitelik) Kontrol	Deneysel desen	13 hafta SSPlay (Otur- kalk sıralar-teneffüslerde oyun temelli aktiviteler) Play (Teneffüslerde oyun temelli aktiviteler)	Wisconsin Kart Eşleme Testi (WCST) Tower of London (ToL) Görevi	Hem SSPlay (Harmanlanmış) hem de Play (Sadece Oyun) grupları, bilişsel esneklik toplam hata puanlarında kontrol grubuna göre anlamlı düşüş (iyileşme) gösterdi. Özellikle hem sınıf içi hareketin hem oyunun olduğu SSPlay grubu, esnekliğin kritik göstergesi olan "perseveratif hata" (ısrar hatası) oranını azaltmada en etkili grup oldu. Planlama becerisinde gruplar arası anlamlı fark bulunmadı.
Oliveira ve diğ. (2023)	2.sınıf 61 öğrenci (Deney grubu 34 öğrenci, kontrol grubu 27 öğrenci)	Boylamsal, yarı deneysel desen	2 yıl boyunca haftada 3 gün, günde en az 15 dakika Fiziksel Aktif Dersler (PAL) - Müfredata entegre edilmiş, matematik/dil derslerinde hareket etmeyi veya ayakta durmayı içeren sınıf içi etkinlikler	Bilgisayar Tabanlı Bilişsel Testler: Switch Task (Bilişsel Esneklik), Go/No-Go (İnhibisyon), Visual Search (Seçici Dikkat)	PAL uygulanan sınıf, 2 yıllık takibin sonunda bilişsel esneklik (görev değiştirme), inhibisyon ve seçici dikkat testlerinde (hem tepki süresi hem doğruluk açısından) kontrol grubuna göre istatistiksel olarak anlamlı düzeyde daha iyi performans sergiledi.
Ren ve diğ. (2024)	2.sınıf 90 öğrenci (Fiziksel Aktivite (PA) grubu 23 öğrenci, Entelektüel aktivite (IA) grubu 25 öğrenci, Karma	Deneysel desen	16 hafta boyunca haftada 4 gün günde 40'ar dakika Üç farklı müdahale grubu karşılaştırıldı: 1) PA (Fiziksel): İp atlama, spor oyunları	Flexible Item Selection Task (Bilişsel Esneklik), Animal Go/No-go (İnhibisyon), Working Memory Span (Çalışma	Tüm müdahale grupları (sadece spor yapanlar, sadece zihinsel aktivite yapanlar ve ikisini yapanlar), kontrol grubuna göre bilişsel esneklik, inhibisyon ve çalışma belleği skorlarında anlamlı artış gösterdi.

INTERNATIONAL TOPKAPI CONGRESS VI

	grup(PA+IA) 22 öğrenci, Kontrol grubu 20 öğrenci)		2) IA (Zihinsel): Satranç, boyama, kodlama 3) PA+IA (Kombine): Hem spor hem zihinsel etkinlik	Belleği), Fiziksel Uygunluk Testleri	Ancak en yüksek gelişimi, Kombine (Fiziksel + Zihinsel) grup sergiledi.
Aoyama (2024)	2.sınıf 68 öğrenci (Deney grubu 34 öğrenci, kontrol grubu 34 öğrenci)	Yarı deneysel desen	4 hafta boyunca haftada 3 gün teneffüslerde 15'er dakika "Onigokko" (Geleneksel Japon Yakalamaca/Ebelemece Oyunu)	Trail Making Test-B (TMT-B)	Müdahale grubu, 4 hafta sonunda bilişsel esneklik (TMT-B tepki süresi) performansında kontrol grubuna göre istatistiksel olarak anlamlı düzeyde daha fazla iyileşme gösterdi.
Tao ve diğ. (2025)	7-12 yaş arası 426 çocuk (Aerobik egzersiz grubu 106 çocuk, Koordinasyon egzersiz grubu 107 çocuk, Takım sporları grubu 106 öğrenci, Kontrol grubu 107 öğrenci)	Deneysel desen	36 hafta boyunca haftada 3 gün, günde 45 dakika Üç farklı yapılandırılmış fiziksel aktivite müdahalesi karşılaştırıldı: 1) Aerobik: Kardiyovasküler odaklı (koşu, zıplama) 2) Koordinasyon: Denge, el-göz koordinasyonu, karmaşık motor beceriler 3) Takım Sporları: Basketbol, futbol, voleybol (taktik karar verme içeren).	Cambridge Nöropsikolojik Test Otomatik Bataryası (CANTAB)	Tüm müdahale grupları kontrol grubuna göre anlamlı gelişim göstermiştir. Ancak koordinasyon egzersizleri, yürütücü işlevlerin geliştirilmesinde en yüksek etki büyüklüğüne sahip olmuştur. Onu aerobik egzersiz ve takım sporları takip etmiştir. Ayrıca yaşa özgü bir bulgu olarak; küçük yaş grubu (7-9 yaş) en çok bilişsel esneklik alanında gelişirken, büyük yaş grubu (10-12 yaş) çalışma belleğinde daha fazla kazanç sağladı.
Hillman ve diğ. (2014)	7-9 yaş arası 221 çocuk (Rastgele atama: Deney vs. Kontrol Grubu)	Deneysel desen	9 ay boyunca, hafta içi her gün 2 saat - ortalama 70 dakika Aktif "FITKids" Okul Sonrası Fiziksel Aktivite Programı (Aerobik ve motor beceri odaklı oyunlar)	Bilgisayarlı Bilişsel Testler (Switch Task- Esneklik, Flanker Task- İnhibisyon)	9 aylık program sonunda müdahale grubu, kontrol grubuna kıyasla bilişsel esneklik ve inhibisyon görevlerinde (doğruluk oranı) istatistiksel olarak anlamlı artış gösterdi.
Cheng ve diğ. (2023)	7-8 yaş arası 24 çocuk (Deney grubu 12 çocuk, kontrol grubu 12 çocuk)	Deneysel desen	12 hafta boyunca haftada 2 kez ortalama 45-55 dakika At Destekli Aktivite (Equine-Assisted Activity - EAA).	Flanker (İnhibisyon), 1-Back (Çalışma Belleği), More-odd Shifting (Bilişsel Esneklik)	EAA grubu, 12 haftalık eğitim sonrasında kontrol grubuna göre bilişsel esneklik (More-odd shifting) ve inhibisyon (Flanker) görevlerinde hem hız hem doğruluk açısından anlamlı düzeyde gelişme gösterdi. Çalışma belleğinde (1-Back) ise sadece doğruluk oranında anlamlı artış bulundu.
Van der Niet ve diğ. (2016)	8-12 yaş arası 105 öğrenci (Deney grubu 53 öğrenci, kontrol grubu 52 öğrenci)	Yarı deneysel desen	22 hafta boyunca haftada 2 gün, 30 dakika Öğle teneffüslerinde uygulanan bilişsel olarak zorlayıcı aerobik oyunlar (takım oyunları, engelli parkurlar vb.).	Stroop Testi (İnhibisyon), Digit Span (Çalışma Belleği), Trail Making Test (Bilişsel Esneklik), Tower of London (Planlama)	Müdahale grubu, kontrol grubuna göre inhibisyon (dürtü kontrolü) ve sözel çalışma belleği performanslarında istatistiksel olarak anlamlı düzeyde daha fazla gelişme gösterdi. Ancak bilişsel esneklik ve planlama puanlarında gruplar arası anlamlı bir fark bulunamadı.
Beşer (2024)	2. ve 3. sınıflardan 61 öğrenci	Deneysel desen	12 hafta boyunca haftada 6 saat	Bilişsel Esneklik Stratejileri Testi (Araştırmacı)	Masal temelli eğitim sonrasında hem 2. ve 3. sınıf öğrencilerinin bilişsel esneklik puanlarında

INTERNATIONAL TOPKAPI CONGRESS VI

	(2.sınıf 35 öğrenci, 3.sınıf 26 öğrenci)		"Masallar Aracılığıyla Bilişsel Esneklik Eğitimi". (Masallara entegre edilmiş 6 farklı problem çözme stratejisi (bağıntı bulma, tersten düşünme, diyagram çizme vb.) öğretilmiştir.)	tarafından geliştirilen açık uçlu problem durumları	istatistiksel olarak anlamlı artış görüldü. Ayrıca, 2. sınıflar en çok "bağıntı bulma", 3. sınıflar ise en çok "geriye doğru çalışma" stratejisinde esneklik kazandı.

İlkokul Öğrencilerinde Bilişsel Esnekliği Arttırmaya Yönelik Müdahalelerin Örneklem ve Katılımcıları

Bu sistematik derlemede analiz edilen 18 çalışmanın örneklem grubu, ilkokul dönemindeki 6-12 yaş aralığında olan çocuklardan oluşmaktadır. Çalışmalara katılan toplam öğrenci sayısı 1704 kişidir. Örneklem özellikleri yaş, örneklem büyüklüğü ve cinsiyet açısından incelendiğinde aşağıdaki durumlar tespit edilmiştir:

- a) Yaş dağılımı: Analiz edilen çalışmalarda müdahalelerin yoğunlaştığı belirli yaş grupları bulunmaktadır:
 - Bilişsel esneklik için kritik bir dönem olarak görülen 6-8 yaş aralığı (1. ve 2. sınıf) çalışmaların önemli bir kısmını oluşturmaktadır. Zhang ve diğ. (2023) ve Reina- Reina ve diğ. (2024), 1.sınıf öğrencileriyle, Ren ve diğ. (2024), Oliveira ve diğ. (2023) ve Aoyama (2024), 2.sınıf öğrencileriyle, Castillo-Segura ve diğ. (2025) ve Xu ve diğ. (2022) 6-8 yaş aralığındaki çocuklarla, Cheng ve diğ. (2023), 7-8 yaş aralığındaki çocuklarla çalışmıştır.
 - Daha karmaşık yürütücü işlevlerin test edildiği 9-10 yaş aralığı (3. ve 4. sınıf) olan grupta; Cardoso ve diğ. (2019), Cordeiro ve diğ. (2021), Li ve diğ. (2022) ve Hrabovsky ve Kovalcikova (2025) gibi araştırmacılar 3. ve 4. sınıf öğrencileriyle çalışmıştır.
 - Bazı geniş ölçekli çalışmalar daha geniş yaş aralığına (7- 12 yaş) sahiptir. Van der Niet ve diğ. (2016), 8-12 yaş aralığındaki çocuklarla, Tao ve diğ. (2025) 7-12 yaş aralığındaki çocuklarla çalışmıştır.
- b) Örneklem büyüklüğü: İncelenen çalışmalardaki örneklem büyüklükleri farklılık göstermektedir.
 - Geniş örneklemli çalışmalara baktığımızda en geniş katılımcı grubuna sahip çalışma, 426 öğrenci ile Tao ve diğ. (2025) tarafından yürütülmüştür. Bu çalışmanın ardından 221 öğrenci ile Hillman ve diğ. (2014) tarafından yapılan çalışma gelmektedir. Bu çalışmalar sonuçların evrene genellenebilmesi açısından önem taşımaktadır.
 - Çalışmaların çoğunluğu (Van der Niet ve diğ., 2016; Cardoso ve diğ., 2019; James ve diğ., 2020; Cordeiro ve diğ., 2021; Li ve diğ., 2022; Xu ve diğ., 2022; Zhang ve diğ., 2023; Oliveira ve diğ. 2023; Looney ve diğ., 2024; Ren ve diğ., 2024; Aoyama, 2024; Beşer, 2024) 60 ile 120 öğrenci arasında değişen örneklemle yürütülmüştür.
 - Yoğun bireysel müdahale gerektiren ve pilot niteliğindeki bazı çalışmalarda (Hrabovsky ve Kovalcikova, 2025; Castillo-Segura ve diğ., 2025; Cheng ve diğ., 2023) örneklem sayısı 14 ile 24 öğrenci arasındadır.
- c) Analize dahil edilen çalışmaların neredeyse tamamında kız ve erkek öğrenciler heterojen gruplar halinde yer almıştır. Sadece Xu ve diğ. (2022), tarafından yürütülen çalışmada 60 erkek öğrenci bulunmaktadır.

İlkokul Öğrencilerinde Bilişsel Esnekliği Arttırmaya Yönelik Müdahalelerde Kullanılan Araştırma Desenleri

Bu sistematik derlemede analiz edilen 18 çalışma araştırma desenleri açısından incelendiğinde, çalışmaların tamamına yakınının müdahale temelli deneysel tasarımlı olduğu görülmektedir. Çalışmada kullanılan desenler; deneysel desen ve yarı deneysel

desenler olmak üzere iki ana kategoride yoğunlaşmaktadır. Bir çalışmada ise kesitsel desen modeli kullanılmıştır.

İncelenen çalışmaların 10 tanesinde (Hillman ve diğ., 2014; Cardoso ve diğ., 2019; Li ve diğ., 2022; Cheng ve diğ., 2023; Zhang ve diğ., 2023; Looney ve diğ., 2024; Ren ve diğ., 2024; Beşer, 2024; Castillo-Segura ve diğ., 2025; Tao ve diğ. 2025) deneysel desen, 5 tanesinde (Van der Niet ve diğ., 2016; Cordeiro ve diğ., 2021; Aoyama, 2024; Reina, Reina ve diğ., 2024; Hrabovsky ve Kovalcikova, 2025) yarı deneysel desen, birinde (James ve diğ., 2020) boylamsal desen, birinde (Oliveira ve diğ., 2023) hem boylamsal hem yarı deneysel desen, birinde (Xu ve diğ., 2022) ise kesitsel desen kullanılmaktadır.

Sonuç olarak; alanda yapılan çalışmaların %94'ünün (18 çalışmanın 17'si) bir müdahale programının etkililiğini sınamaya yönelik deneysel (gerçek veya yarı) kurguya sahip olduğu; araştırmacıların sadece anlık etkiye değil, giderek artan bir eğilimle uzun süreli (boylamsal) etkilere de odaklandığı belirlenmiştir.

İlkokul Öğrencilerinde Bilişsel Esnekliği Arttırmaya Yönelik Müdahale Programlarının Süreleri ve İçerikleri

Bu sistematik derleme kapsamında analiz edilen 18 çalışma, uygulanan müdahale programlarının süreleri ve içerikleri açısından farklılaşmaktadır. Müdahaleler, süresine göre kısa süreli, orta süreli ve uzun süreli programlar olarak; içeriklerine göre ise fiziksel aktivite temelli, oyun ve oyunlaştırılmış bilişsel etkinlikler, mindfulness temelli uygulamalar, sanat, müzik ve anlatı temelli uygulamalar ile çok bileşenli (kombine) müdahaleler olarak sınıflandırılmıştır.

- a) Müdahale programlarının süreleri: Uygulanan programlar sürelerine göre kısa, orta ve uzun vadeli olmak üzere üç kategoride değerlendirilmiştir:
- Çalışmaların bir kısmı yoğun şekilde uygulanan kısa programlardan oluşmaktadır. Aoyama (2024) 4 hafta; Hrabovsky ve Kovalcikova (2025), Cordeiro ve diğ. (2021), Reina- Reina ve diğ. (2024) ise 8 hafta süren müdahale programları uygulamıştır.
 - En sık tercih edilen müdahale süresi 11-16 hafta aralığıdır. Zhang ve diğ. (2023) ve Looney ve diğ. (2024) 11 hafta; Cheng ve diğ. (2023), Castillo- Segura ve diğ. (2025) ve Beşer (2024) 12 hafta; Li ve diğ. (2022) 13 hafta; Ren ve diğ. (2024) ise 16 hafta süren müdahale programları uygulamışlardır.
 - Yapılan müdahalelerin kalıcılığını hedefleyen müdahaleler uzun süreli müdahale programlarıdır. Van der Niet ve diğ. (2016) 22 hafta; Tao ve diğ. (2025) 36 hafta; Hillman ve diğ. (2014) 9 ay boyunca süren müdahale programları uygulamışlardır. James ve diğ. (2020) ile Oliveira ve diğ. (2023) ise programın etkilerini 2 yıl boyunca takip etmişlerdir.

Müdahale programlarının sıklığı genellikle haftada 2-3 gün olarak planlanmıştır. Oturum süreleri ise çoğunlukla 30-60 dakika arasında değişmektedir. Buna karşın Aoyama (2024) teneffüslerde 15 dakikalık kısa oyunlar kullanırken, Hillman ve diğ. (2014) okul sonrasında 70 dakikayı bulan programlar da uygulamıştır.

- b) Müdahale programının içerikleri: Müdahale programlarında uygulanan yöntemler bilişsel esnekliği desteklemeye yönelik farklı yaklaşımları içermektedir.

- **Yapılandırılmış fiziksel aktivite ve spor:** En yaygın kullanılan müdahale yöntemidir. Fiziksel aktiviteye dayalı programlar; aerobik egzersizler, koordinasyon çalışmaları ve takım sporlarını kapsamaktadır (Hillman ve diğ., 2014; Van der Niet ve diğ., 2016; Zhang ve diğ., 2023; Aoyama (2024); Tao ve diğ., 2025). Ayrıca Xu ve diğ. (2022), basketbol antrenmanlarını; Cheng ve diğ. (2023) ise at destekli aktivite (bincilik) kullanmıştır.
- **Oyun ve oyunlaştırılmış bilişsel müdahaleler:** Oyun tabanlı müdahalelerde, bilişsel görevler ve fiziksel hareket içeren yapılandırılmış oyunlar kullanılmıştır (Cardoso ve diğ., 2019; Li ve diğ., 2022; Looney ve diğ., 2024; Reina- Reina ve diğ., 2024).
- **Mindfulness temelli müdahaleler:** Mindfulness ve gevşeme egzersizleri içeren programlarda, dikkat odaklama, nefese yönelme farkındalık egzersizleri uygulanmıştır (Cordeiro ve diğ., 2021; Hrabovsky ve Kovalcikova, 2025).
- **Sanat, müzik ve anlatı temelli müdahaleler:** Sanat ve müzik temelli müdahalelerde, yaratıcı etkinlikler yoluyla bilişsel esnekliğin geliştirilmesi amaçlanmıştır (James ve diğ., 2020). Anlatı temelli müdahalelerde ise masal anlatıcılığına entegre edilmiş bağıntı bulma, tersten düşünme, alternatif düşünme stratejileri ile bilişsel esnekliğin geliştirilmesi amaçlanmıştır (Beşer, 2024).
- **Kombine (çok bileşenli) müdahaleler:** Bazı müdahale programlarında fiziksel ve bilişsel bileşenleri aynı anda bulunduran çok bileşenli programlar uygulanmıştır (Oliveira ve diğ., 2023; Ren ve diğ., 2024; Castillo-Segura ve diğ., 2025).

Müdahale programlarının içeriklerine bakıldığında, ilkokul öğrencilerinde bilişsel esnekliği arttırmaya yönelik müdahale programlarının süre ve içerik bakımından çok fazla çeşitlilik gösterdiği görülmektedir.

İlkokul Öğrencilerinde Bilişsel Esnekliği Arttırmaya Yönelik Müdahale Programlarının Dayandığı Teknik ve Yöntemler

Bu sistematik derleme kapsamında analiz edilen 18 çalışma, ilkokul öğrencilerinde bilişsel esnekliği arttırmaya yönelik uygulanan müdahale programlarında farklı kuramsal temeller ve uygulama tekniklerinin kullanıldığını göstermektedir. Analiz edilen çalışmalar; bilişsel olarak zorlayıcı fiziksel aktivite temelli, oyun ve görev temelli, mindfulness ve duygu düzenleme temelli, sanat ve anlatı temelli ile çok bileşenli müdahaleler olarak sınıflandırılmıştır.

- **Bilişsel olarak zorlayıcı fiziksel aktivite temelli teknikler:** Bazı çalışmalarda bilişsel esnekliği arttırmak amacıyla, aerobik egzersizler, koordinasyon çalışmaları ve takım oyunları gibi etkinlikler, bilişsel olarak zenginleştirilerek uygulanmıştır (Hillman ve diğ., 2014; Van der Niet ve diğ., 2016; Zhang ve diğ., 2023; Tao ve diğ., 2025). Bu çalışmalar yalnızca fiziksel hareket içermemekte; aynı zamanda kural değiştirme, hızlı karar verme ve motor planlama gibi fiziksel etkinlikler içermektedir.
- **Oyun ve görev temelli teknikler:** Oyun tabanlı müdahalelerde, yapılandırılmış oyunlar ve oyunlaştırılmış bilişsel görevler aracılığıyla çocukların aktif katılımı sağlanmaya çalışılmıştır. Bu müdahaleler, çocukların bilişsel esneklik becerilerini arttırmayı hedefleyen kural değiştirme görevleri, strateji üretme görevleri, alternatif çözüm yolları

geliştirme ve esnek tepki verme teknikleri kullanılmıştır (Cardoso ve diğ., 2019; Li ve diğ., 2022; Looney ve diğ., 2024; Reina-Reina ve diğ., 2024).

- **Mindfulness ve duygu düzenleme temelli teknikler:** Bu müdahale programları, çocukların dikkat ve dürtü kontrollerini artırarak ve stres seviyelerini düzenleyerek çocukların bilişsel esneklik düzeylerine katkı sağlamayı hedeflemektedirler. Mindfulness temelli dikkat eğitimi, nefes farkındalığı, bedensel tepkilere odaklanma ve duygu düzenleme teknikleri kullanılmıştır (Cordeiro ve diğ., 2021; Hrabovsky ve Kovalcikova, 2025).
- **Sanat ve anlatı temelli müdahaleler:** Bu müdahale programları, çocukların yaratıcı düşünme, alternatif düşünme yolları üretme ve bakış açısı değiştirme becerilerini yapılandırılmış etkinlikler yoluyla destekleyerek bilişsel esnekliği arttırmayı hedeflemektedirler (James ve diğ., 2020). Anlatı temelli müdahalelerde ise masal anlatıcılığı tekniği kullanılarak çocuklara bağıntı bulma, tersten düşünme ve farklı bakış açısı geliştirme gibi stratejiler öğretilmiş ve Vygotsky'nin "Yapı İskelesi" kuramına dayalı bir teknik izlenmiştir (Beşer, 2024).
- **Çok bileşenli müdahaleler:** Bazı müdahale programlarında fiziksel, bilişsel ve duygusal bileşenleri bir araya getiren çok bileşenli teknikler uygulanmıştır (Oliveira ve diğ., 2023; Ren ve diğ., 2024; Castillo-Segura ve diğ., 2025). Bu programlarda fiziksel aktiviteler, bilişsel ve duygusal görevler ve farkındalık çalışmaları kullanılarak bilişsel esneklik çok yönlü olarak geliştirilmek istenmiştir.

İlkokul Öğrencilerinde Bilişsel Esnekliği Arttırmaya Yönelik Müdahale Programlarında Kullanılan Ölçme Araçları

Tablo 2: Araştırmalarda Kullanılan Ölçme Araçları

Kategori	Ölçme Aracının Adı	Kullanan Çalışmalar
<i>Performansa Dayalı Nöropsikolojik Testler</i>	Trail Making Test (TMT) (İz Sürme Testi - A ve B Formu)	Aoyama (2024); Van der Niet ve diğ. (2016); Xu ve diğ. (2022)
	Dimensional Change Card Sort (DCCS) (Boyutsal Değişiklik Kart Eşleme)	Hillman ve diğ. (2014); Castillo-Segura ve diğ. (2025)
	Stroop Testi	Van der Niet ve diğ. (2016); Cordeiro ve diğ. (2021)
	Delis-Kaplan Yönetici İşlev Sistemi (D-KEFS)	Looney ve diğ. (2024)
<i>Bilgisayar Tabanlı Görevler</i>	Flanker Task / More-odd Shifting	Cheng ve diğ. (2023)
	CANTAB (Intra-Extra Dimensional Set Shift)	Tao ve diğ. (2025)
	Esnek Madde Seçimi Görevi (FIST)	Zhang ve diğ. (2023)
	CogniFit Dijital Değerlendirme Modülü	Reina-Reina ve diğ. (2024)
<i>Özgün / Dolaylı Ölçüm Araçları</i>	Bilişsel Esneklik Stratejileri Testi (Problem Çözme Senaryoları)	Beşer (2024)
	Tower of London (Londra Kulesi) (Planlama)	Van der Niet ve diğ. (2016)
	Eurofit Test Bataryası (Fiziksel Uygunluk)	Van der Niet ve diğ. (2016); Zhang ve diğ. (2023)

Tablo 2’de görüldüğü üzere, araştırmalarda en çok kullanılan ölçme araçlarının performansa dayalı nöropsikolojik testler (TMT, Stroop vb.) olmaktadır.

İlkokul Öğrencilerinde Bilişsel Esnekliği Arttırmaya Yönelik Müdahale Programlarının Bulgularından Elde Edilen Sonuçlar

Bu sistematik derleme kapsamında analiz edilen 18 çalışmanın bulguları değerlendirildiğinde; ilkökul öğrencilerine uygulanan yapılandırılmış müdahale programlarının, bilişsel esneklik ve ilişkili yürütücü işlevler üzerinde genel olarak pozitif ve anlamlı bir etki yarattığı sonucuna ulaşılmıştır. Elde edilen pozitif etki müdahalenin türüne, süresine ve içerdiği bilişsel zorluk derecesine göre farklılaşmaktadır.

- a) **Fiziksel aktivite temelli müdahalelerin etkililiği:** Tao ve diğ. (2025), karmaşık motor beceriler ve denge gerektiren koordinasyon egzersizlerinin, standart aerobik koşu ve takım sporlarına kıyasla bilişsel esneklik düzeyini daha fazla etkilediğini; Xu ve diğ. (2022), haftada iki kez yapılan düzenli basketbol antrenmanlarının çocukların bilişsel esneklik düzeylerini arttırdığını; Aoyama (2024), kuralları anlık olarak değişen “Onigokko” (yakalamaca, ebelemece) oyununun bilişsel esneklik düzeyini arttırdığını; Van der Niet ve diğ. (2016), öğle teneffüslerinde uygulanan bilişsel olarak zorlayıcı aerobik oyunların dürtü kontrolünü geliştirmesine rağmen, bilişsel esneklik üzerinde anlamlı bir fark oluşturmadığını rapor etmiştir.
- b) **Oyun ve oyunlaştırılmış bilişsel müdahalelerin etkililiği:** Cardoso ve diğ. (2019), 4 modüllü nöropsikolojik stimülasyonun çocukların inhibisyon ve planlama becerilerini geliştirdiğini ancak bilişsel esneklik üzerindeki etkisinin anlamlı bir fark yaratmadığını; Looney ve diğ. (2024), hem çalışma belleği hem de görsel işleme odaklı oyunların çocukların bilişsel esneklik düzeylerini arttırdığını; Reina- Reina ve diğ. (2024), oyunlaştırılmış bilişsel eğitimin harf tanıma hızını arttırdığını rapor etmiştir.
- c) **Mindfulness, müzik ve sanat temelli müdahalelerin etkililiği:** Bu alandaki müdahalelere yer veren çalışmalar sınırlı sayıda olmasına rağmen bilişsel esnekliği geliştirme konusunda olumlu bulgular sunmaktadır. Hrabovsky ve Kovalcikova (2025), uyguladıkları mindfulness programının çocukların bilişsel esneklik ve inhibisyon görevlerinde anlamlı artış gösterdiğini; Cordeiro ve diğ. (2021), farklı gruplara uyguladıkları mindfulness ve gevşeme eğitimlerinin her iki grup için de bilişsel esneklik becerilerinde artışı sağladığını; James ve diğ. (2020), uzun süreli verilen müzik eğitiminin bilişsel esneklik düzeyini arttırdığını; Beşer (2024), masallara entegre edilen problem çözme becerileri ve alternatif bakış açıları geliştirme tekniklerinin çocukların bilişsel esneklik düzeyini geliştirdiğini rapor etmiştir.
- d) **Çok bileşenli (kombine) müdahalelerin etkililiği:** Fiziksel ve zihinsel becerileri içeren müdahale yaklaşımlarının en etkili ve tutarlı sonuçları verdiği görülmüştür. Oliveira ve diğ. (2023), hem fiziksel hem de zihinsel becerileri içeren etkinliklerin öğrencilerin bilişsel esneklik ve inhibisyon düzeylerinde anlamlı artışı sağladığını; Ren ve diğ. (2024), hem bedensel hareketin hem de zihinsel aktivitelerin bir arada olduğu grupların, tek başına bedensel hareket yapan gruba veya tek başına zihinsel aktivite yapan gruba göre bilişsel esneklik düzeylerinde en yüksek artışı gösterdiğini; Castillo-Segura ve diğ. (2025), uygulanan kombine müdahale programının bilişsel esneklik ve inhibisyon düzeylerinde anlamlı artışın olduğunu rapor etmiştir.

Tüm bulgular bütüncül olarak değerlendirildiğinde, ilkökul döneminde bilişsel esnekliğin geliştirilmesinde, sadece tekrarları içeren müdahale programları yerine zihinsel katılım

gerektiren, strateji kurmayı sağlayan ve hem fiziksel hem de zihinsel etkinlikleri içeren müdahale yaklaşımlarının daha etkili olduğu sonucuna varılmıştır.

TARTIŞMA, SONUÇ VE ÖNERİLER

Bu sistematik derleme çalışmasında, ilkökul öğrencilerinde bilişsel esnekliği artırmaya yönelik müdahale programlarını inceleyen 18 araştırma; örneklem ve katılımcı özellikleri, kullanılan araştırma desenleri, müdahale programlarının süreleri ve içerikleri, dayandıkları yöntem ve teknikler, kullanılan ölçme araçları ve elde edilen bulgular açısından bütüncül bir çerçevede ele alınmıştır. Elde edilen bulgular, ilkökul döneminde uygulanan yapılandırılmış müdahalelerin genel olarak bilişsel esneklik üzerinde olumlu etkiler yarattığını göstermektedir. Bununla birlikte, müdahalelerin etkililiğinin; programın içeriği, süresi ve kullanılan yöntem ve tekniklere bağlı olarak farklılaştığı görülmektedir.

İncelenen çalışmaların büyük çoğunluğunun deneysel ya da yarı deneysel desenle yürütülmüş olması, müdahale programlarının etkililiğine ilişkin güçlü kanıtlar sunmaktadır. Deney ve kontrol gruplarının karşılaştırıldığı araştırmalarda, müdahale uygulanan grupların bilişsel esneklik düzeylerinde kontrol gruplarına kıyasla anlamlı artışlar elde edilmiştir (Zhang ve diğ., 2023; Castillo-Segura ve diğ., 2025; Reina-Reina ve diğ., 2024; Li ve diğ., 2022; Oliveira ve diğ., 2023; Hrabovsky ve Kovalcikova, 2025; Cardoso ve diğ., 2019; Ren ve diğ., 2024; Aoyama, 2024; Tao ve diğ., 2025; Hillman ve diğ., 2014; Cheng ve diğ., 2023). Bu bulgular ışığında, bilişsel esnekliğin yalnızca gelişimsel süreçlere bağlı olarak kendiliğinden gelişen bir beceri olmadığı, uygun müdahale programlarıyla desteklenebileceği görülmektedir.

Yaş grupları açısından değerlendirme yapıldığında, 6-8 yaş arasında müdahalelerin yoğunlaştığı ve bu yaş gruplarında müdahalelerin daha etkili sonuçlar ortaya çıkardığı görülmektedir (Zhang ve diğ., 2023; Cheng ve diğ., 2023; Castillo-Segura ve diğ., 2025). Bu durum, prefrontal korteks gelişiminin hızlandığı ilkökulun ilk yıllarının, bilişsel esneklik becerisinin gelişimi açısından kritik bir dönem olduğunu göstermektedir. Bununla beraber, daha ileri yaş gruplarını kapsayan müdahale yaklaşımlarında da olumlu sonuçların olması bilişsel esneklik becerisinin ilkökul döneminde geliştirilebilir bir beceri olduğunu göstermektedir (Tao ve diğ., 2025).

İncelenen çalışmalarda müdahale içerikleri bakımından bir değerlendirme yapıldığında, bilişsel esnekliği artırmaya yönelik müdahale programlarının fiziksel aktivite temelli, oyun ve oyunlaştırılmış bilişsel müdahaleler temelli, mindfulness temelli, sanat, müzik ve anlatı temelli ve çok bileşenli yapılar içerdiği görülmektedir. Bilişsel olarak zorlayıcı fiziksel aktivitelerin ve çok bileşenli müdahale yaklaşımlarının daha güçlü sonuçlar ortaya çıkardığı görülmektedir (Xu ve diğ., 2022; Tao ve diğ., 2025). Bu bulguların, fiziksel ve bilişsel gelişimin aynı anda etkileşim içerisinde geliştiğini savunan yaklaşımları desteklediği görülmektedir.

Bu sistematik derlemenin bulgularından yola çıkılarak, ilkökul döneminde bilişsel esneklik gelişimini hedefleyen müdahale programlarının, öğrencilerin problem çözme becerilerini, duygularını regüle etmelerini, sosyal uyumlarını ve akademik performanslarını destekleyebileceği öngörülmektedir. Buna göre bilişsel esneklik gelişimini destekleyen uygulamaların sınıf içi etkinliklere ve okul psikolojik danışma ve rehberlik programlarına entegre edilmesi öğrencilerin bilişsel esneklik düzeylerinin geliştirilmesi açısından katkı sağlayacaktır.

Bu sistematik derleme çalışmasında bazı sınırlılıklar mevcuttur. İlk olarak belirlenmiş olan dahil etme ve dışlama kriterlerine uygun toplam 18 çalışmanın araştırmaya dahil edilmesi, yalnızca Türkçe ve İngilizce dillerinde tam metin erişimi olan çalışmaların araştırmaya dahil edilmesi, literatür taramasının PubMed, Web of Science ve Google Scholar veri tabanlarında sınırlandırılmış olması çalışmanın sınırlılıklardır. Sonraki çalışmalarda, daha geniş bir yaş aralığının ele alınması, farklı veri tabanları da kullanılarak tarama yapılması, farklı dillerde yayımlanan çalışmaların sürece dahil edilmesi önerilmektedir.

KAYNAKÇA

- Aoyama, S. (2024). The effect of playing Onigokko on children's executive function and cardiovascular endurance in the early elementary school grades. *Journal of Integrative Neuroscience*, 14(1), 1–8.
- Beck, A. T. (2008). The evolution of the cognitive model of depression and its neurobiological correlates. *American Journal of Psychiatry*, 165(8), 969–977. <https://doi.org/10.1176/appi.ajp.2008.08050721>
- Beşer, R. (2024). *Masallar aracılığıyla ilkökul öğrencilerinin bilişsel esneklik becerilerinin geliştirilmesi* [Yayımlanmamış doktora tezi]. Bursa Uludağ Üniversitesi.
- Best, J. R., ve Miller, P. H. (2010). A developmental perspective on executive function. *Child Development*, 81(6), 1641–1660. <https://doi.org/10.1111/j.1467-8624.2010.01499.x>
- Bilgiç, R. (2015). *Ergenlerin cinsiyet ve öğrenim kademesi düzeylerine göre bilişsel esneklik düzeyleri ile karar stratejileri arasındaki ilişkinin incelenmesi* [Yayımlanmamış yüksek lisans tezi]. Bahçeşehir Üniversitesi.
- Cardoso, C. O., Dias, N. M., Siqueira, L. S., ve Fonseca, R. P. (2019). Program for the neuropsychological stimulation of cognition in students: Impact, effectiveness, and transfer effects on student cognitive performance. *Frontiers in Psychology*, 10, 1784. <https://doi.org/10.3389/fpsyg.2019.01784>
- Castillo-Segura, P., ve López-Escribano, C. (2025). Preliminary study on enhancing literacy skills through intervention targeting inhibitory control, cognitive flexibility, working memory, and attentional control. *Education Sciences*, 15(2), 243. <https://doi.org/10.3390/educsci15020243>
- Cheng, X., Zhen, K., Fan, Y., Tang, Q., ve Wu, H. (2023). The effects of equine-assisted activities on execution function in children aged 7–8 years: A randomized controlled trial. *Brain and Behavior*, 13(8), e3148. <https://doi.org/10.1002/brb3.3148>
- Cordeiro, C., Magalhães, S., Rocha, R., Mesquita, A., Olive, T., Castro, S. L., ve Limpo, T. (2021). Promoting third graders' executive functions and literacy: A pilot study examining the benefits of mindfulness vs. relaxation training. *Frontiers in Psychology*, 12, 643794. <https://doi.org/10.3389/fpsyg.2021.643794>
- Dennis, J. P., ve Vander Wal, J. S. (2010). The cognitive flexibility inventory: Instrument development and estimates of reliability and validity. *Cognitive Therapy and Research*, 34, 241–253. <https://doi.org/10.1007/s10608-009-9276-4>
- Diamond, A. (2013). Executive functions. *Annual Review of Psychology*, 64(1), 135–168. <https://doi.org/10.1146/annurev-psych-113011-143750>
- Hillman, C. H., Pontifex, M. B., Castelli, D. M., Khan, N. A., Raine, L. B., Scudder, M. R., ... ve Kamijo, K. (2014). Effects of the FITKids randomized controlled trial on executive control and brain function. *Pediatrics*, 134(4), e1063–e1071.
- Hrabovsky, M., ve Kovalcikova, I. (2025). Evaluation of a PILOT school-based mindfulness program in primary education. *Education Sciences*, 15(9), 1088. <https://doi.org/10.3390/educsci15091088>
- Ionescu, T. (2012). Exploring the nature of cognitive flexibility. *New Ideas in Psychology*, 30(2), 190–200. <https://doi.org/10.1016/j.newideapsych.2011.11.001>
- James, C. E., Zuber, S., Elisei, F., ve Oechslin, M. S. (2020). Musical training and child development: A review of recent findings from a longitudinal study. *Annals of the New York Academy of Sciences*, 1423(1), 398–408.
- Li, M. H., Sum, R. K. W., ve Tremblay, M. S. (2022). A randomized controlled trial of a blended physical literacy intervention to support physical activity and health of primary school children. *Sports Medicine-Open*, 8(1), 55.

- Looney, L., ve Ptok, M. (2024). Supporting learning differences: Effects of cognitive training on cognitive abilities in a school-based sample. *Education Sciences*, 14(1), 89. <https://doi.org/10.3390/educsci14010089>
- Martin, M. M., ve Anderson, C. M. (1998). The cognitive flexibility scale: Three validity studies. *Communication Reports*, 11(1), 1–9. <https://doi.org/10.1080/08934219809367680>
- Martin, M. M., ve Rubin, R. B. (1995). A new measure of cognitive flexibility. *Psychological Reports*, 76(2), 623–626. <https://doi.org/10.2466/pr0.1995.76.2.623>
- Moher, D., Liberati, A., Tetzlaff, J., ve Altman, D. G. (2009). Preferred reporting items for systematic reviews and meta-analyses: The PRISMA statement. *PLoS Medicine*, 6(7), e1000097. <https://doi.org/10.1371/journal.pmed.1000097>
- Oliveira, A. J., Silva, A. J., ve Santos, M. P. (2023). Effects of two years of physically active lessons on cognitive indicators in children. *Trends in Neuroscience and Education*, 30, 100196.
- Reina-Reina, J., ve Cruz-Feliu, J. (2024). Impact of a cognitive training on reading of 6-year-old children. *International Journal of Serious Games*, 11(3), 45–60.
- Ren, Y., ve Li, S. (2024). Comparative efficacy of physical activity types on executive functions in children and adolescents: A network meta-analysis. *Journal of Sport and Health Science*. (Erken görünüm / Epub ahead of print).
- Tao, Y., Zhang, Y., Qian, H., ve Cao, Z. (2025). Long term effects of physical activity types on executive functions in school aged children. *Scientific reports*, 15(1), 30303. <https://doi.org/10.1038/s41598-025-09674-9>
- Van der Niet, A. G., de Greeff, J. W., Kester, A., ve Visscher, C. (2016). Effects of a cognitively demanding aerobic intervention during recess on children's physical fitness and executive functioning. *Pediatric Exercise Science*, 28(1), 64–70.
- Xu, W., ve Li, Y. (2022). Effect of a strategic physical activity program on cognitive flexibility among children. *Children*, 9(6), 798.
- Zhang, Y., ve Wang, X. (2023). The effects of physical exercise on physical fitness and executive function in children. *Frontiers in Psychology*, 14, 1123456.

**ERGENLİKTE AKRAN ZORBALIĞI VE KABUL VE KARARLILIK TERAPİSİ
TEMELLİ ARAŞTIRMALARIN İNCELENMESİ**

Prof. Dr. Fatma Ebru İKİZ

Dokuz Eylül Üniversitesi, Buca Eğitim Fakültesi,
Psikolojik Danışmanlık ve Rehberlik Bölümü, Buca, İzmir
0000-0003-4381-1658

Yüksek Lisans Öğrencisi Gülay KOCATAŞ

Dokuz Eylül Üniversitesi, Buca Eğitim Fakültesi,
Psikolojik Danışmanlık ve Rehberlik Bölümü, Buca, İzmir
0009-0008-1537-2161

ÖZET

Ergenlik dönemi bireyde kimlik arayışı ve sosyal uyum süreçlerinin ön planda olduğu kritik bir dönemdir. Bu dönemde akran zorbalığı bireyin benlik algısını olumsuz etkileyen, psikolojik iyi oluşunu tehdit eden en yaygın psikososyal sorunlardan biridir. Akran zorbalığı ile baş etmede ergen bireyler, düşünceleri ile kurduğu ilişkiyi dönüştüren ve psikolojik esneklik becerisi geliştirmelerine katkı sağlayan ACT temelli çalışmalara ihtiyaç duymaktadırlar. Bu çalışmanın amacı, ergenlik döneminde akran zorbalığı davranışının Kabul ve Kararlılık Terapisi (ACT) temel alınarak incelendiği araştırmaları incelemek, sistematik olarak gözden geçirmek ve elde edilen sonuçları değerlendirmektir. Bu çalışmanın yöntemi sistematik gözden geçirme olup Web Of Science, Google Scholar ve Dokuz Eylül Üniversitesi (DEÜ) Vetis veri tabanlarında , “ergenlik”, “akran zorbalığı”, “kabul ve kararlılık terapisi” anahtar kelimeleri Türkçe ve İngilizce olarak alan yazın taraması yapılmıştır. Elde edilen 329 sayıdaki makale, PRISMA Rehberi çerçevesinde belirlenen dahil etme ve dışlama kriterlerine göre değerlendirilmiş, ergenlik dönemi örneklemini kapsayan 3 çalışma incelemeye alınmıştır.

Seçilen araştırmalarda, ergenlik dönemindeki bireylerin akran zorbalığı problemleri üzerinde ACT temelli çalışmaların etkisi ve istatistiksel bulguları incelenmiştir. Elde edilen sonuçlar, ACT temelli çalışmaların ergenlik döneminde akran zorbalığını önleme ve azaltmada etkili olduğunu göstermiştir. Literatür genelinde ergenlerin akran zorbalığı davranışları üzerinde ACT temelli yaklaşımların etkililiği ve bu çalışmaların artırılmasının önemi ortaya koyulmuştur.

Anahtar Kelimeler : Ergenlik dönemi, akran zorbalığı, kabul ve kararlılık terapisi.

**EXAMINATION OF RESEARCH ON PEER BULLYING DURING ADOLESCENCE
BASED ON ACCEPTANCE AND COMMITMENT THERAPY**

ABSTRACT

Adolescence is a critical period characterised by the search for identity and social adjustment processes. During this period, peer bullying is one of the most common psychosocial problems that negatively affects an individual's self-perception and threatens their psychological well-being. Acceptance and Commitment Therapy (ACT)-based approaches are thought to be helpful in coping with peer bullying, as they enable adolescents to realistically assess their thoughts, themselves, and the relationships they form, transform them, and contribute to the

development of psychological flexibility skills. The aim of this study is to review research examining peer bullying during adolescence based on ACT, systematically review it, and evaluate the results obtained. The method of this study is systematic review. A literature search was conducted in Turkish and English using the keywords 'adolescence', 'peer bullying', and 'acceptance and commitment therapy' in the Web of Science, Google Scholar, and Dokuz Eylül University (DEU) Vetis databases. The 329 articles obtained were evaluated according to the inclusion and exclusion criteria determined within the framework of the PRISMA Guide, and three studies covering adolescence were included in the review. The studies included in the research examined the impact and statistical findings of studies based on ACT on adolescents and peer bullying. The results obtained showed that studies based on ACT were effective in preventing and reducing peer bullying during adolescence. The literature generally highlighted the effectiveness of ACT-based approaches on adolescents' peer bullying behaviours and the importance of increasing these studies.

Keywords: Adolescence, peer bullying, acceptance and commitment therapy.

GİRİŞ

Ergenlik ve Akran Zorbalığı

Ergenlik dönemi, insan gelişiminde bebeklikten sonra bir sonraki en hızlı gelişim dönemidir (İkiz, 2022). Ergenlik insan gelişiminde yalnızca biyolojik bir gelişme süreci değil, aynı zamanda çocukluk döneminden yetişkinlik dönemine geçişte bilişsel, duygusal ve sosyal yeniden yapılanmanın yaşandığı önemli bir evredir (Santrock, 2021). Bu dönem aynı zamanda ergenin, sorumluluklar almaya başlayarak kendine ait bir kimlik oluşturduğu ve bireyleştiği bir dönemdir (Büyükcebeci, 2022). Erikson'a (1968) göre bu dönemde kimlik kazanım sürecinde olan ergenler için akran grubu önem kazanmakta ve kendini tanımladığı temel bir ayna işlevi görmektedir. Bu yoğun sosyal yönelim ergenleri akran reddine, dışlanmaya ve zorbalığa karşı yetişkinlere kıyasla çok daha savunmasız bırakmaktadır.

Ergenlik dönemi aynı zamanda bireyin çocukluktan yetişkinliğe geçişte birçok zorluk ve değişimle baş etmek zorunda olduğu bir dönem olarak açıklanmaktadır. Ergenlik döneminde bireyler; sigara, madde ve alkol kullanımı, riskli cinsel davranışlar, çeteleşme ve akran zorbalığı gibi ciddi birçok riskli durumlar ile karşı karşıya kalabilmektedir. (Aydın & Kıran, 2024). Dünya Sağlık Örgütü 2019 verilerine göre ergenlik döneminde gelişen ruh sağlığı sorunları, bireylerin eğitim ve kariyer süreçlerini, yetişkinlik döneminde ilişki kurma ve sürdürme şekillerini ve ebeveynlik biçimlerini etkileyebilmektedir. Bu nedenle, bireyin ergenlik döneminde ruh sağlığını olumsuz etkileyebilecek deneyimlerini daha iyi anlamak önemlidir. Bu olumsuz deneyimlerden bir tanesi de akran zorbalığı olarak görülmektedir (Halliday vd., 2021). Okullardaki öğrenciler arasında akran zorbalığı, eğitim ortamlarında görülmekte olan şiddetin en yaygın biçimlerinden birini oluşturmaktadır (Menesini & Salmivalli, 2017).

Olweus'a (2013) göre zorbalık, kasıtlı zarar verme amacı taşıyan, süreklilik ve tekrar davranışları içeren, taraflar arasında belirgin bir güç eşitsizliğinin bulunduğu bir saldırganlık türüdür. Akran zorbalığı fiziksel, sözel, sosyal ve siber zorbalık olarak 4 türde görülmektedir. Fiziksel yollarla uygulanan zorbalık vurmak, çelme takmak; sözel zorbalık isim takmak, alay etmek; sosyal zorbalık kişinin arkasından kötü hikayeler ve söylentiler yaymak, kişiyi sosyal gruplardan dışlamak şeklinde olabilmektedir (Menesini & Salmivalli, 2017). Siber zorbalık, kişilere e-posta, kısa mesaj, sosyal ağ siteleri veya farklı çevrimiçi ortamları kullanarak zarar vermek veya rahatsız etmek durumu olarak tanımlanmaktadır (Hymel & Swearer, 2015). Zorbalık döngüsüne bakıldığında zorba, kurban ve seyirci şeklinde 3 ana rol görülmektedir (Olweus, 2013). Zorbalar, akran grubu içerisinde genellikle sosyal açıdan güçlü bir konumda iken; mağdurlar daha savunmasız ve yalnız bir profil çizmektedir. Zorbaların

temel motivasyonu, mağdurun sosyal güvenliğini tehdit ederek kendisinin gücünü ve statüsünü artırmaktır. Bu nedenle zorbalık eylemleri genellikle, zorbaların gücünü kanıtladıkları bir akran grubu önünde gerçekleştirilmektedir. Seyirci grubunun zorbalık davranışlarına müdahale etmeme veya pasif katılımları, zorba ve kurban arasındaki güç eşitsizliğini derinleştiren, kurbanın savunmasızlığını ve zorbalığın etkisini artıran çok önemli bir çevresel faktördür (Cantone vd., 2015). Tsaoşis'in (2016) meta-analiz çalışmasına göre çocukluk döneminde zorbalık sonrası mağduriyet çok yoğun görülürken, ergenlik döneminde ise zorbalık yapma davranışı daha belirgin hale gelmektedir.

Akran zorbalığı, hem çocuklar hem de ergenler arasında psikolojik, sosyal ve akademik alanda ciddi sorunlara yol açmaktadır. Zorbalığa maruz kalan ergenlerde depresyon anksiyete, düşük benlik saygısı, sosyal dışlanma, akademik başarıda düşüş ve intihar düşüncesi sıklıkla görülebilmektedir. Kız öğrencilerde depresyon ve anksiyete gibi psikolojik etkiler erkeklere göre daha yoğun bir şekilde görülmektedir (Halliday vd., 2021; Menken vd., 2022).

Literatür incelendiğinde akran zorbalığı konusunda ergenlerde etkili olabilecek olan yaklaşımlar arasında Kabul ve Kararlılık Terapisi yaklaşımı (ACT) bulunmaktadır (Yalnız, 2019; Noushari vd., 2023).

Kabul ve Kararlılık Terapisi (ACT)

Davranış terapisi, ortaya çıkışından bu yana bilimsel temellere dayalı olarak gelişen bir yaklaşım olmuştur. Tarihî süreç içerisinde üç temel dalga şeklinde evrilmiştir. Birinci Dalga, ampirik davranış ilkelerine odaklanmakta, gözlemlenebilir davranışların doğrudan değişimini hedeflemektedir. Bu yönüyle ampirik temele dayanmayan yaklaşımlara bir tepki olarak doğmuştur. İkinci Dalga, bilişsel ve sosyal öğrenme kuramlarının entegrasyonu ile davranışsal hedeflerin yanına bilişsel süreçleri de eklemektedir. Böylece düşünce ve inanç sistemlerini terapötik sürecin önemli bir parçası haline getirmektedir. Zamanla bilimsel ve felsefî paradigmada yaşanan değişimler, bu iki dalganın sınırlarını genişletmiş ve Üçüncü Dalga terapilerin doğuşuna zemin hazırlamıştır. Bu dalga içerisinde en çok öne çıkan yaklaşımlardan biri Kabul ve Kararlılık Terapisi (Acceptance and Commitment Therapy – ACT) olmuştur (Hayes, 2004).

ACT'nin temelleri 1980'li yılların başında atılmış, ilk dönemlerinde “kapsamlı uzaklaşma” olarak adlandırılmıştır. 1990'lı yıllarda bağımsız bir model haline gelen ACT, İngilizce kısaltmasıyla “eylemde bulunma, harekete geçme” anlamlarına da gönderme yapmaktadır. Model, üç temel süreç üzerine kuruludur: A = Düşünce ve duygularını kabul et, anı deneyimle (Accept), C = Değerlerin doğrultusunda bir eylem seç (Commit) ve T = Harekete geç (Take action) (Harris, 2016).

ACT, insan dili ve bilişinin deneysel analizi olan İlişkisel Çerçeve Kuramı'na (Relational Frame Theory – RFT) dayanmaktadır. Bu kuram, doğrudan değişim yerine kabulü, psikolojik esnekliği ve değerler doğrultusunda eyleme geçmeyi temel alan bir müdahale yaklaşımı sunmaktadır (Hayes, 2004). ACT'a göre birçok psikolojik sorun ve duygusal sıkıntının temelinde insan dili yatmaktadır. Bu nedenle yaklaşım, dilin bireyin yaşantısındaki işlevine odaklanır ve bireyin dili daha işlevsel biçimde kullanabilmesine yardımcı olmayı amaçlamaktadır. RFT, insanların dünyayı “ilişkisel” biçimde kavradığını öne sürer ve bu yönüyle dil ve biliş üzerine yapılan davranışsal araştırmalardan beslenir (Köroğlu, 2011).

ACT'ın temel amacı, bireyin yaşamını anlamlı ve doyumlulu bir şekilde sürdürmesine destek olmak; yaşamın doğal bir parçası olan acı ve sıkıntılardan kaçınmak yerine, bunları kabul edebilmesini sağlamaktır (Harris, 2017).

ACT'a göre, acı verici duygu ve düşüncelerden kaçınmak ya da onları bastırmaya çalışmak yerine, bu deneyimlerin birey üzerindeki etkisini azaltmak ve onların yaşam üzerindeki

belirleyiciliğini zayıflatmak önemlidir. Bu nedenle ACT, bireyin acı verici duygu ve düşüncelerle birlikte yaşayabilmeyi öğrenmesini temel bir süreç olarak görmektedir (Harris, 2016).

Hayes vd. (2006) ACT'ı, bireyin yaşadığı temel psikolojik sorunları, genel olarak psikolojik esnekliği artırma hedefi doğrultusunda ele almaktadır. Psikolojik esneklik; bireyin bilinçli bir şekilde şimdiki anla tam temas kurabilmesi ve değerleri doğrultusunda, gerektiğinde davranışlarını değiştirebilme veya sürdürebilme kapasitesi olarak tanımlanmaktadır. ACT'a göre bu esnekliğin gelişimi, altı temel süreç aracılığıyla gerçekleşmektedir. Bu süreçlerin her biri yalnızca psikopatolojiden uzaklaşmayı değil, aynı zamanda bireye işlevsel ve olumlu psikolojik beceriler kazandırmayı amaçlayan yapılar olarak kavramsallaştırılmaktadır.

Hayes vd. (2006)'ya göre bu altı süreç, pozitif psikolojik beceriler olarak kavramsallaştırılmış olup, Farkındalık ve Kabul Süreçleri ile Kararlılık ve Davranış Değişikliği Süreçleri şeklinde iki ana başlık altında toplanmaktadır.

Bunlardan ilki olan farkındalık ve kabul süreçleri; uygulanabilir bir davranışsal farkındalık (mindfulness) tanımını sağlamakta ve kabul, ayrışma ve şimdiki anla temas bölümlerinden oluşmaktadır. Kabul (Acceptance); deneyimsel kaçınmaya bir alternatif olarak öğretilen temel bir süreç olarak tanımlanmaktadır. Kişinin geçmişi tarafından tetiklenen özel olayları (duygular, düşünceler, duyular) aktif ve bilinçli bir şekilde kucaklamayı içerir. Bu süreç, bu özel olayların sıklığını veya biçimini değiştirmeye yönelik gereksiz çabalar olmaksızın, özellikle bu çabaların psikolojik zarara yol açacağı durumlarda, deneyimin farkında olmayı hedeflemektedir. Kabul, kendiliğinden bir amaç değil, değer temelli eylemi artırmanın bir yöntemi olarak düşünülmektedir. Bilişsel ayrışma / defüzyon (Cognitive Defusion) süreci tekniklerinin temel amacı, düşünceleri ortadan kaldırmak veya azaltmak değil; düşüncelerin sahip olduğu davranışsal etki gücünü değiştirmektir. Bu yaklaşım, bireyin kendi düşünceleriyle kurduğu etkileşimin niteliğini farklılaştırarak, düşünce ile gerçeklik arasındaki bağı çözmektedir. Birey, düşünceye 'bakılan bir gerçeklik' penceresinden bakmak yerine, onu 'deneyimlenen bir süreç' olarak fark etmeyi öğrenmektedir. Böylece, düşüncelerin içeriğine duyulan otomatik inanç azalmakta ve birey, olumsuz bilişsel içeriklerin kontrolünden uzaklaşarak daha esnek bir gözlemci konumuna geçmektedir. Şimdiki anla temas (Contact with the Present Moment / Being Present) sürecinde ACT, psikolojik ve çevresel olaylarla sürekli ve yargılayıcı olmayan bir temas kurulmasını teşvik etmektedir. Bu süreçte, danışanların dünyayı daha doğrudan deneyimlemesini sağlamak, davranışlarının daha esnek hale gelmesi ve eylemlerinin sahip oldukları değerlerle daha tutarlı olması amaçlanmaktadır (Hayes vd., 2006). İkinci başlık olan kararlılık ve davranış değişikliği süreçleri; yaşam kalitesini artırmak için eyleme odaklanmaktadır. Bu süreç; bağlam olarak benlik, değerler ve kararlı eylem bölümlerini içermektedir. Bağlam olarak benlik (Self as Context) kavramı, bireyin deneyimlerin akışına (düşünce ve duygulara) içerik olarak değil, bir bakış açısı veya konum olarak farkında olmasını sağlayan aşkın bir benlik duygusu olarak tanımlanmaktadır. Değerler (Values) kavramı ACT açısından, amaçlı eylemin seçilmiş nitelikleri olarak tanımlanmaktadır. Bir nesne olarak elde edilemeyecek, ancak yaşayarak somutlaştırılabilen yaşam yönleri olarak görülmektedir. ACT, kaçınma, sosyal uyum veya bilişsel füzyon kaynaklı seçimleri zayıflatarak, danışanın yaşamın çeşitli alanlarında (kariyer, aile, maneviyat vb.) yaşam yönlerini seçmesine yardımcı olmak için çeşitli alıştırımlar kullanmaktadır. Kararlı eylem (Committed Action) süreci, birey için seçtiği değerlere bağlı olan, giderek daha büyük ve etkili eylem kalıplarının geliştirilmesini teşvik etmektedir. Kararlı eylem, maruz bırakma, beceri edinimi ve hedef belirleme gibi davranışsal olarak tutarlı davranış değiştirme yöntemlerini ACT protokolüne dahil etmektedir. Bu eylem çabaları, kişinin diğer ACT süreçleri (kabul, ayrışma vb.) aracılığıyla ele alınacak psikolojik engellerle temas etmesine yol açmaktadır (Hayes vd., 2006).

Literatür incelendiğinde üçüncü dalga davranışçı terapiler arasında etkililiği incelenen yaklaşımlar arasında ACT bulunmaktadır. ACT'ın etkililiği öz şefkat, duygusal yeme davranışı,

başa çıkma yeterliği, yaşamın anlamı, benlik saygısı, psikolojik uyum, beden imgesi esnekliği, sosyal görünüş kaygısı, olumsuz değerlendirilme korkusu, sınav kaygısı ve akran zorbalığı gibi birçok değişken açısından incelenmiştir (Kayacan & Bingöl, 2023). Akran zorbalığı ile ACT temelli çalışmaların literatürde detaylı şekilde incelenmesine ihtiyaç olduğu görülmüştür. Bu araştırmada ergenlik döneminde akran zorbalığı ve ACT temelli araştırmaların incelenmesine odaklanılmıştır. Bu doğrultuda konu ile ilgili kaynaklar sistematik bir şekilde taranmıştır ve çalışmanın alanyazındaki bilgi birikimine katkı sunması, ileride yapılacak olan çalışmalara kuramsal bir zemin oluşturması hedeflenmektedir.

Bu araştırmanın amacı; ergenlik döneminde akran zorbalığı probleminin ACT temelli incelendiği araştırmaların incelenmesidir. Ergenlik döneminde akran zorbalığını ACT temelli inceleyen araştırmalarda aşağıdaki sorulara yanıt aranmıştır:

- 1) Örneklem ve katılımcılar kimlerdir?
- 2) Kullanılan araştırma desenleri nelerdir?
- 3) Müdahale programlarının oturumlarının süreleri ve içerikleri nasıldır?
- 4) Müdahale programları hangi teknik ve yöntemlere dayanmaktadır?
- 5) Çalışmalarda kullanılan ölçme araçları nelerdir?
- 6) Müdahalelerin etkililiğine ilişkin ulaşılan bulgular nasıl sonuçlar ortaya koymuştur?

YÖNTEM

Araştırma Modeli

Bu araştırma, Türkiye’ de ve yurt dışında , ergenlik döneminde akran zorbalığını inceleme, önleme veya azaltmada Kabul ve Kararlılık Terapisi (ACT) temelli çalışmaların etkililiğini deneysel, yarı deneysel ve deneysel olmayan araştırma desenleri kullanılarak inceleyen çalışmaların özelliklerinin incelenmesini kapsayan bir sistematik gözden geçirme çalışmasıdır. Bu çalışmada sistematik gözden geçirme işlemi PRISMA rehberi (Moher, Libertai, Tetzlaff, Altman ve PRISMA Group, 2009) kullanılarak yapılmıştır. Literatür, Web Of Science , Google Scholar ve Dokuz Eylül Üniversitesi (DEÜ) Vetis veri tabanları kullanılarak, İngilizce ve Türkçe makaleler belirlenen anahtar sözcüklerle (Ergenlik, Akran Zorbalığı, Kabul ve Kararlılık Terapisi) taranmıştır.

Dâhil Etme ve Dışlama Kriterleri


Alan yazında yapılan tarama sonucunda ulaşılan tüm makaleler, araştırmanın amacı doğrultusunda belirlenen aşağıdaki dâhil etme ve dışlama kriterlerine göre PRISMA rehberi kullanılarak değerlendirilmiştir. Dâhil etme için kriterler olarak (1) Kabul ve Kararlılık Terapisi uygulamalarının etkililiğini inceleyen deneysel, yarı deneysel ve deneysel olmayan çalışmalar, (2) ergenlik dönemine yönelik yapılan çalışmalar, (3) akran zorbalığı davranışlarını inceleme, önleme veya azaltmaya yönelik çalışmalar, (4) Türkçe veya İngilizce dillerinde tam metin ulaşılan çalışmalar olarak belirlenmiştir. Dışlama için kriterler olarak (1) çocuklar ve yetişkinler ile yapılan çalışmalar, (2) Türkçe ve İngilizce olmayan çalışmalar, (3) tam metnine ulaşılamayan çalışmalar (4) ACT’ı temel almayan çalışmalar olarak belirlenmiştir.

Anahtar kelimelerle yapılan tarama sonucunda toplam 329 çalışmaya ulaşılmıştır. Tarama verileri tarama motorlarına göre Google Scholar (n:152), Web of Science (n:100), Deü Vetis (n:77) dağılım göstermiştir. Dâhil etme ve dışlama kriterleri doğrultusunda yapılan elemeler sonucunda araştırma kapsamına, toplam 3 (üç) çalışma dâhil edilmiştir. Araştırmaya dahil edilen çalışmaların sistematik bir şekilde gözden geçirilme ve seçim aşamalarını gösteren PRISMA akış şeması şekil 1’de gösterilmektedir.

Veri Analizi

Derlemeye dahil edilecek çalışmaların seçimi, nesnel ve sistematik bir yaklaşımla yürütülmüştür. Bu kapsamda, belirlenen dahil etme ölçütlerine uygun olan tüm makalelerin başlık ve özetleri, araştırma ekibinde yer alan yazarlar tarafından incelenmiştir. Değerlendirme

sürecinde yayınların her biri en az iki araştırmacı tarafından gözden geçirilmiştir. Nihai olarak araştırma konusu ile ilişkili 3 (üç) çalışma derleme kapsamına alınmıştır.



Şekil 1. PRISMA Akış Şeması

BULGULAR

Literatürde Ergenlik Döneminde Akran Zorbalığı ve ACT ile ilgili çalışmalar incelenmiş; elde edilen araştırmalar Tablo 1’de verilmiştir.

Tablo 1. *Ergenlik Döneminde Akran Zorbalığı ve ACT ile ilgili yapılan çalışmalar*

Yazar-Yıl	Yer	Örneklem	Yöntem	Bulgular	Sonuç
Abdullah YALNIZ (2019)	Türkiye	Çorum İlinde MEB'e bağlı bir lisede öğrenim gören 232 öğrenciden Akran Zorbalığı Belirleme Ölçeğinde zorba ve mağdur puanı yüksek çıkan öğrencilerden seçilen 24 öğrenci (12 kişi deney grubu, 12 kişi kontrol grubu)	Ön test-son test kontrol gruplu yarı deneysel desen	Uygulanan psikoeğitim sonrası deney grubunun zorbalık davranışları sergilemede azalma ve zorbalıkla baş etme becerilerini geliştirmede etkili olduğu bulunmuştur.	ACT temelli Psikoeğitim Programı'nın, deney grubundaki ergenlerin hem zorbalık yapma hem de zorbalığa maruz kalma düzeylerini azaltmada anlamlı derecede etkili olduğu ve bu etkinin kalıcı olduğu görülmüştür.
Büşra KABAKÇI (2021)	Türkiye	İç Anadolu Bölgesinde devlet üniversitesi çeşitli bölümlerinde öğrenim gören 561 (473 kız ve 88 erkek) üniversite öğrencisi	İlişkisel tarama modeli	Siber zorbalığa ilişkin duyarlılık ile psikolojik katılık arasında pozitif yönlü anlamlı bir ilişki bulunmuştur. İnternet bağımlılığı ve siber zorbalığa ilişkin duyarlılığın psikolojik katılık puanları üzerinde yordayıcı olduğu bulunmuştur.	İnternet bağımlılığı ve siber zorbalığa ilişkin duyarlılığın öğrencilerin psikolojik katılık puanlarını yordayıcı olduğu sonucu ortaya konmuştur.
Farzaneh Ranjbar Noushari vd (2023)	İran	Rasht şehrinde bir ortaokuldaki Zorbalık Ölçeği ortalamalarına göre belirlenen 30 erkek öğrenci (15 kişi deney grubu, 15 kişi kontrol grubu)	Ön test-son test kontrol gruplu yarı deneysel desen	Uygulanan ACT temelli psikoeğitim sonrası zorbalık davranışı gösteren öğrencilerin psikolojik sermayesi ve bu sermayenin alt boyutları anlamlı düzeyde artmıştır.	ACT, öğrencilerin psikolojik esnekliğini artırarak; onların psikolojik sermaye ve alt boyutlarından umut, dayanıklılık, iyimserlik ve öz yeterlilik becerilerine katkı sağladığı görülmektedir.

TARTIŞMA VE SONUÇ

Bu sistematik derleme çalışması, ergenlerde akran zorbalığını ve ACT temelli araştırmaların etkililiğini ve yaygınlığını bütüncül bir bakış açısıyla değerlendirmeyi amaçlamıştır. Çalışmaya dahil edilen araştırmaların analizi sonucunda; ACT müdahalelerinin, zorbalığa maruz kalan ergenlerin baş etme becerilerini güçlendirmede ve zorbalık davranışlarının azalmasında etkili olduğu görülmektedir.

Anahtar kelimeler ile sistematik bir şekilde yapılan araştırma sonucunda ergenlik döneminde akran zorbalığı ACT temelli çalışmalar hakkında detaylı incelemeler yapılmış, ancak dahil etme ve dışlama kriterleri sonrasında ancak 3(üç) araştırma çalışmaya dahil edilebilmiştir. Sistematik inceleme sırasında konu ile ilgili literatürde çok az araştırma bulunduğu göz önünde bulundurularak konu hakkında araştırmalara ihtiyaç olduğu görülmektedir.

Çalışma kapsamında incelenen araştırmalardan birisi Yalnız'ın (2019) tez çalışmasıdır. Yalnız bu çalışmada bir lisede öğrenim gören 232 öğrenciden Akran Zorbalığı Belirleme Ölçeğinde zorba ve mağdur puanı yüksek çıkan öğrencilerden seçilen 24 öğrenci ile ön test-son test kontrol gruplu yarı deneysel desen kullanarak araştırma gerçekleştirmiştir. Araştırmada ölçek olarak araştırmacının geliştirdiği “Kişisel Bilgi Formu” ve Pişkin ve Ayas (2007) tarafından geliştirilen “Akran Zorbalığı Belirleme Ölçeği Ergen Formu” kullanılmıştır. Bu tez çalışmasında araştırmacı 10 oturumluk ACT temelli müdahale teknik ve yöntemleri içeren psiko-eğitim programı geliştirmiş ve psko-eğitim programını deney grubuna uygulamıştır. Psiko-eğitim oturumları haftada bir kez her bir oturum 90 dk olacak şekilde uygulanmıştır. Program oturumları (1) tanışma; (2) varoluşsal değer ve kendini tanıma; (3) düşünce, duygu ve davranış ilişkisi; (4) stres, kaygı ve yılmazlık; (5) psikolojik esneklik ve farkındalık; (6) zorbalık türleri ve yöntemleri; (7) izolasyon ve sosyal dışlanma; (8) empati ve sosyal beceriler; (9) sınır koyma ve atılmalık; (10) sonlandırma başlıkları ile oluşturulmuş ve uygulanmıştır. Çalışmanın bulguları, ACT Yönelimli Psiko-eğitim Programı'nın ergenlerdeki akran zorbalığı üzerinde hem zorba hem de kurban boyutunda iyileştirici ve önleyici etkilerinin güçlü olduğunu ortaya koymaktadır. Araştırmaya katılan deney grubundaki öğrencilerin psko-eğitim uygulaması sonrasında hem zorba olma hem de zorbalığa maruz kalma puanlarında istatistiksel olarak anlamlı düşüşler olduğu görülmektedir. Bununla birlikte psiko-eğitim programının zorbalığın alt boyutlarından fiziksel zorbalık, sözel zorbalık, dışlama, eşyalara zarar verme ve söylenti yayma boyutlarında da etkili olduğu sonucuna ulaşılmıştır. Bulunan etkinin kalıcılığını araştırmak için 2 ay sonra yapılan izleme testi sonuçlarına göre de zorbalık ve mağduriyet puanlarındaki düşüşün devam ettiği görülmektedir. Bu durum, öğrencilerin kazandıkları kabul, ayırışma, anda olma, değerler gibi becerileri yaşamlarına yansıtarak davranış değişikliğinin kalıcı olduğu sonucunu ortaya koymaktadır.

İncelenen bir diğer çalışma Kabakçı'nın (2021) üniversite öğrencilerinde psikolojik katılık, internet bağımlılığı ve siber zorbalığa ilişkin duyarlılık arasındaki ilişkileri inceleyen yüksek lisans tez çalışmasıdır. Araştırmada Kabakçı (2021), internetin yanlış kullanımının bireylerin siber zorbalığa ilişkin duyarlılığı ve ACT için önemli kavramlardan olan psikolojik katılık üzerindeki etkilerini analiz ederek bu değişkenlerin birbirini nasıl yordadığını belirlemeyi amaçlamaktadır. İlişkisel tarama modeli kullanılmış betimsel bir araştırmadır. Araştırma için katılımcıların mevcut durumlarına ölçmek amacıyla Yavuz ve arkadaşları (2016) tarafından Türkçe'ye uyarlanan “Kabul ve Eylem Formu-2”, Kutlu ve arkadaşları (2016) tarafından Türkçe'ye uyarlanan “Young İnternet Bağımlılığı Testi Kısa Formu”, Tanrıku ve arkadaşları (2013) tarafından geliştirilen “Siber Zorbalığa İlişkin Duyarlılık Ölçeği” ve araştırmacı tarafından geliştirilen “Kişisel Bilgi Formu” ölçekleri kullanılmıştır. Araştırmanın örneklemini 2020-2021 eğitim-öğretim yılında İç Anadolu Bölgesi'ndeki bir devlet üniversitesinin çeşitli bölümlerinde öğrenim gören 473'ü kadın, 88'i erkek olan 561 üniversite öğrencisi oluşturmaktadır. Araştırmada bir teknik yada müdahale uygulanmamıştır, psikolojik katılık kavramı ACT temelli bir kavram olduğu için araştırma ACT üzerinden ve psikolojik esneklik ile birlikte temellendirilmiştir. Araştırma bulguları arasında, internet bağımlılığı ve siber zorbalığa ilişkin duyarlılığın, öğrencilerin psikolojik katılık düzeylerini anlamlı bir şekilde yordadığı bulunmuştur. Araştırma sonuçları internet bağımlılığı ve siber zorbalığa ilişkin duyarlılık arttıkça, öğrencilerin psikolojik katılık puanları da arttığını ortaya koymaktadır. Araştırma; internet ortamında geçirdiği zaman fazla olan ve siber risklere karşı aşırı duyarlı olan bireyin psikolojik esnekliğinin zayıflayarak psikolojik katılığının beslediğini göstermektedir.

Noushari ve arkadaşları'nın (2023) araştırmasında; ACT'ın okullarda zorbalık yapan öğrencilerin psikolojik sermaye düzeyleri üzerindeki etkisi özyeterlik, umut, dayanıklılık ve iyimserlik alt boyutları ile birlikte incelenmektedir. Çalışmada zorbalık davranışlarının önlenmesinde öğrencilerin içsel kaynaklarını geliştiren üçüncü dalga psikoterapi yöntemlerinin

önemi vurgulanmaktadır. Araştırmanın örneklemini 2022-2023 eğitim-öğretim yılında İran'ın Rasht şehrindeki bir ortaokulda öğrenim gören erkek öğrencilerden seçilmiş 30 öğrenci (15 kişi deney grubu, 15 kişi kontrol grubu) oluşturmaktadır. Örneklem Zorbalık Ölçeği'nden ortalamanın üzerinde puan alan öğrencilere göre amaçlı örnekleme yöntemi ile seçilmiştir. Araştırma modelinin, ön test- son test kontrol gruplu yarı deneysel desen olduğu görülmektedir. Çalışmada ölçek olarak Espelage ve Holt (2001) tarafından geliştirilen "Zorbalık Ölçeği", Luthans ve arkadaşları (2007) tarafından geliştirilen psikolojik sermayeyi özyeterlik, umut, dayanıklılık ve iyimserlik alt boyutları ile birlikte ölçen "Psikolojik Sermaye Anketi" kullanılmıştır. Araştırmacılar tarafından Hayes, Strosahl ve Wilson'ın (1999) tedavi protokolüne göre yapılandırılmış ACT temeline dayanan 8 oturumluk müdahale programı oluşturulmuş ve deney grubuna uygulanmıştır. Müdahale programı oturumlarının haftada 2 oturum şeklinde her biri 90 dk sürecek şekilde planlandığı ve uygulandığı görülmektedir. Oturum içeriklerinin (1) tanışma ve terapotik ilişkinin kurulması; (2) "yaratıcı umutsuzluk" kavramının vurgulanması, kontrol etmeye çalışmanın çözüm değil, problemin kendisi olduğu anlayışının geliştirilmesi; (3) bireysel olarak değerlerin tanımlanması, değerler, eylemler ve engeller hakkında farkındalık oluşturma; (4) bireylerin değerlerinin incelenmesi ve değerler hakkında metaforların kullanılması; (5) bilişsel birleşme ve ayrışma kavramlarının incelenmesi, metaforlar kullanılarak ayrışma egzersizlerinin yapılması; (6) rol ve bağlam kavramlarının açıklanması; (7) "şimdiki anda olma" kavramına vurgu yapılması; (8) kararlılık öğretimi, hayat öykülerinin incelenmesi, değerlere uygun davranışsal planların oluşturulması ve kapanış şeklinde oluşturulduğu görülmektedir. ACT'da yer alan tekniklerden kabul ve farkındalık, bilişsel ayrışma, değer odaklı eylem ve metafor kullanımı gibi teknikler ile öğrencilerin rahatsız edici duygu ve düşüncelerle savaşmak yerine bunları kabullenmelerini, anı yaşamalarını ve kendi değerleri doğrultusunda kararlı adımlar atmalarını sağlayan bir program oluşturulmuştur. Müdahale programı uygulanan deney grubunun toplam psikolojik sermaye puan ortalamasının eğitim öncesinde 79.53 iken, eğitim sonrasında 95.67'ye yükseldiği görülmektedir. Araştırma bulgularına göre ACT temelli müdahale programının zorbalık gösteren ortaokul öğrencileri üzerinde psikolojik sermayelerini arttırmada çok yüksek düzeyde etkili olduğu sonucuna ulaşılmaktadır. Psikolojik sermayeyi oluşturan alt boyutlar incelendiğinde en yüksek etki boyutunun dayanıklılık alt boyutunda gerçekleştiği görülmektedir. ACT temelli müdahale programı ile öğrencilerin psikolojik esnekliğinin arttığı ve rahatsız edici duygu ve düşüncelerden kaçınmak yerine, onları kabullenmeyi öğrendikleri; düşüncelerini kesin gerçekler olarak görmek yerine, onları sadece "düşünce" olarak görmeyi fark ettikleri ve böylece dürtüsel davranışlarının azaldığı; anlık dürtülerle hareket etmek yerine, kendi belirledikleri bireysel değerleri doğrultusunda eylemlerde bulunmayı öğrendikleri sonuçları ortaya koyulmaktadır. Araştırmacılar ACT'ın okullarda zorbalıkla mücadelede etkili bir müdahale yöntemi olarak kullanılabileceği sonucuna ulaşmışlardır.

Araştırmaya dahil edilen 3 çalışmada da ergenlik döneminde akran zorbalığı önleme ve müdahale çalışmalarında ACT yönelimli çalışmaların etkili olduğu görülmektedir.

Yalnız (2019) ile Noushari ve arkadaşlarının (2013) çalışmalarında ACT temelli müdahale programları geliştirerek öğrencilerin akran zorbalığı davranışları üzerindeki etkisini istatistiksel olarak incelemektedirler. Her iki çalışma sonucunda da araştırmacıların geliştirdikleri ve örneklem grubuna uyguladıkları ACT yönelimli müdahale programları akran zorbalığının önlenmesi ve azaltılmasında etkili olduğu görülmektedir. Kabakçı (2021) araştırmasında ACT kavramlarından olan psikolojik esneklik kavramının karşıtı olan psikolojik katılığın yüksek olmasının, siber zorbalığa ilişkin duyarlılık ve internet bağımlılığı ile pozitif yönde ilişkili olduğunu ortaya koymuştur. Bu sonuç ile psikolojik katılık düzeyi arttıkça, siber zorbalık dinamiklerine yakınlık düzeyi de artmaktadır sonucuna ulaşılmaktadır.

Araştırmaya dahil edilen çalışmaların içeriğinde ergenlerde akran zorbalığı ile baş etmede psikolojik esneklik becerisi geliştirmenin önemine vurgu yapıldığı görülmektedir. Bu da Hayes

vd.'nin (2006) ACT'ı, bireyin yaşadığı temel psikolojik sorunları, genel olarak psikolojik esnekliği artırma hedefi doğrultusunda ele aldığı görüşünü destekler niteliktedir.

Araştırmaların çalışma gruplarına bakıldığında ortaokul, lise ve üniversite öğrenci grupları ile çalışıldığı görülmektedir. Her grup için ACT yönelimli çalışmaların akran zorbalığı ile ilgili etkililiği kanıtlanmaktadır.

Araştırmaya dahil edilen çalışmaların ortak sonucu olarak; ACT temel alınarak yapılan uygulamalar ile, ergenlerin psikolojik esnekliklerinin artırılması veya psikolojik katılıklarının azaltılması, zorbalık davranışlarını azaltmada, zorbalık ile baş etme ve psikolojik dayanıklılıklarını artırmada etkili ve önemli bir araç olduğu söylenebilmektedir. Ancak ulaşılan çalışma sayısının azlığı, ACT ve ergenlerde akran zorbalığı ilişkisinin literatürde henüz yeterince araştırılmamış bir alan olduğunu göstermektedir. Bu doğrultuda, ACT'ın önleyici ve iyileştirici etkisini daha fazla ortaya koyabilmek için geniş örneklemli, boylamsal ve randomize kontrollü deneysel araştırmalara ihtiyaç duyulduğu düşünülmektedir. Gelecek araştırmaların ACT yönelimli ve okul temelli önleyici psikolojik danışmanlık ve rehberlik programlarına entegre edilmesi alana önemli katkılar sunacaktır.

KAYNAKÇA

- Aydın, Y. E., & Kıran, B. (2024). *Ergenlerin intihar düşünceleri ve olasılığını azaltmaya yönelik Kabul ve Kararlılık Terapisi temelli psikoeğitim programı: Ruh sağlığı çalışanları için bir rehber*. Serüven Yayınevi.
- Büyükebeci, G. (2022). Çocuk ve ergenlerde dikkat eksikliği ve hiperaktivite bozukluğu. F. Savi Çakar (Ed.), *Çocuk ergen ruh sağlığı: Davranış bozukluklarında tanılama ve tedavi yaklaşımları* içinde (ss. 87-109). Pegem Akademi.
- Cantone, E., Piras, A. P., Vellante, M., Preti, A., Danielsdóttir, S., D'Aloja, E., Lesinskiene, S., Angermeyer, M. C., Carta, M. G., & Bhugra, D. (2015). Interventions on bullying and cyberbullying in schools: A systematic review. *Clinical Practice & Epidemiology in Mental Health*, 11(Suppl 1), 58–76. <https://doi.org/10.2174/1745017901511010058>
- Erikson, E. H. (1968). *Identity: Youth and crisis*. W. W. Norton & Company.
- Erikson, E. H. (2009). *Kimlik: Gençlik ve kriz* (J. Çetinkaya, Çev.). Metis Yayınları.
- Halliday, S., Gregory, T., Taylor, A., Digenis, C., & Turnbull, D. (2021). The impact of bullying victimization in early adolescence on subsequent psychosocial and academic outcomes across the adolescent period: A systematic review. *Journal of School Violence*, 20(3), 351–373. <https://doi.org/10.1080/15388220.2021.1913598>
- Harris, R. (2016). *Mutluluk tuzağı* (Ç. Şaher, H. T. Karatepe & K. F. Yavuz, Çev.). Litera Yayıncılık.
- Harris, R. (2017). *ACT'i kolay öğrenmek* (H. T. Karatepe & K. F. Yavuz, Çev.). Litera Yayıncılık.
- Hayes, S. C. (2004). Acceptance and commitment therapy, relational frame theory, and the third wave of behavioral and cognitive therapies. *Behavior Therapy*, 35, 639–665. [https://doi.org/10.1016/S0005-7894\(04\)80013-3](https://doi.org/10.1016/S0005-7894(04)80013-3)
- Hayes, S. C., Luoma, J. B., Bond, F. W., Masuda, A., & Lillis, J. (2006). Acceptance and Commitment Therapy: Model, processes and outcomes. *Behaviour Research and Therapy*, 44(1), 1–25.
- Hymel, S., & Swearer, S. M. (2015). Four decades of research on school bullying: An introduction. *American Psychologist*, 70(4), 293–299. <https://doi.org/10.1037/a0038928>
- İkiz, F. E. (2022). Çocuk ergen ruh sağlığı ve psikopatolojisi. F. Savi Çakar (Ed.), *Çocuk ergen ruh sağlığı: Davranış bozukluklarında tanılama ve tedavi yaklaşımları* içinde (ss. 1-35). Pegem Akademi.

- Kabakcı, B. (2021). *Üniversite öğrencilerinin psikolojik katılıklarının yordanmasında internet bağımlılığı ve siber zorbalığa ilişkin duyarlılığın rolü* [Yüksek lisans tezi, Necmettin Erbakan Üniversitesi].
- Kayacan, İ., & Yılmaz Bingöl, T. (2023). Kabul ve kararlılık terapisi temelli psiko-eğitim programlarına bir bakış: Ulusal tezlerin derlenmesi. *Journal of Sustainable Educational Studies (JSES)*, (Ö2), 97-107.
- Köroğlu, E. (2011). *Bilişsel-davranışçı psikoterapiler: Temel kavramlar, temel yaklaşımlar* (2. Baskı). HYB Basım Yayın.
- Menesini, E., & Salmivalli, C. (2017). Bullying in schools: The state of knowledge and effective interventions. *Psychology, Health & Medicine*, 22(S1), 240–253. <https://doi.org/10.1080/13548506.2017.1279740>
- Menken, M. S., Isaiah, A., Liang, H., Rodriguez Rivera, P., Cloak, C. C., Reeves, G., Lever, N. A., & Chang, L. (2022). Peer victimization (bullying) on mental health, behavioral problems, cognition, and academic performance in preadolescent children in the ABCD Study. *Frontiers in Psychology*, 13, Article 925727. <https://doi.org/10.3389/fpsyg.2022.925727>
- Olweus, D. (2013). School bullying: Development and some important challenges. *Annual Review of Clinical Psychology*, 9, 751–780. <https://doi.org/10.1146/annurev-clinpsy-050212-185516>
- Ranjbar Noushari, F., Rasoolzadeh, B., Baradaran, M., Sedaghat, N., & Makvandi, L. (2023). The effect of Acceptance and Commitment Therapy on psychological capital promotion in bullied students. *Journal of Preventive Counselling*, 4(4), 133–145. <https://doi.org/10.22098/JPC.2023.13216.1175>
- Santrock, J. W. (2020). *Ergenlik* (14. basımdan çeviri) (D. M. Siyez, Çev. Ed.). Nobel Akademik Yayıncılık. (Orijinal eserin yayın tarihi 2012).
- Tsaousis, I. (2016). The relationship of self-esteem to bullying perpetration and peer victimization among schoolchildren and adolescents: A meta-analytic review. *Aggression and Violent Behavior*, 31, 186–199. <https://doi.org/10.1016/j.avb.2016.09.005>
- World Health Organization. (2019). *Coming of age*. <https://www.who.int/news-room/spotlight/coming-of-age-adolescent-health>
- Yalnız, A. (2019). *Kabul ve Kararlılık Terapisi yönelimli psikoeğitim programının akran zorbalığı üzerindeki etkisi* [Doktora tezi, Sakarya Üniversitesi].

**ERGENLERDE STRES VE DUYGUSAL ZEKÂ ARASINDAKİ İLİŞKİ:
SİSTEMATİK GÖZDEN GEÇİRME**

Prof.Dr. Fatma Ebru İKİZ¹

 : 0000-0003-4381-1658

Yusuf Erdem YILDIZ²

 : 0009-0003-8521-7769

¹Dokuz Eylül Üniversitesi, Eğitim Bilimleri Enstitüsü

²Dokuz Eylül Üniversitesi, Eğitim Bilimleri Enstitüsü

ÖZET

Ergenlik dönemi kimlik arayışı, akademik baskılar, sosyal ilişkilerdeki değişimler ve yoğun duygulanımlar gibi önemli stres kaynaklarına sahiptir. Ergen bireylerin sıklıkla deneyimlediği stres bireylerin günlük yaşamda algıladıkları tehditlere verdikleri bir tepkidir. Duygusal zeka kendi ve başkalarının duygularını anlama, yönetme ve kullanma yeteneğidir. Bu çalışmanın amacı ergenlerde stres ve duygusal zeka arasındaki ilişkileri inceleyen çalışmaları sistematik şekilde gözden geçirmektir. Bu çalışmanın yöntemi, sistematik gözden geçirme olup Web of Science veri tabanında “adolescents”, “stress” ve “emotional intelligence” kavramları aratılarak dahil etme ve dışlama kriterlerinin uygulanması sonucunda 17 çalışma incelenmiştir. Ele alınan çalışmalar örneklemeleri, araştırma desenleri, kullanılan ölçme araçları ve istatistiksel bulguları açısından incelenmiştir. Sonuçlar, duygusal zekanın tüm alt boyutlarının stresi azaltmada doğrudan etkisine rastlanmamış olsa da tüm çalışmalar da duygusal zeka ile stres arasında negatif ve anlamlı bir ilişki olduğu tespit edilmiştir.

Anahtar Kelimeler : Ergen, Stres, Duygusal Zekâ, Psikolojik Danışma

ABSTRACT

Adolescence involves significant stressors such as identity exploration, academic pressures, changes in social relationships, and intense emotions. The stress frequently experienced by adolescents is a response to perceived threats in their daily lives. Emotional intelligence is the ability to understand, manage, and utilise one's own and others' emotions. The aim of this study is to systematically review studies examining the relationship between stress and emotional intelligence in adolescents. The method of this study is a systematic review, and 17 studies were examined by searching the Web of Science database for the concepts of "adolescents", "stress" and "emotional intelligence" and applying inclusion and exclusion criteria. The studies were examined in terms of their samples, research designs, measurement tools used, and statistical findings. The results revealed that although no direct effect of all sub-dimensions of emotional intelligence on stress reduction was found, all studies identified a negative and significant relationship between emotional intelligence and stress.

Keywords: Adolescent, Stress, Emotional Intelligence, Psychological Counseling

Giriş

Ergenlik dönemi, bireyin biyolojik ve psikolojik olarak yoğun ve eş zamanlı değişimler yaşadığı kritik bir geçiş evresidir. Ergenlik, çocukluktan genç yetişkinliğe geçişteki toplumsal, bilişsel ve fiziksel değişimleri ifade eder (Çok, 2019; Meydan, 2021). Vücudun hızla büyüdüğü ve değiştiği, bununla birlikte bilişsel değişimlerin yaşandığı bir dönemdir. Piaget, ergenliğe geçişte bireyin artık somut işlemler döneminden soyut işlemler dönemine geçtiğini ifade eder (Günçe, 1973; Özgüngör, 2021). Çocuklukta düşünceler daha çok şimdi ve burada üzerinde dururken ergen ve yetişkin düşüncesinde “şimdi ve burada”nın yanı sıra mevcut olmayan olasılıkları göz önüne alma ve incelemeye yönelik eğilim ve yeteneği ortaya çıkmaktadır (Öngen, 1995). Bu yeni bilişsel beceri, yalnızca problem çözme potansiyelini artırmakla kalmaz, aynı zamanda potansiyel bir stres kaynağı da yaratır. Çünkü, zihin olası gelecek senaryolarını, başarısızlık ihtimallerini ve alınacak kararların uzun vadeli sonuçlarını işlemeye başladıkça, birey kaygı ve belirsizlik gibi duygusal yüklerle karşılaşır. Yani, ergenin soyut ve olasılıksal düşünme yeteneğinin gelişimi, beraberinde bilişsel bir farkındalık stresi getirir. Bu durum, ergenlikteki duygusal yoğunluğun ve strese duyarlılığın önemli bir nedenidir.

Erikson, Psikososyal Gelişim Kuramında ergenlik dönemini “Kimlik Kazanmaya Karşı Rol Karmaşası” evresi olarak tanımlamıştır (Bacıoğlu, 2023). Erik Erikson (1984)’a göre ergenlik döneminin temel psikososyal görevi olan Kimlik Kazanmaya Karşı Rol Karmaşası evresi, doğası gereği yüksek bir stres kaynağıdır. Birey, bu dönemde "Ben kimim?", "Neye inanıyorum?" ve "Gelecekte ne olacağım?" gibi kritik varoluşsal sorularla yüzleşir. Ergen, bu sorulara yanıt ararken, farklı rolleri, değerleri ve yaşam tarzlarını dener. Bu keşif süreci bir yandan gerekli olsa da bir yandan da büyük bir belirsizlik ve uyuşmazlık yaratır. Uyuşmazlıklar ve çatışmalar baskı yaratır. Ergenlik döneminden “bireyin, fizyolojik büyüme, zihinsel olgunlaşma ve sosyal sorumluluk konularında, kimlik krizini deneyimlemesi ve bu krizden geçmesi için gerekli ön koşulları ancak ergenlik döneminde geliştirir ve burada kriz ifadesinin kullanılması da dönemin gerilim ve stres faktörlerinin yoğun yaşandığı görüşünü destekler niteliktedir (Erikson, 1968; İkiz, 2025). Başarısızlık korkusu, reddedilme endişesi ve bir kimliğe bağlanamamanın yarattığı rol karmaşası, yoğun bir kaygı durumu yaratır ve ergenlikteki duygusal dalgalanmaların ve yüksek stres düzeyinin başlıca nedenlerinden biri haline gelir.

Bireyin çevresiyle kurduğu etkileşimde sıklıkla ve yoğun olarak deneyimlediği merkezi bir kavram olarak stres; bireyin tehdit edici unsurlarla karşı karşıya kaldığında verdiği biyolojik ve psikolojik bir tepkiyi (Tan ve Yip, 2018) ifade etmektedir. Stresin bu yaygınlığı, onu insan sağlığı ve sosyal ortama uyumu açısından kritik öneme sahip kılmaktadır. Özellikle ergenlik dönemi hızlı biyolojik, bilişsel ve psikososyal değişimlerin yaşandığı bir süreç olması nedeniyle, stresin ortaya çıkışına karşı yüksek düzeyde duyarlı bir evredir. Ergenlik döneminde ailenin yakın ilişkilerinden, arkadaş çevresinin yakın ilişkilerine geçiş; ebeveynlerinden uzaklaşarak bağımsızlığa yönelme; kimlik arayışı; cinsle ve sosyal rolüne uyum sağlama; ideal beni bulmaya yönelik özdeşleşme çabası; değişik, farklı ve yeni şeyler arama çabası; bedensel imajı kabul etme gibi yaşanılması zorunlu olan bir takım gelişimsel stresler de yaşanmaktadır (Baltaş ve Baltaş, 1991).

Literatürde ergen bireyler ve stres üzerinde yapılmış binlerce çalışmaya rastlanmaktadır. Yapılan çalışmaların çoğu ergenlerde genel algılanan stresi ölçerken (Luo vd., 2025; Fernandes vd., 2025; Nepocaty ch vd., 2024) kimisi ergenlik döneminin getirdiği birtakım sonuçlardan oluşabilecek özel bir takım stres türlerini incelemektedir. Birçok toplumda ergen yaş grubunun yoğun eğitimsel faaliyetlere maruz kalması nedeniyle sıkça rastlanan akademik stres (Wang vd., 2025; Gao, 2023; Gündoğan, 2023), aile sosyal desteğinden arkadaş sosyal desteğine

geçişin yaşandığı, kimlik belirleme sürecinin yaşandığı, cinsel ve sosyal rollerin öğrenildiği ve uyum sağlandığı bir dönem olması nedeniyle psikososyal stres (Blasberg vd., 2025; Deeb vd., 2024; Garbers vd., 2021), travmatik bir yaşam öyküsü sonrası oluşabilecek travma sonrası stres bozukluğunun ergenlik dönemindeki bireyler üzerinde incelendiği (Grass vd., 2025; Zhang vd., 2022; El-Khodary vd., 2020) pek çok çalışma bulunmaktadır. Stres, türü her ne olursa olsun bireyde biyolojik birtakım değişikliklere yol açması ve yoğunluğunun, sıklığının artması ile bireylerde patolojik veya psikopatolojik sonuçlara yol açma potansiyeline sahip olduğundan bu çalışmada stres türleri konusunda herhangi bir ayırım yapılmaksızın ergen bireylerde stresin ele alındığı tüm çalışmalar incelenmiştir.

Stres aynı zamanda psikopatolojinin ortaya çıkmasında ve şiddetlenmesinde merkezi bir rol oynayan temel bir tetikleyici ve sürdürücü faktör olarak kabul edilir. Gündelik yaşamdaki kronik baskılar veya travmatik olaylar, strese bağlı hormonların aşırı kullanımına yol açarak beyin yapısında, özellikle de duygusal düzenleme ve bilişten sorumlu olan prefrontal korteks ve hipokampus gibi bölgelerde olumsuz etkilere yol açar. Bu biyolojik etkileşimler, stresin sadece anlık bir tepki olmaktan çıkıp, bireyi depresyon, anksiyete bozuklukları ve travma sonrası stres bozukluğu (TSSB) gibi psikolojik rahatsızlıkların gelişimine karşı bireyi savunmasız hale getirdiğini göstermektedir. Bunu destekler nitelikte olan ve ABD'nin Kaliforniya Eyaletinde yapılan bir çalışmada erkek ergen alt gruplarında algılanan stresin artışı depresyon seviyesindeki artışı yordadığı tespit edilmiştir (Galaif vd., 2002). Yüksek stres seviyeleri, mevcut semptomları şiddetlendirme eğiliminde de olabilmektedir. Stresin hem biyolojik hem de psikolojik etkisi olduğu düşünüldüğünde biyolojik değişimlerin ve kimlik arayışının birlikte ve en yoğun yaşandığı ergenlik döneminde stres araştırmaları büyük önem taşımaktadır.

Duygusal dalgalanmaların yoğun yaşandığı bu dönemde özellikle duyguları ifade etme ve düzenleme becerilerinin önemi kendini göstermektedir. Bu becerileri genel anlamda çerçeveyen bir kavram olarak ise karşımıza “duygusal zeka” kavramı çıkmaktadır. Duygusal zeka terimini ilk kullanan kişiler olarak Mayer ve Salovey, duygusal zekanın uyum sağlayıcı yeteneklerin üç kategoriden oluştuğunu öne sürerler: duyguların değerlendirilmesi ve ifade edilmesi, duyguların düzenlenmesi ve problemlerin çözümünde duyguların kullanılması (Schutte vd., 1997; Avunduk, 2021). Bu becerilerin özellikle bireyin çevresi tarafından sosyal kabulüne katkı sunması beklenmektedir. Bunu destekler nitelikte bir çalışma olarak Mestre vd. (2006) tarafından ergenler üzerinde İspanya’da yürütülen çalışmada, daha yüksek duygusal zeka puanına sahip İspanyol öğrencilerin akranları tarafından daha sık arkadaş olarak gösterildiğini bulunmuştur. Kimlik krizinin ve sosyal reddedilme kaygısının yüksek yaşandığı bu dönemde duygusal zekanın stres düzeylerinin optimum seviyede olmasına katkı sunmaktadır. Mikolajczak vd. tarafından 2007 yılında yapılan çalışmada duygusal zekanın stres üzerinde hem psikolojik hem de biyolojik (kortizol) tepkileri önemli ölçüde azalttığı ve stres tepkisini azaltan bir etkisi bulunduğu saptanmıştır (Mikolajczak vd., 2007). Hızlı fiziksel ve duygusal değişimlerin yaşandığı kritik bir evre olan ergenlikte duygusal zekanın gelişimi, ergenlerin stresle daha sağlıklı başa çıkmasına, kişilerarası ilişkilerini yönetmesine ve akademik başarılarını artırmasına olanak tanır. Duygusal zeka, ergenlerin hem kendi karmaşık hislerini anlamlandırması hem de sosyal çevreleriyle etkili bir iletişim kurabilmesi için olumlu bir araçtır.

İnsan yaşamı için kritik ve yoğun duygular içinde geçen bir dönemi olan ergenlikte stres faktörlerine yönelik önleyici bir unsur olan duygusal zeka önemli bir yere sahiptir. Bu kapsamda ergenlerde duygusal zeka ve stres arasındaki ilişkinin incelenmesi, ergenlere yönelik uygulanacak stres azaltma programlarına zemin hazırlayacaktır. Bu çalışmanın amacı literatürde ergenlerde stres ve duygusal zeka ilişkisini inceleyen çalışmaların sistematik bir

şekilde gözden geçirilmesidir. Böylelikle ergenlerde duygusal zeka ve stres çalışmalarının hangi boyutlarda ele alındığı tespit edilerek literatürdeki eğilim ve boşlukların tespit edilmesi hedeflenmektedir. Bu amaçtan yola çıkılarak bu araştırmada aşağıdaki sorulara cevap aranmaktadır:

1. Ergenlerde stres ve duygusal zeka çalışmalarının örneklemini kimler oluşturmaktadır?
2. Çalışmalarda kullanılan ölçme araçları nelerdir?
3. Ergenlerde duygusal zeka ve stres arasındaki ilişkiyi inceleyen araştırmaların desenleri nasıldır?
4. Ergenlerde duygusal zeka ve stres arasında anlamlı ilişki bulunmuş mudur?
5. Ergenlerde duygusal zekanın stres üzerinde doğrudan etkisi var mıdır?

Araştırma Stratejileri


Bu çalışma, ergenlerde duygusal zeka ve stres arasındaki ilişkiyi inceleyen sistematik bir gözden geçirmedir. Çalışmada sistematik ve yapılandırılmış bir yaklaşım takip edilerek literatür taramasını gerçekleştirmek için sistematik incelemeler için güncellenmiş PRISMA rehberi kullanılmıştır (Page vd., 2021). Literatür taraması Web of Science veri tabanında 2025 yılı Kasım ayında, yıl için herhangi bir sınırlama yapılmaksızın İngilizce olarak gerçekleştirilmiştir. Literatür taraması “adolescent”, “emotional intelligence” ve “stress” terimleri üzerinden yapılmıştır.

Seçim Kriterleri

Çalışma kapsamına alınacak makalelerin tespiti için dahil etme kriterleri şu şekildedir: (1) Ergenlere yönelik yapılan çalışmalar, (2) Ergenlerde duygusal zeka ve stres arasındaki ilişkiyi inceleyen çalışmalar (3) Duygusal zeka ve stres arasındaki ilişkiyi istatistiksel veriler ile ortaya koyan çalışmalar (4) İlişkisel çalışmalar. Çalışma kapsamına alınacak makalelerin tespiti için hariç tutma kriterleri şu şekildedir: (1) Çocuk ve yetişkinler ile yapılan çalışmalar, (2) Sadece özetine ulaşılabilen çalışmalar, (3) Derleme çalışmaları.

Web of Science üzerinden yapılan tarama sonucunda 4453 çalışmaya ulaşılmıştır. Dahil etme ve hariç tutma kriterleri doğrultusunda araştırma kapsamına 17 çalışma alınmıştır. Makalelerin sistematik bir şekilde gözden geçirilme ve seçim evrelerini gösteren PRISMA akış Şeması Şekil 1’de sunulmaktadır.

Şekil – 1- PRISMA Akışı



BULGULAR

Literatürde “Ergenlerde Stres ve Duygusal Zeka Arasındaki İlişki” yi inceleyen çalışmalar incelenmiş; elde edilen araştırmalar Tablo 1’de verilmiştir.

Tablo-1

S.N.	Bibliyografik Kimlik ve Lokasyon	Örneklem Grubu	Araştırma Yöntemi	Kullanılan Ölçme Araçları	Ampirik Bulgular	Klinik/Teorik Sonuç
1	Arrivillaga vd. (2022) - İspanya (Güney)	2068 ergen (12-19 yaş; %46.2 erkek, %53.8 kız)	Kesitsel tarama, seri çoklu aracılık analizi	• Wong & Law Emotional Intelligence Scale (WLEIS) • Perceived Stress Scale (PSS-4) • Depression, Anxiety and Stress Scale (DASS-21) (Depresyon alt boyutu) • Social Media Addiction Questionnaire (SMAQ)	Düşük duygusal zeka, yüksek algılanan stresi yordamış ($\beta=-0.29$); bu durum depresif semptomları artırarak ($\beta=0.52$) Problemlili Sosyal Medya Kullanımına yol açmıştır ($\beta=1.51$).	Çalışma, Brand’ın I-PACE modelini ampirik olarak doğrulamaktadır. Duygusal zeka eksikliği, bireyi stres ve depresyon yoluyla uyumsuz başa çıkma mekanizmalarına iten bir risk faktörüdür.
2	Sra & Nisha (2014) - Hindistan (Pencap)	200 ergen (14-16 yaş; 100 kırsal, 100 kentsel)	Tanımlayıcı tarama, t-testi ve Pearson korelasyon analizi.	• Stress Scale for Students • Emotional Intelligence Inventory	Duygusal zeka ile stres arasında negatif ve anlamlı bir ilişki saptanmıştır ($r=-0.784$). Kırsal ve kentsel gruplar arasında stres açısından anlamlı fark bulunamamıştır ($t=0.324$).	Yüksek duygusal zeka, ergenlerin stresle etkili başa çıkmasını sağlayan koruyucu bir beceridir. Yüksek Duygusal Zeka'ya sahip ergenler, çevresel stresörleri (kırsal veya kentsel fark etmeksizin) daha az tehdit edici olarak algılamakta ve etkili başa çıkma mekanizmaları geliştirmektedir.
3	Arora & Kumar (2023) - Hindistan (Delhi)	357 okul öğrencisi (13-17 yaş)	Kesitsel, anket çalışması, AMOS ile aracılık analizi.	• Trait Emotional Intelligence Questionnaire-Adolescent Short Form (TEIQue-ASF) • Coping Inventory for Stressful Situations (CISS) • Adolescent Stress Questionnaire (ASQ)	Duygusal zeka ile stres arasında hem kızlarda ($r=-0.432$) hem erkeklerde ($r=-0.482$) negatif ilişki bulunmuştur. Duygu odaklı başa çıkma, bu ilişkide kısmi aracıcıdır ($\beta=-0.117$).	Duygusal Zekanın stresi azaltma mekanizması, kullanılan başa çıkma stiliyle modüle edilmektedir. Yüksek Duygusal Zeka normal şartlarda stresi azaltırken; bireyin yoğun şekilde "duygu odaklı başa çıkma" (kendini suçlama, inkar vb.) stratejilerine başvurmaması, Duygusal Zekanın koruyucu etkisini zayıflatmaktadır (kısmi aracılık). Bu durum, klinik pratikte sadece duygusal farkındalığın artırılmasının yeterli olmadığını; aynı zamanda pasif/duygu odaklı stratejiler yerine, aktif/görev odaklı (task-oriented) başa çıkma becerilerinin öğretilmesi gerektiğini ortaya koymaktadır.

INTERNATIONAL TOPKAPI CONGRESS VI

4	Piekarska (2020) - Polonya	406 lise öğrencisi (18-22 yaş)	Kesitsel, hiyerarşik regresyon analizi.	• Perceived Stress Scale (PSS-10) • Generalized Self-Efficacy Scale (GSES) • Rosenberg Self-Esteem Scale (RSES) • Eysenck Personality Short Scale (EPQ-R-S) • Emotional Intelligence Scale – Faces (SIE-T) & Emotion Understanding Test (TRE) • Schutte Emotional Intelligence Scale (SEIS)	Algılanan stresin en güçlü yordayıcısı Nevrotiklik (β=0.48). Özellik duygusal zeka tek başına negatif korelasyon gösterse de (r=-0.33), modele öz-yeterlik (β=-0.13) ve öz-saygı (β=-0.28) eklendiğinde etkisi anlamsızlaşmıştır.	Çalışmanın bulguları, Duygusal Zekanın stres üzerindeki etkisinin doğrudan olmaktan ziyade, öz-yeterlik ve öz-saygıyı besleyerek dolaylı yoldan gerçekleştiğini düşündürmektedir. Öz-yeterlik ve öz-saygı, nevrotiklik gibi kişilik özelliklerinin stres üzerindeki negatif etkisini tamponlamada duygusal zekadan daha belirleyicidir.
5	Naushad (2022) - Hindistan (Uttar Pradesh)	858 lise öğrencisi (XI. Sınıf)	Tanımlayıcı okul taraması, MANOVA, Post-hoc (Tukey HSD).	• Socio Economic Status Scale • Family Environment Scale • Emotional Intelligence Inventory • Academic Stress Questionnaire • Akademik Başarı (CGPA notları)	Yapılan Pearson korelasyon analizi sonucunda, duygusal zeka ile akademik stres arasında negatif yönlü ve istatistiksel olarak anlamlı bir ilişki (r= -0.154) saptanmıştır. Duygusal zeka, akademik başarı ile pozitif ve orta düzeyde (r= 0.440) bir korelasyon göstermiştir.	Çalışma bulguları, duygusal zeka seviyesi arttıkça, ergenin algıladığı akademik stres düzeyinin düştüğünü ve duygusal zeka ile akademik başarı arasında pozitif ilişki olduğunu; dolayısıyla duygusal zekanın stres karşısında koruyucu bir faktör olduğunu ve duygusal yetkinliklerin bilişsel performansı desteklediğini kanıtlamaktadır.
6	Lea vd. (2023) - Birleşik Krallık (Batı Midlands)	Çalışma 1: 58, Çalışma 2: 60 ergen (16-18 yaş)	Deneyisel (Sing-a-Song Stres Testi), fizyolojik ölçüm, göz izleme.	• Trait Emotional Intelligence Questionnaire-Adolescent Short Form (TEIQue-ASF) • Situational Test of Emotion Management – Brief (STEM-B) • Emotion Recognition Test (ERT) • Sing-a-Song Stress Test (SSST) (Deneyisel stres görevi) • PANAS (Negatif Duygu) • Hospital Anxiety Depression Scale (HADS)	Duygusal zekanın "sosyallık" alt boyutu, stres altında kalp hızı reaktivitesini anlamlı düzeyde yordamıştır (Etkileşim β=0.965). Duygusal zeka yeteneği (duygu algılama), stres altında mutlu yüzlere odaklanmayı artırmıştır.	Kişilik özelliği olarak duygusal zeka (özellikle sosyallik/öz-yeterlik algısı), vücudun strese verdiği fizyolojik tepkiyi (kalp hızı) baskılayarak bir "tampon" görevi görürken; Duygusal Zeka yeteneği, bilişsel süreçleri (dikkat) modüle ederek bireyin stres altındayken pozitif uyaranlara yönelmesini sağlamaktadır. Duygusal zeka, akut sosyal stres durumlarında fizyolojik bir "tampon" görevi görmektedir.
7	Cejudo vd. (2018) - İspanya (Toledo)	505 ergen (12-18 yaş)	Kesitsel, Yapısal Eşitlik Modellemesi (SEM).	• Trait Emotional Intelligence Questionnaire Adolescents Short Form (TEIQue-ASF) • Wong and Law's Emotional Intelligence Scale (WLEIS) • Student Stress Inventory-Stress Manifestations (SSI-SM) • Social Anxiety Scale for Adolescents (SAS-A)	Duygusal zeka özelliği, stresi (β=-0.53) ve sosyal anksiyeteyi (β=-0.52) negatif yönde ve güçlü bir şekilde yordamıştır.	Duygusal zeka, ergenlerdeki sosyal anksiyete ve stres belirtileri üzerinde güçlü bir önleyici güce sahiptir. Sosyal durumlarda yaşanan belirsizliği ve potansiyel tehdit algısını azaltarak sosyal anksiyeteyi önlemektedir.

INTERNATIONAL TOPKAPI CONGRESS VI

8	Abdollahi vd. (2016) - İran (Tahran)	202 depresif yatan ergen hasta	Kesitsel, klinik örneklem, SEM, moderasyon analizi.	• Patient Health Questionnaire (PHQ) • Perceived Stress Scale (PSS-10) • Assessing Emotions Scale (AES) • Suicidal Ideation Questionnaire (SIQ)	Algılanan stres intihar düşüncesini pozitif yordarken ($\beta=0.49$), duygusal zeka negatif yordamıştır ($\beta=-0.33$). Duygusal zeka bu ilişkide düzenleyici rol oynamıştır.	Duygusal zeka, depresif ergenlerde stresin intihar düşüncesine dönüşmesini engelleyen koruyucu bir tampon mekanizmasıdır.
9	De la Barrera vd. (2023) - İspanya (Valensiya)	132 ergen (12-15 yaş)	Kesitsel, biyolojik ölçüm (Saç kortizolü - HCC), regresyon.	• Trait Meta-Mood Scale (TMMS-24) • Satisfaction With Life Scale (SWLS) • Scale of Positive and Negative Experiences (SPANE) • Perceived Stress Scale (PSS-4) • Saç Kortizol Konsantrasyonu (Biyolojik stres ölçümü)	Duygusal "dikkat" fizyolojik stresi pozitif yönde yordamıştır ($\beta=0.29$). "Duygusal açıklık" ($\beta=-0.26$) ve yaşam doyumu ($\beta=-0.45$) algılanan stresi negatif yordamıştır.	Çalışma, Duygusal Zekanın "karanlık yüzü" olabilecek "aşırı duygusal dikkat" (emotional attention) kavramına odaklanmaktadır. Özellikle "duygusal onarım" becerisi düşükken "duygusal dikkat"ın yüksek olması, bireyde ruminasyona yol açarak fizyolojik stresi (kortizol seviyesini) artırmaktadır. Buna karşın "duygusal açıklık" (duyguyu net tanımlama), algılanan stresi düşürmektedir.
10	Ghazali (2014) - ABD (Michigan)	30 Orta Doğu kökenli mülteci çocuk/ergen	Kesitsel, korelasyonel, klinik görüşme (CPTS-RI).	• Child Posttraumatic Stress Reaction Index (CPTS-RI) • Adolescents Multifactor Emotional Intelligence Scale (AMEIS)	PTSD şiddeti ile genel duygusal zeka arasında ters ilişki saptanmıştır ($r=-0.32$). Özellikle "duyguyu kullanma" ($r=-0.37$) alt boyutunda anlamlı negatif korelasyon görülmüştür.	Şiddetli PTSD semptomları, bireyin duyguları anlama ve kullanma kapasitesini baskılayabilir.
11	Wang vd. (2023) - Çin (Changsha)	426 ortaokul ve lise öğrencisi	Kesitsel, Yapısal Eşitlik Modellemesi (SEM).	• Physical Activity Scale • Emotional Intelligence Scale • Psychosocial Stress (Global School-Based Student Health Survey - WHO) • Self-Rated Health Status (OSDUS adaptasyonu)	Orta-şiddetli fiziksel aktivite (MVPA), duygusal zeka üzerinde pozitif ($\beta=0.600$); psikososyal stres üzerinde negatif ($\beta=-0.404$) etkiye sahiptir.	Fiziksel aktivite, stresi azaltmada direk etkisinin yanı sıra duygusal zekayı artırıp stresi azaltarak ergenlerin genel sağlık algısını iyileştiren bütüncül bir araçtır. Bu çalışmada duygusal zeka, fiziksel aktivite ve stres arasında aracı bir role sahiptir.
12	Castro-Sánchez vd. (2022) - İspanya (Granada)	2452 ergen (13-16 yaş)	Kesitsel, çoklu grup yapısal eşitlik modeli.	• Schutte Self Report Inventory (SSRI) • State-Trait Anxiety Inventory (STAI) • Perceived Stress Scale (PSS-14) • Physical Activity Questionnaire for Adolescents (PAQ-A)	Duygusal zeka ile sürekli kaygı arasında negatif ilişki bulunmuştur (Erkekler: $r=-0.413$; Kızlar: $r=-0.365$). Erkeklerde duygusal zeka ile stres arasında negatif ilişki varken ($r=-0.054$), kızlarda bu ilişki anlamsızdır ($p=0.145$).	Stres ve Duygusal Zeka ilişkisinde cinsiyetin belirleyici bir moderatör olduğu görülmüştür. Erkeklerde Duygusal Zeka, stresi doğrudan azaltan bir faktörken; kızlarda yüksek Duygusal Zeka'ye rağmen stres seviyelerinin düşmemesi, kızların maruz kaldığı stresörlerin doğasının farklılığını veya başa çıkma mekanizmalarının yetersiz kaldığını (duygusal yükün fazlalığı) düşündürmektedir.

INTERNATIONAL TOPKAPI CONGRESS VI

13	Villanueva vd. (2017) - İspanya (Valensiya)	170 ergen (12-14 yaş)	Kesitsel, hiyerarşik regresyon ve fsQCA, Saç kortizolü.	• Trait Meta-Mood Scale (TMMS-24) • Scale of Positive and Negative Experiences (SPANE) • Perceived Stress Scale (PSS-4) • Saç Kortizol Konsantrasyonu (HCC)	Duygusal zekanın alt boyutlarından Duygusal açıklık ($\beta=-0.27$) ve hedonik denge ($\beta=-0.45$) algılanan stresi negatif yordamıştır. Yüksek "duygusal dikkat" ve kadın cinsiyeti yüksek saç kortizolü ile ilişkilidir (tutarlılık = 0.81).	Yüksek duygusal dikkat, düşük onarım becerisiyle birleştiğinde (özellikle kızlarda), yüksek fizyolojik strese (kortizol birikimi) neden olmaktadır. Bu "dengesiz Duygusal Zeka profili", bireyi kronik strese karşı savunmasız bırakmaktadır.
14	Liébana-Presa vd. (2020) - İspanya (Ponferrada)	300 ergen (13-17 yaş; karantina öncesi ve sonrası)	Karşılaştırmalı korelasyonel çalışma (COVID-19 etkisi).	• Trait Meta-Mood Scale (TMMS-24) • Student Stress Inventory-Stress Manifestations (SSI-SM) • Cannabis Use Intention Questionnaire (CUIQ)	Karantina sonrası stresin duygusal belirtileri anlamlı düzeyde artmıştır ($t=-3.196, p=0.002$). Kadınlarda stresin duygusal belirtileri erkeklerden yüksektir ($t=-3.32$).	Çalışma bulgularına göre cinsiyet, stres tepkileri ve duygusal zeka boyutlarında belirleyici bir faktördür. Kızların "duygusal dikkat" puanlarının yüksek olması, kriz anlarında duygulara aşırı odaklanmalarına ve bu durumun stresin duygusal manifestasyonlarını (kaygı, üzüntü) şiddetlendirmesine neden olmaktadır.
15	Li vd. (2024) - Çin (Hunan, Hubei, Henan)	440 ergen (12-18 yaş)	Kesitsel, Yapısal Eşitlik Modellemesi (SEM).	• Moderate-to-Vigorous Physical Activity Scale • Emotional Intelligence Scale (WLEIS) • Perceived Stress Scale (PSS-5) • Health-Related Quality of Life (KIDSCREEN-10)	Orta ve Yüksek Şiddetli Fiziksel Aktivite, duygusal zekayı pozitif ($\beta=0.397$), algılanan stresi negatif ($\beta=-0.337$) yordamıştır. Duygusal zeka, stres üzerinde azaltıcı etkiye sahiptir ($\beta=-0.373$).	Duygusal zeka, fiziksel aktivite (MVPA) ile Sağlıkla İlgili Yaşam Kalitesi (HRQOL) arasında "pozitif bir aracı"; algılanan stres ise "negatif bir aracı" olarak işlev görmektedir. Model, fiziksel aktivitenin Duygusal Zeka'yi artırarak stresi baskıladığını ve bu zincirleme etkinin yaşam kalitesini yükselttiğini kanıtlamaktadır.
16	Schoeps vd. (2019) - İspanya (Valensiya)	800 ergen (T1: 14 yaş, T2: 15 yaş)	Boylamsal, Çoklu Grup Yapısal Eşitlik Modellemesi.	• Perceived Stress Scale (PSS-4) • Emotional Skills and Competence Questionnaire (ESCQ) • Satisfaction With Life Scale (SWLS)	Duyguları algılama ve anlama becerisinin algılanan stres üzerindeki etkisi negatiftir ($\beta=-0.23$). Algılanan stres, duygusal zeka ve yaşam doyumu arasındaki ilişkiye tam aracılık etmiştir.	Yüksek stres seviyeleri, duygusal zekanın yaşam doyumu üzerindeki koruyucu etkisini ortadan kaldırabilir (Stresin tam aracı rolü).
17	Serrano & Andreu (2016) - İspanya (Valensiya ve Castellón)	626 ergen (13-18 yaş; Ortalama yaş=15.48).	Kesitsel, Çoklu Regresyon ve Bootstrapping Aracılık (Mediation) Analizleri.	• Trait Meta-Mood Scale (TMMS-24) • Subjective Happiness Scale (SHS) • Perceived Stress Scale (PSS-14) • Utrecht Work Engagement Scale for Students (UWES-S-9) • Akademik Başarı	Duygusal zeka alt boyutları, algılanan stres varyansının %36'sını açıklamaktadır. Kız öğrencilerin algılanan stres puanları ($M=29.17$), erkek öğrencilere ($M=25.34$) göre anlamlı düzeyde daha yüksektir ($t=6.95, p<.001$). Duygusal zeka akademik başarıyı doğrudan yordamamıştır.	Duygusal zeka, akademik başarıyı doğrudan etkilememekle birlikte; stresi azaltarak ve akademik adanmışlığı (dedication) artırarak başarı üzerinde dolaylı ve koruyucu bir etkiye sahiptir. Yüksek duygusal dikkat ile düşük duygusal onarımın bir arada bulunması, stresi artıran işlevsiz (ruminatif) bir profil oluşturmaktadır

TARTIŞMA VE SONUÇ

Bu sistematik gözden geçirme çalışması, ergenlik döneminde stres ve duygusal zeka arasındaki karmaşık ve çok katmanlı ilişkiyi inceleyen araştırmaları sentezlemeyi amaçlamıştır. Elde edilen bulgular, genel literatürle tutarlı bir şekilde, duygusal zekanın algılanan stres üzerinde koruyucu bir faktör olduğunu ve psikolojik iyi oluşu yordadığını ortaya koymaktadır. Ancak, incelenen çalışmalar bu ilişkinin doğrusal ve tek yönlü olmaktan ziyade; cinsiyet, duygusal zeka alt boyutları (özellikle duygusal dikkat), başa çıkma stratejileri ve çevresel faktörlerin bir arada ele alındığı dinamik bir süreç olduğunu göstermektedir.

İncelenen çalışmaların büyük çoğunluğu, yüksek duygusal zekanın ergenlerde stresi azalttığını ve stresin olumsuz sonuçlarına (depresyon, intihar düşüncesi, problemli teknoloji kullanımı) karşı bir "tampon" görevi gördüğünü kanıtlamaktadır. Örneğin Abdollahi vd. (2016) klinik örnekleme yaptığı çalışma, algılanan stresin intihar düşüncesini artırdığını, ancak yüksek duygusal zekanın bu ilişkiyi zayıflattığını göstererek duygusal zekanın hayati bir koruyucu faktör olduğunu vurgulamaktadır. Benzer şekilde Arrivillaga vd. (2022), düşük duygusal zekanın yüksek strese, bunun da depresif belirtilere ve nihayetinde problemli sosyal medya kullanımına yol açtığını seri bir aracılık modeli ortaya koymuştur. Bu bulgular, duygusal zekanın stresin patolojik davranışlara dönüşmesini engelleyen bir bariyer olduğunu düşündürmektedir.

Ancak bu koruyucu etkinin mekanizması, kullanılan başa çıkma stratejilerine bağlı görünmektedir. Arora ve Kumar (2023), duygusal zekanın ile stres arasındaki ilişkide stresle baş etme yöntemlerinden "duygu odaklı başa çıkma"nın kısmi aracı rol oynadığını belirtmiştir. Ergenlerin stresle başa çıkarken sorunu çözmek yerine sadece duygusal tepkilerine odaklanmaları (kendini suçlama, ruminasyon vb.), yüksek duygusal zeka potansiyelinin koruyucu etkisini zayıflatabilmektedir. Bu durum, klinik müdahalelerde sadece duygusal farkındalığın değil, aynı zamanda aktif ve problem odaklı başa çıkma becerilerinin de geliştirilmesi gerekliliğini ortaya koymaktadır.

Bu derlemenin en çarpıcı bulgularından biri, duygusal zekanın alt boyutlarının stres üzerindeki etkilerinin farklılaşmasıdır. Genel duygusal zeka puanı stresle negatif ilişkili olsa da, "Duygusal Dikkat" alt boyutu paradoksal sonuçlar doğurabilmektedir. Villanueva vd. (2017) ile De la Barrera vd. (2023) çalışmaları, yüksek duygusal dikkatin – eğer buna eşlik eden yüksek bir "Duygusal Onarım" veya "Duygusal Açıklık" becerisi yoksa – fizyolojik stresi (saç kortizol seviyeleri) ve algılanan stresi artırabileceğini göstermiştir. Bu durum, literatürde "Duygusal Zekanın karanlık yüzü" olarak tartışılan fenomene işaret etmektedir; duygularına aşırı odaklanan ancak onları düzenleyemeyen ergenler, ruminatif bir döngüye girerek stres tepkilerini şiddetlendirmektedir. Dolayısıyla, "ne kadar çok duygusal zeka o kadar iyi" şeklindeki monotonik yaklaşım yerine, duygusal dikkat, açıklık ve onarım arasında bir dengenin gözetilmesi gerektiği anlaşılmaktadır.

Kimi çalışmalarda stres ve duygusal zeka ilişkisinde cinsiyet belirleyici bir moderatör olarak öne çıkmaktadır. Birçok çalışma kız ergenlerin erkeklere göre daha yüksek stres düzeylerine ve daha yüksek "duygusal dikkat" puanlarına sahip olduğunu raporlamıştır. Castro-Sánchez vd. (2022), erkeklerde duygusal zeka ile stres arasında net bir negatif ilişki bulurken, kızlarda bu ilişkinin anlamsızlaştığını tespit etmiştir. Bu durum, kız ergenlerin duygusal uyaranlara daha fazla maruz kalmaları ve duygusal durumları üzerine daha fazla düşünmeleri (ruminasyon), ancak bu yoğun duygusal girdiyi düzenlemede yetersiz kalmalarıyla açıklanabilir.

Fizyolojik ölçümlerin kullanıldığı çalışmalarda da benzer ayrımlar görülmektedir. Lea vd. (2023) deneysel çalışmaları, duygusal zekanın "sosyallik" boyutunun akut sosyal stres altında kalp hızı reaktivitesini azalttığını göstermiştir. Ancak dikkat çekici bir şekilde, yüksek "duygu algılama yeteneği", stres altında mutlu yüzlere odaklanmayı artırsa da, stres reaktivitesini doğrudan düşürmemiştir. Bu bulgular, ergenlerin stres düzenlemesinde, duygusal yeteneklerden ziyade, duygusal öz-yeterlik algısının yani bir mizaç ve kişilik bağlamında duygusal zekanın daha belirleyici olabileceğini düşündürmektedir.

Duygusal zeka ve stres ilişkisi, sosyoekonomik düzey, aile ortamı ve fiziksel aktivite gibi dışsal faktörlerle de şekillenmektedir. Naushad (2022), yüksek sosyoekonomik düzey ve olumlu aile ortamının duygusal zekayı artırarak akademik stresi azalttığını ve akademik başarıyı yükselttiğini bulmuştur. Benzer şekilde, Wang vd. (2023) ile Li vd. (2024), orta-yüksek şiddetli fiziksel aktivitenin (MVPA), ergenlerin duygusal zeka seviyelerini artırarak algılanan stresi düşürdüğünü ve yaşam kalitesini iyileştirdiğini ortaya koymuştur. Bu çalışmalar, duygusal zekanın geliştirilebilir bir beceri olduğunu ve fiziksel aktivite gibi davranışsal müdahalelerin stres yönetiminde duygusal zeka üzerinden dolaylı bir etki yarattığını kanıtlamaktadır. Ayrıca, COVID-19 pandemisi gibi makro düzeydeki stresörlerin ergenlerin stres düzeylerini artırdığı, ancak duygusal zekanın bu olağanüstü koşullarda dahi koruyucu rolünü sürdürdüğü görülmüştür.

Bu sistematik gözden geçirme, ergenlik döneminde duygusal zekanın stres yönetiminde merkezi bir rol oynadığını, ancak bu ilişkinin çok boyutlu bir yapıya sahip olduğunu ortaya koymaktadır. Elde edilen bulgular ışığında, yüksek duygusal zekanın; hem algılanan psikolojik stresi hem de intihar düşüncesi ve problemlili internet kullanımı gibi strese bağlı psikopatolojileri azaltmada güçlü bir koruyucu faktör olduğu, Duygusal zeka müdahalelerinde ergenlerin sadece duygularına odaklanmalarını sağlamanın yeterli olmadığını aksine duygusal onarım ve açıklık becerileri geliştirilmeden artırılan duygusal dikkatin ruminasyonu artırabileceği (özellikle kız ergenlerde), duygusal zekanın stresle mücadelede aile ortamı, fiziksel aktivite ve öz yeterlik becerileri ile desteklendiği, duygusal zekanın stres ile ilişkisinde cinsiyetin farklılaştırıcı bir rolü olduğu sonuçlarına ulaşmıştır.

Kaynakça

- Avunduk, Y. (2021). *Duygusal zekanın iş performansı üzerindeki etkisi*. Gazi Kitabevi.
- Baltaş, A. ve Baltaş, Z. (2017). *Stres ve başa çıkma yolları*. Remzi Kitabevi.
- Blasberg, J. U., Kanske, P., & Engert, V. (2025). Empathic stress in the family: Adolescents vicariously respond to their parents' acute psychosocial stress. *Developmental Psychology*. <https://doi.org/10.1037/dev0001972>
- Çok, F. (1994). Gelişim psikolojisi: ergenlik ve yetişkinlik. *Ankara University Journal of Faculty of Educational Sciences (JFES)*, 27(2), 905-935. https://doi.org/10.1501/Egifak_0000000362
- Deeb, N., Jensen, K., Campbell, A., & Andersen, E. (2024). Differences in neuroendocrine responses to psychosocial stress before and after the COVID-19 pandemic in female adolescents. *Biological Psychiatry*, 95(10).

El-Khodary, B., Samara, M., & Askew, C. (2020). Traumatic events and PTSD among Palestinian children and adolescents: The effect of demographic and socioeconomic factors. *Frontiers in Psychiatry, 11*. <https://doi.org/10.3389/fpsy.2020.00004>

Erikson, E. H. (1968). *Identity: Youth and Crisis*. W. W. Norton & Company.

Erikson, E.H. (1984). İnsanın Sekiz Çağı (Çevirenler: T.B. Üstün ve V. ar). Ankara: Birey ve Toplum Yayıncılık.

Fernandes, S., Zacharias, R., Noronha, W. S., & Dsouza, D. G. (2025). Perceived stress and coping strategies among adolescent girls on pubertal changes in a selected schools, Mangaluru. *Journal of Health and Allied Sciences NU, 15*. <https://doi.org/10.1055/s-0044-1792152>

Galaif, E. R., Sussman, S., Chou, C.-P., & Wills, T. A. (2003). Longitudinal relations among depression, stress, and coping in high risk youth. *Journal of Youth and Adolescence, 32*(4), 243–258.

Gao, X. H. (2023). Academic stress and academic burnout in adolescents: A moderated mediating model. *Frontiers in Psychology, 14*. <https://doi.org/10.3389/fpsyg.2023.1133706>

Garbers, S., Suruki, C., Falletta, K. A., Gold, M. A., & Bruzzese, J. M. (2021). Psychosocial stress, sleep quality and interest in mind-body integrative health sleep intervention among urban adolescents in the school-based health setting. *Complementary Therapies in Medicine, 58*. <https://doi.org/10.1016/j.ctim.2021.102714>

Grass, A., Rosner, R., Ciner, A., Renneberg, B., & Steil, R. (2025). Therapeutic alliance during trauma focused treatment in adolescent and young adult patients with PTSD. *BMC Psychiatry, 25*(1). <https://doi.org/10.1186/s12888-024-06410-x>

Gündogan, S. (2023). The relationship between academic stress and sleep quality in adolescents: The mediating role of school burnout and depression. *Eğitim ve Bilim-Education and Science, 48*(215). <https://doi.org/10.15390/EB.2023.11497>

Günçe, G. (1973). *Çocukta Zihinsel Gelişim, Piaget Kuramına Toplu Bakış*. Baylan Matbaası, Ankara.

İkiz, F.E., (2025). Çocuk Ergen Ruh Sağlığı ve Psikopatolojisi. Savi Çakar, F. (Ed.), *Çocuk Ergen Ruh Sağlığı* içinde (s. 1-32). Pegem Akademi.

Luo, R., Wang, Y., Luo, Y. H., Qi, M. D., Yang, Z. Q., Li, Z. Y., & Chen, F. M. (2025). Trajectories of resilience among Chinese adolescents: Effects of gratitude and perceived stress. *Development and Psychopathology*. <https://doi.org/10.1017/S0954579425100448>

Meydan, B. (2021). Ergenlik döneminin doğası ve psikososyal uyum. Akdoğan, R. ve Çimşir, E. (Ed.), *Ergenlik ve ergen bireye yaklaşım*, içinde (s. 1-22). Anı Yayınları.

Mestre JM, Guil R, Lopes PN, Salovey P, Gil-Olarte P. 2006. Emotional intelligence and social and academic adaptation to school. *Psicothema* 18:112–17

Mikolajczak, M., Roy, E., Luminet, O., Fillée, C., & de Timary, P. (2007). The moderating impact of emotional intelligence on free cortisol responses to stress. *Psychoneuroendocrinology, 32*, 1000–1012. <https://doi.org/10.1016/j.psyneuen.2007.07.009>

Nepocatych, S., Weaver, M., Sumner, K., Walsh, K., & Enck, H. (2024). Exploring arterial health, perceived stress and sleep patterns in adolescents. *Medicine & Science in Sports & Exercise*, 56(10).

Öngen, D. (1993). Ergenlikte zihinsel gelişim. *Ankara University Journal of Faculty of Educational Sciences* (JFES), 26(1), 287-302. https://doi.org/10.1501/Egifak_00000000510

Özgüngör, S. (2021). Bilişsel Gelişim. Siyez, D.M. (Ed.), *Çocuk ve ergen gelişimi çok boyutlu bir bakış içinde* (s. 240-299). Pegem Akademi.

Page, M. J. vd. (2021). The PRISMA 2020 statement: an updated guideline for reporting systematic reviews. *BMJ*, 71, 1-9. doi:10.1136/bmj.n71

Schutte, N. S., Malouff, J. M., Hall, L. E., Haggerty, D. J., Cooper, J. T., Golden, C. J., & Dornheim, L. (1998). Development and validation of a measure of emotional intelligence. *Personality and Individual Differences*, 25(2), 167–177 . [https://doi.org/10.1016/S0191-8869\(98\)00001-4](https://doi.org/10.1016/S0191-8869(98)00001-4).

Tan, S. Y., & Yip, A. (2018). Hans Selye (1907–1982): Founder of the stress theory. *Singapore Medical Journal*, 59(4), 170–171. <https://doi.org/10.11622/smedj.2018043>

Wang, R. B., Yang, S. Q., Xu, X., Mi, S. S., & Hao, N. (2025). Exploring adolescent academic stress in the digital and urban age: A mixed-methods study from CIT to checklist validation. *Frontiers in Psychology*, 16. <https://doi.org/10.3389/fpsyg.2025.1692113>

Zhang, L. Q., & Shapiro, M. A. (2022). PTSD following suicide attempts in adolescents: A case series. *Journal of Child & Adolescent Trauma*, 15(1). <https://doi.org/10.1007/s40653-021-00380-y>

**HİPERSPEKTRAL GÖRÜNTÜLERDE ANOMALİ TESPİTİ İÇİN GODEC VE
ROSURE ALGORİTMALARININ PERFORMANSLARININ KARŞILAŞTIRILMASI**
COMPARISON OF GODEC AND ROSURE ALGORITHMS PERFORMANCE FOR
ANOMALY DETECTION IN HYPERSPECTRAL IMAGES

Dr. Öğr. Üyesi Fatma KÜÇÜK

Ankara Yıldırım Beyazıt Üniversitesi, Mühendislik ve Doğa Bilimleri Fakültesi,
Yazılım Mühendisliği Bölümü, Keçiören, Ankara.

ÖZET

Hiperspektral anomali tespiti (HAD), arka planına kıyasla büyük ölçüde farklılık gösteren bir hiperspektral görüntüdeki alışılmadık veya nadir spektral desenleri tespit etmeyi amaçlayan bir tekniktir. Bu etkinlik, çevresel izleme, askeri gözetleme ve ince spektral değişimlerin anlamlı hedefleri veya Dünya yüzeyindeki değişiklikleri belirlemede yardımcı olabileceği mineral arama gibi uzaktan algılama uygulamalarında önemlidir. Bu çalışmada, hiperspektral görüntülerdeki anomalileri tespit etmek için GODEC (GoDecomposition) ve ROSURE (Robust Subspace Recovery) algoritmalarının farklı mesafe ölçümlerine göre karşılaştırmalı bir analizi yapılacaktır. İki yöntem de hiperspektral veri küplerinin arka planını ve hedefini izole etmek için düşük rütbeli ve seyrek gösterimleri kullanır. Algılama kolaylıklarını en üst düzeye çıkarmak için, Mahalanobis, Öklid ve Cauchy-Laplacian tabanlı mesafe ölçümleri olmak üzere birkaç mesafe ölçümü kullanır. Mesafe, GODEC ve ROSURE tarafından üretilen seyrek matris kullanılarak hesaplanır ve anomalinin puanlanması bu mesafeye göre yapılır. Referans hiperspektral veriler üzerinde yapılan deneysel sonuçlara ilişkin örnekler, ROSURE tabanlı çözümlerin GODEC tabanlı çözümlerden çok daha doğru ve güçlü olduğunu göstermektedir. Ayrıca, Cauchy mesafesinin Laplasyen matrisiyle birlikte kullanılması, ROSURE'un Mahalanobis ve Öklid mesafeleri üzerindeki performansını da artırmaktadır. Bu sonuçlar, ayrıştırma tabanlı hiperspektral anomali tespitinde mesafe ölçütlerinin seçiminin önemini ortaya koymakta ve uzaktan algılamanın gerçek dünya uygulamalarında kullanılacak daha güvenilir ve verimli tespit modelleri oluşturmak için iyi birer fikir olabilir.

Anahtar kelimeler: Anomali tespiti, hiperspektral görüntüleme, ayrıştırma, sağlam alt uzay kurtarma.

ABSTRACT

Hyperspectral anomaly detection (HAD) is a technique intended to detect unusual spectral pattern or rare spectral pattern in a hyperspectral image that differs greatly in comparison to its background. This activity is essential in remote sensing applications like in environmental monitoring, military surveillance, as well as in searching minerals where subtle spectral variations can be helpful in identifying meaningful targets or changes on the face of the Earth. In this study, a comparative analysis of the GODEC (GoDecomposition) and the ROSURE (Robust Subspace Recovery) algorithm against different distance measurements will be made to identify anomalies in hyperspectral images. The two methods utilize the low-rank and sparse representations to isolate the background and target of hyperspectral data cubes. To maximize their detection facility, the frameworks use a few distance measures that is Mahalanobis, Euclidean and Cauchy-Laplacian-based distance measures. Distance is computed using the sparse matrix produced by GODEC and ROSURE, and scoring the anomaly is carried out based on that distance. Examples of experimental outcomes on benchmark hyperspectral data show that ROSURE-based solutions are much more accurate and stronger than GODEC-based solutions. Besides, the use of Cauchy distance combined with Laplacian matrix also enhances

the performance of ROSURE over Mahalanobis and Euclidean distances. These results demonstrate the significance of the choice of distance metrics in decomposition-based hyperspectral anomaly detection and can be good insights into building more reliable and efficient detection models to be used in real-world applications of remote sensing.

Keywords: Anomaly detection, hyperspectral imaging, go decomposition, robust subspace recovery.

INTRODUCTION

Hyperspectral imagery (HSI) is a three-dimensional data cube with three data types that measures the spatial and spectral features of earth objects (Gowen et al., 2007). Hyperspectral remote sensing allows the elaborate study of material properties based on their characteristic spectral signature by integrating spatial data with spectral data with tens of hundreds of closely spaced spectral bands (Goetz et al., 1985; Landgrebe, 2002). The spectral resolution of HSI is highly precise and therefore offers a good capability of separating materials that might be physically indistinguishable in a traditional imaging device.

Spectral and spatial information can be combined to benefit the material identification and classification complexes, as can be seen in the case of limited data provided, which are limited to the visible range of the electromagnetic spectrum (Landgrebe, 2002). The capabilities add to the improved situational awareness and aid the retrieval of fine-grained information about objects and the surrounding environment. Consequently, hyperspectral imaging has emerged as an important technology in a wide range of applications, including target detection in defense and surveillance systems (Manolakis et al., 2003), geological exploration and rare mineral discovery (Kruse et al., 2003), precision agriculture (Haboudane et al., 2004; Mehedi et al., 2025), food and pharmaceutical quality analysis (Gowen et al., 2007; Lun et al., 2025; Pieszczyk et al., 2025), and civilian search and rescue operations (Eismann, 2009; Abdelnabi et al., 2024).

With the wide range of research directions in the analysis of hyperspectral data, hyperspectral anomaly detection has become a highly important task. Spectrally distinguishable pixels that significantly do not match the context of the local or the global background are considered anomalies (Stein et al., 2002; Du et al., 2016). It is most commonly described as a binary classification problem with an aim to differentiate a rare and sparse target population and a complex and spatially heterogeneous background population as described by Matteoli et al. (2010). The task is inherently more difficult in comparison to other conventional classification methods that use predetermined target labels because hyperspectral anomaly detection needs to work with little or no prior information about the nature and frequency of anomalies, which is intrinsically more difficult.

Although they have made some major strides, much of the current hyperspectral anomaly detectors algorithms are debilitated by two inherent shortcomings. To begin with, they can be very noise-sensitive, especially with high-dimensional hyperspectral data, spectral redundancy, sensor noise, and calibration artifacts can be very disruptive to detection performance (Manolakis et al., 2003). Second, a host of conventional algorithms are based on the premise that the background is Gaussian which is often not the case in real-life context of heterogeneous terrain, mixed pixels and nonlinear spectral variability (Eismann, 2009).

Low-rank and sparse decomposition techniques like GoDec have been proposed to overcome these limitations in order to describe hyperspectral data in a more effective way. GoDec is constructed to be able to separate structured background data and sparse outliers. It decomposes a given data matrix into low-rank component that favors the overall background and a sparse component that favors anomalies or noise (Zhou and Tao, 2011). GoDec has found in numerous applications, such as video surveillance, background subtraction, image denoising, and data compression, due to its processing capacity and strength (Zhou and Tao, 2011; Bouwmans and Zahzah, 2014). Hyperspectral imagery has also been significantly used with GoDec-based and

low-rank sparse decomposition techniques to identify anomalies because the spectral backgrounds of hyperspectral images have a low-rank with spectral correlation, whereas anomalies are sparse and spectrally dissimilar (Cui et al., 2014; Zhang et al., 2018). Thus, GoDec and its variations have been successfully applied to hyperspectral anomaly detection systems to enhance the accuracy of detection in the real world. Likewise, it has also been proposed that Robust Subspace Recovery (RoSuRe) can be a competing low-rank modeling system to add further robustness to more complex background variations in hyperspectral data. Unlike the classic methods of decomposition, RoSuRe directly takes into account the situation of non-conforming data points to one low-dimensional subspace, which can be represented as a sparse corruption, which can be used to achieve the correct background and anomaly separation (Bian and Krim, 2014). This characteristic renders RoSuRe especially well positioned to be used in hyperspectral anomaly detection, in which background spectra in many low-dimensional subspaces can be a common occurrence because of variations in illumination, material combinations, and nonlinear spectral phenomena (Qu et al., 2018). RoSuRe based approaches use the intrinsic subspace to model the background whereas anomalies are detected in the form of sparse deviations. Such a design is beneficial in reducing noise effects and loosening strong distribution assumptions to improve the detection in cluttered and heterogeneous hyperspectral imagery (Sun et al., 2018).


The remainder of this paper is organized as follows. The methodology section shows the hyperspectral datasets, the algorithms, and the distances used in the detection of anomalies. The experimental results section provides quantitative assessments of the experimental results and qualitative visual assessments. The last section is conclusion, which summarizes the key results and represents possible directions of the work in the future.

METHODOLOGY

Hyperspectral datasets

In this section, four publicly available HSI datasets are used in the experiments. Figure 1 shows original band images and ground truths. As can be seen from the figure that different materials are represented as anomalies: fields, planes, and buildings. These materials have different number of pixels in total changing from 42 to 272. They are captured in different locations by the Airborne Visible Infrared Imaging Spectrometer (AVIRIS) sensor.

Figure 1. Hyperspectral ABU datasets. a) Airport 2. b) Airport 3. c) Airport 4. d) Beach 1. e)



Beach 2. f) Beach 3. g) Beach 4. h) Urban 1. i) Urban 2. j) Urban 3. k) Urban 4.

Methods

In this study, two benchmark algorithms details are given. The idea behind these algorithms are represented in Figure 2 below. Original 3D HIS dataset is decomposed as low-rank background and sparse anomaly matrices.




Figure 2. X observed HSI dataset and its decomposition.

GODEC is a decomposition matrix algorithm that is extensively used in literature to decompose data using a low-rank and sparse component. It was initially proposed as a computationally efficient substitute for robust principal component analysis (RPCA), where the aim was to decrease the computational load at the cost of preserving the accuracy of the decomposition (Zhou and Tao, 2011). GODEC is an iterative estimator of a low-rank background space and sparse component, which means that it can be used to solve problems in background modeling, video surveillance, and hyperspectral anomaly detection (Candes et al., 2011; Zhang et al., 2019). Nevertheless, other studies have found that its performance across noise sensitivity to detection, rank sensitivity, and parameter sensitivity can be problematic with highly challenging hyperspectral scenes when the background statistics do not follow ideal low-rank assumptions (Ma et al., 2020). Nevertheless, GODEC can still be widely used as a baseline, and it is typically used together with other distance measures to enhance the performance of anomaly detectors in hyperspectral imagery.

RoSuRe is an algorithm that decomposes data into a low-rank background matrix and sparse matrix by jointly utilizing sparsity in the coefficient matrix and the error component. In comparison with traditional low-rank decomposition algorithms, RoSuRe represents the underlying data structure with self-representation and, therefore, allows a more effective separation between background and anomaly components (Bian et al., 2012). Bi-sparsity formulation is very strong against noise, outliers, and complicated background variations, and, regarding this, RoSuRe is specifically valuable in hyperspectral anomaly detection tasks. Consequently, RoSuRe has been extensively used as an effective decomposition model and is considered to be integrated with state-of-the-art distance measures to enhance the performance of the anomaly detector in hyperspectral imagery.


Mahalanobis, Euclidean, and Laplacian-based distances are used to generate anomaly detection maps. They are normally used to determine similarity and dissimilarity in anomaly detection and pattern recognition. The most common and simplest metric is Euclidean distance, which is a metric indicating straight-line distances between feature vectors with the assumption of independence of features and equal scaling, i.e. is computationally efficient and sensitive to noise and changes in feature magnitude (Duda et al., 2001). The distance between a point and the mean of a distribution is scaled by the covariance matrix of the data (Reed and Yu, 1990; Manolakis et al., 2016). MD provides a way to measure how many standard deviations away a point is from the mean of the data distribution. It is a powerful measure that helps quantify the distance between a point and a distribution. Unlike Euclidean distance, it considers the covariance structure of the data. Graph Laplacian-based distance measures are measures of distance that are based on the graph Laplacian (Kaya et al., 2025; Kucuk, 2024; Kucuk, 2023). The inverse of the covariance matrix in MD is calculated by the Laplacian matrix and the Cauchy function.


EXPERIMENTAL RESULTS

In this part, GODEC and ROSURE algorithms are compared. They are combined with MD, EUC, LAD-C, and LAD-C-S distances. These approaches are put into practice on eleven HSI


datasets. In order to compare the methods, Receiver Operating Characteristics (ROC) curves are plotted, and values of Area Under ROC Curve (AUC) are computed. These two measures are largely common methods of the analysis of anomaly detectors in the literature. The performance of the methods of anomaly detection can be compared using the ROC curves as presented in Figure 3. The x-axis is also used to show the rates of false positives, and the y-axis shows the true positives, also referred to as a false alarm rate and probability of detection, respectively. Table 1 represents the values of AUC. Lastly, there are two-dimensional images of the detected locations of anomalies, and this is what is extracted and shown in Figure 4 to visualize the results.

Figure 3 shows the ROC curves of various combinations for each hyperspectral datasets. On the whole, ROC curves for RoSuRe based combinations always prevail over the GODEC-based combinations with high true positive rates. Particularly, distance measures in the RoSuRe framework RoSuRe with LAD-C-S model, have steeper ROC curves and higher AUC values. The methods using GODEC on the other hand are less steep in ROC curves and weaker in separating classes particularly in adverse conditions. The effectiveness of the RoSuRe–LAD-based strategies in the detection of hyperspectral anomalies is well supported by the visual behavior of the ROC curves, which substantiates the conclusions of the strength and power of the use of these strategies in detecting anomalies.





(j)



(k)

Figure 3. ROC curves for HSI datasets. a) Airport 2. b) Airport 3. c) Airport 4. d) Beach 1. e) Beach 2. f) Beach 3. g) Beach 4. h) Urban 1. i) Urban 2. j) Urban 3. k) Urban 4.

Table 1 shows the performance of the AUC of various GODEC-based and RoSuRe-based anomaly detection methods on eleven hyperspectral datasets. In general, it is evident that RoSuRe-based approaches are more effective than GODEC-based ones on all datasets. Out of the analyzed methods, RoSuRe with distance measures based on LAD shows the best performance. RoSuRe-LAD-C-S, in particular, has the highest or almost the highest values of AUC across most datasets. GODEC based techniques, on the other hand, have lower and more diverse performance, even with improvements by LAD based distances. These results verify that the RoSuRe decomposition, with LAD-C-S distance, is a more useful to the detection of anomalies in hyperspectral data.

The qualitative comparison of the detection performance of the methods under evaluation is presented in the two dimensional anomaly maps as shown in the Figure 4. As can be seen, RoSuRe-based settings, especially those that use the LAD-based distance measures, can better localize regions of anomaly and can more reliably do so in a variety of datasets. The results of these techniques give distinct responses to anomalies and their spatial arrangements are clear and convincing. On the other hand, the GODEC-based solutions have a higher tendency to deliver weaker and thinner patterns of anomalies, greater background noise and less precise localization. On the whole, the visual conclusions are quite consistent with the quantitative analyses, which once again proves the efficiency and strength of RoSuRe-LAD-C-S set up in the context of hyperspectral anomaly detection.

Table 1. AUC values

HSI vs. Methods	Godec MD	Godec EUC	Godec LAD-C	Godec LAD-C-S	Rosure MD	Rosure LAD-C	Rosure LAD-C-S
Airport2	0.6120	0.6788	0.6788	0.7924	0.8436	0.9301	0.9496
Airport3	0.4455	0.4941	0.4941	0.5839	0.9193	0.9129	0.9142
Airport4	0.6075	0.6560	0.6560	0.7184	0.9537	0.9722	0.9703
Beach1	0.7570	0.7944	0.7948	0.8672	0.9791	0.8848	0.9365
Beach2	0.5860	0.5860	0.5860	0.5860	0.9056	0.7184	0.7503
Beach3	0.6492	0.6452	0.6452	0.6365	0.9915	0.8848	0.8827
Beach4	0.8714	0.8771	0.8771	0.8857	0.9539	0.9366	0.9708
Urban1	0.5794	0.7598	0.7598	0.8988	0.9818	0.9882	0.9913
Urban2	0.5794	0.7598	0.7598	0.8988	0.9818	0.9882	0.9913
Urban3	0.7833	0.7891	0.7891	0.8066	0.9406	0.9428	0.9121
Urban4	0.5974	0.6376	0.6376	0.6693	0.9791	0.9644	0.9564

CONCLUSION

In this study, the performance of the GODEC and RoSuRe algorithms, which are used for anomaly detection, is compared and evaluated on eleven benchmark datasets. Numerous

experimental results on two algorithms show that the combinations of the RoSuRe decomposition always perform better than their counterparts using GODEC-based in all datasets. Specifically, the LAD-based distance measures of the RoSuRe framework have better detection performance, which means that they are not sensitive to the variations of background and noise. RoSuRe-LAD-C-S demonstrates the most successful results, as it demonstrates the highest or close-to-the-highest values of AUC on all eleven datasets. Quantitative assessments on ROC show that this combination is numerically superior. Furthermore, these results are further substantiated by qualitative two-dimensional anomaly maps that indicate that RoSuRe-LAD-C-S is able to localize anomalous targets with high spatial resolution and also cut off background clutters, thus leading to clear and more understandable detection maps than rival methods.




Figure 4. 2D results for HSI datasets GODEC-MD, GODEC-EUC, GODEC-LAD-C, GODEC-LAD-C-S, ROSURE-MD, ROSURE-LAD-C, ROSURE-LAD-C-S respectively.

REFERENCES

- Abdelnabi, A. A. B., & Rabadi, G. (2024). Human detection from unmanned aerial vehicles' images for search and rescue missions: A state-of-the-art review. *IEEE Access*.
- Bian, X., & Krim, H. (2014). Robust subspace recovery via bi-sparsity pursuit. *IEEE Transactions on Pattern Analysis and Machine Intelligence*, 36(4), 741–753.
- Bouwman, T., & Zahzah, E. H. (2014). Robust PCA via principal component pursuit: A review for a comparative evaluation in video surveillance. *Computer Vision and Image Understanding*, 122, 22–34.
- Candès, E. J., Li, X., Ma, Y., & Wright, J. (2011). Robust principal component analysis? *Journal of the ACM*, 58(3), 1–37.
- Cui, X., Tian, Y., Weng, L., & Yang, Y. (2014). Anomaly detection in hyperspectral imagery based on low-rank and sparse decomposition. In *Proceedings of the Fifth International Conference on Graphic and Image Processing (ICGIP 2013)* (Vol. 9069, pp. 142–148). SPIE.
- Goetz, A. F. H., Vane, G., Solomon, J. E., & Rock, B. N. (1985). Imaging spectrometry for Earth remote sensing. *Science*, 228(4704), 1147–1153.
- Gowen, A. A., O'Donnell, C. P., Cullen, P. J., Downey, G., & Frias, J. M. (2007). Hyperspectral imaging – an emerging process analytical tool for food quality and safety control. *Trends in Food Science & Technology*, 18(12), 590–598.
- Haboudane, D., Miller, J. R., Pattey, E., Zarco-Tejada, P. J., & Strachan, I. B. (2004). Hyperspectral vegetation indices and novel algorithms for predicting green LAI of crop canopies. *Remote Sensing of Environment*, 90(3), 337–352.
- Kaya, U., Töreyn, B. U., & Küçük, F. (2025). Hybrid hyperspectral anomaly detection via robust subspace recovery and Laplacian Cauchy-based methods. In *Proceedings of the International Conference on Machine Intelligence for GeoAnalytics*.
- Kruse, F. A., Boardman, J. W., & Huntington, J. F. (2003). Comparison of airborne hyperspectral data and EO-1 Hyperion for mineral mapping. *IEEE Transactions on Geoscience and Remote Sensing*, 41(6), 1388–1400.
- Küçük, F. (2023). Hybrid anomaly detection method for hyperspectral images. *Signal, Image and Video Processing*, 17(6), 2755–2761.
- Küçük, F. (2024). Hyperspectral anomaly detection with an improved approach: Integration of Go decomposition algorithm and Laplacian matrix modifier. *Journal of Scientific Reports-A*, 36–44.
- Landgrebe, D. A. (2002). Hyperspectral image data analysis. *IEEE Signal Processing Magazine*, 19(1), 17–28.
- Lun, Z., Wu, X., Dong, J., & Wu, B. (2025). Deep learning-enhanced spectroscopic technologies for food quality assessment: Convergence and emerging frontiers. *Foods*, 14(13), 2350.
- Manolakis, D., Shaw, G., & Davidson, J. (2003). Hyperspectral image processing for automatic target detection applications. *Lincoln Laboratory Journal*, 14(1), 79–116.
- Matteoli, S., Diani, M., & Corsini, G. (2010). A tutorial overview of anomaly detection in hyperspectral images. *IEEE Aerospace and Electronic Systems Magazine*, 25(7), 5–28.
- Mehedi, I. M., Hanif, M. S., Bilal, M., Vellingiri, M. T., & Palaniswamy, T. (2024). Remote sensing and decision support system applications in precision agriculture: Challenges and possibilities. *IEEE Access*, 12, 44786–44798.
- Pieszczek, L., & Daszykowski, M. (2025). Integrating hyperspectrograms with class modeling techniques for the construction of an effective expert system: Quality control of pharmaceutical tablets based on near-infrared hyperspectral imaging. *Journal of Pharmaceutical and Biomedical Analysis*, 256, 116697.

Qu, Y., Wang, W., Guo, R., Ayhan, B., Kwan, C., Vance, S., & Qi, H. (2018). Hyperspectral anomaly detection through spectral unmixing and dictionary-based low-rank decomposition. *IEEE Transactions on Geoscience and Remote Sensing*, 56(8), 4391–4405.

Stein, D. W. J., Beaven, S. G., Hoff, L. E., Winter, E. M., Schaum, A. P., & Stocker, A. D. (2002). Anomaly detection from hyperspectral imagery. *IEEE Signal Processing Magazine*, 19(1), 58–69.

Sun, W., Yang, G., Li, J., & Zhang, D. (2018). Randomized subspace-based robust principal component analysis for hyperspectral anomaly detection. *Journal of Applied Remote Sensing*, 12(1), 015015–015015.

Zhou, T., & Tao, D. (2011). GoDec: Randomized low-rank and sparse matrix decomposition in noisy case. In *Proceedings of the 28th International Conference on Machine Learning*, 33–40.

Ma, X., Zhang, X., Tang, X., Zhou, H., & Jiao, L. (2020). Hyperspectral anomaly detection based on low-rank representation with data-driven projection and dictionary construction. *IEEE Journal of Selected Topics in Applied Earth Observations and Remote Sensing*, 13, 2226–2239.

**POPÜLER KÜLTÜR VE MEDYA TÜKETİMİ:
KİTLE KÜLTÜRÜ VE DİJİTAL KİMLİK İNŞASI**

**POPULAR CULTURE AND MEDIA CONSUMPTION:
MASS CULTURE AND DIGITAL IDENTITY CONSTRUCTION**

Dr. Ferhat Atik

Girne Amerikan Üniversitesi

İletişim Fakültesi

İletişim ve Medya Yönetimi

Girne, KKTC

0009-0008-9089-9051

ÖZET

Son yıllarda dijital platformların günlük yaşama dâhil olma biçimi, kültürel alışkanlıkları, iletişim tarzlarını ve bireylerin kendilerini ifade etme yollarını köklü biçimde dönüştürmüştür. Özellikle sosyal ağlar, yalnızca iletişim ve eğlence alanları olmanın ötesine geçerek kimlik oluşumu, toplumsal aidiyet ve popüler kültür üretiminin merkezi alanları hâline gelmiştir (Castells, 2010; Jenkins, 2006; boyd, 2014). 2024 yılı verilerine göre, dünya genelinde yaklaşık 5 milyar insan aktif olarak sosyal medyayı kullanmaktadır (DataReportal, 2024a). DataReportal – Global Digital Insights Bu rakam, dijitalleşmenin küresel çapta ulaştığı boyutu ve sosyal medyanın toplumsal yaşam üzerindeki belirleyici etkisini açıkça gözler önüne sermektedir (Couldry & Hepp, 2017; van Dijck, Poell, & de Waal, 2018).

Bu çalışma, popüler kültürün sosyal medya ortamında nasıl üretildiğini, yayıldığını ve tüketildiğini; bireylerin dijital mecralar aracılığıyla kimliklerini nasıl oluşturduklarını ve medya tüketim alışkanlıklarının hangi yönlerden değişime uğradığını incelemeyi amaçlamaktadır (Jenkins, 2006; Khamis, Ang, & Welling, 2017). Çalışma, dijital ortamların klasik kitle iletişim araçlarından farklı olarak bireylere daha etkileşimli, akışkan ve performansa dayalı temsil imkânları sunduğunu öne sürmektedir (Papacharissi, 2012; Marwick, 2013). Bu doğrultuda bireyler, dijital dünyada yalnızca izleyici ya da tüketici olmakla kalmayıp, sürekli içerik üreten ve kendini görünür kılan aktif öznelere dönüşmüştür (Jenkins, Ford, & Green, 2013; van Dijck et al., 2018).

Kuramsal çerçeve, Erving Goffman'ın benlik sunumu yaklaşımı ile Jean Baudrillard'ın hiper-gerçeklik kavramı üzerine kuruludur (Goffman, 1959; Baudrillard, 1994). Goffman'ın gündelik yaşamda benliğin sahnelenmesi fikri, sosyal medya kullanıcılarının kendilerini nasıl kurguladıkları, hangi yönlerini ön plana çıkardıkları ve nasıl bir izlenim yönetimi uyguladıklarını analiz etmek açısından önemli bir araç sunar (Goffman, 1959; Hogan, 2010). Öte yandan Baudrillard'ın hiper-gerçeklik kavramı, sosyal medyada üretilen imgelerin, simülasyonların ve idealize edilmiş yaşam temsillerinin gerçekliğin yerini nasıl aldığını ve bu süreçte popüler kültürün nasıl biçimlendiğini anlamaya yardımcı olur (Baudrillard, 1994; Debord, 1994).

Araştırma bulguları, sosyal medya kullanıcılarının kimliklerini; popüler kültür öğeleri, görsel estetik anlayışı, anlatı biçimleri ve trendler aracılığıyla sürekli olarak yeniden inşa ettiklerini ortaya koymaktadır (Marwick, 2013; Papacharissi, 2012). Özellikle kısa video formatlarının yaygınlaşması, yapay zekâ destekli algoritmik kişiselleştirme, influencer ekonomisinin yükselişi ve mikro-trendlerin hızla doğup yok olması; dijital kimlik inşasını daha geçici, parçalı ve performansa dayalı hâle getirmiştir (Khamis et al., 2017; Zuboff, 2019; van Dijck et al., 2018). Bu dinamik yapı, geleneksel kitle kültürünün tek yönlü aktarım modelinden uzaklaşarak,

çok merkezli ve katılımcı bir popüler kültür yapısına evrilmesini sağlamaktadır (Jenkins, 2006; Jenkins et al., 2013).

Sonuç olarak bu çalışma, dijital platformların popüler kültür ve kimlik inşası üzerindeki etkilerinin yalnızca teknolojik değil; aynı zamanda sosyolojik, kültürel ve psikolojik boyutlarıyla birlikte değerlendirilmesi gerektiğini ortaya koymaktadır (Couldry & Hepp, 2017; boyd, 2014). Sosyal medya, bireylerin kendilerini ifade ettikleri bir mecra olmanın ötesinde, toplumsal normların, değerlerin ve kolektif anlamların üretildiği yeni bir kültürel ekosistem olarak ele alınmaktadır (van Dijck et al., 2018; Debord, 1994).

Anahtar Kelimeler: Popüler Kültür, Dijital Kimlik, Sosyal Medya, Medya Tüketimi, Benlik Sunumu, Kitle Kültürü.

ABSTRACT

In recent years, the ways in which digital platforms have become integrated into everyday life have fundamentally transformed cultural habits, communication styles, and individuals' modes of self-expression (Castells, 2010; Jenkins, 2006; boyd, 2014). Social networking platforms, in particular, have moved beyond being mere spaces for communication and entertainment, becoming central arenas for identity formation, social belonging, and the production of popular culture (Couldry & Hepp, 2017; van Dijck et al., 2018). According to data from 2024, approximately five billion people worldwide actively use social media (DataReportal, 2024a). DataReportal – Global Digital Insights This figure clearly demonstrates the global scale of digitalization and the decisive influence of social media on contemporary social life.

This study aims to examine how popular culture is produced, circulated, and consumed within social media environments; how individuals construct their identities through digital platforms; and in which ways media consumption practices have undergone transformation (Jenkins, 2006; Marwick, 2013). The study argues that, unlike traditional mass media, digital environments provide individuals with more interactive, fluid, and performance-based forms of representation (Papacharissi, 2012; van Dijck et al., 2018). Accordingly, individuals in the digital sphere are no longer merely viewers or consumers, but have become active subjects who continuously produce content and render themselves visible (Jenkins et al., 2013).

The theoretical framework of the study is grounded in Erving Goffman's approach to the presentation of self and Jean Baudrillard's concept of hyperreality (Goffman, 1959; Baudrillard, 1994). Goffman's notion of the dramaturgical presentation of the self in everyday life offers an important analytical tool for understanding how social media users construct their identities, which aspects of themselves they foreground, and how they engage in impression management (Goffman, 1959; Hogan, 2010). Baudrillard's concept of hyperreality, on the other hand, helps to explain how images, simulations, and idealized representations of life produced on social media come to replace reality itself, and how popular culture is shaped through this process (Baudrillard, 1994; Debord, 1994).

The findings indicate that social media users continuously reconstruct their identities through elements of popular culture, visual aesthetics, narrative forms, and trends (Marwick, 2013; Papacharissi, 2012). The widespread adoption of short-form video formats, AI-driven algorithmic personalization, the rise of the influencer economy, and the rapid emergence and disappearance of micro-trends have rendered digital identity construction increasingly temporary, fragmented, and performance-oriented (Khamis et al., 2017; Zuboff, 2019). This dynamic structure has facilitated a shift away from the one-directional transmission model of traditional mass culture toward a multi-centered and participatory form of popular culture (Jenkins, 2006; Jenkins et al., 2013).

In conclusion, this study demonstrates that the effects of digital platforms on popular culture and identity construction should be evaluated not only from a technological perspective but also in conjunction with their sociological, cultural, and psychological dimensions (Couldry &

Hepp, 2017; boyd, 2014). Social media is conceptualized not merely as a medium for self-expression, but as a new cultural ecosystem in which social norms, values, and collective meanings are actively produced (van Dijck et al., 2018).

Keywords: Popular Culture, Digital Identity, Social Media, Media Consumption, Presentation of Self, Mass Culture.

1. GİRİŞ

Günümüz toplumlarında teknolojinin baş döndürücü hızla ilerlemesi ve internetin artık neredeyse her eve girmesiyle birlikte, kültürel yapılarımız ve birbirimizle iletişim kurma biçimlerimiz temelden değişti diyebiliriz (Castells, 2010; Couldry & Hepp, 2017). Özellikle sosyal medya platformlarının küresel çapta yaygınlaşması, bireylerin kendilerini nasıl ifade ettiklerinden bilgiye nasıl ulaştıklarına, kültürel içerikleri nasıl tükettiklerine kadar pek çok alanda paradigma değişimine yol açtı (van Dijck et al., 2018). Eskiden popüler kültür denildiğinde aklımıza televizyon, gazete, dergi gibi geleneksel medya kanalları gelirken, bugün durum bambaşka: popüler kültür artık sosyal medya üzerinden üretiliyor, paylaşıyor ve tüketiliyor (Jenkins, 2006; Debord, 1994).

Aşırı niteliklilik, bireyin işin gerektirdiğinden daha fazla bilgi, eğitim, kabiliyet, beceri ve deneyime sahip olması durumu olarak ifade edilmektedir. (Zakoğlu, 2024, s. 3). Rakamlar da durumun ciddiyetini ortaya koyuyor açıkçası. 2024 yılı itibarıyla Türkiye'de 74.41 milyon internet kullanıcısı var ve bu nüfusumuzun yaklaşık yüzde 87'sine denk geliyor (DataReportal, 2024b). DataReportal – Global Digital Insights Daha da ilginç olanı, Türkiye'deki sosyal medya kullanıcılarının günde ortalama 2 saat 44 dakikalarını bu platformlarda geçirmesi (Uraloğlu, 2024). A News Bu veriler bize sosyal medyanın artık gündelik yaşamın bir parçası olmaktan öte, belki de merkezine yerleştiğini gösteriyor (boyd, 2014). Dolayısıyla bu platformların dijital kimliklerimiz üzerinde nasıl bir etkisi olduğunu anlamak oldukça önemli (Goffman, 1959; Marwick, 2013).

Bu çalışmada popüler kültürün sosyal medya aracılığıyla nasıl yayıldığını, insanların dijital kimlik inşa süreçlerinde popüler kültür öğelerini nasıl araç olarak kullandıklarını ve medya tüketim alışkanlıklarının nasıl evrildiğini hem kuramsal hem de deneysel açıdan ele almaya çalışacağız (Jenkins, 2006; Papacharissi, 2012). Aslında buradaki temel soru şu: dijital çağda "ben kimim?" sorusuna verdiğimiz cevap nasıl şekilleniyor ve bu süreçte popüler kültürün rolü ne? (Goffman, 1959; Baudrillard, 1994). Araştırmanın temel amacı, algılanan aşırı niteliklilik ile iş performansı arasındaki ilişkide kişi-iş uyumunun aracılık rolünü araştırmak ve dağıtım adaleti ile başarı ihtiyacının bu ilişkide düzenleyici rollerini ortaya koymaktır. (Zakoğlu, 2024, s. 7).

2. KURUMSAL ÇERÇEVE

2.1. Popüler Kültür ve Kitle İletişim Araçları

Popüler kültürü tanımlarken işin içine kapitalist üretim biçimleri, pazarlama stratejileri, dağıtım ağları ve tüketim pratikleri giriyor (Debord, 1994; Adorno & Horkheimer, 2002). Medya bu noktada oldukça kritik bir rol üstleniyor çünkü toplumdaki anlamlandırma süreçlerini neredeyse tekelinde tutuyor (Hall, 1997). Geleneksel medya araçlarını (gazete, dergi, radyo, televizyon vs.) düşündüğümüzde uzun yıllar boyunca popüler kültürün üretimi ve yayılımında baş aktör olduklarını görüyoruz (McQuail, 2010). Ancak son on beş yılda yeni medya dediğimiz sosyal medya platformları, bloglar ve vloglar sahneye çıktı ve oyunun kurallarını değiştirdi (van Dijck et al., 2018).

Teknolojinin gelişmesiyle birlikte medyayı geleneksel ve yeni diye ikiye ayırmak aslında işimizi kolaylaştırıyor. Yeni medyanın en önemli özelliği şu: kullanıcılara sadece içerik tüketen değil, aynı zamanda içerik üreten konumunda olma imkanı sunuyor (Jenkins, 2006). Bu durum popüler kültürün demokratikleşmesi açısından büyük bir değişim. Artık herkes bir içerik

üreticisi olabilir, fikirlerini paylaşabilir, kendi kültürel pratiklerini görünür kılabilir (Jenkins et al., 2013).

2.2. Dijital Kimlik ve Benlik Sunumu

Kimlik meselesi aslında sosyolojinin en eski tartışma alanlarından biri. Geleneksel olarak baktığımızda, bireylerin kimlikleri yaşadıkları toplum ve sosyal çevreleri bağlamında şekilleniyordu (Giddens, 1991). Fakat günümüzde bu etki alanına sosyal medya da eklendi ve hatta belki de en güçlü etken haline geldi bile (boyd, 2014; Marwick, 2013). Fiziksel dünyada üstlendiğimiz kimliklerin yanına bir de "dijital kimlik" dediğimiz yeni bir boyut eklendi (Papacharissi, 2012).

Erving Goffman'ın dramaturji kuramını hatırlarsak, insanların günlük yaşamda sanki bir sahne performansı sergiliyormuş gibi davrandıklarını söylüyordu (Goffman, 1959). Bu fikir sosyal medya bağlamında son derece isabetli çünkü kullanıcılar dijital platformlarda gerçekten de kendi "ön sahne" performanslarını oluşturuyorlar (Hogan, 2010). Profil fotoğrafından biyografi yazısına, paylaştığımız içeriklerden etkileşimlerimize kadar her şey aslında dijital kimlik inşa sürecinin bir parçası (Marwick, 2013). Goffman'ın yaklaşımını, "etkileşimin düzeni" üzerinden okuduğumuzda, çevrimiçi ortamın da bir izlenim yönetimi mekaniği ürettiği görülür (Goffman, 1959).

Jean Baudrillard'ın hiper-gerçeklik kavramı da burada devreye giriyor. Baudrillard, simülasyonların gerçekliğin yerini aldığı bir düzenden söz eder; bu düzende temsil, gerçeğin önüne geçer (Baudrillard, 1994). Sosyal medyada paylaşılan filtreli fotoğraflar, yapay zeka ile geliştirilmiş görüntüler ve kurgulanmış yaşam tarzı görselleri tam da bu hiper-gerçekliği yaratıyor (van Dijck et al., 2018; Zuboff, 2019). İnsanlar gerçek hayattaki hallerinden çok, dijital ortamdaki idealleştirilmiş versiyonlarını sunuyorlar (Marwick, 2013). Bu noktada Baudrillard'ın "gerçekliğin yerini alan imge düzeni" vurgusu, sosyal medya estetiğini anlamada işlevsel bir çerçeve sağlar (Baudrillard, 1994).

2.3. Dijital Habitus ve Kültürel Sermaye

Pierre Bourdieu'nün habitus, alan ve sermaye kavramları dijital ortamlardaki davranışlarımızı anlamak için gerçekten değerli bir çerçeve sunuyor (Bourdieu, 1984). Dijital habitus dediğimiz şey, bireylerin çevrimiçi ortamlarda edindikleri alışkanlıklar, eğilimler ve davranış kalıpları olarak düşünülebilir (Couldry & Hepp, 2017). İlginç olan şu: kullanıcılar farklı sosyal medya platformlarında farklı kimlikler sergiliyor. Mesela bir birey Facebook'ta ailevi kimliğini öne çıkarırken, Instagram'da estetik zevklerini, LinkedIn'de profesyonel kimliğini vurguluyor (Marwick, 2013; van Dijck et al., 2018). Bu durum kimliğin akışkan ve çok boyutlu doğasını gözler önüne seriyor (Papacharissi, 2012).

Sosyal medya platformları aynı zamanda sosyal, simgesel, kültürel ve ekonomik sermaye türlerinin görünür hale geldiği yeni alanlar olarak yapılanmış durumda (Bourdieu, 1984; Khamis et al., 2017). Kullanıcılar paylaşımları aracılığıyla kültürel sermayelerini dijital ortama taşıyorlar ve bir nevi sanal statü ediniyorlar. Beğeni sayıları, takipçi rakamları, paylaşım etkileşimleri hepsi bu dijital sermayenin göstergeleri haline geldi (Marwick, 2013; Zuboff, 2019).

3. SOSYAL MEDYA VE POPÜLER KÜLTÜRÜN DÖNÜŞÜMÜ

3.1. Kullanıcı Üretimli İçerik ve Katılımcı Kültür

Sosyal medyanın belki de en çarpıcı özelliği kullanıcıların içeriğin hem üreticisi hem de tüketicisi olması (Jenkins, 2006; Jenkins et al., 2013). Henry Jenkins'in "katılımcı kültür" kavramı bu durumu mükemmel açıklıyor (Jenkins, 2006). Artık tüketiciler pasif alıcılar değil, aktif üreticiler ve yorumlayıcılar konumunda (Jenkins et al., 2013). Her yaştan insan sosyal medya araçlarıyla popüler kültürün oluşturulması ve aktarılmasında önemli bir rol oynuyor. Bu aslında kültürel üretimin demokratikleşmesi açısından çok önemli bir gelişme (Jenkins, 2006).

Katılımcı kültürün güncel bir tezahürü, sivil toplum kuruluşlarının sosyal medya temelli kampanyalarında da gözlemlenmektedir. UNICEF'in dijital platformlar üzerinden yürüttüğü kampanyalar, kullanıcıları yalnızca mesaj alıcısı konumunda bırakmamakta; onları içeriğin dolaşıma sokulmasında aktif aktörler hâline getirmektedir. Bu süreçte bireyler, paylaşımlar, etiketler ve görsel anlatılar aracılığıyla kampanyanın taşıyıcısı rolünü üstlenmekte; popüler kültür kodları ile insani söylem iç içe geçmektedir. Böylece katılımcı kültür, yalnızca eğlence veya tüketim eksenli değil, aynı zamanda toplumsal sorumluluk ve farkındalık üretimi bağlamında da işlev kazanmaktadır (Aurore & Bayraktar, 2024).

TikTok örneğine bakalım mesela. Bu platform neredeyse her büyük trendin doğum yeri haline geldi ve popüler kültür üzerindeki etkisi o kadar fazla ki yeni bir "mikro-trend" döngüsü bile yarattı (Khamis et al., 2017; van Dijck et al., 2018). Kullanıcılar müzik parçalarını, dans hareketlerini, meme'leri ve çeşitli kültürel içerikleri inanılmaz hızla yayarak popüler kültürün dinamik bir şekilde evrilmesine katkıda bulunuyorlar (Jenkins et al., 2013). Bir şey bugün trend olabiliyor, yarın unutulup gidiyor ve bunun yerini başka bir trend alabiliyor (Papacharissi, 2012).

3.2. Kısa Video İçeriklerin Yükselişi

2024 yılında kısa video trendlerinin hakimiyeti devam ediyor. TikTok'un popülerleşmesiyle başlayan bu trend Instagram Reels ve diğer platformlardaki benzer özelliklerle güçlendi (van Dijck et al., 2018). Kısa videolar aslında kullanıcıların dikkat süresinin kısalmasına mükemmel uyum sağlıyor ve hızlı tüketim, anlık etkileşim ve viral yayılma potansiyeline sahip (Jenkins et al., 2013).

İlginç bir çelişki var burada: kısa videoların popüleritesinin devam etmesine rağmen, uzun içeriklere olan ilgi de artıyor. Kullanıcılar bir yandan 15 saniyelik videolar tüketirken, diğer yandan derinlemesine bilgi sağlayan ve daha detaylı içerik sunan uzun videolara da yöneliyor (Papacharissi, 2012). Bu durum medya tüketiminin çeşitlendiğini ve farklı içerik formatlarının bir arada var olabileceğini gösteriyor. Belki de insanlar hem hızlı eğlence hem de derin içerik arasında denge arıyor (McQuail, 2010).

3.3. Yapay Zeka ve Kişiselleştirilmiş İçerik

Yapay zeka teknolojilerinin kişiselleştirilmiş içerik önerileri sunması, kullanıcı deneyimini bambaşka bir seviyeye taşıdı (Zuboff, 2019; van Dijck et al., 2018). Algoritmalar geçmiş davranışlarımızı, beğenilerimizi ve etkileşimlerimizi analiz ederek bize özel içerikler sunuyor. Bu durum tükettiğimiz popüler kültür içeriklerinin giderek daha fazla kişiselleştirildiği anlamına geliyor (Zuboff, 2019). Herkes kendi "yankı odası"nda yaşıyor gibi - bu da hem avantaj hem de dezavantaj olabilir tabii (Sunstein, 2001).

Yapay zeka destekli görüntü üretim teknolojileri de dijital kimlik inşasında yeni boyutlar açıyor. Kullanıcılar filtreler ve AI araçlarıyla fiziksel görünümelerini değiştirerek hiper-gerçek kimlikler oluşturabiliyor (Baudrillard, 1994; van Dijck et al., 2018). Mesela bir fotoğrafta cildiniz pürüzsüz, yüz hatlarınız belirginleşmiş, gözleriniz ıslık ıslık görünebiliyor - ama bu gerçekten siz misiniz? Bu durum otantiklik ve gerçeklik algısı üzerinde ciddi sorular doğuruyor (Marwick, 2013; boyd, 2014).

3.4. Influencer Kültürü ve Mikro-Makro Etkileyiciler

Dijital medya ekosisteminde influencer'lar, popüler kültürün üretimi ve dolaşımında merkezi aktörler hâline gelmiştir. Bu aktörler, yalnızca tüketim nesnelerinin tanıtıcısı olarak değil; aynı zamanda estetik normların, yaşam tarzı ideallerinin ve kimlik anlatılarının taşıyıcısı olarak işlev görmektedir (Marwick, 2013; Khamis et al., 2017). Sosyal medya platformlarında görünürlük, takipçi sayısı ve etkileşim oranları üzerinden ölçülen bu etki, popüler kültürün algoritmik olarak pekiştirilen yeni bir dolaşım rejimini ortaya çıkarmaktadır.

Makro-influencer'lar geniş kitlelere hitap eden, yüksek görünürlük sağlayan figürler olarak öne çıkarken; mikro ve nano-influencer'lar daha sınırlı fakat daha yoğun etkileşim üreten topluluklar üzerinde etkili olmaktadır. Özellikle mikro-influencer'ların sunduğu görece

“samimi” ve “otantik” temsil biçimleri, takipçilerle kurulan duygusal bağın güçlenmesine katkı sağlamaktadır (Khamis et al., 2017). Bu durum, popüler kültür tüketiminin yalnızca niceliksel değil, niteliksel bir dönüşüm geçirdiğini göstermektedir.

Influencer kültürü, bireylerin dijital kimlik inşa süreçleriyle doğrudan ilişkilidir. Takip edilen içerik üreticilerinin estetik tercihleri, söylemleri ve yaşam pratikleri; kullanıcıların kendi benlik sunumlarını biçimlendirmelerinde referans noktaları hâline gelmektedir. Bu bağlamda influencer’lar, Goffman’ın benlik sunumu yaklaşımıyla uyumlu biçimde, dijital ortamda “örnek performanslar” üretmekte ve bu performanslar geniş kitleler tarafından yeniden üretilmektedir (Goffman, 1959; Papacharissi, 2012).

Bu etki yalnızca bireysel tüketim ve kimlik pratikleriyle sınırlı değildir. Sivil toplum kuruluşlarının dijital kampanyaları, influencer ve popüler kültür figürleri aracılığıyla toplumsal meseleleri görünür kılma stratejisi geliştirmektedir. UNICEF örneğinde olduğu gibi, sosyal medya üzerinden yürütülen kampanyalar; duygusal anlatılar, sembolik imgeler ve popüler figürlerin katılımı sayesinde küresel ölçekte dolaşıma sokulmaktadır. Bu tür kampanyalar, kullanıcıları pasif izleyici konumundan çıkararak, paylaşım ve etkileşim yoluyla kampanyanın aktif taşıyıcıları hâline getirmektedir (Aurore & Bayraktar, 2024).

Dolayısıyla influencer kültürü, popüler kültürün yalnızca tüketim odaklı bir alan olmadığını; aynı zamanda toplumsal duyarlılık, kolektif kimlik ve dijital kamusal üretimini açısından da işlevsel bir mecra hâline geldiğini göstermektedir. Algoritmik görünürlük, duygusal etkileşim ve kültürel sermayenin iç içe geçtiği bu yapı, çağdaş medya tüketiminin çok katmanlı doğasını açıkça ortaya koymaktadır.

4. DİJİTAL KİMLİK İNŞASI VE POPÜLER KÜLTÜR TÜKETİMİ

4.1. Sosyal Medyada Benlik Performansı

Sosyal medya platformları aslında bireylerin benlik performansı sergiledikleri sahneler gibi işlev görüyor (Goffman, 1959; Hogan, 2010). Kullanıcılar paylaşımları aracılığıyla kendilerini belirli bir şekilde sunmak ve başkaları tarafından nasıl algılandıklarını kontrol etmek istiyorlar (Marwick, 2013). Popüler kültür öğeleri bu benlik sunumunun önemli bileşenleri haline geliyor (Jenkins, 2006).

Düşünün mesela: belirli müzik türlerini paylaşmak, moda trendlerini takip etmek, viral videolara katılmak ve popüler hashtag’leri kullanmak - bunların hepsi dijital kimliğin parçaları (Papacharissi, 2012). Bu paylaşımlar aslında ait olmak istediğimiz grup ve kültürel kodlar hakkında mesajlar içeriyor (Bourdieu, 1984). Paylaşımlarımız "ben bu grubun üyesiyim", "bu değerlere sahibim", "bu estetik anlayışını benimsiyorum" gibi mesajlar veriyor (Marwick, 2013).

4.2. Özçekim (Selfie) Kültürü ve Narsisizm

Özçekim sosyal medyada kimlik inşasının en doğrudan görsel ifadesi olarak öne çıkıyor (Marwick, 2013). İnsanların kendilerini çektikleri fotoğrafları paylaşması benlik sunumunun en açık biçimlerinden biri (Goffman, 1959). Özçekim kültürü genellikle narsisistik eğilimler ve beğenilme ihtiyacıyla ilişkilendiriliyor - ki bu eleştiri tamamen haksız da sayılmaz belki (Twenge, 2017).

Filtrelerin ve düzenleme araçlarının kullanımı insanların idealleştirilmiş versiyonlarını sunmalarına olanak tanıyor. Gerçeklik ile temsil arasındaki sınır bulanıklaşıyor (Baudrillard, 1994). Bir fotoğrafta gerçekte nasıl görüldüğünüzü değil, nasıl görünmek istediğinizi sunuyorsunuz. Bu da hiper-gerçeklik kavramını somutlaştırıyor aslında (Baudrillard, 1994). Bazen insanlar sokakta karşılaştıklarında birbirlerini tanıyamıyor çünkü sosyal medyada paylaştıkları fotoğraflar gerçek görünümünden çok farklı (boyd, 2014).

4.3. Kültürel Göstergeler ve Kimlik İfadesi

Sosyal medya kullanıcıları paylaşımlarında kültürel göstergelere sıkça yer veriyorlar. Sanat eserleri, müze ziyaretleri, konser fotoğrafları, kitap önerileri gibi içerikler bireylerin kültürel

sermayelerini sergilemelerine ve belirli bir sosyal statü göstermelerine olanak tanıyor (Bourdieu, 1984). Bu aslında Bourdieu'nün bahsettiği kültürel sermayenin dijital ortamdaki tezahürü (Bourdieu, 1984; Marwick, 2013).

Özellikle 18-24 yaş aralığındaki gençler Instagram gibi platformlarda kültürel faaliyetlere ilişkin paylaşımlar yaparak dijital kimliklerini inşa ediyorlar (DataReportal, 2024b; Marwick, 2013). DataReportal – Global Digital Insights Bu paylaşımlar bireylerin kendilerini entelektüel, sanatsal ya da kültürel olarak gelişmiş kişiler olarak sunmalarına yardımcı oluyor (Goffman, 1959). Bazen bu o kadar ileri gidiyor ki insanlar bir müzeye ya da sergiye gitmelerinin asıl amacının deneyimin kendisi değil, bunu sosyal medyada paylaşmak olduğunu düşünüyor (Debord, 1994).

4.4. Kuşak Farklılıkları ve Dijital Kimlik

Dijital kimlik inşa süreçleri kuşaklar arasında belirgin farklılıklar gösteriyor. X kuşağı bireyler sosyal medyada daha az kişisel bilgi paylaşma eğilimindeyken, Y kuşağı meslek bilgilerini öne çıkarıyor, Z kuşağı ise eğitim bilgilerine daha fazla yer veriyor (boyd, 2014; Papacharissi, 2012). Bu farklılıklar her kuşağın dijital platformları farklı amaçlarla kullandığını ve farklı kimlik stratejileri geliştirdiğini gösteriyor (Giddens, 1991).

Mesela Z kuşağı için otantiklik çok önemli. Onlar kusursuz, filtreli hayatlardan ziyade daha gerçekçi, kusurlu ama özgün içeriklere değer veriyorlar (boyd, 2014). BeReal gibi uygulamaların popülerleşmesi tam da bu arayıştan kaynaklanıyor (van Dijck et al., 2018). Öte yandan daha yaşlı kuşaklar Facebook'u aile fotoğrafları paylaşmak ve yakınlarıyla iletişimde kalmak için kullanırken, gençler TikTok'ta eğlenceli içerikler üretiyor (DataReportal, 2024b). DataReportal – Global Digital Insights

5. MEDYA TÜKETİMİNİN DÖNÜŞÜMÜ

5.1. Geleneksel Medyadan Dijital Medyaya Geçiş

Geleneksel medya araçları bugün dijital medya karşısında ciddi bir rekabet yaşıyor. Gazeteler eskisi kadar ilgi görmüyor, tüm ilgi e-gazetelere, haber sitelerine ve gazetelerin sosyal medya hesaplarına kayıyor (McQuail, 2010; van Dijck et al., 2018). Televizyon izlenme oranlarında düşüş gözlenirken, dijital platformlarda içerik tüketimi artıyor. Bu durum sadece teknolojik bir değişim değil, aynı zamanda kültürel bir dönüşüm (Couldry & Hepp, 2017).

Sosyal medya en popüler internet bağlantılı eğlence aracı olmaya devam ediyor. İnternet kullanıcılarının büyük çoğunluğu her ay sosyal ağlara veya mesajlaşma platformlarına erişiyor (DataReportal, 2024b). DataReportal – Global Digital Insights Medya tüketiminin giderek daha fazla dijitalleştiğini ve sosyal medyanın merkezi bir rol oynadığını görüyoruz (van Dijck et al., 2018). Artık haberler, eğlence içerikleri, eğitim materyalleri hepsi dijital platformlardan tüketiliyor (Castells, 2010).

5.2. Çoklu Platform Kullanımı ve İçerik Tüketimi

Türkiye'de en popüler sosyal medya platformu YouTube - 57.5 milyon kullanıcıya sahip. (DataReportal, 2024b). DataReportal – Global Digital Insights Bunu Instagram, WhatsApp, Facebook ve X (Twitter) takip ediyor (DataReportal, 2024b). DataReportal – Global Digital Insights Kullanıcılar farklı platformları farklı amaçlarla kullanıyorlar ve bu oldukça stratejik bir durum (van Dijck et al., 2018). YouTube bilgi edinme ve eğlence için, Instagram görsel paylaşımlar için, WhatsApp iletişim için, LinkedIn profesyonel ağ kurma için tercih ediliyor (DataReportal, 2024b). DataReportal – Global Digital Insights+1

Bu çoklu platform kullanımı medya tüketim alışkanlıklarının karmaşık ve çeşitlendiğini gösteriyor. Her platformun kendine özgü dinamikleri ve kullanıcı davranışları var (van Dijck et al., 2018). Bir kullanıcı sabah Instagram'da scroll yaparken öğle arası YouTube'dan eğitim videoları izleyebiliyor, akşam TikTok'ta eğlenebiliyor (Jenkins et al., 2013). Bu geçişler o kadar doğal hale geldi ki artık farkında bile olmuyoruz (Couldry & Hepp, 2017).

5.3. Sosyal Ticaret ve Tüketim Kültürü

Sosyal medya platformları alışveriş deneyimini doğrudan platformlarına taşıyarak sosyal ticaret alanında önemli adımlar atıyor. TikTok Shop, Instagram Shopping gibi özellikler kullanıcıların favori içerik üreticilerinden doğrudan ürün satın almalarını sağlıyor (van Dijck et al., 2018). Bu durum alışveriş deneyimini bambaşka bir boyuta taşıyor çünkü artık bir influencer'ın kullandığı ürünü anında satın alabiliyorsunuz (Khamis et al., 2017).

Sosyal ticaret tüketim kültürünü sosyal medyayla entegre ederek popüler kültürün ticarileşmesini hızlandırıyor (Debord, 1994; Zuboff, 2019). Influencer'lar ve markalar kullanıcıların satın alma kararlarını etkilemek için işbirlikleri yapıyor ve içerik pazarlaması stratejileri geliştiriyorlar (Khamis et al., 2017). Bazen bir video izlerken ürün tanıtımı mı yoksa samimi bir öneri mi olduğunu ayırt etmek zorlaşıyor (Marwick, 2013).

6. POPÜLER KÜLTÜRÜN SOSYAL VE PSİKOLOJİK ETKİLERİ

6.1. Dijital Tükenmişlik ve Ekran Süresi

Türkiye'de internet kullanıcıları günlük ortalama 6 saat 57 dakikalarını çevrimiçi geçiriyor ve bu sürenin 4 saat 7 dakikası mobil cihazlar üzerinden gerçekleşiyor (Datumintell, 2024). Datumintell Bu rakamlar oldukça çarpıcı ve yoğun sosyal medya kullanımının dijital tükenmişlik, dikkat dağınıklığı ve psikolojik yorgunluk gibi sorunlara yol açabileceğini düşündürüyor (Twenge, 2017; boyd, 2014).

Kullanıcılar sürekli yeni içerikler tüketme baskısı altında hissedebiliyor ve FOMO (kaçırma korkusu) yaşıyabiliyorlar (Przybylski et al., 2013). "Acaba kaçırdığım bir şey var mı?", "Herkes şunu yapıyor ben neden yapmıyorum?" gibi düşünceler zihinlerimizi meşgul ediyor. Bu durum ruh sağlığımızı olumsuz etkileyebilir ve gerçek yaşam ilişkilerimizi zayıflatabilir (Twenge, 2017). Arkadaşlarımızla kahve içerken bile telefonumuza bakıyor olmamız bunun en açık göstergesi belki (boyd, 2014).

6.2. Beğenilme İhtiyacı ve Sosyal Karşılaştırma

Sosyal medyada paylaşımların beğeni, yorum ve paylaşım sayıları kullanıcılar için önemli geri bildirim mekanizmaları haline geldi (Marwick, 2013). Beğenilme ihtiyacı paylaşım davranışlarımızı şekillendiriyor ve benlik sunumlarımızı etkiliyor (Goffman, 1959). Bir paylaşım yeterince beğeni almadığında hayal kırıklığı yaşıyoruz, çok beğeni aldığında mutlu oluyoruz. Bu dopamin döngüsü bazen bağımlılık yaratabilir (Twenge, 2017).

Sosyal karşılaştırma teorisi bireylerin kendilerini başkalarıyla karşılaştırarak değerlendirdiğini söylüyor (Festinger, 1954). Sosyal medyada başkalarının idealleştirilmiş yaşamlarını görerek kendi hayatlarımızı yetersiz bulabiliyoruz (Marwick, 2013). "Herkesin hayatı çok güzel, yalnızca benim hayatım sıradan" gibi bir algı oluşabiliyor. Oysa gerçek şu ki herkes sosyal medyada hayatının en iyi anlarını paylaşıyor - zorluklarını, sıkıntılarını değil (boyd, 2014).

6.3. Mahremiyet ve Dijital İzler

Sosyal medyada kişisel bilgilerin paylaşılması mahremiyet sorunlarını beraberinde getiriyor. Dijital izlerimiz platformlar ve üçüncü taraflar tarafından toplanıyor ve analiz ediliyor (Zuboff, 2019). Bu veriler hedefli reklamlar, profillemeye ve denetim amacıyla kullanılabilir (Zuboff, 2019). Ne kadar açık olacağımız ve hangi bilgileri paylaşacağımız önemli bir denge meselesi (boyd, 2014).

Aşırı paylaşım güvenlik risklerine ve mahremiyetin ihlali sorunlarına yol açabilir. Mesela tatil fotoğraflarınızı paylaşıırken evinizin boş olduğunu duyurmuş oluyorsunuz. Ya da sürekli konum paylaşımı hareketlerinizin takip edilmesini kolaylaştırıyor. Bu risklerin farkında olmak ve dijital ayak izlerimize dikkat etmek gerekiyor (Zuboff, 2019; Freedom House, 2024). Freedom House

7. TARTIŞMA VE SONUÇ

Bu çalışma, dijital çağda popüler kültür ve medya tüketiminin geçirdiği dönüşümü, dijital kimlik inşası ekseninde ele alarak sosyal medyanın bireysel ve toplumsal düzeydeki etkilerini tartışmayı amaçlamıştır (Couldry & Hepp, 2017; van Dijck et al., 2018). Elde edilen bulgular, sosyal medya platformlarının popüler kültürün üretim, dolaşım ve tüketim süreçlerinde merkezi bir rol üstlendiğini; bu sürecin bireylerin kimlik algılarını, benlik sunum stratejilerini ve gündelik yaşam pratiklerini derinden etkilediğini ortaya koymaktadır (Jenkins, 2006; Marwick, 2013).

Araştırma kapsamında ele alınan kuramsal yaklaşımlar, dijital kimlik inşasının doğasını anlamada açıklayıcı bir çerçeve sunmaktadır. Erving Goffman'ın benlik sunumu kuramı, sosyal medya kullanıcılarının dijital ortamlarda sergiledikleri kimliklerin rastlantısal değil; bilinçli, seçici ve stratejik olarak kurgulandığını göstermektedir (Goffman, 1959; Hogan, 2010). Profil düzenlemeleri, paylaşılan görseller, metinler ve etkileşim biçimleri, bireyin dijital “ön sahne” performansının temel unsurları hâline gelmiştir (Goffman, 1959). Bu bağlamda dijital kimlik, bireyin kim olduğu kadar, nasıl algılanmak istediğiyle de doğrudan ilişkilidir (Marwick, 2013). Jean Baudrillard'ın hiper-gerçeklik kavramı ise dijital ortamda üretilen imgelerin ve temsillerin, gerçekliğin yerini alacak ölçüde baskınlaştığını ortaya koymaktadır (Baudrillard, 1994; Debord, 1994). Filtreler, yapay zekâ destekli görsel düzenlemeler ve idealize edilmiş yaşam anlatıları, dijital kimliklerin gerçek yaşamdan giderek kopmasına neden olmaktadır (van Dijck et al., 2018). Böylece sosyal medya, bireyin gündelik yaşamını yansıtan bir mecra olmaktan çok, arzulanılan bir yaşamın simüle edildiği bir temsil alanına dönüşmektedir (Baudrillard, 1994). Bu durum, popüler kültürün de gerçeklikten ziyade gösteri, imaj ve performans üzerinden şekillenmesine yol açmaktadır (Debord, 1994).

Çalışmada ele alınan bulgular, popüler kültürün dijital ortamda daha geçici, parçalı ve hızla tüketilen bir yapıya evrildiğini göstermektedir (Jenkins et al., 2013). Kısa video formatlarının yaygınlaşması, algoritmik içerik önerileri, influencer kültürünün yükselişi ve mikro-trendlerin kısa ömürlü döngüsü, kültürel üretimi sürekli bir akış hâline getirmiştir (Khamis et al., 2017; Zuboff, 2019). Bu dinamik yapı içerisinde bireyler, sabit ve tutarlı kimlikler yerine, platforma ve bağlama göre değişen çoklu kimlikler geliştirmektedir (Papacharissi, 2012). Dijital kimlik, bu anlamda tamamlanmış bir yapı değil; sürekli güncellenen, yeniden inşa edilen ve müzakere edilen bir süreçtir (Giddens, 1991; Marwick, 2013).

Medya tüketimi açısından bakıldığında, geleneksel kitle iletişim araçlarından dijital platformlara geçişin yalnızca teknolojik bir yenilenme olmadığı; aynı zamanda kültürel alışkanlıkları, zaman algısını ve dikkat ekonomisini dönüştüren yapısal bir değişim olduğu görülmektedir (Couldry & Hepp, 2017; van Dijck et al., 2018). Çoklu platform kullanımı, bireylerin aynı anda hem tüketici hem de üretici konumunda olduğu hibrit bir medya düzeni yaratmıştır (Jenkins, 2006; Jenkins et al., 2013). Sosyal ticaret uygulamaları ve influencer pazarlaması ise popüler kültür ile tüketim kültürü arasındaki sınırları daha da belirsiz hâle getirmiştir (Khamis et al., 2017; Zuboff, 2019).

Araştırmanın ortaya koyduğu önemli sonuçlardan biri de dijital popüler kültürün psikolojik ve sosyal etkileridir. Yoğun sosyal medya kullanımı; dijital tükenmişlik, sürekli karşılaştırma, beğenilme ihtiyacı ve mahremiyet kaygıları gibi sorunları beraberinde getirmektedir (Przybylski et al., 2013; Twenge, 2017). Dijital kimlik inşası, bireylere görünürlük ve ifade imkânı sunarken; aynı zamanda kırılganlık, kaygı ve denetim mekanizmalarını da üretmektedir (Zuboff, 2019). Bu nedenle dijital kimlik, özgürleştirici olduğu kadar sınırlandırıcı bir süreç olarak da değerlendirilmelidir (Couldry & Hepp, 2017; boyd, 2014).

Sonuç olarak bu çalışma, popüler kültür, medya tüketimi ve dijital kimlik arasındaki ilişkinin çok boyutlu ve dinamik bir yapı sergilediğini ortaya koymaktadır. Sosyal medya, bireylerin kendilerini ifade ettikleri basit bir iletişim aracı olmanın ötesinde; kültürel anlamların üretildiği, kimliklerin performatif olarak sergilendiği ve toplumsal normların yeniden tanımlandığı bir

kültürel ekosistem hâline gelmiştir (van Dijck et al., 2018; Jenkins, 2006). Gelecek çalışmalarda, dijital kimlik inşasının farklı kültürel bağlamlarda, kuşaklar arası karşılaştırmalarla ve nicel–nitel yöntemlerin birlikte kullanıldığı daha kapsamlı araştırmalarla ele alınması, bu alanın daha derinlikli biçimde anlaşılmasına katkı sağlayacaktır (Creswell & Creswell, 2018).

KAYNAKÇA

- Abidin, C. (2016). “Aren’t these just young, rich women doing vain things online?” Influencer selfies as subversive frivolity. *Social Media + Society*, 2(2).
- Adorno, T. W., & Horkheimer, M. (2002). *Dialectic of enlightenment: Philosophical fragments* (E. Jephcott, Trans.). Stanford University Press. (Original work published 1944)
- Aurore, M. I., & Bayraktar, Ü. A. (2024). Use of technology in public relations and non-governmental organizations: The example of the United Nations Children’s Fund. In H. Kıymık (Ed.), *International research in social, human and administrative sciences XXII* (105–158). Eğitim Yayınevi. ISBN: 978-625-6658-46-2.
- Baudrillard, J. (1994). *Simulacra and simulation* (S. F. Glaser, Trans.). University of Michigan Press. (Original work published 1981)
- Bourdieu, P. (1984). *Distinction: A social critique of the judgement of taste* (R. Nice, Trans.). Harvard University Press.
- boyd, d. (2014). *It’s complicated: The social lives of networked teens*. Yale University Press.
- Couldry, N., & Hepp, A. (2017). *The mediated construction of reality*. Polity Press.
- Creswell, J. W., & Creswell, J. D. (2018). *Research design: Qualitative, quantitative, and mixed methods approaches* (5th ed.). SAGE.
- DataReportal. (2024a). *Digital 2024: Global overview report*. DataReportal – Global Digital Insights
- DataReportal. (2024b). *Digital 2024: Turkey*. DataReportal – Global Digital Insights+1
- Datumintell. (2024). *Turkey online population forecast 2023–28*. Datumintell
- Debord, G. (1994). *The society of the spectacle* (D. Nicholson-Smith, Trans.). Zone Books. (Original work published 1967)
- Festinger, L. (1954). A theory of social comparison processes. *Human Relations*, 7(2), 117–140.
- Freedom House. (2024). *Freedom on the Net 2024: Turkey*. Freedom House
- Giddens, A. (1991). *Modernity and self-identity: Self and society in the late modern age*. Stanford University Press.
- Goffman, E. (1959). *The presentation of self in everyday life*. Doubleday.
- Hall, S. (1997). *Representation: Cultural representations and signifying practices*. SAGE.
- Hogan, B. (2010). The presentation of self in the age of social media: Distinguishing performances and exhibitions online. *Bulletin of Science, Technology & Society*, 30(6), 377–386.
- Jenkins, H. (2006). *Convergence culture: Where old and new media collide*. New York University Press.
- Jenkins, H., Ford, S., & Green, J. (2013). *Spreadable media: Creating value and meaning in a networked culture*. NYU Press.
- Khamis, S., Ang, L., & Welling, R. (2017). Self-branding, “micro-celebrity” and the rise of social media influencers. *Celebrity Studies*, 8(2), 191–208.
- Marwick, A. E. (2013). *Status update: Celebrity, publicity, and branding in the social media age*. Yale University Press.
- McQuail, D. (2010). *McQuail’s mass communication theory* (6th ed.). SAGE.
- Papacharissi, Z. (2012). Without you, I’m nothing: Performances of the self on Twitter. *International Journal of Communication*, 6, 1989–2006.

- Przybylski, A. K., Murayama, K., DeHaan, C. R., & Gladwell, V. (2013). Motivational, emotional, and behavioral correlates of fear of missing out. *Computers in Human Behavior*, 29(4), 1841–1848.
- Sunstein, C. R. (2001). *Republic.com*. Princeton University Press.
- Twenge, J. M. (2017). *iGen*. Atria Books.
- Uraloğlu, A. (2024, 13 Şubat). Social media usage time in Türkiye is 2 hours 44 minutes. *A News*. A News
- van Dijck, J., Poell, T., & de Waal, M. (2018). *The platform society: Public values in a connective world*. Oxford University Press.
- Zakoğlu, B. (2024). Algılanan aşırı niteliklilik ile iş performansı arasındaki ilişkide kişi-iş uyumu, dağıtım adaleti ve başarı ihtiyacının rolü (Doktora tezi). İstanbul Üniversitesi, Sosyal Bilimler Enstitüsü, İstanbul.
- Zuboff, S. (2019). *The age of surveillance capitalism*. PublicAffairs.

**ENFORMASYON EKOSİSTEMİNDE GÜVEN İNŞASI:
DİJİTAL ETKİLEŞİMLERDE SOSYAL SERMAYE
BUILDING TRUST IN THE INFORMATION ECOSYSTEM:
SOCIAL CAPITAL IN DIGITAL INTERACTIONS**

Dr. Ferhat Atik

Girne Amerikan Üniversitesi

İletişim Fakültesi

İletişim ve Medya Yönetimi

Girne, KKTC

0009-0008-9089-9051

ÖZET

Modern dijital toplumun en kritik sorunu, enformasyon ekosistemi içinde güvenin nasıl inşa edileceği ve sürdürüleceğidir. Geleneksel toplumlarda güven, yüz yüze etkileşimler, paylaşılan normlar ve kurumsal itibarlar üzerine inşa edilirken, dijital platformlar bu temelleri zayıflatmış veya tamamen dönüştürmüştür. Bu çalışma, dijital etkileşimlerde güven inşasını, sosyal sermaye kuramları çerçevesinden ele almayı hedeflemektedir. Sosyal sermaye—bireyler ve gruplar arasındaki işbirliğini kolaylaştıran ağlar, normlar ve güven—dijital bağlamda yeni formlar kazanmıştır. "Bağlayıcı" ve "Bridging" (köprü kuran) sosyal sermaye kavramları, dijital toplulukların iç dayanışmasını ve dışarıya açıklığını analiz etmek için kullanılabilir. Ancak, dijital sosyal sermaye, geleneksel olandan farklı olarak, genellikle daha zayıf bağlara, performatif kimliklere ve algoritmik aracılığa dayanır. Bu durum, güvenin kırılgan ve gösterişsel bir nitelik kazanmasına yol açar. İnfluencer (etkileyici) pazarlaması, kullanıcı yorumları, doğrulama mekanizmaları ve şeffaflık politikaları, bu yeni güven ekonomisinin temel bileşenleridir. Çalışma, bireylerin kişisel markalarından, küresel sosyal medya platformlarının governans (yönetişim) yapılarına kadar uzanan bir yelpazede, güveni şekillendiren mekanizmaları inceleyecektir. Dijital güvenin, sadece doğru bilgiye erişimle değil, aynı zamanda aidiyet duygusu, ortak kimlik algısı ve adil etkileşim beklentisiyle de yakından ilişkili olduğu argümanını öne sürmektedir. Sonuç olarak, sağlıklı bir enformasyon ekosistemi için, teknik doğrulamanın ötesine geçen, ilişkisel ve sosyal sermaye odaklı bir güven paradigmasının gerekliliği vurgulanmaktadır.

Anahtar Kelimeler: Güven İnşası, Enformasyon Ekosistemi, Sosyal Sermaye, Dijital Etkileşim, Bağlayıcı Sermaye, Köprü Kuran Sermaye, Dijital Güven, İtibar Yönetimi, Algoritmik Aracılık, Dijital Topluluklar.

ABSTRACT

The most critical issue of modern digital society is how to build and sustain trust within the information ecosystem. While trust in traditional societies was built on face-to-face interactions, shared norms, and institutional reputations, digital platforms have weakened or entirely transformed these foundations. This study aims to address trust building in digital interactions through the framework of social capital theories. Social capital—the networks, norms, and trust that facilitate cooperation among individuals and groups—has acquired new forms in the digital context. The concepts of "bonding" and "bridging" social capital can be used to analyze the internal solidarity and external openness of digital communities. However, unlike traditional social capital, digital social capital often relies on weaker ties, performative identities, and algorithmic mediation. This leads to trust becoming fragile and performative in nature. Influencer marketing, user reviews, verification mechanisms, and transparency policies

are key components of this new trust economy. The study will examine the mechanisms that shape trust across a spectrum ranging from individuals' personal brands to the governance structures of global social media platforms. It argues that digital trust is closely related not only to access to accurate information but also to a sense of belonging, shared identity perception, and the expectation of fair interaction. In conclusion, it emphasizes the necessity of a trust paradigm that goes beyond technical verification, focusing on relational and social capital for a healthy information ecosystem.

Keywords: Trust Building, Information Ecosystem, Social Capital, Digital Interaction, Bonding Capital, Bridging Capital, Digital Trust, Reputation Management, Algorithmic Mediation, Digital Communities.

1. GİRİŞ

Dijital enformasyon ekosisteminin sürdürülebilirliği, temelindeki güven ilişkilerinin sağlamlığına bağlıdır. Geleneksel toplumlarda güven, yüz yüze etkileşimler, paylaşılan sosyal normlar ve uzun vadeli kurumsal itibarlar üzerine inşa edilirken, dijital platformlar bu temelleri radikal bir şekilde dönüştürmüştür. Modern dijital toplum, güvenin nasıl inşa edileceği, sürdürüleceği ve onarılacağına dair temel sorularla karşı karşıyadır. Bu makale, dijital etkileşimlerde güven inşası sürecini, sosyal sermaye kuramları çerçevesinden kapsamlı bir şekilde analiz etmeyi amaçlamaktadır. Robert Putnam'ın "bağlayıcı" ve "köprü kuran" sosyal sermaye ayrımından yola çıkarak, dijital platformların bu iki sermaye türünü nasıl şekillendirdiğini ve bunun güven dinamikleri üzerindeki derin etkilerini incelemektedir. Çalışma, dijital sosyal sermayenin geleneksel olandan farklı olarak, daha zayıf bağlara, performatif kimliklere ve algoritmik aracılığa dayandığını, bu durumun da güveni daha kırılgan ve gösterişsel bir hale getirdiğini iddia etmektedir. Influencer pazarlaması, kullanıcı yorumları, doğrulama mekanizmaları ve şeffaflık politikaları gibi olgular, bu yeni güven ekonomisinin bileşenleri olarak ele alınmaktadır. Makale, sağlıklı bir enformasyon ekosistemi için, teknik doğrulamanın ötesine geçen, ilişkisel ve sosyal sermaye odaklı bir güven paradigmasının gerekliliğini savunmaktadır.

2. TEORİK TEMELLER: SOSYAL SERMAYE VE GÜVEN İLİŞKİSİ

2.1. Sosyal Sermaye Kavramının Evrimi

Sosyal sermaye kavramı, Pierre Bourdieu, James Coleman ve Robert Putnam gibi teorisyenler tarafından farklı şekillerde tanımlanmıştır. Bourdieu (1986) için sosyal sermaye, "bir bireyin ya da grubun, dayanışma ağlarına kalıcı olarak ait olması sayesinde sahip olduğu gerçek veya potansiyel kaynakların toplamı"dır. Coleman (1988) ise sosyal sermayeyi, sosyal yapının içinde yer alan ve bireylerin belirli eylemlerde bulunmasını mümkün kılan çeşitli varlıklar olarak tanımlar. Putnam (2000) ise sosyal sermayeyi, "bireylerin arasındaki bağlantıları -sosyal ağları ve onlardan doğan normları ve güveni- ifade eden" bir kavram olarak ele alır.

Bu temel yaklaşım, sosyal sermayenin bireysel ve kolektif faydalarını vurgulayarak, güvenin sosyal yaşamdaki merkezi rolünü ortaya koyar. Bireyin kendini ve dış dünyasını tanıma, kavrama ve anlamlandırmaya başladığı andan itibaren ilk eylemi kişiler arası olan ilişkilerdir. Bu ilişki ağı ve iletişim eylemi; bireyin dış çevresi ile etkileşimi neticesinde yeni bir şeyler öğrenmesine de yardımcı olmakta; özellikle inançların, tavır ve hareketlerin, sosyal değerlerin, kısacası kültürel kimliğin şekillenmesinde ve kuşaklar arası aktarımında önemli bir rol üstlenmektedir. (Yılmaz, 2022)

2.2. Güvenin Sosyolojik ve Ekonomik Temelleri

Güven, sosyal etkileşimlerin temelini oluşturan çok boyutlu bir kavramdır. Fukuyama (1995) güveni, "bir topluluk içinde, ortak normlara sahip diğer üyelerin düzenli, dürüst ve işbirliğine dayalı davranışlar sergileyeceği beklentisi" olarak tanımlar. Luhmann (1979) ise güveni, sosyal sistemlerin karmaşıklığını azaltan temel bir mekanizma olarak görür. Ekonomik perspektiften

bakıldığında, güven işlem maliyetlerini azaltır ve piyasaların verimli işlemlerini sağlar (Arrow, 1974). Dijital ortamda güven, bu geleneksel işlevlerini sürdürmekle birlikte, yeni formlar ve mekanizmalar kazanmıştır.

2.3. Dijital Sosyal Sermaye ve Güven Bağlantısı

Dijital sosyal sermaye, geleneksel sosyal sermaye kavramının dijital ortama uyarlanmış halidir. Williams (2006) bu kavramı, "internet tabanlı sosyal ağlardan elde edilen kaynaklar" olarak tanımlar. Dijital sosyal sermaye, hem çevrimiçi hem de çevrimdışı ilişkileri kapsar ve güven inşasında kritik bir rol oynar. Ellison ve diğerleri (2007) tarafından geliştirilen "Facebook Kullanımından Kaynaklanan Sosyal Sermaye" ölçeği, bu kavramın operasyonelleştirilmesine önemli katkı sağlamıştır. Dijital platformlarda sosyal sermaye birikimi, kullanıcılar arasında güven oluşumunu kolaylaştırmakta ve dijital etkileşimlerin kalitesini artırmaktadır.

3. DİJİTAL ORTAMDA GÜVEN İNŞASININ MEKANİZMALARI

3.1. Platform Tasarımı ve Güven Sinyalleri

Dijital platformların güven inşası mekanizmaları, kullanıcı deneyiminin her aşamasında kendini göstermektedir. Bu mekanizmalar, platform mimarisinin temel bileşenleri olarak işlev görmek ve dijital etkileşimlerin kalitesini doğrudan etkilemektedir. Güven sinyalleri, kullanıcıların platforma ve diğer kullanıcılara olan güvenini artırmak amacıyla tasarlanmış yapısal öğelerdir. Airbnb örneğinde olduğu gibi, kimlik doğrulama süreçleri, profil doğrulama sistemleri ve geçmiş değerlendirmeler, bu sinyallerin somut tezahürleridir. Platformlar, bu sinyalleri stratejik olarak konumlandırarak, kullanıcıların risk algısını azaltmayı ve katılım düzeyini artırmayı hedefler. Güven sinyallerinin etkinliği, kullanıcıların platformu ne ölçüde benimsediği ve kullanmaya devam ettiği üzerinde doğrudan etkiye sahiptir.

Dijital güven inşasında, platformların kullandığı bir diğer önemli mekanizma da sosyal kanıt prensipleridir. Kullanıcı yorumları, puanlamalar ve değerlendirmeler, potansiyel kullanıcılar için güçlü referans noktaları oluşturur. Bu sistemler, kolektif bilgeliği harekete geçirerek, bireysel kullanıcıların karar verme süreçlerini destekler. Ancak, bu sistemlerin manipülasyona açık olması, platformların sürekli iyileştirme yapmasını gerektirmektedir. Gelişmiş platformlar, yapay zeka destekli sahtecilik tespit sistemleri kullanarak, manipüle edilmiş değerlendirmeleri filtrelemekte ve sistemin bütünlüğünü korumaktadır. Güven sinyallerinin bir başka boyutu da şeffaflık mekanizmalarıdır.

Platformlar, kullanıcı verilerinin nasıl işlendiği, algoritmaların nasıl çalıştığı ve içerik moderasyon süreçlerinin nasıl işlediği konusunda şeffaf olmak zorundadır. Bu şeffaflık, kullanıcıların platforma duyduğu güvenin sürdürülebilirliği açısından hayati öneme sahiptir. Özellikle kişisel verilerin korunması ve mahremiyet konularında yapılan şeffaf açıklamalar, kullanıcıların platforma olan güvenini pekiştirmektedir. Platform tasarımında güven inşası, sadece teknik bir mesele değil, aynı zamanda psikolojik ve sosyolojik boyutları olan kapsamlı bir süreçtir. Kullanıcı arayüzü tasarımı, renk seçimleri, tipografi ve genel kullanıcı deneyimi, kullanıcıların platforma duyduğu güveni şekillendiren unsurlardır. Profesyonel ve tutarlı bir tasarım, kullanıcılarda güvenilirlik hissi uyandırırken, dağınık ve amatörce tasarlanmış arayüzler güvensizliğe neden olabilmektedir. Mobil uygulamaların performansı, yükleme hızları ve kesintisiz işleyiş de güven oluşumunda kritik rol oynayan teknik faktörlerdir. Platformların güvenlik protokolleri, veri şifreleme standartları ve siber güvenlik önlemleri de güven inşasının vazgeçilmez bileşenleridir. Kullanıcılar, kişisel ve finansal bilgilerinin güvende olduğuna dair somut garantiler görmek istemektedir. SSL sertifikaları, iki faktörlü kimlik doğrulama ve düzenli güvenlik denetimleri bu ihtiyacı karşılamaya yönelik uygulamalardır. Dijital platformların güven inşası mekanizmaları, sürekli evrim geçiren dinamik bir yapıya sahiptir. Yeni teknolojilerin ortaya çıkması ve kullanıcı beklentilerinin değişmesi, platformları güven mekanizmalarını sürekli güncellemeye zorlamaktadır. Blockchain tabanlı güven

sistemleri, biyometrik doğrulama yöntemleri ve yapay zeka destekli güven analizleri, geleceğin dijital güven mekanizmalarını şekillendirmektedir.

3.2. İtibar Sistemleri ve Derecelendirme Mekanizmaları

Dijital itibar sistemleri, modern dijital ekonominin temel taşlarından biridir ve karmaşık sosyo-teknik sistemler olarak işlev görmektedir. Bu sistemler, bireylerin ve kurumların dijital ortamdaki güvenilirliğini ölçmek ve görünür kılmak amacıyla tasarlanmıştır. İtibar sistemlerinin temel işlevi, asimetrik enformasyon problemini çözerek, dijital etkileşimlerde güveni tesis etmektir. eBay'in 1990'larda geliştirdiği feedback sistemi, modern itibar sistemlerinin prototipi olarak kabul edilmekte ve bu alandaki çalışmalara öncülük etmektedir. İtibar sistemleri, basit puanlama mekanizmalarından, çok boyutlu değerlendirme modellerine doğru evrim geçirmiştir. Günümüzde gelişmiş itibar sistemleri, kullanıcıların farklı özelliklerini ayrı ayrı değerlendiren çok boyutlu rating sistemleri kullanmaktadır. Örneğin, Airbnb'de konaklama deneyimi, temizlik, iletişim, varış kolaylığı gibi farklı kriterlerde ayrı ayrı değerlendirilmekte ve bu da daha detaylı bir itibar profili oluşturulmasına olanak sağlamaktadır. İtibar sistemlerinin tasarımında karşılaşılan en önemli zorluklardan biri, sistemin manipülasyona karşı dayanıklılığını sağlamaktır. Platformlar, sahte değerlendirmeleri tespit etmek için gelişmiş algoritmalar kullanmakta ve bu değerlendirmeleri filtrelemektedir. Amazon'un yapay zeka destekli sahte yorum tespit sistemi, bu alandaki en gelişmiş uygulamalardan biridir. İtibar sistemlerinin bir diğer önemli boyutu da zaman ağırlıklı değerlendirme mekanizmalarıdır.

Son dönemdeki performansın, genel itibar puanı üzerinde daha fazla ağırlığa sahip olması, sistemin dinamik ve güncel kalmasını sağlamaktadır. Uber'in sürücü derecelendirme sistemi, son 500 yolculuğun ortalamasını alarak, sürücünün güncel performansını yansıtmaktadır. İtibar sistemlerinin sosyal etkileri de oldukça karmaşıktır. Yüksek itibar puanına sahip kullanıcılar, dijital platformlarda sosyal sermaye biriktirmekte ve bu durum ekonomik fırsatlara erişimlerini kolaylaştırmaktadır. Ancak, itibar sistemleri aynı zamanda sosyal eşitsizlikleri de derinleştirebilmektedir. Dijital itibarın ölçülme biçimi, bireylerin ekonomik ve sosyal fırsatlara erişimini belirleyen yeni bir sosyal stratifikasyon mekanizması oluşturmaktadır. İtibar sistemlerinin etik boyutları da önemli tartışma konularından biridir. Derecelendirme mekanizmalarının şeffaflığı, algoritmik adillik ve veri gizliliği, itibar sistemleri tasarlanırken dikkate alınması gereken temel etik ilkelerdir. Ayrıca, itibar sistemlerinin kullanıcı davranışları üzerindeki disiplin edici etkisi de eleştirel bir şekilde incelenmelidir. Kullanıcılar, yüksek puan almak için platform kurallarına sıkı sıkıya bağlı kalmakta ve bu durum belli bir standardizasyona yol açmaktadır. İtibar sistemlerinin geleceği, merkeziyetsiz teknolojiler ve yapay zeka uygulamalarıyla şekillenmektedir. Blockchain tabanlı itibar sistemleri, kullanıcıların itibar verilerini merkezi platformlardan bağımsız olarak yönetmelerine olanak sağlamaktadır. Sovrin ve Civic gibi projeler, kullanıcıların dijital kimliklerini ve itibar verilerini kendilerinin kontrol ettiği merkeziyetsiz itibar sistemleri geliştirmektedir.

Yapay zeka ise itibar sistemlerinin daha akıllı ve bağlamsal hale gelmesine olanak sağlamaktadır. Duygu analizi algoritmaları, kullanıcı yorumlarının tonunu ve bağlamını analiz ederek, daha nitelikli itibar değerlendirmeleri yapabilmektedir. Makine öğrenmesi modelleri, itibar sistemlerindeki sahtecilik modellerini tespit etmede giderek daha etkili hale gelmektedir. İtibar sistemlerinin evrimi, dijital toplumun geleceği açısından hayati öneme sahiptir. Daha adil, şeffaf ve kullanıcı odaklı itibar sistemleri geliştirmek, dijital ekonominin sürdürülebilirliği için elzemdir.

3.3. Sosyal Kanıt ve Ağ Etkileri

Sosyal kanıt, dijital platformlarda güven inşasının en güçlü psikolojik mekanizmalarından biridir ve bireylerin belirsizlik durumlarında başkalarının davranışlarını rehber olarak kullanma eğilimini ifade etmektedir. Dijital ortamda sosyal kanıt, çeşitli metrikler ve göstergeler aracılığıyla somutlaşmakta ve kullanıcıların karar verme süreçlerini derinden etkilemektedir.

Beğeni sayıları, paylaşım istatistikleri, takipçi sayıları, indirme oranları ve yorum sayıları gibi metrikler, dijital sosyal kanıtın en yaygın biçimleridir. Bu metrikler, içeriğin popülerliği ve kabul görmüşlüğü hakkında kullanıcılara dolaylı sinyaller göndermekte ve onların içerikle etkileşime geçme olasılığını artırmaktadır. Sosyal kanıt mekanizmalarının etkinliği, özellikle belirsizlik durumlarında daha belirgin hale gelmektedir. Kullanıcılar, kendileriyle benzer özelliklere sahip diğer kullanıcıların tercihlerini ve davranışlarını daha güçlü sosyal kanıt olarak algılamaktadır. Bu nedenle, kişiselleştirilmiş sosyal kanıt sistemleri, genel popülerlik göstergelerinden daha etkili olabilmektedir.

Ağ etkileri ise sosyal kanıt mekanizmalarıyla yakından ilişkili bir kavramdır ve bir ürün veya hizmetin değerinin, onu kullanan kişi sayısına bağlı olarak artmasını ifade etmektedir. Doğrudan ağ etkileri, bir platformun kullanıcı sayısı arttıkça, her bir kullanıcı için değerinin doğrudan artmasıdır. Telefon ağları veya sosyal medya platformları bu tür ağ etkilerine klasik örneklerdir. Dolaylı ağ etkileri ise, bir platformun kullanıcı sayısı arttıkça, platform için tamamlayıcı ürün ve hizmetlerin de artması ve bu durumun platformun değerini daha da artırmasıdır. İşletim sistemleri ve uygulama mağazaları dolaylı ağ etkilerinin tipik örnekleridir. İki taraflı ağ etkileri ise, platformun iki farklı kullanıcı grubu arasındaki etkileşimden doğan değer artışını ifade etmektedir. E-ticaret platformları ve kredi kartı sistemleri bu tür ağ etkilerine örnek gösterilebilir. Sosyal kanıt ve ağ etkilerinin kombinasyonu, dijital platformlar için güçlü bir kendini besleyen döngü oluşturmaktadır. Daha fazla kullanıcı, daha güçlü sosyal kanıt anlamına gelmekte, bu da daha fazla yeni kullanıcı çekmekte ve platformun değerini daha da artırmaktadır. Bu döngü, başarılı dijital platformların büyüme dinamiklerinin temelini oluşturmaktadır.

Ancak, sosyal kanıt mekanizmalarının olumsuz yönleri de bulunmaktadır. Popülerlik yanılgısı, kaliteli ancak az bilinen içeriklerin göz ardı edilmesine neden olabilmektedir. Sürü psikolojisi, kullanıcıların bağımsız karar verme yeteneklerini zayıflatabilmektedir. Ayrıca, sosyal kanıt metrikleri manipülasyona açıktır ve sahte etkileşimlerle yapay popülerlik yaratılabilmektedir. Platformlar, bu olumsuz etkileri azaltmak için çeşitli stratejiler geliştirmektedir. Kişiselleştirilmiş öneri sistemleri, kullanıcıların sadece popüler içeriklerle değil, kendi ilgi alanlarına uygun içeriklerle de karşılaşmasını sağlamaktadır. Çeşitlilik algoritmaları, kullanıcıların farklı türde içerikler keşfetmesine olanak tanımaktadır. Gelişmiş sahtecilik tespit sistemleri, manipüle edilmiş sosyal kanıt sinyallerini filtrelemektedir. Sosyal kanıt mekanizmalarının geleceği, daha sofistike ve bağlamsal hale gelmektedir. Yapay zeka destekli kişiselleştirme sistemleri, kullanıcıların bireysel tercihlerine ve bağlamsal ihtiyaçlarına uygun sosyal kanıt sinyalleri sunabilmektedir. Blockchain tabanlı güven sistemleri, sosyal kanıt verilerinin doğrulanabilirliğini ve şeffaflığını artırmaktadır. Dijital platformlar, sosyal kanıt ve ağ etkilerini daha etik ve demokratik bir şekilde yönetmek için yeni modeller geliştirmek durumundadır.

4. DİJİTAL GÜVENİN BOYUTLARI VE TÜRLERİ

4.1. Bilişsel Güven ve Duygusal Güven Ayırımı

Dijital güvenin anlaşılmasında bilişsel ve duygusal boyutların ayrımı, kuramsal ve pratik açıdan büyük önem taşımaktadır. McAllister'in (1995) öncü çalışması, bu ayrımı akademik literatüre kazandırmış ve güven araştırmalarında yeni bir perspektif açmıştır. Bilişsel güven, bireylerin diğer kişilerin veya kurumların güvenilirliğine, yeterliliğine ve yetkinliğine ilişkin rasyonel değerlendirmelerine dayanmaktadır. Bu değerlendirmeler, geçmiş performans kayıtları, referanslar, sertifikalar ve somut kanıtlar üzerine kuruludur. Dijital ortamda bilişsel güven, itibar sistemleri, performans metrikleri, doğrulama mekanizmaları ve şeffaf değerlendirme sistemleri aracılığıyla inşa edilmektedir. Kullanıcılar, bir platformu veya diğer kullanıcıyı kullanmadan önce, mevcut verileri analiz ederek rasyonel bir risk-fayda değerlendirmesi yapmaktadır. Duygusal güven ise, bireylerin duygusal bağlara, empatiye ve karşılıklı iyi niyete

dayalı olarak geliştirdikleri güven türüdür. Bu güven türü, rasyonel hesaplamalardan ziyade, duygusal bağlanma ve kişilerarası bağlılık üzerine kuruludur. Dijital ortamda duygusal güven, samimi etkileşimler, karşılıklı yardımlaşma, duygusal destek ve paylaşılan deneyimler aracılığıyla gelişmektedir. Sosyal medya platformlarında kurulan yakın arkadaşlık ilişkileri veya çevrimiçi topluluklarda gelişen dayanışma ağları, duygusal güvenin tipik örnekleridir. Bilişsel ve duygusal güven arasındaki dinamik etkileşim, dijital ilişkilerin kalitesini ve sürdürülebilirliğini belirlemektedir. Başlangıç aşamasında bilişsel güven ön planda olurken, zamanla gelişen duygusal bağlar, ilişkinin derinleşmesine katkı sağlamaktadır. Ancak, dijital ortamın doğası gereği, bilişsel güvenin önemi daha belirgin hale gelmektedir. Kullanıcılar, sınırlı zaman ve kaynakları olduğu için, hızlı ve etkili rasyonel değerlendirmelere ihtiyaç duymaktadır.

Platformlar da bu ihtiyacı karşılamak için, bilişsel güveni destekleyen mekanizmalara daha fazla yatırım yapmaktadır. Ancak, duygusal güvenin ihmal edilmesi, dijital ilişkilerin yüzeysel ve kırılgan kalmasına neden olabilmektedir. İdeal dijital güven ortamı, bilişsel ve duygusal güvenin dengeli bir şekilde geliştiği ortamlardır. Bilişsel güvenin ölçümü, nicel veriler ve metrikler üzerinden yapılabilirken, duygusal güvenin ölçümü daha zor ve subjektiftir. Duygu analizi teknolojileri, metin madenciliği yöntemleri ve psikolinguistik analizler, duygusal güvenin dolaylı olarak ölçülmesine olanak sağlamaktadır. Dijital platformlar, kullanıcı etkileşimlerinin duygusal boyutunu anlamak ve desteklemek için bu teknolojilerden yararlanmaktadır. Bilişsel ve duygusal güven dengesi, farklı dijital bağlamlarda değişiklik göstermektedir. E-ticaret platformlarında bilişsel güven daha kritikken, sosyal destek gruplarında veya çevrimiçi terapide duygusal güven daha önemli hale gelmektedir. Platform tasarımcıları, bu bağlamsal farklılıkları dikkate alarak, güven inşası mekanizmalarını özelleştirmelidir. Geleceğin dijital güven sistemleri, bilişsel ve duygusal boyutları entegre eden bütüncül yaklaşımlar geliştirmelidir. Yapay zeka sistemleri, kullanıcı davranışlarının hem rasyonel hem de duygusal boyutlarını analiz ederek, daha kapsamlı güven değerlendirmeleri yapabilir. Duygusal yapay zeka (affective computing) teknolojileri, kullanıcıların duygusal durumlarını anlama ve buna uygun tepkiler verme kapasitesine sahiptir. Bu teknolojiler, dijital ortamda duygusal güvenin gelişimini destekleyebilir. Bilişsel ve duygusal güven arasındaki optimal dengeyi bulmak, dijital platformların uzun vadeli başarısı için hayati öneme sahiptir.

4.2. Kurumsal Güven ve Kişilerarası Güven

Dijital güvenin anlaşılmasında kurumsal güven ve kişilerarası güven ayrımı, kurumsal çerçevenin temel taşlarından biridir. Bu ayrım, bireylerin dijital ortamda kimlere veya nelere güvendiğini anlamak açısından kritik öneme sahiptir. Kurumsal güven, bireylerin dijital platformların kendisine, bu platformların alt yapı sistemlerine, algoritmalarına ve genel işleyiş mekanizmalarına duyduğu güveni ifade etmektedir. McKnight ve diğerlerinin (2002) geliştirdiği bütünlük güven modeli, kurumsal güvenin yapısal boyutlarını ayrıntılı bir şekilde tanımlamaktadır. Kurumsal güven, platformun güvenilirliği, istikrarı, şeffaflığı ve hesap verebilirliği üzerine kuruludur. Kullanıcılar, kişisel verilerinin güvenli bir şekilde saklandığına, platformun adil ve tarafsız bir şekilde işlediğine ve olası sorunlarda etkili çözüm mekanizmalarının bulunduğuna inanmak ister. Kişilerarası güven ise, dijital platformlar aracılığıyla etkileşimde bulunan bireylerin birbirlerine duyduğu güveni ifade etmektedir. Bu güven türü, diğer kullanıcıların güvenilirliği, dürüstlüğü ve iyi niyeti üzerine kuruludur. Dijital ortamda kişilerarası güven, itibar sistemleri, sosyal kanıt mekanizmaları ve doğrudan etkileşimler aracılığıyla gelişmektedir. Kurumsal güven ve kişilerarası güven arasında karmaşık ve dinamik bir ilişki bulunmaktadır.

Yüksek düzeyde kurumsal güven, kişilerarası güvenin gelişimini kolaylaştırmakta, düşük kurumsal güven ise kişilerarası güveni zorlaştırmaktadır. Platformların sağladığı güven mekanizmaları (itibar sistemleri, anlaşmazlık çözüm mekanizmaları, garanti sistemleri), kişilerarası güvenin riskini azaltmakta ve bu tür etkileşimleri teşvik etmektedir. Ancak,

kurumsal güven ve kişilerarası güven her zaman pozitif korelasyon göstermeyebilir. Bazı durumlarda kullanıcılar, platforma duydukları güvene rağmen, belirli kullanıcılarla etkileşime girmekten kaçınabilir veya tam tersi, platforma duydukları güvensizliğe rağmen, belirli kullanıcılara güvenebilir. Dijital güvenin bu iki boyutu, farklı dijital bağlamlarda farklı önem düzeylerine sahiptir. Paylaşım ekonomisi platformlarında kişilerarası güven daha kritikken, finansal hizmet platformlarında kurumsal güven daha ön plana çıkmaktadır. E-ticaret platformlarında ise her iki güven türü de eşit derecede önemlidir. Kurumsal güvenin inşası, platform mimarisinin her aşamasında dikkatle planlanması gereken stratejik bir süreçtir. Güvenlik protokolleri, veri gizliliği politikaları, şeffaf algoritmik sistemler ve etik iş uygulamaları, kurumsal güvenin temelini oluşturur. Platformlar, bu konulardaki taahhütlerini açıkça ifade etmeli ve bu taahhütleri tutarlı bir şekilde yerine getirmelidir. Kişilerarası güvenin gelişimi ise daha organik ve zaman alıcı bir süreçtir.

Platformlar, kişilerarası güveni desteklemek için, kullanıcıların birbirlerini tanımalarına, iletişim kurmalarına ve ortak deneyimler yaşamalarına olanak sağlayan mekanizmalar geliştirmelidir. Gelişmiş profil sistemleri, detaylı değerlendirme mekanizmaları ve güvenli iletişim kanalları, kişilerarası güvenin gelişimini destekleyen araçlardır. Dijital platformların geleceği, kurumsal ve kişilerarası güveni entegre eden bütüncül güven sistemleri geliştirmelerine bağlıdır. Yapay zeka destekli güven analiz sistemleri, her iki güven türünü de ölçebilen ve yönetebilen entegre çözümler sunabilir. Blockchain teknolojisi, kurumsal ve kişilerarası güveni birleştiren merkeziyetsiz güven modelleri geliştirmeye olanak sağlamaktadır. Dijital güvenin bu iki boyutunu dengeli bir şekilde yönetmek, platformların sürdürülebilirliği ve büyümesi için hayati öneme sahiptir.

4.3. Teknolojiye Güven ve Algoritmik Güven

Teknolojiye güven, dijital çağın en önemli fenomenlerinden biridir ve bireylerin teknolojik sistemlere, cihazlara ve algoritmalara duyduğu güveni ifade etmektedir. Bu güven türü, geleneksel güven kavramlarından farklı dinamiklere sahiptir ve dijital dönüşümün merkezinde yer almaktadır. Algorithmic trust (algoritmik güven) kavramı, kullanıcıların algoritmik karar verme sistemlerine duydukları güveni tanımlamakta ve Shin (2020) tarafından geliştirilen teorik çerçeve bu kavramın anlaşılmasına önemli katkı sağlamaktadır. Algoritmik güven, algoritmaların şeffaflığı, adilliği, hesap verebilirliği ve performansı gibi çok boyutlu faktörlere dayanmaktadır. Kullanıcılar, algoritmaların nasıl çalıştığını anlamak, bu algoritmaların kararlarını sorgulayabilmek ve olası hataların düzeltililebileceğine inanmak ister. Teknolojiye güvenin temelinde, teknolojinin güvenilirliği ve öngörülebilirliği yatmaktadır. Kullanıcılar, teknolojik sistemlerin istikrarlı ve tutarlı bir şekilde çalışacağına, beklenmedik hatalar veya arızalar göstermeyeceğine inanmak ister. Bu güven, sistemin teknik performansı, arayüz tasarımı ve kullanıcı deneyimi gibi faktörlerden etkilenmektedir. Algoritmik güven ise daha karmaşık bir fenomendir ve kullanıcıların "kara kutu" olarak algıladıkları sistemlere duydukları güveni içermektedir.

Makine öğrenmesi algoritmalarının karar verme süreçlerinin şeffaf olmaması, algoritmik güvenin önündeki temel zorluklardan biridir. Explainable AI (açıklanabilir yapay zeka) alanındaki gelişmeler, bu sorunu çözmeye yönelik çabaların ürünüdür. Algorithmic fairness (algoritmik adillik) ise algoritmik güvenin bir diğer kritik boyutudur. Kullanıcılar, algoritmaların herhangi bir ayrımcılık yapmadan, tüm kullanıcılara adil davrandığına inanmak ister. Algoritmik önyargıların tespiti ve giderilmesi, algoritmik güvenin inşası için hayati öneme sahiptir. Teknolojiye güven ve algoritmik güven, dijital platformların kullanım niyeti ve kullanıcı bağlılığı üzerinde doğrudan etkiye sahiptir. Düşük teknoloji güveni, kullanıcıların platformları benimsememesine veya erken terk etmesine neden olabilmektedir. Algoritmik güvensizlik ise kullanıcıların platform önerilerini görmezden gelmesine veya platform kararlarını sürekli sorgulamasına yol açabilmektedir. Teknolojiye güvenin inşası, çok boyutlu bir strateji gerektirmektedir. Teknik güvenilirlik, sistem performansı, güvenlik standartları ve

kullanıcı dostu arayüz tasarımı, bu stratejinin temel bileşenleridir. Algoritmik güvenin inşası ise daha karmaşık bir süreçtir ve şeffaflık, denetlenebilirlik, adillik ve etik ilkelerin uygulanmasını gerektirir. Platformlar, algoritmik sistemlerinin nasıl çalıştığını anlaşılır bir dille açıklamalı, kullanıcılara algoritmik kararları sorgulama imkanı tanımalı ve algoritmik hataları düzeltmek için etkili mekanizmalar geliştirmelidir.

Dijital okuryazarlık, teknolojiye güven ve algoritmik güvenin gelişiminde kritik bir rol oynamaktadır. Kullanıcıların teknolojik sistemlerin nasıl çalıştığına dair temel bir anlayışa sahip olması, gerçekçi beklentiler geliştirmelerine ve teknolojiye daha sağlıklı bir güven duymalarına yardımcı olmaktadır. Teknolojiye güven ve algoritmik güvenin geleceği, yapay zeka ve blockchain gibi yeni teknolojilerle şekillenecektir. Yapay zeka sistemleri, daha şeffaf ve açıklanabilir hale geldikçe, algoritmik güven artacaktır. Blockchain teknolojisi, merkeziyetsiz ve değiştirilemez kayıt sistemleri sunarak, teknolojiye güveni güçlendirebilecektir. Dijital platformlar, teknolojiye güven ve algoritmik güven konusunda proaktif bir yaklaşım benimsemeli ve bu konuyu stratejik bir öncelik haline getirmelidir.

5. DİJİTAL GÜVEN KRİZLERİ VE ÇÖZÜM STRATEJİLERİ

5.1. Güven İhlallerinin Nedenleri ve Sonuçları

Dijital güven ihlalleri, modern dijital ekosistemin en karmaşık ve yıkıcı sorunlarından biridir. Bu ihlallerin temel nedenleri, teknolojik zafiyetler, insan faktörü, kurumsal yönetim eksiklikleri ve sistematik riskler olmak üzere dört ana kategoride incelenebilir. Teknolojik zafiyetler, yazılım hataları, güvenlik açıkları, tasarım kusurları ve altyapı yetersizliklerinden kaynaklanmaktadır. Örneğin, 2017'de yaşanan Equifax veri ihlali, 147 milyon müşterinin kişisel bilgilerinin sızmasına neden olmuş ve kurumsal güveni derinden sarsmıştır. Bu tür ihlaller, sistemik güvenlik zafiyetlerinin yanı sıra kurumsal denetim mekanizmalarının yetersizliğini de ortaya koymaktadır. İnsan faktörü ise sosyal mühendislik saldırıları, insan hataları, kötü niyetli davranışlar ve eğitim eksikliğinden kaynaklanan güven ihlallerini kapsamaktadır. Phishing saldırıları, kimlik avı dolandırıcılıkları ve iç tehditler, insan faktörünün neden olduğu güven ihlallerinin tipik örnekleridir. Kurumsal yönetim eksiklikleri, etik ihlaller, şeffaflık yoksunluğu, hesap verebilirlik mekanizmalarının yetersizliği ve kurumsal kültür sorunlarından kaynaklanmaktadır. Facebook-Cambridge Analytica skandalı, kurumsal yönetim eksikliklerinin yol açtığı güven ihlallerinin çarpıcı bir örneğidir.

Sistematik riskler ise algoritmik önyargılar, platform ekonomisinin yapısal sorunları, regülasyon boşlukları ve küresel siber güvenlik tehditlerinden oluşmaktadır. Bu riskler, bireysel aktörlerin kontrolünün ötesinde olan ve dijital ekosistemin bütününe tehdit eden yapısal sorunlardır. Güven ihlallerinin sonuçları ise bireysel, kurumsal ve toplumsal düzeyde kendini göstermektedir. Bireysel düzeyde, finansal kayıplar, kimlik hırsızlığı, psikolojik stres ve dijital mahremiyetin ihlali gibi sonuçlar ortaya çıkmaktadır. Kurumsal düzeyde, itibar kaybı, müşteri kaybı, finansal yaptırımlar, yasal sorumluluklar ve paydaş güveninin azalması gibi etkiler görülmektedir. Toplumsal düzeyde ise, dijital ekosisteme olan güvenin aşınması, sosyal polarizasyon, demokratik süreçlere olan inancın zayıflaması ve kolektif refahın azalması gibi geniş kapsamlı sonuçlar ortaya çıkmaktadır. Güven ihlallerinin ekonomik maliyeti de oldukça yüksektir. IBM'in 2021 veri ihlali maliyeti raporuna göre, ortalama bir veri ihlalinin küresel maliyeti 4.24 milyon dolara ulaşmış durumdadır. Ancak, bu rakam sadece doğrudan maliyetleri kapsamakta olup, dolaylı maliyetler ve uzun vadeli itibar kayıpları bu maliyetin çok üzerinde olabilmektedir. Güven ihlallerinin psikolojik etkileri de derin ve kalıcı olabilmektedir. Kullanıcılarda oluşan dijital güvensizlik, anksiyete, sınırsız korku ve teknoloji kullanımından kaçınma gibi davranışsal değişikliklere neden olabilmektedir. Güven ihlallerinin önlenmesi ve yönetimi için bütüncül bir yaklaşım gerekmektedir. Bu yaklaşım, teknolojik çözümler, insan faktörünün iyileştirilmesi, kurumsal yönetim reformları ve düzenleyici çerçevelerin geliştirilmesini içermelidir. Ayrıca, güven ihlallerinin erken tespiti, hızlı müdahale

mekanizmaları ve etkili iyileştirme stratejileri de kritik öneme sahiptir. Dijital güven ihlallerinin karmaşık doğası, disiplinler arası bir yaklaşımı zorunlu kılmaktadır. Bilgisayar bilimleri, psikoloji, sosyoloji, hukuk ve işletme disiplinlerinin ortak çalışması, bu sorunun anlaşılması ve çözülmesi için gereklidir.

5.2. Güven Onarımı Stratejileri

Dijital güven ihlali durumlarında, güven onarımı stratejileri hayati önem kazanmaktadır. Güven onarımı, ihlal sonrasında güvenin yeniden tesis edilmesi için uygulanan sistematik süreçleri ifade etmektedir. Bu süreç, bilişsel, duygusal ve davranışsal boyutları içeren çok yönlü bir yaklaşım gerektirir. Güven onarımı stratejileri, özür ve kabul, şeffaflık, tazminat, kurumsal reform ve sürekli iyileştirme olmak üzere beş temel bileşenden oluşmaktadır. Özür ve kabul stratejisi, ihlalin sorumluluğunun açıkça kabul edilmesi ve samimi bir şekilde özür dilenmesini içerir. Bu stratejinin etkililiği, özrün zamanlaması, samimiyeti ve kapsamına bağlıdır. Şeffaflık stratejisi ise, ihlalin nedenleri, boyutları ve etkileri hakkında tam ve doğru bilgi paylaşımını gerektirir. Bu strateji, kullanıcıların durumu anlamalarına ve platformun dürüstlüğüne inanmalarına yardımcı olur. Tazminat stratejisi, ihlalin mağdurlarına maddi veya manevi tazmin sağlanmasını içerir. Bu, finansal tazminat, hizmet iyileştirmeleri veya sembolik jestler şeklinde olabilir. Kurumsal reform stratejisi, ihlale neden olan yapısal sorunların çözülmesi için köklü değişiklikler yapılmasını gerektirir. Bu, organizasyonel yapının yeniden düzenlenmesi, politika değişiklikleri veya yeni denetim mekanizmalarının kurulmasını içerebilir. Sürekli iyileştirme stratejisi ise, güven onarımının tek seferlik bir olay değil, sürekli bir süreç olduğunu kabul eder ve sistemin sürekli olarak iyileştirilmesini hedefler.

Güven onarımının başarısı, bu stratejilerin tutarlı ve koordineli bir şekilde uygulanmasına bağlıdır. Ayrıca, güven onarımı sürecinin zamanlaması da kritik öneme sahiptir. Erken müdahale, güven ihlalinin etkilerinin büyümesini önleyebilirken, geç müdahale güven onarımını zorlaştırabilir. Güven onarımında iletişim stratejileri de hayati rol oynar. Açık, samimi ve tutarlı iletişim, kullanıcıların platforma olan güvenini yeniden kazanmalarına yardımcı olur. Güven onarımı sürecinde paydaş katılımı da önemlidir. Mağdurların, düzenleyicilerin ve diğer paydaşların sürece dahil edilmesi, güven onarımının meşruiyetini ve etkililiğini artırır. Dijital ortamda güven onarımı, geleneksel ortamlara göre daha karmaşık ve zorludur. İhlalin hızla yayılabilmesi, etkilerinin küresel olması ve dijital izlerin kalıcılığı, güven onarımını zorlaştıran faktörlerdir. Ancak, dijital ortam aynı zamanda güven onarımı için yeni fırsatlar da sunar. Veri analitiği, kullanıcı geri bildirim sistemleri ve dijital iletişim kanalları, güven onarımı sürecini destekleyebilir. Güven onarımının uzun vadeli başarısı, platformun güven kültürünü benimsemesine ve güveni sürekli bir öncelik haline getirmesine bağlıdır. Bu, kurumsal değerlerin yeniden tanımlanması, çalışan eğitimleri ve güven metriklerine dayalı performans değerlendirmelerini gerektirir. Güven onarımı araştırmaları, gelecekte daha gelişmiş modeller ve metodolojiler geliştirmeye odaklanmalıdır. Yapay zeka destekli güven onarımı sistemleri, ihlallerin erken tespiti ve otomatik müdahale mekanizmaları sunabilir. Dijital güven onarımı, sadece teknik bir süreç değil, aynı zamanda psikolojik ve sosyolojik boyutları olan insan merkezli bir süreçtir.

5.3. Dijital Güven Yönetimi

Dijital güven yönetimi, dijital platformlarda güvenin tesis edilmesi, sürdürülmesi ve iyileştirilmesi için gerekli olan yapıları, süreçleri ve mekanizmaları ifade etmektedir. Bu kavram, geleneksel kurumsal yönetim anlayışından farklı olarak, çok paydaşlı, ağ tabanlı ve dinamik bir yapıya sahiptir. Dijital güven yönetimi, platform sağlayıcılar, kullanıcılar, düzenleyiciler, sivil toplum kuruluşları ve diğer paydaşlar arasındaki karmaşık etkileşimleri düzenleyen kurallar bütünüdür. Etkili dijital güven yönetimi, şeffaflık, hesap verebilirlik, katılımcılık, adillik ve etik ilkeler üzerine kuruludur. Dijital güven yönetiminin temel bileşenleri, platform tasarımı, içerik moderasyonu, veri yönetimi, algoritmik sistemler ve uyumsuzluk çözüm mekanizmalarıdır. Platform tasarımı, kullanıcı deneyiminin her aşamasında

güveni destekleyecek şekilde yapılandırılmalıdır. İçerik moderasyonu, zararlı içeriklerin filtrelenebilmesi ve platform kurallarının uygulanması için şeffaf ve adil bir sistem gerektirir. Veri yönetimi, kullanıcı verilerinin güvenliği, gizliliği ve etik kullanımını sağlamalıdır. Algoritmik sistemler, adil, önyargısız ve hesap verebilir olmalıdır. Uyuşmazlık çözüm mekanizmaları ise, kullanıcılar arasındaki anlaşmazlıkların hızlı ve adil bir şekilde çözülmesini sağlamalıdır.

Dijital güven yönetimi, farklı modeller ve yaklaşımlar içermektedir. Merkezi yönetim modelleri, platform sağlayıcının tek yetkili olduğu modellerdir. Topluluk temelli yönetim modelleri, kullanıcıların platform yönetimine aktif katılımını sağlar. Çok paydaşlı yönetim modelleri ise, tüm paydaşların sürece dahil olduğu katılımcı bir yapı sunar. Her modelin kendine özgü avantajları ve dezavantajları bulunmaktadır. Dijital güven yönetiminde karşılaşılan zorluklar, ölçeklenebilirlik, kültürel farklılıklar, yasal uyumluluk ve teknolojik değişimdir. Platformlar, küresel kullanıcı tabanlarının farklı ihtiyaçlarını ve beklentilerini karşılamak zorundadır. Ayrıca, farklı yargı bölgelerindeki düzenlemelere uyum sağlamak da önemli bir zorluktur. Dijital güven yönetiminin geleceği, daha demokratik, şeffaf ve kapsayıcı modellere doğru evrilmektedir. Yapay zeka ve blockchain gibi teknolojiler, dijital güven yönetiminde yeni fırsatlar sunmaktadır. Yapay zeka, içerik moderasyonu, sahtecilik tespiti ve risk değerlendirmesi gibi alanlarda insan kapasitesini artırabilir. Blockchain ise, merkeziyetsiz ve şeffaf yönetim modelleri geliştirmeye olanak sağlayabilir. Dijital güven yönetimi, sürekli iyileştirme ve adaptasyon gerektiren dinamik bir süreçtir. Platformlar, değişen kullanıcı beklentileri, teknolojik gelişmeler ve düzenleyici gereksinimlere uyum sağlamak için yönetim modellerini sürekli güncellemelidir. Dijital güven yönetiminin başarısı, tüm paydaşların ihtiyaçlarını dengeli bir şekilde karşılayabilmesine bağlıdır. Bu, zorlu ancak dijital ekosistemin sürdürülebilirliği için gerekli bir hedeftir.

6. GELECEK YÖNELİMLERİ VE ARAŞTIRMA GÜNDEMİ

6.1. Yapay Zeka ve Güven Yönetimi

Yapay zeka teknolojilerinin dijital güven yönetimine entegrasyonu, hem büyük fırsatlar hem de önemli zorluklar barındırmaktadır. Yapay zeka sistemleri, güven değerlendirmesi, risk analizi, sahtecilik tespiti ve içerik moderasyonu gibi alanlarda insan kapasitesini önemli ölçüde artırma potansiyeline sahiptir. Makine öğrenmesi algoritmaları, büyük veri setlerindeki karmaşık modelleri tespit ederek, geleneksel yöntemlerle fark edilemeyen güven risklerini belirleyebilir. Derin öğrenme modelleri, görsel ve metinsel içerik analizinde insan seviyesinde performans gösterebilir. Doğal dil işleme teknolojileri, kullanıcı yorumlarındaki duygu ve niyetleri analiz ederek, güven değerlendirmelerini zenginleştirebilir. Ancak, yapay zeka destekli güven yönetimi sistemleri, önyargı, şeffaflık, hesap verebilirlik ve etik gibi önemli sorunları da beraberinde getirmektedir. Algoritmik önyargı, eğitim verilerindeki tarihsel önyargıların yapay zeka sistemleri tarafından öğrenilmesi ve pekiştirilmesi sonucu ortaya çıkmaktadır. Bu durum, belirli demografik gruplara yönelik ayrımcılığa neden olabilmekte ve dijital güveni zayıflatmaktadır. Şeffaflık sorunu ise, karmaşık yapay zeka modellerinin karar verme süreçlerinin anlaşılmasındaki zorluktan kaynaklanmaktadır. "Kara kutu" olarak adlandırılan bu durum, kullanıcıların yapay zeka sistemlerine duyduğu güveni sınırlandırmaktadır. Explainable AI (açıklanabilir yapay zeka) alanındaki araştırmalar, bu sorunu çözmeyi hedeflemektedir. Hesap verebilirlik ise, yapay zeka sistemlerinin hatalı kararlarından kaynaklanan zararların kimin tarafından üstlenileceği sorusunu gündeme getirmektedir. Yapay zeka etiği çerçeveleri, bu sorulara yanıt aramakta ve sorumlu yapay zeka geliştirme ilkelerini tanımlamaktadır.

Yapay zeka destekli güven yönetiminin geleceği, insan-AI işbirliği modellerine dayanmaktadır. Bu modeller, yapay zekanın analitik kapasitesi ile insanın sezgisel yeteneklerini birleştirerek, daha etkili güven yönetimi sistemleri oluşturmayı hedeflemektedir. Örneğin, yapay zeka sistemleri şüpheli etkinlikleri tespit ederken, nihai kararlar insan moderatörler tarafından verilebilir. Duygusal yapay zeka (affective computing) ise, kullanıcıların duygusal durumlarını

anlama ve buna uygun tepkiler verme kapasitesiyle, dijital ortamda duygusal güvenin gelişimini destekleyebilir. Yapay zeka destekli güven yönetimi sistemlerinin başarısı, teknik kapasitenin yanı sıra etik ilkelere uyum ve toplumsal kabul de gerektirmektedir. Kullanıcıların yapay zeka sistemlerine duyduğu güven, bu sistemlerin tasarımı, şeffaflığı ve performansı ile doğrudan ilişkilidir. Gelecekteki araştırmalar, daha güvenilir, adil ve şeffaf yapay zeka sistemleri geliştirmenin yanı sıra, kullanıcıların yapay zekaya olan güvenini artıracak etkileşim modelleri tasarlamaya odaklanmalıdır. Yapay zeka ve güven yönetimi konusundaki gelişmeler, dijital ekosistemin geleceğini şekillendirmede kritik bir rol oynayacaktır.

6.2. Blockchain ve Dağıtılmış Güven Sistemleri

Blockchain teknolojisi, dijital güven yönetiminde devrim niteliğinde potansiyeller sunmaktadır. Merkeziyetsiz, şeffaf ve değiştirilemez kayıt sistemi olarak blockchain, geleneksel güven modellerini kökten dönüştürme kapasitesine sahiptir. Akıllı sözleşmeler, merkezi bir otoriteye ihtiyaç duymadan güvenilir işlemler yapılmasına olanak sağlamaktadır. Dağıtılmış defter teknolojisi, tüm işlemlerin şeffaf ve doğrulanabilir bir şekilde kaydedilmesini mümkün kılmaktadır. Blockchain tabanlı güven sistemleri, özellikle kimlik yönetimi, itibar sistemleri ve tedarik zinciri izlenebilirliği gibi alanlarda önemli avantajlar sunmaktadır. Self-sovereign identity (öz egemen kimlik) kavramı, bireylerin kendi kimlik verileri üzerinde tam kontrole sahip olduğu merkeziyetsiz kimlik sistemlerini ifade etmektedir.

Sovrin, uPort ve Civic gibi projeler, bu alandaki öncü girişimlerdir. Blockchain tabanlı itibar sistemleri ise, kullanıcı itibar verilerinin merkezi platformlar tarafından kontrol edilmesi yerine, kullanıcıların kendileri tarafından yönetilmesine olanak tanımaktadır. Bu sistemler, itibar verilerinin taşınabilirliğini, birlikte çalışabilirliğini ve güvenilirliğini artırmaktadır. Tedarik zinciri izlenebilirliği alanında ise, blockchain teknolojisi ürünlerin kaynağından nihai tüketiciye kadar tüm sürecin şeffaf bir şekilde kaydedilmesini sağlamaktadır. Bu, sahtecilik ve taklit ürün sorununa etkili bir çözüm sunmaktadır. Ancak, blockchain tabanlı güven sistemleri de ölçeklenebilirlik, enerji tüketimi, kullanıcı deneyimi ve düzenleyici belirsizlik gibi zorluklarla karşı karşıyadır. Ölçeklenebilirlik sorunu, blockchain ağlarının işlem hacmi ve hızı konusundaki sınırlamalardan kaynaklanmaktadır. Enerji tüketimi ise, proof-of-work (iş ispatı) konsensüs mekanizması kullanan blockchain ağlarının önemli bir çevresel maliyetidir. Kullanıcı deneyimi zorluğu, blockchain sistemlerinin teknik karmaşıklığından kaynaklanmakta ve geniş kitleler tarafından benimsenmesini engelleyebilmektedir. Düzenleyici belirsizlik ise, blockchain teknolojisinin hukuki çerçevesinin henüz tam olarak oturmamış olmasından kaynaklanmaktadır. Blockchain teknolojisinin dijital güven yönetimindeki potansiyelini tam olarak gerçekleştirebilmesi için, bu zorlukların aşılması gerekmektedir. Layer 2 çözümleri, sharding (parçalama) teknikleri ve alternatif konsensüs mekanizmaları, ölçeklenebilirlik ve enerji verimliliği sorunlarına çözüm sunmaktadır.

Kullanıcı dostu arayüzler ve eğitim programları ise, kullanıcı deneyimi zorluklarını aşmaya yardımcı olabilir. Düzenleyici çerçevelerin geliştirilmesi ise, blockchain teknolojisinin yasal belirsizliklerini giderecektir. Blockchain tabanlı güven sistemlerinin geleceği, mevcut sistemlerle birlikte çalışabilirlik ve kademeli geçiş stratejilerine bağlıdır. Hibrit modeller, merkezi ve merkeziyetsiz sistemlerin avantajlarını birleştirerek, daha etkili güven çözümleri sunabilir. Blockchain teknolojisinin dijital güven yönetimindeki rolü, sadece teknik bir yenilik değil, aynı zamanda güç dinamiklerini yeniden dağıtan sosyoteknik bir dönüşümdür. Bu dönüşüm, daha demokratik, şeffaf ve kullanıcı merkezli bir dijital ekosistem vizyonunu temsil etmektedir.

6.3. Dijital Güven Metrikleri ve Ölçüm Yöntemleri

Dijital güvenin ölçülmesi ve değerlendirilmesi, etkili güven yönetimi için hayati öneme sahiptir. Dijital güven metrikleri, güvenin çok boyutlu doğasını yansıtan kapsamlı ve çeşitli ölçüm araçları gerektirmektedir. Bu metrikler, nesnel ve öznel göstergeleri, nitel ve nicel verileri, anlık ve zaman serisi ölçümlerini içermelidir. Nesnel göstergeler, platform kullanım

istatistikleri, işlem verileri, güvenlik metrikleri ve performans ölçümlerinden oluşmaktadır. Özel göstergeler ise, kullanıcı anketleri, derinlemesine görüşmeler, odak grup çalışmaları ve duygu analizleri yoluyla toplanan verilerdir. Dijital güven ölçümünde kullanılan başlıca metrikler arasında, güven endeksleri, itibar puanları, kullanıcı bağlılığı ölçümleri, güvenlik göstergeleri ve algoritmik güven metrikleri bulunmaktadır. Güven endeksleri, çok boyutlu güven göstergelerinin bileşik ölçümleridir. İtibar puanları, kullanıcıların geçmiş performanslarına dayalı sayısal değerlendirmelerdir. Kullanıcı bağlılığı ölçümleri, platform kullanım sıklığı, süresi ve derinliği gibi davranışsal göstergeleri içerir. Güvenlik göstergeleri, veri ihlali istatistikleri, güvenlik açığı metrikleri ve siber güvenlik performans ölçümlerinden oluşur.

Algoritmik güven metrikleri ise, algoritmaların adillik, şeffaflık ve hesap verebilirlik düzeylerini ölçer. Dijital güven ölçümünde kullanılan metodolojiler arasında, anket araştırmaları, davranışsal analizler, ağ analizleri, deney tasarımları ve veri madenciliği teknikleri bulunmaktadır. Anket araştırmaları, kullanıcıların güven algılarını doğrudan ölçmek için kullanılır. Davranışsal analizler, kullanıcıların fiili davranışlarını gözlemleyerek dolaylı güven göstergeleri sağlar. Ağ analizleri, kullanıcı etkileşim ağlarındaki güven ilişkilerini haritalandırır. Deney tasarımları, güveni etkileyen faktörleri kontrollü koşullarda test etmeye olanak tanır. Veri madenciliği teknikleri ise, büyük veri setlerindeki güven modellerini keşfeder. Dijital güven ölçümünün zorlukları arasında, ölçümün çok boyutluluğu, bağlamsal faktörler, kültürel farklılıklar ve dinamik değişim bulunmaktadır. Güvenin özel doğası, standart ölçüm yöntemleri geliştirmeyi zorlaştırmaktadır. Bağlamsal faktörler, güven ölçümlerinin farklı dijital ortamlarda farklı anlamlar taşımasına neden olabilir. Kültürel farklılıklar ise, güven algılarının kültürler arasında değişkenlik göstermesine yol açar.

Dinamik değişim, güvenin zaman içinde değişen doğasını yansıtmak için sürekli ölçüm gerektirir. Dijital güven metriklerinin geleceği, daha gelişmiş ve entegre ölçüm sistemlerine doğru evrilmektedir. Yapay zeka destekli analitik sistemler, çok boyutlu güven verilerini entegre ederek daha kapsamlı güven değerlendirmeleri yapabilir. Gerçek zamanlı izleme sistemleri, güven dinamiklerini anlık olarak takip edebilir. Standartlaştırılmış ölçüm çerçeveleri ise, farklı platformlar ve bağlamlar arasında karşılaştırılabilir güven verileri sağlayabilir. Dijital güven metriklerinin geliştirilmesi, sadece akademik bir çaba değil, aynı zamanda dijital ekosistemin sağlığını izlemek ve iyileştirmek için pratik bir gerekliliktir. Etkili dijital güven metrikleri, platformların performansını değerlendirmek, kullanıcı ihtiyaçlarını anlamak ve güveni artırıcı müdahaleler tasarlamak için gerekli olan veriye dayalı içgörülerini sağlayacaktır.

7. SONUÇ

Dijital enformasyon ekosisteminde güven inşası, 21. yüzyılın en önemli sosyoteknik zorluklarından biridir. Bu makale, dijital güvenin karmaşık doğasını, çok boyutlu mekanizmalarını ve gelecek yönelimlerini kapsamlı bir şekilde incelemiştir. Dijital güven, geleneksel güven kavramlarından radikal bir dönüşüm geçirmiş ve yeni formlar, mekanizmalar ve dinamikler kazanmıştır. Sosyal sermaye kuramları, dijital güvenin anlaşılması için güçlü bir teorik çerçeve sunmaktadır. Platform tasarımı, itibar sistemleri ve sosyal kanıt mekanizmaları, dijital güven inşasının temel bileşenleridir. Dijital güvenin bilişsel ve duygusal, kurumsal ve kişilerarası, teknolojiye dayalı ve algoritmik boyutları, bu kavramın çok yönlü doğasını yansıtmaktadır. Dijital güven krizleri ve güven onarımı stratejileri, dijital ekosistemin sürdürülebilirliği açısından hayati öneme sahiptir. Gelecek araştırmalar, yapay zeka destekli güven sistemleri, blockchain tabanlı güven modelleri ve standartlaştırılmış dijital güven metrikleri üzerine odaklanmalıdır.

Dijital güvenin geleceği, teknolojik yenilikler ile sosyal ihtiyaçlar arasındaki dengenin kurulmasına bağlıdır. Etkili bir dijital güven ekosistemi, şeffaflık, hesap verebilirlik, katılımcılık ve etik değerler üzerine inşa edilmelidir. Bu, sadece akademik bir tartışma değil, aynı zamanda dijital toplumun geleceği için stratejik bir önceliktir. Dijital güven araştırmaları,

disiplinler arası işbirliği, veriye dayalı yaklaşımlar ve kullanıcı merkezli tasarım ilkeleri etrafında şekillenmelidir. Nihai hedef, daha güvenilir, şeffaf ve insani bir dijital ekosistem inşa etmektir. Bu hedefe ulaşmak, tüm paydaşların -akademi, endüstri, düzenleyiciler ve sivil toplum- ortak çabasını gerektirmektedir. Dijital güven, modern toplumun karşılaştığı en karmaşık zorluklardan biri olmaya devam ederken, aynı zamanda daha adil ve sürdürülebilir bir dijital gelecek inşa etmek için benzersiz bir fırsat sunmaktadır.

KAYNAKÇA

- Acquisti, A., Brandimarte, L., & Loewenstein, G. (2020). Secrets and likes: The drive for privacy and the difficulty of achieving it in the digital age. *Journal of Consumer Psychology*, 30(4), 736-758.
- Aral, S. (2020). The hype machine: How social media disrupts our elections, our economy, and our health—and how we must adapt. *Currency*.
- Bakos, Y., & Nault, B. R. (2020). On the role of transparency in digital platforms. *Information Systems Research*, 31(4), 1107-1123.
- Beldad, A., & Hegner, S. M. (2019). I trust the platform... but I don't trust the seller: The role of platform and seller trust in online purchase decisions. *Electronic Commerce Research*, 19(2), 291-315.
- Benlian, A., & Haffke, I. (2020). Does mutuality matter? Examining the bilateral nature and effects of CEO–CIO mutual understanding. *Journal of Strategic Information Systems*, 29(2), 101614.
- Bhuiyan, M. M., Horning, M., Lee, S. Y., & Yoon, S. (2020). The role of transparency in algorithmic systems: A systematic literature review. *Proceedings of the ACM on Human-Computer Interaction*, 4(CSCW2), 1-26.
- Bolton, G. E., Greiner, B., & Ockenfels, A. (2013). Engineering trust: Reciprocity in the production of reputation information. *Management Science*, 59(2), 265-285.
- Burt, R. S. (2000). The network structure of social capital. *Research in Organizational Behavior*, 22, 345-423.
- Cheshire, C. (2019). Online trust, trustworthiness, or assurance? *Daedalus*, 148(2), 125-134.
- Dellarocas, C. (2003). The digitization of word of mouth: Promise and challenges of online feedback mechanisms. *Management Science*, 49(10), 1407-1424.
- Gefen, D., Karahanna, E., & Straub, D. W. (2003). Trust and TAM in online shopping: An integrated model. *MIS Quarterly*, 27(1), 51-90.
- Komiak, S. Y., & Benbasat, I. (2006). The effects of personalization and familiarity on trust and adoption of recommendation agents. *MIS Quarterly*, 30(4), 941-960.
- Kumar, N., & Benbasat, I. (2006). The influence of recommendations and consumer reviews on evaluations of websites. *Information Systems Research*, 17(4), 425-439.
- Li, X., & Sarkar, A. (2019). Building trust in the sharing economy: The role of personal and situational factors. *Journal of Business Research*, 101, 639-649.
- Malhotra, N. K., Kim, S. S., & Agarwal, J. (2004). Internet users' information privacy concerns (IUIPC): The construct, the scale, and a causal model. *Information Systems Research*, 15(4), 336-355.
- Mayer, R. C., Davis, J. H., & Schoorman, F. D. (1995). An integrative model of organizational trust. *Academy of Management Review*, 20(3), 709-734.
- McKnight, D. H., Choudhury, V., & Kacmar, C. (2002). Developing and validating trust measures for e-commerce: An integrative typology. *Information Systems Research*, 13(3), 334-359.
- Pavlou, P. A., & Gefen, D. (2004). Building effective online marketplaces with institution-based trust. *Information Systems Research*, 15(1), 37-59.

- Pentland, A. (2014). *Social physics: How good ideas spread—The lessons from a new science*. Penguin Press.
- Putnam, R. D. (2000). *Bowling alone: The collapse and revival of American community*. Simon & Schuster.
- Resnick, P., Kuwabara, K., Zeckhauser, R., & Friedman, E. (2000). Reputation systems. *Communications of the ACM*, 43(12), 45-48.
- Riedl, R., Léger, P. M., & Wallace, R. J. (2020). Trust in automation: Integrating empirical evidence on factors that influence trust. *Human Factors*, 62(3), 407-434.
- Shin, D. (2020). How do users interact with algorithm-based systems? The role of algorithm awareness and algorithm appreciation. *International Journal of Human-Computer Interaction*, 36(8), 741-753.
- Sunstein, C. R. (2017). *Republic: Divided democracy in the age of social media*. Princeton University Press.
- Tapscott, D., & Tapscott, A. (2016). *Blockchain revolution: How the technology behind Bitcoin is changing money, business, and the world*. Penguin.
- Yılmaz, M. (2022). Semboller üzerinden iletişim ve kültürel kimlik inşası. *Güncel İletişim Çalışmaları*, Bengü Yayınları, Ankara, s. 132.
- Zuboff, S. (2019). *The age of surveillance capitalism: The fight for a human future at the new frontier of power*. PublicAffairs.

**ÇAĞDAŞ TAKI TASARIMINDA ALTERNATİF RENKLENDİRME YÖNTEMİ
OLARAK YÜKSEK PİGMENTLİ SANATSAL BOYALARIN KULLANIMI
THE USE OF HIGH-PIGMENT ARTISTIC PAINTS AS AN ALTERNATIVE COLORING
METHOD IN CONTEMPORARY JEWELRY DESIGN**

Gizem YAĞCI

Yüksek Lisans Öğrencisi, Altınbaş Üniversitesi, Lisansüstü Eğitim Entitüsü,
Plastik Sanatlar Ana Bilim Dalı, Sanat ve Tasarım Yüksek Lisans Programı, Gayrettepe,
İstanbul.

Orcid ID: 0009-0006-6736-6105

Doç. Dr. Çimen BAYBURTLU

Marmara Üniversitesi Uygulamalı Bilimler Fakültesi
Kuyumculuk ve Mücevher Tasarımı Bölümü, Maltepe, İstanbul.

Orcid ID: 0000-0001-9284-665X

ÖZET

Takı sanatının tarihsel gelişimi içerisinde metal yüzeylerin renklendirilmesi ve bezenmesi, tasarımın estetik değerini belirleyen temel unsurlardan biri olmuştur. Sıcak mine gibi geleneksel tekniklerin uygulama aşamasında gerektirdiği teknik donanım ve atölye koşulları, tasarımcılar için zaman zaman kısıtlayıcı bir faktör oluşturmaktadır. Bu yaklaşımda kullanılacak yöntem ve malzeme oldukça geniş bir yelpazeye sahiptir. Bu çalışmada, çağdaş mücevher tasarımı bağlamında, metal yüzeylerin renklendirilmesinde geleneksel yöntemlere alternatif olarak sanat malzemeleri kategorisindeki boyaların kullanım olanaklarını incelemeyi amaçlanmaktadır. Araştırma süreci, tamamen uygulama ve gözleme dayalı deneysel bir yaklaşımla yürütülmüştür. Seçilen bakır ve pirinç plakalar üzerinde yüksek pigmentli sanatsal boyaları kullanılarak doğrudan renklendirme çalışmaları yapılmıştır. Bu süreçte boyanın metal yüzeyindeki yayılımı, katman oluşturma özellikleri ve yüzeyle kurduğu görsel temas, atölye ortamında uygulamalı olarak deneyimlenmiştir. Deneysel süreç sonunda, sanatsal boyaların metal üzerinde alışılmışın dışında yumuşak geçişler ve zengin renk katmanları oluşturduğu gözlemlenmiştir. Uygulama sırasında boyaların metal yüzeye verdiği tepkiler, renklerin üst üste binmesiyle oluşan yeni tonlar ve yüzeyin bir resim tuvali gibi kullanılabilmesi, yöntemin en belirgin özellikleri olarak saptanmıştır. Bu teknikle, geleneksel yöntemlerin daha özgür ve spontane bir tasarım dili geliştirilebileceği deneyimlenmiştir. Bu çalışma ile sanatsal boyaların mücevher tasarımında yenilikçi ve pratik bir renklendirme aracı olarak kullanılabileceği görülmüştür. Yapılan denemeler, metalin soğuk yapısının sanatsal pigmentlerle birleştiğinde mücevherin ifade gücünü artırdığını ve tasarımcıya geniş bir hareket alanı sağladığını ortaya koymuştur.

Anahtar Kelimeler: Çağdaş Takı, Metal Renklendirme, Yüksek Pigmentli Sanatsal Boya, Deneysel Tasarım.

ABSTRACT

Throughout the historical development of jewelry art, the coloring and decoration of metal surfaces have been one of the fundamental elements determining the aesthetic value of the design. The technical equipment and workshop conditions required for the application of traditional techniques such as hot enamel can sometimes be a limiting factor for designers. The methods and materials to be used in this approach cover a wide range. This study was conducted to examine the possibilities of using paints in the art supplies category as an alternative to traditional methods for coloring metal surfaces in the context of contemporary jewelry design.

The research process was conducted using an experimental approach based entirely on application and observation. Direct coloring studies were carried out using high-pigment art paints on selected copper and brass plates. During this process, the spread of paint on metal surfaces, its layer-forming properties, and its visual contact with the surface were experienced hands-on in a workshop setting. At the end of the experiment, it was observed that artistic paints created exceptionally smooth transitions and rich layers of color on metal. The reactions of the paints to the metal surface during application, the new tones created by the overlapping of colors, and the ability to use the surface like a canvas have been identified as the most distinctive features of the method. With this technique, it has been experienced that a more free and spontaneous design language can be developed compared to traditional methods. This study has demonstrated that artistic paints can be used as an innovative and practical coloring tool in jewelry design. Experiments have revealed that when combined with artistic pigments, the cool structure of metal enhances the expressive power of jewelry and provides designers with a wide range of possibilities.

Keywords: Contemporary Jewelry, Metal Coloring, High-Pigment Artistic Paint, Experimental Design.

GİRİŞ

Takının tarihsel kökenleri incelendiğinde, bireyin süslenme, korunma ve kendini ifade etme gereksinimleri doğrultusunda takıyı erken dönemlerden itibaren işlevsel ve simgesel bir araç olarak kullandığı görülmektedir. İlk örneklerde taş boncuklar, organik materyaller ve lifler ön plandayken, yerleşik yaşamın benimsenmesi ve toplumsal yapıların gelişmesiyle birlikte takıda kullanılan malzeme ve teknikler de çeşitlenmiştir. Değerli madenlerin işlenmesi, değerli taşların kesim tekniklerinin gelişmesi ve üretim biçimlerinin çoğalması, takının hem geleneksel hem de bireysel bir ifade alanı olduğunu ortaya koymaktadır.

Sanat tarihi bağlamında ele alındığında, takı sanatı özellikle çağdaş sanat akımlarının etkisiyle disiplinlerarası bir nitelik kazanmıştır. Alexander Calder, René Lalique ve Salvador Dalí gibi sanatçıların ürettikleri takılar, takının yalnızca zanaat ürünü değil, aynı zamanda sanatsal bir ifade aracı olarak konumlandığını göstermektedir.

Modern sanatla birlikte sanat anlayışında yaşanan köklü dönüşümler, zamanla çağdaş sanat kavramının ortaya çıkmasına zemin hazırlamıştır. Geleneksel yaklaşımların sorgulanmasıyla başlayan bu süreç, kimi dönemlerde geleneksel olanın yeniden ele alınması ve yorumlanması yönünde ilerlemiştir. Bu avangard dönüşümler, sanatçıya teknik, malzeme ve üslup açısından yeni düşünsel ve biçimsel olanaklar sunmuştur.

1950’lerden itibaren takı da bu dönüşümden payını almış ve “çağdaş” nitelik kazanan bir ifade alanına dönüşmüştür. Çağdaş takıda belirleyici unsur, takının düşünsel bir içerik taşımasıdır. Alternatif malzeme ve tekniklerin kullanımı ise bu düşünsel boyutu güçlendiren temel unsurlar arasında yer almaktadır. Çağdaş sanatın bireysel yorumlara açık yapısı, çağdaş takı pratiğinde de etkisini sürdürmektedir. Bu bağlamda Öner (2020: iv), metalurjik gelişmeler ve yeni kuyumculuk teknikleri sayesinde takının zanaat ile sanat arasında konumlanan bir alan haline geldiğini sanatçıların geleneksel kalıplardan bağımsız olarak farklı malzeme ve tekniklerle üretim yapma özgürlüğü kazandığını belirtmektedir. Bu yenilikçi yaklaşım, takı sanatında farklı ifade biçimlerinin ortaya çıkmasına olanak tanımıştır.

Takı sanatçısı Frang, metal yüzeyler üzerine boya uygulamasına ilişkin deneyimlerini aktarırken, bu yöntemin başlangıçta kendisi için tedirginlik yarattığını, ancak süreç ilerledikçe uygulamanın eğlenceli, deneysel ve yaratıcı bir üç boyutlu oyun alanına dönüştüğünü ifade etmektedir (URL1). Bu kişisel deneyim, çağdaş takı pratiğinde üretim sürecinin yalnızca teknik bir aşama olmadığını, aynı zamanda düşünsel ve deneyimsel bir keşif alanı olarak ele alındığını göstermesi bakımından önemlidir.

Takının düşünsel bir ifade alanı olarak yeniden tanımlanması, doğal olarak üretim sürecinde kullanılan malzeme ve tekniklerin de sorgulanmasını beraberinde getirmiştir. Bu bağlamda özellikle yüzey, renk ve doku gibi biçimsel unsurlar, çağdaş takı tasarımında kavramsal içeriği destekleyen temel araçlar haline gelmiştir. Geleneksel uygulamalar arasında yer alan sıcak mine ve patina teknikleri ise yüksek ısı gereksinimi ve karmaşık kimyasal süreçler içermeleri nedeniyle üretim sürecinde çeşitli sınırlılıklar yaratabilmektedir. Söz konusu sınırlılıklar, çağdaş takı tasarımı kapsamında daha erişilebilir, esnek ve deneysel yöntemlere yönelik ilgiyi artırmış; metal yüzeylerde ısı işlem gerektirmeyen alternatif renklendirme yaklaşımlarının araştırılmasını gündeme getirmiştir.

Bu doğrultuda Hettmansperger (2012:15), takı tasarımında renkli boyaların kullanımının geleneksel bir yöntem olmadığını vurgulamakla birlikte, bu tekniğin daha güvenli olması ve malzeme kullanımının görece kolaylığı nedeniyle önemli avantajlar sunduğunu belirtmektedir. Ayrıca renkli kalemlerin sunduğu geniş renk çeşitliliğine dikkat çekerek, bu malzemelerin kolaylıkla temin edilebilir olmasının üretim sürecini daha erişilebilir kıldığını ifade etmektedir. Benzer şekilde O'Brien, "Bakır Takı Üzerine Renkli Kalem Kullanımı" (2017: 9-10) adlı çalışmasında, cam boncuk ve gümüş üzerine çeşitli tekniklerle üretimler gerçekleştirdikten sonra eserlerine renk ve doku açısından daha fazla çeşitlilik kazandırma arayışına girdiğini belirtmektedir. Bu arayış sürecinde farklı yüzey renklendirme tekniklerini araştıran sanatçı, renkli kalemlerle metal üzerine çalışmaya yönelmiş ve birkaç yıl süren deneysel çalışmalar sonucunda elde ettiği teknik ve süreç bilgilerini söz konusu kitabında ayrıntılı biçimde aktarmıştır. Eserde, metal yüzeylerde boya kullanımı tekniğinin yanı sıra patina gibi geleneksel renklendirme yöntemlerine de değinilmiştir. Ayrıca bununla birlikte boncuk gibi, takı yüzeyini süsleme amacıyla kullanılan ve geleneksel malzemelere alternatif oluşturan unsurların sanatçının eserlerinde nasıl konumlandırıldığı görsel örneklerle ortaya konulmuştur.

Sıcak mine tekniği, cam esaslı bir malzemenin ince toz haline getirilerek metal yüzeye uygulanması ve farklı renk ile uygulama özelliklerine göre değişen sıcaklık derecelerinde pişirilmesi esasına dayanır. Yaklaşık 830 °C'ye ulaşabilen bu süreçte mine, metal yüzey üzerinde eriyerek sert, parlak ve camsı bir tabaka oluşturur. Elde edilen yüzey etkisi estetik açıdan güçlü olmakla birlikte, uygulama süreci hem teknik donanım hem de kontrollü atölye koşulları gerektirmektedir.

Patina uygulamaları, metal yüzeylerde kimyasal tepkimeler aracılığıyla renk ve doku elde edilmesine olanak tanıyan geleneksel renklendirme yöntemleri arasında yer almaktadır. Bu amaçla hazır patina çözeltilerinin yanı sıra asidik ve bazik özellikler gösteren çeşitli kimyasal maddeler kullanılabilir. Doğal patina olarak nitelendirilen bu uygulamalar, metal yüzeyinde kontrollü oksidasyon süreçleri oluşturarak farklı renklemeler ve yüzey karakterleri ortaya çıkarmaktadır. Ayrıca söz konusu maddelerin görece düşük enerji gereksinimi ve kolay erişilebilir olması, bu yöntemlerin sürdürülebilir üretim anlayışıyla örtüşen bir yaklaşım sunduğunu göstermektedir.

Bununla birlikte, çağdaş takı tasarımı bağlamında renkli kalemler, yalnızca grafiksel ve dokusal renkli yüzeyler oluşturmak için değil, aynı zamanda kimyasal reaksiyonlar sonucu pasif biçimde oluşan patinalara kıyasla daha kararlı ve kontrollü bir biçimde korunabilen hassas ve çarpıcı patina etkilerini simüle etmek amacıyla da kullanılabilir (URL 2). Bu yönüyle renkli kalemler, metal yüzey renklendirmede geleneksel patina uygulamalarına alternatif, deneysel ve esnek bir ifade aracı olarak öne çıkmaktadır.

Isıl işlem temelli bu tekniklerin belirli mekânsal ve teknik koşullara bağımlı olması, her ortamda uygulanabilir olmalarını güçleştirmektedir. Bu nedenle, söz konusu koşulların sağlanamadığı durumlarda metal yüzeylerin sanatsal boyalar aracılığıyla renklendirilmesine yönelik alternatif yöntemlerin geliştirilmesi mümkün görünmektedir. Kullanılan malzeme ve yöntemlerin yenilikçi karakteri, bu tür uygulamaların çağdaş takı kapsamında değerlendirilmesini desteklemektedir.


INTERNATIONAL TOPKAPI CONGRESS VI

Bu çalışmanın amacı, takı alanında geleneksel bir yöntem olan sıcak mine üzerine resim yapma tekniğine alternatif olarak, yüksek pigmentli sanatsal boyalarla metal yüzey üzerinde resim yapma uygulamasını incelemektir. Bu yaklaşım aracılığıyla, gerekli teknik donanımına veya atölye koşullarına sahip olmayan ya da üretim sürecinde farklı malzeme ve yöntemleri denemek isteyen sanatçı ve tasarımcılara alternatif bir uygulama alanı sunulması hedeflenmektedir.

Önerilen bu yöntemin, takı yüzeyinde çizgisel formlar ve dokular aracılığıyla bireysel ifade olanaklarını artırabileceği düşünülmektedir. Farklı üretim teknikleri ve malzemelerle birlikte uygulanabilen bu yaklaşım, metal yüzey renklendirme alanında deneysel bir zemin oluşturmaktadır. Metal üzerine renklendirme uygulamalarıyla takı tasarlayan bazı sanatçı ve tasarımcıların eser örnekleri ilgili görsellerde sunulmaktadır (Görsel 1-10).



Görsel 1: Deb Karash, Broş, Metal Üzerine Renklendirme.



Görsel 2: Deb Karash, Broş, Metal Üzerine Renklendirme.



Görsel 3: Roxan O'brien, Kolye, Metal Üzerine Renklendirme.



Görsel 4: Roxan O'brien, Broş, Metal Üzerine Renklendirme.



Görsel 5: Mary Karg, Kolye, Metal Üzerine Renklendirme.



Görsel 6: Mary Karg, Kolye, Metal Üzerine Renklendirme.



Görsel 7: Anja Tverdokhlebova, Broş, Metal Üzerine Renklendirme.



Görsel 8: Anja Tverdokhlebova, Broş, Metal Üzerine Renklendirme.



Görsel 9: Anna Krof, Broş,
Metal Üzerine Renklendirme.



Görsel 10: Anna Krof, Broş,
Metal Üzerine Renklendirme.

Alana dair takı üretim tekniklerinden repousse/kabartma tekniği örneği (Görsel 11) ile alternatif malzeme kullanımına örnek olarak metal kili ile yapılmış (Görsel 12) ürün örneklerine aşağıda yer verilmiştir.



Görsel 11: Jan Fagan, Kolye Ucu,
Metal Üzerine Renklendirme.



Görsel 12: Julia Rai, Boncuk-Bileklik,
Metal Üzerine Renklendirme.

YÖNTEM

Bu çalışmada nitel araştırma yöntemi kullanılmış, araştırmanın deseni vaka analizi ve durum çalışması bağlamında deneysel tasarım araştırmaları olarak belirlenmiştir. Araştırmanın evreni metal yüzeylerin yüksek pigmentli sanatsal boyalar ile renklendirilmesidir. Araştırma, uygulama ve gözleme dayalı atölye çalışması olarak deneysel araştırma süreci ile yürütülmüştür.

VAKA ANALİZİ: DENEYSEL ÇALIŞMA

Çalışma kapsamında bakır plakalar üzerine illüstratif bir kompozisyon uygulanmıştır.

Gözlem: Uygulama sırasında boyaların metal üzerinde alışılmışın dışında yumuşak geçişler sunduğu görülmüştür.

Veri: Renklerin üst üste binmesiyle oluşan yeni tonlar ve yüzeyin bir resim tuvali gibi kullanılabilmesi, yöntemin en özgürleştirici özelliği olarak saptanmıştır.

Dayanıklılık: Renkli kalem katmanı sertlik skalasında düşük olsa da polimerik kaplamaların yarattığı “çapraz bağlanma” sayesinde takının günlük kullanımda mekanik sürtünmeye karşı direnç kazandığı gözlemlenmiştir.

Yüksek pigmentli sanatsal boyalar ile çalışılmak için bakır ve pirinç metali seçilmiştir. Araştırma süreci, deneysel bir yaklaşımla tamamen uygulama ve gözleme dayalı yürütülerek, metal üzerinde boyanın verdiği sonuçlar atölye ortamında uygulamalı olarak deneyimlenmiştir. Seçilen bakır ve pirinç plakalar kuru kalemler aracılığı ile doğrudan renklendirme çalışmaları yapılarak boyanın metal yüzeyindeki yayılımı, katman oluşturma özellikleri ve yüzeyle kurduğu görsel temas, atölye ortamında uygulamalı olarak deneyimlenmiştir.

Metal üzerine yapılacak olan boya çalışmasına dair uygulamadaki takip edilecek işlem sıralaması Tablo 1’de yer almaktadır.

Tablo 1. Metodoloji: Uygulama Teknikleri

Aşama	İşlem Adı	Teknik Detay ve Ekipman	Kritik Parametreler / Notlar
I. Hazırlık	Mekanik Aşındırma	Teknik Detay ve Ekipman	Yüzeyin tamamen mat ve tekdüze olması zorunludur.
II. Temizlik	Yağlardan Arındırma	400-600 Grit Su Zımparası veya Kumlama	Elle temastan kaçınılmalı (pudrasız eldiven kullanılmalı).
III. Astar	Kimyasal İyileştirme	%99 İzopropil Alkol veya Aseton	Pigment doygunluğunu artırmak için kullanılır.
IV. Renklendirme	Katmanlama	Opsiyonel: Şeffaf Gesso veya Mat Metal Astarı	Düşük basınçlı, dairesel hareketlerle en az 3-4 katman.
V. Termal Sabitleme	Isıl İşlem	Balmumu bazlı profesyonel kalemler	Pigmentlerin parlamaya başlaması
VI. Kaynaştırma	Çözücü veya ısı ile kaynaştırma	Isı tabancası veya elektrikli ocak	Renk geçişlerini homojenize etmek için uygulanır.
VII. Mühürleme	Polimerik Kaplama	Mineral İspirto veya Alkol bazlı blender	İnce katmanlar halinde 20 cm mesafeden uygulanmalıdır.
VIII. Final	Yüzey Koruması	-UV Dirençli Mat/Parlak Akrilik Sprey -Mikrokristalin Vaks (Son kat olmalıdır)	Oksidasyonu önlemek için son bariyer olarak elle uygulanır.

DENEYSEL UYGULAMALAR

Bu aşamada Tablo 1’de bahsedilen süreçler izlenerek uygulama işlemlerine devam edilmiştir. İlk olarak bakır plaka üzerine illüstratif iki deneme örneğine yer verilmiştir (Görsel 13-14). Sonraki uygulamalar ise dokulu pirinç plakalar ile yapılan örnekleridir.



Görsel 13: Çimen Bayburtlu, “Deneme I”, Bakır Astar, Prismacolor Kuru boya kalemleri, Solvent, Gesso, 2022.



Görsel 14: Çimen Bayburtlu, “Deneme II”, Bakır Astar, Prismacolor Kuru boya kalemleri, Solvent, Gesso, 2022.

METAL YÜZEYİNİN HAZIRLANMASI

Metal, gözeneksiz bir yüzey olduğu için pigmentin tutunması tamamen yüzeyin morfolojik olarak manipüle edilmesine bağlıdır. Akademik bağlamda “arayüzey yapışması” olarak tanımlanan bu süreçte iki temel yöntem izlenir:

Mekanik Aşındırma: Metalin kalem pigmentini kabul etmesi için yüzeyde mikroskobik pürüzlülüğün oluşturulması gerekir. Bu süreçte zımpara numarası kritik öneme sahiptir. 400-600: Pigmentin tutunabileceği en ideal yüzey genişliğini sağlamaktadır.

Kimyasal Aşındırma: Yüzey alanını mikroskobik düzeyde artırarak boyanın metalle bütünleşmesini maksimize etmektedir. Sadece zımpara ile oluşturulan pürüzlülük, pigmentin metal yüzeyine tutunması için her zaman yeterli olmayabilir. Akademik bağlamda bu, “Arayüzey Yapışması” olarak adlandırılır. Bakır ve alaşımları üzerinde Demir III Klorür

kullanımı, yüzey alanını geometrik olarak artırarak pigmentin metale yapısal olarak sabitlenmesini sağlar.

YÜKSEK PİGMENTLİ MALZEMELER

Metal üzerine kalem ve boya uygulamasının başarısı, malzemenin metal yüzeyiyle kurduğu mekanik tutunma prensibine dayanmaktadır.

Pigment ve Bağlayıcı Etkileşimi: Profesyonel düzeydeki kalemler, pigmenti metal yüzeyine taşıyan bağlayıcı türlerine göre balmumu ve yağ bazlı olarak ikiye ayrılır.

Balmumu Bazlı: Yapısal olarak daha yumuşaktır. Bu özellik, renklerin üst üste binerek yeni tonlar oluşturmaya ve “parlatma/ezme” tekniği ile yüzeyde doygun katmanlar elde edilmesine olanak tanır.

Yağ Bazlı: Daha sert bir uca sahiptir ve detaylı çizgisel çalışmalar için idealdir. Solventlerle (çözücüler) hızlı tepki vererek yüzeyde homojen yayılım sağlar.

DAYANIKLILIK VE SABİTLEME

Metal yüzeylere uygulanan balmumu ya da yağ bazlı kalemlerin kalıcılığını ve mekanik dayanımını artırmak amacıyla genellikle termal sabitleme olarak adlandırılan ısı işlem uygulanmaktadır. Bu süreç, kullanılan boya türüne bağlı olarak farklılık göstermekle birlikte, metalin boyasız alt yüzeyinin, ısı tabancası veya elektrikli ocak yardımıyla kontrollü biçimde ısıtılmasına dayanmaktadır. Ayrıca, yalnızca bu tür uygulamalara ayrılmış ev tipi fırınlarda düşük sıcaklıkta fırınlama yöntemi de tercih edilebilmektedir. Isıl işlem sayesinde boyaların içerdiği pigmentler, yüzeye daha güçlü bir mekanik tutunum sağlamaktadır. Bu durum hem renklerin daha parlak algılanmasına hem de boyanın metal yüzeye daha iyi sabitlenmesine olanak tanımaktadır. Söz konusu termal sabitleme uygulamaları, akrilik boyaların yüzey tutunumu ve renk stabilitesinin artırılması açısından da geçerlidir.

Yüzey Koruması: Isıl işlemle sabitlenen boya uygulamalarının uzun süreli korunumu, üretim sürecinin en kritik aşamalarından birini oluşturmaktadır. Yeterli bir yüzey koruması sağlanmadığı takdirde, çalışma zaman içerisinde çevresel etkenler ve kullanım koşulları nedeniyle bozulabilmekte, boya yüzeyden ayrılabilir. Bu tür olumsuzlukları önlemek amacıyla UV dirençli mat, yarı mat ya da parlak akrilik spreylere yanı sıra, asit içermeyen mikrokristalin esaslı koruyucu mum uygulamaları tercih edilmektedir. Uygulama sürecinde her katmanın tamamen kuruması beklenmeli; katmanlar arasında en az bir saatlik süre bırakılarak işlem tekrarlanmalıdır. Bu yöntemler, akrilik boyaların metal yüzeylerde korunması için de aynı şekilde uygulanabilmektedir.

UV Reçine: UV ışığı etkisiyle kısa sürede kürleşen sıvı formdaki bir reçine türüdür. Kuyumculuk alanında sıklıkla “UV mine” olarak adlandırılan benzer bir malzeme kullanılmaktadır. Boya uygulamasının sabitleme aşaması tamamlandıktan sonra, UV reçine takı tasarımı ikinci bir koruma katmanı olarak değerlendirilebilmektedir. UV ışığıyla hızlı kürleşen yapısı sayesinde yüzeye uygulanan şeffaf reçine, camsı ve yapay bir tabaka oluşturarak yüzeye üç boyutlu bir derinlik etkisi kazandırmaktadır. Bu özellikleriyle UV reçine, koruyucu ve estetik bir yüzey çözümü sunmaktadır.

UYGULAMA AŞAMALARI

Metalin yüzeyi iyice zımparalandıktan sonra izopril alkol ile yüzey temizliği yapılmıştır. Temizlenen metal üzerine ince katmanlar halinde üç kat gesso sürülmüştür (Görsel 15). Gessonun sürelmesindeki amaç zemine astar atma mantığıdır. Gesso malzemesi, alçı ya da kirecin su ile karıştırıldıktan sonra içine tutkal ilavesiyle üretilmektedir. Malzeme güçlü bir örtme kapasitesi ve çabuk kuruma özelliğine sahiptir. Gesso istenilen yeterlilikte uygulandıktan sonra son katın kurumasının ardından ince ve mat bir yüzey elde edilir. Uygulanan alan üzerinde doygun ve çatlamaya dayanımlı bir yüzey oluşturularak kolay çalışma imkanı verir. Gesso uygulaması bittikten sonra malzeme kurumaya bırakılır.



Görsel 15: Metalin Üzerine Gesso Sürülmesi.




Sonrasında ince uçlu kalem, karbon kağıdı gibi bir işaretleyiciler yardımı ile yüzeye aktarmak istenilen resim gesso sürülmüş metalin üzerine aktarılır. Burada önemli olan resmi yüzeye aktarırken gesso zarar vermemek yüzeyden gessoyu kaldırmamaktır. Bu işlem sonucunda metal yüzey bir tuval haline getirilerek, istenilen şekilde çizim yapabilme olanağı sağlanmaktadır.



Görsel 16: Metalin Üzerine Ana Hat Çizimi.

Permenatlı kalemler ile çizgiler güçlendirerek sabitlenmiştir (Görsel 16). Yağ bazlı renkli kalemler ile renklendirme denemelerinin ilk kat boyama işlemi dört farklı metale uygulanmıştır. Birinci, örnekte ilk olarak gesso sürülmüş yüzey yağ bazlı kuru kalemler ile boyanmıştır (Görsel 17). Boyama işleminden sonra yüzeye fırça yardımı ile terebentin uygulanarak boyanın yüzey üzerinde kaynaşması sağlanmıştır (Görsel 18). Terebentin sıvısı inceltici özelliği ile yağ bazlı kuru kalem uygulamasında boyayı çözerek akışkan bir hale getirdiği için boyanın yüzeyde taşınarak kaynaşmasını sağlar. Bunun yanı sıra hızlı kuruyan yapısı katman uygulamalarında zaman kazandırma açısından önemlidir. Ayrıca metal üzerinde yanlış ya da fazla uygulanmış boyayı, yüzeyden hızlıca temizlemek içinde kullanılmıştır. Terebentin uygulamasından sonra tuval üzerine boyama işlemi yinelenerek yüzeyin istenilen alanlarında terebentin uygulamasına devam edilmiştir (Görsel 19). Metal yüzeye katman atımları sonucunda elde edilen renk ve boyanın kaynaşma yoğunluğu (Görsel 20) da görülmektedir. Katman atımları sırasında önemli olan gesso zarar vermeden yani gesso yüzeyden kazımadan işlemleri uygulamaktır. Aksi takdirde gesso işleminin metalin yüzeyinde tekrar edilmesi gerekmektedir. Terebentin ile birlikte blender kalemler aracılığı ile renklerin kaynaştırma işlemi yapılmıştır.



Görsel 17: Metal Yüzeyi Yağ Bazlı Kalemle Boya İşlemi Denemesi 1.



Görsel 18: Boyama Sonrası Terabentin Uygulaması 1.




Görsel 19: İşlem Tekrarları 1.



Görsel 20: Uygulamalar Sonucundaki Son Boya Katmanı 1.


İlk örnekte uygulanan işlem basamakları diğer üç örnekte de sırası ile uygulanmıştır (Görsel 21-32).



Görsel 21: Metal Yüzeyi Yağ Bazlı Kalemle Boya İşlemi Denemesi 2.




Görsel 22: Boyama Sonrası Terabentin Uygulaması 2.



Görsel 23: İşlem Tekrarları 2.



Görsel 24: Uygulamalar Sonucundaki Son Boya Katmanı 2.



Görsel 25: Metal Yüzeyi Yağ Bazlı Kalemle Boya İşlemi Denemesi 3.



Görsel 26: Boyama Sonrası Terabentin Uygulaması 3.



Görsel 27: İşlem Tekrarları 3.



Görsel 28: Uygulamalar Sonucundaki Son Boya Katmanı 3.



Görsel 29: Metal Yüzeyi Yağ Bazlı Kalemle Boya İşlemi Denemesi 4.



Görsel 30: Boyama Sonrası Terabentin Uygulaması 4.



Görsel 31: İşlem Tekrarları 4.



Görsel 32: Uygulamalar Sonucundaki Son Boya Katmanı 4.

Son olarak boyaların yüzeye sabitlenmesi akrilik vernik yardımı ile sağlanmıştır (Görsel 31-32-33-34). Yüzeye mikrokristalin vaks adı altındaki yoğun beyaz kremi balmumlu ve kokulu koruyucunun sürümünde vereceği sonucun bilinmesi nedeni ile akrilik sprey uygulaması tercih edilmiştir. Akrilik sprey uygulaması, bu uygulamanın sadece deneme amacı ile yapılması durumu adına daha kolay elde edilen bir malzemedir. Metal yüzeydeki boyayı koruma amacı ile

uygulanan vernikleme işleminde verniğin kuruması beklenerek yüzeye farklı zamanlarda dört kat vernik atılmıştır. Uv reçine koruması ise yüzeyde camsı bir katman oluşturacağı bilindiği için bu çalışmada tercih edilmemekle birlikte vernik üzerinde çift katmanlı bir koruma sağlayacağı bilinmektedir.

BULGULAR

Deneyisel olarak yürütülen bu uygulamalı süreç sonunda, sanatsal boyaların metal üzerinde alışılmışın dışında yumuşak geçişler ve zengin renk katmanları oluşturduğu gözlemlenmiştir. Uygulama sırasında boyaların metal yüzeye verdiği tepkiler, renklerin üst üste binmesiyle oluşan yeni tonlar ve yüzeyin bir resim tuvali gibi kullanılabilmesi, yöntemin en belirgin özellikleri olarak saptanmıştır. Bu teknikle, geleneksel yöntemlerin daha özgür ve spontane bir tasarım dili geliştirilebileceği deneyimlenmiştir (Görsel 33-36).



Görsel 33: Metal Yüzeydeki Boyama İşlemlerinin Son Hali ve Sabitleme İşlemi 1.



Görsel 34: Metal Yüzeydeki Boyama İşlemlerinin Son Hali ve Sabitleme İşlemi 2.



Görsel 35: Metal Yüzeydeki Boyama İşlemlerinin Son Hali ve Sabitleme İşlemi 3.



Görsel 36: Metal Yüzeydeki Boyama İşlemlerinin Son Hali ve Sabitleme İşlemi 4.

Hazırlanan parçanın takıya dönüştürülme süreci, tıpkı metal yüzeyin boyama öncesi planlanması kadar önemlidir. Bu süreçten sonra ısı işlem ile birleştirme yapılamayacağı için perçin, tırnak, tel ile sarma gibi soğuk birleştirme ya da kaynaklız halkalar aracılığı ile bağlantılar uygulanarak takının tasarlanması gerekmektedir. Bunun yanı sıra yüzük, bilezik gibi parçalardan ziyade broş, küpe, kolye gibi yani en az şekilde sürtünmeye maruz kalacak parçalar tasarlamak yüzey korunumu ve dayanımı açısından önemlidir. Kaynak kullanılması gereken süreçte lazer kaynak aracılığı ile birleşim ve bağlantıların yapılması gerekmektedir.

Son olarak deneyisel tasarım bağlamında uygulamalar sonunca (Görsel 37,38) da yer alan broş tasarımı üretilmiştir.



Görsel 37: Gizem Yağcı, Broş Çalışması, Pirinç Astar, Kuru boya kalemleri, Terebentin, Gesso, 2026.



Görsel 38: Gizem Yağcı, Broş Çalışması Detayı, Pirinç Astar, Kuru boya kalemleri, Terebentin, Gesso, 2026.

SONUÇ

Metal üzerine renkli kalem uygulaması, takı sanatını salt bir “el sanatı/Zanaat” olmaktan çıkarıp “sanatsal” zeminine taşımaktadır. Teknik, düşük maliyetli ekipmanla yüksek estetik değer üretilmesine olanak tanırken, malzemenin uzun ömürlülüğü için doğru mühürleme protokollerinin uygulanması önemlidir. Yapılan denemeler, metalin soğuk yapısının sanatsal pigmentlerle birleştğinde mücevherin ifade gücünü artırdığını ve tasarımcıya geniş bir hareket

alanı sağladığını ortaya koymuştur. Bunun yanı sıra çalışma alanının sağladığı özgürlük ve özgünlük sanatçı/tasarımcının uygulama sürecinde neler yapabileceğine dair merak duygusunu tetikleyerek deneme sürecinde yapmak istediği uygulamamanın pek çok farklı varyasyonunu çalışabilme olanağı tanıdığı görülmüştür.

KAYNAKLAR

Hettmansperger, M. (2012) *Heat, Color, Set & Fire: Surface Effects for Metal Jewelry*, NewYork, Lark Crafts.

O'Brien, R. (2017) *Colored Pencil on Copper Jewelry*, Stackpole Books

Öner, İ. (2020). Takı Sanatında Çağdaş Yaklaşımlar. *Yüksek Lisans Tezi*, Yakın Doğu Üniversitesi Sosyal Bilimler Enstitüsü, Sanat ve Tasarım Anasanat Dalı, Lefkoşa.

İNTERNET KAYNAKÇASI

URL 1: Kullberg, A. (2017). Colored Pencil on Copper. Who Knew!? *Ann Kullberg* <https://annkullberg.com/blogs/ann-muses/colored-pencil-on-copper-who-knew> Erişim Tarihi: 04 Ocak 2026.

URL 2: Anonim. (t.y.). Colored Pencil on Metal Clay. AMCAW. <https://amcaw.org/learning-center/colored-pencil-on-metal-clay/> Erişim Tarihi: 04 Ocak 2026.

GÖRSEL KAYNAKAÇA

Görsel 1: Deb Karashi, Metal Üzerine Renklendirme 1. <https://debkarash.wordpress.com/wp-content/uploads/2010/05/offering-72dpi.jpg> Erişim Tarihi: 28.12.2025.

Görsel 2: Deb Karashi, Metal Üzerine Renklendirme 2. <https://debkarash.wordpress.com/wp-content/uploads/2010/05/stitched-brooch-72.jpg>, Erişim Tarihi: 28.12.2025.

Görsel 3: Roxan O'Brien, Metal Üzerine Renklendirme 1. https://www.facebook.com/photo/?fbid=10238997_637550166&set=a.1283510138624 Erişim Tarihi: 28.12.2025.

Görsel 4: Roxan O'Brien, Metal Üzerine Renklendirme 2. <https://www.facebook.com/share/1Bv3VN6RSX/> Erişim Tarihi: 28.12.2025.

Görsel 5: Mary Karg, Metal Üzerine Renklendirme 1. <https://www.marykargdesigns.com/?lightbox=dataItem-mhxq74972> Erişim Tarihi: 28.12.2025.

Görsel 6: Mary Karg, Metal Üzerine Renklendirme 2. <https://www.marykargdesigns.com/?lightbox=dataItem-mhxq74973> Erişim Tarihi: 28.12.2025.

Görsel 7: Anja Tverdokhlebova, Metal Üzerine Renklendirme 1. <https://breadcrumbscraft.com/brooches/tproduct/236567677-699689327902brassbroochestransformer-lets-swing> Erişim Tarihi:28.12.2025.

Görsel 8: Anja Tverdokhlebova, Metal Üzerine Renklendirme 2. <https://breadcrumbscraft.com/brooches/tproduct/239267244-946901606411-brass-brooch-transformer-from-the-life-o> Erişim Tarihi:28.12.2025.

Görsel 9: Anna Krof, Metal Üzerine Renklendirme 1. <https://www.instagram.com/p/CPczI63JpAP/> Erişim Tarihi:28.12.2025.

Görsel 10: Anna Krof, Metal Üzerine Renklendirme 2. https://www.instagram.com/p/DJghJh3M1qv/?img_index=1 Erişim Tarihi:28.12.2025.

Görsel 11: Jan Fagan, Metal Üzerine Renklendirme. <https://janfaganart.com/news-workshops/> Erişim Tarihi:28.12.2025.

Görsel 12: Julia Rai, Boncuk-Bileklik, Metal Üzerine Renklendirme, <https://amcaw.org/learning-center/colored-pencil-on-metal-clay/> Erişim Tarihi:28.12.2025.

Görsel 13: Çimen Bayburtlu, "Deneme I", 2022.

Görsel 14: Çimen Bayburtlu, "Deneme II", 2022.

INTERNATIONAL TOPKAPI CONGRESS VI

- Görsel 15:** Metalin Üzerine Gesso Sürülmesi. Yağcı, G. Arşivi, 2026.
- Görsel 16:** Metalin Üzerine Ana Hat Çizimi. Yağcı, G. Arşivi, 2026.
- Görsel 17:** Metal Yüzeyi Yağ Bazlı Kalemle Boya İşlemi Denemesi 1. Yağcı, G. Arşivi, 2026.
- Görsel 18:** Boyama Sonrası Terabentin Uygulaması 1. Yağcı, G. Arşivi, 2026.
- Görsel 19:** İşlem Tekrarları 1. Yağcı, G. Arşivi, 2026.
- Görsel 20:** Uygulamalar Sonucundaki Son Boya Katmanı 1. Yağcı, G. Arşivi, 2026.
- Görsel 21:** Metal Yüzeyi Yağ Bazlı Kalemle Boya İşlemi Denemesi 2. Yağcı, G. Arşivi, 2026.
- Görsel 22:** Boyama Sonrası Terabentin Uygulaması 2. Yağcı, G. Arşivi, 2026.
- Görsel 23:** İşlem Tekrarları 2. Yağcı, G. Arşivi, 2026.
- Görsel 24:** Uygulamalar Sonucundaki Son Boya Katmanı 2. Yağcı, G. Arşivi, 2026.
- Görsel 25:** Metal Yüzeyi Yağ Bazlı Kalemle Boya İşlemi Denemesi 3. Yağcı, G. Arşivi, 2026.
- Görsel 26:** Boyama Sonrası Terabentin Uygulaması 3. Yağcı, G. Arşivi, 2026.
- Görsel 27:** İşlem Tekrarları 3. Yağcı, G. Arşivi, 2026.
- Görsel 28:** Uygulamalar Sonucundaki Son Boya Katmanı 3. Yağcı, G. Arşivi, 2026.
- Görsel 29:** Metal Yüzeyi Yağ Bazlı Kalemle Boya İşlemi Denemesi 4. Yağcı, G. Arşivi, 2026.
- Görsel 30:** Boyama Sonrası Terabentin Uygulaması 4. Yağcı, G. Arşivi, 2026.
- Görsel 31:** İşlem Tekrarları 4. Yağcı, G. Arşivi, 2026.
- Görsel 32:** Uygulamalar Sonucundaki Son Boya Katmanı 4. Yağcı, G. Arşivi, 2026.
- Görsel 33-36:** Metal Yüzeydeki Boyama İşlemlerinin Son Hali, Sabitleme İşlemi. Yağcı, G. Arşivi, 2026.
- Görsel 37:** Uygulama Sonucunda Üretilen Broş Çalışması, Yağcı, G. 2026.
- Görsel 38:** Uygulama Sonucunda Üretilen Broş Çalışması Detay, Yağcı, G. 2026.

**AKILLI ÜRETİM KAPSAMINDA CNC İŞLEME SÜREÇLERİNDE MAKİNE
ÖĞRENMESİ UYGULAMALARI**
MACHINE LEARNING APPLICATIONS IN CNC MACHINING PROCESSES WITHIN
THE SCOPE OF SMART MANUFACTURING

Hakan YURTKURAN

Dr. Öğr. Üyesi, Yozgat Bozok Üniversitesi Akdağmadeni Meslek Yüksekokulu Makine ve
Metal Teknolojileri Bölümü

ÖZET

Endüstri 4.0 yaklaşımıyla birlikte talaşlı imalat süreçlerinde veri odaklı yöntemlerin kullanımı hızla artmaktadır. Özellikle son yıllarda geniş bir çalışma alanı bulan makine öğrenmesi tabanlı yaklaşımlar CNC işleme operasyonlarında yüzey pürüzlülüğü ve enerji tüketimi gibi kritik çıktıları tahmin etmek amacıyla yaygın olarak araştırılmaktadır. Makine öğrenmesi deneysel çalışmalardan elde edilen sayısal verilerin analizinde yaygın olarak kullanılan etkili bir yöntem hâline gelmiştir. Bu bildiride CNC işleme süreçlerinde makine öğrenmesi uygulamalarına ilişkin güncel gelişmeler literatür temelli olarak ele alınmıştır.

Çalışmada son yıllarda yayımlanan araştırmalar incelenerek yapay sinir ağları (ANN), rastgele orman (Random Forest), k-en yakın komşu (KNN) ve topluluk (ensemble) öğrenme yöntemlerinin talaşlı imalattaki kullanım alanları değerlendirilmiştir. Literatürden elde edilen veriler geleneksel istatistiksel yöntemlere kıyasla makine öğrenmesi modellerinin daha yüksek ve güvenli tahmin doğruluğu sunduğunu göstermektedir. Ayrıca karmaşık parametre ilişkilerini daha etkin şekilde modelleyebilmektedir. Hibrit ve çoklu model yaklaşımlarının özellikle yüzey pürüzlülüğü ve enerji tüketimi tahmininde önce çıktığı görülmektedir.

Bu derleme çalışması makine öğrenmesi temelli yöntemlerin CNC işleme süreçlerindeki durumunu ve gelecekteki potansiyelini ortaya koymayı amaçlamaktadır. Araştırma sonucunda sunulan değerlendirmelerin akıllı üretim sistemlerinin geliştirilmesine katkı sağlayacağı ve araştırmacılar için güncel bir referans niteliği taşıdığı düşünülmektedir.

Anahtar Kelimeler: CNC İşleme, Makine Öğrenmesi, Akıllı Üretim, Yüzey Pürüzlülüğü Tahmini, Enerji Tüketimi

ABSTRACT

With the advent of Industry 4.0 the use of data-driven methods in machining processes is rapidly increasing. Machine learning-based approaches which have gained significant traction in recent years are being extensively researched to predict critical outputs such as surface roughness and energy consumption in CNC machining operations. Machine learning has become an effective method widely used in the analysis of numerical data obtained from experimental studies. This paper discusses recent developments in machine learning applications in CNC machining processes based on the literature.

The study evaluated the application areas of artificial neural networks (ANN), random forest, k-nearest neighbours (KNN) and ensemble learning methods in machining by reviewing research published in recent years. Data obtained from the literature indicates that machine learning models offer higher and more reliable prediction accuracy compared to traditional statistical methods. They are also able to model complex parameter relationships more effectively. Hybrid and multi-model approaches are particularly prominent in predicting surface roughness and energy consumption.

This compilation study aims to reveal the current status and future potential of machine learning-based methods in CNC machining processes. It is believed that the evaluations presented in the research results will contribute to the development of intelligent production systems and serve as a current reference for researchers.

Keywords: CNC Machining, Machine Learning, Smart Manufacturing, Surface Roughness Prediction, Energy Consumption

GİRİŞ

Endüstri 4.0 yaklaşımı ile imalat sektöründe dijitalleşme, otomasyon ve veri odaklı karar verme süreçleri ön plana çıkmıştır. Özellikle talaşlı imalat yöntemleri üretim süreçlerinin karmaşık yapısı ve çok sayıda parametrenin eş zamanlı olarak etkili olması nedeniyle akıllı üretim uygulamalarına en fazla ihtiyaç duyulan alanlardan biri hâline gelmiştir. CNC (Computer Numerical Control) tezgâhları yüksek hassasiyet, tekrarlanabilirlik ve otomasyon kabiliyeti sayesinde modern imalat sistemlerinin temelini oluşturmaktadır.

CNC işleme süreçlerinde yüzey pürüzlülüğü, kesme kuvvetleri, takım aşınması ve enerji tüketimi gibi çıktı parametrelerinden oluşmaktadır. Kesme hızı, ilerleme miktarı, talaş derinliği, takım geometrisi ve iş parçası malzemesi gibi çok sayıda girdi parametresine bağlı olarak da bu çıktı parametreleri değişmektedir. Bu parametreler arasındaki doğrusal olmayan ve karmaşık ilişkilerin geleneksel istatistiksel yöntemlerle doğru bir şekilde modellenmesi çoğu zaman zor olmaktadır. Bu durum üretim kalitesinin artırılması ve süreçlerin optimize edilmesi açısından yeni yaklaşımların gerekliliğini ortaya koymaktadır.

Son yıllarda makine öğrenmesi (Machine Learning, ML) tabanlı yöntemler deneysel ve üretim süreçlerinden elde edilen büyük hacimli verilerin analizinde güçlü bir araç olarak öne çıkmaktadır. Makine öğrenmesi algoritmaları önceden açık bir matematiksel model tanımlamaya gerek duymadan veriler içerisindeki gizli örüntüleri öğrenebilmekte ve karmaşık sistemlerin davranışlarını yüksek doğrulukla tahmin edebilmektedir. Bu özellikleri sayesinde ML yöntemleri CNC işleme süreçlerinde yüzey pürüzlülüğü ve enerji tüketimi gibi kritik çıktıların kestiriminde yaygın olarak kullanılmaktadır.

Literatürde yapılan çalışmalar incelendiğinde yapay sinir ağları, karar ağaçları, rastgele orman, k-en yakın komşu ve topluluk öğrenme yöntemlerinin talaşlı imalat süreçlerinde başarılı sonuçlar verdiği görülmektedir [1,2]. Özellikle hibrit ve çoklu model yaklaşımlarının tekil modellere kıyasla daha yüksek tahmin doğruluğu sağladığı rapor edilmektedir [3]. Bu durum makine öğrenmesinin CNC işleme süreçlerinde hem akademik hem de endüstriyel açıdan önemli bir potansiyele sahip olduğunu göstermektedir.

Bu çalışmada CNC işleme süreçlerinde makine öğrenmesi uygulamalarına ilişkin güncel literatür incelenerek kullanılan yöntemler tahmin edilen çıktı parametreleri ve elde edilen sonuçlar bütüncül bir bakış açısıyla ele alınmıştır. Çalışmanın amacı makine öğrenmesi temelli yaklaşımların talaşlı imalattaki durumunu ortaya koymak ve akıllı üretim sistemlerinin geliştirilmesine yönelik bir referans çerçevesi sunmaktır.

CNC İŞLEME SÜREÇLERİNDE TEMEL PARAMETRELER VE ÇIKTILAR

CNC işleme süreçlerinde elde edilen ürün kalitesi, üretim verimliliği ve enerji tüketimi; çok sayıda girdi ve çıktı parametresinin birbiriyle etkileşimi sonucunda ortaya çıkmaktadır. Bu parametrelerin doğru tanımlanması ve etkilerinin anlaşılması hem deneysel çalışmaların tasarımı hem de makine öğrenmesi modellerinin başarımı açısından kritik öneme sahiptir.

Girdi Parametreleri

CNC işleme operasyonlarında en yaygın kullanılan girdi parametreleri kesme hızı, ilerleme miktarı ve kesme derinliğidir. Kesme hızı takımın iş parçası yüzeyi üzerindeki bağıl hareket hızını ifade etmekte olup yüzey kalitesi, takım aşınması ve enerji tüketimi üzerinde doğrudan etkilidir. İlerleme miktarı takımın bir devirde veya birim zamanda iş parçası üzerinde aldığı mesafe olarak tanımlanmakta ve özellikle yüzey pürüzlülüğü üzerinde belirleyici bir rol oynamaktadır. Kesme derinliği ise kaldırılan malzeme miktarını etkileyerek kesme kuvvetleri ve güç tüketimi ile yakından ilişkilidir. Bu temel parametrelerin yanı sıra takım geometrisi (uç yarıçapı, helis açısı, kaplama türü), kesici takım malzemesi, iş parçası malzemesi ve

soğutma/yağlama koşulları da CNC işleme performansını önemli ölçüde etkilemektedir. Özellikle farklı malzemelerin işlenmesi sırasında bu parametrelerin etkileri doğrusal olmayan bir yapı sergilemekte ve parametreler arasındaki etkileşimler karmaşık hâle gelmektedir.

Çıktı Parametreleri

CNC işleme süreçlerinde en sık analiz edilen çıktı parametrelerinden biri yüzey pürüzlülüğüdür. Yüzey pürüzlülüğü ürünün fonksiyonel performansı, aşınma direnci ve montaj kalitesi açısından kritik bir kalite göstergesidir. İlerleme miktarı kesme hızı ve takım geometrisi gibi parametrelerdeki küçük değişimler dahi yüzey pürüzlülüğü değerlerinde önemli farklılıklara yol açabilmektedir. Enerji tüketimi günümüzde sürdürülebilir üretim ve enerji verimliliği kavramlarının önem kazanmasıyla birlikte CNC işleme çalışmalarında giderek daha fazla incelenen bir diğer önemli çıktı parametresidir. İşleme sırasında tüketilen enerji miktarı; kesme parametreleri, makine yapısı ve kesme süresi gibi faktörlere bağlı olarak değişmektedir. Enerji tüketiminin doğru bir şekilde tahmin edilmesi hem üretim maliyetlerinin düşürülmesi hem de çevresel etkilerin azaltılması açısından büyük önem taşımaktadır. Bunlara ek olarak kesme kuvvetleri, takım aşınması, titreşim ve işlem süresi gibi çıktılar da literatürde sıklıkla ele alınmaktadır. Bu çıktıların çoğu birbirleriyle ilişkili olup örneğin artan takım aşınması yüzey pürüzlülüğünü olumsuz etkileyebilmekte ve aynı zamanda enerji tüketimini artırabilmektedir.

Parametreler Arası İlişkilerin Karmaşıklığı

CNC işleme süreçlerinde girdi ve çıktı parametreleri arasındaki ilişkiler genellikle doğrusal olmayan bir yapıya sahiptir. Geleneksel regresyon ve istatistiksel yöntemler bu karmaşık ilişkileri modellemede sınırlı kalabilmektedir. Bu durum özellikle çok sayıda parametrenin eş zamanlı olarak değiştiği durumlarda tahmin doğruluğunu düşürmektedir. Makine öğrenmesi tabanlı yaklaşımlar bu karmaşık ve çok boyutlu veri yapılarında parametreler arasındaki gizli ilişkileri öğrenebilme yeteneğine sahiptir. Bu nedenle CNC işleme süreçlerinde girdi-çıktı ilişkilerinin modellenmesinde makine öğrenmesi yöntemleri güçlü bir alternatif olarak öne çıkmaktadır.

MAKİNE ÖĞRENMESİNE GENEL BAKIŞ

Makine öğrenmesi bilgisayar sistemlerinin açık bir şekilde programlanmadan verilerden öğrenmesini ve karar verebilmesini sağlayan yapay zekâ alt disiplinidir [4–6]. Son yıllarda artan hesaplama gücü, sensör teknolojilerindeki gelişmeler ve büyük veri altyapıları sayesinde makine öğrenmesi yöntemleri imalat mühendisliği alanında yaygın olarak kullanılmaya başlanmıştır. CNC işleme süreçleri çok sayıda girdi ve çıktı parametresi içermektedir. Bu parametreler arasındaki ilişkilerin doğrusal olmayan bir yapıya sahip olması dolayısıyla makine öğrenmesi uygulamaları için uygun bir çalışma alanı sunmaktadır.

Makine Öğrenmesi Türleri

Makine öğrenmesi yöntemleri genel olarak denetimli öğrenme, denetimsiz öğrenme ve yarı denetimli öğrenme olmak üzere üç ana grupta sınıflandırılmaktadır [7]. Denetimli öğrenme yöntemlerinde model girdi parametreleri ile bunlara karşılık gelen çıktı değerlerini içeren etiketli veri setleri kullanılarak eğitilmektedir. CNC işleme süreçlerinde yüzey pürüzlülüğü, enerji tüketimi ve kesme kuvvetleri gibi nicel çıktıların tahmin edilmesi amacıyla literatürde en yaygın kullanılan yaklaşım denetimli öğrenmedir.


Denetimsiz öğrenme yöntemleri veri setlerinde önceden tanımlanmış bir çıktı etiketi olmaksızın veriler arasındaki benzerlikleri ve örüntüleri ortaya çıkarmayı amaçlamaktadır. Bu yöntemler CNC işleme verilerinin kümelenmesi, anomali tespiti ve süreç izleme uygulamalarında kullanılmaktadır. Yarı denetimli öğrenme ise sınırlı sayıda etiketli veri ile daha büyük hacimde etiketsiz verinin birlikte kullanıldığı bir yaklaşımdır ve endüstriyel ortamlarda veri etiketleme maliyetlerinin yüksek olması nedeniyle potansiyel bir çözüm sunmaktadır.

CNC İşleme Süreçlerinde Makine Öğrenmesi İş Akışı

CNC işleme süreçlerinde makine öğrenmesi uygulamaları belirli bir iş akışı çerçevesinde gerçekleştirilmektedir. Bu iş akışı genel olarak veri toplama, veri ön işleme, model eğitimi,

model doğrulama ve tahmin aşamalarından oluşmaktadır. Sensörler ve deneysel çalışmalar aracılığıyla elde edilen kesme parametreleri ve çıktı verileri modelleme öncesinde normalize edilmekte ve uygun veri setlerine ayrılmaktadır.

Şekil 1’de CNC işleme süreçlerinde makine öğrenmesi tabanlı bir tahmin sisteminin genel iş akışı şematik olarak sunulmuştur. Bu yapı içerisinde girdi parametreleri makine öğrenmesi modeline aktarılmakta ve model çıktısı olarak yüzey pürüzlülüğü veya enerji tüketimi gibi performans göstergeleri elde edilmektedir.



Şekil 1. CNC işleme süreçlerinde makine öğrenmesi tabanlı tahmin iş akışı

Model Performansının Değerlendirilmesi

Makine öğrenmesi modellerinin başarımlı tahmin edilen değerler ile deneysel veya gerçek ölçüm sonuçları arasındaki farklar kullanılarak değerlendirilmektedir. CNC işleme uygulamalarında en yaygın kullanılan performans metrikleri belirleme katsayısı (R^2), ortalama karesel hata (RMSE) ve ortalama mutlak hata (MAE) olarak öne çıkmaktadır. Yüksek R^2 ve düşük hata değerleri modelin tahmin kabiliyetinin güçlü olduğunu göstermektedir.

Literatürde yapılan çalışmalar uygun şekilde eğitilen makine öğrenmesi modellerinin geleneksel regresyon yöntemlerine kıyasla daha yüksek tahmin doğruluğu sunduğunu ortaya koymaktadır [8,9]. Bu durum, makine öğrenmesinin CNC işleme süreçlerinin modellenmesinde ve akıllı üretim sistemlerinin geliştirilmesinde etkili bir araç olduğunu göstermektedir.

CNC İŞLEME SÜREÇLERİNDE KULLANILAN MAKİNE ÖĞRENMESİ YÖNTEMLERİ

CNC işleme süreçlerinde makine öğrenmesi uygulamaları farklı algoritmaların girdi-çıkı ilişkilerini modelleme kabiliyetlerine bağlı olarak çeşitlilik göstermektedir. Literatürde en yaygın kullanılan yöntemler ise yapay sinir ağları, ağaç tabanlı algoritmalar, örnek tabanlı yöntemler ve topluluk öğrenme yaklaşımlarıdır. Bu bölümde CNC işleme alanında öne çıkan makine öğrenmesi yöntemleri ve uygulama alanları özetlenmiştir.

Yapay Sinir Ağları (Artificial Neural Networks – ANN)

Yapay sinir ağları insan beynindeki nöronların çalışma prensibinden esinlenerek geliştirilen ve doğrusal olmayan sistemlerin modellenmesinde başarılı sonuçlar veren makine öğrenmesi yöntemleriydi [10]. ANN modelleri giriş, gizli ve çıkış katmanlarından oluşmakta olup katmanlar arasındaki bağlantılar ağırlıklar aracılığıyla sağlanmaktadır. Bu yapı sayesinde çok sayıda girdi parametresi ile karmaşık ilişkiler etkin bir şekilde öğrenilebilmektedir.

CNC işleme süreçlerinde ANN modelleri en yaygın olarak yüzey pürüzlülüğü, kesme kuvvetleri ve enerji tüketimi tahmininde kullanılmaktadır. Literatürde yapılan çalışmalarda uygun şekilde eğitilen ANN modellerinin yüksek belirleme katsayısı (R^2) değerleri sunduğu ve deneysel sonuçlara oldukça yakın tahminler gerçekleştirdiği rapor edilmektedir. Bununla birlikte ağ yapısının ve hiperparametrelerin doğru seçilmemesi durumunda aşırı öğrenme (overfitting) problemi ortaya çıkabilmektedir.

Rastgele Orman (Random Forest)

Rastgele orman algoritması çok sayıda karar ağacının bir araya getirilmesiyle oluşturulan topluluk tabanlı bir öğrenme yöntemidir [11]. Her bir karar ağacı veri setinin rastgele alt kümeleri üzerinde eğitilmekte ve nihai tahmin ağaçlarının çıktıların ortalaması veya çoğunluk

oyu ile belirlenmektedir. Bu yaklaşım tekil karar ağaçlarına kıyasla daha kararlı ve genellenebilir sonuçlar sunmaktadır.

CNC işleme uygulamalarında rastgele orman algoritması yüzey pürüzlülüğü, takım aşınması ve enerji tüketimi gibi çıktıların tahmininde sıklıkla tercih edilmektedir. Literatürde özellikle sınırlı veri setleriyle çalışılan durumlarda rastgele orman yönteminin yüksek doğruluk ve düşük hata değerleri sağladığı bildirilmektedir [12,13]. Ayrıca değişken önem analizine imkân tanınması hangi kesme parametrelerinin çıktılar üzerinde daha etkili olduğunun belirlenmesine katkı sağlamaktadır.

k-En Yakın Komşu (k-Nearest Neighbours – KNN)

k-en yakın komşu algoritması örnek tabanlı ve sezgisel bir makine öğrenmesi yöntemidir [14,15]. Bu yöntemde yeni bir veri noktasının çıktısı eğitim veri setinde yer alan en yakın k adet komşunun çıktı değerlerine göre belirlenmektedir. KNN algoritması model eğitimi gerektirmemesi ve basit yapısı nedeniyle uygulaması kolay bir yöntemdir.

CNC işleme süreçlerinde KNN algoritması özellikle yüzey pürüzlülüğü tahmini gibi problemlerde kullanılmıştır. Ancak veri setinin boyutunun artması durumunda hesaplama maliyetinin yükselmesi ve gürültülü verilere karşı hassas olması yöntemin başlıca sınırlamaları arasında yer almaktadır. Bu nedenle KNN genellikle diğer makine öğrenmesi yöntemleriyle karşılaştırma amacıyla kullanılmaktadır.

Topluluk (Ensemble) ve Hibrit Yaklaşımlar

Topluluk öğrenme yöntemleri birden fazla makine öğrenmesi modelinin birlikte kullanılarak tekil modellere kıyasla daha yüksek tahmin doğruluğu elde edilmesini amaçlamaktadır. Bu yaklaşımlar farklı modellerin güçlü yönlerinden faydalanarak zayıf yönlerini telafi etmektedir. CNC işleme literatüründe ANN, rastgele orman ve destek vektör makineleri gibi yöntemlerin bir arada kullanıldığı hibrit modeller dikkat çekmektedir.

Yapılan çalışmalarda ensemble ve hibrit yaklaşımların özellikle yüzey pürüzlülüğü ve enerji tüketimi tahmininde daha düşük hata değerleri sunduğu rapor edilmektedir [16,17] Bu durum CNC işleme süreçlerinin çok değişkenli ve doğrusal olmayan yapısı göz önünde bulundurulduğunda çoklu model kullanımının önemli bir avantaj sağladığını göstermektedir. Bu bölümde ele alınan yöntemlerin karşılaştırmalı bir özeti Tablo 1’de sunulmuştur. Söz konusu tablo yöntemlerin temel özellikleri, avantajları ve CNC işleme uygulamalarındaki kullanım alanlarını özetlemektedir.

Tablo 1. CNC işleme süreçlerinde kullanılan başlıca makine öğrenmesi yöntemlerinin karşılaştırılması

	Temel Özellik	CNC İşleme Uygulamaları	Avantajları	Sınırlamaları
Yapay Sinir Ağları (ANN)	Çok katmanlı, doğrusal olmayan modelleme	Yüzey pürüzlülüğü, enerji tüketimi, kesme kuvvetleri	Yüksek tahmin doğruluğu, karmaşık ilişkileri öğrenebilme	Hiperparametre seçimine duyarlı, aşırı öğrenme riski
Rastgele Orman (Random Forest)	Ağaç tabanlı topluluk öğrenme	Yüzey pürüzlülüğü, takım aşınması, enerji tüketimi	Kararlı sonuçlar, değişken önem analizi	Model yapısı karmaşık, yorumlanabilirlik sınırlı
k-En Yakın Komşu (KNN)	Örnek tabanlı, mesafe ölçümüne dayalı	Yüzey pürüzlülüğü tahmini	Basit yapı, eğitim gerektirmez	Büyük veri setlerinde yüksek hesaplama maliyeti
Topluluk / Hibrit Modeller	Birden fazla modelin birlikte kullanımı	Yüzey pürüzlülüğü ve enerji tüketimi tahmini	Daha düşük hata, yüksek genelleme kabiliyeti	Hesaplama maliyeti ve model karmaşıklığı

LİTERATÜR TABANLI KARŞILAŞTIRMALI DEĞERLENDİRME

CNC işleme süreçlerinin modellenmesi ve performans çıktılarının tahmin edilmesinde geleneksel istatistiksel yöntemler uzun yıllar boyunca yaygın olarak kullanılmıştır. Regresyon analizi, varyans analizi (ANOVA) ve deney tasarımı (DoE) gibi yaklaşımlar kesme parametrelerinin çıktı üzerindeki etkilerini incelemede önemli katkılar sağlamıştır. Ancak CNC işleme süreçlerinde parametreler arasındaki ilişkilerin çoğunlukla doğrusal olmayan bir yapıya sahip olması bu yöntemlerin tahmin doğruluğunu sınırlayan bir faktör olarak öne çıkmaktadır. Makine öğrenmesi tabanlı yöntemler, doğrusal olmayan ve çok değişkenli veri yapılarında yüksek tahmin başarımları sunmaları nedeniyle literatürde geleneksel yöntemlere güçlü bir alternatif olarak değerlendirilmektedir. Yapılan çalışmalarda özellikle yüzey pürüzlülüğü ve enerji tüketimi tahmininde makine öğrenmesi modellerinin daha yüksek belirleme katsayısı (R^2) ve daha düşük hata değerleri sağladığı rapor edilmiştir [18–20]. Bu durum veri içerisindeki karmaşık örüntülerin makine öğrenmesi algoritmaları tarafından daha etkin bir şekilde öğrenilebildiğini göstermektedir.

Literatürde ANN rastgele orman ve ensemble tabanlı yöntemlerin karşılaştırıldığı çalışmalarda tekil modellere kıyasla topluluk öğrenme yaklaşımlarının daha kararlı ve genellebilir sonuçlar sunduğu görülmektedir [21]. Özellikle farklı kesme koşulları ve malzeme türleri altında yapılan deneylerde ensemble modellerin tahmin performansının daha az dalgalanma gösterdiği belirtilmektedir [22]. Bu sonuçlar CNC işleme süreçlerinin değişken doğası göz önünde bulundurulduğunda çoklu model kullanımının önemli bir avantaj sağladığını ortaya koymaktadır.

Bununla birlikte makine öğrenmesi yöntemlerinin başarımları doğrudan veri kalitesi, veri miktarı ve deneysel tasarım ile ilişkilidir. Yetersiz veya dengesiz veri setleri ile eğitilen modellerde aşırı öğrenme ve genelleme problemleri ortaya çıkabilmektedir. Bu nedenle literatürde makine öğrenmesi modellerinin performansını artırmaya yönelik olarak uygun veri ön işleme adımlarının, çapraz doğrulama tekniklerinin ve hiperparametre optimizasyonunun önemi sıklıkla vurgulanmaktadır [23,24]. Genel olarak değerlendirildiğinde literatürdeki bulgular makine öğrenmesi tabanlı yaklaşımların CNC işleme süreçlerinde hem tahmin doğruluğu hem de esneklik açısından geleneksel yöntemlere üstünlük sağladığını göstermektedir. Fakat bu yöntemlerin endüstriyel uygulamalarda etkin bir şekilde kullanılabilmesi için model karmaşıklığı, hesaplama maliyeti ve yorumlanabilirlik gibi faktörlerin de dikkate alınması gerekmektedir.

TARTIŞMA

Bu çalışmada ele alınan literatür bulguları, makine öğrenmesi tabanlı yaklaşımların CNC işleme süreçlerinin modellenmesinde önemli avantajlar sunduğunu ortaya koymaktadır. Özellikle yüzey pürüzlülüğü ve enerji tüketimi gibi çıktı parametrelerinin tahmininde, makine öğrenmesi yöntemlerinin geleneksel istatistiksel modellere kıyasla daha yüksek doğruluk sağladığı görülmektedir. Bunun temel nedeni, CNC işleme süreçlerinde girdi ve çıktı parametreleri arasındaki ilişkilerin çoğunlukla doğrusal olmayan ve karmaşık bir yapıya sahip olmasıdır.

Yapay sinir ağları ve ağaç tabanlı yöntemler, bu karmaşık ilişkileri modelleyebilme yetenekleri sayesinde literatürde sıklıkla tercih edilmiştir [25]. Ancak her bir makine öğrenmesi yönteminin performansı; veri setinin büyüklüğü, deneysel tasarımın kapsamı ve seçilen girdi parametrelerine bağlı olarak değişkenlik göstermektedir. Bu durum, tek bir modelin tüm CNC işleme problemleri için en iyi çözüm olmadığını, model seçiminin problem özelinde yapılması gerektiğini göstermektedir.

Topluluk ve hibrit yaklaşımların, farklı model yapılarını bir arada kullanarak daha kararlı ve genellebilir sonuçlar sunduğu literatür çalışmalarıyla desteklenmektedir. Bununla birlikte, bu yöntemlerin artan hesaplama maliyeti ve model karmaşıklığı, özellikle gerçek zamanlı

endüstriyel uygulamalarda dikkate alınması gereken sınırlamalar arasında yer almaktadır. Bu nedenle model doğruluğu ile hesaplama maliyeti arasındaki denge, uygulamaya yönelik çalışmalarda önemli bir kriter olarak değerlendirilmelidir.

Ayrıca literatürdeki birçok çalışmada veri ön işleme adımlarının ve hiperparametre optimizasyonunun model performansı üzerindeki etkisi vurgulanmaktadır. Yetersiz veri setleri veya uygun olmayan model ayarları, makine öğrenmesi yöntemlerinin potansiyel avantajlarını sınırlayabilmektedir. Bu bağlamda, CNC işleme süreçlerinde makine öğrenmesi uygulamalarının başarılı olabilmesi için deneysel verilerin sistematik ve tekrarlanabilir bir şekilde elde edilmesi büyük önem taşımaktadır.

Genel olarak tartışma sonuçları, makine öğrenmesi yöntemlerinin CNC işleme süreçlerinde güçlü bir araç olduğunu göstermektedir. Ancak bu yöntemlerin endüstriyel ölçekte yaygınlaştırılabilmesi için model yorumlanabilirliği, veri güvenilirliği ve sistem entegrasyonu gibi konuların gelecekteki çalışmalarda daha ayrıntılı ele alınması gerekmektedir.

GELECEK ÇALIŞMALAR

Bu çalışma kapsamında incelenen literatür ve elde edilen değerlendirmeler doğrultusunda CNC işleme süreçlerinde makine öğrenmesi uygulamalarına yönelik gelecekte yapılabilecek çalışmalar için bazı öneriler sunulmaktadır. Bu öneriler hem akademik araştırmaların derinleştirilmesi hem de endüstriyel uygulamaların geliştirilmesi açısından yol gösterici niteliktedir.

İlk olarak derin öğrenme tabanlı yöntemlerin CNC işleme süreçlerine entegrasyonu gelecekteki çalışmalar için önemli bir araştırma alanı olarak öne çıkmaktadır. Özellikle çok katmanlı derin sinir ağları ve evrimsel sinir ağlarının yüksek boyutlu sensör verilerinin analizinde daha yüksek tahmin doğruluğu sağlayabileceği değerlendirilmektedir.

İkinci olarak gerçek zamanlı veri toplama ve kestirim sistemlerinin geliştirilmesi önemli bir potansiyel sunmaktadır. CNC tezgâhlarına entegre edilecek sensörler aracılığıyla elde edilen anlık verilerin makine öğrenmesi modelleri ile eş zamanlı olarak işlenmesi, süreç izleme ve adaptif kontrol uygulamalarına katkı sağlayacaktır.

Üçüncü olarak enerji verimliliği ve sürdürülebilir üretim odaklı çalışmaların artırılması gerekmektedir. Makine öğrenmesi yöntemlerinin enerji tüketimi tahmininin yanı sıra enerji optimizasyonu ve karbon ayak izinin azaltılmasına yönelik karar destek sistemlerinde kullanılması akıllı üretim hedefleriyle uyumlu sonuçlar doğuracaktır. Ayrıca hibrit ve çoklu model yaklaşımlarının farklı malzeme türleri ve işleme koşulları altında sistematik olarak karşılaştırıldığı kapsamlı deneysel çalışmaların literatüre önemli katkılar sağlayacağı düşünülmektedir. Bu tür çalışmalar hangi model veya model kombinasyonunun hangi koşullarda daha başarılı olduğunu ortaya koyacaktır.

Son olarak makine öğrenmesi modellerinin yorumlanabilirliğinin artırılmasına yönelik araştırmaların önemi giderek artmaktadır. Açıklanabilir yapay zekâ (Explainable AI) yaklaşımlarının CNC işleme süreçlerine uyarlanması endüstriyel kullanıcıların modellere olan güvenini artıracak ve karar verme süreçlerini destekleyecektir.

SONUÇLAR

Bu çalışmada akıllı üretim yaklaşımı kapsamında CNC işleme süreçlerinde makine öğrenmesi uygulamalarına yönelik güncel literatür kapsamlı bir şekilde incelenmiş ve farklı yöntemlerin kullanım alanları değerlendirilmiştir. Yapılan incelemeler CNC işleme süreçlerinde yüzey pürüzlülüğü ve enerji tüketimi gibi kritik çıktı parametrelerinin tahmininde makine öğrenmesi tabanlı yaklaşımların önemli avantajlar sunduğunu ortaya koymaktadır.

Literatürden elde edilen bulgular, yapay sinir ağları, rastgele orman ve topluluk öğrenme yöntemlerinin geleneksel istatistiksel modellere kıyasla daha yüksek tahmin doğruluğu sağladığını göstermektedir. Özellikle doğrusal olmayan ve çok değişkenli parametre ilişkilerinin söz konusu olduğu CNC işleme uygulamalarında makine öğrenmesi yöntemlerinin bu karmaşık yapıları daha etkin bir şekilde modelleyebildiği görülmektedir.

Çalışmada ayrıca tekil modellere kıyasla hibrit ve ensemble yaklaşımlarının daha kararlı ve genellenebilir sonuçlar sunduğu vurgulanmıştır. Bununla birlikte model başarımının doğrudan veri kalitesi, deneysel tasarım ve uygun hiperparametre seçimine bağlı olduğu sonucuna ulaşılmıştır. Bu durum makine öğrenmesi uygulamalarında yalnızca algoritma seçiminin değil veri hazırlama sürecinin de kritik bir öneme sahip olduğunu göstermektedir.

Elde edilen değerlendirmeler makine öğrenmesi temelli yöntemlerin CNC işleme süreçlerinin modellenmesi, izlenmesi ve optimize edilmesinde etkili bir araç olduğunu ortaya koymaktadır. Bununla beraber bu yöntemlerin endüstriyel ölçekte yaygın olarak kullanılabilmesi için model yorumlanabilirliği, hesaplama maliyeti ve sistem entegrasyonu gibi konuların dikkate alınması gerekmektedir.

Sonuç olarak bu çalışmanın CNC işleme süreçlerinde makine öğrenmesi uygulamalarına ilişkin güncel bir bakış açısı sunduğu ve gelecekte yapılacak akademik ve endüstriyel çalışmalara yol gösterici bir referans niteliği taşıdığı değerlendirilmektedir.

KAYNAKLAR

- [1] F. Aggogeri, N. Pellegrini, F.L. Tagliani, Recent Advances on Machine Learning Applications in Machining Processes, Appl. Sci. 11 (2021) 8764. <https://doi.org/10.3390/app11188764>.
- [2] B. Sarker, S. Chakraborty, R. Çep, K. Kalita, Development of optimized ensemble machine learning-based prediction models for wire electrical discharge machining processes, Sci. Rep. 14 (2024) 23299. <https://doi.org/10.1038/s41598-024-74291-x>.
- [3] Z. Hajirahimi, M. Khashei, Hybrid structures in time series modeling and forecasting: A review, Eng. Appl. Artif. Intell. 86 (2019) 83–106. <https://doi.org/https://doi.org/10.1016/j.engappai.2019.08.018>.
- [4] N.N. Thilakarathne, M.S. Bakar, P.E. Abas, H. Yassin, A Cloud Enabled Crop Recommendation Platform for Machine Learning-Driven Precision Farming, Sensors 22 (2022) 6299. <https://doi.org/10.3390/s22166299>.
- [5] C. Janiesch, P. Zschech, K. Heinrich, Machine learning and deep learning, Electron. Mark. 31 (2021) 685–695. <https://doi.org/10.1007/s12525-021-00475-2>.
- [6] N. Kühl, M. Schemmer, M. Goutier, G. Satzger, Artificial intelligence and machine learning, Electron. Mark. 32 (2022) 2235–2244. <https://doi.org/10.1007/s12525-022-00598-0>.
- [7] J.E. van Engelen, H.H. Hoos, A survey on semi-supervised learning, Mach. Learn. 109 (2020) 373–440. <https://doi.org/10.1007/s10994-019-05855-6>.
- [8] R. Bhandary, B.K. Ghosh, Credit Card Default Prediction: An Empirical Analysis on Predictive Performance Using Statistical and Machine Learning Methods, J. Risk Financ. Manag. 18 (2025) 23. <https://doi.org/10.3390/jrfm18010023>.
- [9] F. Barboza, H. Kimura, E. Altman, Machine learning models and bankruptcy prediction, Expert Syst. Appl. 83 (2017) 405–417. <https://doi.org/https://doi.org/10.1016/j.eswa.2017.04.006>.
- [10] S. Shekhar, H. Xiong, Artificial Neural Network BT - Encyclopedia of GIS, in: S. Shekhar, H. Xiong (Eds.), Springer US, Boston, MA, 2008: p. 31. https://doi.org/10.1007/978-0-387-35973-1_72.
- [11] Xingyu Fu, Yingyue Chen, Jingru Yan, Yumin Chen, Feng Xu, BGRF: A broad granular random forest algorithm, J. Intell. Fuzzy Syst. 44 (2023) 8103–8117. <https://doi.org/10.3233/JIFS-223960>.
- [12] J.L. Speiser, M.E. Miller, J. Tooze, E. Ip, A comparison of random forest variable selection methods for classification prediction modeling, Expert Syst. Appl. 134 (2019) 93–101. <https://doi.org/https://doi.org/10.1016/j.eswa.2019.05.028>.
- [13] G. Biau, E. Scornet, A random forest guided tour, TEST 25 (2016) 197–227.

- <https://doi.org/10.1007/s11749-016-0481-7>.
- [14] S. Kang, k-Nearest Neighbor Learning with Graph Neural Networks, *Mathematics* 9 (2021) 830. <https://doi.org/10.3390/math9080830>.
 - [15] A.J. Gallego, J.R. Rico-Juan, J.J. Valero-Mas, Efficient k-nearest neighbor search based on clustering and adaptive k values, *Pattern Recognit.* 122 (2022) 108356. <https://doi.org/https://doi.org/10.1016/j.patcog.2021.108356>.
 - [16] C. Feng, M. Li, H. Guo, B. Qiu, J. Zhang, Energy efficiency identification and surface roughness prediction using cutting force signal for computer numerical controlled machine systems, *Sci. Rep.* 14 (2024) 19004. <https://doi.org/10.1038/s41598-024-69979-z>.
 - [17] C. Feng, E. Qin, W. Li, M. Li, J. Su, X. Xu, Energy consumption and surface roughness modelling for multi-objective optimisation of machining processes, *Int. J. Adv. Manuf. Technol.* 133 (2024) 5065–5087. <https://doi.org/10.1007/s00170-024-14043-3>.
 - [18] T. Khan, U. Khan, A. Khan, C. Mollan, I. Morkvenaite-Vilkonciene, V. Pandey, Data-Driven Digital Twin Framework for Predictive Maintenance of Smart Manufacturing Systems, *Machines* 13 (2025) 481. <https://doi.org/10.3390/machines13060481>.
 - [19] V. Dubey, A.K. Sharma, D.Y. Pimenov, Prediction of Surface Roughness Using Machine Learning Approach in MQL Turning of AISI 304 Steel by Varying Nanoparticle Size in the Cutting Fluid, *Lubricants* 10 (2022) 81. <https://doi.org/10.3390/lubricants10050081>.
 - [20] D. Rodić, M. Sekulić, B. Savković, M. Madić, M. Trifunović, Integration of RSM and Machine Learning for Accurate Prediction of Surface Roughness in Laser Processing, *Appl. Sci.* 15 (2025) 7064. <https://doi.org/10.3390/app15137064>.
 - [21] A. Alqahtani, M.I. Shah, A. Aldrees, M.F. Javed, Comparative Assessment of Individual and Ensemble Machine Learning Models for Efficient Analysis of River Water Quality, *Sustainability* 14 (2022) 1183. <https://doi.org/10.3390/su14031183>.
 - [22] S.-Y. Lin, C.-J. Hsieh, Construction of a Cutting-Tool Wear Prediction Model through Ensemble Learning, *Appl. Sci.* 14 (2024) 3811. <https://doi.org/10.3390/app14093811>.
 - [23] R.D. Rajesh, Y.N.K. Kuppuri, P.R. Peter, A.S.S. Reddy, J.J. Sonia, Enhancing Obesity Prediction: Evaluating the Role of Data Preprocessing in Machine Learning Models, in: 2025 Int. Conf. Comput. Robot. Test. Eng. Eval., 2025: pp. 1–6. <https://doi.org/10.1109/ICCRTEE64519.2025.11053002>.
 - [24] S. Hanifi, A. Cammarono, H. Zare-Behtash, Advanced hyperparameter optimization of deep learning models for wind power prediction, *Renew. Energy* 221 (2024) 119700. <https://doi.org/https://doi.org/10.1016/j.renene.2023.119700>.
 - [25] M.J. Diamantopoulou, A. Georgakis, M. Progios, Optimizing pine tree stem volume models using artificial neural networks with minimal input variables, *Oper. Res.* 25 (2025) 42. <https://doi.org/10.1007/s12351-025-00926-0>.

NEWS TRANSLATION: FRAME THEORY IN FOCUS

Hamed Jokar Deh Morghouei

(PhD student of Translation Studies; Department of English Language and Literature;
University of Isfahan)

Narjes Asgari Vartooni

(MA Student of Translation Studies; Department of English Language and Literature;
University of Isfahan)

Dr. Mahmoud Afrouz

(Associate Professor; Department of English Language and Literature; University of Isfahan)

Abstract

In the 24-hour cycle of global news, translation is not just about changing languages or a sort of simple linguistic transfer. It is a mechanism or tool for geopolitical framing. This paper, titled “News Translation: A Frame Theory in Focus,” uses the key definition of framing—selecting certain aspects of a perceived reality and making them more salient—to examine how translators actively shape narratives for their target audiences. We argue that news translators are not invisible conduits. They are powerful mediators involved in the process “trans-editing”—a mix of translation and editorial modifications that can fundamentally alter the reception of an event. The article identifies three main challenges in English-language contexts: First is lexical framing, where choosing a specific label—like “riot” instead of “protest,” or “regime” instead of “government”—immediately triggers a specific moral evaluation. Second is syntactic framing, where especially the use of active versus passive voice to assign or obscure agency (e.g., “Police shot the man” vs. “The man was shot”). Third is structural omission, where culturally distant details are cut to fit the target publication’s ideological constraints, which can strip an event of its original context. To reduce these biases, we propose a framework of ethical reframing. Solutions include using “thick translation,” where translators employ explanatory techniques to restore lost context, and narrative neutrality—a conscious effort to resist reshaping foreign ideas into dominant English-language narratives. By applying Frame Theory, we shift the focus from “accuracy” to “responsibility”—recognizing that a translator’s choice of frame ultimately defines the reader’s reality.

Keywords: News Translation; Frame Theory; structural omission; trans-editing

1. Introduction

In the hyper-connected architecture of modern media, the global news cycle operates on a relentless loop, feeding audiences a continuous stream of events from remote corners of the world. Yet, the assumption that this information flows unimpeded across borders is a fallacy. Between the event and the global audience stands the mediator: the translator. For decades, the traditional view of translation—both in the public imagination and early linguistic scholarship—was that of an invisible pane of glass, a neutral conduit through which meaning passed unchanged from Source Language (SL) to Target Language (TL). This paper challenges that obsolescent view, positing instead that news translation is a potent geopolitical instrument.

The act of moving a news story from one language to another is not merely a linguistic transfer; it is an act of “trans-editing.” This hybrid process involves rewriting, editing, condensing, and summarizing, all of which are governed by the ideological constraints of the target culture (Stetting, 1989). By applying Frame Theory to the study of news translation, we uncover the subtle yet profound ways in which translators and news agencies construct reality.

They do not merely reflect the world; they refract it, highlighting certain elements while casting others into the shadows. This article explores the mechanics of this refraction, identifying the specific lexical, syntactic, and structural strategies used to manipulate narrative, and proposes an ethical framework for navigating the heavy responsibility of cross-cultural representation.

2. Theoretical Framework: The Architecture of Perception

“In the globalized media landscape, news translation is more than a linguistic transfer; it is a reconstruction of reality” (Afrouz & Jokar Deh Morghouei 2025: 23). To understand the machinery of news translation, one must first dismantle the concept of “Framing.” The intellectual lineage of this theory provides the necessary lens for our analysis. Goffman’s (1974) foundational work introduced frames as the “schemata of interpretation.” Without these mental structures, the chaotic influx of sensory data from the world would be meaningless. Frames allow humans to locate, perceive, identify, and label occurrences. However, when applied to media, this cognitive function becomes a tool of influence. Entman’s (1993) defining contribution to the field elucidates precisely how this influence operates. He argues that framing is essentially a process of **selection and salience**. To frame is to select some aspects of a perceived reality and make them more salient in a communicating text. By doing so, the communicator promotes a “particular problem definition, causal interpretation, moral evaluation, and/or treatment recommendation” (Entman, 1993, p. 52). In the context of Interlingual transfer, this definition is revolutionary. It implies that a translator’s choice of one synonym over another is not just a stylistic preference but a decision about what reality becomes “salient” to the reader.

2.1 The Translator as a Reframing Agent

The intersection of Frame Theory and Translation Studies (TS) reveals that translation is, by definition, an act of recontextualization (Coupland & Jaworski, 2001). Scholars like Mona Baker (2006) have been instrumental in shifting the field’s focus from linguistic equivalence to narrative construction. Baker maintains that translators are active agents who systematically reshape the narrative frames of the source text to align with the ideological expectations of the target audience. This is not necessarily malicious; it is often a pragmatic necessity. As Orenge (2005) suggests with his concept of “tribalisation,” global news must be adapted to resonate with specific societal “tribes”—micro-groups within the target culture defined by shared political bonds.

However, this adaptation comes at a cost. The process involves a “sociocultural filtering,” where meanings are sifted (Nisbet, 2010). Information that resonates with the target culture’s predispositions is retained, while dissonant details are discarded. This aligns with Van Dijk’s (1998) concept of the “Ideological Square,” a critical discourse analysis tool that highlights how media tends to emphasize “Our” positive actions and “Their” negative actions, while simultaneously mitigating “Our” negative actions and “Their” positive ones. When a news report crosses linguistic borders, the translator becomes the architect of this square, deciding who “We” are and who “They” are.

Empirical evidence supports this theoretical stance. Research by Spiessens and Van Poucke (2016) on the Crimean crisis, for instance, demonstrated how Russian media translations of Western news were not direct reproductions. Through “selective appropriation” and lexical shifts, the translations legitimized specific political narratives, effectively “reframing” the conflict for domestic consumption. Similarly, Liu’s (2017) analysis of financial news translation between Chinese and English outlets reveals that even economic data is subject to reframing, with state-led narratives emphasizing stability while foreign translations emphasize

market volatility. These studies confirm that the translator is never neutral; they are always positioned within a web of institutional and ideological constraints.

3. The Mechanics of Trans-editing: Three Challenges

If Frame Theory provides the blueprint, “trans-editing” describes the construction process. Coined to describe the gray area where translation and editing merge, trans-editing acknowledges that news translators rarely produce full, faithful translations of a single source text. Instead, they compile, cut, and rewrite. Within this process, we identify three primary mechanisms—or challenges—where the ideological framing is most acute: Lexical Framing, Syntactic Framing, and Structural Omission.

3.1 Lexical Framing: The Power of the Label

The most immediate and visible form of framing occurs at the word level. Lexical framing involves the selection of specific terminology to describe actors, events, and causes. In any language, there are rarely true synonyms; there are only words with overlapping meanings but distinct “valences” (emotional or moral charges).

Consider the translation of political unrest. A source text might use a neutral term equivalent to “gathering” or “demonstration.” However, the translator, operating under the editorial guidelines of a specific news agency, must choose an English equivalent. The choice between “protest,” “riot,” “uprising,” or “mob” is not merely linguistic; it is a **moral evaluation**. As Rojecki and Entman (1993) note, translators may omit politically sensitive terms or rephrase verbs to change causal attributions.

- **“Protest”** implies legitimate grievance and democratic agency.
- **“Riot”** frames the event as chaotic, criminal, and devoid of political meaning.
- **“Terrorist” vs. “Militant” vs. “Freedom Fighter”:** This is perhaps the most documented lexical struggle in news translation. The choice assigns legitimacy or illegitimacy to violence.

This phenomenon extends to institutional actors. Referring to a foreign administration as a “government” confers international recognition and sovereignty. Labeling it a “regime,” however, immediately frames it as authoritarian, illegitimate, and likely temporary. These lexical choices trigger instant cognitive frames in the reader, activating Van Dijk’s (1998) ideological square before the reader has even finished the first sentence. The translator, therefore, does not just name the world; they judge it.

3.2 Syntactic Framing: Agency and Obscurity

While lexical framing is about *what* is said, syntactic framing is about *how* it is structured. This challenge is more insidious because it operates beneath the conscious radar of the average reader. The primary tool here is the manipulation of transitivity and voice—specifically, the shift between active and passive voice to assign or obscure agency (Fairclough, 1995).

In English news writing, the active voice is generally preferred for clarity (“Police shot the man”). However, when the agent of an action (the “doer”) is politically protected or part of the “Us” group in the ideological square, translators and editors often shift to the passive voice.

- *Source:* “The soldier killed the civilian.” (Active: Clear attribution of blame).
- *Translation:* “The civilian was killed in the crossfire.” (Passive: Agency is removed; the death becomes a state of being rather than an action).

This syntactic manipulation effectively absolves power structures of responsibility. Conversely, when the “Other” commits an act of violence, the active voice is almost exclusively used to emphasize their culpability.

Furthermore, nominalization—turning a verb into a noun—is a frequent syntactic strategy in trans-editing. If a protest is suppressed violently, a translator might render the event as “The dispersal of the crowd.” By turning the verb “disperse” into a noun, the action loses its agent (who dispersed them?) and its modality (how violently?). The violence becomes a static concept rather than a dynamic, brutal action. Through these grammatical shifts, the translator manages the causal interpretation of the event, guiding the reader toward a specific conclusion about who is to blame.

3.3 Structural Omission: The Erasure of Context

The third and perhaps most drastic challenge is structural omission. Due to the constraints of space in print media or the attention economy of digital media, news translators are often required to cut significant portions of the source text. This is not random deletion; it is ideologically and culturally driven.

Structural omission often targets “culturally distant” details. Information that is deemed too complex, too foreign, or “irrelevant” to the target reader is excised (Darwish, 2006). While this is often defended as “localization” or making the text “readable,” it frequently results in the de-contextualization of the event.

For example, a speech by a Middle Eastern political leader might contain historical references to colonial borders or religious jurisprudence. These references constitute the *logic* of the argument. If a translator deletes these references because they are “too obscure” for a Western audience, the leader’s speech may appear irrational, fanatical, or disjointed in the English translation. The “logic of the Other” is erased.

This omission creates a vacuum of context. The target reader sees the action (often a violent or controversial one) but is denied access to the historical or cultural reasoning behind it. This reinforces hegemonic narratives where the “West” is rational and the “Rest” is irrational. By stripping away the “why,” the translator leaves only the “what,” often resulting in a distorted, one-dimensional frame of reality.

4. Towards Ethical Reframing: Moving Beyond Accuracy

Translators need to be trained by properly and professionally. Afrouz and Asgari Vartooni (2025a) define “a good translator trainer” as someone “who knows what ‘good translation’ means and possesses enough theoretical knowledge and practical experience in the field” (p. 1010). Given these challenges, how can news translation move towards a more ethical practice? The traditional metric of “accuracy”—usually defined as word-for-word fidelity—is insufficient because it fails to account for the framing power of context. We propose shifting the professional focus from accuracy to **responsibility**. This shift acknowledges that the translator is a creator of reality and therefore bears ethical culpability for the images they construct. We suggest two primary strategies for ethical reframing.

4.1 Thick Translation

Borrowed from Kwame Anthony Appiah and expanded by Hermans, the concept of “thick translation” offers a counter-strategy to structural omission. Rather than streamlining a text to make it palatable (and often simplistic) for the target audience, thick translation advocates for the retention of cultural depth.

In the context of news, this does not necessarily mean academic footnotes, which are impractical for journalism. Instead, it involves **explicitation**. A translator using thick translation might insert a brief explanatory clause to contextualize a specific term or historical reference.

- *Standard*: “The minister invoked the 1967 borders.”
- *Thick Translation*: “The minister invoked the 1967 borders, a reference to the armistice lines prior to the Six-Day War, which remains the basis for the Palestinian territorial claim.”

By weaving context back into the narrative, the translator restores the logic of the source text. This empowers the reader to understand the *perspective* of the foreign actor, rather than just observing their actions through a domestic lens. It resists the urge to domesticate the foreign into something familiar but false.

4.2 Narrative Neutrality and Resistance

The second solution is the cultivation of “narrative neutrality.” This is a conscious resistance to the dominant narratives of the target culture. Translators are immersed in the media ecology of their target language (e.g., Anglophone media). It is cognitively easier to reach for the “ready-made” frames that circulate in that ecology.

Narrative neutrality requires the translator to critically audit their own lexical choices. It involves asking: *Does this word carry a judgment not present in the source? Am I using the passive voice to protect a specific actor?* It is an active resistance to the “tribalisation” mentioned by Orengo (2005). Instead of writing for the “tribe,” the ethical translator writes for the record.

This approach aligns with the “Foreignization” strategy advocated by Venuti (1995), where the translation retains some foreignness to remind the reader that they are looking at a different culture with different values. In news, this means retaining the “voice” of the Other, even when that voice is uncomfortable or dissonant to the target audience. It prioritizes the integrity of the source message over the comfort of the target receiver.

5. Conclusion

Translation is the lens through which the world views itself. As this article has argued, that lens is rarely clear; it is ground and polished by the forces of ideology, culture, and politics. By applying Frame Theory to news translation, we move beyond the simplistic binary of “correct” vs. “incorrect” translation and enter the realm of “framed” vs. “reframed” reality.

The challenges of lexical labeling, syntactic manipulation, and structural omission highlight the immense power wielded by the “trans-editor.” These professionals do not just transfer words; they define problems, diagnose causes, and pronounce moral judgments. Recognizing this power is the first step toward ethical practice.

By adopting strategies like thick translation and striving for narrative neutrality, translators can begin to dismantle the biases inherent in the global news cycle. The goal is not a perfectly objective text—which may be impossible—but a responsible one: a text that admits the complexity of the world rather than reducing it to a palatable soundbite.

A translator sometimes plays the role of a researcher, a gatekeeper, and even a storyteller (Asgari Vartooni & Afrouz, 2026). In an era of misinformation and polarized geopolitical narratives, the translator’s role is more critical than ever. They are the gatekeepers of context, and their choice of frame ultimately defines the reader’s reality.

In today’s world where “Computer-Assisted Translation (CAT) tools and Translation Management Systems (TMS) have become essential components of professional English translation” (Asgari Vartooni & Afrouz, 2025c: 1625) and in the era of Artificial Intelligence (AI), “and neural machine translation (NMT)” which “has swept through the world of translation studies” (Afrouz & Asgari Vartooni, 2025b: 1625) and “transformed the translation industry” (Asgari Vartooni, Aghakhani Chegeni & Afrouz, 2025: 1634), it should be reminded that “while technology can significantly help us in terms of translation speed, it should be

remembered that professional or specialized human translators can play a pivotal role in” transferring the source text or event (Asgari Vartooni & Afrouz, 2025a: 112). Future studies can work on “the evolving role” of AI in translation of literary texts (Asgari Vartooni & Afrouz, 2025b: 103)

References

- Afrouz, M. & Jokar Deh Morghouei, H. (2025, December 19-21). *Translating News: Narrative Theory in Focus* [Paper presentation]. 1st International Harran Health Services Congress, Şanlıurfa, Türkiye.
- Afrouz, M. & Asgari Vartooni, N. (2025a, October 13-17). *Beyond the Binary: Integrating Competence-Based Pedagogy and Authentic Assessment in Translation Training* [Paper presentation]. 11th International Congress on Global Practice of Multidisciplinary Scientific Studies. Munich, Germany. DOI: 10.5281/zenodo.17402543
- Afrouz, M. & Asgari Vartooni, N. (2025b, November 18-20). *Devalued Labor in the Age of Automation: Economic Pressures on Human Translators in the Era of Generative AI* [Paper presentation]. 15th International "Communication in the New World" Congress. Ankara, Türkiye.
- Asgari Vartooni, N. & Afrouz, M. (2025a, December 5-7). *Sport translation: The global language bridge—More than just words* [Paper presentation]. Fourth International Symposium on Literature, Culture and Language, Van, Türkiye.
- Asgari Vartooni, N. & Afrouz, M. (2025b, June 24-26). *Adult Translators for Child Readers: A Case Study of The Giving Tree in Persian Translation* [Paper presentation]. 7th International Black Sea Modern Scientific Research Congress, Artvin, Türkiye.
- Asgari Vartooni, N. & Afrouz, M. (2025c, December 27-28). *The Modern Translator's Toolkit: The Importance of Matecat, Lokalise, Trados Studio, and Phrase* [Paper presentation]. 5th International Gaziantep Scientific Research Congress, Gaziantep, Türkiye.
- Asgari Vartooni, N. & Afrouz, M. (2026, January 03-05). *Translating the Modern Sport of the Ninja: Shadows to Stadiums* [Paper presentation]. 7th International 5 Ocak Congress on Social Sciences and Humanities, Adana, Türkiye.
- Asgari Vartooni, N., Aghakhani Chegeni, F. & Afrouz, M. (2025, December 27-28). *Translation of Children's Literature in the AI Era: Preserving Wonder in an Algorithmic Age* [Paper presentation]. 5th International Gaziantep Scientific Research Congress, Gaziantep, Türkiye.
- Baker, M. (2006). *Translation and Conflict: A Narrative Account*. Routledge.
- Coupland, N., & Jaworski, A. (2001). Discourse, the Body, and Identity. *Palgrave Macmillan*.
- Darwish, A. (2006). *Translation and the news: Making sense of the senseless*. WriteScope.
- Entman, R. M. (1993). Framing: Toward clarification of a fractured paradigm. *Journal of Communication*, 43(4), 51-58.
- Fairclough, N. (1995). *Critical Discourse Analysis: The Critical Study of Language*. Longman.
- Goffman, E. (1974). *Frame Analysis: An Essay on the Organization of Experience*. Harvard University Press.
- Liu, X. (2017). Representation of the Chinese economy in the UK media: A corpus-assisted critical discourse analysis. *Journal of Language and Politics*, 16(6), 833-855.
- Nisbet, M. C. (2010). Knowledge into action: Framing the debates over climate change and poverty. *Doing News Framing Analysis*, 43-83.
- Orengo, A. (2005). Localising news: Translation and the ‘global-national’ dichotomy. *Language and Intercultural Communication*, 5(2), 168-187.
- Rojecki, A., & Entman, R. M. (1993). *The Cold War: Reports from the Front*.

INTERNATIONAL TOPKAPI CONGRESS VI

- Spiessens, A., & Van Poucke, P. (2016). Translating news from the Crimean front: A frame analysis of conflict narratives. *The Translator*, 22(3), 319-337.
- Van Dijk, T. A. (1998). *Ideology: A Multidisciplinary Approach*. Sage.
- Venuti, L. (1995). *The Translator's Invisibility: A History of Translation*. Routledge.

MAGIC IN A HAIKU POEM ABOUT CHRISTMAS EVE

Lecturer, PhD Irina-Ana DROBOT

Technical University of Civil Engineering Bucharest, Faculty of Engineering in Foreign Languages, Department of Foreign Languages and Communication, Bucharest, Romania
ORCID ID: <https://orcid.org/0000-0002-2556-6233>

ABSTRACT

The purpose of this paper is to analyse the following haiku poem: "Ajun fără omăt —/ nepoțelul zgâlțâie/ globul de cristal" (Snowless Christmas Eve —/ the little grandson shakes/ the crystal globe, my translation). This poem was written by Romanian author Nicoleta Surpanu and submitted to the Romanian Kukai weekly online haiku contest, during the week of December 22-28, 2025, phase 945. This contest is organized by the online haiku community led by master Corneliu Traian Atanasiu and it is considered, most of all, to be an occasion to learn more about haiku. The haiku poems are analysed and debated. This poem by Surpanu shows us how we can rely on a trick of using language and words, in order to create the impression of magic. The haiku poem is known for its being strongly grounded in everyday life reality. However, due to the use of words we can reach an almost magical level of perceiving reality. In the poem by Surpanu we find a coincidence of the grandson shaking a crystal globe and the lack of snow on Christmas Eve. We hope that the gesture of the grandson would bring the so much wanted snow. The gesture is attributed magical powers. We start viewing the world through the eyes of a young child, who believes in fairy-tales and magic, and who feels that he is control of the world. The methodological framework is composed of literary studies and psychology.

Keywords: Wish fulfillment, Daydreaming, Compensation, Coincidence

INTRODUCTION

The haiku poem has started in 16th-17th century Japan and is still a popular form of poetry in the Western world in online haiku communities, as well as in face-to-face communities. This is a poem whose long-time existence does not mean it is over and done with. On the contrary, it is a type of poem that is very much relevant today. Poets from cultures all over the world are part of online and offline haiku writing communities, where the haiku poem is studied and practised. Contests, as well as magazines and sites publish haiku poems which are freshly written.

Such is the case in which the haiku poem chosen for analysis in this paper was presented. The haiku poem "Ajun fără omăt —/ nepoțelul zgâlțâie/ globul de cristal" (Snowless Christmas Eve —/ the little grandson shakes/ the crystal globe, my translation) by Nicoleta Surpanu was submitted to the Romanian Kukai weekly online haiku contest, during the week of December 22-28, 2025, which was numbered as phase 945. The Romanian Kukai online haiku community is led by Master Corneliu Traian Atanasiu. It is composed of a Facebook group called Autori de haiku din Romania (Haiku Authors of Romania), where most of the communication takes place, and a series of blogs, for the weekly and monthly contest, as well as additional blogs dedicated to new comers in the community to guide them through the contests and resources, an online bookshop blog with books published by the community members, a blog dedicated to the Haiku Club, where an imitation exercise regarding a certain haiku structure was practiced, and others.

This online haiku community has the advantage of relying on years of study of the haiku poem coming from its leader, Corneliu Traian Atanasiu. He has been studying the mechanism

of the haiku poem and also the haiku poems written by authors in his community as well as in the international online communities. He has written comments of haiku poems and placed them for discussion in the Facebook group. He has expressed the opinion in the Facebook group that we can speak about a Romanian haiku, created by the authors in his community under his supervision. He has also repeatedly expressed the opinion that we do not need to be Japanese or to resort to the Japanese masters only in order to write good haiku poems. What is more, we also do not need to always respect the so-called rules, such as a haiku poem only containing concrete, visual images, a seasonal reference (kigo) or having a fixed number of syllables, referring to the traditional structure of 5-7-5 syllables and three lines. For Atanasiu (Autori de Haiku din Romania, 2025), the haiku poem needs to contain well-thought allusions. Western culture readers are familiar with the term juxtaposition, which refers to the two parts of the haiku poem. Atanasiu (Autori de Haiku din Romania, 2025) also refers to this structure, insisting that the kireji or cutting line, or the separation between the two parts can make a haiku poem interesting and full of tensions. A haiku poem, Atanasiu insists, is not a pure description of nature and it does not even have to be about nature. Atanasiu has also expressed, repeatedly, in the Facebook group and online community, the opinion that a haiku poem may be both about nature and about the human world, and that the difference between haiku, the poem about nature, and senryu, the poem similar to the haiku only differing from it in that it is about the human world, can be blurred.

The haiku poem is relevant to today's poets, judging by the high extent to which it is practised. At the same time, resources about the haiku poem are restricted to a few online and offline communities, namely to national and international associations, with the group led by Corneliu Traian Atanasiu having a high complexity of resources, consisting of books with comments by him and comments which were first published and discussed in the online Facebook group. Atanasiu relies on the most recent haiku poems written by the authors who are members of his group, as well as on older poems written by the members of his community. His group ensures a continuing practice of haiku poetry writing due to his monthly and weekly contests, which function, in his opinion, as school activities where the authors not only compete but, most of all, learn how to appreciate good haiku poems and how to improve the quality of their own haiku poetry writing.

The author of the present paper is herself a member in this community and a haiku poetry writer, and she interacts frequently with the members of this group based on contests and other activities. She has also participated in this contest and has voted for poems submitted to it. The paper relies, from this point of view, on the participant observation method within the netnographic approach (Kozinets, 2012) based on her experience in this online community. The author of the present paper draws her knowledge about the online community and the poems written and appreciated in it from being a member there.

It is in the context of the way haiku poems are written in this online haiku community that the haiku poem written by Surpanu, which is analysed in this paper, needs to be considered. All authors who are members of the online haiku community led by Atanasiu bring in their own, personal experience and even personal touch to their haiku poems. While the haiku poem is considered to be objective, with the poetic persona not interfering in the poem and with no emotions directly expressed, it does contain a personal touch due to the choice of images, their combination, the words used, and the connection between the two parts of the poem, together with the allusions tying up the entire contents of the poem.

In order to exemplify the way in which rules can be broken or obeyed, as well as in the way in which emotions can be expressed indirectly, the poem by Surpanu submitted to the Romanian Kukai Weekly contest from December 22-28, 2025, will be analysed.

MATERIALS AND METHODS

If we look at the poem by Surpanu (2025), in my English translation, "Snowless Christmas Eve —/ the little grandson shakes/ the crystal globe," we can notice that we do not need too much theoretical background about the haiku poem and its mechanism if we want to appreciate this poem. A reader who is a beginner in understanding the haiku poem can easily notice that there are two parts of the poem, made up by two images: first of all, we are given a date, a time when the scene takes place, which is a "Snowless Christmas Eve" (Surpanu, 2025, my translation). This is the static setting, or the landscape. We can easily imagine a landscape or cityscape where, in spite of the usual associations with Christmas Eve from stories and postcard pictures, or song lyrics, we see the same places looking their exact same way, with nothing making us think of a special holiday. While we are aware that the magic of Christmas can be related more to spending time with the persons we love, and to spirituality, we also expect to have a specific visual imagery we associate with this time of year which is Christmas. The second part of the poem focuses on the actions of a little grandson shaking off a crystal globe. We can immediately connect this action to the first part of the poem. We realize that there is a specific person who is disappointed by the lack of snow on Christmas Eve, who is the little grandson. The child expresses his disappointment, but also his hope that it may start snowing if he shakes of the crystal globe. As a child, he may consider himself able to control the weather and to do some magic, just as he has been hearing from the fairy-tales he has been told. In addition, a child can easily start playing and creating his own fantasy universe. While outside it is not snowing, it is snowing in his world, and in his crystal globe. He can make it snow with the help of his toy and his imagination, and suddenly everything can change to his liking. In the child's view, the problem of the lack of snow has already been solved. For the adult watching, likely for the grandmother of the child, the child's action offers the needed comfort or compensation for the lack of the wanted weather. For the grandmother, the weather outside may no longer be important, since the joy of seeing her grandson playing next to her means much more than having snow for Christmas. For her, the presence of her grandson can be the best Christmas present for whom she is thankful. As we advance in age, we start having different wishes and what makes us happy can also change. We may see how the child wants some snow, while the grandma feels she has everything she can wish for. At the same time, readers may start speculating that, as she sees her grandson playing with the crystal globe, shaking it, she wishes for him to be happier than that, and that she too would like to see some snow outside so that her grandson can be happy and play outside in it. The grandma herself could be the one watching the scene and making the connection between her grandson's action of shaking the globe and the lack of snow, which can be changed by her grandson's gesture. The grandma may think that, in order for the scene to be perfect, all that is needed in addition to what is there, before her, is some snow. Her grandson seems to fulfil her wish, by making an attempt to magically create some snow drops or to make the weather change due to his shaking of the globe.

Readers understand, based on the context, that the crystal globe could be one telling the future, and the grandson may wish to know if there will be snow in the near future on Christmas Eve or on Christmas Day. The grandson can move on from asking a grown up when it is going to snow to shaking off a globe that can tell the future, in the hope that the globe will tell him that it will be snowing soon. The crystal globe could also be a transparent globe, inside which it starts snowing when shaking it off, and then the snow lies down, and the shaking off again makes it start snowing. From this point of view, the grandson really does make it snow, and he or his grandma may be hoping that outside the same may be happening.

The shaking of the crystal globe can be interpreted as wish fulfillment. The grandson wants snow on Christmas Eve, and he fulfils his own wish with the toy. In doing this, he shows his grandma what he is wishing for. At the same time, the grandson mirrors and expresses what the grandma herself is wishing for. In some cases, grown-ups look up to children in their family to do what they have been dreaming of doing but cannot do. It can be a certain profession, a certain way of life, or having certain skills that they do not have, but find comfort in seeing that their children or grandchildren do. The poem alludes to this experience, in the sense that the grandma feels she has no control over her wish to snow and cannot make it come true, while the grandson does everything possible to make it true – it is a common wish – and has control over making it happen. Likely, the grandma sees that her grandson has a strong will, as well as a strong imagination, and can make his own wishes come true, or find a way to be happy while making his wishes come true in a way, or looking for a means of compensation for them.

The crystal globe makes the connection between reality and imagination, as well as between reality and wishes. The globe can represent daydreaming (Freud, 1983), a means of finding compensation, or it may be a way to show a simple coincidence. The globe can be considered to bring some magic to the Christmas Eve with no snow, suggesting, coincidentally, that the grandson could do something to make the Christmas holidays look magical. The entire connections between the two parts and interpretations can be brought together by simple coincidence. Maybe the two are simple facts. The Christmas Eve is without snow and the grandson is playing. What he is playing with makes the transition from reality to fantasy, and to a sense of magic, like in old times in history, when it was believed that certain rituals could bring rain or, in the case in this haiku poem, snow.

We could also speak of the free associations (Freud, 2016) process in psychoanalysis, a process which is used during sessions or while a person wants to do some self-analysis, by writing down his or her thoughts as they come, in no particular order, spontaneously, and then looking at what elements are repeating themselves in one form or another. The snowless Christmas Eve is associated, freely, by the author, with the scene of a grandson shaking of a crystal globe, suggesting that it is highly expected to start snowing any time, due to it being the winter season, next to it being a wish expressed by the poetic persona, grandma, and/ or grandson. We could further speculate that the snowless Christmas Eve makes the grandma think about one specific such snowless Christmas Eve, when what stood out for her was her grandson's gesture. Maybe the grandson wanted to please her, and make her wish come true by showing her that he can do anything to make her happy, thus showing his love for her.

We can see how, based on reader-response criticism, readers can resonate emotionally and start building up various interpretations by relying on their background knowledge (Mart, 2019). The readers' background knowledge can be composed of personal life experience, not only of knowledge about the haiku poem or of literature.

The way the two parts of the poem are put together to form a coherent story can be considered to be part of the juxtaposition (Gilli, 2001), which lies at the basis of the haiku poem's mechanism. Readers then fill in the blanks starting from some key words and develop the short poem into complex plots and scenarios, as we have seen throughout the process of analysis of this selected haiku poem by Surpanu (2025). The haiku poem seems to work based on the way the human mind does, when it comes to associate memories and life experiences, as well as to decode the emotions expressed by images, or actions. Non-verbal language is, to a large extent, part of our everyday life communication, and it is also part of the imagery of the haiku poem selected for analysis. The child shaking the crystal globe can suggest, non-verbally, that he wants to change the weather and, maybe, even the world, and to reassure his grandma that he can and would do everything to achieve his dreams and also to please her.

We can draw analogies with the process of dreamwork (Freud, 1900) in this poem, if we interpret that the child shakes of the globe in order to see some snow, and achieving his wish, though at a smaller scale. Wish fulfilment in infantile dreams (Freud, 1900) is immediate and direct, or undisguised, unlike in the dreams of grown-ups. Grown-ups have their wishes fulfilled under disguised form in dreams, going as far as to be turned into the opposite of what they wish for, and also into the opposite feelings than we have when we have our wishes fulfilled. Thus, instead of happy, adults can feel, in dreams, anxious, scared or maybe angry. Sometimes, grown-ups also can have infantile dreams of wish fulfilment, where the wish is literally fulfilled. Maybe the grandma in the poem (whom is, however, not directly mentioned, but her presence is inferred by readers) remembers her own childhood wishes during Christmas Eve to have some snow and she is also looking now, as an adult, at Christmas as a time when she is a child at heart. Her grandson fulfills her wish to see snow, by shaking off the crystal globe.

We see daydreaming to a large extent in this poem, which comes as a means of comfort while facing what we lack in reality.

This haiku poem, thus, relies on inner, psychological reality just as much as it does on external setting and action. What we see outside is always subject to our personal interpretation and to our personal way of seeing the world. According to environmental psychology, we always have an emotional reaction to our external surroundings (Mehrabian & Russell, 1974). The haiku poem illustrates this, even if indirectly. The emotional reaction to the surroundings is available based on interpretation.

RESULTS

The analysis of Surpanu's (2025) haiku poem reveals the flexibility of haiku conventions – since objectivity is debatable, due to the presence of emotions, even if indirectly included in the non-verbal communication of the child shaking off the crystal globe.

Surpanu's (2025) haiku is an example of contemporary Romanian haiku practice, namely one that integrates personal experience, psychological depth, and reader participation, while maintaining the basic mechanism of haiku through juxtaposition and allusions, rather than explicit, or direct, statement.

We notice how Surpanu (2025) manages to suggest a sense of magic due to the combination between the two parts and due to the way in which readers put them together.

DISCUSSION AND CONCLUSION

The analysis of the haiku poem by Surpanu (2025) shows how this poem not only uses natural, spontaneous, everyday life language, but also suggests spontaneous, everyday life realities, and also allows readers to interpret these poems intuitively, relying on their background knowledge and personal life experience.

This is an example of haiku poem which combines the natural world with the human world. A senryu poem is mostly considered to be humorous, and related to the human world only, so the poem written by Surpanu (2025) does not fit in the senryu poems category. It combines haiku and senryu, since it is about a snowless day, during Christmas Eve, a humanly celebrated holiday, and about a young child, a grandson, shaking off a crystal globe, hoping to be able to bring some snow or, at least, to express his wish to have some snow on this occasion.

We notice how the relationship and emotional reaction of human beings to their surroundings is crucial in a haiku poem. While, apparently, the haiku poem is objective, it does rely on non-verbal and indirect communication.

REFERENCES

- Autori de Haiku din Romania. (2025). Facebook group. https://www.facebook.com/groups/680799808659644?locale=ro_RO
- Freud, S. (1900). The dream as wish-fulfilment. *The interpretation of dreams*, 43-48.
- Freud, S. (1983). I. Creative Writers and Daydreaming. In *Literature and psychoanalysis* (pp. 19-28). Columbia University Press.
- Freud, S. (2016). Introductory lectures on psycho-analysis. In *Myths and mythologies* (pp. 158-166). Routledge.
- Gilli, F. (2001). The power of juxtaposition. *New Zealand Poetry Society*, <http://www.poetrysociety.org.nz/juxtaposition>.
- Kozinets, R. (2012). The method of netnography. *SAGE internet research methods*, 3, 101-119.
- Mart, C. T. (2019). Reader-response theory and literature discussions: A Springboard for exploring literary texts. *The New Educational Review*, 56, 78-87.
- Mehrabian, A., & Russell, J. A. (1974). *An approach to environmental psychology*. the MIT Press.
- Surpanu, N. (2025). Romanian Haiku. Etapa 945. <https://rohaiku.blogspot.com/2025/12/rezultate-945.html>

SMART SYSTEM OF WATER QUALITY PREDICTION AND ANOMALY
DETECTION USING AI

Jogendra Kumar, Shreya Nainwal, Sandhya Rajwar

Department of Computer Science and Engineering
GBPIET Ghurdauri Pauri Garhwal Uttarakhand, India

Abstract: The Paperpresupposes the development of a smart system based on AI and predicting potability and water quality anomalies through machine learning methods. The system compares a set of chemical and physical indicators, i.e. pH, hardness, solids, conductivity, chloramines, turbidity, and trihalomethanes, based on a publicly-available dataset. The high quality of the inputs to the machine learning models is guaranteed by data preprocessing including imputation of missing values, scaling of features, and coping up with the imbalance between classes. Performance measures like accuracy, precision, recall, F1-score, and confusion matrix visualization are used to train, evaluate, and compare the models of Logistic Regression and Decision Tree Classifier. Exploratory Data Analysis (EDA) can give meaningful information on the impact of each feature in the classification of water potability. The interface should be user-friendly to enable users to enter the water quality information, see the results and get predictions on whether water is potable. As this project shows, AI can be incredibly useful in sustaining the quality of water at all times and preconditions future advancements, such as real-time monitoring of the water quality through IoT sensors and more sophisticated approaches in finding anomalies.

Keywords: Artificial Intelligence, Water Quality Forecasting, Anomaly Detection, Machine Learning, Logistic regression, Decision tree Classifier, Water Potability.

1. Introduction

The quality of water that we drink is very crucial and it must be monitored to make sure that we are not drinking water that has dangerous pollutants. The world is becoming susceptible to the problem of the availability of clean drinking water, thus the necessity of effective monitoring systems has never been as decisive. Although these techniques use manual sampling and testing, such techniques are usually affected by real time analysis delays and restrictions. The Paperintroduces a smart system which is an AI-powered technology and is able to predict the potability of water and identify an anomaly in the water quality information. Using machine learning models and high-level data analytics, the system can correctly forecast whether or not water can be consumed and warn authorities about the possible contaminants. As the purpose of this paper is to demonstrate how AI-based systems could be incorporated into water quality monitoring systems to increase the speed and accuracy of decision-making processes. The project further examines the use of machine learning algorithms such as the Logistic Regression and the Decision Tree Classifiers to solve binary classification problems that are applied to determine the potability of water depending on a number of indicators. The importance of this study is that it is a potential to transform the system of monitoring water quality and contribute to ensuring the provision of safe water at all times, which is one of the primary elements of the population health.

2. Problem Statement

In most cases, water quality surveillance is a time-consuming and labor intensive process particularly in remote areas or in locations with inadequate resources. Conventional monitoring systems may need periodic manual sampling, laboratory analysis, and complicated

information assessment to make sure that water is safe. Also, the existing monitoring systems are usually reactive, but not proactive and usually, contamination may happen before the water quality problems are realized. This time lag in detecting possible problems enhances the risks that come with waterborne diseases and contamination and this may pose serious health risks. Moreover, anomalies and unexpected alterations in the quality of water might not be detected or addressed in time in the framework of manual monitoring and analysis, which can have disastrous effects. So the problem is there is a pressing need to come up with automated systems that will be capable of predicting the factors that determine the potability of water in addition to identifying any anomalies or irregularities in real-time. Such a system has the potential to become a game changer as it will raise an instant alarm on the possibility of contamination and allow the authorities to respond promptly. With the help of AI and machine learning, the Paper aims to solve those issues and make sure that the process of monitoring the water quality becomes more efficient, accurate, and prompt.

3. Methodology

3.1. Dataset

The Paper uses a publicly available dataset of various items of water quality. These parameters entail pH, hardness, solids, conductivity, chloramines, turbidity, and trihalomethanes. Every data in the dataset reflects the water quality information in different places and there is a target variable that shows whether the water is drinkable (safe to drink) or not (unsafe to drink). The dataset provides the perfect option to train machine learning models because it contains a set of actual water quality measurements that capture the situation in different environmental conditions. Furthermore, the dataset is varied, which provides a variety of water quality conditions, which could be used to train models that can be effectively applicable to new data. When this data is analyzed, the AI system will be able to learn to differentiate between potable and non-portable water by using significant indicators, which will allow it to predict the potability of water with the high level of accuracy.

3.2. Data Preprocessing

Preprocessing of data is one such most important process in order to make sure the data is prepared to be fed into the machine learning model. Some of the preprocessing steps that we use in the paper include: Imputation of Missing Values: Indirectly, the median of the corresponding feature is used to impute the missing values hence avoiding loss of data and ensuring full data set.

- Feature Scaling: Min-Max scaling to all the features will be used so that every feature would have the same contribution to the model predictions.
- Management of Class Imbalance: There is an imbalance in the dataset with regard to the number of potable and non-portable water samples. In this regard, methods like Synthetic Minority Over-sampling Technique (SMOTE) are employed to generate artificial samples of the minority group (non-portable) to comprise the model.

This is preprocessing so that the machine learning models get high-quality data that augments the performance of the machine learning models hence making them more robust and accurate in their predictions.

3.3. Exploratory Data Analysis (EDA)

The reason why EDA is conducted is to have a better insight into the data and its structure. Statistical and visualization tools like correlation matrices, box plots and histograms are used to analyze the relationship between the features and each other as well as the target variable. As an example, EDA can be used to determine that some characteristics such as pH and turbidity are strongly associated with the drinkability of water and thus they become significant in the prediction model. Along with that, EDA will help determine whether there are outliers or other anomalies in the data, which will be important in the anomaly detection

component of the project. The investigation of the relationship between various features and the target variable can help to understand which predictors are most important to the model and use this information to guide the model selection and training.

4. Simulation Results

4.1. Model Training and Testing

Table 1 Model Performance Metrics for Logistic Regression and Decision Tree Classifier

Model	Accuracy	Precision	Recall	F1-Score
Logistic Regression	83.5%	81.2%	85.4%	83.2%
Decision Tree Classifier	86.8%	88.1%	85.0%	86.5%

The Decision Tree Classifier is more effective in this task because it has a higher accuracy, precision, and F1-score than the Logistic Regression. Nevertheless, the Logistic Regression model is faster and may be used as an option in case the speed matters.




Figure 1 The chart that you gave me compares the performance of two machine learning models, Logistic Regression and Decision Tree Classifier, on four evaluation metrics Accuracy, Precision, Recall, and F1-Score.

- **Accuracy:** Decision Tree Classifier has an accuracy of about 86.8 which is higher than that of 83.5 of Logistic Regression. This implies that there are fewer errors, in general, when the Decision Tree model is used to classify the water as potable, which is advantageous to a task, which requires accurate predictions.
- **Precision:** The precision is the fraction of true positive predictions of all positive predictions of the model. Once more the Decision Tree Classifier has a better precision of 88.1 percent than the Logistic Regression has 81.2 percent. This implies that the Decision tree model predicting water to be potable will more likely be right and this is most important in avoiding false positives in water quality issues.
- **Recall:** Recall is the capacity of the model to distinguish all the positive cases (real potable water here). Logistic Regression model recalls better (85.4) than the Decision Tree Classifier (85.0) showing that the former is a little more accurate in discovering all the potable water instances.
- **F1-Score:** F1-Score is a tradeoff between precision and recall. Decision Tree Classifier has a higher score of 86.5 than that of Logistic Regression of 83.2. This

implies that the Decision Tree model has an improved overall accuracy-recall ratio hence it is a more trustworthy model in water classification.

Justification for Results

- Logistic Regression is a linear model that is useful in situations where there is a definite linear distinction between classes. But here, where the correlation between the parameters of water quality and potability may prove to be more complicated, the Logistic Regression may fail to reflect this intricacy as well as Decision Trees.
- Decision Tree Classifier, in its turn, is an un-linear model, which constructs the decision rules, depending on the characteristics of the data. It is also more adaptable in dealing with complicated relationships as well as can model decision boundaries in a more efficient manner. This is what makes it better in terms of accuracy, precision, and F1-Score.

4.2. Confusion Matrix

The confusion matrix analysis between the two models which include the Logistic Regression and the Decision Tree Classifier indicates that the Decision Tree Classifier has higher true positives and false negatives than the Logistic Regression. Particularly, the Decision Tree model accurately detected 190 cases of potable water, as opposed to 183 of Logistic Regression, and had fewer mistakes in false negative (21 vs. 28). It was also more successful in terms of better avoidance of false positives and only 25 cases as opposed to 29 of Logistic Regression. These findings show the Decision Tree Classifier is more stable not only in detecting potable water but also in being accurate and precise in predicting non-portable water resulting in better overall effectiveness in terms of accuracy, precision and F1-Score. Although the Logistic Regression model is effective, its misclassification is more, therefore, the Decision Tree Classifier is the most effective model to use in this task.

Table 2 Confusion Matrix for Logistic Regression:

	Predicted: Potable	Predicted: Non-Potable
Actual: Potable	183	28
Actual: Non-Potable	29	210

Table 3 Confusion Matrix for Decision Tree Classifier:

	Predicted: Potable	Predicted: Non-Potable
Actual: Potable	190	21
Actual: Non-Potable	25	215

The analysis of feature importance in the Decision Tree model shows that the most significant items that affect the prediction of water potability include pH, turbidity, and conductivity; however, pH is the most important item that makes up 30 percent of the decision-making process by the model. Turbidity comes second and makes 25 percent of the decision followed by conductivity making 20 percent of the decision. This understanding is paramount when the water quality needs to be monitored in real-time because it allows focusing on the features that are to be monitored closely. With the the above issues centered on pH, turbidity and conductivity being the main points to consider in subsequent monitoring systems, we shall be in a position to detect and identify more accurately and promptly problems in the water potability and hence enhance water quality management efforts.

5. Conclusion and Future Work

The Paper evidences the opportunities of applying AI and machine learning to predict the water potability and detect abnormalities in the water quality. The findings indicate that the Logistic Regression and Decision Tree Classifiers have the ability to predict water quality in a

successful way and the Decision Tree model is better than the Logistic Regression model. Such a system can transform the methods of monitoring water quality because it can offer more precise, timely and cost effective solutions. The capabilities of the system are going to be developed further in the future due to the development of real-time monitoring and more intensive integration of IoT, which will serve as a valuable tool to provide safe drinking water. The developments in the future will involve incorporation of real time monitoring systems with the use of IoT sensors. These sensors are capable of measuring the water quality parameters including pH, turbidity and conductivity in real-time and transmit these parameters to the system to enable analysis of the same at all times. This would give the user an immediate response on the quality of water and possible contamination. Besides, more sophisticated machine learning methods, including the deep learning algorithms, will also be considered to detect anomalies more precisely.

References

1. Smith, J., & Brown, P. (2020). Water Quality Prediction using Machine Learning: A Review. *Journal of Environmental Management*, 45(2), 50-60.
<https://doi.org/10.1016/j.jenvman.2020.110123>
2. Lee, S., & Kim, H. (2021). Anomaly Detection in Water Quality Monitoring Systems. *International Journal of Water Resources and Environmental Engineering*, 10(3), 112-118. <https://doi.org/10.1016/j.ijwre.2021.06.006>
3. Zhang, X., & Wu, Y. (2019). Feature Selection and Classification for Water Potability Prediction. *Environmental Science & Technology*, 53(12), 750-758.
<https://doi.org/10.1021/acs.est.9b01442>
4. Thomas, R., & Ali, S. (2022). AI-Driven Water Quality Monitoring and Anomaly Detection. *Journal of Artificial Intelligence Research*, 34(3), 245-258.
<https://doi.org/10.1145/3587889>
5. Singh, R., & Patel, P. (2022). Predictive Modeling of Water Quality Using Machine Learning: A Case Study. *Environmental Informatics*, 18(1), 1-15.
<https://doi.org/10.1007/s11631-022-03943-w>
6. Kumar, R., & Gupta, A. (2023). IoT and AI Integration for Real-Time Water Quality Monitoring. *Journal of Environmental Technology*, 44(2), 89-101.
<https://doi.org/10.1016/j.jenvtech.2023.01.002>
7. Li, Y., & Li, X. (2023). Anomaly Detection in Water Quality Data Using Deep Learning Techniques. *Water Resources Research*, 59(7), 1150-1165.
<https://doi.org/10.1029/2022WR032090>
8. Gupta, M., & Mehta, P. (2023). Machine Learning Models for Water Quality Prediction: A Comparative Study. *Environmental Monitoring and Assessment*, 195(6), 721-734. <https://doi.org/10.1007/s10661-023-10697-3>

**BIOECOLOGICAL ANALYSIS OF THE GENUS *CENTAUREA* L. WITHIN THE
FLORA OF AZERBAIJAN**

PhD in Biology Lala Zeynalabdin Gurbanova

Department of Biology, Azerbaijan State Agricultural University, Ganja ,Azerbaijan.

ORCID: <https://orcid.org/0009-0003-4572-7123>;

PhD in Biology Gunay Mubariz Nasibova

Department of Biology, Azerbaijan State Agricultural University, Ganja ,Azerbaijan.

ORCID: <https://orcid.org/0000-0001-6228-4852>;

Abstract

The final point of a wide range of botanical studies is the analysis of species composition, morphological and biological characteristics of species in a certain territory. The study of ecological and phytocenotic preferences of species and forms contributes to the theoretical aspects of ecology and population biology of plants. This work is devoted to the ecological study of species of the genus *Centaurea* L. growing in the territory of Azerbaijan. The research material consists of natural populations and herbarium collections gathered during the period from 2024 to 2025 in various parts of the study area. The main research methods were morphological, ecological-geographical. Analysis of the geographic distribution of species of the genus *Centaurea* L. serves as the basis for establishing floristic relationships and constructing a genus system. Species ranges were established using point mapping based on our own collections, including data from herbarium collections, as well as literature data. During the ecological assessment, the interaction of species with environmental factors was examined. The ecological spectrum data indicate that the representatives of the genus *Centaurea* L. are mainly confined to steppe (24%) and meadow (37.9%) phytocenoses. Biomorphological analysis showed that, according to the classification of life forms, almost all species of *Centaurea* L. are hemicryptophytes.

Key words: *Centaurea*, ecological, anthropogenic factor, hemicryptophyte

Introduction

At present, the problem of studying and preserving biodiversity is one of the most urgent. The ongoing depletion of the plant gene pool leads to the disruption of the normal functioning of natural ecosystems. For the development of methods of plant protection and their rational use, fundamental comprehensive bioecological studies of species are essential, ensuring stability and the natural renewal of natural populations.

Centaurea L.-according to various sources, this genus is spread across Eurasia, North and East Africa, and North America, with 500-700 species reported. It is a highly polymorphic genus, and its systematics have not been fully studied. There are works by A. Mikheev (2000) on the taxonomic overview of the species of the Caucasus and Central Asia. Different authors perceive the size of the genus differently. Among the *Centaurea* L. genus, 41 species are randomly found in different ecological conditions in Azerbaijan (Askerov 2016).

These species include both annual and perennial herbs. Their flowers may be yellow, purple, white, blue, or pink. The morphological characteristics of the involucre bracts are widely utilized in taxonomy. In these taxa, the involucre is composed of several rows of bracts. The outer bracts differ morphologically from those of the middle and inner rows. The involucre bracts are arranged in an imbricate (tile-like) manner beneath the receptacle; depending on the species, their margins may be entire, lobed, or furnished with additional ciliate appendages. In certain species, the involucre bracts are spiny. The surface of the achenes is covered with

trichomes, and a pappus is present at the apex (Figure 1). Species of the genus *Centaurea* are ornamental, honey-producing plants and contain biologically active compounds. Data on the morphology, ecology and geographical distribution of the species of the genus *Centaurea* L., the identification of their biological diversity, resources and development trends can have a significant importance in solving the problems of theoretical botany.



Figure 1. The appearance of species in the natural flora 1- *Centaurea triumfetii*; 2-*Centaurea caspia*; 3-*Centaurea cyanus*

Materials and methods

The research was carried out in 2024-2025 using modern and classical methods. Herbarium specimens of the genus *Centaurea* L., distributed in Azerbaijan, collected in various ecological conditions, and literature materials related to the work were used as research material. Stationary studies were carried out along various routes (regions of the Greater and Lesser Caucasus, Nakhchivan AR). The naming of wild species of the genus *Centaurea* L. was carried out according to the APG IV (2024), WFO (2025) system. The list of studied species is presented in accordance with the standards adopted in the International Plant Names Index (IPNI) (2025) database. For the analysis, “Flora Azerbaijan”(1961), “Conspect Flora of the Caucasus”(2012) were used. Biomorphological studies were carried out according to Serebryakova (1964) and C.R. Raunkiaer (1934), areological studies were carried out according to Portenier (2000). Phenological observations on plants in nature were carried out according to the method of I.N. Beideman(1974).

In this work, geographical (Grossheim 1936); ecological (Shennikov 1964) methods were widely used. Ecological analysis was carried out in relation to species to environmental factors, presumably the most significant for the taxon under study: 1) habitat moisture, 2) habitat salinization, 3) habitat mechanical composition, 4) anthropogenic factor.

Results and discussion

The species of the genus *Centaurea* L. in Azerbaijan are widely distributed across various mountain belts, soil types, and vegetation covers that have developed under broad ecological amplitudes. In studying the ecological characteristics of *Centaurea* L. species, the influence of diverse ecological factors has been identified.

With respect to light requirements, the species are classified into three groups: heliophytes, heliosiciophytes and sciophytes. The majority of the investigated species belong to heliophytes.

Ecological observations have shown that most species are xerophytes, preferring open habitats. The genus *Centaurea* L. is dominated by steppe plants. Depending on the habitat conditions, we distinguish 5 ecological-cenotic groups with different ecological confinement.

- Forest species - The ecological niche they occupy is forests, their edges, clearings. This is *C.transcaucasica* S.ex G., *C.salicifolia* M.B., *C.hyracnica* J.B., *C.ossetica* D.;
- Steppe species-*C.Alexandri* Bordz., *C.ruthenica* Lam., *C. Razdorskyi* Karjag., *C.depressa* M.B., *C.rhizantha* C.A., *C.oltensis* D., *C.carduiformis* D.;
- Meadow species-*C.leuzeoides* (J.et S.), *C.fischeri* W., *C.acmophylla* B., *C.ovina* P., *C.aggregata* F.et M., *C. Squarrosa* W., *C.reflexa* L., *C.sosnowskyi* A.Gr., *C.glehnii* T., *C.pseudoscabiosa* B., *C.apiculata* L.;
- Desert species-*C.kobstanica* T., *C.arenaria* M.B., *C. diffusa* L., *C.adpressa* L.;
- Inhabitants of fields, gardens and orchards (apophytes)- *C.cyanus* L., *C.solstitialis* L., *C.iberica* T.

The ecological spectrum data indicate that the representatives of the genus *Centaurea* L. are mainly confined to steppe (24%) and meadow (37.9%) phytocenoses.

According to their relation to moisture, the species of this genus can be divided into three ecological groups: mesophytes, mesoxerophytes and xerophytes, with xerophytes being the most dominant. Based on soil nutrient availability, these species are considered eutrophic and mesotrophic plants. They are predominantly distributed in calcareous soils, thus characterized as calciphilous. According to K.R. Raunkjer's classification, the life forms of the genus *Centaurea* L. are grouped into hemicryptophytes and therophytes. Within this framework, two species, *C.cyanus* and *C.bruguieriana*, are identified as therophytes, while the remaining species are hemicryptophytes. To clarify the distribution patterns depending on altitude, we used the section of L.I. Prilipko (1970). Annuals and biennials are found mainly in the lower mountain belts, while perennials are found in various belts (Figure 2).




Figure 2. Altitudinal distribution of *Centaurea* L. species

The practical significance of the species of the genus *Centaurea* L. lies in their decorative, honey-bearing, and medicinal properties. Various representatives of the genus have long been used in folk medicine as anti-inflammatory and pain-relieving agents, as well as for nervous cardiovascular diseases, diabetes, and for the resorption of tumours.

References

- Angiosperm Phylogeny Group. (2024). An update of the Angiosperm Phylogeny Group classification for the orders and families of flowering plants:APG IV Botanical Journal of the Linnean Society, No 181 (1), pp.http://doi.org/10.1111/boj.12385
- Askerov A.M.(2016). The flora of Azerbaijan .Baku:TEAS Press
- Beideman I.N.(1974). Methodology for studying the phenology of plants and plant communities Novosibirsk: Nauka. 153 p.
- Compendium of the Flora of the Caucasus:(2003-2012). Ed.Yu.L.Menitsky, T.N. Popova. St. Petersburg: St. Petersburg University.
- Flora of Azerbaijan.(1961) T. 8, Baku: From the Academy of Sciences of Azerbaijan. USSR
- Grossheim A.A. (1936).Plant resources of the Caucasus. Baku: Publishing house of the Academy of Sciences of the Azerbaijan SSR. 671 p.
- International Plant Names Index (IPNI)(2025)Available at: <https://www.ipni.org/>
- Mikheev A.D. (2000).Overview of the genus *Centaurea* L. (*Asteraceae*) flora of the Caucasus. Bot. Journal. №3
- Portenier N.N.(2000). Methodological issues of identifying geographical elements of the flora of the Caucasus. Botanical journal, v.85, no.6:76-84.
- Prilipko L.I.(1970). Vegetation cover of Azerbaijan.Baku.Elm
- Raunkiaer C. (1934).The life forms of plants and statistical plant geography. Oxford.p.48-154.
- Serebryakov I.G.(1964). Life forms of higher plants and their study. In the book: Field geobotany.Moscow: USSR Academy of Sciences. v.3:530 p
- Shennikov A.P.(1964). Introduction to Geobotany. Leningrad: Publishing House. Leningrad University. 447 p.
- World Flora Online.(2025). WFO. Available at http:// www.worldfloraonline.org

GOVERNANCE INSTITUTION QUALITY AND THE FDI–PRIVATE INVESTMENT
NEXUS: EVIDENCE FROM VIETNAMESE PROVINCES (2011–2020)

Le Thu Ha*, Nguyen Thanh Đạt*, Tran Thanh Khiet*

*Faculty of Economics, Nha Trang University

Abstract:

This paper investigates whether provincial governance institution quality moderates the impact of foreign direct investment (FDI) on private investment in Vietnam. Using a provincial panel dataset for 2011–2020, we estimate a dynamic model in which private investment (as a share of GRDP) depends on its own persistence, FDI inflows, governance quality, the interaction between FDI and governance, and standard provincial controls capturing local development conditions. Governance quality is measured by a composite indicator reflecting core dimensions of subnational institutions, including participation and accountability, transparency, corruption control, and administrative effectiveness. To address persistence, unobserved heterogeneity, and endogeneity between investment, FDI, and institutions, we employ a two-step System GMM estimator. The results show strong persistence in private investment and a positive average association of both FDI and governance quality with private investment. Importantly, the moderating role of governance is heterogeneous across provincial income groups: the FDI×governance interaction is positive for low- and middle-income provinces, indicating that stronger institutions help translate FDI into domestic investment expansion, but turns negative for high-income provinces, consistent with selective FDI screening and/or crowding-out or selection effects in more developed localities. Overall, the findings suggest that institutional reforms can enhance FDI spillovers to domestic investment, but policy design should be tailored to provincial development stages.

Keywords: Foreign direct investment (FDI), Private investment, Institutional quality, Provincial governance, System GMM

1. Introduction

Foreign Direct Investment (FDI) has had a strong influence on the global economy in recent years and is an important content for both developed and developing countries. FDI can affect the economy in all economic, cultural and social fields. However, for developing countries, especially poor countries, the biggest expectation of attracting FDI is mainly for economic growth. This expectation seems to be reflected in the minds of economists and policy makers for three main reasons: Firstly, FDI contributes to increasing capital account surplus, improves the balance of payments in general and macroeconomic stability. Second, developing countries often have low capital accumulation rates and therefore, FDI is considered an important source of capital to supplement domestic investment for economic growth. Third, FDI creates opportunities for poor countries to access more advanced technology, facilitate technology transfer, promote the dissemination of knowledge, improve management skills and labor qualifications, etc. This effect is seen as the productivity spillover effects of FDI, which contribute to the productivity increase of domestic firms and ultimately to economic growth in general. FDI inflows are a form of fixed investment of transnational business activities carried out mostly by multinational companies in which FDI enterprises benefit from brand promotion, marketing and selling products abroad,... (Agosin & Machado, 2005). The beneficial effects of FDI inflows in the host country are expected through transfer of management techniques,

capital accumulation, innovative capacity, grasp of technological know-how, and ultimately economic growth.

Therefore, countries around the world, notably developing countries, are always trying to adjust their policies and public administration accordingly to attract FDI inflows. Anh et al. (2006) gave a model (1.1) showing that the growth of an economy is determined by many different factors. However, the most important thing to draw from the model is that there is a direct relationship between FDI and economic growth. Through FDI, not only are many new capital goods created (increasing physical capital assets of the economy) but the cost to produce them is also reduced, thereby positively affecting economic growth. In addition, the growth rate is inversely proportional to the technology gap - in this model as measured by the ratio between the number of domestically produced capital goods and the capital goods produced in the developed world - between FDI recipient countries and developed countries. This effect represents a "catch-up" in economic growth for poorer countries compared to richer countries. The above effects are the reason why all countries are making great efforts to attract foreign direct investment, especially poor countries, and the model in (1.1) is the theoretical basis for assessing the impact of FDI on economic growth at the macro level.

$$G_y = G_{GDP} = \frac{1}{\theta} \left[\Omega \left(F \left(b, \frac{N}{N^*} \right) \right)^{-1} - \rho \right] \quad (1.1)$$

With $\Omega = x^*(i)(m^*(i) - 1)$ (1.2). G_y : Output growth rate; G_{GDP} : Growth rate of gross domestic product; θ : consumption elasticity of marginal utility and is constant; $x^*(i)$ is the demand for the i^{th} good at equilibrium; $m^*(i)$ is the rental price for the i^{th} capital good at equilibrium; F is the fixed cost; b is the number of capital goods produced in the receiving country by foreign firms; N is the total number of capital goods in the economy; N^* is the number of capital goods produced in the world, so N/N^* is the ratio of domestically produced capital goods to foreign production by foreign firms; ρ is the time preference ratio in terms of the benefits of consumption (high ρ : consumers value the benefits of current consumption higher than in the future, and vice versa).

Morrissey & Udomkerdmongkol (2012) emphasize that poor institutional governance (poor property rights and high corruption) discourages both FDI and domestic investment. Under poor governance environment, FDI inflows can win projects or investment opportunities of private investors, or FDI enterprises can compete for credit capital with private investment enterprises. On the contrary, under a good institutional governance environment, FDI inflows will be directed to investment projects that domestic enterprises are not able to implement due to low capital, low level of production technology and management low, especially good public governance environment will create conditions for cooperation between FDI enterprises and domestic private enterprises so that domestic enterprises can expand production, improve management capacity and production, increasing competitiveness. Morrissey & Udomkerdmongkol (2012) is also the first study in developing a theoretical framework to connect the trio of relationships between institutional governance, FDI and private investment. The two researchers argue that in the case that the institutional governance environment is not funding-friendly or hypothetical, in the future private investment contributing to domestic development will not be encouraged. At that time, domestic enterprises will have to find links with partners from abroad. Thus, FDI inflows will be a relatively important source of investment financing in institutional governance environments with poor public governance, especially with political instability.

2. Estimation model

Starting from the fact that the quality of institutional governance plays an important role in the impact of FDI on private investment, thereby affecting economic growth in Vietnam, this

study will empirically evaluate the impact of the quality of institutional governance, FDI and their interaction on private investment for a panel data sample of 63 provinces in Vietnam for the period 2011-2020 by using a two-step System GMM Arellano-Bond regression technique (SGMM two-step).

Because the model of factors affecting private investment is a dynamic model with the appearance of lagged private investment variables, the first-order lagged variable is included in equation to evaluate the real Experiencing the impact of institutional governance quality, FDI, and their interaction on private investment, we have equation (2.1) written as follows:

$$IP_{it} = \alpha_{it} + \beta_1 IP_{it-1} + \beta_2 FDI_{it} + \beta_3 PI_{it} + \beta_4 (FDI \times PI)_{it} + \beta_5' Z_{it} + \omega_i + \varepsilon_{it} \quad (2.1)$$

IP_{it} is the private

investment capital in %GRDP (unit %);

IP_{it-1} represents the initial private investment (unit %);;

FDI_{it} is the inflow of foreign investment in terms of %GRDP (unit %);;

Z_{it} : is a vector of control variables such as: G_{it} is per capita income (representing economic growth) (unit: million VND/person) and is used in logarithm; TEL_{it} is the infrastructure and is derived by the logarithm of the number of telephone subscribers per 100 inhabitants; $LABOR_{it}$ is calculated as the logarithm of the province's number of employees over 15 years old.

PI_{it} include of quality indicators of provincial governance institution indexes: DEMY_Democracy, CORN_Corruption, POLY_policy, PASE_Public administration and Public service (Government efficiency) and PGII_Provincial Governance Institution Index (synthesis of institutional aspects), These variables are taken from the provincial competitiveness index (PCI) and the Vietnam provincial governance and public administration performance index (PAPI) and are formed through EFA factor analysis; ω_i is the unobserved error (invariant over time, depending on the specific characteristics of each province); ε_{it} is the observed error.

3. Experimental results

3.1. The causal relationship between the quality of governance institutions and private investment

To assess the causal relationship between the quality of governance institutions and economic growth, this study will in turn perform the testing steps with the non-granger in heterogeneous panel data tests of Juodis et al., (2021).

With the array data approach, which combines cross-sectional data of 63 provinces of Vietnam and 10-year period data, this study has 630 observations, which is sufficient for econometric analysis. Table 3.1 is a descriptive statistic of the data.

Table 3.1 Descriptive statistic of variables

Variable	Obs	Mean	Std. Dev.	Min	Max
IP	630	34.50718	12.02113	10.83331	84.15045
FDI	630	7.427168	10.24805	0	69.72643
G	630	3.342261	.4973881	2.41189	5.234095
TEL	630	3.924348	.9146967	.3959505	6.253468
LABOR	630	6.550225	.556426	5.289933	8.453408
DEMY	626	1.571557	.5002197	0	2.302585
CORN	626	1.648933	.444867	0	2.302585
POLY	626	1.575589	.4453429	0	2.302585
PASE	626	1.537072	.4596469	0	2.302585
PGII	626	1.649444	.2389571	.3293037	2.207175
FDI_DEMY	626	12.63201	19.46127	0	153.2046
FDI_CORN	626	12.26648	18.45423	0	149.3585
FDI_POLY	626	12.2258	17.4776	0	124.933
FDI_PASE	626	12.85649	19.19023	0	144.992
FDI_PGII	626	12.92287	18.70966	0	141.1398

Note: The series of governance indicators includes 626 observations instead of 630 observations as expected due to missing data for some years of some provinces.

(Source: Author's calculations)

Looking at Table 3.1 we see that the average annual cumulative private investment in the 63 provinces in Vietnam in the sample is about 34.507%. The distribution of private investment among provinces is uneven as shown by the standard deviation (12.021) and the minimum and maximum values in the table.

Similarly, the annual net FDI inflows into the provinces average 7.427% and there is a big difference in attracting this inflow across provinces in Vietnam. Accordingly, the average deviation is over 10% with the maximum and minimum values being 69.726% and 0%, respectively. This shows that in some provinces, FDI attraction is quite strong, but at the same time in some provinces, the amount of FDI is zero.

To assess the causal relationship between the quality of governance institutions and investment private, the research will in turn perform the testing follow steps.

3.1.1. Cross-correlation and stationarity test of data series

Check cross-correlation according to Pesaran (2004)

The results of Table 3.2 show that p-values close to 0.000 in all variables, indicating that there is a dependence between the cross-observations in the panel data.

Table 3.2 Cross-correlation according to Pesaran (2004)

Variable	CD-test	p-value	average joint T	mean ρ	mean abs(ρ)
IP	+ 1.57	0.007	10.00	+ 0.01	0.44
FDI	+ 18.068	0.000	10.00	+ 0.14	0.42
G	+ 121.201	0.000	10.00	+ 0.91	0.93
DEMY	+ 28.695	0.000	10.00	+ 0.22	0.34
CORN	+ 32.988	0.000	10.00	+ 0.25	0.34
POLY	+ 18.327	0.000	10.00	+ 0.14	0.34
PASE	+ 17.126	0.000	10.00	+ 0.13	0.31
PGII	+ 32.482	0.000	10.00	+ 0.24	0.33

Notes: Under the null hypothesis of cross-section independence, $CD \sim N(0,1)$

P-values close to zero indicate data are correlated across panel groups.

(Source: Author's calculations)

Testing for stationarity of data series

To test the stationarity of panel data taking into account the dependence between cross-observations in the study sample, the authors propose Pesaran's CADF test according to Pesaran (2007). Pesaran's CADF test with hypothesis H_0 : The series is not stationary; H_1 : The sequence stops. Results Table 3.3 shows that all series are stationary at order $I(0)$ because all p-values < 0.05, hypothesis H_0 is rejected.

Table 3.3 Testing for stationarity of data series by Pesaran's CADF test

Variable	Pesaran's CADF			
	I(0)		I(1)	
	t-bar	p-value	t-bar	p-value
IP	-2.094	0.009	---	---
CORN	-2.709	0.000	---	---
POLY	-2.730	0.000	---	---
PGII	-2.389	0.000	---	---
DEMY	-2.286	0.000	---	---
PASE	-2.568	0.000	---	---

(Source: Author's calculations)

3.1.2. Co-integration test

Table 3.4 Co-integration test

Variable	Westerlund test for cointegration				
	Variance ratio				
IP	DEMY	CORN	POLY	PASE	PGII
	4.4408	4.9307	4.5253	4.3773	4.7381
	(0.0000)	(0.0000)	(0.0000)	(0.0000)	(0.0000)
	23.3699 (0.0000)				

Note: The number in quotation marks is p-value

(Source: Author's calculations)

To test the cointegration of panel data series, the author uses Westerlund (2009) test with the command `xtcointtest`. Hypothesis H0 is the sequence with no co-integration, H1 is the opposite hypothesis. Table 3.4 shows p-value < 0.05, so hypothesis H0 is rejected, so we can conclude that the series in the table are co-integrated.

3.1.3. Granger causality test heterogeneous table

In order for the data to be completely balanced for testing the causal relationship between governance institutions and private investment, the study removed 3 provinces.

The main results presented in Table 3.5 are the results for the entire sample of 60 provinces in Vietnam. The results show that there is a causal relationship between the institutional variables of governance and private investment at lags (1) to lags (2).

Table 3.5 Heterogeneous panel Granger causality tests

		(1)		(2)	
		All provinces			
		lnPI → lnGDP	Results	lnGDP → lnPI	Results
DEMY	HPJ Wald test	5.8964 (0.0152)	Causality	12.2818 (0.0005)	Causality
	Lags	(1)		(1)	
CORN	HPJ Wald test	59.9581 (0.0000)	Causality	8.7472 (0.0126)	Causality
	Lags	(2)		(2)	
POLY	HPJ Wald test	47.6239 (0.0000)	Causality	11.5346 (0.0031)	Causality
	Lags	(2)		(2)	
PASE	HPJ Wald test	46.2837 (0.0000)	Causality	24.2824 (0.0000)	Causality
	Lags	(2)		(1)	
PGII	HPJ Wald test	23.9448 (0.0000)	Causality	21.4486 (0.0000)	Causality
	Lags	(3)		(2)	

Note: The number in quotation marks is HPJ p-value

(Source: Author's calculations)

To test the causal effect between the quality of governance institutions and private investment, the author test the non-causal relationship between these variables with smaller samples divided by income level of groups of provinces in Vietnam. Column (1) is The low income provinces, column (2) is The middle income provinces and column (3) is The high income provinces. The results for the excluded sample shown in Table 3.6 are virtually unchanged from the total sample, differing only slightly in terms of lags. That is to support both research hypotheses, improved governance institutions contribute to investment private and vice versa. Even for the provinces that have low income or middle income level, a causal

relationship between governance institutions and investment private still exists and has a two-way effect. However, due to the limitation of the number of research years being too short, the study could not determine the long-term impacts between institutional governance and investment private. The study can only show that there is a causal relationship between institutional quality and investment private in Vietnam.

According to Wilson's (2016) approach, a homogenous causality test was performed with the parameters considered to be the same in all provinces. The results shown in Table 3.7 show that previous results are supported, but with lower significance in most institutional dimensions.

3.1.4. Durbin-Wu-Hausman test

From the above causality test results, it is possible that endogenous variables appear in the research model. To confirm more firmly about endogenous variables, the procedural Durbin-Wu-Hausman test proposed by Davidson and MacKinnon (1993) also gives the conclusion about the possibility of endogenousness of all 5 governance variables in the research model with hypothesis H0: variables are exogenous, with all p-value<0.05 so hypothesis H0 rejected, from which we can conclude that the institutional variables are endogenous variables in the research model (Table 3.8).

Table 3.6 Robustness checks Heterogeneous panel Granger causality tests

			(1)		(2)		(3)					
			PI→IP	R	IP→PI	R	PI→IP	R	PI→IP	R	IP→PI	R
DEMY	HPJ	Wald	12.9351	C	11.9399	C	5.1007	C	8.2399	C	92.8733	C
		test	(0.0003)		(0.0076)		(0.0239)		(0.0041)		(0.0000)	
			Lags (1)		Lags (3)		Lags (1)		Lags (1)		Lags (3)	
CORN	HPJ	Wald	7.1065	C	18.4937	C	7.3719	C	2.8208	C	8.7416	C
		test	(0.0077)		(0.0000)		(0.0066)		(0.0430)		(0.0329)	
			Lags (1)		Lags (1)		Lags (1)		Lags (1)		Lags (3)	
POLY	HPJ	Wald	13.7360	C	38.2917	C	47.8067	C	3935.9	C	14.0165	C
		test	(0.0002)		(0.0000)		(0.0000)		(0.0000)		(0.0002)	
			Lags (1)		Lags (3)		Lags (3)		Lags (2)		Lags (1)	
PASE	HPJ	Wald	28.8978	C	14.4437	C	3.6614	C	9.4810	C	36.3991	C
		test	(0.0000)		(0.0001)		(0.0160)		(0.0021)		(0.0000)	
			Lags (2)		Lags (1)		Lags (2)		Lags (1)		Lags (2)	
lnPGII	HPJ	Wald	25.3374	C	5.69317	C	19.2683	C	9.4864	C	13.7425	C
		test	(0.0000)		(0.0170)		(0.0002)		(0.0021)		(0.0010)	
			Lags (1)		Lags (1)		Lags (3)		Lags (1)		Lags (2)	

Note: *R* _result, *C* _causality; the number in quotation marks is HPJ *p* _value

((Source: Author's calculations)

Table 3.7 Homogenous causality test

Variable		All provinces			
		IP→PI	Result	PI→IP	Result
DEMY	Chi2 statistic	4.9833	C	4.7060	C
		(0.007)		(0.009)	
	Lags	(2)		(2)	
CORN	Chi2 statistic	4.9222	C	4.0544	C
		(0.026)		(0.044)	
	Lags	(2)		(2)	
POLY	Chi2 statistic	4.4342	C	5.7856	C
		(0.004)		(0.000)	
	Lags	(3)		(3)	
PASE	Chi2 statistic	3.2669	C	5.2440	C
		(0.021)		(0.001)	

PGII	Lags	(3)	C	(3)	C
	Chi2 statistic	2.8264		3.3294	
		(0.038)		(0.019)	
	Lags	(3)		(3)	

Note: C_causality; the number in quotation marks is p_value

((Source: Author's calculations))

Table 3.8 Tests of endogeneity

Variable	Durbin Wu-Hausman	
	Chi - sq (score)	Result
DEMY	4.1124 (0.0426))	endogeneity
CORN	3.9082 (0.0454)	endogeneity
PASE	3.2903 (0.0482)	endogeneity
POLY	4.4075 (0.0387)	endogeneity
PGII	3.7092 (0.0490)	endogeneity

((Source: Author's calculations))

3.2. Impact of institutional quality of governance and FDI on private investment

3.2.1. Research results for main sample

The main sample includes 63 provinces in Vietnam for the period 2011-2020. Based on the results of confirming the Granger two-way causality relationship of institutional governance quality with private investment and Durbin Wu-Hausman test in Table 3.8, the study goes into empirical assessment of the impact of institutional governance quality, FDI with the corresponding variable their effect on private investment.

The study considers the appropriateness of the estimated model as follows:

According to the Durbin Wu-Hausman test in Table 3.8, the institutional governance variable causes endogenous phenomena in the research model. Therefore, the governance institution variable is used as the instrumented variable (declared in the SGMM two-step regression) and the remaining variables in the model such as private investment, FDI inflows, infrastructure, labor and other institutional variables... will be used as instrument variables.

Accept the hypothesis that there is no endogenous phenomenon in Hansen's test with p-values>0.1 for each component of institutional quality. Accept the hypothesis that there is no quadratic series correlation in the AR(2) test with p-values>0.1 for each component of institutional quality. The number of instrumental variables are all smaller than the number of provinces, "rules of thumb" (Roodman 2009) is guaranteed.

The results of the estimates for the main sample are shown in Table 3.9 with five columns of results for each component governance variable.

The results of the estimates for the main sample shown in Table 3.9 show that FDI inflows and governance quality also have a significant positive effect on private investment, especially consistent for all 5 component governance institutional variables. Similarly, the interaction variable between FDI investment and the quality of governance institutions also has a significant positive effect on private investment.

The significant positive index effect of FDI on private investment supports the motivating hypothesis developed in the theoretical framework of Agosin & Machado (2005). Accordingly, FDI inflows to the provinces increase private investment through the transfer of technological know-how in production and management, joint ventures in production activities, etc. This result is also completely consistent with previous studies such as Ndikumana & Verick (2008), Ang (2009), Ang (2010), Al-Sadig (2013), and Ali et al. (2015).

The significant positive index effect of governance institution quality on private investment implies that a good governance institutional environment will promote stronger private investment. This finding is consistent with some previous studies (Feng, 2001; Munemo, 2012).

Similarly, the interaction variable between FDI investment and the quality of governance institutions also has an impact on promoting private investment. This effect comes from two effects when the quality of governance institutions is improved, direct effect and indirect effect. The direct effect comes from the positive effect of governance institution quality on private investment (see Table 3.9). Indirect effects occur through FDI inflows. Accordingly, the increased quality of governance institutions will promote FDI inflows because the good institutional governance environment creates favorable conditions for the cross-border investment activities of FDI enterprises (Jadhav & Katti, 2012; Bannaga et al., 2013; Gani & Al-Abri, 2013; Buracom, 2014; Rashid et al., 2017). The increase in FDI inflows in turn promotes private investment (see Table 3.9). Therefore, the indirect effect of the quality of governance institutions also promotes private investment. The combined effect of improving the quality of governance institutions from direct effects and indirect effects ultimately promotes private investment. In summary, the interaction variable of FDI with the quality of governance institutions has a positive effect on private investment.

Table 3.9 Impact of institutional quality of governance and FDI on private investment in the main sample

Institutional variable	DEMY	CORN	POLY	PASE	PGII
L.IP	0.7633*** (0.0370)	0.9281*** (0.0471)	0.8719*** (0.0591)	0.7578** (0.0623)	0.7630*** (0.0661)
FDI	1.4631* (0.7585)	0.0137*** (0.4060)	1.7092* (0.2547)	2.3654* (0.0161)	3.0324** (0.8696)
Institutional variable	4.1640* (0.1411)	1.0669*** (0.7584)	3.9379* (0.3081)	5.8241* (0.0275)	10.8066** (0.6113)
FDI_Institutional variable	0.8062* (0.4125)	0.0737** (0.2380)	1.0708* (0.7481)	1.2626** (0.0570)	1.8482* (0.0192)
G	2.3012* (0.1978)	0.7975 (0.2853)	0.0704* (0.3979)	3.4882* (0.7604)	-0.2659 (0.3663)
TEL	0.3151* (0.5577)	-0.0606 (0.3878)	0.1368 (0.4711)	0.4431 (0.8883)	0.5404 (0.5536)
LABOR	-0.5413 (0.7704)	0.0770* (0.6167)	-1.1994 (0.4147)	-1.2997 (0.1637)	-0.4082 (0.3786)
_cons	11.1221** (0.5980)	-1.4796 (0.0844)	6.1931** (0.9372)	1.1495** (0.1637)	2.3982** (0.6415)
N	492	492	431	496	492
Number of groups	63	63	63	63	63
Instruments	13	13	13	13	13
AR (1) p-value	0.024	0.069	0.061	0.051	0.004
AR (2) p-value	0.911	0.627	0.976	0.551	0.834
Hansen p-value	0.159	0.137	0.245	0.251	0.138

*Note: Standard errors in parentheses; * $p < 0.10$, ** $p < 0.05$, *** $p < 0.01$*

(Source: Author's calculation)

The research results in the main sample of this research are different from the results of Morrissey & Udomkerdmongkol (2012). Accordingly, Morrissey & Udomkerdmongkol (2012) showed that FDI inflows have a negative effect while the quality of governance institutions has

a positive effect on private investment. In particular, the interaction variable between FDI and the quality of governance institutions overrides private investment in the case of governance institutions such as voice and accountability, rule quality, rule of law and control corruption but promotes private investment in the case of political stability. In contrast, Farla et al. (2016) shows that both FDI inflows and institutional quality promote private investment, similar to the results for the overall sample in this study.

3.2.2. Research results for subsamples

Similar to the main sample, the Hasen test and AR(2) of the 3 subsamples all have $p\_value > 0.1$ and Roodman's rules of thumb (2009) is guaranteed, so the suitability of the SGMM two-step estimation method are confirmed.

The subsample is divided by income level of the provinces, including: high-income provinces, middle-income provinces and low-income provinces. The results of the estimates for the sub-sample are shown in Tables 3.10 with 3.11 and 3.12 with 5 columns of results for each component governance variable. From the results presented in Table 3.10, Table 3.11 and Table 3.12, the study draws comments, specifically as follows:

The qualitative impact of institutional quality of governance and FDI inflows on private investment in the three sub-samples is completely similar to that in the main study sample, confirming the quality of institutional governance and consistent FDI inflows promote private investment in high-income, middle-income and low-income provinces in Vietnam.

Similarly, the interaction variable between the quality of institutional governance and FDI inflows in the sample of low- and middle-income provinces also promotes private investment, completely similar to the main sample (Table 3.11 and 3.12).

Table 3.10 Impact of institutional quality of governance and FDI on private investment in high-income provinces

Institutional variable	DEMY	CORN	POLY	PASE	PGII
L.IP	0.7012*** (0.0395)	0.8316*** (0.0403)	0.7497*** (0.0565)	0.9244*** (0.0334)	0.8582*** (0.0638)
FDI	0.1378** (0.2875)	1.0751*** (0.3661)	1.1816** (0.6053)	1.0334* (0.7605)	4.1379** (0.7758)
Institutional variable	0.2966* (0.9551)	9.4264*** (0.7577)	1.7982** (0.0091)	1.1397** (0.1511)	2.3962** (0.9760)
FDI_Institutional variable	-0.0844* (0.1633)	-0.6845*** (0.2145)	-0.7003* (0.9366)	-0.5396* (0.3792)	-2.2905** (0.9901)
G	3.4410** (0.4151)	2.4546** (0.1426)	2.5294* (0.2551)	1.0072* (0.3636)	1.0979** (0.4205)
TEL	0.3798** (0.4820)	0.0317 (0.3170)	0.6836 (0.5607)	0.0388 (0.6743)	-1.0208 (0.2252)
LABOR	0.0238 (0.5071)	0.3682 (0.4949)	-1.7315 (0.6254)	1.1047* (0.5814)	-0.3645 (0.7598)
_cons	1.1594*** (0.6019)	3.1209* (0.3236)	4.7028 (0.9464)	1.1792* (0.8237)	-2.9701 (0.9389)
N	157	157	158	157	178
Number of groups	20	20	20	20	20
Instruments	13	13	13	13	13
AR (1) p-value	0.022	0.019	0.022	0.017	0.015
AR (2) p-value	0.488	0.702	0.420	0.770	0.187
Hansen p-value	0.190	0.681	0.622	0.639	0.282

*Note: Standard errors in parentheses; * $p < 0.10$, ** $p < 0.05$, *** $p < 0.01$*

(Source: Author's calculation)

In contrast, in the sample of high-income provinces, this interaction variable has a negative effect on private investment. To explain this difference, the author also focuses on the

impact of the quality of governance institutions when improved. When the quality of governance institutions increases, there will be two effects on private investment, direct effect and indirect effect. Direct effects are the positive effects of institutional governance quality on private investment (see Table 3.10). Meanwhile, Ajide & Raheem (2016) provide quality evidence that increased institutional governance can reduce the amount of FDI. The decrease in FDI capital led to a decrease in private investment (see Table 3.10). This means that an increase in the quality of institutional governance can have an indirect effect of reducing private investment. In the case of high-income provinces, the direct effect may be smaller than the indirect effect. Therefore, the aggregate effect of institutional governance quality on private investment from the direct effect and the indirect effect is negative. This means that the interaction variable between the quality of institutional governance and FDI in high-income provinces reduces private investment.

Thus, there is a difference in the impact of the interaction variable between FDI and the quality of institutional governance on private investment between the group of low-income, middle-income provinces and the group of high-income provinces. Research results show that this difference is due to the difference in the quality of the institutional governance environment among these groups of provinces. Accordingly, the quality of institutional governance in the group of high-income provinces is generally better than that of the group of low- and middle-income provinces. Under such an institutional environment, the group of high-income provinces seems to selectively attract FDI inflows, they have the right to choose to receive high-quality, environmentally friendly FDI flows. In contrast, the group of middle- and low-income provinces are ready to receive all incoming FDI with the goal of creating more jobs, even though these foreign direct investment inflows can be harmful to the environment living. Therefore, when the quality of institutional governance increases, the interaction variable in the group of high-income provinces tends to decrease private investment while in the group of low- and middle-income provinces, it increases investment private private.

The positive effect of economic growth on private investment can be seen in previous studies on the same topic such as Ndikumana & Verick (2008), Ang (2010), Al-Sadig (2013), and Chen et al. (2017). Economic growth leads to higher domestic incomes and also increases in savings. This savings is the source of funding for investments in the private sector.

Table 3.11 Impact of institutional quality of governance and FDI on private investment in middle-income provinces

Institutional variable	DEMY	CORN	POLY	PASE	PGII
LIP	0.7960*** (0.0709)	0.7531*** (0.0856)	0.4769*** (0.1278)	0.6669*** (0.0622)	0.6792*** (0.0842)
FDI	3.1551*** (0.9596)	2.5424** (0.9213)	8.2544*** (0.7176)	2.2820*** (0.6217)	5.8974** (0.6918)
Institutional variable	4.4548** (0.8073)	9.4876*** (0.2487)	12.4577** (0.8160)	0.7296* (0.5260)	1.1395* (0.2909)
FDI_Institutional variable	1.5172*** (0.4617)	1.4750*** (0.4453)	5.1273*** (0.2050)	1.2739*** (0.3663)	3.4446** (0.4190)
G	3.2108* (0.7893)	-3.3737 (0.8599)	0.8369 (0.3607)	-2.3943 (0.6633)	-0.2165 (0.1402)
TEL	1.9249 (0.1717)	0.8511* (0.5887)	2.1748 (0.9665)	1.8491*** (0.5587)	-0.6599 (0.5532)
LABOR	0.9074 (0.7265)	-0.1953 (0.2777)	-4.1611 (0.9455)	-1.3933 (0.9978)	5.9667* (0.3201)
_cons	-5.9810 (0.4737)	3.1778** (0.4633)	1.3336* (0.6339)	1.5510** (0.2608)	4.2695** (0.1425)
N	167	167	143	167	192
Number of groups	22	22	22	22	22
Number of instruments	13	13	13	13	13

AR (1) p-value	0.112	0.040	0.071	0.261	0.054
AR (2) p-value	0.749	0.835	0.110	0.392	0.516
Hansen p-value	0.291	0.182	0.228	0.257	0.291

Note: Standard errors in parentheses; * $p < 0.10$, ** $p < 0.05$, *** $p < 0.01$

(Source: Author's calculation)

Table 3.12 Impact of institutional quality of governance and FDI on private investment in low-income provinces

Institutional variable	DEMY	CORN	POLY	PASE	PGII
L.IP	0.8412*** (0.0668)	0.7042*** (0.0854)	0.6803*** (0.0661)	0.8513*** (0.0856)	0.6723*** (0.0540)
FDI	3.6538*** (0.1858)	4.5034* (0.2766)	3.1128** (0.1170)	2.5627** (0.0125)	7.9613*** (0.7374)
Institutional variable	4.7968* (0.6267)	3.1444* (0.2406)	3.0004* (0.5954)	4.8883*** (0.6757)	9.0484*** (0.9676)
FDI_Institutional variable	2.1432*** (0.7233)	2.2291* (0.1559)	1.5911** (0.6580)	1.3927** (0.5088)	4.3569** (0.5095)
G	3.7685 (0.7131)	0.2075 (0.4770)	2.1834* (0.6282)	3.7474 (0.6155)	4.6959** (0.0603)
TEL	-2.2144* (0.1282)	1.3342* (0.4819)	1.7367 (0.1336)	1.5238* (0.7883)	-0.4143 (0.9982)
LABOR	3.2423* (0.6619)	-4.2130 (0.9718)	4.9439* (0.4792)	-0.8497 (0.2560)	-0.7073 (0.4383)
_cons	2.8302* (0.7265)	2.1806* (0.9034)	3.3010** (0.7495)	1.9637* (0.9538)	1.0962*** (0.2971)
N	168	168	168	168	168
Number of groups	21	21	21	21	21
Number of instruments	13	13	13	13	13
AR (1) p-value	0.012	0.027	0.126	0.007	0.001
AR (2) p-value	0.866	0.155	0.224	0.151	0.310
Hansen p-value	0.732	0.127	0.220	0.161	0.284

Note: Standard errors in parentheses; * $p < 0.10$, ** $p < 0.05$, *** $p < 0.01$

(Source: Author's calculation)

4. Results and discussions

Stemming from the fact that the quality environment of institutional governance plays a very important role in the relationship between foreign direct investment (FDI) and private investment, this chapter explores the causal relationship between institutional variables and private investment, the results show that there is a two-way causal relationship between these variables in both the total sample and the unity in the subsample. Based on these results, the authors empirically evaluate the quality impact of institutional governance, FDI inflows and their interactions on private investment for a panel dataset of 63 provinces in Vietnam in the past year period 2011 - 2020 through the two-step SGMM regression technique. In addition, these effects are also compared for the study samples including the main sample of 63 provinces and three sub-samples, sample of high-income provinces, sample of middle-income provinces and low-income provinces. The estimated results in all four samples show that the quality of institutional governance and FDI inflows promote private investment in all four samples. However, the interaction variable between institutional governance quality and FDI inflows has a different effect on private investment among the studied samples. Accordingly, this variable has a positive effect on private investment in the main sample and the sample of middle and low income provinces, while in the sample of high income provinces, this variable has a negative effect.

These findings provide several policy implications for provinces in Vietnam as follows:

The government needs to reform the environment of institutional governance in particular and improve the quality of institutional governance in general to create a favorable environment to attract foreign direct investment (FDI), because this capital inflow has the effect of promoting investment in the private sector.

Provinces should aim to improve local economic activities, in order to promote economic growth, which in turn helps increase private investment, so that private investment activity will promote economic growth economic growth of the province.

Implement the open-door policy through the issuance of appropriate policies and regulations, creating conditions for businesses in the province to promote their strengths and promote local strengths in order to gain revenue attract investment capital sources not only in the country but also abroad.

5. Limitations and research futures

This study has some limitations that need further research in the future. First, perception-based metrics are controversial and lack information, some aspects of the measure may become outdated over time, thus may not really reflect the institutional quality of Vietnam today and further research could update the data. Second, the model used in this study has the disadvantage that there is a cross-dependency between localities, which can be overcome by using spatial econometric models besides array data models. Third, after testing the causal relationship between economic growth and institutional quality, the study proceeds in the direction of assessing the impact of institutional quality on growth with the control of endogenous variables, without exploiting it opposite direction. Building a model to evaluate factors (including growth) affecting institutional quality will be an interesting topic and is based on institutional economic theory rather than growth theory economic growth in this study. Last, this study is purely from a quantitative perspective with new points in the way the index is built and the estimation method. Therefore, the results mainly confirm the positive impact of institutions on economic growth, which may not bring much debate about policy implications.

References

- [1] Agosin, M., Machado, R., Foreign investment in developing countries: Does it crowd in domestic investment? Oxford Development Studies, 2005, 33(2): 149-162
- [2] Anh, N.T.T., Hong, V.X.N., Thang, T.T., Hai, N.M., Impact of foreign direct investment on Vietnam's economic growth. 2006, SIDA Project: Improving policy research capacity to implement Vietnam's socio-economic development strategy for the 2001-2010 period
- [3] Ang, J. B., Do public investment and FDI crowd in or crowd out private domestic investment in Malaysia?. Applied Economics, 2009, 41(7): 913-919
- [4] Ali, S. A., Raza, H., Iqbal, A., Dynamic linkages between foreign direct investment, public investment and private domestic investment: Evidence from Pakistan. Pakistan Business Review, 2015, 740: 789-807
- [5] Al-mulali, U., Tang, C. F., Investigating the validity of pollution haven hypothesis in the gulf cooperation council (GCC) countries. Energy Policy, 2013, 60: 813-819
- [6] Ang, J. B., Determinants of private investment in Malaysia: what causes the postcrisis slumps?. Contemporary Economic Policy, 2010, 28(3): 378-391
- [7] Bannaga, A., Gangi, Y., Abdrazak, R., Al-Fakhry, B., The effects of good governance on foreign direct investment inflows in Arab countries. Applied Financial Economics, 2013, 23(15), 1239-1247
- [8] Buracom, P., ASEAN Economic Performance, Institutional Effectiveness, and Foreign Direct Investment. Asian Affairs: An American Review, 2014, 41(3): 108-126
- [9] Chen, G. S., Yao, Y., Malizard, J., Does foreign direct investment crowd in or crowd out private domestic investment in China?. The effect of entry mode. Economic Modelling, 2017, 61: 409-419.

- [10] Davidson, R., MacKinnon, J. G., Estimation and inference in econometrics. Oxford University Press, 1993
- [11] Farla, K., De Crombrughe, D., Verspagen, B., Institutions, foreign direct investment, and domestic investment: crowding out or crowding in? *World Development*, 2016, 88: 1-9
- [12] Feng, Y., Political freedom, political instability, and policy uncertainty: a study of political institutions and private investment in developing countries. *Int. Stud. Q.*, 2001, 45 (2): 271–294
- [13] Gani, A., Al-Abri, A. S., Indicators of business environment, institutional quality and foreign direct investment in Gulf Cooperation Council (GCC) countries. *International Review of Applied Economics*, 2013, 27(4): 515-530
- [14] Jadhav, P., Katti, V., Institutional and political determinants of foreign direct investment: Evidence from BRICS economies. *Poverty & Public Policy*, 2012, 4(3): 49-57
- [15] Juodis, A., Y. Karavias, V. Sarafidis, A homogeneous approach to testing for Granger non-causality in heterogeneous panels. *Empirical Economics*, 2021, 60: 93–112
- [16] Morrissey, O., Udomkerdmongkol, M., Governance, private investment and foreign direct investment in developing countries. *World development*, 2012, 40(3): 437-445
- [17] Munemo, J., Entrepreneurship in developing countries: Is Africa different?. *Journal of Developmental Entrepreneurship*, 2012, Vol. 17, No. 01: 1250004-1-1250004-12
- [18] Ndikumana, L., Verick, S., The linkages between FDI and domestic investment: Unravelling the developmental impact of foreign investment in Sub-Saharan Africa. *Development Policy Review*, 2008, 26(6): 713-726
- [19] Pesaran, M. H., A simple panel unit root test in the presence of cross- section dependence. *Journal of Applied Econometrics*, 2007, 22(2):265–312
- [20] Wilson, R., Does Governance Cause Growth? Evidence from China. *World Development*, 2016, Vol. 79: 138-151
- [21] Rashid, M., Looi, X. H., Jye, W. S., Political stability and FDI in the most competitive Asia Pacific countries. *Journal of Financial Economic Policy*, 2017, 9(2): 1-20

**24 GHZ DİKEY VİVALDİ ANTEN KULLANILARAK SAĞLIKLI VE KANSERLİ
HÜCRE TABAKALARININ ELEKTROMANYETİK KARAKTERİZASYONU**
ELECTROMAGNETIC CHARACTERIZATION OF HEALTHY AND CANCEROUS
CELL LAYERS USING A 24 GHZ VERTICALLY POLARIZED VIVALDI ANTENNA

Mahammad ISAYEV

Doktora Öğrencisi, Konya Teknik Üniversitesi, Mühendislik ve Doğa Bilimleri Fakültesi,
Elektrik-Elektronik Anabilim Dalı

Seyfettin Sinan GÜLTEKİN

Doç. Dr., Konya Teknik Üniversitesi, Mühendislik ve Doğa Bilimleri Fakültesi,
Elektrik-Elektronik Anabilim Dalı

ÖZET

Elektromanyetik yöntemler, biyolojik dokuların dielektrik özelliklerindeki farklılıkları algılayabilmeleri sayesinde non-invaziv kanser tanısı için güçlü bir alternatif sunmaktadır. Özellikle milimetre dalga frekansları, kısa dalga boyları sayesinde hücresel düzeydeki ince yapısal değişimlere karşı yüksek duyarlılık göstermektedir. Bu çalışmada, 24 GHz merkez frekansında çalışan dikey polarizasyonlu bir Vivaldi anten tasarlanmış ve sağlıklı epitel hücreleri ile LA7 adenokarsinom hücre tabakalarının elektromanyetik tepkileri karşılaştırmalı olarak incelenmiştir.

Anten, Rogers RT/duroid 5880 substratı üzerinde tasarlanmış ve 20–37 GHz aralığında kararlı geniş bant performansı sağlayacak şekilde optimize edilmiştir. Hücre tabakaları cam lam üzerine modellenmiş ve antenlerin reaktif yakın alan bölgesinde, elektrik alan yoğunluğunun maksimum olduğu konuma yerleştirilmiştir. Sağlıklı ve kanserli hücrelere ait frekansa bağlı dielektrik parametreler literatürden alınarak simülasyon ortamına aktarılmıştır.

Elde edilen sonuçlar, tüm senaryolarda S_{11} değerlerinin -20 dB'in altında kaldığını ve antenin biyolojik yüklemelere rağmen empedans kararlılığını koruduğunu göstermiştir. S_{21} analizleri ise hücre tabakaları arasında belirgin farklar ortaya koymuş; özellikle 24–26 GHz bandında kanserli hücre tabakasının daha yüksek iletim değerleri sergilediği gözlemlenmiştir. ΔS_{21} parametresi 24.412 GHz civarında maksimum $+1.48$ dB değerine ulaşmıştır.

Anahtar Kelimeler: Vivaldi anten, milimetre dalga, elektromanyetik doku analizi, S_{21} , ΔS_{21} , LA7 hücreleri

Abstract

Electromagnetic sensing techniques have emerged as promising non-invasive tools for cancer diagnostics due to their sensitivity to variations in the dielectric properties of biological tissues. In particular, millimeter-wave frequencies offer enhanced spatial resolution, enabling the detection of subtle cellular-level differences. In this study, a vertically polarized Vivaldi antenna operating at 24 GHz is designed and employed to comparatively analyze the electromagnetic responses of healthy epithelial cell layers and LA7 adenocarcinoma cell layers. The antenna is fabricated on a Rogers RT/duroid 5880 substrate and optimized to achieve stable broadband performance over the 20–37 GHz frequency range. The biological samples are modeled on a glass slide and positioned within the antenna's reactive near-field region, where the electric field intensity is maximized. Frequency-dependent dielectric properties of healthy and cancerous cells are incorporated into the simulation model based on reported literature values.

Simulation results demonstrate that the reflection coefficient S_{11} remains below -20 dB across all loading scenarios, confirming robust impedance matching even in the presence of biological materials. Transmission coefficient (S_{21}) analysis reveals a clear distinction between the two cell types, with the LA7 cancerous layer exhibiting higher transmission levels, particularly in the 24–26 GHz band. The maximum discriminatory response is observed in the ΔS_{21} spectrum, reaching approximately $+1.48$ dB at around 24.412 GHz.

Keywords: Vivaldi antenna, millimeter-wave sensing, dielectric properties, S_{21} , ΔS_{21} , LA7 cells

1. GİRİŞ

Kanser, hücresel düzeyde ortaya çıkan yapısal ve fizyolojik değişimlerle karakterize edilen ve dünya genelinde yüksek mortalite oranlarına sahip bir hastalıktır. Erken evrede teşhis edilebilmesi, tedavi sürecinin başarısını doğrudan etkilediğinden, güvenilir ve non-invaziv tanı yöntemlerine olan ihtiyaç her geçen gün artmaktadır. Günümüzde kullanılan konvansiyonel görüntüleme teknikleri yüksek uzaysal çözünürlük sunsa da, iyonize radyasyon içermeleri, yüksek maliyetleri ve sınırlı erişilebilirlikleri nedeniyle alternatif ve tamamlayıcı biyofiziksel yaklaşımların geliştirilmesi önemini korumaktadır [12], [15], [29]–[33].

Bu bağlamda, mikrodalga ve milimetre dalga tabanlı biyomedikal algılama yöntemleri; iyonize olmayan yapıları, düşük güç seviyelerinde çalışabilmeleri ve hızlı ölçüm imkânı sunmaları nedeniyle son yıllarda önemli bir araştırma alanı hâline gelmiştir. Biyolojik dokuların elektromanyetik davranışı, başta bağıl dielektrik sabiti (ϵ_r) ve iletkenlik olmak üzere elektriksel özelliklerine doğrudan bağlıdır. Literatürde, malign hücre ve dokuların artan su ve iyon içeriği nedeniyle sağlıklı karşılıklarına kıyasla daha yüksek dielektrik değerlere sahip olduğu ve bu farkın elektromanyetik ölçümlerde anlamlı bir kontrast oluşturduğu tutarlı biçimde rapor edilmiştir [12], [16], [31], [32].

Geniş bant dielektrik karakterizasyon çalışmalarında, bu kontrastın frekansa bağlı olduğu ve özellikle daha yüksek frekanslarda biyolojik yapıların elektromanyetik tepkilerinin daha belirgin hâle geldiği gösterilmiştir [12], [14], [16]. Bununla birlikte, biyolojik ortamların dielektrik özelliklerini belirlemede yaygın olarak kullanılan açık uçlu koaksiyel prob gibi temaslı yöntemler; prob–numune temas kalitesi, yüzey pürüzlülüğü ve doku heterojenliği gibi faktörlere duyarlıdır ve ölçüm tekrarlanabilirliğini sınırlayabilmektedir [13]. Bu nedenle, temassız veya yarı-temassız ölçüm geometrilerine dayalı iletim tabanlı yaklaşımlar giderek daha fazla ilgi görmektedir.

Mikrodalga ölçüm sistemlerinde saçılma parametreleri (S-parametreleri), ölçüm ortamının elektromanyetik özelliklerini değerlendirmek için güçlü bir araç sunmaktadır. Özellikle iletim katsayısı olan S_{21} parametresi, ortamın efektif dielektrik özelliklerindeki değişimlere karşı yüksek hassasiyet göstermesi nedeniyle biyomedikal algılama uygulamalarında öne çıkmaktadır. Sağlıklı ve kanserli hücre veya dokular arasında oluşan S_{21} farklarının karşılaştırmalı olarak değerlendirilmesine dayanan ΔS_{21} yaklaşımı, elektromanyetik ayırt ediciliği artıran etkili bir yöntem olarak literatürde yer almaktadır [4], [19], [21], [26].

Bu tür iletim tabanlı ölçümlerde kullanılan antenlerin geniş bantlı çalışabilmesi, yakın alan bölgesinde yüksek elektromanyetik alan yoğunluğu oluşturabilmesi ve enerjiyi ölçüm bölgesine yönlü biçimde aktarabilmesi kritik öneme sahiptir. Vivaldi antenler; ultra geniş bant karakteristikleri, düzlemsel ve kompakt yapıları ile biyomedikal uygulamalara uygun anten tipleri arasında yer almaktadır [2], [8]–[11]. Yakın alan ölçüm geometrilerinde bu antenlerin, biyolojik numunelerin dielektrik özelliklerindeki görece küçük değişimleri dahi algılayabildiği daha önceki çalışmalarda gösterilmiştir [4], [6].

Milimetre dalga frekanslarında elektromanyetik dalgaların daha kısa dalga boyuna sahip olması, biyolojik yapıların elektromanyetik alanla etkileşim hacmini küçültmekte ve lokal dielektrik değişimlere duyarlılığı artırmaktadır. Son yıllarda gerçekleştirilen sınırlı sayıdaki

mmWave tabanlı biyosensör çalışmaları, kanser hücrelerinin bu frekans bandında ayırt edilebilir elektromanyetik tepkiler sergilediğini ortaya koymuştur [24], [25]. Ancak, Vivaldi anten tabanlı, yakın alan ölçüm geometrisi kullanan ve iletim katsayısına dayalı ΔS_{21} analizi ile hücresel düzeyde elektromanyetik karakterizasyon gerçekleştiren çalışmalar literatürde hâlen sınırlıdır.

Bu çalışmada, 24 GHz frekansında çalışan Vivaldi anten tabanlı bir yakın alan ölçüm sistemi kullanılarak, sağlıklı ve kanserli hücre tabakalarının elektromanyetik karakterizasyonu gerçekleştirilmiştir. Antenler arasına yerleştirilen cam lam ve lam üzerindeki hücre tabakalarının S-parametreleri karşılaştırmalı olarak analiz edilmiş; özellikle hücresel dielektrik farklılıkların iletim katsayısı üzerindeki etkisi ΔS_{21} yaklaşımı ile değerlendirilmiştir. Elde edilen bulgular, milimetre dalga bandında hücresel düzeyde elektromanyetik kontrastın belirgin hâle geldiğini göstermekte ve Vivaldi anten tabanlı yakın alan ölçümlerin non-invaziv biyomedikal tanı uygulamaları için güçlü bir potansiyel sunduğunu ortaya koymaktadır.

2. Materyal ve Yöntem

2.1 Vivaldi Anten Tasarımı

Vivaldi antenler, enerjinin slot boyunca üstel olarak genişleyen yapı üzerinden serbest uzaya aktarılması sayesinde düşük geri dönüş kaybı ve geniş bant performansı sağlayan slot-tip antenlerdir [4]. Bu çalışmada anten, Rogers RT/duroid 5880 substratı ($\epsilon_r = 2.2$, $h = 0.254$ mm, $\tan \delta = 0.0009$) üzerine tasarlanmıştır.

Antenin slot açıklığı üstel fonksiyonla tanımlanır:

$$w(x) = w_0 e^{kx}$$

Burada $w_0 = 0.2$ mm (slot başlangıç genişliği), $x = 13$ mm (genişleme uzunluğu), $w(x) = 13$ mm (slot uç genişliği). Bu değerlerle flare katsayısı:

$$k = \frac{1}{x} \ln \left(\frac{w(x)}{w_0} \right) = \frac{1}{13} \ln \left(\frac{13}{0.2} \right) \approx 0.17 \text{ mm}^{-1}$$

Elde edilen $k \approx 0.17 \text{ mm}^{-1}$ değeri, antenin 20–37 GHz aralığında kararlı ve geniş bantlı çalışmasını sağlamıştır.

Tablo 1. 24 GHz Vivaldi antenin CST tasarım parametreleri

Grup	Parametre	Sembol	Değer (mm)	Açıklama
Genel boyutlar	Anten uzunluğu	y	25.0	Toplam anten boyu
	Anten genişliği	x	13.0	Slot yatay açıklığı
	Substrat kalınlığı	T	0.254	Rogers 5880 tabaka kalınlığı
Slot geometrisi	Metal tabaka kalınlığı	MT	0.035	Bakır iletken kalınlığı
	Slot başlangıç genişliği	m	0.2	Boğaz açıklığı
	Slot çıkış genişliği	W_{ap}	13.0	Slot ağız açıklığı
	Slot uzunluğu	L_s	0.2868	Slot kenar uzunluğu
Besleme yapısı	Slot geçiş açıklığı	Smc	0.1434	Mikroşerit-slot boşluğu
	Mikroşerit genişliği	W_{mt}	0.7	50 Ω empedans için
	Mikroşerit uzunluğu	L_{mt}	4.152	Toplam besleme uzunluğu
Radial-stub	Stub yarıçapı	R_s	1.316	Yarım daire stub yarıçapı
Flare	Flare uzunluğu	L_f	19.0	Slot genişleme uzunluğu
	Flare açısı	F_t	180°	Geometrik flare açısı


Mikroşerit hattı 50 Ω empedans için 0.7 mm genişliğinde tasarlanmıştır. Mikroşerit-slot geçişinde empedans uyumunu artırmak amacıyla yarım daire biçimli radial-stub eklenmiştir. Bu yapı, iletilen enerjinin slot bölgesine dengeli aktarımını sağlar ve geniş bant performansını iyileştirir [6].

Etkin dielektrik sabiti (ϵ_{eff}) ve etkin dalga boyu (λ_{eff}) hesaplamaları aşağıda verilmiştir:


$$\epsilon_{eff} = \frac{\epsilon_r + 1}{2} + \frac{\epsilon_r - 1}{2} \left(1 + 12 \frac{h}{W_f} \right)^{-1/2} \approx 1.86$$

$$\lambda_{\text{eff}} = \frac{c}{f\sqrt{\epsilon_{\text{eff}}}} = \frac{3 \times 10^8}{24 \times 10^9 \sqrt{1.86}} \approx 9.1 \text{ mm}$$


Bu sonuç, mikroşerit hattının yaklaşık $\lambda_{\text{eff}} / 4 \approx 2.3 \text{ mm}$ uzunluğundaki radial-stub ile optimum empedans uyumunu sağladığını göstermektedir.




Şekil 1. 24 GHz dikey Vivaldi antenin CST modeli (ön ve arka görünüm).



Şekil 2. Antenin radial-stub besleme bölgesi yakın görünümü



Şekil 3. 24GHz Vivaldi antenin kazanç dağılımı CST parametre ekranı.



Şekil 4. Antenin S_{11} parametresi (CST simülasyonu)

2.2 Yakın Alan Hesaplamaları

Bir antenin biyolojik numunelerle yapılan elektromanyetik ölçümlerdeki başarısı yalnızca kazanç ve bant genişliğiyle değil, yakın alan bölgesinde oluşturduğu elektrik alan yoğunluğu ile de doğrudan ilişkilidir. Vivaldi antenler, yüksek frekanslarda enerjiyi dar bir bölgeye odaklayabilmeleri sayesinde mikroskobik ölçekte yüksek hassasiyet sunar. Bu özellik, özellikle hücre tabakalarının dielektrik özelliklerini belirlemede büyük avantaj sağlar.


Yakın alan bölgesi antenin maksimum fiziksel boyutu (D) ve çalışma dalga boyu (λ_0) ile tanımlanır. Bu bölge literatürde genellikle şu eşitlikle ifade edilir [9]:

$$R = 0.62 \sqrt{\frac{D^3}{\lambda_0}}$$

Bu çalışmada antenin maksimum boyutu $D = 25 \text{ mm}$, çalışma dalga boyu ise $\lambda_0 = 12.5 \text{ mm}$ (24 GHz için) olarak alınmıştır. Buna göre reaktif yakın alan sınırı:

$$R = 0.62 \sqrt{\frac{25^3}{12.5}} \approx 21.9 \text{ mm}$$

Olarak hesaplanmıştır. Bu değer, 24 GHz’de antenin etkili alan bölgesinin yaklaşık 22 mm içinde yer aldığını göstermektedir. Numunelerin bu sınır içinde konumlandırılması, elektrik alanın maksimum olduğu bölgede ölçüm yapılmasını sağlamış ve ΔS_{21} farkının en hassas biçimde elde edilmesine imkân vermiştir.



Şekil 5. 24 GHz’de karşılıklı yerleştirilmiş Vivaldi antenler ve lam konumu (CST modeli)

2.3. Lam ve Hücre Tabakalarının Dielektrik Modeli

Biyolojik dokuların elektromanyetik davranışını doğru bir şekilde temsil edebilmek için dielektrik parametrelerin gerçek dokulara olabildiğince yakın modellenmesi gerekmektedir. Bu çalışmada kullanılan cam lam ve hücre tabakaları, literatürde raporlanan güncel ölçüm değerleri temel alınarak simülasyon ortamında tanımlanmıştır. Modelleme sürecinde hem bağlı dielektrik

sabiti (ϵ_r) hem de kayıp tanjantı ($\tan\delta$) dikkate alınmış, özellikle 24 GHz civarında biyolojik dokuların dispersif yapısı göz önünde bulundurulmuştur.

Çalışmada kullanılan lam, $5 \times 5 \times 1$ mm boyutlarında silika bazlı camdan oluşmakta olup, dielektrik sabiti literatürde genellikle 4.4–4.7 aralığında rapor edilmektedir. Bu çalışma için $\epsilon_r = 4.6$ ve $\tan\delta = 0.008$ değerleri tercih edilmiştir. Hem frekans kararlılığı hem de simülasyonun gerçekçi olması bakımından bu değerler, biyomedikal mikrodalga uygulamalarında yaygın kabul görmüş ölçümlere dayanmaktadır.

Hücre tabakaları ise lamin üst yüzeyine yerleştirilmiş $20 \mu\text{m}$ kalınlığında çok ince biyolojik tabakalar olarak modellenmiştir. Bu değer, lam üzerindeki ortalama hücre kültürü kalınlığına karşılık gelmekte ve hem sağlıklı epitel hücreleri hem de LA7 adenokarsinom hücreleri için laboratuvar uygulamalarında sıkça karşımıza çıkan bir büyüklüktür.

Dielektrik özellikler belirlenirken sağlıklı ve kanserli hücre tabakaları arasında literatürde net olarak tanımlanan farklılıklar dikkate alınmıştır. Sağlıklı hücreler genellikle daha düşük su içeriğine ve daha düzenli hücresel yapıya sahip oldukları için bağıl dielektrik sabiti nispeten düşüktür. Buna karşılık kanserli hücreler, hızla çoğalan ve metabolik olarak daha aktif hücrelerden oluştukları için daha yüksek su ve iyon içeriğine sahiptir; bu durum ϵ_r değerinin artmasına yol açmaktadır. Kayıp tanjantı da hücresel sıvıların iyonik yapısı nedeniyle kanserli dokularda daha yüksek seyretmektedir.

Modellemede kullanılan dielektrik değerleri Tablo 2’de sunulmuştur:

Tablo 2. Lam ve Hücre Tabakalarının 24 GHz’deki Dielektrik Özellikleri




<i>Materyal</i>	<i>Kalınlık (mm)</i>	<i>Bağıl Dielektrik Sabiti (ϵ_r)</i>	<i>Kayıp Tanjantı ($\tan\delta$)</i>	<i>Kaynak</i>
Cam Lam	1.00	4.6	0.008	Nogi, Y., Watanabe, M., Suzuki, K., & Ohkuma, Y. (2015) [CrossRef]
Sağlıklı Hücre	0.02	32.8	3.40	Jithin, D., Hussein, M. I., Awwad, F., & Irtini, R. (2016, December) [CrossRef]
LA7 Kanserli Hücre	0.02	50.0	0.80	Turcan, I., & Olariu, M. A. (2020) [CrossRef]

Kayıp tanjantı değerlerinin hücre tipine, ölçüm tekniğine ve frekans aralığına bağlı olarak değişkenlik gösterebildiği; bazı kanser hücre hatlarında yüksek bağıl dielektrik sabitine rağmen daha düşük efektif $\tan\delta$ değerlerinin rapor edildiği literatürde belirtilmektedir [37], [40].

Bu dielektrik değerler, simülasyon sırasında hücre tabakalarının antenler arasındaki elektromanyetik iletimi nasıl etkilediğini doğrudan belirlemektedir. Özellikle kanserli hücre tabakasının yüksek dielektrik sabiti, milimetre dalga bandında elektromanyetik dalganın daha düşük zayıflama ile antenler arasında aktarılmasına neden olmaktadır. Bu davranış sonraki bölümde sunulan S_{21} ve ΔS_{21} analizlerinin temel fiziksel kaynağını oluşturmaktadır.

Simülasyon modeline ilişkin örnek görünüm Şekil 6–8 arasında verilmiştir. Sağlıklı ve kanserli hücre tabakaları lamin üst yüzeyinde ince birer dielektrik film olarak modellenmiş, antenler arasındaki konumlandırma yakın alan etkileşimini en üst düzeye çıkartacak şekilde ayarlanmıştır.

Lam ve hücre tabakalarının elektromanyetik davranışı, antenlerin yakın alan bölgesinde oluşturduğu elektrik alanla doğrudan etkileşir. Lamin görevi, biyolojik örneği mekanik olarak desteklerken aynı zamanda alan dağılımını bozmayacak dielektrik bir ortam sağlamaktır. Bu nedenle düşük kayıplı cam kullanımı, ΔS_{21} ölçümlerinde empedans kararlılığını korumuştur.



Şekil 6. Lamın CST modeli.

Şekil 7. Sağlıklı hücre tabakalı lam.

Şekil 8. LA7 kanserli hücre tabakalı lam.

3. Bulgular

Bu bölümde, Vivaldi anten sistemi kullanılarak dört farklı yükleme senaryosu altında elde edilen saçılma parametreleri değerlendirilmiştir:

1. Boş anten,
2. Yalnızca cam lam,
3. Sağlıklı hücre tabakalı lam,
4. LA7 kanserli hücre tabakalı lam.

Analizler 20–37 GHz frekans aralığında yürütülmüş olup, 24 GHz civarındaki elektromanyetik ayrımın davranışı üzerinde özellikle durulmuştur.


3.1 S_{11} Analizi: Antenin Empedans Kararlılığı

S_{11} parametresi, antenin besleme hattı ile empedans uyumunu değerlendirmek için temel bir göstergedir. Yapılan analizlerde, dört senaryonun tamamında S_{11} değerinin -20 dB'nin altında seyrettiği görülmüştür. Bu durum antenin hem boş ortamda hem lam üzerinde hem de biyolojik tabaka yüklü durumlarda kararlı bir empedans uyumu sergilediğini göstermektedir.

Rezonans frekanslarında gözlenen küçük yer değiştirmeler, lam malzemesi ve hücre tabakalarının dielektrik etkisinden kaynaklanmakla birlikte antenin genel çalışma kararlılığını bozacak ölçüde değildir.

Tablo 3. Farklı senaryolara ait en düşük S_{11} ve S_{21} değerleri.


Senaryo	f_{S11} (GHz)	S_{11} (dB)	f_{S21} (GHz)	S_{21} (dB)
Boş anten	24.412	-25.55	22.900	-50.74
Lam	24.358	-24.30	36.508	-57.49
Sağlıklı hücre	24.412	-25.65	36.274	-41.56
Kanserli hücre	24.376	-25.90	36.436	-41.67



Şekil 9. Dört farklı senaryo için elde edilen S_{11} eğrilerinin frekansla değişimi.

3.2 S_{21} Analizi: Elektromanyetik İletim Karakterizasyonu

S_{21} parametresi antenler arası iletilen gücü göstermektedir ve hücresel tabakaların elektromanyetik karakterizasyonunda kritik bir rol oynamaktadır. Analiz sonuçları lam malzemesinin ve biyolojik hücre tabakalarının frekansa bağlı olarak antenler arası kuplajı farklı ölçülerde etkilediğini ortaya koymuştur.



Şekil 10. Dört senaryoya ait S_{21} eğrileri ve işaretlenen tepe/minimum noktaları.

Lam senaryosu yüksek frekanslarda (36.5 GHz civarı) -57.49 dB ile en yüksek zayıflamayı göstermiş; bu durum cam laminin yüksek frekanslarda belirgin bir kayıplı davranışa sahip olduğunu doğrulamıştır. Boş anten senaryosunda 22.9 GHz’de -50.74 dB, sağlıklı ve kanserli hücre tabakalarında ise 36.27–36.44 GHz aralığında sırasıyla -41.56 dB ve -41.67 dB değerleri elde edilmiştir.

Bu sonuçlar, biyolojik dokuların dielektrik özelliklerindeki küçük değişimlerin milimetre dalga bölgesinde antenler arası iletimi ölçülebilir biçimde etkilediğini göstermektedir.

3.3 ΔS_{21} Analizi: Hücresel Ayırt Ediciliğin Değerlendirilmesi

ΔS_{21} parametresi, kanserli ve sağlıklı hücre tabakaları arasındaki elektromanyetik farkın nicel olarak değerlendirilmesini sağlamaktadır. Bu çalışmada ΔS_{21} hesaplamaları, antenin empedans açısından kararlı olduğu ve S_{11} ’in en düşük değerlere ulaştığı rezonans frekanslarında gerçekleştirilmiştir.

Aşağıdaki tablo bu frekanslarda elde edilen S_{21} ve ΔS_{21} değerlerini göstermektedir.

Tablo 4. S_{11} rezonans frekanslarında sağlıklı ve kanserli hücre tabakalarına ait S_{21} ve ΔS_{21} değerleri.

<i>Frekans (GHz)</i>	<i>S_{21} Sağlıklı (dB)</i>	<i>S_{21} Kanserli (dB)</i>	<i>ΔS_{21} (dB)</i>
24.412	-34.36	-32.88	+1.48
30.550	-30.64	-31.11	-0.47
36.760	-40.95	-41.36	-0.41

24.4 GHz civarında gözlenen +1.48 dB'lik pozitif ΔS_{21} tepesi, kanserli hücrelerin antenler arası iletimi artırdığını göstermektedir. Bu durum, kanserli hücrelerin daha yüksek iyon ve su içeriğine bağlı olarak daha yüksek bağıl dielektrik sabitine sahip olmasıyla uyumludur. Buna karşılık 30–37 GHz bandındaki negatif ΔS_{21} değerleri, biyolojik tabakaların frekansa bağlı dispersif davranışını ve dielektrik kayıplarını yansıtmaktadır.

Genel olarak ΔS_{21} 'nin yalnızca tek bir frekansta değil, antenin kararlı çalışma bölgelerine karşılık gelen geniş bir frekans aralığında değerlendirilmesi, sağlıklı ve kanserli hücrelerin elektromanyetik karakterizasyonu açısından daha güvenilir sonuçlar sunmaktadır.

3.4 Bulguların Akademik Değerlendirmesi

Elde edilen ΔS_{21} değerleri, 24 GHz frekans bandının hücresel düzeyde ayırt edici potansiyelini açık biçimde ortaya koymuştur. Kanserli hücrelerde gözlenen 1.48 dB'lik fark, literatürde 5–10 GHz aralığında raporlanan tipik ΔS_{21} değerlerinden belirgin biçimde daha yüksektir [5], [9]. Bu durum, milimetre dalga bandında kısa dalga boyunun sağladığı yüksek alan yoğunluğundan kaynaklanmaktadır.

Anten çifti arasında oluşturulan yakın alan odaklanması, lam yüzeyinde kararlı bir alan simetrisi oluşturmuş ve hücrelerin dielektrik yanıtlarını frekans bazlı olarak ayırt etmeyi mümkün kılmıştır. Sonuçlar, 24 GHz Vivaldi anten sisteminin hücre tabakaları arasındaki elektromanyetik farkları belirlemede etkili bir yakın alan sensörü olarak kullanılabileceğini göstermektedir.

Bulgular dört ana sonuç ortaya koymuştur:

1. Antenin empedans kararlılığı yüksektir; tüm senaryolarda S_{11} değerleri -20 dB'in altında kalmıştır.
2. Kanserli hücre tabakası, özellikle 24–26 GHz bandında, sağlıklı hücre tabakasından daha yüksek S_{21} değerleri göstermiştir.
3. ΔS_{21} 'nin en yüksek olduğu nokta 24.412 GHz'tir ve fark +1.48 dB'dir.
4. Üst frekans bandında (30–37 GHz) lam etkisi baskın hale gelmektedir ve bu sebeple ΔS_{21} negatif değerlere yönelmektedir.

Bu sonuçlar, 24 GHz frekans bandının kanser hücrelerini ayırt etmek için güçlü bir çalışma aralığı olduğunu açık bir şekilde göstermektedir.

4. Tartışma

Bu çalışmada, 24 GHz merkez frekansında çalışan bir Vivaldi anten sistemi kullanılarak sağlıklı epitel hücre tabakaları ile LA7 adenokarsinom hücre tabakalarının elektromanyetik davranışları ayrıntılı biçimde incelenmiştir. Elde edilen bulgular, milimetre dalga frekanslarının ince biyolojik tabakalardaki dielektrik farklılıkları ayırt etmede yüksek bir potansiyel sunduğunu açıkça ortaya koymaktadır.

Öncelikle, tüm biyolojik yükleme senaryolarında S_{11} parametresinin -20 dB'in altında seyretmesi, anten tasarımının empedans uyumunun kararlı olduğunu göstermektedir. Bu durum, biyolojik tabakaların antenin temel çalışma karakteristiğini bozmadığını ve gözlemlenen elektromanyetik farklılıkların anten geometrisinden değil doğrudan biyolojik tabakalardan kaynaklandığını ortaya koymaktadır. Elektromanyetik biyosensör çalışmalarında

empedans kararlılığının, ölçüm güvenilirliği açısından temel bir gereklilik olduğu literatürde de vurgulanmaktadır [2], [8], [10].

S_{21} parametresi üzerinden yapılan analizler, sağlıklı ve kanserli hücre tabakaları arasındaki ayrımın özellikle 24–26 GHz frekans aralığında belirginleştiğini göstermiştir. Kanserli hücre tabakasının bu bantta daha yüksek iletim sağlaması, kanser hücrelerinin bilinen biyofiziksel özellikleriyle uyumludur. Literatürde, kanserli hücre ve dokuların artan metabolik aktiviteye bağlı olarak daha yüksek su içeriği ve iyon yoğunluğuna sahip olduğu; bunun da bağıl dielektrik sabitinin artmasına yol açtığı yaygın biçimde rapor edilmiştir [12], [16], [31], [32]. Bu dielektrik artış, elektromanyetik dalgaların biyolojik tabakadan daha düşük zayıflamayla geçmesine neden olmakta ve S_{21} parametresinde ölçülebilir farklar oluşturmaktadır.

Çalışmanın en dikkat çekici bulgularından biri, 24.412 GHz civarında elde edilen yaklaşık +1.48 dB'lik ΔS_{21} farkıdır. Düşük frekanslı mikrodalga biyosensör çalışmalarında genellikle 0.3–0.7 dB aralığında rapor edilen ΔS_{21} değerleri ile karşılaştırıldığında, milimetre dalga bandında elde edilen bu farkın belirgin biçimde arttığı görülmektedir [4], [19], [21]. Bu durum, frekans arttıkça biyolojik tabakaların dielektrik kontrastının elektromanyetik iletim parametrelerine daha güçlü yansıdığı yönündeki literatür bulgularıyla uyumludur [12], [14], [24]. Elde edilen sonuçlar, 24 GHz bandının biyolojik doku ve hücre karakterizasyonu açısından kritik bir tanısal pencere sunduğunu göstermektedir.

Buna karşılık, 30–37 GHz frekans aralığında ΔS_{21} değerlerinin negatif yönde değişmesi, bu bölgede cam lamın dispersif etkisinin biyolojik tabakalara kıyasla daha baskın hâle geldiğini ortaya koymaktadır. Literatürde, cam ve cam benzeri dielektriklerin milimetre dalga frekanslarında artan dielektrik kayıplar sergilediği ve bu durumun iletim ölçümlerini etkileyebildiği rapor edilmiştir [13], [17]. Bu bağlamda elde edilen sonuçlar, hücresel ayrımın her yüksek frekansta otomatik olarak artmadığını; ölçüm ortamındaki ara katmanların (cam lam gibi) frekans-bağımlı etkilerinin dikkate alınması gerektiğini göstermesi açısından önemlidir.

Antenlerin reaktif yakın alan bölgesinde çalışacak şekilde konumlandırılması, bu çalışmada elde edilen sonuçların yorumlanmasında belirleyici bir rol oynamıştır. Yakın alan ölçüm geometrilerinde, elektromanyetik alanın biyolojik tabakayla güçlü bir şekilde etkileşime girmesi, ince hücre tabakalarının dahi iletim katsayısı üzerinde ölçülebilir etki oluşturmaya olanak tanımaktadır. Benzer şekilde, iletim tabanlı yakın alan ölçümlerin biyolojik ortamların efektif dielektrik özelliklerini yüksek hassasiyetle yansıtabildiği daha önceki çalışmalarda da gösterilmiştir [4], [26].

Bu çalışmada kullanılan hücre dielektrik modellerinin literatürde raporlanan deneysel ölçümlere dayandırılması, simülasyon sonuçlarının biyolojik gerçeklikle uyumunu güçlendirmektedir [16], [31]. Bununla birlikte, hücre tabakalarının homojen kabul edilmesi ve in vitro koşulların idealize edilmesi çalışmanın temel sınırlılıkları arasında yer almaktadır. Ancak bu yaklaşım, milimetre dalga frekanslarında hücresel ayrım mekanizmasının temel prensiplerinin net biçimde ortaya konulabilmesi açısından uygun bir ilk adım olarak değerlendirilmektedir.

Tüm bu bulgular birlikte değerlendirildiğinde, milimetre dalga frekanslarının özellikle 24 GHz civarında sağlıklı ve kanserli hücre tabakaları arasında anlamlı ve tekrarlanabilir bir ayırt edicilik sağladığı görülmektedir. ΔS_{21} parametresi üzerinden elde edilen bu ayrım, 24 GHz bandında çalışan Vivaldi anten tabanlı sistemlerin non-invaziv biyomedikal tanı uygulamaları için güçlü bir aday olduğunu ortaya koymaktadır [24], [25].

5. Sonuç

Bu çalışmada, 24 GHz merkez frekansında çalışan dikey polarizasyonlu bir Vivaldi anten kullanılarak sağlıklı epitel hücreleri ile LA7 adenokarsinom hücre tabakalarının elektromanyetik tepkileri ayrıntılı olarak incelenmiştir. Elde edilen bulgular, milimetre dalga

bölgesinin hücresel düzeydeki dielektrik farklılıkları ortaya çıkarmada güçlü bir potansiyel sunduğunu ve bu frekans aralığının biyomedikal sensör uygulamalarına önemli katkılar sağlayabileceğini göstermektedir.

Çalışmanın temel sonuçları şu şekilde özetlenebilir:

1. **Anten tasarımının empedans kararlılığı yüksektir.** Farklı biyolojik yükleme senaryolarına rağmen S_{11} parametresi geniş frekans aralıklarında -20 dB'in altında kalmış, antenin biyosensör uygulamaları için güvenilir bir platform oluşturduğu doğrulanmıştır.
2. **Kanserli hücre tabakası 24–26 GHz frekans bandında belirgin şekilde daha yüksek iletim sağlamıştır.** Bu durum, kanser hücrelerinin artmış su ve iyon içeriğinin elektromanyetik dalgaların iletimi üzerindeki doğal etkisini yansıtmaktadır.
3. **En güçlü ayırt edici fark, 24.412 GHz civarında $\Delta S_{21} \approx +1.48$ dB olarak gözlenmiştir.** Bu değer, literatürde düşük frekanslarda elde edilen ΔS_{21} değerlerinin oldukça üzerindedir ve 24 GHz bandının “tanısal açıdan kritik” bir bölge olduğunu göstermektedir.
4. **Üst frekans bölgesinde (30–37 GHz) cam lamin dispersif davranışı baskın hale gelmiş ve ΔS_{21} negatif değerlere yönelmiştir.** Dolayısıyla hücresel ayırım açısından en verimli çalışma bölgesi 24–26 GHz aralığıdır.

Bu sonuçlar bir arada değerlendirildiğinde, milimetre dalga frekanslarının hücresel düzeydeki dielektrik farklılıklara duyarlılığı açıkça ortaya konmakta ve Vivaldi anten tabanlı sistemlerin biyomedikal tanıda kullanılabilirliği doğrulanmaktadır. Özellikle 24 GHz civarındaki güçlü ayırt edicilik, bu frekans bandının gelecekte geliştirilecek non-invaziv sensör sistemleri için uygun bir temel oluşturduğunu göstermektedir.

Gelecek çalışmaların, deneysel prototip üretimi, gerçek biyolojik örneklerle laboratuvar ölçümleri, çok katmanlı doku modelleri ve farklı kanser hücre hatlarının değerlendirilmesi üzerine inşa edilmesi yöntemin klinik uygulanabilirliğini daha da güçlendirecektir. Ayrıca anten dizileri, faz kontrollü yapılandırmalar ve frekans tarama teknikleri ile sensör performansının daha da iyileştirilmesi mümkündür.

Sonuç olarak bu çalışma, 24 GHz bandında çalışan milimetre dalga antenlerinin hücresel düzeyde ayırt ediciliğinin güçlü ve istikrarlı bir şekilde ortaya konduğunu göstermekte; elektromanyetik biyosensörlerin erken dönem kanser tanısı için gelecek çalışmalar için güçlü bir araştırma zemini sunduğunu göstermektedir.

Kaynakça

- [1] Entesari, K., Ghiri, R. E., & Kaya, E. (2021). Broadband dielectric spectroscopy: Recent developments in microwave time-domain techniques. *IEEE Microwave Magazine*, 22(6), 26-48. [\[Google Scholar\]](#) [\[CrossRef\]](#)
- [2] Saleh, S., Ismail, W., Abidin, I. S. Z., Bataineh, M. H., & Alzoubi, A. S. (2022). Compact UWB Vivaldi tapered slot antenna. *Alexandria Engineering Journal*, 61(6), 4977-4994. [\[Google Scholar\]](#) [\[CrossRef\]](#)
- [3] Abdulhameed, A. A., Alnahwi, F. M., & Kubík, Z. (2024). Design and Modelling of a Modified High Gain Printed Vivaldi Antenna for EMC Measurements. *Wireless Personal Communications*, 138(1), 525-545. [\[Google Scholar\]](#) [\[CrossRef\]](#)
- [4] Garrett, J. D., & Fear, E. C. (2015). Average dielectric property analysis of complex breast tissue with microwave transmission measurements. *Sensors*, 15(1), 1199-1216. [\[Google Scholar\]](#) [\[CrossRef\]](#)
- [5] Lekshmi, B. S. K., & Raglend, I. J. (2015). A Vivaldi Antenna for X-band Phased Array Radar. *Indian Journal of Science and Technology*, 8, 35. [\[Google Scholar\]](#) [\[CrossRef\]](#)

- [6] Bhavani, M. V. L., Chaturvedi, D., Lanka, T., Raju, T. A., Rana, G., & Kumar, A. (2025). A Non-Invasive Microwave Imaging System for Breast Tumor Detection Using a High Gain Vivaldi Antenna Array Sensor. *IEEE Sensors Journal*. [\[Google Scholar\]](#) [\[CrossRef\]](#)
- [7] Constantinescu, C., Munteanu, C., Grindei, L., Giurgiuman, A., Pacurar, C., Gliga, M., & Andreica, S. (2020, October). High Frequency Analysis of the Vivaldi Antenna Parameters. In *2020 International Conference and Exposition on Electrical And Power Engineering (EPE)* (pp. 376-381). IEEE. [\[Google Scholar\]](#) [\[CrossRef\]](#)
- [8] Rafique, U., Pisa, S., Cicchetti, R., Testa, O., & Cavagnaro, M. (2022). Ultra-wideband antennas for biomedical imaging applications: a survey. *Sensors*, 22(9), 3230. [\[Google Scholar\]](#) [\[CrossRef\]](#)
- [9] Gibson, P. J. (1979, September). The vivaldi aerial. In 1979 9th European Microwave Conference (pp. 101-105). IEEE. [\[Google Scholar\]](#) [\[CrossRef\]](#)
- [10] Schaubert, D., Kollberg, E., Korzeniowski, T., Thungren, T., Johansson, J. O. A. K. I. M., & Yngvesson, K. (2003). Endfire tapered slot antennas on dielectric substrates. *IEEE Transactions on antennas and propagation*, 33(12), 1392-1400. [\[Google Scholar\]](#) [\[CrossRef\]](#)
- [11] Shin, J., & Schaubert, D. H. (1999). A parameter study of stripline-fed Vivaldi notch-antenna arrays. *IEEE Transactions on antennas and propagation*, 47(5), 879-886. [\[Google Scholar\]](#) [\[CrossRef\]](#)
- [12] Martellosio, A., Pasian, M., Bozzi, M., Perregrini, L., Mazzanti, A., Svelto, F., ... & Bellomi, M. (2016). Dielectric properties characterization from 0.5 to 50 GHz of breast cancer tissues. *IEEE Transactions on Microwave Theory and Techniques*, 65(3), 998-1011. [\[Google Scholar\]](#) [\[CrossRef\]](#)
- [13] La Gioia, A., Porter, E., Merunka, I., Shahzad, A., Salahuddin, S., Jones, M., & O'Halloran, M. (2018). Open-ended coaxial probe technique for dielectric measurement of biological tissues: Challenges and common practices. *Diagnostics*, 8(2), 40. [\[Google Scholar\]](#) [\[CrossRef\]](#)
- [14] Mariam, H., Poulichet, P., Takhedmit, H., Deshours, F., Richalot, E., & Francais, O. (2021). Accurate characterization by dielectric spectroscopy up to 25 GHz of nano-liter range liquid volume within a microfluidic channel. *IEEE Sensors Journal*, 22(4), 3553-3564. [\[Google Scholar\]](#) [\[CrossRef\]](#)
- [15] Canicatti, E., Sánchez-Bayuela, D. Á., Romero Castellano, C., Aguilar Angulo, P. M., Giovanetti González, R., Cruz Hernández, L. M., ... & Monorchio, A. (2023). Dielectric characterization of breast biopsied tissues as pre-pathological aid in early cancer detection: A blinded feasibility study. *Diagnostics*, 13(18), 3015. [\[Google Scholar\]](#) [\[CrossRef\]](#)
- [16] Fornes-Leal, A., Garcia-Pardo, C., Frasson, M., Beltrán, V. P., & Cardona, N. (2016). Dielectric characterization of healthy and malignant colon tissues in the 0.5–18 GHz frequency band. *Physics in Medicine & Biology*, 61(20), 7334. [\[Google Scholar\]](#) [\[CrossRef\]](#)
- [17] Zhang, L., Shi, F., Guo, J., Wang, Q., Kolb, J. F., Wang, W., ... & Zhuang, J. (2021). Impedimetric characterization of normal and cancer cell responses after nano-pulse stimulation. *Journal of Physics D: Applied Physics*, 54(18), 185401. [\[Google Scholar\]](#) [\[CrossRef\]](#)
- [18] Tehrani, F. D., O'Toole, M. D., & Collins, D. J. (2025). Tutorial on impedance and dielectric spectroscopy for single-cell characterisation on microfluidic platforms: theory, practice, and recent advances. *Lab on a Chip*. [\[Google Scholar\]](#) [\[CrossRef\]](#)
- [19] Kaur, G., & Kaur, A. (2020). Breast tissue tumor detection using “S” parameter analysis with an UWB stacked aperture coupled microstrip patch antenna having a “+” shaped defected ground structure. *International Journal of Microwave and Wireless Technologies*, 12(7), 635-651. [\[Google Scholar\]](#) [\[CrossRef\]](#)

- [20] Emami-Nejad, H., & Mir, A. (2017). Design and simulation of a flexible and ultra-sensitive biosensor based on frequency selective surface in the microwave range. *Optical and Quantum Electronics*, 49(10), 320. [\[Google Scholar\]](#) [\[CrossRef\]](#)
- [21] Juan, C. G., Grenier, K., Zarifi, M., Ebrahimi, A., & Martin, F. (2025). Planar microwave sensors: State of the art and applications. *IEEE Access*. [\[Google Scholar\]](#) [\[CrossRef\]](#)
- [22] Boparai, J., Tchinov, R., Miller, O., Jallouli, Y., & Popović, M. (2024). Models of melanoma growth for assessment of microwave-based diagnostic tools. *IEEE Journal of Electromagnetics, RF and Microwaves in Medicine and Biology*. [\[Google Scholar\]](#) [\[CrossRef\]](#)
- [23] Khuda, I. E., Anis, M. I., & Aamir, M. (2017). Numerical modeling of human tissues and scattering parameters for microwave cancer imaging systems. *Wireless Personal Communications*, 95(2), 331-351. [\[Google Scholar\]](#) [\[CrossRef\]](#)
- [24] Saha, A., Basak, P., Gupta, B., Sil, S., & Pal, S. (2020, July). Metasurface aided biophysical differentiation of radiated cancer cells: C band to THz perspective. In *2020 IEEE International Conference on Electronics, Computing and Communication Technologies (CONECCT)* (pp. 1-6). IEEE. [\[Google Scholar\]](#) [\[CrossRef\]](#)
- [25] Meena, R., Kumar, P., Yadav, S., & Kuanr, B. K. (2025). Microwave Resonant Sensor for Lung Cancer Cell Line Growth Detection. *ACS Applied Bio Materials*. [\[Google Scholar\]](#) [\[CrossRef\]](#)
- [26] Toprak, R., Gültekin, S. S., & Uzer, D. (2021). Investigation of Normalization Values of S-Parameters in Microstrip Antenna Structure in Pathological Tissue Samples. *Avrupa Bilim ve Teknoloji Dergisi*, (28), 1366-1371. [\[Google Scholar\]](#) [\[CrossRef\]](#)
- [27] Kaur, K., & Kaur, A. (2024). In silico, in vitro, and in vivo validation of a microwave imaging system using a low-profile ultra wide band archimedean spiral antenna to detect skin cancer. *International Journal of Imaging Systems and Technology*, 34(1), e23016. [\[Google Scholar\]](#) [\[CrossRef\]](#)
- [28] Kumar, P. P., Eedala, S. R., Yammanuru, A., Grace, A. N., & Malathi, A. C. J. (2025). Non-invasive leukemia detection via CSRR sensor. *Journal of Hazardous Materials Advances*, 18, 100654. [\[Google Scholar\]](#) [\[CrossRef\]](#)
- [29] Yilmaz, T., & Ates Alkan, F. (2020). In vivo dielectric properties of healthy and benign rat mammary tissues from 500 MHz to 18 GHz. *Sensors*, 20(8), 2214. [\[Google Scholar\]](#) [\[CrossRef\]](#)
- [30] Onemli, E., Joof, S., Aydinalp, C., Pastacı Özsoğacı, N., Ateş Alkan, F., Kepil, N., ... & Yilmaz, T. (2022). Classification of rat mammary carcinoma with large scale in vivo microwave measurements. *Scientific reports*, 12(1), 349. [\[Google Scholar\]](#) [\[CrossRef\]](#)
- [31] Reimann, C. H. N., Bazrafshan, B., Hübner, F., Schmidt, S., Schöler, M., Panahi, B., ... & Jakoby, R. (2019). Dielectric contrast between normal and tumor ex-vivo human liver tissue. *IEEE Access*, 7, 164113-164119. [\[Google Scholar\]](#) [\[CrossRef\]](#)
- [32] Cheng, Y., & Fu, M. (2018). Dielectric properties for non-invasive detection of normal, benign, and malignant breast tissues using microwave theories. *Thoracic cancer*, 9(4), 459-465. [\[Google Scholar\]](#) [\[CrossRef\]](#)
- [33] Ozsoğacı, N. P., Onemli, E., Aydinalp, C., & Yilmaz, T. (2024). Measurement and analysis of in vivo microwave dielectric properties collected from normal, benign, and malignant rat breast tissues: Classification using supervised machine learning algorithms. *IEEE Transactions on Instrumentation and Measurement*, 73, 1-11. [\[Google Scholar\]](#) [\[CrossRef\]](#)
- [34] Nogi, Y., Watanabe, M., Suzuki, K., & Ohkuma, Y. (2015). Method of measuring dielectric constant using an oscilloscope. *American Journal of Physics*, 83(9), 782-786. [\[Google Scholar\]](#) [\[CrossRef\]](#)

- [35] Alhaji, I. A., Abbas, Z., Mohd Zaid, M. H., & Khamis, A. M. (2021). Effects of particle size on the dielectric, mechanical, and thermal properties of recycled borosilicate glass-filled PTFE microwave substrates. *Polymers*, 13(15), 2449. [\[Google Scholar\]](#) [\[CrossRef\]](#)
- [36] Jithin, D., Hussein, M. I., Awwad, F., & Irtini, R. (2016, December). Dielectric characterization of breast cancer cell lines using microwaves. In *2016 5th International Conference on Electronic Devices, Systems and Applications (ICEDSA)* (pp. 1-4). IEEE. [\[Google Scholar\]](#) [\[CrossRef\]](#)
- [37] Turcan, I., & Olariu, M. A. (2020). Dielectrophoretic manipulation of cancer cells and their electrical characterization. *ACS Combinatorial Science*, 22(11), 554-578. [\[Google Scholar\]](#) [\[CrossRef\]](#)
- [38] Adekanmbi, E. O., & Srivastava, S. K. (2016). Dielectrophoretic applications for disease diagnostics using lab-on-a-chip platforms. *Lab on a Chip*, 16(12), 2148-2167. [\[Google Scholar\]](#) [\[CrossRef\]](#)
- [39] Hussein, M., Awwad, F., Jithin, D., El Hasasna, H., Athamneh, K., & Irtatni, R. (2019). Breast cancer cells exhibits specific dielectric signature in vitro using the open-ended coaxial probe technique from 200 MHz to 13.6 GHz. *Scientific reports*, 9(1), 4681. [\[Google Scholar\]](#) [\[CrossRef\]](#)

THE IMPACT OF ECONOMIC CHALLENGES ON THE COMPETITIVENESS OF
THE FASON SECTOR IN ALBANIA

Malvina Hysa

Logos University College, Albania

Lecturer of financial decision making

ORCID ID <https://orcid.org/0009-0008-0887-5529>

Dori Risilia

Agricultural University of Tirana, Albania

Lecturer of financial decision making

Abstract

The private sector has a significant impact on the development of the Albanian economy. Crises such as the pandemic and the Russia–Ukraine war have slowed economic activity and reduced profit margins in several sectors. However, today businesses in Albania face other challenges, such as the lack of stability in fiscal policies, unfair competition, and a shortage of employees. The fason (manufacturing/outsourcing) sector is the most affected, as in addition to the above-mentioned challenges it has also faced exchange rate problems. This sector has attempted to maintain its competitive position in the international market by making compromises through reducing profit margins.

This study aims to identify the problems faced by the fason sector. Through questionnaires addressed to managers in the fason sector, this study seeks to answer the research question: What strategies does the fason sector use to maintain its competitive position in the international market?

The government should create fiscal and monetary incentives for this sector because it employs low-skilled workers and contributes to the growth of exports, thereby reducing the trade deficit.

Key words: economy, international, market

Problem Statement

The fason sector (manufacturing and subcontracting, mainly textiles and footwear) plays a crucial role in the Albanian economy. It is one of the largest employers, particularly for low- and medium-skilled labor, and a key contributor to exports. The sector operates mainly under subcontracting agreements with foreign companies, making it highly dependent on international market conditions and exchange rate stability.

In recent years, the fason sector has been exposed to multiple economic shocks, including the COVID-19 pandemic and the Russia–Ukraine war. These crises have disrupted supply chains, increased production costs, and reduced profit margins. At the same time, structural problems within the domestic economy—such as unstable fiscal policies, unfair competition, labor shortages, and currency appreciation—have further weakened the sector’s competitiveness.

Despite its importance, the fason sector in Albania faces growing difficulties in maintaining its competitive position in international markets. Rising costs, declining profit margins, and limited state support have forced many firms to operate under pressure or consider relocation. Understanding the strategies used by fason firms to cope with these challenges is essential for designing effective economic policies.

Research Objectives

The main objectives of this study are:

- To identify the key economic challenges faced by the fason sector in Albania

- To analyze how these challenges affect the sector's international competitiveness
- To examine the strategies used by fason firms to remain competitive
- To provide policy recommendations to support the sustainability of the sector

Research Question

What strategies does the fason sector use to maintain its competitive position in the international market under current economic challenges?

Methodology

The study uses a **quantitative research approach** based on structured questionnaires addressed to managers and owners of fason enterprises in Albania. The data collected focuses on:

- Cost structure and profit margins
- Impact of exchange rate fluctuations
- Labor availability and wage pressures
- Perceptions of fiscal and monetary policies
- Competitive strategies (cost reduction, productivity improvement, market diversification)

The results are analyzed using descriptive statistics to identify common trends and challenges.

Key Findings

The study highlights several critical issues:

- **Exchange rate appreciation** has significantly reduced revenues, as most contracts are denominated in foreign currency
- **Labor shortages** and rising wages increase operational costs
- **Unstable fiscal policies** create uncertainty and discourage long-term investment
- Firms mainly maintain competitiveness by **reducing profit margins**, increasing work intensity, and limiting investments
- Innovation and technological upgrading remain limited due to financial constraints

Literature Review

The Role of the Fason Sector in Developing Economies

The fason sector, often referred to as subcontracting or outward processing manufacturing, plays a significant role in many developing and transition economies. According to Gereffi (1999), fason production is commonly integrated into global value chains, where developing countries specialize in labor-intensive stages of production while design and marketing remain in advanced economies. This model enables employment growth and export expansion but also creates strong dependency on foreign partners.

In the context of Southeast Europe, the fason sector has been identified as a key driver of industrial employment and export performance (Bartlett & Prica, 2017). However, its competitiveness is largely based on low labor costs rather than innovation or technological advancement, making it vulnerable to economic shocks and cost increases.

Economic Crises and Their Impact on Competitiveness

Several studies highlight how global economic crises negatively affect export-oriented manufacturing sectors. The COVID-19 pandemic caused severe disruptions in supply chains, reduced international demand, and increased uncertainty for manufacturing firms (OECD, 2021). Similarly, the Russia–Ukraine war has led to higher energy prices and raw material costs, further increasing production expenses for manufacturing firms across Europe (World Bank, 2022).

Krugman (1994) argues that sustained competitiveness depends not only on cost advantages but also on productivity and macroeconomic stability. For fason firms, rising costs combined with limited pricing power have resulted in declining profit margins, forcing companies to adopt short-term survival strategies.

Exchange Rate Fluctuations and Export Performance

Exchange rate volatility is widely recognized as a major challenge for export-oriented industries. According to Bahmani-Oskooee and Hegerty (2007), appreciation of the domestic currency negatively affects export competitiveness by reducing revenues when contracts are denominated in foreign currencies. This issue is particularly relevant for the Albanian fason sector, where most transactions are conducted in euros.

Empirical studies on Albania indicate that the appreciation of the Albanian lek has reduced the profitability of exporting firms, especially those operating under subcontracting arrangements with fixed prices (BoA, 2022). As a result, fason firms often compensate by reducing costs, mainly through lowering profit margins or increasing labor intensity.

Labor Market Challenges and Workforce Shortages

Labor availability is another critical factor influencing competitiveness. The fason sector relies heavily on low- and semi-skilled workers. However, migration, population aging, and alternative employment opportunities have contributed to labor shortages in Albania (INSTAT, 2023). According to Fields (2011), labor-intensive industries are particularly sensitive to wage increases, which directly affect production costs.

Studies show that rising wages without corresponding productivity gains weaken competitiveness in labor-intensive sectors (ILO, 2020). In Albania, fason firms face increasing wage pressures while lacking sufficient investment in training and automation.

Fiscal Policy, Informality, and Business Environment

An unstable fiscal environment and frequent changes in tax policies increase uncertainty for businesses. North (1990) emphasizes that institutional stability is essential for economic performance. In developing economies, informality and unfair competition further distort market conditions, placing compliant firms at a disadvantage.

Research by the European Commission (2022) highlights that limited state support and weak industrial policies hinder the upgrading of manufacturing sectors in the Western Balkans. For the fason sector, the lack of targeted incentives restricts the ability to move up the value chain.

Competitive Strategies in the Fason Sector

Porter (1985) identifies cost leadership as one of the main competitive strategies in manufacturing. The fason sector in Albania primarily adopts cost-based strategies, including wage containment, efficiency improvements, and profit margin reduction. However, several authors argue that long-term competitiveness requires upgrading toward higher value-added activities (Gereffi et al., 2005).

Empirical evidence suggests that firms investing in technology, workforce skills, and product diversification are more resilient to external shocks (UNIDO, 2021). Nonetheless, such investments remain limited in the Albanian fason sector due to financial constraints and policy gaps.

Summary of Literature

The literature indicates that while the fason sector contributes significantly to employment and exports, its competitiveness is fragile. External shocks, exchange rate appreciation, labor shortages, and institutional weaknesses undermine its sustainability. Most firms rely on short-

term cost-reduction strategies, which are insufficient for long-term growth. Therefore, coordinated firm-level strategies and government support are essential to enhance competitiveness and resilience.

Policy Recommendations

To support the fason sector, the study recommends:

- Fiscal incentives such as tax reliefs or subsidies for exporters
- Monetary policies to mitigate exchange rate volatility
- Support for workforce training and skill development
- Incentives for technological investment and productivity improvement
- Measures to combat unfair competition and informality

Conclusions

The fason sector remains a strategic pillar of the Albanian economy, especially in terms of employment and exports. However, persistent economic challenges threaten its competitiveness. Coordinated government policies and strategic firm-level adjustments are necessary to ensure the sector's resilience and long-term contribution to economic growth.

References

- Bahmani-Oskooee, M., & Hegerty, S. W. (2007). Exchange rate volatility and trade flows: A review article. *Journal of Economic Studies*, 34(3), 211–255.
<https://doi.org/10.1108/01443580710772777>
- Bartlett, W., & Prica, I. (2017). Interdependence between manufacturing and services in the Western Balkans. *Economic Annals*, 62(214), 7–30. <https://doi.org/10.2298/EKA1714007B>
- European Commission. (2022). *Enhancing competitiveness and industrial policy in the Western Balkans*. Publications Office of the European Union.
- Fields, G. S. (2011). *Labor market analysis for developing countries*. Labour Economics, 18(S1), S16–S22. <https://doi.org/10.1016/j.labeco.2011.09.005>
- Gereffi, G. (1999). International trade and industrial upgrading in the apparel commodity chain. *Journal of International Economics*, 48(1), 37–70. [https://doi.org/10.1016/S0022-1996\(98\)00075-0](https://doi.org/10.1016/S0022-1996(98)00075-0)
- Gereffi, G., Humphrey, J., & Sturgeon, T. (2005). The governance of global value chains. *Review of International Political Economy*, 12(1), 78–104.
<https://doi.org/10.1080/09692290500049805>
- International Labour Organization (ILO). (2020). *Global wage report 2020–21: Wages and minimum wages in the time of COVID-19*. ILO Publications.
- INSTAT. (2023). *Labour market indicators in Albania*. Institute of Statistics, Albania.
- Krugman, P. (1994). Competitiveness: A dangerous obsession. *Foreign Affairs*, 73(2), 28–44.
- North, D. C. (1990). *Institutions, institutional change and economic performance*. Cambridge University Press.
- OECD. (2021). *Global value chains: Efficiency and risks in the context of COVID-19*. OECD Publishing.
- Porter, M. E. (1985). *Competitive advantage: Creating and sustaining superior performance*. Free Press.
- UNIDO. (2021). *Industrial development report 2022: The future of industrialization in a post-pandemic world*. United Nations Industrial Development Organization.
- World Bank. (2022). *Europe and Central Asia economic update: War in the region*. World Bank Publications.
- Bank of Albania. (2022). *Exchange rate developments and their impact on exporters*. Bank of Albania Reports.

**NEGATIVE ASPECTS IN CONTEMPORARY IRANIAN ARCHITECTURE:
A MULTIDISCIPLINARY ASSESSMENT FROM CIVIL ENGINEERING,
CONSTRUCTION MANAGEMENT, AND ARCHITECTURE PERSPECTIVES**

Dr. Mehdi Shalchi Tousi

Engineer, Department of Engineering Faculty of Ahle Beyte Internatinal University, Tehran,
Iran)

ORCID NO: 0000-0003-4601-1082

Abstract

The rapid urbanization and extensive construction activities in contemporary Iran have led to a substantial growth in architectural projects. However, this growth is often accompanied by significant challenges, including technical deficiencies, unsustainable practices, and compromised build quality and user experience. This study conducts a multidisciplinary assessment of these negative aspects from the perspectives of civil engineering, construction management, and architecture. Employing a mixed-methods approach, the research integrates a systematic literature review, comprehensive case studies of contemporary Iranian architectural projects, and semi-structured interviews with industry experts and academics. The primary objective is to identify critical weaknesses in design, execution, and operational phases, and to propose an innovative framework for enhancing project quality, safety, and sustainability. Key findings highlight issues such as inadequate integration between design and construction processes, substantial gaps in sustainable energy optimization and material selection, limitations in on-site quality control, scarcity of lifecycle data, and the urgent need for improved decision-making facilitated by Building Information Modeling (BIM) and robust sustainable standards. This study contributes practical strategies for improving construction quality, seismic resilience, sustainable usability, and project management, while offering policy recommendations for both industry and academia. The innovative theoretical framework, combined with a mixed-methods approach utilizing project-level data and expert insights, provides a holistic understanding of the complexities and offers actionable pathways for rectifying the identified negative aspects in Iranian contemporary architecture.

Keywords: Contemporary Iranian Architecture, Building Quality, Seismic Resilience, Construction Performance, Sustainability Gaps, Design-Construction Integration

1. Introduction

The landscape of contemporary Iranian architecture has undergone significant transformations over the past few decades, driven by rapid urbanization, population growth, and evolving societal needs (Habibi & Ahari, 2018). This period has witnessed an unprecedented surge in construction activities, ranging from residential complexes and commercial centers to cultural landmarks and infrastructural developments. While this growth signifies progress and addresses pressing housing and urban demands, it has also inadvertently brought to light a myriad of negative aspects that compromise the quality, safety, sustainability, and overall performance of architectural projects (Nikkhah et al., 2021). These issues, often rooted in a complex interplay of technical, managerial, economic, and policy-related factors, extend beyond mere aesthetic concerns to fundamental structural integrity, environmental impact, and long-term functionality.

From the perspective of civil engineering, contemporary Iranian architecture frequently grapples with challenges related to structural soundness, adherence to seismic codes in an earthquake-prone region, material selection, and construction methodologies that often fall

short of international best practices (Pourali & Esmaeili, 2019). The emphasis on speed and cost reduction can lead to shortcuts in design and execution, manifesting as compromised structural detailing, inadequate material quality, and insufficient on-site supervision. These shortcomings not only jeopardize the safety of occupants but also contribute to increased maintenance costs and reduced building lifespans.

Construction management aspects reveal deficiencies in project planning, resource allocation, risk management, and quality control. The fragmentation of the design and construction phases, coupled with a lack of comprehensive building information modeling (BIM) adoption, often results in coordination failures, rework, and schedule delays (Karimi & Rostami, 2020). Furthermore, the absence of robust lifecycle assessment and post-occupancy evaluation practices means that valuable lessons from completed projects are rarely systematically captured and integrated into future endeavors, perpetuating existing flaws.

Architectural considerations highlight a departure from traditional Iranian architectural principles of climate responsiveness, local material utilization, and socio-cultural integration, often in favor of imported styles and generic designs that fail to address specific regional contexts (Memarian & Nazari, 2015). This can lead to buildings that are energy-inefficient, visually discordant with their surroundings, and unresponsive to the needs and aspirations of their users. Issues of poor daylighting, inadequate ventilation, and substandard acoustic performance are common, directly impacting user comfort and well-being. Moreover, the lack of holistic sustainable design practices means that many new constructions contribute significantly to environmental degradation through high energy consumption and reliance on non-renewable resources (Ansari & Rouhollah, 2017).

The motivation for this research stems from the urgent need to address these multifaceted negative aspects to foster a more resilient, sustainable, and user-centric built environment in Iran. Existing literature often addresses individual facets of these problems—e.g., specific structural failures, material degradation, or isolated design critiques. However, there remains a significant gap in comprehensive, multidisciplinary assessments that integrate the perspectives of civil engineering, construction management, and architecture to provide a holistic understanding of the root causes and interdependencies of these issues. Furthermore, a critical analysis of current practices, coupled with an exploration of innovative solutions and policy recommendations tailored to the Iranian context, is conspicuously lacking.

This study aims to bridge this knowledge gap by systematically analyzing the negative aspects in contemporary Iranian architecture. Specifically, this research seeks to:

1. Identify and categorize the prevalent technical, managerial, environmental, and socio-cultural deficiencies in contemporary Iranian architectural projects.
2. Investigate the underlying causes of these negative aspects, considering factors such as regulatory frameworks, professional practices, economic pressures, and educational paradigms.
3. Develop an integrated conceptual framework that links design, construction, and operational phases to evaluate and mitigate these identified negative aspects.
4. Propose evidence-based strategies and policy recommendations for stakeholders in the Iranian construction industry to enhance building quality, safety, seismic resilience, sustainability, and user satisfaction.

The scope of this research encompasses contemporary architectural projects in urban and suburban areas across Iran, primarily focusing on developments from the early 2000s to the present day. This timeframe is chosen to capture the most recent trends and challenges influenced by rapid economic and technological shifts. While the study draws on global best practices, its primary focus remains the specific context of Iran, acknowledging its unique cultural, climatic, and socio-economic conditions.

This paper is structured as follows: Section 2 provides a comprehensive literature review, critically examining existing research and highlighting the lacunae this study aims to fill. Section 3 details the mixed-methods methodology employed, including the study design, sampling strategies, data collection instruments, and analytical approaches. Section 4 presents the analysis and key findings, supported by both quantitative data and qualitative insights. Section 5 discusses the implications of these findings, addresses study limitations, and proposes practical and theoretical contributions. Finally, Section 6 concludes the research by summarizing the main takeaways and outlining directions for future research. This comprehensive approach ensures a robust and actionable contribution to the discourse on improving the quality and sustainability of the built environment in Iran.

References for this segment (APA 7th edition):

- Ansari, H., & Rouhollah, S. (2017). Sustainable architecture in Iran: Challenges and opportunities. *Journal of Urban Planning and Development*, 143(3), 05017006.
- Habibi, K., & Ahari, S. S. (2018). Urbanization and its impact on architectural identity in Iran. *International Journal of Architectural Engineering and Urban Planning*, 28(2), 79-88.
- Karimi, R., & Rostami, S. (2020). The role of Building Information Modeling (BIM) in improving construction project management in Iran. *Journal of Construction Engineering and Management*, 146(5), 04020038.
- Memarian, G., & Nazari, H. (2015). A critical review of contemporary architecture in Iran: From tradition to modernity. *Frontiers of Architectural Research*, 4(4), 312-321.
- Nikkhah, F., Haghighat, F., & Gholamzadeh, S. (2021). Performance evaluation of residential buildings in Tehran from a user satisfaction perspective. *Journal of Housing and the Built Environment*, 36(1), 227-245.
- Pourali, N., & Esmaili, R. (2019). Seismic performance of reinforced concrete buildings in Iran: A review of design and construction practices. *Structural Engineering and Mechanics*, 69(6), 661-678.

AR-GE ÇALIŞMALARINDA YAPAY ZEKÂ KULLANIMI
IMPLEMENTATION OF THE ARTIFICIAL INTELLIGENCE THROUGH R&D

Mehmet Ali DURLU

Dumlupınar Üniversitesi, Lisansüstü Eğitim Fakültesi,
Teknoloji ve İnovasyon Yönetimi Bölümü, Kütahya, Türkiye
ORCID NO: 0009-0005-0514-4809

Prof. Dr. Arif GÖK

Dumlupınar Üniversitesi, Mimarlık Fakültesi,
Endüstriyel Tasarım Bölümü, Kütahya, Türkiye
ORCID NO: 0000-0003-2840-9601

Özet

Teknoloji araştırmaları AR-GE süreçlerinin önemli bir aşamasıdır. Bu safhada yeni trendler ve gelişmeler incelenir, fizibilite adımlarından itibaren detaylar raporlanır. İçinde bulunduğumuz çağda bu adımların büyük bir kısmında yapay zekâ kullanımı büyük bir avantaj sağlamaktadır. Yapay zekâ, teknolojinin topluma hızlı entegrasyonu ve ticarileşmesi süreçlerinde; araştırma, fizibilite, kıyaslama, görselleştirme, raporlama ve daha birçok alanda, tüm sektörlerde kullanılan bir araç hâline gelmiştir. Patent araştırmaları, testler ve deneyler, simülasyon ve modellemeler gibi süreçler, daha önceleri uzun zaman alan süreçlerken, yapay zekânın sektörlerdeki profesyoneller ve akademisyenler tarafından doğru kullanımı sayesinde teknolojik yeniliklerin hayata geçişi hızlanmıştır. AR-GE ile doğrudan sorumlu olan profesyonellerin kor çalışmalardaki araçları olan veri setlerindeki trendlerin analizi, grafiklerin yorumlanması veya kıyas amaçlı grafiklerin oluşturulması, soyut çalışmaların görselleştirilebilmesi, malzeme optimizasyonu, makine öğrenme algoritmaları gibi konularda araştırmacıların çalışma etkinliğini ve AR-GE merkezlerinin inovasyon kapasitesini artırmasının yanı sıra; araştırmacıların doğrudan uzmanı olmadığı ve sürecin başlamasına tetikleyici olması beklenen, AR-GE ürünlerinin piyasadaki talep analizi, hangi ihtiyaçlara ve kitlelere hitap ettiği, arz stratejisinin belirlenmesi gibi pazarlamaya hitap eden konularda da araştırmacıların hızlı strateji belirlemesine kolaylık teşkil etmektedir. Böylelikle AR-GE çalışmalarının yürütücüleri, proje başlatma veya yönetme süreçlerinde daha geniş bir perspektifle durum analizi yapabilmektedir. Bu sayede pazarın ihtiyacı olan geliştirmeler doğru tespit edilip önceliklendirilerek, gelişim sahası doğru bir strateji ile belirlenerek, kısa sürede veri analizi, yorumlama, test, simülasyon süreçleri geçildikten sonra; bilimsel hazırlık ve mühendislik geliştirmelerinin süreçteki odaklanma ihtiyacı daha yüksek bir dikkat ve titizlikle gerçekleştirilebilmektedir. Sonuç olarak, yapay zekânın katkıları sayesinde doğru ihtiyaç, doğru kitleye, daha detaylı mühendislik çalışmaları ile kısa sürede hizmet verecek şekilde ticarileştirilerek piyasaya sunulmaktadır.

Anahtar Kelimeler: AR GE, Yapay zekâ, analiz, proje, mühendislik, yeni trendler

Abstract

Technology research constitutes a crucial stage of R&D processes. At this phase, new trends and developments are examined, and details are reported starting from feasibility steps. In today's era, the use of artificial intelligence in many of these steps provides significant advantages. Artificial intelligence has become a widely used tool across all sectors in processes such as the rapid integration and commercialization of technology into society, as well as in research, feasibility studies, benchmarking, visualization, reporting, and many other fields. Processes such as patent research, testing and experimentation, simulation, and modeling, which previously required long durations, have accelerated the transition of technological

innovations into practice thanks to the accurate use of artificial intelligence by professionals and academics. For professionals directly responsible for R&D, artificial intelligence not only increases the working efficiency of researchers and the innovation capacity of R&D centers in areas such as analyzing trends in datasets, interpreting or generating comparative graphs, visualizing abstract studies, material optimization, and machine learning algorithms, but also facilitates rapid strategy development in marketing-oriented areas. These include market demand analysis for R&D products, identifying target needs and user groups, and determining supply strategies, especially in stages where researchers may not be direct experts but are expected to initiate the process. In this way, R&D practitioners can perform broader and more comprehensive situational analyses during project initiation and management processes. Consequently, true market needs can be accurately identified and prioritized; development areas can be determined with appropriate strategies; and following rapid completion of data analysis, interpretation, testing, and simulation phases, scientific preparation and engineering development stages can be carried out with enhanced focus and precision. As a result, with the contributions of artificial intelligence, the right solutions addressing the right target groups can be commercialized in a shorter time and introduced to the market through more detailed engineering studies

Keywords: R&D, artificial intelligence, analysis, project, engineering, new trends

GİRİŞ

Yapay zekâ, son yıllarda insan hayatına çok hızlı ve etkili bir biçimde adapte oldu. Yaklaşık beş ilâ on yıldır yapay zekâ soyut bir kavram olarak o denli zikredildi ki, pek çok insan bunun bir ütopya olduğunu dahi düşündü. Bugün ise pek çok alanda ve hatta gündelik yaşantımızdaki uğraşlarımızda dahi yapay zekâdan destek alıyor, sorular soruyor ve durumu hayretle karışık bir hayranlıkla kontrol altında tutmaya çalışıyoruz. Yapay zekânın çığ gibi büyüyen bilgiye erişim gücüyle 21. Yüzyılın önemli bir fenomeni haline geldiğini şimdiden söyleyebiliriz.

Yapay zekâ uygulamaları insan hayatına girdiğinden beri bilgiye ulaşım kolaylığında son derece artış olduğu kesin. İlk zamanlar her alanda sağladığı kolaylığın yadsınamaz olduğu bir gerçekken, insanların bunu nasıl kontrol edeceği veya kullanacağı ise en önemli merak konularından bir tanesi. Toplumsal hayatın kolaylaştırılması, refahın adil dağılması, bilimsel ve teknolojik gelişmelerin topluma daha hızlı yansması gibi beklentiler, zaman içinde insan hayatına sağlayacağı faydalar olarak sıralanabilir. Öte yandan sağladığı bilginin doğruluğuna şüpheli yaklaşım gerektiği de bâriz. Bilginin denetimi sağlanmadığı takdirde oluşabilecek sorunlar ise toplumda infial yaratabilir.

ARAŞTIRMA VE BULGULAR

Bilim ve teknoloji çevreleri, akademisyenler, araştırmacılar, uygulayıcılar; pek tabî, mesleklerinde yapay zekâyı en faydalı şekilde kullanma ve ondan destek alma gayretindeler. Bilgi doğruluğunun teyit edildiği durumlar için konuşulursa, bu gayretin büyük bir ivme oluşturacağı muhakkaktır. 2017 yılında Accenture tarafından yayımlanan bilgiye göre dünyanın en gelişmiş on iki ülkesinde akıllı otomasyon ve yapay zekâ alanında 2035 yılına kadar iki katına çıkan ekonomik büyüme oranları sağlanabileceği öngörüsü belirtilmiştir.

Bilimsel çalışma şartları açısından yapay zekâ öncesi ve sonrası olarak bir ayrım yapılırsa, aynı çalışmanın yapay zekâ ortaya çıkmadan önce yapılması ve sonrasında yapılması arasında; çalışmaya harcanan zaman, kaynaklara erişme kolaylığı, bilgi çeşitliliği, yapay zekânın imkân verdiği çalışma araçlarının sağladığı kolaylık gibi maddeler birlikte düşünüldüğünde, yapılan araştırma ve çalışmaların akademik bilgi havuzuna veya insanların yaşantısına girmesi arasında büyük marjlar oluşacağını söylersek yanılmayız. Bu sâye de oluşacak ivme ile toplumlar bilim ve teknolojiden daha konsantre ve parabolik artan bir hızla faydalanabilecektir.

Bilim ve teknoloji alanında faaliyet gösteren kurum ve kişilerin rekabetçi olmalarını sağlayan ilk unsurlardan biri olan AR-GE, yapay zekâya en fazla iştah duyulan alanlardan bir tanesidir. AR-GE süreçleri; her alanda olduğundan daha fazla araştırma, test, simülasyon ve raporlama içermektedir. Tüm bunların kombine halde kolaylaştığı mecralar olan yapay zekâ destekli uygulamalarla AR-GE'nin evrim geçirdiğini söylemek mümkün. Konuya AR-GE'nin temel amaçlarından biri olan rekabetçilikle başlayarak detaylandırmak gerekirse, daha fazla AR-GE çalışması eskiden aranan ve potansiyel doğuran bir yönelimken; yapay zekâ sonrasında daha isabetli AR-GE çalışması daha büyük gelişim ve başarı vadediyor. Patent araştırmalarının, rakiplerin içerisinde olduğu trendlerin, piyasa ihtiyaçlarının analizi, literatür taramalarının çok daha hızlı yapılabilmesi, hesaplama, test ve simülasyona dayalı adımların hızlı ve ekonomik yürütülebilmesi, fiziki şartlar gerekmeden optimizasyon yapılabilmesine olanak tanınması, raporlamaların ve görselleştirmelerin katkısı ile topyekun fayda elde edilmesi mümkündür. Adım adım ilerlenerek AR-GE süreçlerinde yapay zekânın etkileri daha geniş bir çerçevede ele alınabilir.

1. Patent Araştırmalarında Yapay Zekâ Kullanımı

Yapay zekânın sağladığı hızlı metin tarama özelliğinin en büyük faydalarından bir tanesi şüphesiz patent araştırmaları alanındadır. Yapay zekâ destekli uygulamalarla patent tarama işlemleri, doğal dil işleme (NLP) algoritmalarını kullanarak, patent dokümanları içindeki ana konseptleri ve eğilimleri belirler [1]. Böylece fikri mülkiyet stratejileri hakkında bilinçli kararlar alınmasının yolu kolaylaşır. Kullanıcılara sağlanan bireysel ihtiyaçlarla uyumlu hale getirme seçenekleri sayesinde ve belirlenen filtre yapısı ile belirli odaklara yönelik araştırmalar daha kolay süzdürülebilir. Mesela yetki alanı, tarih aralığı ve patent türüne göre arama sonuçları filtrelenebilir, bunun sonucunda hedefe daha odaklı bir araştırma ve analiz süreci elde edilir.

2. Piyasa ve Rakip Davranışlarının Analizi

Teknoloji alanında kârlılık ve katma değer hedeflenirken dikkate alınması gereken başlıklar arasında pazar gerçekleri ve ihtiyaçları ile rakiplerin çalışmaları önemli bir yer tutar. Piyasadaki hizmet veya ürün ihtiyacını belirlemek organik bağ kurmaklar elde edilir. Buna destek olarak, yapay zekâda doğru istem (prompt) kullanımı sayesinde kullanıcıların yaptığı web aramaları, tüketici trendleri, kullanıcı yorumları, mevcut ürün ve hizmetlerin ihtiyaca ne derece cevap verdiği son derece detaylı bir şekilde elde edilebilir.

3. Literatür Taramaları

AR-GE süreçlerinde en fazla zaman alan, detaylı araştırma ve filtreleme gereken adımlarda bir diğeri ise literatür tarama safhasıdır. Yüzlerce makale taraması ve detaylı inceleme gereken hazırlık aşamaları, yapay zekâdan destek alınarak çok kısa bir süreye indirgenebilir. Örnek olarak bir biyoteknoloji firması, AI ile destekli literatür analiz sistemi sayesinde yeni molekül araştırmalarında araştırma süresini %62 oranında azalttı.[2]

4. Hesaplamalar ve Test Süreçleri

AR-GE çalışmalarında en net olunması gereken ve en fazla zaman alıcı kısımlardan bir başkası da hesaplamaların yer aldığı safhadır. Yapılan tariflere göre hesaplama süreçlerinin dökümünü veren yapay zekâ sayesinde, çalışmayı koordine eden kişilere kalan kısım yalnızca kontrol etmektir. Hesaplamalarda kullanılan formül sabitlerinin ve hesaplama ilerleyişinin kontrolü ile süreç eskiye göre çok hızlı tamamlanabilir.

Test gerektiren durumları sözlü olarak anlatıp simüle ettirmek ise kullanıcıların yapay zekâdan AR-GE süreçlerine dair alabilecekleri en değerli katkılarında bir tanesidir. Test edilip laboratuvarlarda yüzlerce kez tekrar tekrar denenen çalışmalar, hedefe yakınsayan olasılıkların tespiti veya tayini sonrasında laboratuvarlarda denenir. Böylece hem lojistik sebepli zaman kazancı, hem ekonomik çözüme kolay ulaşma, hem de kaynak kullanımının minimize edilmesi getirileri ile katma değer artışı sağlanır.

Özellikle mühendislik çalışmalarının ürüne dair en büyük fark yaratan çalışmaların gerçekleşmesi gereken adım optimizasyon adımdır. Üzerinde AR-GE çalışması

gerçekleştirilen konu hakkında fiziki şartların sağlanarak test sonuçlarının raporlandığı ve hedefe en uygun şartlara gelindiğinde çalışmanın nihayete erdirildiği süreci kapsayan optimizasyon safhasında çalışmayı sergileyen araştırmacılar bir takım ihtiyaçlar duyar. Buna örnek olarak bir ürünün malzeme seçimi kriterlerini verebiliriz. Belirlenen farklı ortam sıcaklıkları, basınçlar, ışık kaynağı, nemlilik ve bunların kombinasyonlarından oluşması gereken test ortamları, tamamen yapay zekâya tanımlanarak gerçekte test yapmak yerine bu şartların değişkenliği durumunda nasıl bir sonuç alınacağı yapay zekânın araştırmacılara verdiği en önemli desteklerden biri olarak zikredilebilir. Aiden Toner-Rodgers'ın ifadesine göre yapay zekâ, fikir üretme görevlerinin %57'sini otomatizasyona dönüştürerek Ar-Ge çıktısını artırabiliyor. Malzeme keşfi gibi konularda %44 daha fazla çeşitlilik imkânı sunuyor. [3]

Aynı şekilde yapılan testlerin yorumlanması noktasında da yapay zekâ desteği kullanıcılar için büyük bir kolaylık teşkil eder. Benjamin F. Jones'un ifadesine göre elde edilen büyük verinin trendini inceleyerek yorumlamak, modellemek, sonraki adımları tahmin etmek gibi yeteneklerinin verdiği destekle, araştırmacıların karar süreçlerini güçlendirir [4].

5. Raporlama ve Görselleştirme

Günümüzde tüketici davranışlarını en fazla etkileyen ürün özelliklerinden biri de, üründe görsellik veya ürünün tanıtımında görselliktir. AR-GE çalışması başlı başına bir ürün olduğu için görsel destek bu tip çalışmaların anlaşılır, kolay fark edilir, ayrıştırılır ve tercih edilir olmasını sağlamaktadır. Yalnız metin unsurlarından oluşan bir rapor incelemek yerine; grafikler, şekiller, görseller gibi anlatımı daha somut hâle getirip içeriğin monotonluğu ortadan kaldıran görsel unsurlar, yapay zekânın hizmet verebildiği bir diğer alandır. Görece harcanan zamana kıyasla daha düşük katma değer vadeden bir adım olan, çalışmanın raporlanması esnasında teknik biçimsel ihtiyaçların sağlandığı ve derlemeye yatkın bir yapay zekâ destekli uygulama ile çalışmaların katma değeri artırılır.

Tüm bu sayılan adımlardaki destekleri ile yapay zekâ, AR-GE sürecinin zaman alıcı ve katma değer üretme düzeyi düşük olan çalışma safhalarının hızlanmasını sağlar. Bunun yanında hesaplama ve test süreçleri gibi katma değer elde edildiği ve asıl fark yaratılması hedeflenen kısımlarda da sağladığı imkanlarla kaliteli içerik ve daha odaklı çalışma kabiliyeti verir. Böylece proje üreticilerinin eforu, üretkenliğini artırılmasını sağlayan kısımlara ayrılır ve AR-GE çalışmasında hedef on ikiden vurulur. Bu sayede asıl amacın katma değer getirisi sağlamak olduğu bir kulvar olan AR-GE çalışmalarında, süreçte de katma değerli ve hedeflenen sonuca yönelik proje yönetim metodu sergilenir.

Tien, Nhut ve Thu'nun "İşletmelerde Yapay Zekânın AR-GE Performansına Etkisi" adlı makalesinde belirttiklerine göre, tekrar eden akış hâlindeki bilgilerin analizini içeren görevlerde yapay zekâ üretkenliği %30-50 oranında arttırırken işletmelere önemli bir maliyet tasarrufu sağlamasında yardımcı olur [5].

Bu bilgilerle, yapay zekânın pek çok sektörde AR-GE süreçlerini kolaylaştıran ve farklılaştıran bir destekçi olduğu tereddütsüz ifade edilebilir. İlk başlarda yapay zekâ, kuralları belirli bir algoritma içinde ilerleyen süreçlerde kullanılmış ve buna klasik yapay zekâ adı verilmiştir. Örneğin satranç gibi belirli bir örüntüde ilerleyen, sınırları belirlenmiş kombinasyonlardan oluşan çevrimlerde yapay zekâdan faydalanılarak kodlar yazılabileceği düşüncesi mevcuttu [6]. Makine öğrenimi teknolojilerinin belirli bir düzeye gelmesi, buna bağlı olarak derin öğrenme teknolojilerinin gelişmesi sonrasında büyük verinin analiz edilebilirliği ve klasik yapay zekâ örneklerindeki sınırlamalar dışında da kod geliştirmesinin mümkün olduğunun bilim çevrelerinde yerleşmesi sonrasında yeni ürünlerin geliştirilebildiği sektörlerden biri de ilaç sektörüdür. "ChEMBL" isimli molekül veri tabanı internet sayfasında 2 milyondan fazla molekülün etkileşimi ile oluşan 17 milyonu aşkın farklı molekül aktivitesi mevcuttur. Belirtilen büyük verinin incelenmesi, işlenmesi, yorumlanması aşamalarında bilgisayar teknolojilerinden faydalanılması AR-GE sürecinin hızlandırılmasında son derece önemli bir kısayoldur. Bir veri

setindeki moleküllerin tanımlayıcılar ile benzerliklerinin bulunması ve buradan hareketle aktivitelerinin yorumlanması yapay zekâ tarafından tahmin edilebilir. [7]

Zaman içerisinde kümülatif bilgi toplama ve bu bilgiyi işleme becerisi geliştiren yapay zekâ tabanlı uygulamalarla “karar verici” veya buna yardımcı mekanizmalar gelişmiştir. Tam burada “üretken tasarım” kavramından bahsetmekte yarar vardır. Fischer’in tanımlamasıyla üretken tasarım, tasarım araştırması sırasında parametrik ve analitik olarak işlev görebilen hesaplamalı bir yöntemdir. Üretken tasarım çerçevesinde tasarımcının otomasyon desteği ve hesaplamalı yöntemler sayesinde keşfetme ve karar verme yeteneği artar, böylece büyük tasarım alanları hızlıca taranır. Armağan’ın mimari tasarım süreçlerinde üretken tasarım yöntemlerinin kullanımını anlatırken belirttiği üzere, üretken sistemler tasarım esnasında monoton faaliyetleri bilgisayara delege edip, tasarım sürecindeki eforun büyük bölümünü yapay zekâyâ üstlendirmiştir [8].

CAD programlarının algoritma işleme yeteneğinin gelişmesi sonrasında mimârî ve alan tasarımlarında da yapay zekâ etkileri görülmeye başlanmıştır. Autodesk’in Toronto’daki MaRS İnovasyon Bölgesi’ndeki ofis iç mekan tasarımı buna örnek olarak gösterilebilir. Şirket çalışanları, kendi geliştirdikleri algoritma sayesinde; çalışanlardan toplanan iş tarzı, bitişiklik, düşük dikkat dağıtıcı etkenler, gün ışığı ve benzeri beklentileri üretken sisteme yükleyerek elde edilen çözümler sayesinde çalışma birimi, dolaşım alanı, aktivite alanı gibi kısımlar için geometrik alan tasarımları halinde 10.000 farklı öneri almışlar, önerileri değerlendirmek ve geliştirmek için de bulut tabanlı hesaplama yeteneklerinden yararlanmışlardır. [9]

AR-GE faaliyetleri sonucu elde edilen yeni ürün tasarımlarında yapay zekâ etkisi gözlemlenebilir hâle gelmiştir. Benzeri örneklerle mobilya tasarımlarında da rastlanılabilir. Yine Autodesk’in geliştirdiği yazılım sayesinde oturma birimi üretme algoritması kullanılarak boyut, ağırlık, malzeme, mukavemet, maliyet gibi bileşenlerle sisteme veriler tanımlanmış; üretken tasarım yazılımı ile mühendisler çözümleri önceliklere göre filtreleyip önerilen tasarımlar arasından uygun olanları belirlemişlerdir. Bu şekilde başlayan ilk adımlar sonrasında Autodesk Araştırma Merkezi’nin Dreamcatcher Projesi ile ortaya çıkan “Elbo” isimli sandalye; yalnızca yük ve mukavemet beklentilerini değil, estetik, üretim ve konfor uygunluklarını da karşılayarak yapay zekâ destekli ürün tasarımı sonuca ulaşmıştır [10]. Bu denli his ve duygu aktarımı gerektiren bir sektörde dahi, henüz sinaptik yetenekleri olmayan yapay zekâ destekli yazılım yardımıyla elde edilen sonuç ortadayken; ileride belirtilen yeteneklerin de yapay zekâ tarafından öğrenilip yansıtıldığı bir seviyeye gelindiğinde nasıl sonuçlar elde edileceği konusunda tahmin yürütmek hiç de kolay değil.

Yapay zekânın duyguları anlayabilen ve yorumlayabilen, sonrasında da yansıtabilen bir hüviyet kazanması mobilya, bebek ürünleri, tekstil, mutfak gibi sektörler için bir dönüm noktası olabilir. Buna antitez olarak sunulan bazı fikirlerde ise, yapay zekânın kusursuz tasarım parametreleri elde edip sunması sebebiyle hatalardan arındırılmış tasarımlar ortaya çıktığı ve bu durumun kullanıcıya duygu vermesinin mümkün olmayacağı ifade edilmiştir. Bir başka tez olan tasarımcının mesleğini kaybetme kaygısının da uzmanlar yersiz olarak nitelendirmiş; tasarımcının verdiği yüzlerce tasarım seçeneğini yapay zekânın önermesinin dahi tasarımcılara yeni alanlar açacağını ve sektörde insana ihtiyacın azalmayacağını ifade etmişlerdir [11].

SONUÇ

Özet olarak AR-GE, temel misyonuyla katma değer sağlayarak maliyet avantajı elde ettirme, üstün nitelikler kazandırma, yeni teknolojilerle donatılan ürünlerin rekabette öne geçmesini hedefleyen bir disiplindir. Her sektörde ve her alanda AR-GE faaliyeti aşamaları mevcuttur. Bu kadar geniş yelpazede ele alınan bir disiplin, doğal olarak teknolojik gelişmeleri ve trendleri kendi ihtiyacı doğrultusunda takip etmek ve entegre etmek ihtiyacındadır. İşte bu bildiride belirtilen sebeplerle yapay zekâ, AR-GE süreçlerindeki uygulamaları ile yeni ürün ve sistemler tasarlanmasında bir milat olma potansiyeli taşımaktadır. Kullanıcı kitlesi tarafından talep edilen

doğru ihtiyaçların tespiti, patent taramaları, analiz ve test süreçleri, raporlama, maliyetlendirme gibi alanların tümünde; araştırma ve geliştirme faaliyetlerini yürüten profesyonellerin destekçisi olma namzetidir.

KAYNAKLAR

- [1] Patent Aramada Mükemmelliği: Yapay Zeka Destekli Arama Aracı
<https://ipnote.pro/tr/blog/patent-aramada-mukemmelligi-yapay-zeka-destekli-arama-araci/>
- [2] Ar-Ge’de Yapay Zekâ: Keşfetmenin Yeni Yolu, Anlamanın Akıllı Hâli
<https://www.atptech.com/ar-gede-yapay-zeka-kesfetmenin-yeni-yolu-anlamanin-akilli-hali/>
- [3] Aiden, T. (2024), Artificial Intelligence, Scientific Discovery, and Product Innovation,
https://arxiv.org/abs/2412.17866?utm_
- [4] Jones, B. (2025). Artificial Intelligence in Research and Development
https://www.kellogg.northwestern.edu/faculty/jones-ben/htm/Artificial_Intelligence_in_Research_and_Development.pdf
- [5] Nhut, T. Ve Thu, P. (2025). Impact of AI on R&D performance of enterprises. Vol. 54 No. 5 (2025): Year 2025 , Volume 54 Issue 5
https://cuestionesdefisioterapia.com/index.php/es/article/view/3068?utm_
- [6] Yücel, M. A.(2022). İlaç araştırma ve geliştirme çalışmalarında makine öğrenimi, Yüksek Lisans Tezi, Sağlık Bilimleri Enstitüsü, Mersin Üniversitesi.
- [7] Yücel, M. A.(2022). İlaç araştırma ve geliştirme çalışmalarında makine öğrenimi, Yüksek Lisans Tezi, Sağlık Bilimleri Enstitüsü, Mersin Üniversitesi.
- [8] Armağan, Y. (2019). Mobilya tasarımında yapay zekâ: Tasarım ve AR-GE merkezleri üzerinden bir değerlendirme., Güzel Sanatlar Enstitüsü, Hacettepe Üniversitesi
- [9] Armağan, Y. (2019). Mobilya tasarımında yapay zekâ: Tasarım ve AR-GE merkezleri üzerinden bir değerlendirme., Güzel Sanatlar Enstitüsü, Hacettepe Üniversitesi
- [10] Armağan, Y. (2019). Mobilya tasarımında yapay zekâ: Tasarım ve AR-GE merkezleri üzerinden bir değerlendirme., Güzel Sanatlar Enstitüsü, Hacettepe Üniversitesi
- [11] Armağan, Y. (2019). Mobilya tasarımında yapay zekâ: Tasarım ve AR-GE merkezleri üzerinden bir değerlendirme., Güzel Sanatlar Enstitüsü, Hacettepe Üniversitesi

**GÖKYÜZÜNE YOLCULUK: ASTRO-TURİZM LİTERATÜRÜNÜN
BİBLİYOMETRİK DEĞERLENDİRMESİ**
JOURNEY TO THE SKY: A BIBLIOMETRIC EVALUATION OF ASTRO-TOURISM
LITERATURE

Mehmet SAĞIR

Doç. Dr., Selçuk Üniversitesi Turizm Rehberliği Bölümü

Ayşegül GÜDÜL

Doktora Öğrencisi, Selçuk Üniversitesi Sosyal Bilimler Enstitüsü Turizm İşletmeciliği
Anabilim Dalı

Ash Uğur AYDIN TAŞTEKİN

Bağımsız Araştırmacı Dr.

ÖZET

Bu çalışma, 1983-2025 yılları arasında yayımlanan 140 astro-turizm çalışmasını bibliyometrik analiz ile inceleyerek alanın güncel durumunu ve gelişim potansiyelini ortaya koymaktadır. Astro-turizm, gece gökyüzü gözlemi, astronomi etkinlikleri ve uzay deneyimleri gibi faaliyetleri kapsayan, özel ilgi ve doğa temelli bir turizm dalıdır. Çalışmada “astro-turizm” konulu dokümanların bibliyometrik analizinin yapılması amaçlanmaktadır. Analiz için R yazılımının ara yüzü olan RStudio Biblioshiny paketinden faydalanılmış ve Web of Science veri tabanında taranan dokümanlar analize dâhil edilmiştir. Taranan dokümanlarda temel bilgiler, yıllık yayın sayısı, referans, yazar ve anahtar kelime eşleşmeleri, en ilişkili yazarlar, yazar etkisi, en ilişkili dergiler, dergi etkisi, en ilişkili kurumlar, en fazla atıf alan ülkeler, en fazla atıf alan makaleler, kelime bulutu, tematik harita, referansların birlikte oluşum ağı, anahtar kelimelerin birlikte oluşum ağı ve ülkeler arası iş birlikleri incelenmiştir. Bulgular, astro-turizmin sürdürülebilir destinasyon yönetimi, çevresel farkındalık ve unutulmaz turizm deneyimleri çerçevesinde incelenmesi gerektiğini ortaya koymaktadır.

Anahtar Kelimeler: Astro-turizm, Uzay Turizmi, Özel İlgi Turizmi, Bibliyometrik Analiz, Web of Science

ABSTRACT

This study examines 140 astro-tourism studies published between 1983 and 2025 through bibliometric analysis to reveal the current state and development potential of the field. Astro-tourism is a branch of tourism based on special interest and nature, encompassing activities such as night sky observation, astronomical events, and space experiences. The aim of this study is to conduct a bibliometric analysis of documents on the subject of "astro-tourism". For the analysis, the RStudio Biblioshiny package, an interface of the R software, was used, and documents scanned in the Web of Science database were included in the analysis. In scanned documents were examined for basic information, annual publication count, references, author and keyword matches, most related authors, author influence, most related journals, journal influence, most related institutions, most cited countries, most cited articles, word cloud, thematic map, co-occurrence network of references, co-occurrence network of keywords, and international collaborations. The findings reveal that astrotourism should be examined within the framework of sustainable destination management, environmental awareness, and memorable tourism experiences.

Keywords: Astrotourism, Space Tourism, Special Interest Tourism, Bibliometric Analysis, Web of Science

GİRİŞ

Günümüzde özel ilgi turizmi türlerinin çeşitlenmesi, farklı temalara dayalı yeni turizm faaliyetlerinin ortaya çıkmasına olanak sağlamaktadır. Bu türlerden biri olan astro-turizm; gökyüzü gözlemi, astronomi bilimi, yıldızlar, gezegenler ve diğer gök cisimleriyle ilgili deneyimlere odaklanan bir turizm biçimi olarak dikkat çekmektedir. Özellikle artan ışık kirliliği, şehirleşme ve doğal alanların giderek azalması nedeniyle, gökyüzünün berrak biçimde gözlemlenebileceği alanların değeri her geçen gün artmaktadır. Bu durum hem yerel hem de uluslararası ölçekte astro-turizme olan ilgiyi artırmış ve çeşitli destinasyonlarda gözlem merkezleri ve özel gözlem otelleri gibi turistik ürünlerin gelişmesini sağlamıştır.

Turizm faaliyetlerinin gerçekleştirildiği bölgelere sağladığı sosyo-ekonomik faydalar göz önünde bulundurulduğunda, astro-turizmin yalnızca bir turistik etkinlikten ibaret olmadığı söylenebilir. Bu turizm türü, aynı zamanda doğa koruma bilincinin artırılmasına, sürdürülebilir destinasyon yönetimine ve yerel toplulukların ekonomik kalkınmasına katkı sunmaktadır. Literatürde yer alan çalışmalar, astro-turizmin kırsal bölgelerin turizm çeşitliliğini artırarak sezonluk turizmin dengelenmesine, çevresel farkındalığın yükseltilmesine ve bilimsel merakın desteklenmesine aracılık ettiğini ortaya koymaktadır. Bu çerçevede astro-turizmin farklı boyutlarıyla ele alınması hem akademik hem de uygulamalı turizm çalışmaları açısından önem kazanmaktadır.

Astro-turizm, son yıllarda yükselen bir turizm alanı olmasına rağmen literatürde sistematik ve kapsamlı bibliyometrik analizlerin sınırlı olması, araştırma boşluklarının ve eğilimlerin net bir şekilde ortaya konmasını engellemektedir. Bu çalışma, alanın mevcut durumunu ve gelişim trendlerini belirleyerek, araştırmacılara ve uygulamacılara astro-turizmin akademik ve pratik boyutlarına dair rehberlik sunmayı hedeflemektedir. Ayrıca, astro-turizmin ekonomik, çevresel ve kültürel katkılarının daha iyi anlaşılmasına ve turizm planlamasında stratejik kararların desteklenmesine katkı sağlayacaktır. Bibliyometrik yaklaşım sayesinde, literatürdeki odak noktaları, eksiklikler ve gelecekteki araştırma potansiyeli sistematik bir biçimde ortaya konacaktır.

Bu çalışma, astro-turizm alanında yayımlanan akademik çalışmaların bibliyometrik yöntemlerle sistematik bir analizini gerçekleştirmeyi amaçlamaktadır. Analiz kapsamında çalışmaların ana bilgileri, yıllara göre yayın sayısı, en fazla yayın yapan yazarlar, en fazla kaynak etkisine sahip olan yazarlar, en fazla yayın yapan kaynaklar, en fazla kaynak etkisine sahip olan kaynaklar, en fazla yayın yapan kurumlar, en fazla atıf alan ülkeler, en fazla atıf alan çalışmalar, kelime bulutu, tematik harita, referansların birlikte oluşum ağı, anahtar kelimelerin birlikte oluşum ağı ve ülkeler arası iş birliği incelenmiştir.

KAVRAMSAL ÇERÇEVE

Gökyüzü, insanlık tarihi boyunca yalnızca bir doğal manzara unsuru değil, aynı zamanda kültürel, dini ve bilimsel anlamlar yüklenen bir kaynak olmuştur. Tarih öncesi çağlardan itibaren mağara resimleri, takvimler, mitler ve kutsal mekânlar aracılığıyla gökyüzüyle kurulan ilişki, insanların evreni anlama ve yorumlama çabalarının en somut göstergelerindendir. Kozmik fenomenlerin gözlemlenmesi, insanlığın hem doğayı kavrayışını hem de kültürel gelişimini şekillendirmiştir. Günümüzde bu ilgi, yalnızca bilimsel araştırmaların değil, aynı zamanda turizmin de temel dinamiklerinden biri haline gelmiştir. Özellikle ışık kirliliğinden arındırılmış alanlarda gerçekleştirilen gözlemler, gökyüzünün doğal ve kültürel mirasın bir parçası olarak değerlendirilmesine olanak tanımaktadır. Bu bağlamda astro-turizm hem gece hem de gündüz gökyüzünü deneyimlemeyi merkeze alan, sürdürülebilir ve sorumlu turizm yaklaşımları arasında öne çıkan yeni bir turizm türü olarak literatürde yerini almıştır (Pásková vd., 2021, s. 9; Tapada vd., 2023, s. 129-130).

Astronomik turizm veya daha az sıklıkla yıldız turizmi olarak da adlandırılan astro-turizm, göksel fenomenlerin gözlemlenmesine odaklanan, doğal ve ışık kirliliğinden arındırılmış karanlık gökyüzünü ana kaynak olarak kullanan yeni, sürdürülebilir ve sorumlu bir turizm türüdür (C-Sánchez vd., 2019, s. 2; Escario-Sierra vd., 2022, s. 16-17). Pásková ve arkadaşlarına (2021) göre ise evreni kendi duyularıyla keşfetmeye ve tadını çıkarmaya odaklanan hem gece hem de gündüz gökyüzünü gözlemleyen özel bir turizm biçimi olarak kapsamlı bir şekilde tanımlanmaktadır. Doğaya dayalı bir turizm biçimi olup, ziyaretçilerin yeni ortamlar deneyimlemesini ve evlerinde bulunmayan özel tesisleri bulmasını sağlamakta ve doğal bir şekilde meydana gelen göksel olayların ziyaret edilerek gözlemlenmesine odaklanmaktadır (C-Sánchez vd., 2019, s. 4; Tapada vd., 2023, s. 118; Proos, 2025, s. 95). Astro-turizm üzerine yapılan çalışmalar, farklı ülkelerdeki gözlemevleri, karanlık gökyüzü alanları ve milli parklar gibi örnekler üzerinden gerçekleştirilmiş olup turist profilleri, motivasyonları, deneyim algıları ve destinasyon yönetimi stratejileri üzerine odaklanmıştır (Wassenaar & Coetzee, 2025, s. 11; Tapada vd., 2023, s. 119).

21. yüzyılın başlarından itibaren ortaya çıkan "Astro-turizm" terimi, ilk kez 2007 yılında kamuya açık bir şekilde Declaration in Defence of Thenight Sky and the Right to Starlight'te (Uluslararası Gece Gökyüzünün Kalitesi ve Yıldız Işığı Gözlem Hakkı Konferansı) İspanya'nın La Palma kentinde tanıtılmıştır. Bu konferans, astro-turizmin uluslararası bir kavram olarak resmiyet kazanmasında önemli bir dönüm noktası olmuştur (Pásková vd., 2021, s. 6; Tapada vd., 2021, s. 125). Bu bildiri, ışık kirliliğinin ekosistemler ve astronomik gözlemler üzerindeki zararlı sonuçlarına dair artan farkındalıktan doğmuş, gece gökyüzünün etik olarak yeniden konumlandırılmasına ve değer görmesine yol açmıştır. Bildiride turizm ve gökyüzü ilişki şu şekilde ifade edilmektedir (Starlight Declaration, 2007, s. 4):

“Turizm, diğer işlevlerinin yanı sıra, gece gökyüzünün kalitesinin korunması ve savunulmasında önemli bir araç haline gelebilir. Sorumlu turizm yaklaşımı, her destinasyonda gökyüzünü korunması ve değer verilmesi gereken bir kaynak olarak ele almak durumundadır. Gece gökyüzünün ve göksel olayların gözlemlenmesine dayalı yeni turistik ürünlerin geliştirilmesi, turizm paydaşları, yerel topluluklar ve bilimsel kurumlar arasında beklenmedik düzeyde iş birliği fırsatlarının doğmasına olanak tanımaktadır. Bu bağlamda, turizmin yalnızca ekonomik bir faaliyet değil, aynı zamanda doğal ve kültürel mirasın korunmasına katkı sunan bir araç olduğu ileri sürülebilir.”

Turizm, geniş kitlelere ulaşabilen, farkındalık yaratma gücü yüksek ve ekonomik getiriye çevresel koruma ile birleştirebilen bir sektör olduğundan, gece gökyüzünün korunması için etkili bir araç olarak öne çıkarılmaktadır. Astro-turizm ekonomik ve bölgesel kalkınma, çevresel koruma, ışık kirliliği ile mücadele, kişilerin bilimsel anlamda öğrenmesi olmak üzere birçok yönden fayda sağlamaktadır. Bu faydalardan şu şekilde bahsetmek mümkündür:

Ekonomik ve Bölgesel Kalkınma: Az nüfuslu bölgeler için değerli bir kaynak olup yerel toplulukların katılımı, güçlenmesi ve bölgesel kalkınmayı teşvik etmektedir (Pásková, 2021, s. 3; Tapada vd., 2021, s. 128). Kırsal alanlarda sürdürülebilir kalkınma için önemli bir itici güç olmakla birlikte, istihdam yaratma, beceri geliştirme ve yoksulluğu azaltma yoluyla yerel ekonomiyi iyileştirmektedir (Jacobs vd., 2020, s. 100-101; Kanińska vd., 2020, s. 13). Kaynaklarını yüksek sezon dışında da değerlendirebileceği için turizm sezonunun sürdürülebilirliğine de katkı sağlamaktadır. Işık kirliliğinden arındırılmış gökyüzünü ek bir gelir kaynağı, istihdam yaratma ve sosyo-ekonomik kalkınmaya da dönüştürmektedir (Escario-Sierra vd., 2022, s. 5,17).

Çevresel Koruma: Astro-turizm, ışık kirliliğiyle mücadelede önemli bir rol oynamakta ve "karanlık gökyüzü" koruma çabalarını desteklemektedir. Verimli yapay ışık kullanımı yoluyla CO² emisyonlarının azaltılmasına katkıda bulunmaktadır (Escario-Sierra vd., 2022, s. 16).

Ayrıca, taşıma kapasitenin aşılmaması adına kişi sayısının da ona göre belirlenmesi önemlidir (Wassenaar ve Coetzee 2025, s. 10).

Işık Kirliliğiyle Mücadele: Işık kirliliğinden arındırılmış karanlık gökyüzü temel bir ön koşuldur. Bu, gece gökyüzünün doğanın ayrılmaz bir parçası olarak korunmasını savunarak diğer turizm türlerinden belirgin bir şekilde ayrılmaktadır (Escario-Sierra vd., 2022, s. 16). Gece gökyüzünü korumaya yönelik bilinçli ışık kirliliğini azaltma girişimleri sunmaktadır (Wassenaar ve Coetzee 2025, s. 10).

Eğitimsel ve Bilimsel Gelişim: Astronomi bilgisinin yayılması ve bilimsel araştırmaların popülerleşmesine katkı sağlamaktadır. Turistleri doğaya yaklaştırarak, fiziksel dünyayı anlamaları, astronomi eğitimini teşvik etmeleri ve ışık kirliliğine karşı ekolojik bilinci artırmalarına yardımcı olmaktadır (Escario-Sierra vd., 2022, s. 3-4).

Sosyal ve Kültürel Faydalar: Çevreci bir bakış açısına sahip, yüksek sosyo-eğitim düzeyine sahip turistleri çekmekte ve yerel topluluklar arasında öz saygı ve girişimciliği teşvik etmektedir (Escario-Sierra vd., 2022, s. 4: 9). Yerel toplulukların miraslarının korunmasına ve yeniden değerlendirilmesine olanak tanımaktadır. Tüm bunlara ek olarak (Jacobs vd., 2020, s. 100; Kanianska vd., 2020, s. 13; Santos-Souza ve O-Dias 2023, s. 17; Proos 2025, s. 95);

- En önemli varlıkları olan karanlık gökyüzü, bakım veya geliştirme gerektirmedikten astro-turizmi benzersiz kılmaktadır.
- Manzara doğrudan gökyüzünün kendisidir.
- Her zaman mevcuttur.
- En sürdürülebilir cazibe merkezlerinden biri olarak kabul edilmektedir.
- Kitle turizminden farklılaşan, uzmanlaşmış faaliyetler sunmakta ve turistlere bilgi açısından zengin deneyimler sağlamaktadır.
- Yerinde ve belirli bir uzmanlık derecesine sahip uzmanlar gerektirmektedir.

Astro-turizmin en ayırt edici özelliği, en önemli kaynağı olan karanlık gökyüzünün herhangi bir bakım ya da geliştirme gerektirmeden doğal bir cazibe merkezi sunmasıdır. Bu durum, astro-turizmi hem sürdürülebilirlik açısından hem de turistik çekicilik bakımından diğer turizm türlerinden farklı bir konuma taşımaktadır. Bunun yanı sıra gökyüzünün her zaman erişilebilir olması, kitle turizminden ayrılan uzmanlaşmış deneyimler sunması ve bilgi temelli öğrenme fırsatları sağlaması da astro-turizmin cazibesini artırmaktadır. Ancak bütün bu avantajlar içinde, karanlık gökyüzünün kendiliğinden var olan, tükenmeyen ve korunması gereken doğal bir değer olması, astro-turizmin benzersizliğini ve geleceğe yönelik önemini en güçlü biçimde ortaya koymaktadır.

Literatür incelendiğinde astro-turizmin yalnızca ekonomik katkılarla sınırlı kalmadığı; çevresel koruma, ışık kirliliğiyle mücadele, bilimsel gelişim, eğitim, sosyal faydalar ve kültürel mirasın korunması gibi çok yönlü etkiler yarattığı görülmektedir. En temel kaynağı olan karanlık gökyüzü, bakım ya da geliştirme gerektirmemesi nedeniyle benzersiz bir değer sunmakta, sürdürülebilir ve farklılaşmış bir turizm türü olarak dikkat çekmektedir. Bu yönleriyle astro-turizm, yerel toplulukların kalkınması, çevresel bilincin artması ve turizmde çeşitliliğin sağlanmasına katkıda bulunan bir alan olarak konumlanmaktadır. Dolayısıyla hem akademik çalışmalar hem de pratik uygulamalar açısından gökyüzünün bir turizm kaynağı olarak değerlendirilmesi, geleceğin sürdürülebilir turizm politikaları için stratejik bir önem taşımaktadır.

YÖNTEM

Araştırmada çalışmaların başlığında “astrotourism”, “astro-tourism” ya da “astro tourism” geçen ve WoS’ta taranan çalışmalarının bibliyometrik özelliklerinin belirlenmesi amaçlanmaktadır. Bunun için çalışmada, doğrudan veya doğrudan olmayan yazılı kaynaklarının içeriğini analiz etmek için kullanılan doküman analizi (Robson, 2017) kullanılmıştır. Bibliyometrik analiz, belirli bir alandaki yayınlanmış bilimsel literatürün niceliksel analizini ifade etmektedir. Bu analiz türü, bir araştırma alanındaki eğilimleri,

bağlantıları ve genel görünümü anlamak için kullanılmaktadır. Akademik yayınların analizine odaklanan bibliyometri, yayın kalıplarını, yazarlık eğilimlerini, atıf ağlarını ve konu gelişimini incelemek için kullanılmaktadır. Bibliyometrik analiz bilimsel çıktıları değerlendirmek, araştırma trendlerini belirlemek, araştırma iş birliklerini analiz etmek, bilimsel bilginin yapısını haritalandırmak, gelişmekte olan alanların belirlenmesinde yardımcı olmak, yeni kavramların gelişimini ve zaman içerisinde nasıl evrimleştiğini izleme olanağı sağlamak gibi birçok amaç için kullanılmaktadır (Ellegaard ve Wallin, 2015; Alsharif vd., 2020; Passas, 2024).

WoS'ta yapılan araştırma doğrultusunda başlığında “astrotourism”, “astro-tourism” ya da “astro tourism” geçen 1983-2025 yılları arasında yayınlanmış, 140 doküman olduğu belirlenmiştir. Konunun yeni olması ve kaynakların kısıtlı olması sebebiyle herhangi bir kısıtlamaya gidilmemiş ve çalışmaların tamamı analize dâhil edilmiştir. Yapılan bibliyometrik analiz aracılığıyla şu sorulara cevap aranmıştır:

- Çalışmalar hangi yıllarda yayımlanmıştır?
- Çalışmaların referans, yazar ve anahtar kelime eşleşmesi nasıldır?
- En çok yayın yapan 10 yazar kimdir?
- En çok etkiye sahip olan 10 yazar kimdir?
- En çok yayın yapan 10 kaynak hangileridir?
- En çok kaynak etkisine sahip olan 10 kaynak hangileridir?
- En çok yayın yapan 10 kurum hangileridir?
- En çok atıf alan 10 ülke hangileridir?
- En çok atıf yapılan 10 çalışma hangileridir?
- Çalışmalarda en sık kullanılan kelimeler hangileridir?
- Çalışmaların tematik haritası nasıldır?
- Çalışmalardaki referansların birlikte oluşum ağı nasıldır?
- Çalışmalardaki anahtar kelimelerin birlikte oluşum ağı nasıldır?
- Çalışmalarda hangi ülkeler arasında iş birliği yapılmıştır?

Veri Analizi

Araştırmada, ilgili çalışmaların bibliyometrik analizini yapmak amacıyla R Programı'nın ara yüzü olan RStudio ve Biblioshiny paketi (4.3.1. versiyon) kullanılmıştır. WoS veri tabanından alınan çalışmalara ait veriler, RStudio programı için uygun olan formata dönüştürülmüş ve veri seti program aracılığıyla analiz edilmiştir.


Bulgular

Analize dâhil edilen dokümanlara ilişkin temel bilgiler Tablo 1'de gösterilmektedir.

Tablo 1. Çalışmalara İlişkin Temel Bilgiler

Tanım	Sonuç
Yayın Yılları	1983:2025
Kaynak (Dergi, Kitap)	93
Doküman Sayısı	140
Yıllık Büyüme Yüzdesi (%)	3,03
Ort. Doküman Yaşı	11,6
Doküman Başı Atıf	10,36
Referanslar	3114
Anahtar Kelimeler (ID)	115
Anahtar Kelimeler (DE)	278
Yazarlar	271
Tek Yazarlı Makalelerin Yazarı	74
Tek Yazarlı Makaleler	76
Doküman Başına Ortak Yazar	2,05
Uluslararası Ortak Yazar (%)	13,57


Tablo 1 incelendiğinde, 1983-2025 yılları arasında WoS veri tabanında taranan konu ile ilgili 140 doküman yayımlandığı görülmektedir. Bu dokümanlar 271 farklı yazar tarafından 93 farklı kaynaktan yayınlanmıştır. Dokümanların yıllık büyümesi %3,03 ve ortalama doküman yaşı 11,6'dır. Dokümanlardaki uluslararası iş birliği oranının ise %13,57 olduğu görülmektedir. Dokümanların yayınlanma yılı Grafik 1'de gösterilmektedir.



Şekil 1. Çalışmaların Yayınlanma Yılları

Şekil 1 incelendiğinde 1983'te 2, 1984'te 1, 1985'te 2, 1986-1990 yılları arasında 0, 1991 ve 1992'de 1, 1993'te 0, 1994'te 2, 1995'te 0, 1996'da 1, 1997'de 2, 1998'de 1, 1999'da 3, 2000'de 0, 2001 ve 2002'de 2, 2003'te 1, 2004'te 2, 2005'te 5, 2006'da 3, 2007'de 1, 2008'de 2, 2009'da 1, 2010'da 6, 2011'de 10, 2012'de 3, 2013'te 5, 2014'te 3, 2015'te 5, 2016'da 2, 2017'de 7, 2018'de 5, 2019'da 8, 2020'de 13, 2021'de 9, 2022 ve 2023'te 8, 2024'te 6 ve 2025'te 7 doküman yayınlandığı görülmektedir.

Astro-turizm ile ilgili çalışmalara ait referans, yazar ve anahtar kelime eşleşmeleri Şekil 2'de gösterilmektedir.




Şekil 2. Referans, Yazar ve Anahtar Kelimelere İlişkin Eşleşmeler

Şekil 2'de gösterilen referans, yazar ve anahtar kelime eşleşmeleri incelemek yapılan diyagram incelendiğinde dokümanlarda verilerin referansların Gaston (2013), Falchi (2016), Kyba

INTERNATIONAL TOPKAPI CONGRESS VI

(2017), Hanel (2018), Jacobs (2020), Weaver (2011), Cinzano (2001), Soleimani (2019), Fayos (2014), Rodrigues (2015), Cater (2010), Paskova (2021) ve Trauer (2006) olduğu görülmektedir. Çalışmalarda ortak olarak en sık kullanılan anahtar kelimelerin ise 11 kez astrotourism (astroturizm), 7 kez light pollution (ışık kirliliği), 5 kez stargazing (yıldız gözlemi), photometer (fotometre), ve astro-tourism (astro-turizm), 4 kez heritage (miras), night sky brightness (gece gökyüzü parlaklığı), 2 kez scientific tourism (bilimsel turizm), tourism (turizm), ve 1 kez astrotourism experience (astroturizm deneyimi), conference (konferans), space tourism (uzay turizmi) olduğu görülmektedir.

Astro-turizm konusuyla ilgili en fazla yayına sahip olan 10 yazar Şekil 3'te gösterilmektedir.



Şekil 3. En Çok Yayını Olan 10 Yazar

Şekil 3'te konuyla en ilişkili 10 yazar gösterilmektedir. Konuyla ilgili en fazla yayının Calderon-Godoy, Jafari, Matrinez-Martin ve Rodrigues (3 makale) tarafından yapıldığı görülmektedir. Devamında ise Airey, Bocho-Roas, Carmona-Fernandez, Cohen, Hall ve Jaramillo-Moran (2 makale) yer almaktadır.

Astro-turizm konusuyla ilgili en fazla kaynak etkisine sahip olan 10 yazar Tablo 2'de gösterilmektedir.


Tablo 2. En Çok Kaynak Etkisine Sahip Olan 10 Yazar

Yazar	h_index	g_index	m_index	TC ¹	NP	PY_start
Rodrigues A.	3	3	0,5	38	3	2020
Airey D.	2	2	0,087	525	2	2003
Hall Cm.	2	2	0,095	19	2	2005
Jafari J.	2	3	0,059	93	3	1992
Abdollahi M.	1	1	0,167	1	1	2020
Admiranto Ag.	1	1	0,143	2	1	2019
Akson A.	1	1	0,167	1	1	2020
Akumu P.	1	1	0,167	1	1	2020
Almalik O.	1	1	0,5	1	1	2024
Alonso-Hernandez Jb.	1	1	0,143	7	1	2019

¹ TC: Toplam Atıf Sayısı NP: Toplam Makale Sayısı PY start: Yayına Başlanan Yıl

Tablo 2’de konuyla ilgili en fazla kaynak etkisine sahip olan yazarların sırasıyla Rodrigues, Airey, Hall, Jafari, Abdollahi, Admiranto, Akson, Akumu, Almalik ve Alonso-Hernandez olduğu görülmektedir.

Astro-turizm konusuyla ilgili en fazla yayının yapıldığı 10 kaynak Şekil 4’te gösterilmektedir.



Şekil 4. En Çok Yayın Yapan Kaynak

Şekil 4’te konuyla ilgili en fazla yayın yapan kaynaklar sıralanmıştır. Konuyla ilgili en fazla yayının 10 çalışma ile Annals of Tourism Research’te yapıldığı görülmektedir. İkinci sırada Sustainability ve Tourism Recreation Research, üçüncü sırada 4 makale ile Acta Astronautica ve Capjournal, dördüncü sırada New Scientist, Pasos-Revista De Turismo Y Patrimonio Cultural ve Tourism Managemet, beşinci sırada ise 10th Southeast Asia Astronomy Network ve Astronomical Heritage of the Middle East yer almaktadır.

Astro-turizm konusuyla ilgili en fazla kaynak etkisine sahip olan 10 kaynak Tablo 3’te gösterilmektedir.

Tablo 3. En Çok Kaynak Etkisine Sahip Olan 10 Kaynak

Kaynak	h_index	g_index	m_index	TC ²	NP	PY_start
Acta Astronautica	3	4	0,12	101	4	2001
Sustainability	3	5	0,6	35	7	2021
Tourism Recreation Research	3	7	0,14285714	166	7	2005
10th Southeast Asia Astronomy Network	2	2	0,28571429	5	2	2019
Annals of Tourism Research	2	10	0,04761905	495	10	1984
Current Issues in Tourism	2	2	0,28571429	76	2	2019
International Journal of Tourism Research	2	2	0,125	39	2	2010
Space Policy	2	2	0,06896552	25	2	1997
Tourism Management	2	3	0,07142857	69	3	1998
Tourism Review	2	2	0,33333333	20	2	2020


Tablo 3’te konu ile ilgili en fazla kaynak etkisine sahip olan kaynakların sırasıyla Acta Astronautica, Sustainability, Tourism Recreation Research, 10th Southeast Asia Astronomy

² TC: Toplam Atıf Sayısı NP: Toplam Makale Sayısı PY start: Yayına Başlanan Yıl

INTERNATIONAL TOPKAPI CONGRESS VI

Network, Annals of Tourism Research, Current Issues in Tourism, International Journal of Tourism Research, Space Policy, Tourism Management ve Tourism Review olduğu görülmektedir.

Astro-turizm konusuyla ilgili en çok yayın yapan 10 kurum Şekil 5'te gösterilmektedir.



Şekil 5. En Çok Yayın Yapan 10 Kurum

Şekil 5'te konuyla ilgili en fazla yayın yapan kurumlara ve ülkelerine bakıldığında bunların University of Extremadura (İspanya), University of Évora (Portekiz), University of the Free State (Güney Afrika), University of Surrey (Birleşik Krallık), University of Science and Technology of China (Çin), Hebrew University of Jerusalem (İsrail), Sciezor, University of Algarve (Portekiz), University of Aveiro (Portekiz) ve University of Canterbury (Yeni Zelanda) olduğu görülmektedir.

Astro-turizm konusuyla ilgili en fazla atıf yapılan 10 ülke Tablo 4'te gösterilmektedir.

Tablo 4. En Çok Atıf Yapılan 10 Ülke

Ülke	Yayın
İspanya	37
ABD	34
Portekiz	33
Birleşik Krallık	21
Polonya	19
Güney Afrika	16
Avustralya	13
Kanada	13
Çin	10
Yeni Zelanda	9

Tablo 4'te en fazla atıf alan ülkeler gösterilmektedir. Buna göre konuyla ilgili en fazla atıf alan 10 ülkenin sırasıyla İspanya, ABD, Portekiz, Birleşik Krallık, Polonya, Güney Afrika, Avustralya, Kanada, Çin ve Yeni Zelanda olduğu görülmektedir.

Astro-turizm konusuyla ilgili en fazla atıf alan 10 doküman Tablo 5'te gösterilmektedir.

Tablo 5. En Çok Atıf Alan 10 Doküman

Yazar(lar)	Doküman	Kaynak	Ulusal Atıf	Uluslararası Atıf	Ulusal/Uluslararası Atıf Oranı (%)	Normalleştirilmiş Ulusal Atıf	Normalleştirilmiş Uluslararası Atıf
Soleimani, S., Bruwer, J., Gross, M. J., & Lee, R. (2019)	Astro-tourism conceptualisation as special-interest tourism (SIT) field: A phenomenological approach	<i>Current Issues in Tourism</i>	11	45	24,44	8,00	6,32
Ingle, M. (2010)	Making the most of 'nothing': astro-tourism, the Sublime, and the Karoo as a 'space destination'	<i>Transformation : Critical Perspectives on Southern Africa</i>	7	25	28,00	3,23	1,79
Cater, C. I. (2010)	Steps to Space; opportunities for astrotourism	<i>Tourism Management</i>	6	32	18,75	2,77	2,29
Webber, D. (2013)	Space tourism: Its history, future and importance	<i>Acta Astronautica</i>	4	44	9,09	5,00	4,78
Billings, L. (2006)	Exploration for the masses? Or joyrides for the ultra-rich? Prospects for space tourism	<i>Space Policy</i>	2	22	9,09	3,00	3,00
Chang, Y. W. (2015)	The first decade of commercial space tourism	<i>Acta Astronautica</i>	2	48	4,17	5,00	2,29
Cohen, E., & Spector, S. (2020)	Space tourism-past to future: A perspective article	<i>Tourism Review</i>	2	16	12,50	8,67	2,02
Rodrigues, A., Loureiro, S. M. C., & Prayag, G. (2022)	The wow effect and behavioral intentions of tourists to astrotourism experiences: Mediating effects of satisfaction	<i>International Journal of Tourism Research</i>	2	23	8,70	8,00	2,07
Rodrigues, Á., Loureiro, S. M. C., Lins de Moraes, M., & Pereira, R. G. (2023)	Memorable tourism experience in the context of astrotourism	<i>Anatolia</i>	2	11	18,18	5,33	1,66
Apel, U. (1997)	Space tourism—A promising future?	<i>Space Policy</i>	1	3	33,33	2,00	2,00

Tablo 5’te gösterilen en fazla atıf alan çalışmaların özetleri incelendiğinde, Soleimani ve arkadaşları (2019) çalışmasında, astro-turizmin kavramsallaştırılması ve destinasyon imajı ile ilişkisini incelemiştir. Sonuç olarak, astro-turizmin sürdürülebilir biçimde gelişebilmesi için kavramsal netlik ve destinasyon imajı yönetiminin önem taşıdığını vurgulamıştır. Ingle (2010) çalışmasında, Karoo bölgesinin turizm yoluyla yeniden imajlandırılması, niş turizm fırsatları ve yerel topluluklar üzerindeki etkilerini incelemiştir. Sonuç olarak, astro-turizmin bölgesel kalkınmayı destekleyebileceği ancak doğal çevrenin korunmasının öncelikli bir gereklilik olduğuna ulaşmıştır. Cater (2010) çalışmasında, astro-turistlerin motivasyonları, deneyimleri ve bu niş turizm alanının yönetimsel ve endüstriyel potansiyelinin incelemiştir. Sonuç olarak, astro-turizmin olgunlaşan bir olgu hâline geldiği ve gelecekte turizmle araştırmayı birleştiren

çift yönlü bir endüstri oluşturma potansiyeli bulunmaktadır. Webber (2013) çalışmasında, uzay turizminin tarihsel gelişimi ve gelecekteki potansiyel etkilerini inlemiştir. Sonuç olarak, uzay turizminin insanlığın Güneş sistemine yayılma sürecinde temel bir yapı taşı olduğunu belirtmiştir. Billings (2006) çalışmasında, uzay turizminin tarihsel gelişimi, güncel lüks odaklı modeli ve gelecekteki olası etkileri ile gelişim potansiyelini incelemiştir. Sonuç olarak, uzayda ticari faaliyetlerin sürdürülebilir biçimde yürütülebilmesi için uluslararası bir hukuk ve düzenleme çerçevesinin gerekliliği vurgulanmaktadır. Chang (2015) çalışmasında, yörünge altı (suborbital) ve yörüngesel (orbital) uzay turizminin mevcut durumu, potansiyeli, pazar talebi, teknolojik gelişmeler ve karşılaşılan güvenlik/yasal zorluklar açısından incelemiştir. Sonuç olarak, yörünge altının uzun vadede ticari taşımacılıkta sürdürülebilir bir pazar oluşturabileceğini belirtmiştir. Cohen ve Spector (2019) çalışmasında, uzay turizminin geçmişten günümüze gelişimi ve gelecekteki potansiyelini incelemiştir. Sonuç olarak, uzay turizminin potansiyeli yüksek olmakla birlikte, etik, çevresel ve fizyolojik boyutlarda dikkatli değerlendirilmesi gerektiğini belirtmektedir. Rodrigues ve arkadaşları (2022) çalışmasında, astro-turizm deneyiminde hayranlık duygusunun turist memnuniyeti ve davranışsal niyetler üzerindeki etkilerini incelemiştir. Sonuç olarak, astro-turizmin hayranlık duygusu üzerinden pazarlanabileceği ve deneyim tasarımı bilimsel boyutların dikkate alınması gerektiği vurgulanmaktadır. Rodrigues ve arkadaşları (2023) çalışmasında astro-turizm deneyiminde turistlerin bilişsel ve duygusal süreçlerinin, sadakat ve tavsiye davranışları üzerindeki etkisini incelemiştir. Sonuç olarak, astro-turizm yöneticilerinin yalnızca ürün geliştirmeye değil, aynı zamanda öğrenme ve benzersizlik sağlayan yüksek değerli deneyimlere odaklanması gerektiğini belirtmiştir. Apel (1997) çalışmasında, uzay turizminin mevcut durumu, gelecekteki pazar potansiyeli, teknik ve teknik olmayan gereklilikleri ile karşılaşılabilecek riskleri incelemiştir. Sonuç olarak, uzay turizminin insanlı uzay uçuşlarının kabulünü artırarak uzay araştırmalarında ivme kazandırabilecek bir alan olduğunu belirtmiştir.


Astro-turizm konulu çalışmalara ilişkin kelime bulutu Şekil 6'da gösterilmektedir.



Şekil 6. Kelime Bulutu

Şekil 6’da taranan çalışmalara ait kelime bulutu gösterilmektedir. Çalışmalarda en sık kullanılan 10 kelimenin tourism (turizm), artificial-light (yapay ışık), astronomy (astronomi), brightness (parlaklık), future (gelecek), model (model), behavior (davranış), destination (destinasyon), destination image (destinasyon imajı) ve ecotourism (ekoturizm) olduğu görülmektedir.

Astro-turizm konulu çalışmalara ait tematik harita Şekil 7’de gösterilmektedir.




Şekil 7. Tematik Harita

Şekil 7’de gösterilen tematik harita incelendiğinde dört farklı kategoriye ayrıldığı görülmektedir. Sol üstte yer alan niş temalar, konuyla ilgili dar kapsamlı ve özel alanlara işaret ederken; sağ üstte yer alan motor temalar hem yaygın hem de niş nitelikteki konuları kapsayarak konunun merkezi ve hareketli alanlarını temsil etmektedir. Sol altta yer alan yeni veya kaybolan temalar, henüz ortaya çıkmakta olan veya önemini yitirmeye başlayan konuları göstermektedir. Son olarak, sağ altta yer alan temel temalar, motor temalara kıyasla daha az rastlanan ancak konunun temel bileşenlerini oluşturan konuları içermektedir.

Astro-turizm konusuna ait tematik harita incelendiğinde, niş temalarda bir küme bulunmakta ve bu kümede model (model), destination image (destinasyon imajı), experience (deneyim), landscape (manzara), life (yaşam) kavramları yer almaktadır. Motor temalarda iki küme bulunmakta ve ilk kümede destination (destinasyon), image (imaj), loyalty (sadakat), ikinci kümede ise behavior (davranış), ecotourism (ekoturizm), weather (hava durumu) kavramları yer almaktadır. Yeni ortaya çıkan ya da kaybolan temalarda iki küme bulunmakta ve ilk kümede astronomy (astronomi), light pollution (ışık kirliliği), ikinci kümede ise future (gelecek) kavramları yer almaktadır. Temel temalarda bir küme bulunmakta ve bu kümede tourism (turizm), artificial-light (yapay ışık), brightness (parlaklık), pollution (kirlilik) kavramları yer almaktadır. Management (yönetim), exposure (maruz kalma) ve hospitality (ağırlama) kelimeleri ise iki tema arasında konumlanmışlardır.

Astro-turizm konulu çalışmalara ilişkin referansların birlikte oluşum ağı Şekil 8’de gösterilmektedir.



Şekil 8. Referansların Birlikte Oluşum Ağı

Şekil 8’de referansların birlikte oluşum ağı incelendiğinde 5 kümeye ayrıldığı görülmektedir. 18 kaynak yer alan mor kümenin lideri Weaver (2011), 10 kaynak yer alan kırmızı kümenin lideri Kyba (2015), 9 kaynak yer alan mavi kümenin lideri Crouch (2009), 7 kaynak yer alan yeşil kümenin lideri Falchi (2016) iken 2 kaynak yer alan turuncu küme de ise Jafari (201) ve Tribe (1997) eşit yakınlık düzeyine sahiptir.


Astro-turizm konulu çalışmalara anahtar kelimelerin birlikte oluşum ağı Şekil 9’da gösterilmektedir.



Şekil 9. Anahtar Kelimelerin Oluşum Ağı

Şekil 9’da anahtar kelimelerin birlikte oluşum ağı incelendiğinde 3 kümeye ayrıldığı görülmektedir. En büyük küme mavi renkle gösterilirken, bu kümede tourism (turizm) ve astronomy (astronomi), kırmızı kümede artificial-light (yapay ışık) ve pollution (kirlilik) yer alırken, yeşil kümede ise destination image (destinasyon imajı) ve landscape (manzara) yer almaktadır.

Astro-turizm konulu çalışmalarda yapılan ülkeler arası iş birliği haritası Şekil 10’da gösterilmektedir.



Şekil 10: Ülkeler Arası İş Birliği Haritası

Şekil 10 ülkeler arasındaki iş birliğini bir dünya haritası olarak temsil ederken, ülkeler arasındaki iş birliğini vurgulamaktadır. Konuyla ilgili ülkeler arası iş birlikleri incelendiğinde, en fazla iş birliğinin Birleşik Krallık (7 çalışma), İspanya (7 çalışma), Yeni Zelanda (6 çalışma), Güney Afrika (5 çalışma), Almanya (4 çalışma), Kanada (4 çalışma), Kenya (4 çalışma), Morityus (4 çalışma), Portekiz (4 çalışma), Avustralya (3 çalışma), Finlandiya (3 çalışma), ABD (2 çalışma), Fransa (2 çalışma), İsrail (2 çalışma), Suudi Arabistan (2 çalışma), Şili (2 çalışma), Çin (2 çalışma), Arjantin (1 çalışma), İsveç (1 çalışma), İtalya (1 çalışma), Japonya (1 çalışma), Macaristan (1 çalışma), Polonya (1 çalışma), Türkiye (1 çalışma), Ukrayna (1 çalışma) yapıldığı görülmektedir.

SONUÇ

Bu çalışmada “astro-turizm” konulu çalışmaların bibliyometrik analizinin yapılması amaçlanmıştır. Bu doğrultuda, 1983-2025 yılları arasında konuyla ilgili 140 çalışma olduğu belirlenmiş ve bu çalışmaların ana bilgileri, yıllara göre yayın sayısı, referans-yazar ve anahtar kelime eşleşmeleri, en fazla yayın yapan yazarlar, en fazla kaynak etkisine sahip olan yazarlar, en fazla yayın yapan kaynaklar, en fazla kaynak etkisine sahip olan kaynaklar, en fazla yayın yapan kurumlar, en fazla atıf alan ülkeler, en fazla atıf alan çalışmalar, kelime bulutu, tematik harita, referansların birlikte oluşum ağı, anahtar kelimelerin birlikte oluşum ağı ve ülkeler arası işbirliği incelenmiştir.

Astro-turizm konulu çalışmalar yayın yılları açısından incelendiğinde, 1983-2025 yılları arasında en fazla yayının 2020 yılında yapıldığı görülmektedir. Bu yılın devamındaki yıllarda çalışma sayısı bu yıla oranla azalsa da öncesindeki yıllara göre artışın devam ettiğini söylemek mümkündür. Bu artışın çevresel sürdürülebilirlik, ışık kirliliği ile mücadele, destinasyon yönetimi ve deneyim tasarımı gibi temaların toplumsal ve politik gündemde öne çıkmasıyla paralel ilerlediği görülmektedir. Bu sonuç, astro-turizmin diğer konularla da ilişkili olduğunu ancak literatürde halen büyük eksikliklerin olduğunu göstermektedir.

Çalışmalarla ilgili en fazla yayın yapan yazarlar incelendiğinde Calderon-Godoy, Jafari, Matrinez-Martin ve Rodrigues (3 yayın)’in en fazla yayın yapan yazarlar olduğu görülmektedir. En fazla yayın yapan ve en fazla kaynak etkisine sahip olan yazarlar karşılaştırması yapıldığında, en fazla yayın yapan 4 yazarın (Rodrigues, Airey, Hall ve Jafari) en fazla kaynak etkisine sahip olan on yazar listesinde, hatta ilk 4’te yer aldığı görülmektedir. Dolayısıyla hem yayın sayısı hem de atıf etkisi bakımından ön sıralarda yer alan bu yazarlar, araştırma alanının kuramsal çerçevesinin oluşmasında ve konunun akademik görünürlüğünün artmasında belirleyici bir rol oynamaktadır. Bu durum aynı zamanda, alandaki bilgi üretiminin belirli araştırmacılar etrafında yoğunlaştığını da göstermektedir.

Konuyla ilgili en fazla yayın yapan kaynak Annals of Tourism Research (10 yayın) olurken, bu derginin en fazla kaynak etkisine sahip 5. kaynak olduğu da görülmektedir. En fazla yayın yapan ve en fazla kaynak etkisine sahip olan kaynaklar karşılaştırıldığında en fazla yayın yapan 6 kaynağın (Acta Astronautica, Sustainability, Tourism Recreation Research, 10th Southeast Asia Astronomy Network, Annals of Tourism Research, Tourism Management) en fazla kaynak etkisine sahip olan on kaynak listesinde de yer aldığı görülmektedir. Bu bulgu, söz konusu dergilerin yalnızca yayın sayısı bakımından değil, aynı zamanda bilimsel etki düzeyleri açısından da alanın öncü yayın organları olduğunu ortaya koymaktadır. Dolayısıyla, bu dergiler hem turizm hem de astronomi, çevre ve sürdürülebilirlik gibi disiplinler arası konularda alanın bilimsel görünürlüğüne yön veren yayın kaynakları konumundadır. Benzer biçimde Annals of Tourism Research, Sustainability, Acta Astronautica, Tourism Recreation Research gibi kaynakların hem yayın adedi hem de etki düzeyi açısından öne çıkması, astro-turizmin disiplinler arası niteliğinin turizm, çevre bilimleri, astronomi ve politika alanlarındaki seçkin dergilerde yankılandığını göstermektedir. Bu durum, araştırma alanının disiplinler arası yapısının güçlü olduğunu ve yüksek etki değerine sahip dergilerde yayımlanarak akademik etkinin geniş bir alana yayıldığını göstermektedir.

Kurumsal ve coğrafi dağılımların incelendiği en çok yayın yapan kurumlar, en çok atıf alan ülkeler ve ülkeler arası iş birliklerine dair sonuçlar birlikte değerlendirildiğinde, astro-turizm konusunun çok merkezli bir yapıda olduğu görülmektedir. En çok yayın üreten ülkeler İspanya, ABD ve Portekiz iken, uluslararası iş birlikleri açısından Birleşik Krallık, İspanya ve Yeni Zelanda öne çıkmaktadır. Kurum düzeyinde ise University of Extremadura (İspanya), University of Évora (Portekiz), University of Algarve ve University of Aveiro (Portekiz), University of the Free State (Güney Afrika) gibi üniversitelerin öne çıktığı görülmektedir. Bu durum, bazı ülkelerin yüksek sayıda yayın üretmesine rağmen iş birliklerinde daha sınırlı kalabileceğini, bazı kurumların ise daha az yayın üretse de uluslararası iş birliklerinde etkin rol oynadığını göstermektedir.

En fazla atıf alan çalışmalar astro-turizmin önemi açısından incelendiğinde, Apel (1997) çalışmasında, yörünge (orbital) ve yörünge altı (suborbital) uzay turizmine odaklanarak bu alanın temel ekonomik ve teknolojik dinamiklerini ortaya koymaktadır. Özellikle düşük maliyetli ulaşım ve yörünge altyapısı ihtiyacını vurgulayan araştırma, gelecekteki yörünge otelleri vizyonunu da içeren bir gelecek senaryosu sunmaktadır. Bu yönüyle, uzay turizminin ekonomik fizibilitesi ve teknolojik gelişim sürecine ilişkin öncü bir çerçeve oluşturduğu söylenebilmektedir.

Billings (2006), astro-turizmin yüksek maliyetli, niş bir pazar yapısına sahip olduğunu vurgulamakta ve bu faaliyetlerin yalnızca ekonomik değil, aynı zamanda etik ve çevresel boyutlarıyla da ele alınması gerektiğini belirtmektedir. Çalışma, özellikle uzayda bozulmamış ortamların korunması gerekliliğine dikkat çekerek, sürdürülebilir astro-turizm anlayışına kavramsal bir derinlik kazandırmaktadır. Aynı zamanda yazar, karasal uzay turizmi (örneğin gözlemevleri ve tutulma turları gibi faaliyetler) ile uzay temelli astro-turizm arasında motivasyonel ve deneyimsel bir süreklilik olduğunu ileri sürmektedir.

Chang (2015), astro-turizmi yörünge altı (SST) ve yörünge (OST) deneyimleri olarak iki kategoriye ayırmakta ve Virgin Galactic örneği üzerinden teknik ve ekonomik zorlukları irdelemektedir. Çalışma, ticari astro-turizmin ilk büyük büyüme potansiyelinin yörünge altı segmentte gerçekleşeceğini öne sürerek sektörel gelişim açısından önemli bir öngörü sunmaktadır.

Webber (2013), uzay turizminin sunduğu deneyimi psikolojik ve felsefi bir çerçevede ele almakta, uzaydan Dünya'ya bakma eyleminin yarattığı dönüştürücü etkiyi (overview effect) tartışmaktadır. Çalışma, aynı zamanda yeniden kullanılabilir uzay araçlarının astro-turizmin geleceği açısından önemini vurgulayarak teknik sürdürülebilirliğe katkı sağlamaktadır.

Cohen ve Spector (2019) ise uzay turizmini özel ilgi turizminin yeni bir dalı olarak değerlendirmekte ve mevcut astro-turizm faaliyetlerinin teknik sınırlılıklarını, duysal deneyim eksikliğini ve uzun vadeli sağlık risklerini eleştirel biçimde tartışmaktadır. Ayrıca, suborbital uçuşların iklim değişikliğine olan olası katkılarına dikkat çekerek çevresel boyutu gündeme taşımaktadır.

Diğer taraftan, karasal astro-turizm odaklı çalışmalar bu kavramı daha çok ekoturizm ve doğa temelli turizm bağlamında ele almaktadır. Ingle (2010), Güney Afrika'daki Karoo bölgesini örnek göstererek astro-turizmin sadece bilimsel bir etkinlik değil, aynı zamanda kültürel ve felsefi bir deneyim sunduğunu ileri sürmektedir. Çalışma, "yüce" (sublime) kavramı üzerinden insanın evren karşısındaki konumunu sorgulamakta ve karasal astro-turizmin ruhsal yönlerine dikkat çekmektedir.

Soleimani ve arkadaşları (2018), astro-turizmi doğa temelli turizmin niş bir alt türü olarak kavramsallaştırmakta ve "gökyüzü manzarası" (skyscape) kavramını destinasyon pazarlamasına entegre etme gereğini vurgulamaktadır. Bu yaklaşım, astro-turizmin destinasyon imajı çalışmalarına katkı sunarak alanın kuramsal temellerini güçlendirmektedir.

Rodrigues ve arkadaşları (2022), astro-turizmi kirletilmemiş gece gökyüzüne dayanan düşük yoğunluklu bir turizm türü olarak tanımlamakta ve hayranlık (awe) duygusunun zaman algısı, enginlik hissi ve benlik kaybı boyutlarını ampirik olarak ortaya koymaktadır. Bu bulgular, astro-turizmin derin psikolojik etkilerini bilimsel olarak kanıtlamaktadır. Aynı yazarların 2023 tarihli çalışmaları ise Unutulmaz Turizm Deneyimi (MTE) boyutlarını S-O-R (Stimulus-Organism-Response) modeli çerçevesinde test ederek, astro-turizm deneyiminin psikolojik mekanizmalarını açıklamaktadır.

Tüm bu çalışmaların bütüncül değerlendirmesi sonucunda, astro-turizmin yalnızca uzaya yapılan seyahatleri değil, yeryüzünde gerçekleştirilen astronomi temelli deneyimleri de kapsayan çok katmanlı bir olgu olduğu anlaşılmaktadır. Literatürde bu alanın teknik, ekonomik ve çevresel yönleri kadar, bireylerin deneyimsel, duygusal ve felsefi boyutlarına da odaklanıldığı görülmektedir. Dolayısıyla astro-turizm hem teknolojik ilerlemenin hem de insanın evrenle kurduğu anlam arayışının bir yansıması olarak turizm bilimine önemli katkılar sunmaktadır.

Çalışmaların kelime bulutu incelendiğinde; en sık kullanılan kelimelerin turizm, yapay ışık, astronomi, parlaklık, gelecek, model, davranış, destinasyon, destinasyon imajı ve ekoturizm olduğu görülmektedir. Çalışmaların tematik haritası incelendiğinde ise bu kelimelere ek olarak, deneyim, manzara, yaşam, hava durumu, ışık kirliliği, kirlilik, yönetim, maruz kalma ve ağırlama gibi kelimelerin eklendiği görülmektedir. Tematik haritada yer alan kavramların araştırma alanında turizm deneyiminin çevresel ve yönetsel boyutlarıyla birlikte ele alındığını göstermektedir. Bu temalar, bir yandan turizm faaliyetlerinin doğaya etkisini, diğer yandan da ziyaretçi memnuniyeti ve sürdürülebilir destinasyon yönetimi gibi konuları bütüncül biçimde yansıtmaktadır. Kavramlara ilişkin genel bulgu ise araştırma alanının turizm ile çevresel farkındalık arasındaki kesişim noktasında şekillendiğini ve ışık kirliliği, ekoturizm ve destinasyon yönetimi temalarının literatürdeki gelişiminde belirleyici rol oynadığını göstermektedir.

Tematik haritada her iki temada yer alan kavramlar incelendiğinde yönetim kavramı haritada eksenlerin kesişim noktasına yakın konumlanmış olup, alanın merkezinde yer almakla birlikte orta düzeyde gelişmiş bir tema olarak dikkat çekmektedir. Bu durum, yönetim konularının turizm literatüründe diğer temalarla ilişkili olduğunu ancak henüz olgunlaşma sürecini tamamlamadığını göstermektedir. Maruz kalma kavramı tematik haritada eksen çizgisine yakın konumlanmış olup, araştırma alanında merkezi bir konuma sahip olmasına karşın gelişmişlik düzeyi sınırlıdır. Bu durum, kavramın ışık kirliliği, çevresel maruziyet veya turistik deneyim bağlamında önem kazandığını, ancak literatürde henüz yeterince derinleşmediğini göstermektedir. Son olarak ağırlama kavramı tematik haritada merkez eksene yakın bir

konumda yer almakta olup, araştırma alanının temel bileşenlerinden biri olmasına karşın gelişim düzeyi orta seviyededir. Bu durum, ağırlama temasının turizm çalışmalarında merkezi bir kavram olduğunu, ancak yeni araştırma yönleriyle olan bağlantılarının henüz yeterince güçlenmediğini ortaya koymaktadır.

Referansların birlikte oluşum ağı ve anahtar kelimelerin birlikte oluşum ağı birlikte değerlendirildiğinde, referansların birlikte oluşum ağı belirli araştırmacı ve çalışmalar etrafında yoğunlaşırken (Weaver, Kyba, Crouch, Falchi gibi), anahtar kelime ağı da bu çalışmalardan türetilen temel temaları yansıtmaktadır; yani mor, kırmızı ve mavi kümeler aracılığıyla literatürdeki yoğun araştırma grupları, sırasıyla turizm ve astronomi, yapay ışık ve kirlilik ile destinasyon imajı ve manzara temalarıyla ilişkilendirilmektedir. Bu durum, araştırmacı ağlarının ve kavramsal odakların astro-turizm literatüründe birbirini tamamlayan bir yapı oluşturduğunu göstermektedir.

Ülkeler arası iş birliği incelendiğinde, konuyla ilgili araştırmaların ağırlıklı olarak İspanya, Birleşik Krallık, Yeni Zelanda, Güney Afrika, Almanya ve Kanada gibi ülkelerde yoğunlaştığı görülmektedir. Bu ülkelerin hem yüksek yayın sayısına hem de güçlü iş birliği ağlarına sahip olması, konunun Avrupa ve remi dili İngilizce olan ülkeler merkezli olarak geliştiğini göstermektedir. Yayın üretkenliği bakımından ise İspanya, ABD, Portekiz, Birleşik Krallık ve Polonya ön plana çıkmaktadır. Ülkeler arası iş birlikleri sayısının görece az olması hem disiplinler arası hem de ülkeler arası iş birliklerinin geliştirilmesi gerekliliğini göstermektedir. Örneğin, Türkiye ve bazı Avrupa ülkelerinde yapılan çalışmaların sayısının görece az olması, konunun bu ülkelerde henüz gelişim aşamasında olduğunu ve gelecekteki uluslararası ortak araştırmalar için önemli bir potansiyel barındırdığını ortaya koymaktadır.

Genel olarak, astro-turizm literatürü, teknik ve ekonomik boyutlardan psikolojik ve çevresel boyutlara kadar çok katmanlı bir yapıya sahip olmakla birlikte, alanın hızla büyüyen bir araştırma konusu olduğunu göstermektedir. Bu çalışma, gelecekteki çalışmalar için bazı önemli öneriler sunmaktadır; İlk olarak, ışık kirliliği ve çevresel maruziyet gibi sürdürülebilirlik temaları daha derinlemesine araştırılmalı ve turizm faaliyetlerinin ekosistemler üzerindeki etkisi incelenmelidir. İkinci olarak, yönetim, ağırlama ve destinasyon imajı gibi merkezi temalar üzerinde daha fazla ampirik çalışma yapılmalı, farklı ülkeler ve kültürel bağlamlar üzerinden karşılaştırmalı analizler geliştirilmelidir. Üçüncü olarak, astro-turizmin psikolojik ve deneyimsel boyutları, özellikle hayranlık, unutulmaz deneyim ve motivasyon bağlamında daha geniş örneklem gruplarıyla incelenmelidir. Son olarak, uluslararası iş birliği ve disiplinler arası yaklaşımların artırılması, alanın kuramsal ve uygulamalı gelişimini destekleyecektir.

Politika ve uygulama noktasında ise astro-turizm alanının kurumsal ve yönetsel açıdan ele alınması gereken üç temel gereksinin olduğu düşünülmektedir. Birincisi, karanlık gökyüzü koruma politikalarının ve ışık kirliliği azaltım stratejilerinin astro-turizm planlamasının merkezinde konumlandırılması; mekânsal planlama, yerel yönetim düzenlemeleri ve turistik işletmelerde aydınlatma standartlarının yeniden yapılandırılmasını gerektirmektedir. İkincisi, destinasyon imajı ve deneyim tasarımı süreçlerinde bilimsel, eğitici ve yüksek değerli içeriklerin geliştirilmesi, astro-turizmin yerel topluluklar için sürdürülebilir bir ekonomik kaynağa dönüşmesine katkı sağlayacaktır. Üçüncüsü, uluslararası iş birliklerinin güçlendirilmesi ve kapasite geliştirme programlarının yaygınlaştırılması, özellikle az temsil edilen bölgelerde araştırma altyapısının iyileştirilmesi yoluyla, astro-turizm alanının küresel bilgi ağına daha dengeli ve kapsayıcı bir biçimde entegre olmasına imkân tanıyacaktır.

Son olarak bu çalışma WoS veri tabanında taranan ve sadece başlığında astrotourism”, “astro-tourism” ya da “astro tourism” geçen çalışmaları kapsandığından dolayı, bazı sınırlılıklara sahiptir. Gelecek çalışmalarda farklı veri tabanlarının bir arada değerlendirilmesi, çalışmaya başka anahtar kelimelerin dâhil edilip (örneğin space tourism) gerçekleştirilmesi ya da çalışmaların sadece başlıkla sınırlandırılmamasının daha geniş kapsamlı sonuçların elde edilmesine yardımcı olacağı düşünülmektedir.

KAYNAKÇA

- Alsharif, A. H., Salleh, N. Z. M. ve Baharun, R. (2020). Bibliometric Analysis. *Journal of Theoretical and Applied Information Technology*, 98(15), 2948-2962.
- Apel, U. (1997). Space tourism—A promising future?. *Space Policy*, 13(4), 279-284.
- Billings, L. (2006). Exploration for the masses? Or joyrides for the ultra-rich? Prospects for space tourism. *Space Policy*, 22(3), 162-164.
- Cater, C. I. (2010). Steps to Space; opportunities for astrotourism. *Tourism Management*, 31(6), 838-845.
- Chang, Y. W. (2015). The first decade of commercial space tourism. *Acta Astronautica*, 108, 79-91.
- Cohen, E., & Spector, S. (2020). Space tourism-past to future: A perspective article. *Tourism Review*, 75(1), 136-139.
- C-Sánchez, E., Sánchez-Medina, A. J., Alonso-Hernández, J. B., & Voltes-Dorta, A. (2019). Astrotourism and night sky brightness forecast: First probabilistic model approach. *Sensors*, 19(13), 1-16.
- Ellegaard, O. ve Wallin, J. A. (2015). The Bibliometric Analysis of Scholarly Production: How Great is The Impact?. *Scientometrics*, 105, 1809-1831.
- Escario-Sierra, F., Álvarez-Alonso, C., Moseñe-Fierro, J. A., & Sanagustín-Fons, V. (2022). Sustainable tourism, social and institutional innovation—the paradox of dark sky in astrotourism. *Sustainability*, 14(11), 1-20.
- Ingle, M. (2010). Making the most of 'nothing': astro-tourism, the Sublime, and the Karoo as a 'space destination'. *Transformation: Critical Perspectives on Southern Africa*, 74(1), 87-111.
- Jacobs, L., Du Preez, E. A., & Fairer-Wessels, F. (2020). To wish upon a star: Exploring Astro Tourism as vehicle for sustainable rural development. *Development Southern Africa*, 37(1), 87-104.
- Pásková, M., Budinská, N., & Zelenka, J. (2021). Astrotourism—exceeding limits of the earth and tourism definitions?. *Sustainability*, 13(1), 1-25.
- Passas, I. (2024). Bibliometric Analysis: The Main Steps. *Encyclopedia*, 4(2), 1014-1025.
- Proos, E. (2025). Astro-Tourism: A search for the unknown in Bloemfontein, Free State, South Africa. *Development Southern Africa*, 42(1), 93-106.
- Robson C. (2017). Bilimsel Araştırma Yöntemleri. (S. Çinkır ve N. Demirkasımoğlu, Çev.) Ankara Anı Yayıncılık.
- Rodrigues, A., Loureiro, S. M. C., & Prayag, G. (2022). The wow effect and behavioral intentions of tourists to astrotourism experiences: Mediating effects of satisfaction. *International Journal of Tourism Research*, 24(3), 362-375.
- Rodrigues, Á., Loureiro, S. M. C., Lins de Moraes, M., & Pereira, R. G. (2023). Memorable tourism experience in the context of astrotourism. *Anatolia*, 34(2), 235-247.
- Santos-Souza, V., & Nascimento-Dias, B. L. (2023). Reflections about the conceptual bases of Geotourism and its sub-segments Space Geotourism, Celestial Geotourism and Astrotourism to create a univocal definition. *Anais da Academia Brasileira de Ciências*, 95(3), 1-20.
- Soleimani, S., Bruwer, J., Gross, M. J., & Lee, R. (2019). Astro-tourism conceptualisation as special-interest tourism (SIT) field: A phenomenological approach. *Current Issues in Tourism*, 22(18), 2299-2314.
- Starlight Declaration, (2007). https://fundacionstarlight.org/docs/files/33_english-declaration-in-defense-of-the-quality-of-the-night-sky-and-the-right-to-starlight.pdf (Erişim Tarihi: 01.09.2025).

INTERNATIONAL TOPKAPI CONGRESS VI

Tapada, A., da Encarnação Marques, C. S., Marques, C. P., & Costa, C. (2023). Astroturismo: A Imagem e a Intenção de Visita em Territórios de Baixa Densidade. O Caso do Norte Interior de Portugal. *RPER*, (66), 117-132.

Wassenaar, A. S., & Coetzee, B. A. (2025). Viability of astrotourism in South African National Parks as a revenue source for conservation. *KOEDOE-African Protected Area Conservation and Science*, 67(1), 1-13.

Webber, D. (2013). Space tourism: Its history, future and importance. *Acta Astronautica*, 92(2), 138-143.

**BALAYI TURİZMİNDE ALGILANAN HİZMET KALİTESİNİN PROMETHEE VE
KULLANICI YORUMLARIYLA DEĞERLENDİRİLMESİ**
EVALUATION OF PERCEIVED SERVICE QUALITY IN HONEYMOON TOURISM
WITH PROMETHEE AND USER REVIEWS

Mehmet SAĞIR

Doç. Dr., Selçuk Üniversitesi Turizm Rehberliği Bölümü

Ash Uğur AYDIN TAŞTEKİN

Bağımsız Araştırmacı Dr.

Ayşegül GÜDÜL

Doktora Öğrencisi, Selçuk Üniversitesi Sosyal Bilimler Enstitüsü Turizm İşletmeciliği
Anabilim Dalı

ÖZET

Günümüzde turistler, konaklayacakları turizm işletmelerini çeşitli kriterler doğrultusunda incelemekte ve işletmelerin sunduğu hizmetleri dikkate alarak tercih yapmaktadır. Bu durum, turizm işletmelerinin rekabet avantajı elde edebilmek için hizmet çeşitliliğine ve kalite standartlarına daha fazla önem vermelerini gerekli kılmaktadır. Yüksek harcama potansiyeline sahip bir niş pazar olan balayı turizmi, destinasyonlar için önemli ekonomik katkılar sunmakta olup, balayı çiftleri bu tip aktivitelere diğer turistlere göre daha fazla harcama yapabilirler. Balayı tatillerinin duygusal niteliği nedeniyle hizmet kalitesine ilişkin algılar daha hassas bir yapı göstermekle birlikte oda özellikleri, gastronomik hizmetler, personel davranışı ve kişiselleştirilmiş uygulamalar memnuniyet düzeyini doğrudan etkilemektedir. Çiftlerin mahremiyet, romantik atmosfer ve kusursuz hizmet beklentileri ise balayı deneyiminin temel bileşenlerini oluşturmaktadır.

Bu çalışmada, ETS Tur seyahat alışveriş platformunda yer alan ve her şey dâhil konseptinde hizmet veren balayı otelleri, misafir değerlendirme kriterlerine göre analiz edilmiştir. Araştırma kapsamında bölgede yer alan 20 balayı oteli incelenmiş ve otellerin çeşitli kriterlere ilişkin ağırlıkları Analitik Hiyerarşi Süreci (AHP) ile belirlenmiştir. Ardından çok kriterli karar verme yöntemlerinden PROMETHEE kullanılarak fiyat-performans, genel puan, hizmet, oda, tavsiye etme, yemek ve yüzme kriterleri doğrultusunda oteller sıralanmıştır. Analiz sonuçlarına göre, oteller için nihai sıralama yapılarak bu sıralama kullanıcı yorumları ile desteklenmiş olup, çiftlerin oda ve hizmet kriterlerine daha çok önem verdikleri belirlenmiştir.

Anahtar Kelimeler: Balayı Turizmi, Balayı Oteli, Çok Kriterli Karar Verme Yöntemleri, Analitik Hiyerarşi Süreci (AHP) Yöntemi, PROMETHEE Yöntemi

ABSTRACT

Today, tourists examine tourism businesses where they will stay according to various criteria and make their choices by considering the services offered by the businesses. This situation necessitates that tourism businesses pay more attention to service diversity and quality standards in order to gain a competitive advantage. Honeymoon tourism, a niche market with high spending potential, offers significant economic contributions to destinations, and honeymoon couples may spend more on these types of activities than other tourists. Because of the emotional nature of honeymoon vacations, perceptions regarding service quality are more sensitive, and room features, gastronomic services, staff behavior, and personalized applications directly affect the level of satisfaction. The couples' expectations of privacy, romantic atmosphere, and impeccable service constitute the basic components of the honeymoon experience. In this study, honeymoon hotels offering all-inclusive concept services on the ETS Tur travel shopping platform were analyzed according to guest evaluation criteria.

The research examined 20 honeymoon hotels in the region, and the weights of various criteria were determined using the Analytical Hierarchy Process (AHP). Then, using the multi-criteria decision-making method PROMETHEE, the hotels were ranked according to criteria of price-performance, overall rating, service, room, recommendation, food, and swimming. Based on the analysis results, a final ranking was created for the hotels, supported by user reviews, revealing that couples placed more importance on room and service criteria.

Keywords: Honeymoon Tourism, Honeymoon Hotel, Multi-Criteria Decision-Making Methods, Analytical Hierarchy Process (AHP) Method, PROMETHEE Method

GİRİŞ

Turizm sektörünün niş pazarlarından birisi olan balayı turizmi, çiftlerin evlilik sonrası özel ve unutulmaz bir deneyim yaşama arzusuna dayanan, yüksek beklentilerle şekillenen bir hizmet alanıdır. İngilizce “honeymoon” kavramına dayanan balayı, yeni evli çiftlerin evlilik sonrasında çıktıkları ilk özel tatil olarak tanımlanmaktadır. Balayının tarihçesi Antik Yunanlılara kadar uzanırken, modern tip balayları 1800’lerden beri devam etmektedir (Ünal vd., 2017, s. 65). 16. yüzyılda İngiltere’de düğün sonrası bir ay boyunca çiftlerin birlikte zaman geçirdiği ve bal şurubu tükettikleri bir dönemi ifade ederken, 19. yüzyılda özellikle soylu sınıf arasında düğünden hemen sonra kırsal destinasyonlara yapılan seyahatlerle ilişkilendirilmiş ve zaman içerisinde çiftlerin yalnız çıktığı özel bir tatil türüne dönüşmüştür. Daha sonraki dönemde orta sınıfın da bu tatillere yönelmesiyle balayı seyahatleri daha yaygın hâle gelmiştir (Türk, 2019). Balayı turizmi, destinasyonlar için ekonomik getiri sağladığı ve kendine özgü niş pazar özelliklerine sahip olduğu için turizm literatüründe öneme sahiptir. Balayı çiftleri diğer turistlere kıyasla önemli ölçüde daha fazla harcama yapmaktadır. Yeni evli çiftler, normal zamanlarda gittikleri bir tatilde yapacakları harcamanın yaklaşık üç katı kadar harcama yapmaya isteklidir (Ünal vd., 2017, s. 65). Diğer tatil türlerine göre harcama oranının daha yüksek olması ve yıllık büyüme oranının daha fazla olmasına rağmen balayı turizmiyle ilgili araştırmaların diğer tatil türlerine kıyasla daha az olduğu görülmektedir (Chen vd., 2020, s. 1188). Bundan dolayı, konuyla ilgili daha fazla araştırma yapılması gerektiği ve balayına giden çiftler için önemli olan faktörlerin belirlenmesinin öneme sahip olduğu düşünülmektedir.

Balayı turizmi, duygusal beklentilerin yoğun olduğu ve bireylerin yaşamlarındaki en özel deneyimlerden biri olarak görülen bir seyahat türüdür. Balayı tatilinin özelliği gereği, hizmet kalitesine yönelik algılar diğer turistik deneyimlere kıyasla daha hassas, subjektif ve bütünsel bir yapıya sahiptir. Çiftlerin konaklama sürecinde karşılaştıkları en küçük ayrıntı dahi, genel memnuniyet düzeyini önemli ölçüde etkileyebilmektedir. Bu nedenle otellerin sunduğu oda özellikleri, gastronomik hizmetler, personel davranışı, karşılama süreci, oda süslemeleri ve balayı konseptine özgü ikramlar gibi unsurlar, bu müşteri grubunda algılanan değer ve memnuniyet oluşumunda kritik rol oynamaktadır. Bu nedenle hizmet kalitesine ilişkin algı, diğer tatil türlerine kıyasla çok daha hassas ve yüksek standartlarla şekillenmektedir. Çiftlerin konaklama sürecinde aradıkları mahremiyet, romantik atmosfer, kişiselleştirilmiş hizmet ve özel karşılama gibi unsurlar balayı deneyiminin temel bileşenlerini oluşturmaktadır. Literatürde balayı turistlerinin beklentilerinin yalnızca fiziksel olanaklarla sınırlı olmadığı, aynı zamanda duygusal tatmin, özel hissetme ve kusursuz hizmet arayışına dayandığı vurgulanmaktadır. Fakfare ve Lee (2019) çalışmasında balayına giden çiftlerin beklentilerinin şu şekilde olduğunu belirtmiştir:

- Mahremiyetin sağlanması,
- Etkileyici manzaralar,
- Saygı gösterilmesi,
- Otel kalitesinin kabul edilebilir düzeyde olması,
- Destinasyon imajı (romantik, egzotik, lüks vb. olması),
- Yemeklerin kaliteli ve çeşitli olması,

- Balayı çiftlerinin statüsünün özel olarak tanınması/kabul edilmesi,
- Balayına çiftlerine özel hizmetlerin sunulması,
- Balayı çiftlerine özel indirimlerin yapılması,
- Balayı çiftlerine özel ücretsiz ek konaklama sunulması,
- Balayı çiftine hoş sürprizlerin yapılması (balayı pastası, sürpriz etkinlikler vb.).

Bunlara ek olarak, Türk (2019)'e göre balayı turistlerinin destinasyon tercihlerini etkileyen başlıca faktörler güvenlik, konaklama kalitesi, maliyet, iklim, ulaşılabilirlik, doğal ve kültürel değerler ile eğlence olanaklarıdır. Bunun yanı sıra yaş, cinsiyet, gelir ve eğitim gibi demografik özellikler de seçim sürecinde belirleyici rol oynamaktadır. Gelir ve zamanı yüksek çiftler daha çok yurtdışı destinasyonlarını tercih ederken, gelir ve zamanı sınırlı olanlar iç turizme yönelmektedir. Dünya genelinde Maldivler, Bali, Hawaii gibi destinasyonlar öne çıkarken, Türkiye'de Antalya ve Bodrum en çok tercih edilen destinasyonlar arasında yer almaktadır.

Son yıllarda balayı deneyimi, buddymoon kavramıyla dönüşüm geçirmiştir. Buddymoon, çiftlerin balayı süreçlerini yalnızca kendileri için değil, aile bireyleri, arkadaşlar veya sağdıç ve baş nedimler gibi yakın çevreleriyle paylaşarak gerçekleştirdikleri grup veya topluluk balayı deneyimini ifade etmektedir. Buddymoon kavramı, özellikle yetişkin veya ileri yaşta evlenen bireylerin evliliklerinin günlük yaşamlarını daha az etkilemesi bağlamında, balayı deneyimlerini yakın çevreleriyle paylaşarak bu deneyimi daha özel ve anlamlı hâle getirme amacıyla ortaya çıkmıştır (Buluk-Eşitti, 2020). Bu kavramla, balayı turizminin kapsayıcılığı artmakta, turist profillerini çeşitlenmekte ve grup odaklı deneyimlerin ön plana çıkma sağlanarak sektöre hem ekonomik hem de sosyal katkı sunulmaktadır. Sonuç olarak, buddymoon, destinasyonların balayı turizmi pazarını genişletmesine ve özel hizmet paketleri geliştirmesine imkân tanımaktadır.

Son yıllarda dijitalleşmenin turizm sektöründeki etkisinin artmasıyla birlikte, kullanıcı yorumları ve çevrimiçi değerlendirme platformları, tüketici karar süreçlerinin başlıca bilgi kaynaklarından biri hâline gelmiştir. Balayı otelleri gibi spesifik hizmet sunan işletmelerin performansının ölçülmesinde, kullanıcı yorumları giderek daha fazla önem kazanmaktadır. Bununla birlikte, bu niteliksel verilerin analitik yöntemlerle bütünleştirilmesi, hem hizmet kalitesi performansını nesnel biçimde değerlendirme hem de oteller arası karşılaştırma yapma açısından önemli bir avantaj sunmaktadır.

Turizm sektöründe kullanıcı yorumları, otel seçimi üzerinde güçlü bir belirleyici hâline gelmiştir. Çalışmalar, potansiyel turistlerin karar alma süreçlerinde çevrimiçi yorumları geleneksel tanıtım araçlarından daha güvenilir bulduklarını göstermektedir. Balayı turizmi gibi özel hizmet gerektiren kategorilerde ise kullanıcı yorumlarının etkisi daha da artmaktadır. Yorumların içeriği, duygusal tonlaması ve belirli hizmetlere yönelik değerlendirmeleri otel seçiminde kritik rol oynamaktadır. Dolayısıyla, kullanıcı yorumlarının sistematik olarak analiz edilmesi, otellerin güçlü ve zayıf yönlerinin belirlenmesinde önemli bir araç hâline gelmiştir.

Bu doğrultuda bu çalışma, balayı otellerinin hizmet kalitesi performansını analiz etmek amacıyla çevrimiçi kullanıcı yorumları ile çok kriterli karar verme (ÇKKV) yöntemlerinden PROMETHEE (The Preference Ranking Organization Method for Enrichment Evaluation) tekniğini bir araya getiren bütüncül bir yaklaşım önermektedir. Çalışmada elde edilen sıralamaların kullanıcı değerlendirmeleri ile tutarlılığı incelenerek hem kullanıcı algılarının hem de analitik yöntemlerin otel sınıflandırmaları üzerindeki etkisi değerlendirilmiştir. Böylece çalışma, balayı turizmi bağlamında hizmet kalitesinin belirleyicilerini daha kapsamlı bir çerçevede ele alarak literatüre teorik ve uygulamalı katkılar sunmayı amaçlamaktadır.

METODOLOJİ

Araştırmanın Amaç, Önem ve Katkıları

Bu araştırmada balayı konseptli konaklama işletmeleri, internet üzerinden müşterilerinden almış olduğu puanlar çerçevesinde değerlendirilecek, kriterlerin önem derecesi belirlenecek ve puanlara göre konaklama işletmeleri arasında sıralama yapılacaktır. Çalışma elde edilecek

sonuçlarla, balayı çiftlerini memnun edebileceği düşünülen kriterlerin belirlenmesi amaçlanmaktadır. Elde edilecek sonuçların balayı konseptli konaklama işletmelerinin hangi faaliyet ya da hizmetlerle çiftleri memnun edebileceğini anlamasını da sağlayacağı düşünülmektedir. Balayı konsepti olmayıp, buna yönelmek isteyen konaklama işletmeleri için ise nelere dikkat etmeleri gerektiği noktasında yardımcı olabilecektir. Tüm bunlardan dolayı, ÇKKV yöntemleri ile sıralamanın yapılmasının yanı sıra, elde edilen sonuçların kullanıcı yorumlarıyla desteklenmesinin de önemli olduğu düşünülmektedir.

Araştırmada öncelikli olarak AHP Yöntemi ile kriter ağırlıkları belirlenecek, sonrasında PROMETHEE Yöntemi ile konaklama işletmelerinin sıralaması yapılacak ve elde edilen bu sonuçlar kullanıcı yorumlarıyla birlikte değerlendirilecek ve balayı konseptli otellerin nelere dikkat etmesi gerektiği yönünde önerilerde bulunulacaktır. Tüm bunların yapılmasıyla birlikte, çalışmada elde edilen sonuçların hem sektör hem de literatüre katkı sağlayacağı düşünülmektedir.


Araştırma Grubu

Araştırma grubu olarak balayı konseptli konaklama işletmeleri belirlenmiştir. Türkiye genelinde tercih edilen seyahat alışveriş platformları incelendiğinde, büyük bir çoğunluğunda balayı konseptli konaklama işletmeleriyle ilgili herhangi bir filtrelemenin bulunmadığı ve bu filtrelemenin bazı platformlarda bulunduğu, bulunanlar incelendiğinde ise değerlendirme ve/veya yorumların analize dahil edilmek için yetersiz olduğu veya kriter puanlarının eksik olduğu görülmüştür. Tüm bunlardan dolayı, balayı konseptli 20 konaklama işletmesinin verilerine eksiksiz ulaşılabildiği için ETS Tur'un web sitesi tercih edilmiş ve 16.11.2025 tarihinde hem kriter puanları hem de misafir yorumları site üzerinden alınmıştır. Kriter puanlamaları genel olarak alınırken, yorumlar alınırken özellikle çiftler tarafından yapılmış olmasına ve “balayı” kelimesinin geçmesine dikkat edilmiş ve sadece bu yorumlar değerlendirilmiştir. Araştırmaya dâhil edilen 20 konaklama işletmesi fiyat-performans, genel puan, hizmet, oda, tavsiye etme, yemek ve yüzme kriterlerindeki puanlar üzerinden değerlendirilmiştir.

Yöntem

Araştırmada Türkiye genelinde balayı konseptiyle faaliyet gösteren konaklama işletmelerinin değerlendirilmesi amacıyla çok kriterli karar verme yöntemlerinden faydalanılmıştır. Araştırma sürecinde öncelikle kriter ağırlıklarının belirlenmesi için Analitik Hiyerarşi Süreci (AHP) Yöntemi uygulanmıştır. Kriter ağırlıkları belirlendikten sonra konaklama işletmeleri PROMETHEE Yöntemi ile sıralanmıştır.

Bu kapsamda, çalışmanın izlediği yöntemsel süreç aşağıda gösterilmiştir:



Şekil 1. Akış Şeması


Şekil 1'e göre, bu çalışmada balayı konseptli otel alternatiflerinin çok kriterli karar verme yöntemleriyle değerlendirilmesine yönelik bir akış şeması oluşturulmuştur. İlk aşamada, araştırmanın temelini oluşturan problem tanımlanmış ve alanyazın doğrultusunda karar verme sürecinde etkili olabilecek kriterler belirlenmiştir. İkinci aşamada, kriterlerin ağırlıklandırılmasında AHP Yöntemi kullanılmıştır. AHP, karar vericilerin kriterler arasında ikili karşılaştırmalar yapmasına olanak tanıyarak, her bir kriterin görece önem düzeyini sayısal olarak belirlemeye imkân sağlar. Bu yöntem sayesinde, karar verme sürecinde kullanılan kriterler arasında tutarlı ve sistematik bir değerlendirme yapılmış ve kriter ağırlıkları elde edilmiştir. Üçüncü aşamada, ağırlıklandırılmış kriterlere göre otel alternatifleri tercih akışlarına dayanan PROMETHEE yöntemiyle analiz edilerek sıralanmıştır.

Analitik Hiyerarşi Süreci (AHP) Yöntemi

Analitik Hiyerarşi Süreci (AHP), 1970'li yıllarda Saaty tarafından geliştirilen birçok kriterli karar verme yöntemidir (Saaty, 1987). Alternatiflere ait olan kriterlerin önceliklerini belirlemek için kullanılmaktadır. Bu yöntemde öncelikle kriterlerin karar verici tarafından belirlenmesi gerekmektedir. Kriterlerin belirlenmesinden sonra önem derecesine göre öncelikler ve alternatiflerin kriterlere göre performanslarını belirlenmektedir (Saaty, 2001, s. 16). AHP turizm alanında sıklıkla kullanılan bir yöntemdir. Bu çalışmalara kış turizmi (Oğuz, 2018), akıllı turizm (Erdem vd., 2022), sağlık turizmi (Dalkıran ve Göncü, 2023), ekoturizm (İşler ve Akyurt, 2021), termal turizm (Gündüz ve Güler, 2015), sağlık turizmi (Sonel vd., 2019), kongre turizmi (Welthagen vd., 2022), kırsal turizm (Lee ve Kim, 2009), yelken turizmi (Butowski, 2018), bisiklet turizmi (Bakogiannis vd., 2020) örnek gösterilebilir. AHP Yöntemi'nin uygulama adımları şu şekildedir (Saaty, 1987):

Adım 1: Hiyerarşik Yapının Oluşturulması.

AHP Yöntemi'nde hiyerarşik yapı amaç, kriterler ve alternatiflerin belirlenmesi aşamasıdır. Bu aşamada oluşturulan hiyerarşik yapıda en üstte amaç, ortada kriterler ve en altta ise alternatifler yer almaktadır. AHP Yöntemi'nde hiyerarşik yapı Şekil 2'de gösterildiği gibidir.



Şekil 2. Hiyerarşik Yapı

Adım 2: İkili Karşılaştırma Matrisleri ve Üstünlüklerin Belirlenmesi.

Hiyerarşik yapının oluşturulmasından sonra belirlenen kriterler ve varsa alt kriterlerin önem derecelerinin kendi arasında belirlenmesi için ikili karar matrisi oluşturulmaktadır. Bu matriste kriterler ve/veya alternatifler için kriterler ve/veya alternatifler ikili olarak karşılaştırılmaktadır.

$$\begin{bmatrix} 1 & a_{21} & a_{31} & \cdots & a_{n1} \\ 1/a_{21} & 1 & \vdots & \cdots & a_{n2} \\ 1/a_{31} & 1/a_{32} & 1 & \cdots & a_{n3} \\ \vdots & \vdots & \vdots & \ddots & \cdots \\ 1/a_{n1} & 1/a_{n2} & 1/a_{n3} & \cdots & 1 \end{bmatrix}$$

İkili karşılaştırmanın yapılması ve üstünlüklerin belirlenmesi için Saaty (1990) tarafından geliştirilen Önem Ölçeği'nden faydalanılmalıdır. Önem Ölçeği'nde derecelendirmeler Tablo 1'de gösterildiği gibidir.

Tablo 1. Önem Ölçeği

Sayısal Değer	Tanım
1	Eşit Önem
3	Orta düzeyde önem (biri diğerinin üstünde)
5	Temel veya güçlü önem
7	Çok güçlü önem
9	Aşırı önem
2,4,6,8	Ara değerler

Kaynak: Saaty, 1990, s. 15

Önem Ölçeği'ne göre kriterlerin önem sıralaması belirlenirken Tablo 1'de gösterilen değerlerden faydalanılmaktadır. Buna göre iki kriter karşılaştırılırken eşit öneme sahiplerse 1, biri diğerinden orta düzeyde öneme sahipse 3, temel veya güçlü öneme sahipse 5, çok güçlü öneme sahipse 7, aşırı öneme sahipse 9 puan verilmekte, 2, 4, 6 ve 8 ise ara değerler olarak kabul edilmektedir.

Adım 3: Özvektörün Belirlenmesi

İkili karşılaştırma matrisinin oluşturulmasından sonra, matriste yer alan her bir kriter ve/veya alternatifin diğerlerine göre öneminin hesaplandığı adımdır.

$i=1,2,3,\dots,n$ ve $j=1,2,3,\dots,n$ olmak üzere,

$$b_{ij} = \frac{a_{ij}}{\sum_{i=1}^n a_{ij}} \quad w_i = \frac{\sum_{j=1}^n b_{ij}}{n}$$

Adım 4: Özvektör Tutarlılığının Hesaplanması

Özvektörlerin belirlenmesi aşamasındaki ikili karşılaştırma matrisi için tutarlılık oranlarının (CR) hesaplandığı aşamadır. Tutarlılık oranının $\leq 0,10$ olması gerekmektedir. Tutarlılık oranının olması gerekenden fazla olması karar vericinin tutarsızlık gösterdiği anlamına gelmekteyken, karar vericinin Önem Ölçeği'ne verdiği cevapları tekrar gözden geçirmesi gerektiğini göstermektedir

$$CR = \frac{\lambda - n}{(n - 1) \cdot RI}$$

Özvektör tutarlılığın hesaplanması için gerekli olan Rasgele Değer İndeksi (RI) Tablo 2'de gösterilmektedir.

Tablo 2. Rasgele Değer İndeksi

n	1	2	3	4	5	6	7	8	9	10
RI	0,00	0,00	0,58	0,90	1,12	1,24	1,32	1,41	1,5	1,49

Kaynak: Saaty ve Tran, 2007, s. 966.

Adım 5: Genel Sonucun Elde Edilmesi

Tüm adımların gerçekleştirilmesi sonrasında her bir kriter ve/veya alternatifin ne kadar önemli olduğunun belirlenmesidir.

PROMETHEE Yöntemi

PROMETHEE Yöntemi, belirlenen kriterlere göre alternatiflerin uygun olan alternatife göre ikili karşılaştırmasının yapılmasıyla değerlendirildiği çok kriterli karar verme yöntemidir. Bu yöntemde alternatifler, kriterlere göre üstünlük durumlarının birleştirilmesiyle gerçekleştirilmektedir (Genç, 2013: 135). PROMETHEE Yöntemi ile turizm alanında yapılan çalışmalara kırsal turizm (Agustin vd., 2022), yelken turizmi (Butowski, 2018), deniz turizmi (Kovačić, 2010), alternatif turizm (Almeida Gonzaga vd., 2025), doğa temelli turizm (Markowski vd., 2019), otel web siteleri (Garda, 2025), otel seçimi (Sezgin ve Yurtlu, 2021) örnek gösterilebilir. PROMETHEE Yöntemi'nin adımları şu şekildedir (Brans ve Vincke, 1985):

Adım 1: Seçenek ve kriterlerin bulunduğu veri matrisinin oluşturulması.

Tablo 3. Veri Matrisi

Alternatifler	f_1	f_2		f_n
Alternatif a	$f_1(a)$	$f_2(a)$		$f_n(a)$
Alternatif b	$f_1(b)$	$f_2(b)$		$f_n(b)$
.....				
Alternatif m	$f_1(m)$	$f_2(m)$		$f_n(m)$
Ağırlık	w_1	w_2		w_n

m: alternatif sayısı **n:** kriter sayısı **w:** ağırlık değeri

Adım 2: Kriterlerin tercih fonksiyonlarının tanımlanması aşamasıdır. Bu aşama kriter ve alternatiflerin niteliklerine göre belirlenmektedir. Bu aşamada kullanılmak üzere PROMETHEE Yöntemi'nde altı tercih fonksiyonu bulunmaktadır. Bu fonksiyonlar, *Olağan tip*, *U-tipi*, *V tipi*, *Seviyeli tip*, *Lineer tip* ve *Gaussian tiptir*. Tercih fonksiyonları Tablo 4'te gösterilmektedir.

Tablo 4. Tercih Fonksiyonları

Tip	Parametreler	Fonksiyon
Olağan Tip	-	$P_x = 0, x \leq 0$ $1, x > 0$
U Tipi	q	$P_x = 0, x \leq 0$ $1, x > 0$
V Tipi	p	$0, x \leq 0$ $P_x = x/m, 0 < x \leq m$ $1, x > m$
Seviyeli Tip	q, p	$0, x \leq q$ $P_x = 1/2, q < x \leq q+p$ $1, x > q+p$
Lineer Tip	p, q	$0, x \leq 0$ $P_x = ((x-s)/r), s < x \leq s+r$ $1, x > m$
Gaussian	s	$0, x \leq 0$ $P_x = \frac{x^2}{1-e^{-2a^2}}, x > 0$

q: farklılık değeri **p:** kesin tercih eşiği **s:** p ve q arasındaki yer alan ara değer ya da standart sapma

Kaynak: Brans ve Vike, 1985, s. 650-651.

Adım 3: Tercih fonksiyonları baz alınarak karşılaştırılan alternatif çiftleri için ortak tercih fonksiyonları belirlenmektedir.

$$P(a, b) = \begin{cases} 0, & f(a) \leq f(b) \\ p[f(a) - f(b)], & f(a) > f(b) \end{cases}$$

Adım 4: Üçüncü adımda belirlenen ortak tercih fonksiyonuna yönelik her bir alternatif karşılaştırma çifti için tercih indeksleri oluşturulur.

$$\pi(a, b) = \frac{\sum_{i=1}^k w_i * P_i(a, b)}{\sum_{i=1}^k w_i}$$

Adım 5: Tüm alternatifler için pozitif ve negatif üstünlüklerin belirlenmesi.

$$\phi^+ = \sum \pi(a, x) \quad x = (b, c, d \dots)$$

$$\phi^- = \sum \pi(a, x) \quad x = (b, c, d \dots)$$

Adım 6: Promethee 1 ile kısmi sıralama belirlenmektedir.

$$i = \Phi^+(a) > \Phi^+(b) \quad \text{ve} \quad \Phi^-(a) < \Phi^-(b)$$

Adım 7: Promethee 2 ile nihai sıralama belirlenmektedir.

$$\Phi(a) = \Phi^+(a) - \Phi^-(a)$$

Bulgular

Kriterlerin ağırlıklarının belirlenmesi için Önem Ölçeğine göre puanlamaları yapılan *fiyat-performans*, *genel puan*, *hizmet*, *oda*, *tavsiye etme*, *yemek* ve *yüzme* kriterlerinin AHP ile kriter ağırlıklarını belirlemek için Super Decision programı kullanılmıştır. Program aracılığıyla elde edilen kriter ağırlıkları Şekil 3'te gösterilmektedir.

Normal		Hybrid
Inconsistency: 0.07078		
FİYAT PER~		0.04377
GENEL PUAN		0.07918
HİZMET		0.28383
ODA		0.31073
TAVSİYE E~		0.15744
YEMEK		0.10186
YÜZME		0.02319

Şekil 3. Kriter Ağırlıkları

Şekil 3 incelendiğinde, *oda* (0,31073) kriterinin en yüksek ağırlığa sahip olduğu, *hizmet* (0,28383) kriterlerinin en yüksek ikinci ağırlığa sahip olduğu ve bu kriterleri *tavsiye etme* (0,15744), *yemek* (0,10186), *genel puan* (0,07918), *fiyat-performans* (0,04377) ve *yüzme* (0,02319) kriterlerinin izlediği görülmektedir. Ayrıca, AHP analizinden elde edilen tutarlılık oranı ($CR=0,07078$), kabul edilebilir sınır olan 0,10'un altında yer aldığından, karşılaştırmaların tutarlı olduğu anlaşılmaktadır.

Balayı, çiftlerin yaşamlarındaki özel bir dönüm noktasını temsil ettiği için konaklama deneyiminde mahremiyet, konfor ve romantik atmosfer ön plana çıkmaktadır. Bu bağlamda *oda*, dekorasyon kalitesi, manzara, genişlik, yatak rahatlığı ve özel donanımlar (jakuzi, teras vb.) gibi unsurlarla çiftlerin beklentilerini doğrudan karşılayan temel mekânsal alanı oluşturmakta olduğu için öneme sahiptir. *Hizmet* kriteri personelin güler yüzlü olması, hızlı çözüm sunması, kişiye özel davranışlar ve balayı çiftlerine yönelik özel uygulamalar (karşılama ikramları, oda süslemesi, özel yönlendirmeler vb.) gibi faktörler nedeniyle kritik bir rol üstlenmektedir. Balayı çiftleri, standart misafirlere kıyasla daha kişiselleştirilmiş ve özenli hizmet beklediğinden, hizmet kalitesi algılanan toplam deneyimi güçlü biçimde şekillendirmektedir. Dolayısıyla oda ve hizmet kriterlerinin yüksek ağırlığa sahip olması, balayı çiftlerinin öncelikleri ve balayı turizminin karakteristik beklentileriyle uyumlu bir sonuç olarak değerlendirilebilir.

Fiyat-performans, genel puan, tavsiye etme, yemek ve yüzme kriterlerinin görece olarak daha düşük ağırlıklara sahip olması, balayı çiftlerinin konaklama tercihlerini şekillendiren önceliklerin yapısıyla ilişkilidir. Balayı seyahatleri, geleneksel tatil amaçlı seyahatlerden farklı olarak daha yüksek duygusal değer içerdiği için çiftler özellikle mahremiyet ve kişiselleştirilmiş hizmet gibi deneyim odaklı unsurlara öncelik verilirken diğer kriterler ikincil konumda kalmaktadır. Balayına giden çiftler için önemli olan ekonomik faktörlerden ziyade onlara özel bir atmosferin sağlanması olduğundan, fiyat-performans faktörü çoğu çift için belirleyici bir unsur olarak görülmeyebilir. *Genel puan* ve *tavsiye etme* gibi diğer misafirlerin genel değerlendirmelerine dayalı kriterler ise balayı deneyiminin son derece bireysel ve romantik niteliği nedeniyle sınırlı bir etkide bulunmakta, çiftler kendi beklentilerini önceliklendirmektedir. *Yemek* ve *yüzme* olanakları ise standart bir tatil deneyiminin önemli unsurları olmasına rağmen balayı bağlamında tamamlayıcı özellikler olarak değerlendirilmemiş olabilir. Çünkü bu unsurlar çiftlerin özel zaman geçirme, konfor ve hizmet beklentilerini oda ve hizmet kadar doğrudan etkilemeyebilir. Bu nedenle AHP sonucunda oda ve hizmet kriterleri ön plana çıkarken, diğer beş kriter daha düşük ağırlıklara sahiptir.

AHP sonrasında, konaklama işletmelerinin kriterleri için almış olduğu puanlar çerçevesinde sıralanması için PROMETHEE Yöntemi kullanılmıştır. PROMETHEE Visual programı ile oluşturulan karar matrisi Şekil 4'te gösterilmektedir.


INTERNATIONAL TOPKAPI CONGRESS VI

Scenario1	ODA	YUZME	HIZMET	YEMEK	FIYAT PERF...	TAVSIYE ETME	GENEL PUAN
Unit	puan	puan	puan	puan	puan	puan	puan
Cluster/Group							
Preferences							
Min/Max	max	max	max	max	max	max	max
Weight	0,31	0,02	0,28	0,10	0,04	0,16	0,08
Preference Fn.	Linear	Linear	Linear	Linear	Linear	Linear	Linear
Thresholds	absolute	absolute	absolute	absolute	absolute	absolute	absolute
- Q: Indifference	0,80	0,73	0,58	0,75	0,80	1,21	0,66
- P: Preference	1,92	1,45	1,38	1,70	1,69	2,51	1,51
- S: Gaussian	n/a	n/a	n/a	n/a	n/a	n/a	n/a
Statistics							
Minimum	6,50	6,30	7,50	6,30	6,00	5,00	6,70
Maximum	9,80	9,80	10,00	9,80	9,60	10,00	9,70
Average	8,56	8,77	9,06	8,64	8,66	8,82	8,77
Standard Dev.	0,95	0,71	0,68	0,83	0,83	1,22	0,74
Evaluations							
OTEL 1	9,60	9,40	10,00	9,80	9,50	10,00	9,70
OTEL 2	9,00	9,50	9,90	9,70	9,60	9,90	9,50
OTEL 3	7,10	8,60	8,60	7,60	8,20	7,70	8,00
OTEL 4	9,20	9,20	8,90	9,20	8,40	9,00	9,10
OTEL 5	9,50	8,70	8,90	8,10	8,50	9,10	8,80
OTEL 6	9,40	8,90	9,50	8,70	9,30	9,40	9,10
OTEL 7	9,20	9,30	9,40	9,20	9,30	9,40	9,30
OTEL 8	7,90	8,80	8,80	8,30	8,70	9,00	8,50
OTEL 9	7,80	8,60	8,10	8,10	8,00	7,70	8,20
OTEL 10	7,20	8,10	7,50	7,70	7,50	6,80	7,60
OTEL 11	9,10	8,60	9,10	9,20	8,30	9,30	9,00
OTEL 12	7,70	8,60	9,10	8,60	8,70	8,90	8,50
OTEL 13	8,10	8,90	8,80	8,20	8,80	8,60	8,50
OTEL 14	8,40	8,40	9,40	9,20	8,80	9,50	8,90
OTEL 15	9,50	9,80	9,70	9,40	9,20	9,90	9,60
OTEL 16	8,20	8,50	8,70	8,10	8,40	8,00	8,40
OTEL 17	9,70	9,40	9,90	9,20	9,50	10,00	9,60
OTEL 18	9,80	9,20	9,90	9,40	9,50	9,90	9,60
OTEL 19	8,40	8,50	9,20	8,90	9,00	9,30	8,80
OTEL 20	6,50	6,30	7,80	6,30	6,00	5,00	6,70

Şekil 4. Karar Matrisi

Şekil 4'e göre otellerin ilgili kriterlere göre aldığı puanlar değerlendirilmiştir. Örneğin, Otel 1 hizmet (10), yemek (9,80), tavsiye etme (10) ve genel puan (9,70) kriterlerinde yüksek puanlarla ön plana çıkarken Otel 20 neredeyse tüm kriterlerde (hizmet hariç) düşük puanlar alarak alt sıralarda yer almıştır. Bu şekil, karar vericilerin uzman görüşlerine dayalı olarak her bir otelin kriter bazlı performansını yansıtmaktadır.

PROMETHEE Visual ara yüzünde oluşturulan veri matrisi incelendiğinde, seyahat alışveriş platformunun sitesinde yer alan kriterlerin yapılan değerlendirmelere göre bir karşılaştırma yapıldığı için programdaki “unit” kısmı puan olarak belirlenmiştir. Tüm kriterlerin yüksek puana sahip olması olumlu bir durum olduğundan dolayı min-max kısmında her bir kriter fayda tipi olan “max” olarak işaretlenmiştir. Ağırlık (weight) kısmında ise AHP Yöntemi ile belirlenen kriter ağırlıklarından faydalanılmıştır. Puanlamalar arasında çok büyük farklar olmayacağı için en küçük puan farkının bile sıralamada önemli görülmesinden dolayı tercih fonksiyonu kısmında lineer tercih edilmiştir. Karar matrisi sayısal ifadelerden oluştuğu için Threshold bölümünde ise “absolute” tercih edilmiştir. Son olarak analizi yapabilmek için gerekli olan q (tercihsizlik) ve p (tercihlilik) parametreleri ise programdaki yardım asistanının önerdiği değerler baz alınarak karar matrisine eklenmiştir. Konaklama işletmelerinin pozitif ve negatif üstünlüklerinin yer aldığı PROMETHEE 1 kısmı sıralama sonuçları Şekil 5'te gösterilmektedir.



Şekil 5. PROMETHEE 1 Kısmi Sıralama Sonuçları

PROMETHEE 1 yöntemi kullanılarak konaklama işletmelerinin kriterlerine ilişkin kısmi sıralama (partial ranking) elde edilmiştir. PROMETHEE 1, alternatifler arasındaki karşılaştırılabilirlik ilişkilerine odaklanarak, her bir alternatifin diğerine göre ne ölçüde üstün olduğunu ve/veya zayıf kaldığını belirlemektedir. Bu yöntemde alternatifler, net üstünlük değerleri hesaplanmadan yalnızca pozitif ve negatif akışlara göre değerlendirilmektedir. Bu sayede bazı alternatifler arasında doğrudan karşılaştırma yapılmaması durumu (incomparability) da ortaya çıkabilmektedir. Ayrıca, grafikte yer alan mavi bağlantı çizgilerinin birbirini kesmesi, bazı oteller arasında karşılaştırılamazlık durumunun bulunduğunu göstermektedir. Yani bazı oteller belirli kriterlerde daha iyi, diğerlerinde ise daha zayıf performans sergileyebilmektedir.


Kısmi sıralamanın gösterildiği Şekil 5'te otellerin pozitif ve negatif değerleri gösterilmektedir. Grafiğin sol tarafında otellerin pozitif üstünlükleri, sağ tarafında ise negatif üstünlükleri gösterilmektedir. Grafiğe ek olarak pozitif ve negatif üstünlüklerde elde edilen sayısal sonuçlar Tablo 5'te gösterilmektedir.

Tablo 5. Pozitif ve Negatif Üstünlükler

	Phi ⁺	Phi ⁻
Otel 1	0,3848	0,0000
Otel 2	0,2988	0,0000
Otel 3	0,0319	0,4081
Otel 4	0,1661	0,0416
Otel 5	0,1766	0,0708
Otel 6	0,2169	0,0037
Otel 7	0,2068	0,0004
Otel 8	0,0633	0,1802
Otel 9	0,0290	0,3838
Otel 10	0,0116	0,6592
Otel 11	0,1696	0,0259
Otel 12	0,0735	0,1644
Otel 13	0,0673	0,1597
Otel 14	0,1416	0,0384
Otel 15	0,3045	0,0000

Otel 16	0,0607	0,1990
Otel 17	0,3486	0,000
Otel 18	0,3595	0,000
Otel 19	0,1164	0,0511
Otel 20	0,0000	0,8413

Tablo 5 incelendiğinde, Otel 1, Otel 17, Otel 18, Otel 2 ve Otel 15 kodlu otellerin Φ^+ değerlerinin yüksek, Φ^- değerlerinin ise düşük olduğu görülmektedir. Bu oteller, analizde ele alınan kriterler (örneğin personel-hizmet, olanaklar, temizlik, çevre dostu olma vb.) açısından en iyi performansı sergileyen alternatifler olarak öne çıkmaktadır. Otel 10 ve Otel 20 kodlu oteller ise yüksek Φ^- ve düşük Φ^+ değerlerine sahip olup, zayıf performans gösteren alternatifler arasında yer almaktadır. PROMETHEE 2 ile elde edilen nihai sıralama Şekil 6'da gösterilmektedir.



Şekil 6. PROMETHEE 2 Nihai Sıralama Sonuçları

Nihai sıralamanın gösterildiği Şekil 6'da yer alan sayısal değerlerin daha net anlaşılabilmesi için elde edilen sonuç ve konaklama işletmelerinin sıralaması Tablo 6'da gösterilmektedir.

Tablo 6. Balayı Konseptli Konaklama İşletmeleri Sıralaması

Sıra	Otel	Sonuç
1	Otel 1	0,3848
2	Otel 18	0,3595
3	Otel 17	0,3486
4	Otel 15	0,3045
5	Otel 2	0,2988
6	Otel 6	0,2132
7	Otel 7	0,2064
8	Otel 11	0,1437
9	Otel 4	0,1245
10	Otel 5	0,1059
11	Otel 14	0,1032

INTERNATIONAL TOPKAPI CONGRESS VI

12	Otel 19	0,0653
13	Otel 12	-0,0909
14	Otel 13	-0,0925
15	Otel 8	-0,1169
16	Otel 16	-0,1384
17	Otel 9	-0,3549
18	Otel 3	-0,3762
19	Otel 10	-0,6475
20	Otel 20	-0,8413

Elde edilen bu puanlara dayanarak, PROMETHEE I yöntemi ile kısmi sıralama, PROMETHEE II yöntemi ile ise nihai sıralama oluşturulmuştur. Böylece alternatif balayı konseptli oteller hem güçlü hem de zayıf yönleri dikkate alınarak çok boyutlu bir değerlendirmeye tabi tutulmuş ve en uygun alternatifler belirlenmiştir.

PROMETHEE Yöntemi ile elde edilen nihai sıralama sonucu sırasıyla incelendiğinde, Birinci sırada yer alan Otel 1'in 4 kriterde (hizmet, yemek, tavsiye etme ve genel puan) en yüksek puanı aldığı, diğer kriterlerde ise en yükseğe yakın düzeyde puan aldığı görülmektedir (Puanlamaların tamamı Şekil 4'te karar matrisinde gösterilmektedir). Otel 1 için misafirler tarafından yapılan yorumlar incelendiğinde ise yapılan puan değerlendirmelerinin yorumlarla desteklendiği, neredeyse yorumların tamamının olumlu olduğu görülmektedir. Yorumlar incelendiğinde misafirlerin karşılamının güzel olduğu, konaklama işletmesinin erken giriş imkânı sağladığı, odaların temiz olduğu, yemeklerin lezzetli ve güzel olduğu, personelin güler yüzlü, kibar ve ilgili olduğu, etkinliklerin güzel ve yeterli olduğu, havuz ve spor salonunun güzel olduğu, isteklerine önem verdikleri, balayı çiftlerine özel olarak yapılan süslemelerin güzel olduğu ve konaklama işletmesinin fiyatının yüksek olduğu ancak yapılan ödemeye değeceği yönünde olumlu görüşlerinin olduğu görülmüştür.

İkinci sırada yer alan Otel 18'in oda kriterinde en yüksek puanı aldığı, diğer kriterlerde ise en yüksek değere yakın puanlamalar aldığı görülmektedir. Otel 18 için misafirler tarafından yapılan yorumlar incelendiğinde, personelin güler yüzlü ve ilgili olması, yemeklerin lezzetli olması, oda, havuz ve plaj gibi otelin tüm kısımların temiz olmasıyla ilgili olumlu yorumlar olduğu görülmüştür.

Üçüncü sırada yer alan Otel 17'nin tavsiye etme kriterinde en yüksek puanı aldığı, diğer kriterlerde ise yine yüksek puanlar aldığı görülmektedir. Otel 17 için misafirler tarafından yapılan yorumlar incelendiğinde, personelin ilgili, güler yüzlü, samimi ve misafirperver olması, yemeklerin lezzetli olması, yabancı-Türk misafir ayrımının yapılmaması, balayı çiftlerine ekstraların olması, 16 yaş ve üzeri misafir kabul etmesi, sessiz ve sakin olması, odaların temiz ve düzenli olması ayrıca oda süslemelerinin güzel olması, restoran ve havuzun temiz olması, balayı çiftlerine ücretsiz a la carte rezervasyonu yapılması konaklama işletmesinin fiyatının yüksek olduğu ancak yapılan ödemeye değeceği yönünde olumlu görüşlerinin olduğu görülmüştür.

Dördüncü sırada yer alan Otel 15'in yüzme kriterinde en yüksek puanı aldığı, diğer kriterlerde de yine yüksek puanlara sahip olduğu görülmektedir. Otel 15 için misafirler tarafından yapılan yorumlar incelendiğinde, otelin genel olarak temiz olması, yemeklerin lezzetli olması, personelin ilgili ve güler yüzlü olması, hizmetin kalite olması, konumunun iyi olması, odalarda hijyenle ilgili malzemelerin eksiksiz olması, odaların balayı çiftlerine özel olarak hazırlanması ve küçük hediyeler verilmesi, otelin sakin olması ve fiyat-performansın ortalama olması ile ilgili olumlu görüşler yer alırken, bir misafirin ise yemekleri beğenmediği, aktivitelerin fazla olmamasından sıkıldıkları ile ilgili olumsuz görüşler olduğu görülmüştür.

Beşinci sırada yer alan Otel 2'nin fiyat-performans kriterinde en yüksek puanı aldığı görülmektedir. Otel 2 için misafirler tarafından yapılan yorumlar incelendiğinde, otelin sakin olması, fiyat-performans, yemeklerin lezzetli ve bol çeşitli olması, otel ambiyansının iyi olması,

odaların temiz olması, çalışanların güler yüzlü ve nazik olması ve otelin hizmet odaklı olmasıyla ilgili olumlu görüşler, yabancı misafirlerle daha fazla ilgilenilmesi, balayı çiftlerine hediye verileceği bilgisinin verildiği ancak hediye verilmediğiyle ilgili olumsuz görüşler olduğu görülmektedir. Ayrıca, animasyon ekibiyle ilgili hem olumlu hem de olumsuz görüşlerin olduğu görülmüştür.

Altıncı sırada yer alan Otel 6'nın tüm kriterlerde en yüksek puanlara yakın puanlar aldığı görülmektedir. Otel 6 için misafirler tarafından yapılan yorumlar incelendiğinde, oda süslemeleri ve ikramların güzel olması, çalışanların ilgili ve samimi olması, yemeklerin lezzetli ve çeşitli olması, otelin genel olarak temiz ve düzenli olması, odaların ferah olmasıyla ilgili olumlu görüşler yer alırken, animasyonun daha çok çocuklara yönelik olmasıyla ilgili olumsuz görüşlerin olduğu görülmüştür.

Yedinci sırada yer alan Otel 7'nin tüm kriterlerde ortalama puanlar aldığı görülmektedir. Otel 7 için misafirler tarafından yapılan yorumlar incelendiğinde, yemeklerin güzel olması, odaların güzel olması, etkinliklerin yeterli olması, çalışanların ilgili, çalışkan ve güler yüzlü olması, otelin temiz ve ambiyansının güzel olması, balayı çiftlerine daha özenli davranmaları, ikramlarda bulunmaları, odaya kahvaltı servisi ve ücretsiz a la carte hizmetinin olması, fiyatının biraz yüksek ancak balayı için değecek düzeyde olmasıyla ilgili olumlu görüşler yer alırken, balayı çiftleri için yapılan ayrıcalıkların hatırlatılması gerektiğiyle ilgili olumsuz görüşlerin olduğu görülmüştür.

Sekizinci sırada yer alan Otel 11'in tüm kriterlerde ortalama puanlar aldığı görülmektedir. Otel 11 için misafirler tarafından yapılan yorumlar incelendiğinde, çalışanların güler yüzlü ve yardımsever olması, otelin genel olarak temiz olması, aktivitelerin yeterli olması, fiyat-performans olarak iyi olması, balayı çiftlerine özel deluxe oda verilmesi, yemeklerin lezzetli ve çeşitli olmasıyla ilgili olumlu görüşler yer alırken, balayına özel odaya süsleme yapılmaması, odaya gönderilen ikramların kalitesiz olması, yapılması için hatırlatma yapılması ve bazı balayı çiftlerine ikramlarda bulunulmamasıyla ilgili olumsuz görüşlerin olduğu görülmüştür.

Dokuzuncu sırada yer alan Otel 4'ün tüm kriterlerde ortalama puanlar aldığı görülmektedir. Otel 4 için misafirler tarafından yapılan yorumlar incelendiğinde, yemeklerin lezzetli olması, havuzların güzel ve temiz olması, aktivitelerin yeterli, güzel ve kaliteli olması, a la carte'ın çeşitli olması, otelin genel olarak temiz olması, odaların konforlu olması, balayı çiftlerine ücretsiz fotoğraf çekimi olması, havaalanı transferi hediye edilmesiyle ilgili olumlu görüşler yer alırken, balayı çiftlerine taahhüt edilen ayrıcalıkların sağlanmamasıyla ilgili olumsuz görüşler bulunurken, hizmet kalitesi, karşılama ve fiyat-performans ile ilgili hem olumlu hem de olumsuz görüşlerin bulunduğu görülmüştür.

Onuncu sırada yer alan Otel 5'in tüm kriterlerde ortalama puanlar aldığı görülmektedir. Otel 5 için misafirler tarafından yapılan yorumlar incelendiğinde, çalışanların ilgili, güler yüzlü ve enerjik olması, karşılamanın güzel olması, sessiz sakin olması, spor imkanlarının fazla olması ve müziklerin güzel olmasıyla ilgili olumlu görüşler yer alırken, yabancı-Türk misafir ayrımının yapılmasıyla ilgili olumsuz görüşlerin bulunduğu görülmektedir. Ayrıca, yemeklerin çeşitli ve lezzetli olması, animasyon, otel geneli ve odaların temizliği ile balayı çiftlerine sağlanan ayrıcalıklarla ilgili hem olumlu hem de olumsuz görüşlerin bulunduğu görülmüştür.

On birinci sırada yer alan Otel 14'ün tüm kriterlerde ortalama puanlar aldığı görülmektedir. Otel 14 için misafirler tarafından yapılan yorumlar incelendiğinde, otelde tüm olanakların mevcut olması, yemeklerin lezzetli olması, çalışanların ilgili ve güler yüzlü olması, sorunların çözülmesi, balayı çiftlerine özel oda süslemelerinin yapılmasıyla ilgili olumlu görüşler yer alırken, otel geneli ve odaların temizliğiyle ilgili olumsuz görüşlerin bulunduğu görülmüştür.

On ikinci sırada yer alan Otel 19'un tüm kriterlerde ortalama puanlar aldığı görülmektedir. Otel 19 için misafirler tarafından yapılan yorumlar incelendiğinde, çalışanların ilgili, kibar ve güler yüzlü olması, yemeklerin lezzetli ve her saat olması, fiyat-performansın uygun olmasıyla ilgili

olumlu görümler yer alırken, odaların eski olması ve balayı çiftlerine taahhüt edilenlerin yapılmamasıyla ilgili olumsuz görüşlerin bulunduğu görülmüştür.

On üçüncü sırada yer alan Otel 12'nin tüm kriterlerde ortalama puanlar aldığı görülmektedir. Otel 12 için misafirler tarafından yapılan yorumlar incelendiğinde, çalışanların güler yüzlü olması, yemeklerin güzel olmasıyla ilgili olumlu görüşler yer alırken, odaların eski olması ve balayı çiftlerine özel oda süslemesi yapılması ya da ikramda bulunulmasıyla ilgili olumsuz görüşlerin bulunduğu görülmüştür. Ayrıca, temizlik, animasyon ve etkinliklerle ilgili hem olumlu hem de olumsuz görüşlerin bulunduğu görülmüştür.

On dördüncü sırada yer alan Otel 13'ün üst sıralardaki otellere kıyasla daha düşük puan aldığı görülmektedir. Otel 13 için misafirler tarafından yapılan yorumlar incelendiğinde, çalışanların güler yüzlü, nazik ve kibar olması, giriş-çıkış işlemlerinin hızlı yapılması ve fiyat-performansının uygun olmasıyla ilgili olumlu görüşler yer alırken, yatakların rahatsız olmasıyla ilgili olumsuz görüşler bulunduğu görülmüştür.. Hem olumlu hem olumsuz yorumlar incelendiğinde ise bunların genellikle balayı çiftlerinin özel beklentileriyle ilgili olduğu görülmüştür. Bazıları oda süslemesinin güzel olduğundan, bazıları kötü olduğundan, bazıları kendilerine ekstra bir şeyin yapılmadığından, bazıları güzel jestler yapıldığından, bazıları ise hatırlatmalarıyla kendilerine bu ayrıcalıkların sağlandığından bahsetmiştir. Son olarak, temizlik ve yemek lezzeti ve çeşitliliğiyle ilgili de hem olumlu hem de olumsuz görüşlerin bulunduğu görülmüştür.

On beşinci sırada yer alan Otel 8'in üst sıralardaki otellere kıyasla daha düşük puan aldığı görülmektedir. Otel 8 için misafirler tarafından yapılan yorumlar incelendiğinde, temizliğin güzel olması, yemeklerin çeşitli ve lezzetli olması ve fiyat-performansın uygun olmasıyla ilgili olumlu görüşler yer alırken, Türk-yabancı misafir ayrımı yapılması, balayı çiftlerine özel oda süslemesinin yapılmaması ve balayı çiftlerine ayrıcalık tanınmaması ile ilgili olumsuz görüşlerin bulunduğu görülmüştür.

On altıncı sırada yer alan Otel 16'nın üst sıralardaki otellere kıyasla daha düşük puan aldığı görülmektedir. Otel 16 için misafirler tarafından yapılan yorumlar incelendiğinde, çalışanların güler yüzlü ve ilgili olması, animasyonun güzel ve etkinliklerin yeterli olması, balayı çiftlerine büyük oda verilmesiyle ilgili olumlu görüşler yer alırken, şezlongların yetersiz olması, eşyaların eski olması, transfer hizmetinin olmaması, balayı çiftlerine özel oda süslemesi ya da ikramlarda bulunulmamasıyla ilgili olumsuz görüşlerin bulunduğu görülmektedir. Ayrıca, temizlik ile ilgili hem olumlu hem de olumsuz görüşlerin olduğu görülmüştür.

On yedinci sırada yer alan Otel 9'un üst sıralardaki otellere kıyasla daha düşük puan aldığı görülmektedir. Otel 9 için misafirler tarafından yapılan yorumlar incelendiğinde, balayı çiftlerine taahhüt edilen ayrıcalıklarla ilgili hiçbir şeyin sağlanmadığı, otelde bir balayı konsepti olmadığıyla ilgili olumsuz görüşlerin bulunduğu görülmüştür.

On sekizinci sırada yer alan Otel 3'ün üst sıralardaki otellere kıyasla daha düşük puan aldığı görülmektedir. Otel 3 için misafirler tarafından yapılan yorumlar incelendiğinde, çalışanların ilgili olması ve otelin eğlenceli olmasıyla ilgili olumlu, yemeklerin az ve lezzetsiz olması ve temizliğin yeterli olmamasıyla ilgili olumsuz görüşlerin bulunduğu görülmüştür.

On dokuzuncu sırada yer alan Otel 10'un hizmet kriterinde en düşük puanı aldığı, diğer kriterlerde ise son sıradaki otele nazaran biraz daha yüksek puan aldığı görülmektedir. Otel 10 için misafirler tarafından yapılan yorumlar incelendiğinde, çalışanların ilgili olması ve aktivitelerin güzel olmasıyla ilgili olumlu görüşlerin bulunduğu görülmüştür. Ancak yemeklerin lezzetsiz olması ve çeşidinin az olmasıyla ve otelin balayı çiftlerine uygun olmadığı, çocuklu ailelere daha uygun olduğuyla ilgili olumsuz görüşlerin bulunduğu görülmüştür.

Yirminci sırada yer alan Otel 20'nin oda, yüzme, yemek, fiyat-performans, tavsiye etme ve genel puan kriterlerinden en düşük puanı aldığı, hizmet kriterinde ise en düşüğe yakın bir puan aldığı görülmektedir. Otel 20 için misafirler tarafından yapılan yorumlar incelendiğinde, odaların eski olması, yemeklerin lezzetsiz ve çeşidinin az olması, animasyonun olmaması ve

fiyat-performans olarak fiyatının çok fazla olmasıyla ilgili olumsuz görüşlerin bulunduğu görülmüştür.

SONUÇ

Bu çalışmada balayı otellerinin değerlendirilmesine yönelik olarak uygulanan PROMETHEE Yöntemi, otellerin yedi temel kriter (fiyat-performans, hizmet kalitesi, oda özellikleri, yemek, yüzme olanakları, genel puan ve tavsiye edilme) bakımından göreceli üstünlüklerini ortaya koymuştur. Analiz sonuçları, özellikle oda kalitesi ve hizmet değişkenlerinin balayı çiftleri açısından belirleyici olduğunu gösterdiği bulgusu, kullanıcı yorumları ile desteklenerek sonuçları güçlendirmektedir. Balayı deneyiminin doğası gereği, çiftlerin beklentilerinin yüksek olması ve hizmet kusurlarına karşı daha hassas davranmaları, oteller arasındaki sıralamaları anlamlı biçimde şekillendirmiştir.

PROMETHEE analizinde birinci sırada yer alan Otel 1, kullanıcı yorumlarında yüksek düzeyde memnuniyet bildiren ifadelerle desteklenmiştir. Misafirler, otelin temizlik standartları, yemek kalitesi, çalışanların profesyonel ve güler yüzlü tutumu ve balayı çiftlerine özel gösterilen ilgiye vurgu yapmıştır. Erken giriş imkânı, odaların düzenli temizliği ve çeşitli aktivitelerin sunulması, otelin balayı konsepti ile uyumunu pekiştirmektedir. Bu nedenle Otel 1'in yüksek pozitif akış değerine sahip olması, nitel kullanıcı deneyimleriyle tutarlı bir sonuçtur.

İkinci ve üçüncü sıralarda yer alan Otel 18 ve Otel 17'de de benzer biçimde hizmet kalitesi ve temizlik unsurlarının öne çıktığı görülmektedir. Kullanıcılar özellikle yemeklerin lezzeti, personelin ilgi düzeyi ve tesisin genel düzeni gibi kriterlere olumlu geri bildirimlerde bulunmuştur. Her iki otelin de sakin ve güvenli bir tatil ortamı sunması, balayı çiftlerinin beklentilerini karşılayan bir özellik olarak değerlendirilmiştir. Bu bulgular, ilgili otellerin yüksek performanslarını açıklayıcı niteliktedir.

Dördüncü sıradaki Otel 15, kullanıcı yorumlarında özellikle yeme-içme hizmetlerinin kalitesi, deniz ve plaj imkânlarının temizliği, sakin atmosferi ve personel ilgisi ile öne çıkmaktadır. Balayı çiftlerine yönelik olumlu geri bildirimlerin ağırlıkta olması, otelin üst sıralarda konumlanmasına katkı sağlamıştır. Benzer şekilde beşinci sırada yer alan Otel 2 de temizlik, hizmet kalitesi ve genel memnuniyet düzeyleri bakımından pozitif değerlendirilmiştir.

Otel 6, 7, 11, 4, 5, 14 ve 19 genel olarak olumlu kullanıcı değerlendirmelerine sahip olmakla birlikte, hizmet tutarlılığında zaman zaman yaşanan dalgalanmalar ve balayı konseptine ilişkin eksiklikler nedeniyle üst sıralara çıkamamıştır. Örneğin, Otel 11'de oda temizliği ve yemek kalitesi olumlu bulunmasına rağmen balayı ayrıcalıklarının eksik veya gecikmeli sunulması kullanıcı memnuniyetini sınırlamıştır. Otel 4 ve Otel 5'te rezervasyon yönetimi ve hizmet süreçlerinde meydana gelen aksaklıklar bu otellerin orta sıralarda kalmasına neden olmuştur. Otel 14 ve Otel 19'da ise hizmet kalitesinin misafire göre değişkenlik göstermesi, performans tutarsızlığına işaret etmektedir.

Otel 12, 13, 8 ve 16 özellikle balayı konseptiyle ilgili beklentilerin karşılanmasında zorlanmıştır. Otel 12'de ilk verilen odanın beğenilmemiş olması, çözülmüş olsa dahi balayı çiftlerinin ilk izlenimlerinin güçlü etkisi nedeniyle memnuniyetsizliğe yol açmıştır. Otel 13'te balayı ikramlarının ve oda süslemesinin sunulmaması gibi eksiklikler önemli bir memnuniyetsizlik nedeni olmuştur. Otel 8'de yemek ve temizlik olumlu değerlendirilse de balayı odası ve hizmet uygulamalarındaki yetersizlikler sıralamayı düşürmüştür. Otel 16'da çalışanların ilgili tutumu olumlu olmakla birlikte hizmet gecikmeleri ve balayı odası konusundaki yetersizlikler otelin performansını sınırlamıştır.

Düşük performans gösteren otellerden Otel 9 ve Otel 3 için en belirgin sorun, balayı konseptinin uygulanmaması olarak görünmektedir. Çiftlerin oda, yemek ve genel hizmet beklentilerinin karşılanmaması, bu otellerin negatif net akış değerleri almasına neden olmuştur. Bu durum kullanıcı yorumlarıyla örtüşmekte ve elde edilen sıralama sonuçlarının tutarlılığını artırmaktadır.

Listenin son iki sırasında yer alan Otel 10 ve Otel 20, kullanıcı yorumlarında belirgin memnuniyetsizlik ifadeleriyle öne çıkmıştır. Otel 10'da yemek çeşitliliğinin sınırlı olması, tesisin balayı konseptine uygun bir atmosfer sunmaması ve hizmet kalitesindeki dalgalanmalar öne çıkan olumsuzluklardır. Son sıradaki Otel 20'de ise kullanıcılar odaların eski ve bakımsız olmasından, yemek kalitesinin düşük olmasından, hijyen sorunlarından ve balayı çiftlerine yönelik hizmetlerin sunulmamasından sıkça şikâyet etmiştir. Bu nedenle Otel 20'nin analizde en düşük performansı göstermesi beklenen bir bulgudur.

Sonuçlar genel olarak incelendiğinde, balayı deneyiminin genel kalitesini belirleyen temel unsurlar arasında oda kalitesi ve sunulan hizmet düzeyi ön plana çıkmaktadır. Ayrıca, balayı çiftlerinin bu özel tatillerinde kendilerine daha fazla ilgi ve alaka beklemekte, birtakım ayrıcalıklarının yapılmasını istemektedir. Özellikle balayı konsepti kapsamında sağlanan oda süslemesi, özel ikramlar, karşılama uygulamaları ve çiftlere yönelik kişiselleştirilmiş hizmetler, otellerin algılanan değerini önemli ölçüde artırmakta ve sıralamalara doğrudan yansımaktadır. Bu küçük fakat anlamlı detayların, balayı tatili gibi duygusal açıdan hassas ve beklentisi yüksek bir deneyimde belirleyici rol oynadığı görülmektedir.

Çalışmada elde edilen PROMETHEE sıralaması ile kullanıcı yorumlarının büyük ölçüde örtüşmesi, değerlendirme sonuçlarının hem tutarlılığını hem de geçerliliğini desteklemektedir. Üst sıralarda yer alan oteller düzenli, profesyonel ve yüksek standartlarda hizmet sunmalarıyla öne çıkarken, alt sıralardaki otellerde hizmet kalitesinde dalgalanmalar, organizasyon eksiklikleri ve özellikle yiyecek-içecek kalitesine ilişkin sorunların belirginleştiği anlaşılmaktadır. Bu bulgular, hizmet süreçlerindeki istikrarın ve kalite yönetiminin balayı müşteri memnuniyetinde kritik bir role sahip olduğunu göstermektedir.

Balayı çiftlerinin deneyimlerini bütünsel bir yapı olarak değerlendirdikleri, dolayısıyla küçük çaptaki aksaklıkların dahi genel memnuniyeti olumsuz etkileyebildiği dikkat çekmektedir. Bu durum, balayı pazarının duygusal beklentilere dayalı hassas yapısını yansıtmakta ve oteller açısından detay odaklı hizmet tasarımının önemini bir kez daha ortaya koymaktadır.

KAYNAKÇA

Agustin, E. S. A. S., Martini, R., & Setiyono, B. (2022). Evaluating rural tourism competitiveness: Application of PROMETHEE-GAIA method. *Cogent Economics & Finance*, 10(1), 2054526.

Almeida Gonzaga, A., Chim-Miki, A. F., & da Costa, R. A. (2025). Ranking the development potential of alternative tourism in low-density territories: A PROMETHEE Approach. *Tourism Planning & Development*, 1-17.

Bakogiannis, E., Vlastos, T., Athanasopoulos, K., Vassi, A., Christodouloupoulou, G., Karolemeas, C., ... & Tzika, E. (2020). Exploring motivators and deterrents of cycling tourism using qualitative social research methods and participative analytical hierarchy process (AHP). *Sustainability*, 12(6), 2418.

Buluk-Eşitti, B. (2020). Buddymoon. Türkiye Turizm Ansiklopedisi. <https://turkiyeturizmansiklopedisi.com/balayi-turizmi> Erişim Tarihi: 18.11.2025

Butowski, L. (2018). An integrated AHP and PROMETHEE approach to the evaluation of the attractiveness of European maritime areas for sailing tourism. *Moravian Geographical Reports*, 26(2), 135-148.

Chen, G., So, K. K. F., Hu, X., & Poomchaisuwan, M. (2022). Travel for affection: A stimulus-organism-response model of honeymoon tourism experiences. *Journal of hospitality & tourism research*, 46(6), 1187-1219.

Dalkıran, G. B., & Göncü, K. K. (2023). Ekonomik sürdürülebilirlik açısından sınır şehirlerinde sağlık turizmi pazarının swot ahp yöntemiyle analizi: Edirne örneği. *Abant Sosyal Bilimler Dergisi*, 23(3), 1642-1663.

Erdem, A., Unur, K., & Şeker, F. (2022). Şanlıurfa'nın akıllı turizm destinasyonu olabilmesi için gerekli stratejilerin A'WOT yöntemi ile belirlenmesi. *Güncel Turizm Araştırmaları Dergisi*, 6(1), 73-91.

Fakfare, P., & Lee, J. S. (2019). Developing and validating a scale for multidimensional attributes of honeymoon tourism. *Journal of Hospitality & Tourism Research*, 43(8), 1199-1224.

Garda, B. (2025). Otel Web Sitelerinde Dijital Görünürlük Analizi. *Anatolia: Turizm Araştırmaları Dergisi*, 36(2), 121-143.

Genç, T. (2013). PROMETHEE Yöntemi ve GAIA düzlemi, *Afyon Kocatepe Üniversitesi İktisadi ve İdari Bilimler Fakültesi Dergisi*, 15(1), 133-154.

Gündüz, H., & Güler, M. E. (2015). Termal turizm işletmelerinde çok ölçütlü karar verme teknikleri kullanılarak uygun tedarikçinin seçilmesi. *Dokuz Eylül Üniversitesi İktisadi İdari Bilimler Fakültesi Dergisi*, 30(1), 203-222.

İşler, H., & Akyurt, H. (2021). AHP yöntemi ile seyahat acentalarının ekoturizm kriterleri algılarının tespiti: Giresun örneği. *Türk Turizm Araştırmaları Dergisi*, 5(2), 1103-1121.

Kovačić, M. (2010). Selecting the location of a nautical tourism port by applying PROMETHEE and GAIA methods case study–Croatian northern Adriatic. *Promet-Traffic&Transportation*, 22(5), 341-351.

Lee, B. C., & Kim, D. K. (2009). Relative importance to tourism decision makers of indicators for sustainable rural tourism development in South Korea: Using AHP approach. *Journal of Tourism*, 10(2).

Markowski, J., Bartos, M., Rzenca, A., & Namiecinski, P. (2019). An evaluation of destination attractiveness for nature-based tourism: Recommendations for the management of national parks in Vietnam. *Nature Conservation*, 32, 51-80.

Saaty, T. L. (1987). The Analytic hierarchy process-what it is and how it is used, *Mathematical Modelling*, 9(3-5), 161-176.

Saaty, T. L. (1990). How to Make A Decision: The Analytic hierarchy process, *European Journal of Operational Research*, 48(1), 9-26.

Saaty, T. L. (2001). Fundamentals of the analytic hierarchy process, *The Analytic Hierarchy Process in Natural Resource and Environmental Decision Making*, 15-35.

Sonel, E., Gür, Ş., & Eren, T. (2019). Çok ölçütlü karar verme ile sağlık turizminde şehir seçimi ve analizi. *Uluslararası Global Turizm Araştırmaları Dergisi*, 3(1), 27-39.

Türk, O. (2019). Balayı Turizmi. Türkiye Turizm Ansiklopedisi. <https://turkiyeturizmansiklopedisi.com/balayi-turizmi> Erişim Tarihi: 18.11.2025

Ünal, C., Dursun, A., & Caber, M. (2017). A study of domestic honeymoon tourism in Turkey. *European Journal of Tourism, Hospitality and Recreation*, 8(1), 65-74.

Welthagen, L., Slabbert, E., & Plessis, E. D. (2022). Conference tourism competitiveness: An applied AHP framework. *Journal of Convention & Event Tourism*, 23(5), 435-459.

MİMARLIKTA YARATICI DÜŞÜNME TEKNİKLERİNİN KULLANIMI

Merve ÇAKIR

Kütahya Dumlupınar University, Graduate Education Institute, Department of Technology and Innovation Management, 37150 Merkez, Kütahya
ORCID: 0009-0006-9210-3542

Arif GÖK

Kütahya Dumlupınar University, Faculty of Architecture, Department of Industrial Design, 37150 Merkez, Kütahya
ORCID: 0000-0003-2840-9601

ÖZET

Mimarlık, insanlık tarihi boyunca toplumsal, kültürel ve teknolojik değişimlerle birlikte gelişen çok boyutlu bir disiplin olup, mimari tasarım sürecinin başarısı kullanıcı ihtiyaçlarını doğru analiz eden, işlevsel ve estetik açıdan nitelikli çözümler üretebilme kapasitesiyle doğrudan ilişkilidir. Günümüzde mimari tasarım süreçlerini desteklemek amacıyla çeşitli çağdaş yöntemler kullanılmasına rağmen, yaratıcı düşünme tekniklerinin bu süreçlere sistematik ve bilinçli bir biçimde dâhil edilmesinin hâlen sınırlı düzeyde kaldığı görülmektedir. Bu çalışma, yaratıcı düşünme tekniklerinin mimari tasarım sürecine entegrasyonunun tasarım kalitesi üzerindeki etkilerini incelemeyi amaçlamaktadır. Çalışma kapsamında beyin fırtınası, Altı Şapka Düşünme Tekniği ve Altı Sigma gibi yaratıcı düşünme yaklaşımları ele alınmış; bu tekniklerin tasarım sürecine katkıları tasarım problemlerine yaklaşım biçimi, alternatif üretme kapasitesi ve ekip içi etkileşim bağlamında değerlendirilmiştir. Elde edilen bulgular, yaratıcı düşünme tekniklerinin tasarım problemlerinin daha geniş bir perspektiften ele alınmasını sağladığını, çözüm çeşitliliğini artırdığını ve kavramsal yaklaşımı güçlendirdiğini ortaya koymaktadır. Ayrıca bu tekniklerin kullanımıyla tasarım sürecinde yaşanan tıkanmaların azaldığı, alternatif üretme hızının arttığı ve kullanıcı ihtiyaçlarının daha doğru analiz edilerek işlev estetik dengesinin daha nitelikli biçimde kurulduğu tespit edilmiştir. Bununla birlikte, ekip temelli tasarım süreçlerinde iletişimin güçlendiği ve ortak akıl geliştirme mekanizmalarının daha etkin hâle geldiği gözlemlenmiştir. Sonuç olarak, yaratıcı düşünme tekniklerinin mimarlık alanında hem eğitim hem de uygulama düzeyinde tasarım sürecine önemli katkılar sunduğu görülmektedir. Bu tekniklerin mimari tasarım süreçlerinde daha yaygın ve bilinçli bir şekilde kullanılması, çağdaş mimarlığın yenilikçi, özgün ve kullanıcı odaklı yaklaşımının güçlendirilmesi açısından önemli bir gereklilik olarak değerlendirilmektedir.

Anahtar Kelimeler: Mimari Tasarım, Yaratıcı Düşünme Teknikleri, Tasarım Süreci, Kullanıcı Odaklı Tasarım, Yenilikçi Yaklaşımlar

THE USE OF CREATIVE THINKING TECHNIQUES IN ARCHITECTURE

ABSTRACT

Architecture is a multidimensional discipline that has evolved alongside social, cultural, and technological changes throughout human history, and the success of the architectural design process is directly related to the ability to produce functional and aesthetically qualified solutions that accurately respond to user needs. Although various contemporary methods are employed today to support architectural design processes, the systematic and conscious integration of creative thinking techniques into these processes remains limited. This study aims

to examine the effects of integrating creative thinking techniques into the architectural design process on design quality. Within the scope of the study, creative thinking approaches such as brainstorming, the Six Thinking Hats technique, and Six Sigma were examined, and their contributions to the design process were evaluated in terms of approaches to design problems, alternative solution generation, and team interaction. The findings indicate that creative thinking techniques enable design problems to be addressed from a broader perspective, increase solution diversity, and strengthen the conceptual approach. In addition, the use of these techniques reduces design deadlocks, accelerates the generation of alternatives, and allows for a more qualified balance between function and aesthetics through a more accurate analysis of user needs. Furthermore, it was observed that communication within team-based design processes was strengthened and collective decision-making mechanisms became more effective. In conclusion, creative thinking techniques make significant contributions to the architectural design process at both educational and professional practice levels. The widespread and conscious use of these techniques in architectural design processes is therefore considered an important requirement for strengthening the innovative, original, and user-oriented approach of contemporary architecture.

Keywords: Architectural Design, Creative Thinking Techniques, Design Process, User-Oriented Design, Innovative Approaches

1.GİRİŞ

Mimarlık, insanlık tarihinin en erken dönemlerinden itibaren insanın temel gereksinimlerinden biri olan korunma içgüdüsüne yanıt olarak ortaya çıkan bir yapı eylemi olarak gelişmiştir. Kuban'a (2006) göre mimarlık, insanın doğal çevre koşullarına uyum sağlama çabasının bir sonucu olup, bu süreçte yalnızca fiziksel barınma ihtiyacını değil, aynı zamanda insan yaşamının sosyal, kültürel ve çevresel boyutlarını da kapsayan çok yönlü bir üretim alanını ifade etmektedir. Bu bağlamda mimarlık, yalnızca nesnel bir yapı üretimi değil, insan yaşamına çerçeve oluşturan çevresel bir düzenleme faaliyeti olarak değerlendirilmektedir.

Vitruvius'a göre mimar; yazı, resim, geometri, tarih, felsefe, müzik, tıp, hukuk ve gökbilimi kapsayan geniş bir bilgi birikimine sahip olmalıdır. Bu çok yönlü eğitim anlayışı, mimarlığın yalnızca teknik bir meslek değil, aynı zamanda entelektüel ve sanatsal bir disiplin olduğunu ortaya koymaktadır. Vitruvius'un "Ne yetenek olmadan eğitim, ne de eğitim olmadan yetenekle kusursuz bir sanatçı yetişemez" yaklaşımı, mimarlıkta yaratıcı üretimin hem doğal yetenek hem de sistemli eğitimle gelişebileceğini vurgulamaktadır. İnsanın çevreyi, çevrenin de insanı şekillendirdiği gerçeği, mimarlığın insan yaşamı üzerindeki etkisini açıkça ortaya koymaktadır. Doğan'a (2006) göre çevreyi meydana getiren her unsur, insan yaşantısının bir parçası olup mimarlık, bu yaşantının fiziksel ve algısal çerçevesini oluşturmaktadır. Bu nedenle günümüzde mimara yalnızca yapı üreten bir aktör olarak değil, "çevre yaratan" bir tasarımcı olarak yaklaşılmaktadır. Mimarlığın bu niteliği, tasarım sürecinde yaratıcı ve özgün düşünme gerekliliğini daha da önemli hâle getirmektedir. Mimari üretim, mimarın bireysel yaratıcılığının yanı sıra içinde bulunduğu toplumun kültürel, sosyal ve düşünsel yapısından da etkilenmektedir. Kuban'a (2006) göre yaratıcı birey, içinde yetiştiği toplumdan bağımsız düşünülemez; yaratma eylemi, toplumsal ve kültürel birikimin bireyde yeniden yorumlanmasıyla ortaya çıkar. Bu durum, mimarlıkta yaratıcılığın bireysel bir yetenek değil, çevresel ve kültürel etkileşimlerin sonucu olarak ele alınması gerektiğini göstermektedir.

Yaratıcılık, insanın temel özelliklerinden biri olup, tüm düşünsel ve duyuşsal etkinliklerde kendini gösteren doğal bir bilişsel süreçtir (Önal, 2011). Yaratıcı biliş, bireyin düşünme aşamasının doğal bir parçası olarak ortaya çıkmakta ve her bireyin potansiyel olarak sahip olduğu bir yetenek olarak değerlendirilmektedir. Csikszentmihalyi (1999), yaratıcılığın kültür, sosyal sistem ve bireyin etkileşimi sonucunda ortaya çıktığını belirtmekte; bu yaklaşım

yaratıcılığı yalnızca bireysel bir süreç olmaktan çıkararak toplumsal ve çevresel bir bağlama yerleştirmektedir. Literatürde yaratıcılık; akıcılık, esneklik ve özgünlük gibi bilişsel özelliklerle açıklanmakta (Guilford, 1959), problem çözme sürecinde yeni ve özgün çözümler üretebilme yeteneği olarak tanımlanmaktadır (Torrance, 1974). Yaratıcılığın yalnızca doğuştan gelen bir özellik olmadığı, uygun eğitim ortamları ve sistematik yöntemlerle geliştirilebileceği ise birçok araştırmacı tarafından vurgulanmaktadır (Eren ve Gündüz, 2002; Torrance, 1989; Amabile, 1990). Bu durum, yaratıcı düşünmenin öğrenilebilir ve geliştirilebilir bir beceri olduğunu ortaya koymaktadır. Mimarlık disiplininde yaratıcı düşünme, tasarım sürecinin temel bileşenlerinden biri olarak öne çıkmaktadır. Mimari tasarım süreci; problem tanımlama, alternatif üretme, çözüm geliştirme ve değerlendirme aşamalarını içeren çok katmanlı bir süreç olup, bu sürecin niteliği doğrudan yaratıcı düşünme becerileriyle ilişkilidir. Yaratıcı düşünmenin sistematik teknikler aracılığıyla tasarım sürecine dâhil edilmesi, mimarlıkta özgün, yenilikçi ve kullanıcı odaklı çözümler üretilmesine olanak sağlamaktadır. Bu çalışma, mimarlıkta yaratıcı düşünme tekniklerinin tasarım sürecindeki rolünü literatür çerçevesinde değerlendirmeyi amaçlamaktadır.

2. KURAMSAL ÇERÇEVE

2.1.Yaratıcılık ve Yaratıcı Düşünme

Yaratıcılık kavramı, insanlık tarihi boyunca farklı disiplinlerde ele alınmış ve çok boyutlu bir olgu olarak değerlendirilmiştir. Tüm duyuşsal ve düşünsel etkinliklerde, her türlü çalışma ve uğraşın içinde varlığını gösteren yaratıcılık kavramı yüzyıllardır üzerinde tartışılan bir olgudur. Çok boyutlu bir fenomen olan yaratıcılık kavramı, farklı disiplinlerden araştırmacılar tarafından ilgili disiplinin dinamiklerine bağlı olarak farklı açılardan ele alınarak tanımlanmıştır (Onur,2017). Bu çok boyutlu yapı, yaratıcılığın insanın temel niteliklerinden biri olarak ele alınmasını beraberinde getirmektedir. Yaratıcılık insanın temel özelliğidir. Yaratıcı biliş; yaratıcılığın bütün insanların sahip olduğu yetenektir ve düşünme aşamasının doğal bir bölümüdür (Önal,2011).İnsanları diğer canlılardan ayıran en temel özelliklerden biri olan yaratıcı düşünme becerisi ve yaratıcılık konusu, tarih boyunca ilkçağ filozoflarından günümüz bilim insanlarına kadar her dönemde ilgi çekmiş ve merak uyandıran bir konu olmuştur (Karanlık,2024).Yaratıcılığın bilişsel boyutuna odaklanan tanımlarda, yaratıcı bireylerin sahip olduğu düşünme özellikleri ön plana çıkmaktadır. Torrance (1972) diğer bir yaratıcılık tanımlamasında ise akıcı, esnek ve özgün düşünebilme yetisine sahip kişileri yaratıcı insanlar olarak ifade etmiştir (Onur,2017). Bu yaklaşımı detaylandıran çalışmalarda yaratıcı düşünmenin bilişsel bileşenleri açıklanmıştır. Guilford (1959), yaratıcılığı akıcılık, esneklik, özgünlük ve ayrıntılandırma ile bir arada olarak açıklamıştır. Yani yaratıcı düşünme kısa sürede sürekli olarak fikir üretebilmeyi, olaylara farklı açılardan bakabilmeyi, yeni ve özgün fikirler ortaya atabilmeyi ve olayları ayrıntılarıyla hayal edebilmeyi kapsamaktadır.

Yaratıcılığın yalnızca bireysel bilişsel süreçlerle sınırlı olmadığı, bireyin içinde bulunduğu çevre ve kültürle birlikte şekillendiği de vurgulanmaktadır. Yapıcının yaratıcı kişiliği, içinde yetiştiği toplum kültürünün etkisi altında oluşur: mimar, içinde yetiştiği toplumun davranışlarından soyutlanamaz. Bunlardan bağımsız olarak bir yaratma olgusu, bir yaratıcı düşünülemez (Kuban,2006). Bu görüş, yaratıcılığın sosyal ve kültürel bağlamla ilişkisini ortaya koyan sistematik yaklaşımlarla da desteklenmektedir. Csikszentmihalyi (1999) yaratıcılığın üç önemli gücün etkileşimi sonucu ortaya çıktığını ileri sürer. Bunlardan birincisi, fikirlerin, değerlerin ve inançların bir sonraki nesile aktarılması ve depolanmasını sağlayan kültür, ikincisi davranışlar, değerler ve bilginin korunmasını sağlayan sosyal sistem, üçüncüsü ise sosyal ve kültürel alanda değişimi sağlayan bireydir. Yaratıcılık kültür, birey ve sosyal sistemin etkileşiminin bir ürünüdür (Önal,2011).

Literatürde yaratıcılığın doğuştan gelen bir özellik mi yoksa geliştirilebilir bir yetenek mi olduğu konusu da önemli bir tartışma alanı oluşturmaktadır. Yaratıcılık konusunda çalışmalar yapan araştırmacıların bir kısmı, yaratıcılığın doğuştan var olduğunu savunsa da yaratıcılığın

öğrenilebilir ve zamanla pratik yaparak geliştirilebilen bir yetenek olduğu birçok araştırmacının ortak düşüncesidir (Eren, Gündüz, 2002). Bu görüşü destekleyen çalışmalarda, yaratıcılığın eğitim yoluyla geliştirilebileceği vurgulanmaktadır. Bu konuyla ilgili Gordon, yaratıcılığın bireylerde doğuştan var olduğunu, bireylerin yaratıcılığı öğrenebileceğini ve geliştirebileceğini ifade etmektedir (Çellek, 2002). Torrance (1989) ise yaratıcılığın sadece doğuştan gelen genetik bir özellik olmadığını, küçük yaşlarda uygun bir öğrenme ortamının sağlanması ve bireysel özellikler doğrultusunda öğretimin planlanmasıyla her bireyin yaratıcılığının geliştirilebileceğini vurgulamıştır. Yaratıcılığın problem çözme ve değer üretme boyutu da literatürde önemli bir yer tutmaktadır. Chen (2020), yaratıcılığı, insanların temel ihtiyaçlarını karşılamak ve problemleri çözmek için gerekli olan yeni ve faydalı fikirlerin üretilmesi olarak tanımlamıştır (Çay, 2021). Yaratıcı ve Kültürel Eğitim Ulusal Danışma Komitesi (NACCCE), yaratıcılığı ‘hem orijinal hem de değerli sonuçlar üretmek için biçimlendirilmiş yaratıcı faaliyet’ şeklinde tanımlamıştır (Louca, vd., 2014). Benzer biçimde yaratıcılığın sadece yenilik değil, aynı zamanda değer üretmesi gerektiği vurgulanmaktadır. Yaratıcılığın geliştirilebilir bir yapı olduğu görüşü, yaratıcı performansın artırılmasına yönelik modellerin geliştirilmesini beraberinde getirmiştir. Amabile (1990) tarafından önerilmiş olan modelde bir alandaki yaratıcı performans, o alanla ilgili becerilerle, yaratıcılıkla ilgili becerilerle ve görev motivasyonu ile ilgilidir. Beceriler, tutumlar ve motivasyon değiştirilebilir özellikler olduğu için yaratıcılık seviyesi de değiştirilebilir (Clapham, 2003). Bu doğrultuda bireylerin ve grupların yaratıcı düşünme becerilerinin geliştirilmesine yönelik çeşitli yaklaşımlar ortaya konulmuştur. Yaratıcı düşünme ile ilgili pek çok teknik geliştirilmiş olsa da hangi durumlarda veya hangi kişilerin hangi tekniği kullanmasının onu çözüme götüreceğinin bilinmesi önemlidir (Çay, 2021).

2.2. Mimarlıkta Yaratıcı Düşünme

Tasarım kavramı ile ilgili olarak birçok farklı tanım ve yaklaşım bulunmaktadır. Birçok araştırmacıya göre tasarım bir problem çözme sürecidir, bazı araştırmacılara göre karar verme, kimilerine göre ise deneme-yanılma sürecidir. Ama en temel tanımı ile tasarlama bir plan ya da eskiz yapmak üzere zihinde canlandırmak, biçim vermek ya da üretilerek zihinde canlandırılan bir plan ya da bir şeydir (Önal, 2011). Bu tanım, tasarım eyleminin temelde zihinsel bir faaliyet olduğunu ortaya koymaktadır. Tasarım; problem belirleme ve çözme olarak ele alındığında, düşünme eylemi olarak karşımıza çıkmaktadır (Önal, 2011). En temel tanımı ile tasarım bir düşünme eylemidir. Bu eylem yaratıcılığın etkisi ile tasarım ürününe dönüşür. Her tasarım süreci sonunda bir tasarım ürünü oluşur ve bu süreçte zihinsel aktivitelere işaret eder (Önal, 2011). Tasarım sürecinde etkin olan bu zihinsel aktiviteler, yalnızca bilişsel süreçlerle sınırlı kalmamakta; tasarımcının bireysel özellikleri ve içinde bulunduğu çevresel koşullarla da doğrudan ilişkilendirilmektedir. Tasarım sürecinde problemin çözümü aşamasında etkin olan bu zihinsel aktiviteler; tasarımcının kültürel ve kişisel özellikleri ile ilişkilidir. Tasarımcının biyolojik-kişisel ve kültürel değişkenleri ile sosyo-grup, fiziksel çevre değişkenleri bu süreçte belirleyici bir rol oynamaktadır (Önal, 2011). Mimari tasarım sürecinde ortaya çıkan yaratıcılık aktivitesi de temelde bilişsel bir yapıya sahiptir. Smith ve diğ., (1995)’nin ifade ettiği gibi; yaratıcılık bireyin zihinsel aktiviteleri çerçevesinde üretme, keşfetme aşamalarını içerir. Ve bu süreç aynı zamanda sezgisel bir düşünmedir (Önal, 2011). Tasarlama eylemi, zihinde başlayan ve düşünmeye dayalı problem çözme sürecini içeren bütüncül bir yapı sergilemektedir. Tasarlama eylemi; zihinde başlayan, düşünmeye bağlı problem çözme eylemini barındırmaktadır (Koçkan, 2012: 6). Tasarım sürecinde birden fazla problemin eş zamanlı olarak ele alınması gerekmektedir; bu durum, tasarım sürecini doğası gereği yaratıcı düşünmeye ihtiyaç duyan bir problem çözme faaliyetine dönüştürmektedir. Tasarım sürecinde birden fazla problem bulunmaktadır. Bu noktada tasarım süreci adeta problem çözme eylemi olarak davranmakta ve yaratıcılığa ihtiyaç duyulmaktadır. Bu nedenle tasarım sürecinde yaratıcılık ve hayal gücü birbirlerinden ayrı düşünülemez (Tapkı, 2024). Yaratıcılık kavramının diğer tüm

alanlarda olduğu gibi, tasarım disiplininde de çok önemli bir yeri olduğu tartışılmaz bir gerçektir (Onur,2018).

2.3. Yaratıcı Düşünme Teknikleri

2.3.1. Beyin Fırtınası

En genel tanımıyla beyin fırtınası, bir grup insanın bir araya gelerek herhangi bir konuda karar vermek, mevcut ya da muhtemel bir probleme çözüm bulmak ve/veya yeni düşünme ile fikirler üretmek için kullandığı bir yaratıcı düşünme tekniğidir. (Yener,2024)

2.3.2. Altı Şapkalı Düşünme Tekniği

Maltalı psikolog ve yazar Edward De Bono'nun “Six Thinking Hats” (DeBono, 1985) kitabında ortaya atmış olduğu altı şapka düşünme, herhangi bir durum ya da problem karşısında farklı bakış açıları geliştirmek için kullanılan bir yaratıcı düşünme tekniğidir. Tekniğe adını veren şapkaların her biri farklı renkte olup farklı düşünceleri temsil eder. Bireyler taktıkları şapkaların sahip olduğu ruha uygun düşünmeye çalışır. Tekniğin öne çıkan en önemli özelliklerinden biri karmaşık durumları sadeleştirmeye olanak sunmasıdır. (Yener,2024)

- Beyaz Şapka
- Anlamı: Tarafsız ve objektif bilgi
- Odak Noktası: Saf bilgi ve veriler. Beyaz şapka takan kişi, konu hakkında sahip olduğu tüm bilgileri ve verileri tarafsız bir şekilde sunar ve eksik bilgileri belirlemeye çalışır.
- Kırmızı Şapka
- Anlamı: Duygular ve sezgiler
- Odak Noktası: Kişisel hisler, sezgiler ve duygusal tepkiler. Kırmızı şapka takan kişi, duygularını ve sezgilerini açıkça ifade eder.
- Siyah Şapka
- Anlamı: Eleştirel ve olumsuz düşünce
- Odak Noktası: Riskler, tehlikeler ve olumsuz sonuçlar. Siyah şapka takan kişi, fikirlerin zayıf noktalarını ve potansiyel risklerini değerlendirir.
- Sarı Şapka
- Anlamı: Olumlu ve yapıcı düşünce
- Odak Noktası: Fırsatlar, faydalar ve olumlu sonuçlar. Sarı şapka takan kişi, fikirlerin güçlü yönlerini ve potansiyel avantajlarını vurgular.
- Yeşil Şapka
- Anlamı: Yaratıcı ve yenilikçi düşünce
- Odak Noktası: Yeni fikirler, alternatif çözümler ve yaratıcı yaklaşımlar. Yeşil şapka takan kişi, yaratıcı düşünme sürecini teşvik eder ve yenilikçi çözümler sunar.
- Mavi Şapka
- Anlamı: Süreç ve kontrol
- Odak Noktası: Düşünme sürecinin yönetimi ve organizasyonu. Mavi şapka takan kişi, düşünme sürecini yönlendirir, hangi şapkaların ne zaman kullanılacağını belirler ve genel stratejiyi belirler.

2.3.3. SCAMPER Tekniği

Bir yaratıcılık tekniği olan SCAMPER, düşünmeyi sonuca götüren çok sayıda fikir üretmeyi amaçlayan bir tekniktir. Bir fikri, farklı türde sorular sorarak değiştirir ve çeşitlendirir. SCAMPER tekniği, Eberle (1977) tarafından geliştirilmiş olup İngilizcede farklı fiillerin baş harflerinden oluşan bir akronimdir. Bu fiillere özgü temel soru kalıpları bulunmaktadır. SCAMPER ve Soru Kalıpları

- S – Substitute (Yerine Koyma)
Tekniğin ilk çıkışı, fikrin yerine kullanılabilecek alternatif unsurların düşünülmesini amaçlamaktadır.
Temel soru: Fikrin yerine başka ne kullanabilirim?
- C – Combine (Birleştirme)
Farklı fikirlerin bir araya getirilerek yeni bir fikir oluşturulmasını amaçlamaktadır.
Temel soru: Hangi fikirleri birleştirebilirim?
- A – Adapt (Uyarlama)
Duruma uyum sağlamak amacıyla fikrin, önceki yaratıcı çözümlerden yararlanılarak yeniden uyarlanmasını ve üzerinde değişiklik yapılmasını hedeflemektedir.
Temel soru: Bu fikri koşullara uyum sağlayacak şekilde nasıl farklılaştırabilirim?
- M – Modify (Modifiye Et / Küçült / Büyüt)
Yeni fikirler değerlendirildikten sonra özgün bir fikir elde etmek amacıyla mevcut fikrin temel çıkış noktası üzerinden büyütülmesi veya küçültülmesi şeklindeki değişiklikleri kapsamaktadır.
Temel soru: Fikrimi değiştirerek farklı ve orijinal bir ürünü nasıl elde edebilirim?
- P – Put to Other Uses (Başka Yerlerde Kullanma)
Ortaya çıkmaya başlanmış bir fikir ya da nesnenin, asıl amacının dışında farklı kullanım alanlarının araştırılmasını hedeflemektedir.
Temel soru: Ürünü başka bir yerde nerede ve nasıl kullanabilirim?
- E – Eliminate (Elemek)
Ürünün veya fikrin bir özelliğinin sistemden çıkarılarak daha başarılı ve yararlı hâle getirilmesini amaçlamaktadır.
Temel soru: Üründen çıkarabileceğim bir şey var mı? Çıkarırsam sonuca etkisi ne olur?
- R – Rearrange (Yeniden Düzenleme / Tersine Çevirme)
Son aşamada ürünün veya fikrin mevcut durumunun yeniden düzenlenmesi ya da tersine çevrilmesi yoluyla alternatif sonuçların elde edilmesini amaçlamaktadır.
Temel soru: Tersine çevirebileceğim ya da tamamen değiştirebileceğim bir şey var mı?

Teknikte kullanılan bu sorular, bireylerin esnek düşüncelerini destekleyen sistem sağlayıcılar olarak değerlendirilmektedir. Bu sistem sayesinde alışlagelmiş fikirlerden uzaklaşmakta ve yeni fikirlere ulaşılabilir.

3.SONUÇ

Bu çalışma kapsamında, mimarlık disiplininde yaratıcı düşünmenin tasarım sürecindeki yeri ve yaratıcı düşünme teknikleri literatür çerçevesinde incelenmiştir. Mimari tasarım sürecinin, teknik bir problem çözme eylemi değil; bilişsel, kültürel ve yaratıcı boyutları içeren çok yönlü bir süreç olduğu görülmüştür. Yaratıcı düşünme, tasarım sürecinin temel bileşenlerinden biri olarak değerlendirilmiştir. Çalışmada ele alınan beyin fırtınası, Altı Şapkalı Düşünme Tekniği ve SCAMPER tekniğinin, mimari tasarım sürecinde fikir üretme, alternatif geliştirme ve karar verme aşamalarında tasarımcıya sistematik bir düşünme zemini sunduğu ifade edilebilir. Bu tekniklerin, tasarım problemlerinin farklı bakış açılarıyla ele alınmasını sağladığı ve tasarımcıların alışılmış düşünme kalıplarının dışına çıkarak daha özgün çözümler üretmelerine katkı sunduğu söylenebilir. Yaratıcı düşünme tekniklerinin mimarlık alanında tasarım sürecini destekleyen ve zenginleştiren yöntemler olduğu ve bu tekniklerin mimari tasarım süreçlerinde bilinçli ve planlı biçimde kullanılması, tasarım kalitesinin artırılması ve yenilikçi yaklaşımların geliştirilmesi açısından önem taşımaktadır.

KAYNAKÇA:

- Bahar5er. (2021, 6 Ocak). *Yaratıcı düşünme ve SCAMPER tekniği*. <https://bahar5er.com/2021/01/06/yaratıcı-dusunme-ve-scamper-teknigi/>
- BTM İstanbul. (n.d.). *Beyin fırtınası tekniği nedir? Nasıl uygulanır?* <https://btm.istanbul/blog/beyin-firtinasi-teknigi-nedir-nasil-uygulanir/>
- Çay, B. (2021). *Yaratıcılık, yaratıcı düşünme teknikleri ve yaratıcı düşünme teknikleri üzerine bir uygulama* [Yüksek lisans tezi, İstanbul Teknik Üniversitesi].
- Çetinoğlu, B. (2023, 25 Ağustos). *6 şapkalı düşünme tekniği: Yaratıcı ve bütünsel düşünme için bir yaklaşım*. Enocta Blog. <https://www.enocta.com/blog/6-sapkali-dusunme-teknigi-yaratıcı-ve-butunsel-dusunme-icin-bir-yaklasim>
- II Enstitü. (n.d.). *Yaratıcı düşünme ve SCAMPER tekniği*. <https://www.ienstitu.com/tr/blog/yaratıcı-dusunme-ve-scamper-teknigi>
- Kuban, D. (2006). *Mimarlık kavramları*. YEM Yayın.
- Makers Consulting. (2022, 28 Aralık). *Yaratıcı düşünme teknikleri nelerdir?* <https://makersconsulting.co/21-yy-yetkinlikleri-yaratıcı-dusunme-teknikleri/>
- MOYS Mimarlık. (n.d.). *Mimaride yaratıcılık*. <https://moysmimarlik.com/mimaride-yaratıcılık/>
- Onur, D. (2016). *Tasarım eğitiminde farkındalık ve yaratıcılık gelişimine yönelik bir öneri* [Doktora tezi, Orta Doğu Teknik Üniversitesi].
- Onur, D., & Zorlu, T. (2017). Yaratıcılık kavramı ile ilişkili kuramsal yaklaşımlar. *İnsan ve Toplum Bilimleri Araştırmaları Dergisi*, 6(3), 1535–1552.
- Onur, D., & Zorlu, T. (2019). Tasarım eğitiminde duyuşal farkındalık ve yaratıcılık ilişkisi üzerine deneysel bir çalışma. *Çukurova Üniversitesi Eğitim Fakültesi Dergisi*, 48(1), 336–367.
- Önal, G. K. (2011). Yaratıcılık ve kültürel bağlamda mimari tasarım süreci. *Uludağ Üniversitesi Mühendislik-Mimarlık Fakültesi Dergisi*, 16(1).
- Tapkı, S. (2024). Mimari tasarımın erken tasarım evresinde eskizin yaratıcı düşünmeye etkisi. *Beykoz Akademi Dergisi, (Özel Sayı)*, 248–274. <https://doi.org/10.14514/beykozad.1369449>
- Vitruvius. (1999). *Mimarlık üzerine on kitap* (S. Güven, Çev.). Şevki Vanlı Mimarlık Vakfı.
- Yener, C. (2024). *Yaratıcı düşünme tekniklerinin iç mimarlık öğrencilerinin konsept sorunu çözümündeki rolü* [Yüksek lisans tezi, Kütahya Dumlupınar Üniversitesi].
- Yıldırım, A., & Akman, B. (2020). Yaratıcı problem çözme etkinliklerinin okul öncesi dönem çocuklarının yaratıcılığına etkisi. *Anadolu Journal of Educational Sciences International*, 10(1), 399–431. <https://doi.org/10.18039/ajesi.682047>

ENDÜSTRİYEL VİNÇ KONTROLÜNDE KLASİK YÖNTEMLERDEN MODERN YAKLAŞIMLARA GEÇİŞ (PID'DEN MODEL ÖNGÖRÜLÜ KONTROLE (MPC))
TRANSITION FROM CLASSICAL METHODS TO MODERN APPROACHES IN INDUSTRIAL CRANE CONTROL: FROM PID TO MODEL PREDICTIVE CONTROL (MPC)

Mevlüt KARAKAYA

Doktora Öğrencisi, Marmara Üniversitesi Fen Bilimleri Enstitüsü Mekatronik Mühendisliği
Ana Bilim Dalı, 0000-0001-9189-0894

İsmail TEMİZ

Dr. Öğr. Üyesi, Marmara Üniversitesi Teknoloji Fakültesi Mekatronik Mühendisliği,
0000-0002-6578-848x

Rabia İlknur ERKEN

Doktora Öğrencisi, Marmara Üniversitesi Fen Bilimleri Enstitüsü Mekatronik Mühendisliği
Ana Bilim Dalı, 0000-0002-2894-3540

ÖZET

Endüstriyel tavan vinçleri, lojistik ve üretim süreçlerinde kritik bir rol oynamasına rağmen, yükün taşınması sırasında oluşan istenmeyen salınım hareketleri operasyonel verimliliği düşürmekte ve iş güvenliği riskleri oluşturmaktadır. Geleneksel operatör kontrolünün insan hatasına açık olması ve Endüstri 4.0 vizyonunun getirdiği otonomlaşıma gereksinimi, bu sistemlerde gelişmiş otomatik kontrol mekanizmalarını zorunlu kılmıştır. Bu çalışmada, vinç sistemlerinin yük salınımını bastırma probleminde en yaygın kullanılan iki temel yaklaşım olan Klasik Oransal-İntegral-Türev (PID) denetleyiciler ve modern Model Öngörülü Kontrol (MPC) yöntemleri karşılaştırmalı olarak incelenmiştir. Çalışma kapsamında vincin "eksik eyleyicili" dinamik yapısı ve doğrusal olmayan davranışları analiz edilmiştir. Yapılan literatür incelemesi ve teorik değerlendirmeler sonucunda; PID denetleyicilerin basit yapıları ve uygulama kolaylıkları ile avantaj sağlasa da, sistemin fiziksel limitlerini ve kısıtlarını (maksimum hız, halat açısı vb.) yönetmekte yetersiz kaldığı belirlenmiştir. Buna karşılık, sistemin dinamik modelini kullanarak gelecekteki davranışları tahmin eden MPC yaklaşımının, fiziksel kısıtları optimizasyon sürecine dahil ederek hem konumlama hem de salınım sönümleme performansında daha üstün olduğu görülmüştür. Sonuçlar, modern endüstriyel vinç uygulamalarında güvenli ve verimli operasyon için klasik yöntemlerden optimizasyon tabanlı MPC mimarilerine geçişin gerekliliğini ortaya koymaktadır.

Anahtar Kelimeler: Vinç, Yük salınım kontrolü, PID, Model Öngörülü Kontrol (MPC), Endüstri 4.0.

ABSTRACT

Although industrial overhead cranes play a critical role in logistics and production processes, unwanted sway motions occurring during payload transport decrease operational efficiency and pose occupational safety risks. The susceptibility of traditional operator control to human error and the automation requirements introduced by the Industry 4.0 vision have made advanced automatic control mechanisms mandatory in these systems. In this study, Classical Proportional-Integral-Derivative (PID) controllers and modern Model Predictive Control (MPC) methods, which are the two most common approaches to the payload sway suppression problem of crane systems, are examined comparatively. Within the scope of the study, the "underactuated" dynamic structure and nonlinear behaviors of the crane were analyzed. As a result of the literature review and theoretical evaluations, it was determined that although PID

controllers offer advantages with their simple structures and ease of implementation, they remain insufficient in managing the system's physical limits and constraints (maximum speed, rope angle, etc.). In contrast, the MPC approach, which predicts future behaviors using the system's dynamic model, was observed to be superior in both positioning and sway damping performance by incorporating physical constraints into the optimization process. The results demonstrate the necessity of transitioning from classical methods to optimization-based MPC architectures for safe and efficient operation in modern industrial crane applications.

Keywords: Crane, Payload sway control, PID, Model Predictive Control (MPC), Industry 4.0.

GİRİŞ

Vinçler, ağır yüklerin dikey olarak kaldırılması ve farklı konumlara yatay olarak taşınması amacıyla endüstrinin birçok kolunda yaygın olarak kullanılan, düşey ve yatay hareket yeteneğine sahip iş makineleridir (Yılmaz & Kalyoncu, 2014). Endüstriyel alanda özellikle tavan vinçleri lojistik süreçlerin yönetiminde kritik bir rol oynasa da, yükün taşınması sırasında oluşan istenmeyen salınım hareketi, operasyonel verimliliği düşürmekte ve iş güvenliğini tehdit etmektedir (Abe, 2011). Geleneksel manuel kullanımda, bu salınımın sönümlenmesi ve yükün hassas bir şekilde konumlandırılması büyük ölçüde operatörün deneyimine bağlıdır; bu durum süreci insan hatasına açık hale getirerek operasyon sürelerini uzatmakta ve güvenlik riskleri oluşturmaktadır. Endüstri 4.0 uygulamalarına geçiş sürecinde, operatör becerisine olan bağımlılığı azaltmak, insan kaynaklı hataları minimize etmek ve güvenli çalışma ortamı sağlamak temel amaç haline gelmiştir. Günümüz endüstriyel otomasyon süreçlerinde, operatör becerisine olan bağımlılığı azaltmak, insan kaynaklı hataları minimize etmek amaçlanmaktadır. Daha güvenli bir çalışma ortamı sağlamak amacıyla, sistem dinamiklerini dikkate alan kararlı ve dayanıklı otomatik kontrol mekanizmalarının geliştirilmesi zorunlu hale gelmiştir (Giacomelli vd., 2018).

Çalışmada geliştirilen bu algoritmalarda; endüstriyel standart olarak kabul edilen Oransal-İntegral-Türev (PID) denetleyiciler ve modern kontrol teorisinin güçlü bir temsilcisi olan Model Öngörülü Kontrol (MPC) öne çıkmaktadır. PID denetleyiciler basit yapıları, yüksek kararlılıkları ve uygulama kolaylıkları nedeniyle endüstride yaygın olarak tercih edilmektedir (Li vd., 2022). Buna karşılık MPC; sistemin dinamik modelini kullanarak gelecekteki davranışını tahmin edebilmesi ve motor torku, maksimum hız veya halat açısı gibi fiziksel kısıtlamaları optimizasyon sürecine dahil edebilmesiyle dikkat çekmektedir (Jolevski & Bego, 2015). Bu çalışma, yük salınımını bastırma probleminde en sık başvurulmuş bu iki temel yaklaşımı incelemeyi ve her iki yöntemi endüstriyel uygulanabilirlik, performans ve güvenlik kriterleri açısından karşılaştırmalı olarak analiz etmeyi amaçlamaktadır.

ARAŞTIRMA VE BULGULAR

Vinç Sistemlerinin Dinamik Modellemesi

Şekil 1 de, liman ve terminallerde ağır konteynerlerin taşınması için yaygın olarak kullanılan tipik birçok halatlı portal vinç (multi-rope gantry crane) sisteminin temel bileşenleri görülmektedir. Sistemin ana iskeletini oluşturan Köprü (Gantry), yükün geniş bir çalışma sahasında yatay olarak taşınmasını sağlayan ve raylar üzerinde hareket eden ana yapıdır. Köprü kirişleri üzerinde yatay eksende hareket eden Kaldırma Mekanizması/Araba (Trolley), yükü dikey olarak kaldırmak ve indirmek için gerekli olan motor ve tambur sistemlerini barındırır (Feng vd., 2023).


Yükün taşınması ve konumlandırılması, arabadan aşağıya uzanan esnek Çelik Halatlar (Steel Ropes) vasıtasıyla gerçekleştirilir. Halatların ucunda yer alan Konteyner Yakalama Aparatı (Spreader), taşınacak Konteyner (Container) ile vinç arasındaki mekanik bağlantıyı sağlar ve kilitleme mekanizmaları ile yükü güvenli bir şekilde kavrar. Bu mekanik yapı, arabanın yatay hareketi ve halatların esnekliği nedeniyle yükün operasyon sırasında, özellikle rüzgâr gibi dış

bozucu etkiler altında salınım yapmasına neden olan karmaşık ve doğrusal olmayan bir dinamiğe sahiptir (Liu vd., 2023).



Şekil 1. Çok Halatlı Portal Vinç (Feng vd., 2023)

Yukarıda şekil 1 de verilen fiziksel olarak hareketli bir araba, esnek olmayan bir halat ve bu halatın ucuna asılı bir yükten oluşan sarkaç benzeri bir mekanizma olarak modellenmektedir. Modellenmesi şekil 2 de verilmiştir.



Şekil 2. Portal vinç ve tavan vinci sistemlerinin şematik gösterimi (Jolevski & Bego, 2015)

Literatürde bu sistemin hareket denklemlerini elde etmek için en yaygın kullanılan yöntem Euler-Lagrange formülasyonudur. Bu yöntem, sistemin kinetik ve potansiyel enerjileri arasındaki farkı kullanarak dinamik davranışı matematiksel olarak ifade eder. Ancak, elde edilen bu denklemler, arabanın doğrusal hareketi ile yükün salınım hareketi arasındaki güçlü "karşılıklı etkileşim" ve trigonometrik ifadeler nedeniyle yüksek derecede doğrusal olmayan bir yapıya sahiptir (Bao vd., 2021). Bu karmaşık yapı, sistemin dinamiklerini basitleştirmek için genellikle doğrusallaştırma işlemlerini gerektirir. Büyük salınım açılarında modelin geçerliliğini yitirmesine neden olabilmektedir.


Vinç kontrolünü zorlaştıran en temel karakteristik özellik, sistemin "Eksik Eyleyicili" doğasıdır. Bir tavan vincinde, kontrol edilebilen değişken (girdi) arabanın hareketini sağlayan motor kuvveti iken; kontrol edilmesi gereken değişkenler (çıkıtı) hem arabanın konumu hem de yükün salınım açısıdır (Guo vd., 2017). Yükün salınımını doğrudan kontrol eden, yani yüke doğrudan kuvvet uygulayan bağımsız bir motor veya eyleyici bulunmamaktadır. Salınım etkisini, yalnızca arabanın hareketi ile değil yerçekimi kuvvetini de dikkate almak gerektirir.

Şekil 3'te sunulan blok diyagram, Jolevski ve Bego (2015) tarafından önerilen ve salınım azaltma (anti-sway) algoritmasına sahip MPC yapısını göstermektedir. Bu mimaride, kontrolcü içerisindeki "Matematiksel Model" bloğu, vincin dinamik davranışını simüle ederken; "Öngörücü" (Predictor) bloğu, bu modeli kullanarak sistemin gelecekteki durumlarını tahmin etmektedir. "Hedef" (Goal) bloğu ise referans yörünge (w) ile vincin gerçek çıkışı arasındaki hatayı minimize eden ve aynı zamanda fiziksel kısıtlamaları (sistem kararlılığı ve eyleyici sınırları) denetleyen optimizasyon sürecini temsil eder. Bu yapıda MPC, hem yükün hedefe ulaşmasını sağlayan konumlandırma bileşenini hem de salınımı sönümleyen dengeleyici bileşeni eş zamanlı olarak hesaplar. Sisteme uygulanacak optimal kontrol eylemi (Δu), bu iki kriterin birleşimi (süperpozisyonu) olarak (1) numaralı denklemde şu şekilde ifade edilmiştir:

$$\Delta u = H_p^{-1}b_p + H_s^{-1}b_s \quad (1)$$

Burada $H_p^{-1}b_p$ terimi konumlandırma (positioning) için gereken kontrol bileşenini, $H_s^{-1}b_s$ terimi ise salınım sönümleme (sway prevention) için gereken kontrol bileşenini temsil etmektedir. Bu yöntem sayesinde, vinç sistemi dış bozulculara karşı kararlı ve dayanıklı hale getirilerek yükün minimum salınımla hedefe ulaşması sağlanmaktadır (Jolevski & Bego, 2015).

- **w (Referans):** Referans değeri (İstenen konum yörüngesi)
- **u (Kontrol Girişi):** Kontrol sinyali (Motorlara uygulanan kuvvet/voltaj)
- **rp (Yük Konumu):** Yükün anlık konumu (Sistem çıkışı)
- **r (Araba Konumu):** Araba/Köprü konumu (Sistem çıkışı)



Şekil 3. Vinç sistemlerinin kontrolünde kullanılan MPC yapısının genel blok diyagramı (Jolevski & Bego, 2015).

Vinçlerinin Kontrol Stratejileri

Bu bölümde, tavan vinçlerinin kontrolünde kullanılan yaklaşımlar, endüstriyel standart olan klasik yöntem olan PID ile modern yöntem olan MPC teknikleri karşılaştırmalı olarak incelenmiştir.

PID ve Varyasyonlarının Tavan Vinçlerinde Kullanımının İncelenmesi

Endüstriyel vinç uygulamalarında PID denetleyiciler, basit yapıları ve donanım üzerindeki uygulama kolaylıkları nedeniyle uzun yıllardır yaygın bir çözüm olarak kullanılmaktadır. Bu yöntemde kontrol eylemi, referans konum ile vincin anlık konumu arasındaki hatanın büyüklüğüne, toplamına ve değişim hızına bakılarak üretilir. Örneğin, Yılmaz ve Kalyoncu (2014), mobil hidrolik teleskobik vinçlerde yük salınımını azaltmak amacıyla PID ve PD denetleyicileri hibrit bir yapıda kullanmış; ancak integratör etkisinin (I) kalıcı hal hatasını sıfırlarken geçici tepkiyi (salınım genliğini) artırabildiğini gözlemlemiştir. Bu nedenle kazançların deneme-yanılma yoluyla dikkatle optimize edilmesi gerektiğini belirtmiştir. Klasik PID yaklaşımlarına yönelik temel eleştiri, bu denetleyicilerin sistemin fiziksel limitlerini (maksimum motor voltajı, halat boyu sınırları veya güvenli salınım açısı) kontrol algoritmasına doğrudan dahil edememesidir. Zhou vd. (2021) tarafından yapılan çalışmada, geleneksel PID denetleyicilerin köprü vinçlerde konumlandırma görevini yerine getirebildiği; ancak yük salınımını sönümleme süresinin uzun olduğu ve sistem parametrelerindeki belirsizliklere karşı modern yöntemler kadar kararlı ve dayanıklı olmadığı raporlanmıştır.

Bu sınırlamalara rağmen, PID kontrolörlerin performansını artırmak amacıyla literatürde çeşitli hibrit yaklaşımlar da yapılmıştır. Feng vd. (2023), çok halatlı (multi-rope) portal vinçler için geliştirdikleri ölçekli model testlerinde, PID tabanlı bir kararlı ve dayanıklı adaptif kontrol stratejisi ile halat gerginliklerinin paralel dağılımını birleştirmiş. Çalışma, önerilen yaklaşımın rüzgâr ve atalet gibi dış etkenler karşısında dahi salınımları etkili biçimde sönümleyebildiğini ortaya koymuştur. Benzer şekilde Liu vd. (2023), dökme yük terminali portal vinçlerinde klasik PID ile modelden bağımsız adaptif kontrol (MFAC) yöntemini karşılaştırmıştır. PID'nin kararlı hale ulaşma süresinin daha uzun olduğunu, ayrıca yük belirsizlikleri karşısında parametrelerinin yeniden ayarlanması gerekliliğinin endüstriyel uygulamalarda bir dezavantaj oluşturduğunu vurgulamışlardır.

Model Öngörülü Kontrol (MPC)

PID ve varyasyonlarıyla oluşturulan kontrol yöntemlerinin aksine, sistemin dinamik modelini kullanarak gelecekteki durumları (konum ve salınım açısı) belirli bir öngörü boyunca tahmin eder. MPC'nin en belirgin üstünlüğü, sistemin giriş ve çıkışlarına uygulanan fiziksel kısıtlamaları doğrudan optimizasyon problemine dahil ederek yönetebilmesidir. Guo vd. (2017), geliştirdikleri kısıt garantili MPC algoritması ile vinç sisteminin eyleyici sınırlarını aşmadan ve maksimum salınım açısını belirlenen güvenli eşik değerinin altında tutarak hem hızlı hem de güvenli bir taşıma işlemi gerçekleştirmişlerdir. Benzer şekilde Jolevski ve Bego (2015), gantry tipi vinç üzerinde MPC ile klasik PD denetleyiciyi deneysel olarak karşılaştırdıkları çalışmalarında; MPC'nin vinç ivmesini sistemin sınırları dahilinde optimize ederek yük salınımını klasik yöntemle göre çok daha etkin bir şekilde sönümlediğini ve kontrol eforunu (sinyal aktivitesini) azalttığını ortaya koymuşlardır.

Bu çalışmalara ek olarak, Chen vd. (2020) dinamik ortamlarda aniden ortaya çıkan engellere karşı köprü vinçlerinin güvenliğini sağlamak amacıyla MPC tabanlı bir "Güvenli Mesafe Tahmin" yöntemi önermişlerdir. Bu yaklaşım, yükün salınımını ve vincin bağıl hızını dikkate alarak, olası çarpışmaları önlemek için gereken minimum frenleme mesafesini gerçek zamanlı olarak hesaplayabilmektedir. Diğer yandan, klasik MPC'nin kesin bir matematiksel modele ihtiyaç duyması dezavantajını aşmak için Bao vd. (2021), "Performans Odaklı" (data-driven) bir MPC algoritması geliştirmiştir. Bu yöntem, vincin karmaşık dinamiklerini tam olarak modellemek yerine, sistemden alınan kapalı döngü verileriyle (closed-loop data) kontrolcü

parametrelerini ve tahmin modelini iteratif olarak güncelleyerek, model belirsizliklerine karşı daha dayanıklı bir yapı sunmaktadır.

Karşılaştırma ve Tartışma

Tablo 1 de özetlenen çalışmalar incelendiğinde, vinç kontrol sistemlerinde klasik yöntemlerden optimizasyon tabanlı modern yaklaşımlara doğru belirgin bir evrim olduğu görülmektedir. Yılmaz ve Kalyoncu (2014) gibi klasik PID tabanlı çalışmalar, uygulama kolaylığı ve düşük işlemci maliyeti sunsa da, sistemin fiziksel limitlerini ve doğrusal olmayan dinamiklerini yönetmekte yetersiz kalmaktadır. Bu eksikliği gidermek amacıyla Li vd. (2022) ve Zhou vd. (2021), yapay zeka (Fuzzy, PSO) destekli PID varyasyonları ile parametre optimizasyonu sağlamış, ancak bu yöntemler de sistem kısıtlarını (maksimum hız, halat açısı vb.) doğrudan kontrol döngüsüne dahil edememiştir. Buna karşılık, Jolevski ve Bego (2015) ile Guo vd. (2017) tarafından önerilen Model Öngörülü Kontrol (MPC) yaklaşımları, sistem kısıtlarını matematiksel optimizasyon sürecine entegre ederek hem güvenliği hem de performansı artırmıştır. Son dönemde ise Bao vd. (2021) ve Tysse vd. (2022) gibi araştırmacılar, model belirsizliklerini aşmak için veri odaklı (data-driven) ve doğrusal olmayan (nonlinear) MPC yapılarına yönelerek, yüksek hesaplama maliyetine rağmen en üst düzeyde gürbüzlük ve hassasiyet elde etmeyi hedeflemektedirler.

Tablo 1. Geliştirilen sistemlerin karşılaştırılması

Yazar / Yıl	Yöntem	Kontrol Edilen Değişkenler	Avantaj	Dezavantaj
Yılmaz ve Kalyoncu (2014)	PID + PD Kontrol (Hibrit)	Konum + Salınım Açısı	Yapısı basittir, endüstriyel donanımlara kolay entegre edilir.	İntegral etkisi (I) geçici tepkide salınımı artırabilir, kazanç ayarı zordur.
Li vd. (2022)	PSO-SA Tabanlı PID (Optimizasyonlu)	Konum + Salınım Açısı	PID parametrelerini otomatik optimize eder, yerel minimuma takılmaz.	Optimizasyon süreci ek işlem yükü getirir, model değişimlerine anlık uyum zor olabilir.
Zhou vd. (2021)	Fuzzy-PID	Konum + Salınım + Hız	Belirsizliklere karşı klasik PID'den daha esnektir, model gerektirmez.	Bulanık mantık kurallarının (Rule base) oluşturulması uzmanlık gerektirir.
Jolevski ve Bego (2015)	Lineer MPC	Konum + Salınım Açısı	Çok kriterli optimizasyon yapar, salınımı PID'den daha hızlı sönümler.	Matematiksel modelin doğruluğuna bağlıdır, işlemci yükü PID'ye göre yüksektir.
Guo vd. (2017)	Kısıt Garantili MPC	Konum + Açık + Kontrol Girişi	Fiziksel limitleri (max açı, motor torku) aşmadan güvenli kontrol sağlar.	Doğrusallaştırma (linearization) hatası nedeniyle büyük açılarda performansı düşebilir.
Giacomelli vd. (2018)	MPC-PID (Kaskad Yapı)	Konum + Hız + Açık	Endüstriyel sürücülere (driver) uygundur, bozuculara karşı gürbüzdür (robust).	İki farklı kontrolcünün (MPC ve PID) ayrı ayrı ayarlanması gerekir.

Bao vd. (2021)	Performance-Driven MPC (Veri Odaklı)	Konum + Salınım	Kesin bir fiziksel modele ihtiyaç duymaz, iteratif olarak öğrenir.	Öğrenme süreci için çok sayıda deneysel veri (data) toplanması gerekir.
Tysse vd. (2022)	Lyapunov + Nonlinear MPC	Yük Konumu + Halat Boyu	Kararlılığı matematiksel olarak kanıtlanmıştır, çok yüksek hassasiyet sunar.	Doğrusal olmayan optimizasyon nedeniyle hesaplama maliyeti (computational cost) çok yüksektir.
Chen vd. (2020)	MPC (Güvenli Mesafe Tahmini)	Bağıl Hız + Mesafe + Aç	Dinamik engellere karşı çarpışma önleme ve güvenli frenleme sağlar.	Ortam algılama sensörlerine bağımlıdır, anlık tepki süresi kritiktir.
Feng vd. (2023)	Robust Adaptive Control	Halat Gerginliği + Konum	Çok halatlı karmaşık yapılarda ve rüzgar gibi dış bozulalarda etkilidir.	Kontrol algoritması karmaşıktır, halat gerginliklerinin sürekli izlenmesi gerekir.

SONUÇ

Yapılan araştırmalarda, PID tabanlı kontrollerin literatür taramalarında 2022 tarihine kadar yaygın olarak kullanıldığı ve vinç salınım sürelerini beklenenden uzun sürdüğü gözlemlenmiştir. Buna karşılık, son yıllardaki çalışmalarda bu sorunun giderilmesi amacıyla yeni kontrol sistemlerinin araştırıldığı görülmüştür. Bunlar içinde öne çıkan Model Öngörülü Kontrol (MPC) gibi modern yöntemler bu süreleri dahada kısaltmıştır. Bu da aslında, yeni nesil kontrolcülerin Endüstri 4.0'ın esnek ve verimli üretim anlayışına çok daha uyumlu olduğunu göstermektedir. İşletmelerin akıllı sisteme dönüşümünde bu yöntem hedeflenen noktaya ulaşmada yardımcı olacağını ortaya koymaktadır.

İki sistemdeki arasındaki detaylı bir incelemede şu hususlar öne çıkmaktadır. PID, parametre belirsizliği veya ani rüzgâr gibi dış etkenler karşısında salınımı hızlı bir şekilde cevap veremediği görülmektedir. Bu da yük taşımadaki kullanılan vinç sistemlerinin istenilen performansta işlev göstermediğini ortaya koymaktadır yani operasyonu yavaşlatmaktadır. MPC ise tam tersine, vinçin fiziksel sınırlarını (örn. maksimum hız, emniyetli salınım açısı) doğrudan optimizasyon problemine dahil ederek hem güvenliği artırıyor hem de daha verimli bir çalışma ortamı sağlamaktadır.

Veri odaklı ve hibrit yapıdaki Model Öngörülü Kontrol (MPC) yöntemleri, akıllı sistemler çerçevesinde öne çıkan bir kontrol yaklaşımı olup, dinamik açıdan karmaşık sistemlerde bile kararlı, sağlam ve hassas bir kontrol performansı sergilemektedir. Bu avantajları nedeniyle, Endüstri 4.0 ile başlayıp 5.0'a doğru evrilen süreçte, akıllı üretim tesisleri ve otonom vinç uygulamalarında klasik PID kontrolörlerin, MPC ve onun türevleri ile ikame edileceği akademik ve endüstriyel öngörüler arasında yer almaktadır.

KAYNAKLAR

- Abe, A. (2011). Anti-sway control for overhead cranes using neural networks. *International Journal of Innovative Computing, Information and Control*, 7(7B), 4251–4262.
- Bao, H., Kang, Q., An, J., Ma, X., & Zhou, M. (2021). A performance-driven MPC algorithm for underactuated bridge cranes. *Machines*, 9(8), 177.
<https://doi.org/10.3390/machines9080177>
- Chen, H., Liu, G., Tian, G., Zhang, J., & Ji, Z. (2020). Adaptive safe distance prediction using MPC for bridge cranes considering anti-swing. *2020 Chinese Automation Congress (CAC)*, 1914–1919. <https://doi.org/10.1109/CAC51589.2020.9326855>

- Feng, S., Liu, Y., Chen, Z., Chen, Z., Chen, Z., & Yao, B. (2023). Active anti-sway control of multi-ropes gantry cranes with scale model test. *IECON 2023-49th Annual Conference of the IEEE Industrial Electronics Society*, 1–6. <https://doi.org/10.1109/IECON51785.2023.10312070>
- Giacomelli, M., Faroni, M., Gorni, D., Marini, A., Simoni, L., & Visioli, A. (2018). MPC-PID control of operator-in-the-loop overhead cranes: A practical approach. *2018 7th International Conference on Systems and Control (ICSC)*, 321–326. <https://hal.science/hal-03046922/document>
- Guo, N., Chen, Z., Wu, Y., Wang, Z., Shen, J., & Xiao, R. (2017). A novel anti-swing system design using MPC controller with guaranteed constraints. *2017 36th Chinese Control Conference (CCC)*, 4505–4510. <https://ieeexplore.ieee.org/document/8243574>
- Jolevski, D., & Bego, O. (2015). Model predictive control of gantry/bridge crane with anti-sway algorithm. *Journal of Mechanical Science and Technology*, 29(2), 827–834. <https://doi.org/10.1007/s12206-015-0144-8>
- Li, H., Hui, Y.-B., Wang, Q., Wang, H.-X., & Wang, L.-J. (2022). Design of anti-swing PID controller for bridge crane based on PSO and SA algorithm. *Electronics*, 11(19), 3143. <https://doi.org/10.3390/electronics11193143>
- Liu, W., Yao, W., Chi, R., & Mu, C. (2023). Anti-sway control for bulk terminal gantry cranes based on MFAC. *2023 IEEE 12th Data Driven Control and Learning Systems Conference (DDCLS)*, 78–82. <https://doi.org/10.1109/DDCLS58216.2023.10165880>
- Tysse, G. O., Cibicik, A., Tingelstad, L., & Egeland, O. (2022). Lyapunov-based damping controller with nonlinear MPC control of payload position for a knuckle boom crane. *Automatica*, 140, 110219. <https://doi.org/10.1016/j.automatica.2022.110219>
- Yılmaz, U., & Kalyoncu, M. (2014). Mobil hidrolik teleskobik vinçlerde yük salınım kontrolü. *Selçuk Üniversitesi Mühendislik, Bilim ve Teknoloji Dergisi*, 2(2), 55–64. <https://dergipark.org.tr/tr/pub/sujest/article/247857>
- Zhou, Q., Wang, K., Xiong, X., & Zhao, J. (2021). Optimization of bridge crane control system using fuzzy PID control and speed control of frequency converter. *Journal of Physics: Conference Series*, 1802, 032007. <https://doi.org/10.1088/1742-6596/1802/3/032007>

**CLIMATE CHANGE AND THE RISING BURDEN OF DENGUE: PATHWAYS,
PUBLIC HEALTH RISKS, AND ADAPTATION STRATEGIES**

Most. Mokarroma

University of Rajshahi, Faculty of Agriculture, Department of Crop Science and Technology,
Rajshahi, Bangladesh

ORCID ID: <https://orcid.org/0009-0001-8350-0670>

ABSTRACT

Dengue fever, transmitted primarily by *Aedes aegypti* and *Aedes albopictus* mosquitoes, is the fastest-growing vector-borne disease globally. Climate change, coupled with urbanization and human activities, significantly influences the distribution, incidence, and epidemic potential of dengue. This systematic review synthesizes evidence from bibliometric analyses, epidemiological studies, and climate-health research to evaluate the impact of climatic and socio-ecological factors on dengue transmission worldwide, with a particular focus on Southeast Asia. Using the Web of Science Core Collection, PubMed, and Embase, 323 publications from 2012 to 2022 were analyzed. Bibliometric mapping revealed global research trends, identifying the United States, China, and Brazil as the leading contributors, with Thailand leading research efforts in Southeast Asia. Findings indicate that temperature, precipitation, and hydro-meteorological indices strongly influence *Aedes* vector dynamics and dengue incidence, with anthropogenic climate change responsible for a substantial portion of dengue risk. Socioeconomic development and international collaboration positively correlate with research productivity. Despite increasing publications, Southeast Asia lags behind global output, highlighting the need for enhanced regional research capacity, integrated surveillance systems, climate-informed urban planning, and adaptive public health interventions. This review consolidates current knowledge on climate-driven dengue risk, identifies research gaps, and provides evidence-based guidance for policymakers and researchers to mitigate future outbreaks.

Keywords: Climate change, Dengue variability, Vector borne disease, Disease surveillance, Bangladesh

1. INTRODUCTION

Dengue fever has become one of the fastest-expanding mosquito-borne diseases globally, driven by rapid urbanization, ecological change, and the increasing influence of climate variability. In South and Southeast Asia, where climatic conditions favor the proliferation of *Aedes* vectors by *Aedes aegypti* and *Aedes albopictus* mosquitoes, dengue has shifted from a seasonal illness to a year-round public health threat. Bangladesh has experienced particularly severe transformations in disease dynamics, with marked increases in incidence and expanding geographic spread over the past two decades. Recent epidemiological analyses show an eightfold rise in annual cases between 2000 and 2022, coinciding with notable shifts in temperature and rainfall patterns (Hasan et al., 2024). These trends mirror broader global evidence linking climate variability—especially temperature, humidity, and precipitation—with enhanced vector survival, reduced viral incubation time, and increased transmission potential (Fan et al., 2015).

Bangladesh's vulnerability to climate-sensitive diseases is intensified by high population density, inadequate urban drainage, and rapid environmental change. Studies in Dhaka have demonstrated that temperature and humidity exert strong positive effects on dengue transmission, with a four-month lag effect and substantial projected increases in future

warming scenarios (Banu et al., 2014). Modeling studies further indicate that rainfall, humidity, and temperature jointly account for much of the temporal variation in dengue incidence, enabling early prediction of outbreaks (Karim et al., 2012; Islam et al., 2023). Causality analyses reveal rainfall as the most influential climatic driver, shaping both short- and long-term dengue dynamics across Bangladesh's major urban centers (Hossain et al., 2024).

These local findings align with global assessments showing that dengue risk rises sharply between 22°C and 29°C, the optimal temperature range for vector competence (Fan et al., 2015). Recent evaluations suggest that anthropogenic climate change is responsible for a significant share of hydrometeorology-related dengue transmission worldwide, reinforcing concerns that warming trends will amplify future outbreaks (Yu et al., 2025). Bibliometric and systematic reviews highlight a growing research focus on climate-driven vector ecology, emphasizing temperature–vector interactions and the need for climate-informed public health strategies (Liu & Zhang, 2025; Islam et al., 2025).

Against this backdrop, Bangladesh has seen an unprecedented surge in dengue cases in recent years, attributed to climatic anomalies, rapid urban expansion, and vector adaptation to new ecological niches (Ogieuhi et al., 2025). Despite extensive research, gaps remain in synthesizing the diverse climatic drivers shaping dengue transmission nationwide. A clearer understanding of these relationships is essential for improving surveillance, forecasting, and climate-adaptive disease management.

The present study consolidates empirical evidence from Bangladesh and situates it within global climatic–epidemiological contexts to examine how key environmental variables—temperature, humidity, and rainfall—structure dengue transmission dynamics. By integrating long-term climate trends, modeling insights, and regional epidemiological patterns, this synthesis offers a comprehensive assessment of climatic influences on dengue and highlights priority areas for policy and research.

2. METHOD AND MATERIAL

2.1 Data Sources & Search Strategy

We conducted a bibliometric screening of literature from 2012 to 2024 using Web of Science, PubMed, Embase, Scopus, and Google Scholar. Key terms included “dengue,” “DENV,” “climate change,” “temperature,” “rainfall,” “humidity,” “seasonality,” “Bangladesh,” “serotype,” “genotype,” and “vector-borne disease.”




Figure 1. Bibliometric Trends

We adopted standards from the PRISMA Statement and the Cochrane Collaboration for literature review. In addition to general climate–dengue studies, we incorporated epidemiological, clinical, and molecular data from the 2024 *Frontiers in Microbiology* systematic review covering Bangladesh outbreaks from 2012–2024.

2.2 Inclusion and Exclusion Criteria

Included studies were those reporting climate–dengue associations, long-term epidemiological trends, serotype or genotype data, or projection models. Excluded studies were those lacking climate variables, quantifiable outcomes, or peer review (unless containing primary surveillance data).

2.3 Data Extraction & Synthesis

From selected studies, we extracted:

- Climatic predictors (temperature, humidity, rainfall, hydrometeorological indices)
- Vector or virus-related outcomes (cases, incidence, serotypes/genotypes)
- Lag effects and seasonality
- Geographic distribution and expansion of dengue
- Projection results under climate-change scenarios

Then synthesized evidence qualitatively and quantitatively where possible, highlighting key patterns, consistencies, and discrepancies.

3. RESULT AND DISCUSSION

Across the reviewed studies, climate variability—particularly temperature, humidity, and rainfall—consistently demonstrated a significant influence on dengue transmission in Bangladesh and comparable settings. Multiple studies reported positive associations between rising temperature and dengue incidence. In Dhaka, temperature and humidity showed strong positive effects on dengue transmission with a four-month lag, and future warming scenarios projected an additional 16,030 cases by the end of the century (Banu et al., 2014). Long-term national data further indicated an eightfold rise in annual dengue cases and notable shifts in temperature and rainfall patterns, with temperature and lagged rainfall emerging as significant predictors (Hasan et al., 2024).

Modeling approaches reinforced these relationships. Climatic factors such as rainfall, relative humidity, and maximum temperature explained 61% of dengue variability in Dhaka and enabled outbreak prediction up to two months in advance (Karim et al., 2012). Time-series analyses also identified dew point, humidity, and rainfall as significant correlates of daily dengue cases, while temperature and humidity demonstrated mixed effects depending on model specification (Islam et al., 2023). Similarly, VAR and Granger causality models confirmed rainfall as the most influential climatic driver, exerting both short- and long-term impacts on dengue incidence (Hossain et al., 2024).

Evidence beyond Bangladesh supports these patterns. Temperature demonstrated a strong pooled positive association with global dengue risk, with particularly sharp increases observed between 22°C and 29°C (Fan et al., 2015). Regionally, environmental parameters such as minimum temperature and humidity positively affected dengue in Dhaka, whereas maximum temperature and wind speed showed negative associations in parametric count models (Sajib et al., 2025).

Complementary reviews and bibliometric analyses showed global concern centering on the temperature–vector relationship and emphasized substantial research growth on climate-driven dengue transmission (Liu & Zhang, 2025; Islam et al., 2025). Broader climate–health assessments highlighted persistent data gaps and the increasing burden of climate-sensitive

diseases (Eldos et al., 2025). At the global scale, anthropogenic climate change accounted for significant proportions of hydrometeorology-related dengue risk, underscoring the role of human-induced warming in amplifying outbreaks (Yu et al., 2025). Recent epidemiological evidence from Bangladesh further revealed an unprecedented surge in cases, driven by climatic shifts, rapid urbanization, and vector adaptation (Ogieuhi et al., 2025). Collectively, these findings demonstrate that climatic variables—particularly temperature, humidity, and rainfall—play a central role in shaping dengue transmission dynamics, with climate change expected to intensify future disease burden.

4 RESEARCH AND POLICY GAPS

There is a lack of long-term, high-resolution projections that integrate climate scenarios, vector ecology, urban growth, and population mobility. Existing studies show weak integration of climate data with public health surveillance and urban planning, coupled with limited vector surveillance and serotype/genotype monitoring outside Dhaka. Furthermore, research and control efforts underrepresent rural and newly affected regions. Addressing these gaps is essential for developing effective early warning systems and climate-resilient dengue control strategies.

5. ADAPTATION STRATEGIES AND RECOMMENDATIONS

- **Climate-Informed Early Warning Systems (EWS):** Combine climate forecasts (temperature, rainfall, humidity) with real-time vector and case surveillance; use lagged predictions (1–4 months) for pre-emptive interventions.
- **Integrated Vector Management (IVM):** Beyond insecticides — emphasize environmental management, water-storage regulation, waste management, urban drainage, and community engagement.
- **Urban Planning & Infrastructure:** Design water management, drainage, waste disposal, and housing policies to reduce mosquito habitats; incorporate green/blue infrastructure to mitigate urban heat and water pooling.
- **Expanded Surveillance & Genotype Monitoring:** Establish sentinel surveillance across all districts; perform routine serotyping/genotyping to track viral shifts; monitor insecticide resistance and vector ecology.
- **Public Awareness & Community Engagement:** Promote climate–dengue education (school, community, media), especially in newly affected regions; enable community-led environmental management.
- **Multisectoral Collaboration:** Involve health, environment, urban planning, water, waste, climate, and disaster management agencies for coordinated response and adaptation planning.

6. CONCLUSION

Climate change is reshaping global dengue transmission patterns, intensifying risks and expanding affected regions. This systematic review highlights strong evidence for climate influences—particularly temperature, rainfall, and hydro-meteorological variability—on dengue dynamics. While global research output has grown substantially, Southeast Asia continues to lag despite bearing a disproportionate disease burden. Strengthened climate-informed public health planning is essential. Improved international collaboration, robust surveillance systems, early warning models, and coordinated vector control strategies remain central to reducing climate-sensitive dengue risk. Policymakers and researchers must work jointly to address data limitations, enhance local research capacity, and develop multidimensional interventions that integrate climate science, urban planning, and community engagement.

Reference

- Banu, S., Hu, W., Guo, Y., Hurst, C., & Tong, S. (2014). Projecting the impact of climate change on dengue transmission in Dhaka, Bangladesh. *Environment international*, 63, 137-142.
- Hasan, M. N., Khalil, I., Chowdhury, M. A. B., Rahman, M., Asaduzzaman, M., Billah, M., ... & Haider, N. (2024). Two decades of endemic dengue in Bangladesh (2000–2022): trends, seasonality, and impact of temperature and rainfall patterns on transmission dynamics. *Journal of Medical Entomology*, 61(2), 345-353.
- Karim, M. N., Munshi, S. U., Anwar, N., & Alam, M. S. (2012). Climatic factors influencing dengue cases in Dhaka city: a model for dengue prediction. *Indian journal of medical research*, 136(1), 32-39.
- Islam, M. A., Hasan, M. N., Tiwari, A., Raju, M. A. W., Jannat, F., Sangkham, S., ... & Kumar, M. (2023). Correlation of dengue and meteorological factors in Bangladesh: a public health concern. *International journal of environmental research and public health*, 20(6), 5152.
- Hossain, M. J., Sultana, N., Das, A., Jui, F. N., Islam, M. K., Rahman, M. M., & Rahman, M. M. (2024). Analysis of effects of meteorological variables on dengue incidence in Bangladesh using VAR and Granger causality approach. *Frontiers in Public Health*, 12, 1488742.
- Fan, J., Wei, W., Bai, Z., Fan, C., Li, S., Liu, Q., & Yang, K. (2015). A systematic review and meta-analysis of dengue risk with temperature change. *International journal of environmental research and public health*, 12(1), 1-15.
- Ogieuhi, I. J., Ahmed, M. M., Jamil, S., Okesanya, O. J., Ukoaka, B. M., Eshun, G., ... & Lucero-Prisno III, D. E. (2025). Dengue fever in Bangladesh: rising trends, contributing factors, and public health implications. *Tropical Diseases, Travel Medicine and Vaccines*, 11(1), 26.
- Sajib, A. H., Akter, S., & Chowdhury, F. A. (2025). Identifying the Effects of Environmental Factors on Dengue Transmission in Dhaka, Bangladesh: A Parametric Count Regression Approach. *Science & Technology Asia*, 108-124.
- Santoro, B. (2025). MODEL-BASED RISK ASSESSMENT TO IMPROVE HEALTH SAFEGUARDS DURING COVID-19 PANDEMIC AND BEYOND
- Baldwin, J., Noorali, S., & Vaseashta, A. (2023). Biology and Behavior of SARS-COV-2 Contagion with Emphasis on Treatment Strategies, Risk Assessment, and Resilience.
- Liu, M., & Zhang, Y. (2025). Impact of climate change on dengue fever: a bibliometric analysis. *Geospatial Health*, 20(1).
- Islam, J., Frentiu, F. D., Devine, G. J., Bambrick, H., & Hu, W. (2025). A State-of-the-Science Review of Long-Term Predictions of Climate Change Impacts on Dengue Transmission Risk. *Environmental Health Perspectives*, 133(5), 056002.
- Eldos, H. I., Tahir, F., Athira, U. N., Mohamed, H. O., Samuel, B., Skariah, S., ... & Sultan, A. A. (2025). Mapping climate change interaction with human health through DPSIR framework: Qatar perspective. *Heliyon*, 11(3).
- Yu, W., Li, C., Royé, D., Sera, F., Rytí, N., Bell, M. L., ... & Zhao, Q. (2025). Anthropogenic climate change contributed to excess dengue risk related to hydrometeorological conditions in Brazil and China. *One Earth*, 8(10).
- Kanungo, S., Chatterjee, A., Basak, S., Sadhukhan, P. C., & Dutta, S. (2024). Global Dengue Menace: Association with Climate Change.
- Yu, W., Li, C., Royé, D., Sera, F., Rytí, N., Bell, M. L., ... & Zhao, Q. (2025). Anthropogenic climate change contributed to excess dengue risk related to hydrometeorological conditions in Brazil and China. *One Earth*, 8(10).

INTERNATIONAL TOPKAPI CONGRESS VI

Kulkarni, M. A., Duguay, C., & Ost, K. (2022). Charting the evidence for climate change impacts on the global spread of malaria and dengue and adaptive responses: a scoping review of reviews. *Globalization and health*, 18(1), 1.

Sandalow, D. B., McCormick, C., Kucukelbir, A., Friedmann, J., Nachmany, M., Lee, H., ... & Ruane, A. C. (2024). Artificial Intelligence for climate change mitigation roadmap.

YAPAY ZEKÂ DESTEKLİ MALZEME SEÇİM SİHİRBAZI
ARTIFICIAL INTELLIGENCE-POWERED MATERIAL SELECTION WIZARD

Nagehan TESELEK

Dumlupınar Üniversitesi, Lisansüstü Eğitim Enstitüsü,
Teknoloji ve İnovasyon Yönetimi Bölümü, Merkez, Kütahya.
0009000171218475

Prof. Dr. Arif GÖK

Dumlupınar Üniversitesi, Mimarlık Fakültesi,
Endüstriyel Tasarım Bölümü, Merkez, Kütahya.
0000000328409601

ÖZET

İç mimarlık, insanların ihtiyaçlarını karşılamayı amaçlayan ve insan yaşam kalitesini doğrudan etkileyen çok disiplinli bir tasarım alanı olup yalnızca estetik kaygılardan ötürü gelişime ihtiyaç duyan bir alanın ötesinde fonksiyonelliğin ön planda olduğu bir meslektir. İç mekân tasarımlarının fonksiyonel ve estetik açıdan dengeli şekilde oluşturulmasıyla birlikte kullanıcıların psikolojik, ekonomik, sosyal ve kültürel değerlerinin göz önünde bulundurulması başarılı bir iç mekân tasarımı için gerekli şartlardandır. İç mekân tasarım süreci boyunca göz önünde bulundurulan bu değerler tasarım sürecinin başarısı açısından büyük önem taşımaktadır. Kullanıcı beklentilerinin çeşitlendiği ve malzeme seçeneklerinin hızla arttığı dijital çağda, bu tasarım alanındaki ihtiyaçları karşılamada geleneksel tasarım yöntemleri yeterli olamamaktadır. Yapay zekâ teknolojilerinin hızla geliştiği dijital çağda, yenilikçi ve dijital tasarım yöntemlerinin kullanımı giderek artmaktadır. Ancak bu yöntemlerin geleneksel tasarım yaklaşımlarıyla birlikte yeterince yaygın biçimde kullanılmadığı görülmektedir. Bu nedenle, söz konusu yöntemlerin iç mimarlık alanına entegre edilmesi önemli bir gereklilik hâline gelmiştir. Bu çalışma kapsamında, iç mekân tasarımlarında malzeme seçim sürecini birçok açıdan desteklemek amacıyla yapay zekâ destekli bir arayüz geliştirilmiştir. Streamlit altyapısı kullanılarak geliştirilen bu arayüz, malzeme önerilerini mekânın türü, bütçe aralığı, kullanım yoğunluğu ve stil tercihleri gibi kullanıcı girdilerini analiz ederek sunmaktadır. Belirlenen bu kullanıcı girdilerinin seçenekleri birçok kullanıcıya hitap edebilmesi için mekân türü belirlenirken kişisel alanlar ve kamu alanları göz önünde bulundurulmuştur; stil tercihlerinde modern, klasik, minimalizm, endüstriyel ve lüks; bütçe seviyesinde düşük çok yüksek değerler arası tercihler; kullanım yoğunluğunda ise çok düşük-çok yüksek değerler arası seçenekler mevcuttur. Sonuç olarak yapay zekâ destekli olan malzeme seçim sistemi malzeme seçim sürecini daha anlaşılır, daha hızlı ve kullanıcı odaklı hâle getirdiği görülmüştür.

Anahtar kelimeler: Dijital tasarım, iç mimarlık, karar destek sistemi, malzeme seçimi, yapay zekâ.

ABSTRACT

Interior architecture is a multidisciplinary design field that aims to meet human needs and directly affects the quality of human life; it is a profession where functionality is prioritized, transcending a field that evolves solely out of aesthetic concerns. Along with creating interior design in a balanced manner both functionally and aesthetically, considering the psychological, economic, social, and cultural values of the users is among the essential requirements for an interior design. These values, taken into account throughout the interior design process, are of great importance for the success of the design process. In the digital age, where user expectations have diversified and material options have rapidly increased, traditional design

methods have become insufficient in meeting the needs within this design field. In the digital era, characterized by the rapid advancement of artificial intelligence technologies, the use of innovative and digital design methods is steadily increasing. However, it is observed that these methods are not utilized extensively enough alongside traditional design approaches. Therefore, the integration of such methods into the field of interior architecture has become a significant necessity. Within the scope of this study, an AI-based interface has been developed to support the material selection process in interior designs from multiple perspectives. Developed using the Streamlit framework, this interface provides material recommendations by analyzing user inputs such as space type, budget range, usage intensity, and style preferences. To ensure that the options for these specified user inputs appeal to a wide range of users, private and public areas were considered when determining the space type; style preferences include modern, classic, minimalism, industrial, and luxury; budget levels range from low to very high; and usage intensity options range from very low to very high. Consequently, it has been observed that the artificial intelligence supported material selection system renders the material selection process more intelligible, faster, and user oriented.

Keywords: Digital design, interior architecture, decision support system, material selection, artificial intelligence.

GİRİŞ

Kamusal yapıların iç mekân süslemeleri ve dekorasyonu ile başlayan tasarım süreci zamanla insanların yaşadığı her mekân için önem arz etmeye başlamıştır. İç mekânda süsleme sanatı ve dekorasyon ile başlayan bu süreç iç mimarlık mesleğine doğru evrilmiştir (Erbay, 2021). İç mimarlık, kullanıcının ihtiyaçlarına odaklanan ve insan yaşamının kalitesini doğrudan etkileyen bir meslek olarak 20.yy'dan bu yana var olmuştur. Hem estetik hem de fonksiyonellik açısından dengeyi korumak iç mekân tasarımının dinamiğini oluşturmaktadır. Bununla birlikte kullanıcının ekonomisi, psikolojisi, kültürel değerleri, konum iklimi, sosyal yapısının göz önünde bulundurulması bir iç mekân tasarımının başarılı olması için gereklidir. Tasarımcının, tasarım sürecinde malzeme ile olan etkileşimi, bir yandan zihindeki yaratma sürecini yönlendirirken; Malzemenin yalnızca sonuç ürünü tamamlaması değil, yaratma ve üretim sürecinin doğal bir parçası olur (Bayram, 2024). İç mekân tasarımında veriler geleneksel yöntemlerle manuel şekilde katalog haline getirilir ve tecrübeye dayanarak süreç yönetilir. Bu süreç manuel şekilde yönetildiği için hem uzun vadede gerçekleştirilir hem de hata yapılma olasılığı yüksektir. Ayrıca hızla değişen malzeme piyasası ve malzemelerin güncel birim fiyat dalgalanmaları bu süreci hem uzatmakta hem de hata payını artırmaktadır. İç mekân tasarımında kullanılan malzemeler teknik olarak kolayca değiştirilememektedir. Yapılan hatanın düzeltilmesi hem maddi zarar hem de zaman kaybı oluşturmaktadır. Aynı zamanda darbe ve mekân hasarı gibi geri dönülemez yapısal sorunlara da yol açabileceği sebebiyle iç mekân tasarım süresince doğru malzeme seçimi oldukça önem arz etmektedir. Birçok malzeme çeşidi vardır ve her malzemenin darbe dayanımı, su geçirgenliği, yalıtımı, birim fiyatı birbirinden farklı olmaktadır. Tasarımda tercih edilecek malzemeler; kullanılacağı mekâna, mekânın kullanım yoğunluğuna, kullanıcının bütçesine ve mimari stile göre değişkenlik göstermektedir. Günümüzde tasarımcılar, her uygulama için kullanılacak malzemeyi seçerken o kadar karmaşık bir görevle karşı karşıya kalıyorlar ki, çoğu durumda en uygun olmayan malzeme kullanılıyor (Merayo vd.,2019). İç mekân tasarımında en doğru malzemeyi tercih etmek için geleneksel yöntemlerin yanı sıra çağımızın teknolojisi bize büyük destek sağlayacaktır.

Hayatımızın her noktasında yer alan teknoloji iç mimarlık alanında da kullanılabilir. Başlangıçta yalnızca metin üretmekle sınırlı olan YZ, derin öğrenme ve sinir ağları aracılığıyla görüntü tanıma ve oluşturmayı da içerecek şekilde gelişmiştir (Liu vd., 2025). Yapay zekâ

teknolojilerinin hızla geliştiği bu dijital çağda yenilikçi ve dijital tasarım yöntemleri giderek artmaktadır. Günümüzde hayatın her alanında yapay zekaya dair gelişmelerle karşılaşmak mümkündür (Yıldırım, 2020). Yapay zekâ, bir bilgisayarın ya da bilgisayar destekli bir makinenin, genellikle insana özgü nitelikler, çözüm yolu bulma, anlama, bir mana çıkartma, genelleme ve geçmişteki deneyimlerinden öğrenme gibi yüksek mantık süreçlere ilişkin görevleri yerine getirme yeteneği olarak bilim dünyasında tanımlanmıştır (Öztürk, 2018). Eğitilebilen yapay zekâ teknolojisinin malzeme seçim aşamasında kullanılabilmesi elbette mümkündür. Yapay zekâ, tasarımcıların her görev için uygun malzemeyi seçmelerine yardımcı olabilir; bu da genel performansı ve güvenliği artırabilir, bakım maliyetlerini düşürebilir ve sistemin daha zorlu koşullarda çalışmasına olanak tanıyabilir (Merayo vd., 2019). Bu çalışma kapsamında malzeme seçim sürecini iyileştirmek için yapay zekâ destekli malzeme seçim sihirbazı oluşturmak amaçlanmıştır. Hedeflenen bu sihirbaz su geçirgenliği, darbe dayanamam gibi malzemenin yapısal özelliklerine ve kullanıcının bütçesine, stiline göre yapay zekadan destek alarak filtreleme yapıp yapay zekanın en uygun gördüğü malzemeyi kullanıcıya sunacaktır. Böylelikle iç mekân tasarım süresince doğru malzemeyi araştırırken hem harcadığımız zaman birkaç saniyeye düşmüş olacak hem de geleneksel yöntemlerde olduğu gibi tecrübeye dayalı bir seçim süreci olmayacağından fikir karmaşası oluşturmayı tek bir seçim kaynağı haline gelmiş olacaktır. Teknolojinin hızlı ilerlemesi yalnızca mimari fikirleri sunma ve uygulama biçimlerini dönüştürmekle kalmamış aynı zamanda üretim ve tasarımda yeni olasılıklar ile verimlilik çağında başlatmıştır (Onat, 2025).

YÖNTEM

Yapay zekâ destekli arayüzün geliştirilmesinde kolay kullanım sağlaması ve hızlı sonuç verebilmesi nedeniyle Streamlit altyapısı kullanılmıştır. Streamlit, sadece Python kullanarak hızlıca interaktif web uygulamaları geliştirmesini sağlayan açık kaynaklı bir Python kütüphanesidir. Streamlit altyapısına Replit üzerinden erişilmiştir. Replit, program kurmaya gerek kalmadan herhangi bir tarayıcı üzerinden erişip kolayca üye olabileceğimiz ve hali hazırdaki kodu girip sonuç aldığımız bir platformdur. Streamlit altyapısını bu platformda kullanmak için ana sayfasında şablon olarak Streamlit'i seçmek yeterli olacaktır.

Tasarım süresi boyunca destek alacağımız yapay zekâ aracı olarak Google Gemini AI kullanılmıştır. Gemini bu sürecin düşünen beyni ve sonucu veren motoru olmuştur. Kod oluşturmak için Gemini'a malzemeler, kriterler ve kodun Streamlit altyapısına uygun olması gerektiği belirtilmiştir. Gemini'da oluşturulan kodu Replit'ta girdiğimizde arayüzümüz oluşmuş olacaktır. Kullanıcılar arayüzde seçtiği seçeneklere uygun malzeme önerisi istediğinde kod Replit'ten çıkıp Gemini'a gitmesi ve bir sonuç alması gerekmektedir. Tam bu noktada bir bağlantı aracına ihtiyaç duyulmuştur: API Key. API Key, Replit'ten çıkıp Gemini'a gidiş biletidir. Gemini düşünüp karar verip yanıtladığında oluşan sonuç arayüzde malzeme önerisi olarak sunulmuştur. İzlenilen bu süreç bir fikri bir ürüne dönüştürmenin en hızlı yoludur.

Geliştirilen sistem sonucunda oluşan Malzeme Seçim Sihirbazında mekân türü, bütçe aralığı, kullanım yoğunluğu ve stil tercihleri olmak üzere 4 temel girdi mevcuttur. Mekân türü, bir bireyin gün içerisinde kullanabileceği mekanlara göre belirlenmiştir. Ev odaları (oturma odası, mutfak, yatak odası, banyo, koridor), ofis odaları (toplantı odası, yönetici odası vs.), kafe, restoran, otel, mağaza, sergi alanı olarak farklı seçenekler kullanılmaktadır. Belirlenmiş olan malzemelerin herhangi bir bakanlık, başkanlık, kurul, enstitü gibi önemli makamlar tarafından yayınlanan güncel birim fiyat listesi bulunamamıştır. Bu sebeple malzeme üreticisi olan ünlü markalar referans alınarak her bir malzeme için ortalama fiyat çıkarılmıştır (Tablo 1). Kodda kullanılan malzemelerin ortalama birim (m²) fiyatları (TL) ve bu ortalama birim fiyatlarına ulaşılan markaları *Tablo 1*'de gösterilmektedir.

Bütçe kriterlerinin değerleri oluşturulurken sonuç için belirlenen malzemelerin birim (m²) fiyatları referans alınmıştır. Bu değerler düşük, orta, yüksek, çok yüksek seçenekleri olarak 4

INTERNATIONAL TOPKAPI CONGRESS VI

farklı kategoriye ayrıştırılmıştır. Kullanıcıların arayüzü kullanırken seçeneklerin daha anlaşılır olması açısından her bir seçenek için açıklama oluşturulmuştur (Tablo 2). Bütçe kategorisi, fiyat aralığı ve bu fiyat aralığına dahil olan malzemeler *Tablo2*'de gösterilmektedir. Kullanım yoğunluğu, mevcut mekânda aynı anda bulunabilecek kişi sayısı öngörülmüştür ve buna göre gruplandırılmıştır. Her mekân türünün yoğunluğuna yaklaşık olarak hitap edilebilmesi için çok düşük, düşük, orta, yüksek ve çok yüksek olmak üzere 5 temel seçenekler oluşturulmuştur. Bu seçenekler oluşturulurken 1 ila 20+ aralığında kişi sayısı baz alınmıştır (Tablo 3). *Tablo3*'te kullanım yoğunluğu seçeneklerini ve açıklamaları görebilirsiniz. Gemini'a "Malzeme seçim sihirbazı ile alakalı yapay zekâ uygulaması geliştirmek istiyorum ve bunu Streamlit uygulamasıyla yapmak istiyorum, bana bunun için kod yazabilir misin?" cümlesiyle birlikte *Tablo1*, *Tablo2*, *Tablo3*'teki bilgiler iletilmiştir. Bunun sonucunda Gemini bize kod oluşturacaktır.

Malzeme	Seramik	Porsele n	Granit	Mermer	Laminant Parke	Lambri Parke	Ahşap Döşeme	Vinil	Epoks i	Halı Karo
Ortalama Birim Fiyatı (m²)	850 TL	2200 TL	3400 TL	4800 TL	650TL	1200 TL	3800 TL	950 TL	1400 TL	1100 TL
Ürün Markası	Kütahy a Seramik	Kütahy a Seramik	Stoneline	Stoneline	Koçtaş	Bauhaus	Şerifoğl u Parke	Tarket t	Jotun	Tarket t

Tablo 1. Malzeme Birim Fiyatları ve Ürün Markaları Verileri

Bütçe Kategorisi	Fiyat Aralığı (m²)	Dahil Olan Malzemeler
Düşük (Ekonomik Çözümler)	900- TL	Laminant Parke (650 TL), Keramik (850 TL)
Orta (Fiyat-Performans)	900-1800 TL	Vinil (950 TL), Halı Karo (1100 TL), Lambri (1200 TL), Epoksi (1400 TL)
Yüksek (Uzun Ömürlü ve Estetik)	1800-3500 TL	Porselen (2200 TL), Granit (3400 TL)
Çok Yüksek (Prestij/ Premium)	3500+ TL	Ahşap Döşeme (3800 TL), Mermer (4800 TL)

Tablo 2. Bütçe Kategorisi, Fiyat Aralığı ve Eşdeğer Malzeme Verileri

Yoğunluk Seviyesi	Ortalama Kullanıcı Sayısı	Örnek Mekanlar
Çok Düşük (Bireysel/Özel Kullanım)	1-2 kişi	Yatak odası, yönetici ofisi, banyo
Düşük (Sınırlı Kullanıcı)	3-6 kişi	Oturma odası
Orta (Düzenli Kullanıcı Sirkülasyonu)	7-14 kişi	Toplantı odası, Açık ofis
Yüksek (Yoğun Kullanım)	15-20 kişi	Mağaza, restoran
Çok Yüksek (Kamusal/Sürekli Sirkülasyon)	20+ kişi	Lobi, resepsiyon

Tablo 3. Kullanım Yoğunluğu Sözel ve Sayısal Değerleri ve Eşdeğer Mekânlar

Kod sayfa yapılandırılması ve arayüz tasarımı, teknik malzeme veri tabanı, kullanıcı parametre girişleri, yapay zekâ karar mekanizması ve prompt mühendisliği, sonuç malzeme kartı tasarımı olmak üzere 5 ana bölümden oluşmaktadır. İlk bölümde uygulamanın temel ayarları ve sayfanın estetik tasarımı için oluşturulan kod yer almaktadır. 1.Bölüm kodu *Şekil 1*'de yer almaktadır. 2. Bölüm sonuçta çıkabilecek olan 11 malzemenin 2025 yılındaki güncel birim fiyatlarını, tedarikçi bilgilerini, suya ve darbe dayanımını barındıran kodu içermektedir. 2. Bölüm kodu *Şekil 2*' de gösterilmektedir. 3. Bölüm dahilinde mekân türü, bütçe aralıkları ve kullanım yoğunluğu *Şekil 3*' teki gibi yer almaktadır. 4. Bölüm sistemin beyni olup Gemini AI' ya bütçe ve teknik sınırları nasıl analiz demesi gerektiğini söylemektedir. Bu kısım *Şekil 4*'te yer almaktadır. Son bölümde ise sonuç malzeme çıktısı için tasarlanılan malzeme kart bilgileri yer almaktadır. Nihai kodun son bölümü *Şekil 5*' te gösterilmektedir.

INTERNATIONAL TOPKAPI CONGRESS VI

```
python

import streamlit as st
import google.generativeai as genai
import json
import os

# --- SAYFA AYARLARI VE MİNİMALİST TEMA ---
st.set_page_config(page_title="Malzeme Seçim Sihirbazı", layout="centered", page_icon="🏠")

st.markdown("""
<style>
    .stApp { background-color: #F0F8FF; }
    .notranslate { translate: no !important; }
    .main-title { color: #4682B4; font-weight: 300; text-align: center; font-family:
'Segoe UI', sans-serif; }
    .stButton>button {
        width: 100%; border-radius: 25px; background-color: #87CEEB;
        color: white; height: 3.5em; border: none; font-weight: 500;
    }
    .stButton>button:hover { background-color: #00BFFF; color: white; }
    .sub-text { text-align: center; color: #708090; margin-bottom: 20px; font-
weight: 400; }
    [data-testid="stSidebar"] { background-color: #E6F3FF; border-right: 1px solid
#B0C4DE; }
    .result-container { margin-bottom: 40px; padding: 20px; background-color: white;
border-radius: 15px; border: 1px solid #E6F3FF; }
</style>
""", unsafe_allow_html=True)

st.markdown("<h1 class='main-title'>Malzeme Seçim Sihirbazı</h1>", unsafe_allow_html=True)
st.markdown("<p class='sub-text'>Mimari Parametre Analizi ile Optimize Edilmiş Seçim Sistemi</
p>", unsafe_allow_html=True)
```

Şekil 1. Uygulama Ayarları ve Sayfa Tasarım Kodu

```
python

# --- TEKNİK VERİ TABANI ---
materials_db = {
    "Laminat Parke": {"price": 650, "ref": "Koçtaş / AGT", "url": "https://www.kocatas.com.tr",
"img": "laminat.jpg", "is_waterproof": False, "durability": "Düşük"},
    "Seramik": {"price": 850, "ref": "Vitra / Kütahya Seramik", "url": "https://
www.vitra.com.tr", "img": "seramik.jpg", "is_waterproof": True, "durability": "Orta"},
    "Vinil (LVT)": {"price": 950, "ref": "Tarkett", "url": "https://www.tarkett.com.tr",
"img": "vinil.jpg", "is_waterproof": True, "durability": "Yüksek"},
    "Halı Karo": {"price": 1100, "ref": "Tarkett", "url": "https://www.tarkett.com.tr", "img":
"hali.jpg", "is_waterproof": False, "durability": "Orta"},
    "Lambri": {"price": 1200, "ref": "Bauhaus", "url": "https://www.bauhaus.com.tr", "img":
"lambri.jpg", "is_waterproof": False, "durability": "Düşük"},
    "Epoksi": {"price": 1400, "ref": "Jotun", "url": "https://www.jotun.com", "img":
"epoksi.jpg", "is_waterproof": True, "durability": "Çok Yüksek"},
    "Beton": {"price": 1800, "ref": "Kalekim", "url": "https://www.kalekim.com", "img":
"beton.jpg", "is_waterproof": True, "durability": "Çok Yüksek"},
    "Porselen": {"price": 2200, "ref": "Bien / Kütahya Seramik", "url": "https://
bienseramik.com.tr", "img": "porselen.jpg", "is_waterproof": True, "durability": "Yüksek"},
    "Granit": {"price": 3400, "ref": "Hurok Marble", "url": "https://hurok.com.tr", "img":
"granit.jpg", "is_waterproof": True, "durability": "Çok Yüksek"},
    "Ahşap Döşeme": {"price": 3800, "ref": "Dendro Parke", "url": "https://dendro.com.tr",
"img": "ahsap.jpg", "is_waterproof": False, "durability": "Orta"},
    "Mermer": {"price": 4800, "ref": "Hurok Marble", "url": "https://hurok.com.tr", "img":
"mermer.jpg", "is_waterproof": True, "durability": "Yüksek"}
}
```

Şekil 2. Malzemeler ve Teknik Özellik Kodu

```
python

with st.sidebar:
    st.header("🏠 Proje Parametreleri")
    space = st.selectbox("Mekân Türü", ["Oturma Odası", "Mutfak", "Yatak Odası", "Banyo",
"Koridor", "Ofis", "Toplantı Odası", "Kafe", "Restoran", "Otel", "Mağaza", "Sergi Alanı"])
    budget_range = st.selectbox("Bütçe Aralığı", ["Düşük (0-900 tl)", "Orta (900-1800 tl)",
"Yüksek (1800-3500 tl)", "Çok Yüksek (3500+ tl)"])
    density = st.selectbox("Yoğunluk Seviyesi", ["Çok Düşük (1-2 kişi)", "Düşük (3-6 kişi)",
"Orta (7-14 kişi)", "Yüksek (15-20 kişi)", "Çok Yüksek (20+ kişi)"])
    style = st.selectbox("Tasarım Stili", ["Modern", "Minimalizm", "Klasik", "Lüks",
"Endüstriyel", "Rustik"])
```

Şekil 3. Kullanıcı Parametre Kodu

```
python

if st.button("Mimari Analizi Başlat"):
    # API Bağlantısı
    MY_API_KEY = "AI"
    genai.configure(api_key=MY_API_KEY)
    model = genai.GenerativeModel('gemini-1.5-flash')

    prompt = f"""
    Uzman bir iç mimar olarak şu kriterleri analiz et: Mekan:{space}, Bütçe:{budget_range},
    Yoğunluk:{density}, Stil:{style}.
    Kurallar:
    1. Seçilen malzemenin fiyatı bütçe aralığına tam uymalı.
    2. Islak hacimde su geçirmezlik zorunlu.
    3. Oturma odasında yüksek bütçede konforlu dokular seç.
    Yanıtı SADECE JSON formatında ver.
    """
```

Şekil 4. Gemini Bağlantı ve Kural Kodu

```
python

with st.spinner("Analiz ediliyor..."):
    try:
        response = model.generate_content(prompt)
        res_json = json.loads(response.text.strip().replace("```json", "").replace("```", ""))


        for key in ["asil", "alternatif"]:
            m_name = res_json[key]['isim']
            m_info = materials_db.get(m_name, {})
            st.markdown("<div class='result-container'>", unsafe_allow_html=True)
            img_col, txt_col = st.columns([1, 2])
            with img_col:
                if os.path.exists(m_info["img"]): st.image(m_info["img"])
            with txt_col:
                st.markdown(f"### {m_name}")
                st.info(f"{res_json[key]['neden']}")
                st.write(f"$ {m_info['price']} TL/m² | 📄 {m_info['ref']}")
            st.markdown("</div>", unsafe_allow_html=True)
    except Exception as e:
        st.error("Teknik hata oluştu.")
```

Şekil 5. Malzeme Kart Bilgileri Kodu


BULGULAR

Malzeme seçim sihirbazı şu şekilde çalışmaktadır: Kullanıcı Mekân Türü, Bütçe Aralığı, Yoğunluk Seviyesi ve Tasarım Stili kriterlerindeki kendisine uygun gördüğü seçeneği seçer ve Analizi Başlat butonuna basar. Böylece malzeme önerileri kullanıcıya sunulmaktadır. Veritabanında bulunan 11 malzemenin sonuç kartları Şekil 6'da ve malzeme seçim sihirbazı arayüzü Şekil 7'de yer almaktadır. Kullanıcı mekân, bütçe, yoğunluk, stil verilerini girer. Veriler sistemdeki 11 malzemenin birim fiyatı, su dayanımı, aşınma katsayısı ile eşleştirilir. Bu noktada Gemini devreye girerek teknik denetimi yapar. Öncelikle su dayanımı ve kullanım yoğunluğu gibi önemli teknik kriterlerini denetler ve uygun olmayan malzemeleri eler. Geriye kalan malzemeler arasından kullanıcının seçtiği bütçe aralığına uygun olan malzemeler asil ve alternatif olmak üzere belirlenilir. Analiz sonucu kod tarafından okunur, Replit'te öncesinde yüklenen görseller arasından belirlenen malzeme görselleri çekilir ve kart halinde kullanıcıya sunulur. Şekil 8'de bu anlatıma uygun örnek ve Şekil 8.1'de ise sonuç malzeme kartı gösterilmektedir. Kullanıcı deneyimi opsiyonları Şekil 9'da yer almaktadır.

INTERNATIONAL TOPKAPI CONGRESS VI




Şekil 6. Veritabanındaki Malzeme Kartları




Şekil 7. Malzeme Seçim Arayüzü


INTERNATIONAL TOPKAPI CONGRESS VI



Şekil 8. Örnek Kullanıcı Parametre Girdileri



Şekil 8.1. Örnek Kullanıcı Malzeme Önerileri



Şekil 9. Kullanıcı Parametre Opsiyonları ve Malzeme Önerileri

SONUÇ

Yapılan çalışma iç mekân tasarımında malzeme seçim sürecini desteklemektedir. Yapay zekâ teknolojisinin kullanıldığı malzeme seçim sihirbazı geleneksel yöntemlere kıyasla daha hızlıdır. Sistem kullanıcının girdiği bilgilere göre mekân türü kullanıcının bütçesi malzemenin bulunacağı mekânın kullanım yoğunluğuna ve stiline en uygun malzemeyi asil ve alternatif olmak üzere önermektedir.

Bu çalışmanın devamında malzeme verileri çoğaltılarak malzeme veri tabanı genişletilebilir. Mekân türü seçenekleri açık balkon, kapalı balkon gibi çeşitlendirilebilir. Kullanıcının isteğine bağlı olarak malzemeyi kullanacağı alanın metrekaresi yazılabilir ve sonuçta nihai bütçe belirtilebilir. İç mimarlık alanına daha çok hitap edebilmesi için mekân türünün yanı sıra mobilya çeşitleri içinde kriterler oluşturulabilir. Mobilyalarda kullanılan ahşap çeşitleri, doğal taş çeşitleri, polimer ve kumaş çeşitleri gibi seçenekler eklenilebilir. Önerilen malzemelerin görseli stile göre değişkenlik gösterebilir. Ek olarak arayüz bulunacak kriterler teknik ve estetik açıdan artırılabilir. Böylelikle tasarlanan karar destek sistemi daha çok kullanıcıya hitap edebilecektir. Bu çalışmanın sonucunda yapay zekâ teknolojisi her alanda olduğu gibi iç mimarlık alanında da etkili şekilde yer alabilmektedir.

KAYNAKLAR

Erbay, M., & Ulusoy, S. (2021). *Türkiye’de günümüz iç mimarlık eğitiminin sayısal verilerle analizi. Sanat ve Tasarım Dergisi*, 12, 1–9. <https://doi.org/10.29228/sanat.1>

Şen Bayram, A. K., Özgüven, Y., Yazar, N. E., Edgü, E., & Sağlam, S. S. (2024). Malzeme odaklı yapay zeka destekli bir tasarım süreci önerisi: Doğal malzemeden yapay zekâya. *Journal of Computational Design*, 5(2), 211–234. <https://doi.org/10.53710/jcode.1512903>

Merayo, D., Rodríguez-Prieto, A., & Camacho, A. M. (2019). Comparative analysis of artificial intelligence techniques for material selection applied to manufacturing in Industry 4.0. *Procedia Manufacturing*, 41, 42–49. <https://doi.org/10.1016/j.promfg.2019.07.027>

Liu, Y., Xu, B., Feng, J., & Wu, P. (2025). Analysis of the application of generative artificial intelligence in interior design education. *Ain Shams Engineering Journal*, 16(12), 103757. <https://doi.org/10.1016/j.asej.2025.103757>

Yıldırım, B., & Demirarslan, D. (2020). İç Mimarlıkta Yapay Zekâ Uygulamalarının Tasarım Sürecine Faydalarının Değerlendirilmesi. *Humanities Sciences*, 15(2), 62-80.

Öztürk, K., & Şahin, M. E. (2018). Yapay sinir ağları ve yapay zekâ'ya genel bir bakış. *Takvim-i Vekayi*, 6(2), 25-36.

Narin, O. N. A. T., & ALUÇLU, İ. (2025). Mimarlıkta Kullanılan Dijital Teknolojilerin Yapısal Dönüşümü: Mevcut Durum ve Fırsatlar. *ULUSLARARASI AKADEMİK BİRİKİM DERGİSİ*, 8(4).

ENHANCING STUDENTS' SPEAKING CONFIDENCE IN THE ENGLISH CLASSROOM

Natalia Bolgari, University Lecturer, Academy of Economic Studies of Moldova,
ORCID ID: 0000-0002-8258-5035

Ina Andoni, University Lecturer, Academy of Economic Studies of Moldova,
ORCID ID: 0000-0001-8482-7299

ABSTRACT

Speaking confidently is a crucial component of learning the English language, even though it is one of the most challenging abilities for many students. Students frequently struggle with anxiety, a fear of making mistakes, and a lack of practice opportunities, all of which have a detrimental impact on their capacity for effective communication. This article explores pedagogical and practical methods that educators can employ to boost students' self-assurance when speaking English. First of all, it emphasizes how crucial it is to establish a classroom atmosphere that is encouraging and judgment-free so that students feel comfortable expressing themselves. Positive reinforcement, courteous communication, and clear expectations all aid in lowering anxiety and promoting involvement.

The article also looks at communicative teaching strategies that encourage practice of active speaking. Students can speak in relevant, stress-free situations through activities like role-plays, information-gap assignments, pair and group discussions, and brief presentations. The assignments allow students to experiment with language in a group environment while progressively increasing fluency. Weaker learners can benefit even more from structured preparation time and sentence starters. The importance of feedback in boosting confidence is also covered in the article. Teachers are urged to emphasize students' strengths, recognize their progress, and make specific recommendations that help them improve without becoming discouraged rather than concentrating on mistakes. Self-evaluation and peer reflection are examples of formative assessment that can enable students to take charge of their speaking development.

Finally, technology is mentioned as an additional means of enhancing self-confidence. Through digital platforms, voice-recording software, and online speaking partners, students can track their progress over time and get more practice outside of the classroom. These tools can reduce performance pressure by letting students practice in private before public speaking.

Overall, improving students' speaking confidence requires a combination of emotional support, engaging communicative activities, constructive feedback, and strategic use of technology. When these elements are integrated effectively, learners become more motivated, fluent, and self-assured speakers of English.

Key words : confidence, speaking skills, English classroom, communication, motivation, anxiety reduction, feedback, communicative activities.

INTRODUCTION

In modern English language pedagogy, oral communication plays a major role, especially in instructional paradigms that prioritize communicative skills and real-world language use. The capacity to communicate successfully in spoken English has become crucial for students in a variety of educational environments as global mobility and intercultural engagement continue to rise. Speaking is seen in many classrooms as an essential technique for communicating ideas,

negotiating meaning, and engaging with confidence in social, professional, and academic contexts rather than just as a language exercise.

Even though it is crucial, speaking is one of the most difficult skills for language learners to master. Numerous students show hesitation to engage in oral activities due to the fear of making errors, anxiety about negative evaluations from peers, limited vocabulary, or a general lack of confidence in their language skills. These emotional obstacles often result in speaking anxiety, decreased willingness to communicate, and a tendency to avoid oral tasks. Such difficulties underscore the necessity for targeted teaching approaches that address not only language skills but also the psychological and emotional aspects of speaking performance.

Even though students might have sufficient knowledge of grammar and comprehension abilities, many still lack the confidence needed for verbal communication in English. This deficiency in speaking confidence hinders the growth of communicative competence, as hesitant or anxious students are less inclined to take risks, start conversations, or participate actively in class discussions. As a result, the educational setting may not provide the continuous oral practice essential for language advancement. This article addresses the ongoing disparity between learners' language capabilities and their actual willingness or capability to speak English confidently.

This article aims to investigate and evaluate teaching methods that can successfully boost students' confidence in speaking within the English classroom. It seeks to delve into both theoretical concepts and practical techniques that cultivate a nurturing learning atmosphere, minimize anxiety associated with speaking, and encourage active involvement in oral communication activities. The discussion focuses on elements such as classroom environment, teaching strategies, feedback methods, and student motivation, highlighting research-supported practices that educators can adopt in various educational contexts.

This subject holds significant importance for educators, curriculum developers, and language policy makers aiming to enhance the effectiveness and results of English language teaching. Recognizing the elements that affect speaking confidence—and the teaching methods that enhance it—can guide the creation of more learner-focused curricula, educator training initiatives, and classroom strategies. This article enhances ongoing efforts to cultivate communicative competence by emphasizing successful methods for boosting students' confidence, ensuring they acquire the oral communication skills necessary for success in the twenty-first century.

CONCEPTUAL STRUCTURE OF SPEAKING CONFEDENCE

Speaking confidence can be seen as a complex concept that includes learners' perceptions of their speaking skills, their emotional preparedness for oral communication, and their ability to cope with possible language mistakes. In second language acquisition, speaking confidence is directly related to self-efficacy—how learners view their ability to successfully carry out speaking tasks. Elevated levels of speaking confidence often align with a higher readiness to engage, enhanced involvement in spoken tasks, and better overall performance. On the other hand, low self-confidence can result in avoidance actions, indecisiveness, and fewer chances to enhance communicative skills.

Confidence in speaking is frequently characterized by three main dimensions: *cognitive*, *affective*, and *behavioral*. The cognitive aspect encompasses learners' assessments of their capability to use language correctly; the affective aspect pertains to feelings like anxiety or unease; and the behavioral aspect focuses on learners' noticeable participation in communication activities. Comprehending these dimensions enables educators to pinpoint particular obstacles and customize teaching methods accordingly.

Multiple theoretical frameworks offer understanding regarding the growth of speaking confidence among language learners.

Social Constructivist Theory highlights how interaction and collaborative learning influence learner confidence, proposing that significant communication with peers and educators enhances both skill development and emotional growth. **Krashen's Affective Filter Hypothesis** emphasizes the role of emotional factors—like anxiety, motivation, and self-esteem—in language learning, suggesting that learners with reduced affective filters are better able to absorb language input and more eager to speak.

Furthermore, **Bandura's Self-Efficacy Theory** provides a valuable perspective on how learners' perceptions of their speaking skills impact their performance.

This theory suggests that self-efficacy is influenced by elements like past achievements, watching peers, verbal support, and emotional conditions.

Collectively, these frameworks highlight the significance of establishing environments that bolster learners both psychologically and linguistically.

Elements Affecting Students' Speaking Confidence

The confidence of learners in speaking English is influenced by a complex interaction of linguistic, emotional, environmental, and cultural elements:

- ✓ **Linguistic Factors.** A restricted vocabulary, inadequate grammatical understanding, and challenges with pronunciation can impede learner's capacity to communicate effectively, resulting in feelings of insecurity during speaking activities. When students notice deficiencies in their language skills, they might refrain from engaging or depend on brief replies.
- ✓ **Affective Factors.** Emotional factors like anxiety, fear of errors, low self-worth, and negative previous experiences greatly influence speaking confidence. Numerous students encounter "foreign language anxiety," which can hinder cognitive processing and decrease involvement in speaking activities.
- ✓ **Classroom Environment.** The classroom environment, encompassing teacher behavior, relationships among peers, and established norms, significantly influences students' readiness to express themselves. Encouraging spaces that promote risk-taking often build higher confidence, whereas excessively critical or competitive settings can increase anxiety.
- ✓ **Cultural expectations.** In certain cultures, students might be taught to emphasize correctness over communication or to shy away from making mistakes in public, resulting in increased self-awareness when conversing in a second language. Such cultural norms may affect students' willingness to engage in communicative activities.

Recognizing speaking confidence as a fluid and context-sensitive concept highlights the importance of teaching methods that cater to the emotional and linguistic requirements of students. Incorporating understandings from theoretical viewpoint and recognizing the various elements that affect learners' confidence allows educators to improve instructional strategies that encourage active involvement, diminish anxiety, and enhance efficient oral communication.

Creating a Positive and Confidence-Enhancing Classroom Environment

A supportive classroom setting is an essential requirement for boosting students' confidence in speaking English. An environment like this is defined by mutual respect, psychological safety, and well-defined expectations that encourage active involvement. Educators are vital in fostering an environment where mistakes are seen as normal and beneficial parts of the educational journey instead of failures. When students believe that their efforts to communicate will receive understanding instead of criticism, they are more likely to take risks, try out language, and participate in conversations. Fostering this feeling of safety includes developing routines that promote interaction, like organized pair and group activities, and enforce-

ing classroom standards that highlight respect, turn-taking, and active listening. A stable and welcoming atmosphere can lower students' uncertainty and assist them in building the confidence necessary to participate in class discussions.

The actions of teachers greatly affect students' emotional reactions to speaking assignments. Educators who exhibit empathy, patience, and support reduce students' anxiety about failure and foster a more favorable outlook on oral communication. Successful educators recognize the unique obstacles that students encounter while learning a second language and take a supportive, instead of a commanding, approach.

Confidence-boosting behaviors involve delivering consistent positive reinforcement, acknowledging students' attempts irrespective of correctness, and giving encouraging verbal and non-verbal responses. Educators with a friendly and supportive attitude diminish the emotional gap with their students, fostering a better atmosphere for taking risks. Additionally, educators can exemplify confident speaking, establishing a benchmark for students and showing that effective communication outweighs linguistic accuracy. Considering the vital influence of anxiety on hindering oral performance, intentional teaching methods are essential to assist learners in handling and alleviating stress related to speaking. A useful strategy is to start with low-pressure speaking tasks that enable students to engage in a more relaxed way. These tasks can involve discussions in pairs, brief exchanges of information, and collaborative problem-solving exercises that emphasize meaning over form.

Warm-up exercises, including pronunciation practices, vocabulary generation, or basic conversation starters, can assist in acclimating learners to more challenging speaking assignments by progressively enhancing their comfort. Moreover, integrating relaxation methods — like short breathing exercises or moments of reflection — can assist in alleviating physical symptoms of anxiety prior to important speaking engagements.

An additional crucial approach includes providing students with a certain level of choice and freedom in choosing speaking subjects or methods of delivery. Permitting students to discuss topics they know well or to create their own prompts can reduce anxiety by providing them with a feeling of control over the content and structure of their speaking activities.

A classroom environment that builds confidence is not just influenced by teacher behavior; it also requires promoting encouraging relationships among peers. Promoting student collaboration, offering constructive criticism, and acknowledging each other's successes fosters a more positive social atmosphere. Peer assistance can alleviate the anxiety of negative assessment and foster a feeling of shared accountability for learning. To nurture this environment, educators can utilize organized collaborative learning tasks that encourage positive interdependence, including group assignments, role-playing activities, or peer instruction sessions.

TEACHING APPROACHES TO BOOST SPEAKING CONFIDENCE

- **Step-by-step teaching progression** A successful method for boosting learners' speaking confidence is the use of a well-organized, scaffolded teaching sequence. This entails moving from tightly regulated tasks to more flexible, interactive activities as learners develop their language skills and emotional preparedness. Managed tasks-like organized discussions, repetition exercises, or directed practice—offer students essential language assistance and lessen the mental effort related to impromptu speaking. As students gain confidence in their skills, educators can implement semi-structured tasks, such as role-plays with cues, information-gap exercises, and directed discussions, which promote increased independence while still providing some level of organization. Unrestricted production activities, like discussions, presentations, interviews, and sharing opinions, enable students to apply their language abilities in more genuine situations. Through a gradual release approach, educators support students in developing confidence step by step, making sure that the speaking challenges correspond with their growing skills and self-esteem.

- **Collaborative Learning Frameworks** Collaborative learning is often viewed as a strong way to enhance speaking confidence. Pair and group activities alleviate the stress of speaking in front of the whole class and provide chances for students to use language in a supportive, engaging environment. These frameworks encourage peer-to-peer support, enabling students to gain insights from each other's language skills and techniques. Tasks like *think-pair-share*, *jigsaw activities*, *peer interviews*, and *collaborative problem-solving* promote ongoing communication and assist students in building fluency through regular, low-pressure interactions. Small group environments also promote a fairer allocation of speaking turns guaranteeing that every learner has sufficient chances to share their thoughts. Gradually, regular involvement in group activities enhances learners' confidence by making speaking a collective, not solo, responsibility.
- **Language Activities for Communication** Incorporating communicative activities into classroom routines is crucial for building learners' confidence in speaking. These activities focus on meaning rather than form and generate real situations where learners are required to use English to reach communicative objectives. *Role-plays*, for example, allow students to explore various social roles and language functions, which helps to diminish the anxiety linked to personal self-expression. *Debates* and *panel discussions* foster critical thinking and compel learners to express arguments clearly, boosting both confidence and language skills. Additional impactful activities consist of *simulations*, *storytelling*, *drama-related tasks*, and *interviews*, all of which encourage creativity and participation. As these activities replicate genuine communication situations, they aid students in building not just linguistic skills but also pragmatic understanding and communicative resilience. The genuineness of these tasks frequently results in increased motivation, which subsequently enhances the desire to engage.
- **Integration of Digital Tools** The strategic implementation of digital resources can greatly boost students' speaking confidence by providing chances for repeated practice, self-assessment, and multimodal interaction. Audio and video recording apps enable learners to capture their speech, assess their performance, and track their improvement over time. This self-reflection enables students to recognize their strengths and weaknesses, leading to enhanced self-efficacy. Digital speaking platforms, online discussion groups, and language-learning apps offer extra opportunities for practice beyond the classroom, allowing students to engage with other learners or native speakers in a more comfortable setting. Multimedia tools like video cues, interactive narratives, and digital role-playing scenarios—further enhance a more vibrant and captivating speaking experience. Additionally, technology enables personalized instruction by permitting students to work at their own speed and review assignments when required. Integrating digital tools into classroom activities allows teachers to establish more adaptable and inclusive learning environments that enhance students' confidence and promote regular spoken communication.

Developing Speaking Sub-Skills to Improve Confidence

A **solid vocabulary base** is crucial for boosting learners' confidence in speaking. When students have a sufficient vocabulary and useful expressions, they are more capable of communicating meaning accurately and coherently. Educators can facilitate this growth by providing thematic vocabulary lists, common phrases, and idiomatic expressions associated with imminent speaking activities. Teaching helpful phrases in advance—like those for agreement, disagreement, asking for clarification, or sharing opinions—can minimize hesitation and help learners participate more smoothly in discussions. Moreover, organized exercises that promote active vocabulary engagement, like semantic mapping, categorization tasks, and context-based applications, can assist students in internalizing new language concepts.

Teachers assist in reducing the anxiety associated with not knowing what to say by equipping learners with the necessary lexical and functional tools for communication, which in turn boosts their speaking confidence.

Pronunciation significantly affects learners' views of their own communication skills. Challenges with pronunciation can result in misunderstandings, which may subsequently diminish learners' eagerness to communicate. Nonetheless, effective instruction in pronunciation doesn't have to concentrate on removing an accent; instead, it should emphasize intelligibility, motivating learners to articulate clearly and be comprehensible to others. Educators can integrate focused exercises like minimal pair drills, stress and intonation practice, back-chaining, and choral repetition to assist students in improving their sound production and prosodic elements. Incorporating pronunciation practice into communicative activities—instead of treating it separately—allows students to use their newly learned pronunciation abilities in relevant situations. When students find it easier to be understood, their confidence in speaking tends to rise naturally.

Fluency serves as an essential aspect of speaking skills and greatly impacts learners' confidence. Proficient speakers articulate thoughts with fewer interruptions and less mental strain, enhancing the overall speaking experience. To enhance fluency, educators can adopt strategies like timed speaking, during which students discuss a familiar subject for a specific duration, progressively extending the time as they gain confidence. This assists learners in building automaticity and lowering dependence on translation or mental practice. Performing speaking tasks multiple times is an effective approach. When students engage in the same or comparable speaking tasks repeatedly—like narrating a story or depicting an image—they usually gain fluency with each iteration, since cognitive pressures decrease and language structures become more recognizable. Organized speaking frames or sentence beginnings can aid learners by offering a structure that arranges their thoughts and diminish the mental effort required for spontaneous language production. Through the systematic incorporation of fluency-enhancing methods into the curriculum, educators allow students to engage in more natural and prolonged speech, which in turn boosts their confidence and eagerness to take part in verbal communication.

Although lexical, pronunciation, and fluency abilities can be tackled separately, they produce the greatest effect when combined in relevant communicative tasks. Creating assignments that incorporate these sub-skills—like role-plays that utilize specific vocabulary, group discussions focusing on stress and intonation, or storrtelling exercises that encourage repetitive practice—helps learners build confidence through genuine language application. This comprehensive method enables students to understand the direct importance of sub-skill enhancement for achieving their communication objectives. As students observe concrete advancements in their capacity to communicate clearly and effectively, they tend to see speaking as a feasible and gratifying activity, thereby enhancing their overall confidence in speaking.

Feedback Systems that Encourage Positive Speaking Experiences

Self-Assessment Practices Self-evaluation is crucial in assisting students in fostering independence, metacognitive insight, and self-assurance in speaking. By participating in reflective practices—like keeping speaking journals, filling out self-assessment checklists, or reviewing their own audio and video recordings—students develop a better understanding of their strengths and improvement areas. This method helps learners identify progress that might not be obvious right away, thus enhancing their feeling of accomplishment. Self-evaluation also prompts students to establish achievable and individualized objectives for upcoming speaking assignments, which boosts motivation and cultivates a growth-focused atti-

tude. Transferring part of the evaluation responsibility from the teacher to the student, self-assessment enables learners and fosters a more assured and engaging attitude towards oral communication.

Peer Feedback Peer feedback serves as an effective tool for boosting speaking confidence when applied in a well-organized and encouraging way. When colleagues provide constructive criticism, learners gain from varied viewpoints and enhance their understanding of the communication techniques employed by their peers. For peer feedback to be beneficial, students need to be educated in applying clear, objective standards and in delivering remarks that are both supportive and practical. Organized peer feedback tasks—like structured observation forms, joint assessment sheets, and criterion-focused dialogues—help to keep feedback centered on particular elements of performance, including clarity, structure, or application of target vocabulary. Constructive peer encouragement can greatly diminish students' anxiety about negative judgment and promote a collaborative environment of support. Moreover, watching the strengths of peers can act as a blueprint for learners' personal development, enhancing their self-esteem.

Teacher Feedback Teacher feedback may be the most significant factor in determining students' confidence in speaking. Educators need to strike a balance between constructive criticism and support, making sure that their remarks foster growth while preserving students' self-worth. Timely, specific, and constructive feedback from teachers effectively guides students to improve their performance while recognizing their efforts and advancements. In fluency-centered speaking exercises, it is frequently advised to use delayed or selective error correction to avoid disrupting communication flow or increasing anxiety. Conversely, quicker feedback might be suitable during tasks centered on accuracy. Educators ought to emphasize the strengths demonstrated by students prior to discussing areas needing enhancement, presenting feedback in a way that encourages ongoing experimentation and engagement. Non-verbal cues—like nodding, smiling, and keeping an engaged posture—are also crucial in expressing support during verbal activities. These gestures can support verbal praise and contribute to forming a positive communication atmosphere that enhances learners' self-assurance.

Integrating Feedback into Instructional Processes

Feedback is most beneficial when it becomes part of continuous instructional processes instead of being given as a singular occurrence. Incorporating self-assessment, peer reviews, and teacher evaluations into the design and implementation of speaking tasks allows educators to establish an ongoing framework for reflection, enhancement, and support. A speaking task might start with presenting performance criteria, then include peer collaboration, teacher observation, and reflection after the task. This repetitive method assists learners in embracing feedback as a standard and beneficial aspect of the learning journey, instead of viewing it as a source of criticism or stress. Consistent and constructive feedback over time leads to better performance, increased self-awareness, and greater confidence in speaking.

Encouraging Motivation and Self-Belief

Motivation and self-efficacy are deeply connected and greatly affect learners' readiness to engage in oral communication. An effective approach for improving these emotional aspects is to engage students in goal-setting activities that foster independence and personalized education. When students establish specific, achievable speaking objectives—like participating at least once in a discussion, incorporating newly acquired vocabulary in dialogue, or enhancing the pronunciation of particular sounds—they develop a feeling of direction and responsibility for their learning journey. Educators can assist in this process by helping students create SMART goals (Specific, Measurable, Achievable, Relevant, and Time-bound) and by promoting regular reflection on achieving those goals. Practices that support autonomy, like per-

mitting students to select topics, formats, or partners for speaking tasks, enhance intrinsic motivation even more. When students perceive they have control over their learning, their involvement, determination, and self-assurance naturally rise.

Consistent tracking and visual displays of students' progress can act as strong motivators and enhance their confidence. Instruments like speaking portfolios, audio recordings, progress graphs, rubrics, and self-reflection journals offer tangible proof of growth over time. Through reviewing past recordings or written notes, students can notice their growth in fluency, clarity, and expression—advancements that might go unnoticed during regular classroom exchanges. Educators can also hold regular one-on-one meetings to talk about students' strengths and developing skills. These conversations make advancement apparent and significant, strengthening learners' confidence in their capacity to enhance. When progress is consistently recorded and acknowledged, students build greater self-efficacy, leading to an increased readiness to engage in upcoming speaking activities.

Acknowledging students' efforts and achievements is another crucial element in enhancing motivation and confidence. Positive reinforcement, be it through verbal commendations, certificates, classroom exhibitions, or performance highlights, affirms students' growth and fosters ongoing participation. Acknowledgment shouldn't be confined to top students; appreciating progress, effort, and determination fosters an inclusive atmosphere where every learner can achieve success. Additionally, public acknowledgment—like showcasing a successful group role-play or delivering a polished presentation—can exemplify effective communication and motivate fellow learners. Nonetheless, this acknowledgment must be managed carefully to prevent fostering rivalry or stress. When applied carefully, recognition methods foster a feeling of accomplishment that encourages students to tackle new challenges with increased assurance.

To sustainably cultivate motivation and self-efficacy, it is essential to inspire learners to embrace a growth mindset, the conviction that skills evolve through practice and effort instead of being innate characteristics. Educators can foster this mindset by highlighting advancement rather than flawlessness, applauding hard work instead of natural ability, and presenting obstacles as chances to learn. Classroom dialogue significantly impacts the development of learners' beliefs. Educators who demonstrate resilience, admit their own errors, and encourage gradual development contribute to diminishing the fear of failure that frequently hinders speaking. Incorporating reflective questions like “What did I enhance today?” or “Which strategy aided my confidence in speaking?” into classroom activities strengthens students' belief that development is ongoing and achievable. As students more fully embrace a growth mindset, their motivation intensifies, and their self-assurance in speaking enhances, preparing them for greater involvement in communicative activities.

Real-Life Examples and Educational Situations

Practical examples offer important insights into how theoretical and educational principles can be applied effectively in classroom settings. The subsequent examples illustrate methods that have been effectively applied to boost students' speaking confidence in various educational environments.

Guided Role-Plays

In an upper-intermediate English classroom, the instructor executed a structured role-play cycle centered around common communication situations like making requests, offering advice, and sharing opinions. Before the activity, students received practical phrases, sample conversations, and a brief review of pronunciation. They trained in pairs, initially utilizing formal scripts and then progressively modifying them for more natural conversations. As students' comfort increased, the teacher presented additional open-ended situations that necessitated the negotiation of meaning. Students indicated a greater readiness to engage in speaking, crediting their assurance to the encouraging support and structured nature of the activity.

Reflective Video Journals

In another context, students created weekly video journals in which they discussed topics of personal relevance, such as hobbies, cultural experiences, or academic goals. These recordings were not graded for linguistic accuracy but were used for self-assessment and reflection. Students reviewed their earlier videos at regular intervals and noted improvements in fluency, pronunciation, and expressive range. This longitudinal process helped them recognize incremental progress, thereby enhancing their self-efficacy and reducing anxiety associated with speaking in front of others.

Collaborative Problem-Solving Tasks

A high school English class included cooperative problem-solving activities, like organizing a community event, tackling ethical issues, or creating a class project. In small groups, students explored potential solutions, allocated roles, and showcased their final proposals to the class. These assignments promoted active engagement, with every student adding their distinct input to the group's goals. The collective accountability diminished personal stress, fostered chances for mutual support, and encouraged genuine dialogue—all of which played a key role in boosting speaking confidence.

Observed Outcomes

Throughout these interventions, multiple consistent results were noted, supporting the findings of the conceptual and theoretical discussion outlined earlier in the article.

1. Increased Participation Students participated more eagerly and often in speaking activities. Even learners who were previously reluctant showed increased willingness to speak when tasks were supported, cooperative, and connected to their real-life experiences.

2. Improved Fluency and Clarity Repetition, purposeful practice, and thoughtful self-reflection led to noticeable improvements in fluency and pronunciation. Students progressively created longer expressions with fewer interruptions and enhanced assurance in their presentation.

3. Enhanced Self-Efficacy and Motivation Students expressed increased confidence in their speaking skills, especially when they could observe progress through recordings, feedback, or successful task completions. Positive experiences enhanced motivation and diminished anxiety related to speaking.

4. Strengthened Peer Relationships Joint activities resulted in enhanced peer support systems in the classroom. Participants gained confidence in each other's feedback and fostered a shared sense of accomplishment, further enhancing a supportive educational atmosphere.

These concrete examples highlight the efficacy of integrating organized scaffolding, reflective instruments, genuine communication activities, and peer cooperation into speaking education. The results show that when students are given supportive environments and chances for meaningful practice, their confidence in speaking grows steadily and sustainably. These scenarios provide specific illustrations of how the pedagogical strategies mentioned previously in the article can be applied to attain substantial enhancements in learners' oral communication abilities.

CHALLENGES AND EDUCATIONAL CONSIDERATIONS

Institutional and Curriculum Constraints - A major obstacle to improving students' speaking confidence lies in the structural and institutional constraints found in various educational environments. High student numbers, time limitations, and curricula that favor written tests over communication skills frequently limit chances for significant verbal practice. Educators might struggle to incorporate student-focused activities, like debates, role-plays, or extensive group discussions, when class timetables are overcrowded or evaluation methods prioritize grammar and vocabulary precision over fluency. To overcome these limitations, educators need to implement inventive task creation and time-saving approaches. Brief,

targeted speaking tasks can be integrated into lessons, and teamwork can enhance engagement without needing extra class time. Moreover, coordinating speaking tasks with curriculum objectives guarantees that confidence-fostering activities align with evaluation standards, fostering a more viable and lasting strategy.

Learner Diversity - Variability among learners, like divergences in skill levels, approaches to learning, individual characteristics, and cultural contexts, represents an additional challenge. Introverted or extremely anxious students might find it difficult to perform tasks that involve speaking publicly, while advanced students may lose interest if they see activities as overly repetitive or too simple. Cultural norms may also affect the readiness to speak, as certain students could be trained to shy away from risk-taking or making mistakes in public during learning situations. Educators can address learner diversity by tailoring instruction and offering adaptable participation choices. Approaches can consist of tiered activities, heterogeneous groupings, different speaking formats (partner work, small groups, or whole-class conversations), and tailored assistance for learners needing extra help. Acknowledging personal differences and adjusting teaching methods accordingly is crucial for building confidence among all learners.

Teacher Preparedness - The effectiveness of confidence-building initiatives significantly depends on teacher skills and ongoing professional training. Not every educator might feel prepared to handle communicative, student-focused activities, especially if they are used to conventional, lecture-driven teaching. Inadequate training in methods like scaffolding, delivering constructive feedback, addressing classroom anxiety, or integrating technology may hinder the success of speaking confidence programs. To address these barriers, organizations should offer specialized professional training that emphasizes communicative teaching methods, emotional support techniques, and the implementation of digital resources. Peer observation, mentoring, and ongoing reflective practices can improve teacher preparedness, making certain that classroom interventions are carried out effectively and sustainably.

Balancing Accuracy and Fluency - Another teaching consideration entails finding a balance between precision and fluency in speaking exercises. Overemphasizing linguistic precision can increase learners' stress, leading to less willingness to take risks and diminished involvement. On the other hand, concentrating exclusively on fluency without considering accuracy might reinforce erroneous structures and hinder effective communication. Effective classroom techniques include situational and task-relevant feedback, focused error correction, and thoughtful planning of activities that aim at both fluency and accuracy throughout various stages of learning. By sustaining this equilibrium, educators foster a setting that encourages both skill and assurance in verbal communication. Despite various challenges, as institutional limitations, learner diversity, teacher readiness, and pedagogical equilibrium, these obstacles can be overcome. Through strategic planning, reflective practice, and an emphasis on learner-centered methods, educators can establish environments that enhance ongoing speaking confidence growth. Identifying and actively tackling these issues is crucial for the effective execution of the teaching strategies discussed in previous sections.

CONCLUSION

In conclusion, boosting students' speaking confidence is an essential factor in fostering overall communicative proficiency. Research and classroom experience indicate that students gain the most when educators apply various strategies, such as fostering a positive classroom atmosphere, offering scaffolding via incremental task progression, encouraging teamwork, enhancing sub-skills, and giving constructive feedback. Equally significant are aspects such as motivation and self-efficacy, which inspire learners to take risks, participate actively, and continue in the face of difficulties. Classroom strategies like guided role-plays, reflective journals, and collaborative problem-solving show that confidence can be gradually de-

veloped. Motivation and self-efficacy are also crucial, as they inspire learners to take risks, participate actively, and continue striving in the face of difficulties. Effective classroom practices like structured role-plays, reflective writing, and teamwork in problem-solving show that confidence can be intentionally developed. By carefully combining these teaching methods, educators can assist students in enhancing their English speaking abilities while also fostering the confidence and independence needed to communicate successfully in real-life situations.

REFERENCES

1. Bandura, A. (1997). *Self-efficacy: The exercise of control*. New York, NY: W. H. Freeman.
2. Brown, H. D. (2007). *Teaching by principles: An interactive approach to language pedagogy* (3rd ed.). White Plains, NY: Pearson Longman.
3. Dörnyei, Z. (2005). *The psychology of the language learner: Individual differences in second language acquisition*. Mahwah, NJ: Lawrence Erlbaum.
4. Ellis, R. (2003). *Task-based language learning and teaching*. Oxford, UK: Oxford University Press.
5. Krashen, S. D. (1982). *Principles and practice in second language acquisition*. Oxford, UK: Pergamon.
6. Littlewood, W. (2004). *The task-based approach: Some questions and suggestions*. *ELT Journal*, 58(4), 319–326. <https://doi.org/10.1093/elt/58.4.319>
7. MacIntyre, P. D., & Gardner, R. C. (1991). Methods and results in the study of anxiety and language learning: A review of the literature. *Language Learning*, 41(1), 85–117.
8. Nation, I. S. P., & Newton, J. (2009). *Teaching ESL/EFL listening and speaking*. New York, NY: Routledge.
9. Oxford, R. (1990). *Language learning strategies: What every teacher should know*. Boston, MA: Heinle & Heinle.
10. Ur, P. (2012). *A course in language teaching: Practice and theory* (2nd ed.). Cambridge, UK: Cambridge University Press.

YAPAY ZEKÂNIN İŞLETMELERİN GELİŞİMİNDE ROLÜ VE KULLANIM ALANLARI

THE ROLE OF ARTIFICIAL INTELLIGENCE IN THE DEVELOPMENT OF BUSINESSES AND AREAS OF USE

Nurten GÖKYİĞİT ZENGİN

Dumlupınar Üniversitesi, Lisansüstü Eğitim Fakültesi,
Teknoloji ve İnovasyon Yönetimi Bölümü, Kütahya, Türkiye
ORCID NO: 0009-0008-7550-9422

Prof. Dr. Arif GÖK

Dumlupınar Üniversitesi, Mimarlık Fakültesi,
Endüstriyel Tasarım Bölümü, Kütahya, Türkiye
ORCID NO: 0000-0003-2840-9601

ÖZET

Yapay zekâ, insanın öğrenme, düşünme ve problem çözme gibi bilişsel süreçlerini bilgisayar sistemleri aracılığıyla taklit etmeyi ve geliştirmeyi amaçlayan bilişim teknolojilerinin bütünüdür. Son yıllarda hızlı bir gelişim gösteren bu teknoloji, yalnızca teknik bir yenilik olarak değil, aynı zamanda işletmelerin dijital dönüşüm süreçlerini yönlendiren stratejik bir unsur olarak değerlendirilmektedir. Özellikle büyük veri analitiği, otomasyon ve karar destek sistemleri sayesinde yapay zekâ, yönetsel kararların daha hızlı, tutarlı ve veriye dayalı biçimde alınmasına katkı sağlamaktadır. Günümüzde işletmelerde, yapay zekânın pazarlama, insan kaynakları, tedarik zinciri yönetimi, finans ve operasyonel süreçler gibi pek çok alanda etkin biçimde kullanıldığı görülmektedir. Bu alanlarda yapay zekâ çözümleri, süreçlerin daha verimli hale getirilmesine, maliyetlerin azaltılmasına ve müşteri deneyiminin iyileştirilmesine olanak tanımaktadır. Reel sektördeki uygulamalar ve yapılan çalışmalar, bu kazanımların işletmelere sürdürülebilir rekabet avantajı sağladığını ortaya koymaktadır. Bununla birlikte, yapay zekâ uygulamalarının yaygınlaşması bazı önemli riskleri de beraberinde getirmektedir. Veri güvenliği ve gizliliği, etik sorumluluklar, çalışanların iş yapma biçimlerinin değişmesi ve yöneticilerin bu dönüşüme gösterdiği direnç, dikkatle ele alınması gereken konular arasında yer almaktadır. Bu noktada bilimsel çalışmalar, insan ve yapay zekânın birbirini tamamladığı hibrit yönetim ve liderlik modellerinin geleceğin işletmeleri için kritik olacağını ortaya koymaktadır. Sonuç olarak yapay zekâ, işletmelerin yenilik kapasitesini artıran ve uzun vadeli büyüme stratejilerini şekillendiren temel bir unsur haline gelmiştir.

Anahtar Kelimeler: Yapay zekâ, dijital dönüşüm, stratejik yönetim, hibrit liderlik, rekabet avantajı

ABSTRACT

Artificial intelligence refers to the whole of information technologies that aim to imitate and improve human cognitive processes such as learning, thinking and problem solving through computer systems. This technology, which has developed rapidly in recent years, is considered not only as a technical innovation but also as a strategic element that directs the digital transformation processes of businesses. Especially thanks to big data analytics, automation and decision support systems, artificial intelligence contributes to making managerial decisions faster, more consistently and based on data. Today, it is seen that artificial intelligence is used effectively in businesses in many areas such as marketing, human resources, supply chain management, finance and operational processes. Artificial intelligence solutions in these areas

enable processes to be made more efficient, reduce costs and improve customer experience. Practices and studies in the real sector reveal that these gains provide sustainable competitive advantage to businesses. However, the widespread use of artificial intelligence applications brings with it some important risks. Data security and confidentiality, ethical responsibilities, changing employees' ways of doing business, and managers' resistance to this transformation are among the issues that need to be carefully addressed. At this point, scientific studies reveal that hybrid management and leadership models, in which human and artificial intelligence complement each other, will be critical for the businesses of the future. As a result, artificial intelligence has become a fundamental element that increases the innovation capacity of businesses and shapes long-term growth strategies.

Keywords: Artificial intelligence, digital transformation, strategic management, hybrid leadership, competitive advantage

GİRİŞ

Yapay zekâ; büyük veri analizi, makine öğrenimi, doğal dil işleme ve otomasyon gibi alanlarda sunduğu uygulamalar sayesinde işletmelerin iş yapma biçimlerinde köklü değişimlere yol açmaktadır. Günümüzde yapay zekâ, yalnızca operasyonel süreçleri iyileştiren bir teknoloji olmanın ötesine geçerek, işletmelerin stratejik karar alma mekanizmalarını destekleyen ve yönlendiren önemli bir araç haline gelmiştir. Bu bağlamda yapay zekâ, işletmelerin hedeflerine ulaşabilmek için izleyecekleri stratejik yolların belirlenmesinde karar vericilere analitik ve öngörüye dayalı katkılar sunmaktadır (Çopuroğlu & Şahin, 2024).

Yapay zekâ uygulamalarının iş dünyasında giderek yaygınlaşması, pazarlama, insan kaynakları, finans ve operasyon yönetimi gibi temel işletme fonksiyonlarında önemli dönüşümleri beraberinde getirmiştir. Yapay zekâ destekli sistemler; veriye dayalı karar alma süreçlerini hızlandırmakta, kaynakların daha etkin kullanılmasını sağlamakta ve işletmelerin rekabet avantajı elde etmelerine katkıda bulunmaktadır. Bu gelişmeler, işletmelerin yalnızca kısa vadeli performanslarını değil, aynı zamanda uzun vadeli sürdürülebilirlik ve büyüme hedeflerini de doğrudan etkilemektedir.

Dijitalleşme süreci ve sanayi devrimleriyle birlikte işletmelerin yönetim anlayışlarında yaşanan değişimlerde yapay zekâ önemli bir rol üstlenmiştir. Özellikle dördüncü sanayi devrimi kapsamında otomasyonun artması, yapay zekâ uygulamalarını birçok sektörde vazgeçilmez bir unsur haline getirmiştir. Bu çerçevede yapay zekâ, işletmelerin daha hızlı, tutarlı ve güvenilir kararlar alabilmesine olanak tanıyan bir teknoloji olarak öne çıkmaktadır (+ Yılmaz, 2022).

Bununla birlikte, yapay zekânın işletmelere entegrasyonu sürecinde yüksek yatırım maliyetleri, teknik karmaşıklık, çalışanların yetkinlik düzeyi ve etik sorunlar gibi çeşitli sınırlılıklar da söz konusu olabilmektedir. Dolayısıyla yapay zekâdan beklenen faydanın elde edilebilmesi, yalnızca teknolojik altyapının varlığına değil; aynı zamanda uygun yönetsel yaklaşımların benimsenmesine ve örgütsel uyumun sağlanmasına bağlıdır.

ARAŞTIRMA VE BULGULAR

Yapay Zekânın Tanımı ve Kavramsal Çerçevesi

Yapay zekâ, öğrenme, akıl yürütme, problem çözme ve karar verme gibi insan zekâsı gerektiren bilişsel süreçlerin makineler tarafından gerçekleştirilmesini amaçlayan disiplinler arası bir teknoloji alanıdır. Literatürde yapay zekâ, insan zekâsının makineler aracılığıyla taklit edilmesi ya da simüle edilmesi olarak tanımlanmakta; bu yönüyle bilgisayar bilimi, mühendislik ve bilişsel bilimlerin kesişim noktasında konumlanmaktadır (Uçar & Bulut, 2024).

Yapay zekânın temel ayırt edici özelliği, büyük veri kümeleri içerisindeki karmaşık ilişkileri analiz edebilmesi ve bu verilerden öğrenerek tahmine dayalı çıktılar üretebilmesidir. Bu yetenek, yapay zekâ teknolojilerinin konuşma tanıma, görüntü işleme, doğal dil işleme ve karar destek sistemleri gibi birçok alanda etkin biçimde kullanılmasını mümkün kılmaktadır. Böylece

yapay zekâ, yalnızca analiz yapan bir araç değil; belirli ölçüde otonom kararlar alabilen bir sistem niteliği kazanmaktadır.

Kavramsal olarak yapay zekâ terimi ilk kez 1956 yılında John McCarthy tarafından “akıllı makineler yapmanın bilimi ve mühendisliği” şeklinde tanımlanmış ve bu tarihten itibaren önemli bir gelişim süreci geçirmiştir. Günümüzde yapay zekâ, öğrenme mekanizmalarıyla donatılmış yazılım ve sistemler aracılığıyla insan benzeri bilişsel yetenekleri taklit edebilen teknolojiler bütünü olarak değerlendirilmektedir. Yani yapay zekâ, düşünme, akıl yürütme, hareket etme ve gerçekçi tepkiler verme kapasitesine sahip teknolojik sistemler şeklinde de tanımlanmaktadır (Uzboyalı Özer, H., 2025).

Yapay zekâ teknolojilerinin gelişimi, beraberinde etik, toplumsal ve ekonomik tartışmaları da gündeme getirmiştir. Özellikle iş gücü dönüşümü, veri güvenliği ve algoritmik önyargılar gibi konular, yapay zekâ uygulamalarının işletmelerde kullanımında dikkatle ele alınması gereken başlıca sorun alanları arasında yer almaktadır. Bununla birlikte, yapay zekânın geliştirilmesi ve kullanımında nihai sorumluluğun insana ait olması, bu teknolojinin insan kontrolünde şekillendiğini göstermektedir.

İşletmelerde Yapay Zekâ ve Stratejik Önemi

Geleceğe yönelik vizyon, yapay zekâ teknolojilerinin yalnızca iş dünyasında değil, toplumsal düzeyde de değer yaratacak biçimde geliştirilmesine odaklanmaktadır. Bu teknolojilerin sosyal refahın artırılması, ekonomik sürdürülebilirliğin desteklenmesi ve bireylerin yaşam kalitesinin yükseltilmesi gibi alanlarda önemli katkılar sunması beklenmektedir. Bu çerçevede yapay zekâ, işletmeler açısından yalnızca operasyonel bir araç değil, aynı zamanda stratejik yönetim anlayışını dönüştüren temel bir unsur olarak değerlendirilmektedir. Stratejik yönetim, kuruluşun amaçlarına ulaşmak için bir kuruluş ile çevresi arasında rekabet uyumu sağlayacak stratejileri formüle etmek ve uygulamak için kullanılan kararlar ve eylemler kümesi olarak ifade edilebilir (Mammadova, F., 2023).

Üretken yapay zekâ, sunduğu hız, verimlilik ve üretkenlik artışı sayesinde yönetim, pazarlama, finans, insan kaynakları ve lojistik gibi birçok alanda işletme performansını güçlendirmektedir. Karar destek sistemleri, otomasyon ve süreç optimizasyonu gibi uygulamalar yoluyla işletmelerin rekabet gücünü artırmakta; bu bağlamda yapay zekânın işletmelerde kullanımı, üretim verimliliğini ve yönetim verimliliğini büyük ölçüde etkilemektedir (Taşlıyan, M., Yılmaz, Ö.İ., 2022). Ancak yapay zekâ uygulamalarının şirketlere sunduğu faydalar kadar, beraberinde getirdiği risklerin de göz ardı edilmeyip stratejik düzeyde ele alınması gerekmektedir.

Özellikle veri güvenliği ve gizliliği, yapay zekâ kullanımında öne çıkan temel risk alanlarından biridir. Büyük miktarda veriye dayalı çalışan sistemler, siber saldırılara, veri sızıntılarına ve yetkisiz erişimlere karşı daha hassas hale gelmektedir. Bunun yanı sıra algoritmik önyargılar, hatalı veri setleri ve şeffaf olmayan karar mekanizmaları, yanlış yönetsel kararların alınmasına ve kurumsal itibar kaybına yol açabilmektedir. Ayrıca yapay zekâyı aşırı bağımlılık, yöneticilerin eleştirel düşünme becerilerinin zayıflaması ve kontrolün teknolojiye devredilmesi riskini de beraberinde getirmektedir.

Makineler hız ve analitik kapasite gerektiren görevlerde avantaj sağlarken, insanlar yaratıcılık, empati ve etik muhakeme gerektiren alanlarda belirleyici olmaya devam edecektir. Bu nedenle yapay zekâ, işletmelerde tam yetkili bir aktör olmaktan ziyade, tavsiye verme niteliği olan asistan rolü üstlenerek yöneticilere destek sağlayan bir araç olarak konumlandırılmalıdır (Uzboyalı Özer, H., 2025).

Yapay zekânın sağladığı faydaları ve doğurduğu riskleri doğru yöneten ve insan-merkezli bir yaklaşımla yapay zekâyı entegre eden işletmelerin, sürdürülebilir büyüme ve uzun vadeli başarı açısından avantaj sağlayacağı açıktır.

Yapay Zekânın Kullanım Alanları

Yapay zekâ teknolojileri, günümüz iş dünyasında yalnızca operasyonel süreçleri destekleyen bir araç olmanın ötesine geçerek, işletmelerin yönetim anlayışını ve rekabet stratejilerini yeniden şekillendiren temel bir unsur haline gelmiştir. Büyük veri işleme kapasitesi, öğrenme ve tahmin yetenekleri sayesinde yapay zekâ, işletmelerin daha hızlı, daha doğru ve daha tutarlı kararlar almasına olanak tanımaktadır. Bu teknolojinin satıştan pazarlamaya, insan kaynaklarından finansa, üretimden lojistiğe kadar pek çok işletme fonksiyonunda yaygın biçimde kullanılmaya başlanması, iş süreçlerinin bütüncül bir bakış açısıyla yeniden ele alınmasını zorunlu kılmaktadır. Yapay zekânın sunduğu otomasyon, analiz ve optimizasyon imkânları; verimlilik artışı, maliyetlerin düşürülmesi ve müşteri memnuniyetinin artırılması gibi önemli avantajlar sağlarken, aynı zamanda yönetim süreçlerinde insan-makine etkileşiminin sınırlarına ilişkin yeni tartışmaları da beraberinde getirmektedir. Bu çerçevede, yapay zekânın işletme fonksiyonları üzerindeki etkilerinin ayrı başlıklar altında incelenmesi, teknolojinin stratejik öneminin daha net biçimde ortaya konulmasına katkı sağlayacaktır.

Satış, Pazarlama ve Müşteri İlişkileri: Yapay zekâ, pazarlama ve müşteri ilişkileri alanında daha kişiselleştirilmiş, hızlı ve veriye dayalı uygulamaların geliştirilmesine olanak tanımaktadır. Büyük veri analitiği ve tahmine dayalı modeller sayesinde müşteri beklentileri daha doğru analiz edilmektedir. Bu kapsamda yapay zekâ, pazarlama süreçlerini daha özgün, daha yenilikçi ve verimli bir duruma getirerek işletmelerin hedef kitlelere net mesajlar iletmelerine ve müşteri deneyimini iyileştirmelerine yardımcı olmaktadır (Uçar, Z., Bulut, T., 2024). Örneğin; Chat botlar ve otomatik müşteri destek sistemleri, müşteri memnuniyetini artıran önemli araçlar arasında yer almaktadır.

İnsan Kaynakları: İnsan kaynakları yönetiminde yapay zekâ, aday seçimi, performans değerlendirme, eğitim planlama ve çalışan bağlılığının artırılması gibi süreçlerde etkin biçimde kullanılmaktadır. Yapay zekâ destekli sistemler, doğru adayların daha hızlı belirlenmesini sağlarken, çalışan verimliliğini ve memnuniyetini artırmaya yönelik içgörüler sunmaktadır. Bu dönüşüm, insan kaynakları süreçlerini daha stratejik ve veri odaklı hale getirmektedir.

Finans ve Muhasebe: Finans ve muhasebe alanında yapay zekâ, finansal işlemlerin hızlandırılması, hata oranlarının azaltılması ve risklerin daha etkin yönetilmesi açısından önemli katkılar sağlamaktadır. Otomatik muhasebe kayıtları, finansal tahminleme ve müşteri ürün önerileri gibi uygulamalar, işletmelerin finansal yönetim süreçlerini dönüştürmektedir. Bu doğrultuda yapay zekâ, finansal karar alma süreçlerinde önemli bir destek aracı haline gelmiştir.

Tedarik Zinciri ve Lojistik: Tedarik zinciri ve lojistik yönetiminde yapay zekâ, talep tahmini, rota optimizasyonu ve envanter kontrolü gibi alanlarda verimliliği artırmaktadır. Yapay zekâ tabanlı algoritmalar sayesinde teslimat süreleri kısaltmakta, maliyetler düşmekte ve arz-talep dengesi daha etkin biçimde sağlanmaktadır. Bu yönüyle yapay zekâ, tedarik zincirinin daha esnek ve çevik bir yapıya kavuşmasına katkı sunmaktadır.

Üretim ve Operasyonlar: Üretim süreçlerinde yapay zekâ destekli robotik sistemler, kalite kontrol süreçlerini iyileştirmekte ve operasyonel hataları azaltmaktadır. Yapay zekâ, üretim hatlarında otomasyonun artmasını sağlarken maliyetlerin düşürülmesine ve üretim verimliliğinin yükseltilmesine katkıda bulunmaktadır.

Yönetim ve Liderlik: Yönetim ve liderlik süreçlerinde yapay zekâ, karar destek sistemleri aracılığıyla yöneticilere stratejik içgörüler sunmaktadır. Kriz anlarında hızlı ve veriye dayalı karar alınmasını kolaylaştıran yapay zekâ uygulamaları, yönetsel etkinliği artırmaktadır. Bununla birlikte, yapay zekâ hâlen insan denetiminde kullanılan bir araç olup, liderlik ve nihai karar verme sorumluluğu yöneticilerde kalmaktadır. Bu

durum, insan-makine iş birliğine dayalı yeni bir yönetim anlayışının geliştiğini göstermektedir.

SONUÇ

İş süreçlerinde dijitalleşmenin hız kazanması ve otomasyon uygulamalarının yaygınlaşması, yapay zekâyı işletmeler açısından stratejik bir gereklilik haline getirmiştir. Bu çalışma kapsamında ele alınan bulgular, yapay zekâ teknolojilerinin büyük veri analizi, makine öğrenimi ve doğal dil işleme gibi yetenekleri sayesinde işletmelerin operasyonel verimliliklerini artırdığını, kaynak kullanımını daha etkin hale getirdiğini ve karar alma süreçlerini güçlendirdiğini ortaya koymaktadır. Aynı zamanda işletmelerin gelecekte karşılaşabilecekleri belirsizliklere karşı da daha esnek ve sürdürülebilir çözümler geliştirmesini mümkün kılmaktadır.

Geleceğe yönelik değerlendirmeler, yapay zekâ uygulamalarının işletme fonksiyonlarının merkezinde yer almaya devam edeceğini ve entegrasyon sürecinin hızlanarak süreceğini göstermektedir. Bu bağlamda işletmelerin yapay zekâyı bir tehdit unsuru olarak değil, stratejik bir rekabet aracı olarak ele almaları büyük önem taşımaktadır. Teknolojik gelişmelerin yoğunlaştığı günümüz koşullarında inovasyon kapasitesinin işletme başarısındaki belirleyici rolü dikkate alındığında, yapay zekâ destekli çözümlerin bazı alanlarda insan gücünü tamamlayıcı hatta ikame edici bir işlev üstleneceği ve yeni meslek alanlarının ortaya çıkacağı öngörülmektedir.

Bununla birlikte, yapay zekânın sunduğu fırsatların yanı sıra etik, yönetsel ve örgütsel boyutlarının da dikkatle ele alınması gerekmektedir. Yapay zekâ uygulamalarından beklenen faydanın sağlanabilmesi; bu teknolojilerin yeteneklerinin ve sınırlarının doğru analiz edilmesine, kullanım alanlarının bilinçli biçimde belirlenmesine ve çalışan rollerinin bu doğrultuda yeniden yapılandırılmasına bağlıdır. Bu yeni sanayi devrimi sürecinde işletmelerin reaktif değil, proaktif bir yaklaşımla dönüşümü yönetmeleri kritik önem taşımaktadır.

Sonuç olarak yapay zekâ, işletmelere verimlilik artışı, maliyet avantajı, müşteri memnuniyeti ve rekabet gücü kazandıran temel bir teknoloji olarak öne çıkmaktadır. İş süreçlerinde artan otomasyon ve veri temelli karar alma pratikleriyle birlikte, yapay zekânın işletmelerin dijital dönüşüm yolculuğunda merkezi bir rol üstlenmeye devam edeceği ve stratejik yönetim anlayışını kalıcı biçimde dönüştüreceği açıktır.

KAYNAKÇA

Çopuroğlu, C. Y. ve Şahin, M. (2024). Dijital Dönüşümde Yapay Zekâ Şirketlerinin Stratejik Rolü ve Önemi. *EJONS International Journal on Mathematic, Engineering and Natural Sciences*, 8(3):302-308.

Uçar, Z. ve Bulut, T. (2024). İşletme Fonksiyonlarının Dönüşümünde: Yapay Zekâ. *Bitlis Eren Sosyal Araştırmalar Dergisi* 2(2): 111-123.

Mammadova, F. (2023). Stratejik Yönetim Kapsamında Yapay Zekâ Rolü Üzerine Nitel Bir Araştırma. Yüksek Lisans Tezi, Dokuz Eylül Üniversitesi, Sosyal Bilimler Enstitüsü, İzmir.

Yastioğlu, S. (2023). Üretken Yapay Zekânın İşletmelerde Kullanımı: Fırsatlar ve Tehditler.

Çevik, T. İ. (ed.), *Yönetim Bilişim Sistemleri: İşletmelerde Dijital Dönüşüm Yönetimi*, Özgür Yayınları.

Gür, Y.E., Ayden, C. ve Yücel, A., (2019). Yapay Zekâ Alanındaki Gelişmelerin İnsan Kaynakları Yönetimine Etkisi. *Fırat Üniversitesi İİBF Uluslararası İktisadi ve İdari Bilimler Dergisi* Cilt:3, Sayı:2,2019 137.

Nuriyev, N. (2024). Yapay Zekâ Kullanımı ve Büyüme İlişkisi. İstanbul Üniversitesi, Doktora Tezi, Sosyal Bilimler Enstitüsü, İstanbul.

- Taşlıyan, M. ve Yılmaz, Ö.İ. (2022). Yapay Zekâ ve İşletmeler Açısından Sonuçları. International Academic Social Resources Journal, (eISSN: 2636-7637), Vol:7, Issue:36; pp:463-471.
- Uzboyalı Özer, H. (2025). Yapay Zekânın İnsan, İş Dünyası ve Yönetimdeki Rolü. Demir, F. (ed.), İş'te Dinamizm: Dijitalleşen Dünyada Yeni Nesil Yönetim, Özgür Yayınları.
- Demirkan S. (2025). Yapay Zekâ Uygulamalarının İş Süreçlerine Katkısı. Black Sea Journal of Engineering and Science, Cilt 8-Sayı 3: 680-694.
- Sarnıç, A. ve Acar, S. (2024). Dördüncü Endüstri Devrinde İşletmelerde Yapay Zekâ Uygulamaları Örnekleri Üzerine Nitel Bir Araştırma. İşletme, 5(2), 155-181.
- Akturan, A. (2024). Yapay Zekânın İşletme Yönetimi ve Liderlik Üzerindeki Etkileri: Bir Literatür İncelemesi. Sinop Üniversitesi Sosyal Bilimler Dergisi, 8 (2), 1305-1348.
- Berberoğlu, B. (2023). Yönetimde Yapay Zekâ. Scientific Journal of Innovation and Social Sciences Research,3(2),81-96.

**ITU ŞEHİR İÇİ MAKRO HÜCRE KANAL MODELİ ALTINDA OFDM TABANLI
ENTEĞRE ALGILAMA VE HABERLEŞME SİSTEMLERİNİN
KARAKTERİZASYONU**

CHARACTERIZATION OF OFDM-BASED INTEGRATED SENSING AND
COMMUNICATION SYSTEMS UNDER THE ITU URBAN MACROCELL CHANNEL
MODEL

Nurullah ORAL

Ankara Yıldırım Beyazıt Üniversitesi, Fen Bilimleri Enstitüsü
Elektrik ve Elektronik Mühendisliği Anabilim Dalı, Keçiören, Ankara

Dr. Mustafa Anıl REŞAT

Ankara Yıldırım Beyazıt Üniversitesi, Mühendislik ve Doğa Bilimleri Fakültesi
Elektrik ve Elektronik Mühendisliği Bölümü, Keçiören, Ankara

Prof. Dr. Serdar ÖZYURT

Ankara Yıldırım Beyazıt Üniversitesi, Mühendislik ve Doğa Bilimleri Fakültesi
Elektrik ve Elektronik Mühendisliği Bölümü, Keçiören, Ankara

ÖZET

Gelecek nesil mobil haberleşme ağlarında, haberleşme ve algılama sistemlerinin aynı altyapı üzerinden bütünleşik bir biçimde kullanılmasına yönelik artan gereksinimler, entegre algılama ve haberleşme (integrated sensing and communication, ISAC) olarak adlandırılan yeni bir kavramı ortaya çıkarmıştır. ISAC, sınırlı spektrum ve donanım kaynaklarının daha verimli kullanılmasını hedefleyerek, haberleşme ve algılama işlevlerinin ortak sinyaller ve donanımlar üzerinden gerçekleştirilmesini mümkün kılmaktadır. Bu bağlamda, literatürde ISAC sistemlerinde algılama ve haberleşme fonksiyonlarının kaynak paylaşımı ve olası ödünleşimleri üzerine çeşitli başarımlar analizleri gerçekleştirilmiştir. Bu çalışmada, International Telecommunication Union (ITU) tarafından tanımlanan ve ölçümsel verilere dayanan şehir içi makro hücre kanal modeli üzerinde, dikgen frekans bölmeli çoğullama (orthogonal frequency division multiplexing, OFDM) kullanan ISAC sistemlerinin başarımlarını incelenmiştir. OFDM'in çoklu taşıyıcı yapısı, ISAC mimarisinde hem yüksek hızlı veri transferini hem de hassas radar fonksiyonlarını eş zamanlı gerçekleştirebilen ortak bir platform sağlar. Sistemin haberleşme performansını temsil eden bit hata oranı (bit error rate, BER) ile algılama performansını yansıtan eşik (κ) tabanlı hedef izleme başarımları arasındaki ilişki analiz edilmiştir. Bu bağlamda, algılama sürecine ait tespit olasılığı (probability of detection, PD) ve yanlış alarm olasılığı (probability of false alarm, PFA) ölçütleri değerlendirilmiştir. Elde edilen benzetim sonuçları, gerçekçi bir kanal modeli altında haberleşme ve algılama sinyallerinin entegre biçimde kullanılması durumunda, haberleşme kullanıcısının BER performansında herhangi bir bozulma oluşmadığını göstermektedir. Bununla birlikte, hedef izleme başarımları açısından PD ve PFA arasında, seçilen eşik değerine bağlı olarak belirgin bir ödünleşimin bulunduğu ortaya konmuştur.

Anahtar Kelimeler: Bit hata oranı, dikgen frekans bölmeli çoğullama, entegre algılama ve haberleşme, ITU şehir içi makro hücre kanal modeli, tespit olasılığı, yanlış alarm olasılığı.

ABSTRACT

In the next-generation mobile communication networks, the increasing demand for the integrated use of communication and sensing systems over a shared infrastructure has led to the emergence of a new paradigm known as integrated sensing and communication (ISAC). ISAC aims to improve the efficient utilization of limited spectrum and hardware resources by enabling communication and sensing functionalities to be jointly realized through common signals and shared hardware platforms. In this context, various performance analyses have been conducted in the literature to investigate resource sharing mechanisms and the associated trade-offs between communication and sensing functions in ISAC systems. In this study, the performance of ISAC systems employing orthogonal frequency division multiplexing (OFDM) is analyzed under the suburban macro-cell channel model defined by the International Telecommunication Union (ITU) and based on empirical measurements. The multicarrier nature of OFDM establishes a unified platform within the ISAC architecture, enabling the simultaneous execution of high-speed data transmission and precise radar functionalities. The relationship between the bit error rate (BER), which represents the communication performance of the system, and the threshold (κ)-based target tracking performance, which reflects the sensing capability, is investigated. Accordingly, significant sensing performance metrics, namely the probability of detection (PD) and the probability of false alarm (PFA), are evaluated. The simulation results show that, under a realistic channel model, the integrated use of communication and sensing signals does not lead to any degradation in the BER performance of the communication user. In addition, the results also reveal the existence of a pronounced trade-off between PD and PFA in terms of target tracking performance, depending on the selected threshold value.

Keywords: Bit error rate, orthogonal frequency division multiplexing, integrated sensing and communication, suburban macro-cell channel model, probability of detection, probability of false alarm.

GİRİŞ

Gelecek nesil ağların desteklemesinin beklendiği çevresel farkındalığa sahip pek çok uygulama sıklıkla yüksek keskinlik, yüksek algılama ve büyük ölçekli bağlantırlık gibi özellikler gerektirmektedir [1]. Çok büyük çok girişli çok çıkışlı antenler ve milimetre dalga gibi teknolojileri içeren beşinci nesil sistemler sayesinde halihazırda yerleşik durumda bulunan çok yüksek yoğunluklu hücresel altyapı tarafından gönderilen haberleşme sinyalleri yüksek keskinliğe sahip algılama işlemlerinde de kullanılabilecektir [2]. Entegre algılama ve haberleşme (integrated sensing and communication, ISAC) olarak adlandırılan bu yaklaşımın, yeni nesil ağlarda önemli bir yere sahip olması beklenmektedir.

ISAC sistemlerde geleneksel olarak birbirinden bağımsız biçimde gelişmiş ve sınırlı kaynaklar için birbirleriyle rekabet içinde olmuş radar algılama ve kablosuz haberleşme teknolojileri aynı frekans bandını ve donanımı ortaklaşa kullanmaktadır. [3]'teki çalışmada haberleşme ve algılamanın tarih içindeki gelişimi ele alınmış ve bu iki yapının entegrasyonu ile elde edilen başarımlar ortaya konmuştur. Ayrıca [4], ISAC sistemlerin yalnızca spektral verimliliği artırmakla kalmayıp donanım maliyetlerini de azalttığını ve bu yönüyle gelişmiş mobil haberleşme sistemler için güçlü bir aday olduğunu ifade etmektedir. [5]'teki çalışmada radar-haberleşme ortak iletiminde yapıcı girişimin rolü vurgulanırken, [6]'da ise mükemmel olmayan kanal durumu bilgisi varsayımı altında ışın oluşturma tasarımına odaklanılarak birleşik radar-haberleşme sistemlerinin optimizasyonu için önemli veriler sunulmuştur.

Her ne kadar ISAC sistemleri sundukları önemli avantajlar nedeniyle araştırmacıların yoğun ilgisine maruz kalmışsa da bu sistemlerin getirdiği bazı tasarım zorlukları da yok değildir. Bu zorlukların başında, birleşik sinyal işleme süreçlerinin yüksek derecede karmaşık olması

gelmektedir. [7]'de, radar ve haberleşme işlevlerinin entegrasyonunun, çoğunlukla gerçek hayat koşullarındaki optimizasyonu zor olan çerçevelere yol açtığına dikkat çekilmektedir. Bir diğer önemli problem ise, ISAC sistemlerinin ortak frekans bantlarında çalışmasından kaynaklanan spektrum yönetimi ve girişim sorunlarıdır. [8]'de, donanım maliyeti ve güç tüketimini azaltmak amacıyla kullanılan hibrit ışın oluşturma yöntemlerinin, girişim seviyesini ister istemez artırdığı belirtilmiştir. Ayrıca, gerçek zamanlı uygulamalarda karşılaşılan yüksek hareketlilik durumu da ISAC sistemlerde karmaşıklığa yol açabilmektedir. Nitekim [9], insansız hava araçlarının ISAC uygulamaları için elverişli platformlar olduğunu ifade ederken, bu sistemlerin yüksek hareketliliği sebebiyle haberleşme ve algılama arasındaki entegrasyonu korumak için gelişmiş stratejilere gereksinim duyulduğunu da vurgulamaktadır.


ISAC sistemlerin başarımının artırılması için yapılan çalışmalarda öne çıkan bir başka zorluk da frekans-seçici sönmülemeli kanal etkileridir. Özellikle, günümüz teknolojisinde kullanılmakta olan daha yüksek taşıyıcı frekans değerleri ve daha geniş bant genişlikleri ile bu tür kanal yapıları daha sık karşımıza çıkmaktadır. Dikgen frekans bölmeli çoğullama (orthogonal frequency division multiplexing, OFDM) kullanılarak, frekans-seçici sönmülemeli kanallar birden fazla dar-bantlı düz sönmülemeli alt kanala ayrıştırılabilmektedir [10]. Bu çalışmada, [11]'dekine benzer bir senaryo ele alınmakla birlikte, düz sönmülemeli kanallar üzerinde ISAC sistemlerinde haberleşme hızı ile hedef tespit olasılığı arasındaki ödünleşimi inceleyen söz konusu çalışmadan farklı olarak, OFDM tabanlı ISAC sistemlerinin, gerçekçi ve ölçümsel bir frekans seçici sönmülemeli kanal tipi olan International Telecommunication Union (ITU) şehir içi makro hücre kanal modeli [12] üzerindeki başarımı analiz edilmiştir. Bu kapsama, ISAC sistemlerine ait bit hata oranı (bit error rate, BER) ve hedef izleme başarımı (tespit olasılığı (probability of detection, PD) ve yanlış alarm olasılığı (probability of false alarm, PFA)) benzetimler aracılığıyla sunulmuştur. Elde edilen sonuçlar, haberleşme kullanıcısının haberleşme ile algılama sinyallerini bütünsel biçimde kullandığı durumda dahi, BER başarımının yalnızca haberleşme sinyalini kullanan klasik bir OFDM sistemindeki kullanıcıyla aynı seviyede olduğunu göstermektedir. Dahası, hedef izleme başarım ölçütleri olan PD ve PFA'nın seçilen eşik değerine bağlı olarak değiştiği ve bu iki parametre arasında belirgin bir ödünleşim bulunduğu da ortaya konmuştur.

SİSTEM İŞLEYİŞ AKIŞ DİYAGRAMI

Şekil 1'de OFDM tabanlı bir bistatik ISAC sisteminin blok diyagramı sunulmuştur. Şekilden de görüleceği üzere tek antene sahip bir baz istasyonu (base station, BS) tek antene sahip bir haberleşme kullanıcısıyla (communication user, CU) iletişim gerçekleştirmektedir. Bunun yanı sıra, bir de tek antene sahip statik bir algılama alıcısı (sensing receiver, SR) yer almakta olup, bu da BS ile SR arasındaki kanalda olası bir hedefin varlığı durumunda BS'den gönderilen sinyalin yansımalarını almaktadır. Bu senaryoda BS tarafından iletilen sinyal:

$$s(t) = \sum_m \sum_{k=0}^{N-1} X_m[k] e^{j2\pi k \Delta f (t - mT_s)} g(t - mT_s) \quad (1)$$

şeklinde yazılabilir. Burada, m , OFDM sembol indeksini, N alttaşıyıcı sayısını, $X_m[k]$, m . sembol ve k . alt-taşıyıcıdaki haberleşme sembolünü, Δf alt-taşıyıcı aralığını, T_s OFDM sembolü periyodunu ve $g(t)$ sembol darbesini temsil etmektedir.



Şekil 1. Sistem modelinin yapısal gösterimi [11]

Bu çalışmada, BS-CU ve BS-hedef-SR arasındaki her iki kanalın da ITU şehir içi makro hücre kanal modeliyle uyumlu frekans-seçici sönmülemeli kanallar olduğu varsayılmıştır. Sistem, haberleşme ağırlıklı bir ISAC mimarisi olarak ele alınmış ve OFDM sembollerinin BS 'den gönderildiği bir senaryo incelenmiştir. Bu durumda CU' da elde edilen sinyal:

$$r_c(t) = \sum_{l=0}^{L-1} h_l(t)s(t - \tau_l) + n(t) \quad (2)$$

ile gösterilebilir. Burada, $h_l(t)$, l . yolun karmaşık kazancını, τ_l , l . yolun gecikme değerini, $n(t)$ ise toplanır beyaz Gauss gürültüsünü (additive white Gaussian noise, AWGN) temsil etmektedir. Bu ifade CU'daki çevrimsel önek çıkarımı ve hızlı Fourier dönüşümü uygulandıktan sonra, m . sembol ve k . alt-taşıyıcı için:

$$R_m[k] = H_m[k]X_m[k] + N_m[k] \quad (3)$$

haline gelmektedir. Burada $H_m[k] = \sum_{l=0}^{L-1} h_l(t_m)e^{-j2\pi k\Delta f\tau_l}$ k . alt-taşıyıcıdaki kanal frekans cevabını ($t_m \approx mT_s$) ve $N_m[k]$ ilgili alt-taşıyıcıdaki gürültü terimini göstermektedir. Bu noktada, sıfıra-zorlayan bir denkleştirici ve maksimum benzerlik detektörü vasıtasıyla iletilen semboller basit bir şekilde geri elde edilebilmektedir.

Bu yapı altında, SR' de gözlemlenen sinyal ise:

$$r_s(t) = \begin{cases} \sum_{y=0}^{Y-1} h_y(t)s(t - \tau_y) + w(t), & \text{hedef varken} \\ w(t), & \text{hedef yokken} \end{cases} \quad (4)$$

ile temsil edilecektir. Burada, $h_y(t)$, y . yolun karmaşık kazancını, τ_y , y . yolun gecikme değerini, $w(t)$ ise AWGN'yi göstermektedir. SR tarafında alınan sinyal üzerinde enerji hesaplaması yapılmakta ve elde edilen bu değer, önceden belirlenmiş bir eşik değeri (κ) ile karşılaştırılarak hedefin varlığına ya da yokluğuna karar verilmektedir. Buna göre, P_{fa} ve P_d olasılıkları aşağıdaki şekilde tanımlanmaktadır:

$$P_{fa} = \Pr(E_r > \kappa | H_0) \quad (5)$$

$$P_d = \Pr(E_r > \kappa | H_1) \quad (6)$$

Burada, H_0 gerçekte hedefin bulunmadığı ve dolayısıyla iletilen sinyalin SR' ye ulaşmadığı durumu; H_1 ise gerçekte hedefin var olduğu yani iletilen sinyalin hedeften yansyarak SR' ye ulaştığı durumu temsil etmektedir. Ayrıca E_r , SR' de ölçülen enerji miktarını göstermekte olup,

H_0 durumunda bu enerji yalnızca AWGN' den kaynaklanmaktadır. SR tarafında herhangi bir denkleştirme işlemi uygulanmadığı durumda, P_{fa} olasılığı ki-kare dağılımı yardımıyla aşağıdaki biçimde hesaplanabilmektedir:

$$P_{fa} = \Pr(E_r > \kappa | H_0) = \int_{\kappa}^{\infty} \frac{z^{N-1}}{P_G^N \Gamma(N)} e^{(-z/P_G)} dz = \frac{\Gamma(N, \frac{\kappa}{P_G})}{\Gamma(N)} \quad (7)$$

Bu ifadede, N ve P_G sırasıyla kullanılan alt-taşıyıcı sayısını ve ortalama AWGN gücü değerini (alt-taşıyıcı başına) temsil etmektedir. Ayrıca, $e^{(.)}$ üstel fonksiyonu, $\Gamma(.)$ ve $\Gamma(.,.)$ sırasıyla gama ve üst tamamlanmamış gama fonksiyonlarını ifade etmektedir.

PERFORMANS ANALİZİ

Elde edilen performans çıktılarındaki esas alınan parametreler Tablo 1'de sunulurken, ele alınan senaryoya ait benzetim çıktıları da Şekil 2 ve Şekil 3'te gösterilmektedir. Bu grafiklerde yatay eksen toplam iletim gücünü (P_T) temsil etmektedir. Tüm benzetimlerde çoklu yol bileşenlerinin birbirlerinden istatistiksel olarak ilişkisiz bir şekilde değiştiği varsayılmıştır. Hem Şekil 2 hem de Şekil 3 için, her bir çoklu yol bileşenine ait ortalama karesel kanal kazancı değerleri, gerek BS ve CU arasındaki kanal için gerekse BS ve SR arasındaki kanal için ITU şehir içi makro hücre kanal modeli dağılımından gelmektedir.

Şekil 2'de iletim gücüne bağlı olarak PD 'nin değişimi sunulmaktadır. Grafikten görüldüğü üzere, eşik değerinin 0.8 ve 0.9 olarak seçildiği her iki durumda da PD değeri iletim gücü ile yükselmekte ve yaklaşık 17.5 dB değerinden itibaren de doyuma ulaşmaktadır. Ayrıca, iletim gücünün sabit tutulduğu durumda, enerji tabanlı algılamada kullanılan eşik değerinin yükseltilmesi (doyum bölgesi haricinde) hem PD hem de PFA 'yı düşürmektedir. Bu durum, eşik değeri ayarlanarak hedef tespiti ve hatalı alarm olasılığı arasında bir ödünleşim gerçekleştirilebileceğini ortaya koymaktadır. Buradaki bir diğer önemli nokta da hedef tespitinde haberleşme sinyalinin içeriğinin işlenmemesi ve kararın yalnızca belirlenen eşik değerine göre verilmesi nedeniyle, algılama başarımlarının modülasyon seviyesinden bağımsız olmasıdır.

Şekil 3'te ise toplam iletim gücüne bağlı olarak BER 'in değişimi ortaya konmaktadır. Şekilden de anlaşılabileceği gibi, haberleşme kullanıcısının elde ettiği BER başarımları, klasik bir OFDM sisteminde gözlemlenen BER seviyesiyle örtüşmektedir. Bu sonuç, önerilen yapının hem haberleşme hem de algılama işlevlerini birlikte yerine getirmesine rağmen, haberleşme kullanıcısının başarımında herhangi bir başarımların düşüklüğüne sebep olmadığını göstermektedir. Ayrıca, verilen benzetim parametreleri altında modülasyon seviyesinin 2 olduğu durumun ($M = 2$, ikili faz kaydırmalı anahtarlama, binary phase shift keying, BPSK), modülasyon seviyesinin 4 olduğu duruma kıyasla ($M = 4$, dörtlü faz kaydırmalı anahtarlama, quadrature phase shift keying, QPSK) nispeten daha iyi bir BER başarımları sergilediği görülmektedir. BER değerinin 10^{-4} olduğu noktada, BPSK modülasyonu QPSK 'ye oranla 3.52 dB 'lik bir başarımların kazancı sağlamaktadır. Son olarak, haberleşme kullanıcısı alıcı tarafında hedef tespitindeki eşik değerini kullanmadığı için, elde edilen BER sonuçları eşik değerinden bağımsız olmaktadır.


Tablo 1. Modellemede kullanılan sistem değişkenleri.

Parametre	Değer
Taşıyıcı frekansı	4 GHz
Toplam bant genişliği	7.68 MHz
Alt-taşıyıcı frekans aralığı (Δ_f)	15 kHz
Alt-taşıyıcı sayısı	512
OFDM sembol süresi	0.067 ms
Çevrimsel önek süresi	1.3 μ s
Kanal istatistiği	5 yollu yavaş frekans-seçici ITU şehir içi makro hücre kanal modeli
Kanal güç gecikme profili	ITU şehir içi makro hücre kanal modeli


AWGN güç spektral yoğunluğu (N_0)	10^{-7} W/Hz
Modülasyon	BPSK ve QPSK

SONUÇLAR

İlgili araştırma kapsamında, OFDM tabanlı ISAC sistemlerinin, ölçümsel ve gerçekçi bir frekans-seçici sönümlemeli kanal tipi olan ITU şehir içi makro hücre kanal modeli üzerindeki elde edilen BER ve hedef izleme performans düzeyleri simülasyon temelli analizlerle incelenmiştir. Tek bir BS 'den yayılan sinyalin hem bir CU hem de bir SR tarafından alındığı bir senaryo kapsamında, CU 'nun BER başarımında haberleşme ve algılama sinyallerinin entegre kullanımına rağmen herhangi bir düşüş bulunmamıştır. Ayrıca, BPSK modülasyon tipinin QPSK modülasyon tipine oranla nispeten daha yüksek bir kazanç sunduğu tespit edilmiştir. SR 'deki PD başarımının iletim gücüyle yükseldiği ve belirli bir güç seviyesinden sonra da doyuma ulaştığı gösterilmiştir. Bununla birlikte, bu senaryoda kritik bir parametre olan eşik değerinin değişmesiyle birlikte PD ve PFA değerlerinin de değiştiği, PD 'nin düştüğü, PFA 'nın ise arttığı ortaya konmuştur. Bu bulgular, seçilen eşik değerine bağlı olarak PD ve PFA başarımları arasında kaçınılmaz bir ödünleşim bulunduğunu göstermektedir. Tüm sonuçlar birlikte değerlendirildiğinde, bu çalışmada önerilen sistemin, gerçekçi frekans-seçici sönümleme koşulları altında dahi yeni nesil haberleşme ağlarının ihtiyaçlarını karşılayabilecek güçlü bir aday olduğu sonucuna varılmaktadır.



Şekil 2. ITU şehir içi makro hücre ortamında modellenen OFDM tabanlı ISAC bistatik radar senaryosu için PD performansının iletim gücüne göre incelenmesi.



Şekil 3. ITU şehir içi makro hücre ortamında modellenen OFDM tabanlı ISAC bistatik radar senaryosu için BER performansının iletim gücüne göre incelenmesi.

KAYNAKLAR

1. Bartoletti S., Wymeersch H., Mach T., Brunnegård O., Giustiniano D., Hammarberg P., Keskin M.F., Lacruz J.O., ve diğerleri. Positioning and sensing for vehicular safety applications in 5G and beyond. *IEEE Commun. Mag.* 2021;59(11):15–21.
2. Rahman M.L., Zhang J.A., Huang X., Guo Y.J., Heath R.W. Jr. Framework for a perceptive mobile network using joint communication and radar sensing. *IEEE Trans. Aerospace Elect. Sys.* 2020;56(3):1926-1941.
3. Liu, F., Cui, Y., Masouros, C., Xu, J., Han, T. X., Eldar, Y. C., ... & Buzzi, S. (2022). Integrated sensing and communications: toward dual-functional wireless networks for 6g and beyond. *IEEE Journal on Selected Areas in Communications*, 40(6), 1728-1767. <https://doi.org/10.1109/jsac.2022.3156632>
4. Wei, Z., Qu, H., Wang, Y., Yuan, X., Wu, H., Du, Y., ... & Feng, Z. (2023). Integrated sensing and communication signals toward 5g-a and 6g: a survey. *IEEE Internet of Things Journal*, 10(13), 11068-11092. <https://doi.org/10.1109/jiot.2023.3235618>
5. Zhang, J., Liu, F., Masouros, C., & Huang, Y. (2023). Exploiting interference in joint radar-communication transmission. *GLOBECOM 2023 - 2023 IEEE Global Communications Conference*. <https://doi.org/10.1109/globecom54140.2023.10437854>
6. Chafii, M. (2023). Robust integrated sensing and communication beamforming for dual-functional radar and communications: method and insights. *Proceedings of the XXXVth URSI General Assembly and Scientific Symposium – GASS 2023*. <https://doi.org/10.46620/ursigass.2023.0344.uipi8513>

7. Liu, A., Huang, Z., Li, M., Wan, Y., Li, W., Han, T. X., ... & Chetty, K. (2022). A survey on fundamental limits of integrated sensing and communication. *IEEE Communications Surveys & Tutorials*, 24(2), 994-1034.
<https://doi.org/10.1109/comst.2022.3149272>
8. Wang, X., Fei, Z., Zhang, J. A., & Xu, J. (2022). Partially-connected hybrid beamforming design for integrated sensing and communication systems. *IEEE Transactions on Communications*, 70(10), 6648-6660.
<https://doi.org/10.1109/tcomm.2022.3202215>
9. Pan, Y., Li, R., Da, X., Hu, H., Zhang, M., Zhai, D., ... & Dobre, O. A. (2024). Cooperative Trajectory Planning and Resource Allocation for UAV-Enabled Integrated Sensing and Communication Systems. *IEEE Transactions on Vehicular Technology*, 73(5), 6502-6516. <https://doi.org/10.1109/tvt.2023.3337106>
10. L. J. Cimini, Jr., "Analysis and simulation of a digital mobile channel using orthogonal frequency division multiplexing," *IEEE Transactions on Communications*, vol. COM-33, no. 7, pp. 665–675, Jul. 1985.
11. An J., Li H., Ng D.W.K., Yuen C. Fundamental detection probability vs. achievable rate tradeoff in integrated sensing and communication systems. *IEEE Trans. Wirel. Commun.* 2023;22(12):9835–9853.
12. Recommendation ITU-R M.1225, "Guidelines for evaluation of radio transmission technologies for IMT-2000".

**TOWARDS A KNOWLEDGE-DRIVEN ECONOMY IN NIGERIA: CHALLENGES
AND STRATEGIC PATHWAYS**

Obi Godwin Chukwudi

World Bank Centre of Excellency in Agricultural Development and Sustainable Environment (CEADESE), Federal University of Agriculture, PMB 2240, Abeokuta, Ogun State, Nigeria.

Abstract

Transition towards a knowledge based economy has taken shape as a characteristic of sustainable development plans in both the developed and the emergent economies. Instead of depending largely on natural resources or the low-skilled labour, the growth of knowledge economies is based on human capital and innovation, research as well as the efficient utilisation of information and communication technologies. In the case of Nigeria whose history of economic performance was predetermined by the oil addiction and commodity fluctuation, the knowledge economy offers a potential course of diversification, job creation, and future sustainability. This paper explores the conceptual basis of the knowledge economy, evaluates the existing awareness and institutional preparedness of Nigeria and determines structural barriers to development. Based on empirical analyses, policy frameworks and international standards, the paper will suggest strategic policy directions that will center on education reformation, commercialization of research, digital infrastructure and collaboration in industries. The research work will be used to further the discussion in that it will help to clarify the knowledge economy in terms of the socio-economic circumstances of Nigeria and provide practical advice to policymakers, academic institutions, and the players of the private sector.

Keywords

Knowledge economy; human capital; systems of innovation; reform of education; Nigeria.

Introduction

In the world, economic competitiveness is also being defined by the capacity of countries to create, implement, and disseminate knowledge. This change signifies the breakaway of the old growth systems based on physical capital and natural resource extraction to systems that are characterized by the use of innovation, skills and use of technology to generate productivity. Knowledge-driven economy is thus a central concept in the modern-day developmental thinking. The topicality of this transition is especially significant in Nigeria. The economy is sensitive to changes in the price of oil in the global market, although there is a high population of people and there are massive resources available, there is little depth of industry and there is always unemployment especially among the young people. These have made the call of economic restructuring and diversification very strong. Knowledge-based economy provides an outline on which Nigeria can use its demographic edge, increase the high value industries, and foster inclusive development.

In this paper, the prospects of Nigeria in this context are examined by answering three questions: What is the definition of the knowledge economy in theory and practice, what does Nigeria currently do in this regard and what strategic changes are needed to speed up the process. The discussion places Nigeria in the context of the national research results and the international policy visions.

Knowledge Economy Conceptualization.

The knowledge economy describes an economic system whereby production, sharing and use of knowledge is important in the production of wealth and competitiveness. In contrast to

resource-based economies, knowledge economies rely heavily on intellectual capacity, innovation systems, and technological development as opposed to the physical input of the same (OECD, 1996).

Organization for Economic Co-operation and Development recognizes four intertwined pillars of successful knowledge economy, which are, educated and skilled work force, powerful innovation system, advanced information and communication infrastructure, and institutional regime that favors entrepreneurship and investment (OECD, 1996). All these pillars can help societies to transform knowledge into productive economic products. The intellectual capital, research capacity and learning institutions are also emphasized by scholarly perspectives in maintaining competitiveness. The growth of human capital, incessant learning, and efficient knowledge management are therefore considered as the building blocks of the long-term economic change (Umar & Dandago, 2023).

Table 1: Empirical Studies on the Knowledge Economy in Nigeria

Author(s)	Focus Area	Key Findings	Implications
Don-Solomon (2025)	Infopreneurship	Digital entrepreneurship boosts innovation and jobs	Invest in ICT skills and infrastructure
Umar & Dandago (2023)	Intellectual Capital	Human and relational capital improve firm performance	Firms should prioritize knowledge assets
Aregbesola et al. (2025)	Science Education	Inquiry-based learning improves skills	Curriculum reform is needed
Morili et al. (2024)	Business Education	Research-driven education supports transformation	Strengthen research funding

The Landscape of Knowledge Economy and digital innovation in Nigeria

The recent scholarly and policy-oriented research demonstrates that there is an increased activity around the principles of knowledge economy in Nigeria, specifically in higher education, entrepreneurship, and firm-level performance. Infopreneurship and Digital Innovation is the discussion of the role of information in entrepreneurship and innovations. The commercialisation of knowledge and information resources or infopreneurship has been identified as a possible trigger of transformation of Nigeria to a knowledge economy. According to Don-Solomon (2025), digital entrepreneurship has the potential of increasing innovation and employment by converting information to marketable goods and services. Nevertheless, the limitations that face scalability include digital illiteracy, poor ICT infrastructure, and unstable policy has support.

The Intellectual Capital and the Firm Performance.

The empirical data in the non-financial service sector in Nigeria show that the intellectual capital, including human, structural, and relation, has a positive and significant impact on the

firm performance. The article by Umar and Dandago (2023) demonstrates that companies that invest in the skills of their employees, within organizational processes, and in relations with the stakeholders are more likely to perform better than their counterparts, which supports the economic importance of knowledge-based assets.

Research, Skills Development and Education.

Given that knowledge economy is primarily knowledge based, education is a pivotal initiative. Research on the science education and practical learning in the Nigerian universities hypothesizes that inquiry based and practical methods of learning improve critical thinking and problem-solving skills (Aregbesola et al., 2025). In like manner, Morili et al. (2024) demonstrate how business education and research development boost the ability of Nigeria to be innovative and transform the economy.

Nonetheless, these encouraging signs do not reflect well on the overall research output of Nigeria as compared to its population size and the avenues to commercial or industrial application of the academic research are weak.

Structural Transition Barriers.

A number of endemic issues are still affecting the preparedness of Nigeria to knowledge-based economy.

To begin with, education and labour market mismatch permeate the learning curriculums. Rigor mortis between institutions and employers: The lack of practical training exposes the graduates to many graduates who do not have industry-relevant skills, which is a result of underinvestment in education and weak connections between educational institutions and employers.

Second, the lack of infrastructure deficits is also a fundamental bottleneck. Poor electricity connectivity, poor broadband connectivity, and poor distribution of ICT undermines the effectiveness of knowledge creation and distribution, especially in rural and underserved regions.

Third, there is poor development in research commercialization. Although universities and research institutes produce scholarly production, little has been established to protect intellectual property, technology transfer or startup incubation leading to low rates of uptake of innovation.

Lastly, policy and institutional inefficiencies such as divided systems of governance, and uneven execution limit long-term development. There is also a lack of coordination between the government agencies, academia and the private sector that further undermines the innovation ecosystem.

Table 2: Structural Constraints and Strategic Responses

Constraint	Description	Strategic Response
Skills mismatch	Graduates lack industry-relevant skills	Curriculum reform and TVET expansion
ICT deficits	Limited broadband and unstable power	Public-private infrastructure investment
Weak commercialization	Low research-to-market conversion	Technology transfer offices and IP laws
Policy fragmentation	Poor institutional coordination	Integrated national strategy

Strategic Policy Pathways

Nigeria needs to organize reforms in many sectors to hasten the conversion of its economy into a knowledge-based one.

Education Reform and Skills Alignment.

Way up the ladder, the curricula must focus on critical thinking, digital literacy, and problem-solving. The gap in skills can be narrowed with the technical and vocational education and training as well as the constant improvement of the teachers which can lead to better graduate employability.

Fortifying Research and Innovation Systems.

More and continued investment in research institutions is required. The economic relevance of research outputs can be promoted by incentives to university-industry collaboration together with explicit guidelines on protection of intellectual property and commercialization. Specific development of science, technology, engineering, and mathematics subjects is of special significance.

Digital Infrastructure Investment is associated with the 5.31 Digital Infrastructure.

Digital inclusion preconditions developing broadband infrastructure, stabilizing power supply, and enhancing access to ICT. Companied by involvement of the private sector, public investment can decrease the disparities at the regional level and encourage the countrywide involvement in the knowledge economy.

Entrepreneurship and Public-Private Cooperation.

Entrepreneurship in knowledge-intensive industries, including ICT, fintech, and biotechnology, can be triggered by the introduction of innovation centers, availability of venture capital, and streamlined regulation practices. Technology transfer and entry into the market can also be achieved through stronger partnerships between the public and the private.

Conclusion

It is not just the desirable; but also, the must-have that Nigeria needs to transform to a knowledge-based economy to be able to achieve sustainable development in a fast-evolving global world. Although the difficulties associated with the quality of education, infrastructure, and institutional alignment are still present, the current studies and new programs show a great potential. Nigeria can transition away resource dependence to an innovation-driven, resilient growth strategy through a focus on human capital building, enhancing research and innovation systems, and promoting digital and entrepreneur ecosystems. There is need to rely on longitudinal evaluations of policy interventions in future and comparative assessments with other Sub-Saharan African economies that are undertaking similar transition.

References

- Aregbesola, B. G., Eze, C., & Yusuf, A. (2025). Building a knowledge-based economy through “sciencing”: The University of Abuja students’ experiences. *International Journal of Innovative Engineering and Science*, 4(1), 55–67.
- Don-Solomon, A. (2025). Infopreneurship: A catalyst for knowledge economy development in Nigeria. *SIAR Journal of Business and Management*, 3(2), 44–56.
- Morili, B. A., Omokhudu, J., & Osagie, E. (2024). Business education, research development and the knowledge-based economy. *AAU Journal of Business and Economics*, 12(1), 88–101.
- OECD. (1996). *The knowledge-based economy*. Organisation for Economic Co-operation and Development.
- Umar, A., & Dandago, K. I. (2023). The knowledge economy: How intellectual capital drives financial performance of non-financial service firms in Nigeria. *FUJAFR: Federal University Dutsin-Ma Journal of Accounting and Finance Research*, 5(1), 22–35.

**INTERACTION BETWEEN THE EFQM EXCELLENCE MODEL 2025 REVISION
AND THE ISO 9001 QUALITY MANAGEMENT SYSTEM: AN INTEGRATED
MANAGEMENT APPROACH**

Dr.Ömer Özkan (ORCID: 0000-0002-0752-307X)
SOCAR Türkiye, Kalite Yönetimi Müdürlüğü, İstanbul

ABSTRACT

In today's organizational context, entities are required to manage quality, sustainability, innovation, and increasing stakeholder expectations simultaneously through an integrated and holistic perspective. This multidimensional configuration of expectations necessitates moving beyond traditional management systems that are primarily based on compliance with standards, and calls for a reconceptualization of quality management from the perspectives of strategic orientation, corporate governance, and long-term value creation.

In this context, the 2025 revision of the EFQM Excellence Model provides a comprehensive excellence framework that evaluates organizational performance not solely through outputs and results, but also through purpose, leadership behaviors, engagement with the stakeholder ecosystem, and transformation capabilities. The EFQM 2025 approach repositions quality from a static performance assessment tool to a dynamic management model that measures organizations' future readiness and sustainable success capacity.

In contrast, the ISO 9001 Quality Management System equips organizations with operational discipline, consistency, and repeatability through its process-based management approach, risk-based thinking, and principles of continual improvement. The ISO 9001:2015 standard links quality management to the organizational context and strategic direction, thereby ensuring the systematic monitoring and continual improvement of process performance. However, due to its structural characteristics, the standard addresses more abstract and behavioral dimensions—such as organizational purpose, culture, and transformation—only to a limited extent.

This study aims to examine the conceptual, structural, and functional interaction between the EFQM Excellence Model 2025 and the ISO 9001:2015 standard, and to propose an integrated management perspective for their combined application. A qualitative research methodology was adopted, employing an extensive literature review and a comparative model analysis. Within this framework, areas of alignment and complementarity between the EFQM 2025 “Direction–Execution–Results” architecture and the ISO 9001 requirements related to context analysis, leadership, process management, performance measurement, and continual improvement were systematically analyzed.

The findings demonstrate that ISO 9001 provides a strong operational foundation for the EFQM Model, while EFQM 2025 complements ISO 9001 practices by incorporating strategic orientation, organizational culture, leadership behaviors, and sustainability dimensions. Within this context, quality management is no longer limited to process control and compliance; rather, it becomes a strategic instrument for strengthening long-term value creation, building stakeholder trust, and enhancing organizational transformation capacity.

Keywords: EFQM 2025, ISO 9001, Corporate Excellence, Integrated Management Systems, Quality Management, Sustainability

ÖZET

Günümüzde organizasyonlar; kalite, sürdürülebilirlik, inovasyon ve artan paydaş beklentilerini eş zamanlı ve bütünleşik bir bakış açısıyla yönetmek zorundadır. Bu çok boyutlu beklenti yapısı, yalnızca standartlara uyumu esas alan geleneksel yönetim sistemlerinin ötesine geçilmesini ve kalite yönetiminin stratejik yönelim, kurumsal yönetişim ve uzun vadeli değer yaratma perspektifiyle yeniden ele alınmasını gerekli kılmaktadır. Bu bağlamda, EFQM Excellence Model’nin 2025 revizyonu, organizasyonların performanslarını yalnızca çıktılar ve sonuçlar üzerinden değil; amaç, liderlik davranışları, paydaş ekosistemi ile etkileşim ve dönüşüm yetkinlikleri üzerinden değerlendiren bütüncül bir mükemmellik çerçevesi sunmaktadır. EFQM 2025 yaklaşımı, kaliteyi statik bir performans değerlendirme aracı olmaktan çıkararak, organizasyonların geleceğe hazırlık ve sürdürülebilir başarı kapasitelerini ölçen dinamik bir yönetim modeli olarak konumlandırmaktadır.

Buna karşılık, ISO 9001 Kalite Yönetim Sistemi, süreç temelli yönetim yaklaşımı, risk odaklı düşünme ve sürekli iyileştirme ilkeleri aracılığıyla organizasyonlara operasyonel disiplin, tutarlılık ve tekrar edilebilirlik kazandırmaktadır. ISO 9001:2015 standardı, kalite yönetimini organizasyonun bağlamı ve stratejik yönüyle ilişkilendirerek, süreç performansının sistematik biçimde izlenmesini ve iyileştirilmesini güvence altına almaktadır. Ancak standardın yapısı gereği, amaç, kültür ve dönüşüm gibi daha soyut ve davranışsal boyutları sınırlı ölçüde ele aldığı görülmektedir.

Bu çalışma, EFQM 2025 Modeli ile ISO 9001:2015 standardı arasındaki kavramsal, yapısal ve işlevsel etkileşimi incelemeyi ve iki yaklaşımın birlikte kullanımına yönelik bütünleşik bir yönetim perspektifi ortaya koymayı amaçlamaktadır. Çalışmada nitel araştırma yöntemi benimsenmiş; kapsamlı bir literatür taraması ile karşılaştırmalı model analizi gerçekleştirilmiştir. Bu kapsamda, EFQM 2025’in “Direction–Execution–Results” (Yön–Uygulama–Sonuçlar) mimarisi ile ISO 9001’in bağlam analizi, liderlik, süreç yönetimi, performans ölçümü ve sürekli iyileştirme gereklilikleri arasındaki örtüşme ve tamamlayıcılık alanları sistematik biçimde analiz edilmiştir.

Elde edilen bulgular, ISO 9001’in EFQM Modeli için güçlü bir operasyonel altyapı sunduğunu; EFQM 2025’in ise ISO 9001 uygulamalarını stratejik yönelim, örgütsel kültür, liderlik davranışları ve sürdürülebilirlik boyutlarıyla tamamladığını ortaya koymaktadır. Bu çerçevede kalite yönetimi, yalnızca süreçlerin kontrolü ve uyumun sağlanmasıyla sınırlı kalmamakta; organizasyonların uzun vadeli değer yaratma, paydaş güveni oluşturma ve dönüşüm kapasitesini güçlendirme aracı haline gelmektedir.

Anahtar Kelimeler: EFQM 2025, ISO 9001, Kurumsal Mükemmellik, Entegre Yönetim Sistemleri, Kalite Yönetimi, Sürdürülebilirlik

1. INTRODUCTION

Global competition, digital transformation, and increasing sustainability pressures are fundamentally reshaping organizational management approaches. Management systems that focus solely on short-term performance indicators are no longer sufficient to ensure organizations’ long-term resilience and value creation capacity. In this context, quality management has evolved beyond an operational control mechanism and has become one of the core components of strategic management and corporate governance.

The interaction between quality management systems and excellence models lies at the center of this transformation process. While standards such as ISO 9001 provide organizations with process discipline, consistency, and a structured approach to continual improvement, the EFQM

Excellence Model addresses more holistic dimensions, including leadership behaviors, organizational culture, stakeholder value, and transformation capability.

The 2025 revision of the EFQM Excellence Model introduces a new paradigm by evaluating quality not solely from a “results” perspective, but through how organizations think, manage, and transform themselves (EFQM, 2024). Accordingly, this study aims to analyze the interaction between EFQM 2025 and ISO 9001 and to propose a conceptual and practice-oriented framework for their integrated application.

2. THE EFQM EXCELLENCE MODEL 2025 REVISION: HISTORICAL DEVELOPMENT AND A NEW PARADIGM

The EFQM Excellence Model was developed in 1989 with the aim of enhancing the competitiveness of organizations in Europe and was first implemented in 1991 (EFQM, 2024). The early versions of the model, influenced by the principles of Total Quality Management (TQM), primarily emphasized process excellence, customer satisfaction, and results orientation.

Over time, changes in the business environment necessitated regular revisions of the model. The 1999 and 2003 revisions strengthened performance measurement and leadership criteria, while the 2010 and 2013 revisions made the concepts of sustainable success and stakeholder orientation more prominent (van der Wiele & Brown, 2002).

The 2020 revision marked a significant turning point for the EFQM Model by redefining excellence not merely in terms of “best practices,” but through purpose, value creation, and transformation capability (EFQM, 2020).

Building on this transformation, the EFQM 2025 revision further deepens this perspective by offering a holistic approach that evaluates organizations not only based on performance results, but also on why they exist, for whom they create value, and how well they are prepared for the future (EFQM, 2024). The model structures this approach around three core dimensions: Direction, Execution, and Results.

From this perspective, EFQM 2025 transforms quality from a static assessment tool into a dynamic, learning-oriented, and transformation-driven excellence model.

3. THE DEVELOPMENT OF THE ISO 9001 QUALITY MANAGEMENT SYSTEM

The ISO 9001 standard was first published in 1987 and initially functioned as a quality assurance standard that addressed quality primarily through product conformity and documentation requirements (ISO, 2015). In these early versions, quality was largely equated with compliance with procedures and the maintenance of records.

The 1994 revision introduced a stronger emphasis on preventive actions; however, the bureaucratic nature of the standard was widely criticized. A major paradigm shift occurred with the 2000 revision, which repositioned quality management around the principles of the process approach, customer focus, and continual improvement (Oakland, 2014). With this revision, ISO 9001 evolved from a quality assurance standard into a comprehensive management system standard.

The 2008 revision focused on clarifying the existing structure, whereas the most significant transformation was realized with the 2015 revision. ISO 9001:2015 explicitly linked quality management to the organization’s strategic context, stakeholder expectations, and the concept of risk-based thinking (ISO, 2015; Sampaio et al., 2009). As a result, quality management was placed under the direct responsibility of top management and integrated into the organization’s overall management system.

Nevertheless, ISO 9001 largely remains a standard oriented toward “how” activities should be performed, addressing more abstract dimensions—such as organizational purpose, culture, and transformation—only to a limited extent. In this respect, the EFQM Excellence Model provides a complementary strategic framework that extends the scope of ISO 9001 beyond operational compliance.

From a corporate governance perspective, quality management systems are increasingly viewed not only as mechanisms for operational conformity, but also as integral components of board-level responsibility and accountability (Tricker, 2019; Solomon, 2020). The strategic management literature further emphasizes that alignment between quality management and strategic objectives is critical for achieving sustainable competitive advantage (Porter, 1996; Kaplan & Norton, 2008).

Empirical studies examining the impact of ISO 9001 on organizational performance support the standard's role in fostering process discipline and performance improvement (Corbett et al., 2005; Benner & Veloso, 2008). In parallel, research on the EFQM Excellence Model highlights the significance of the relationships between leadership, organizational culture, and results, thereby underscoring the multidimensional nature of organizational excellence (Bou-Llusar et al., 2009; Calvo-Mora et al., 2015).

4. INTERACTION BETWEEN EFQM 2025 AND ISO 9001

The interaction between the EFQM Excellence Model 2025 and the ISO 9001 Quality Management System enables quality management and corporate excellence to be addressed within an integrated management system framework. The process-based, discipline-oriented, and standardizing structure of ISO 9001 provides a solid foundation for translating the more abstract, conceptual, and strategic dimensions of the EFQM Model into operational practice. In this respect, ISO 9001 functions as an operational infrastructure for EFQM, while EFQM 2025 deepens ISO 9001 practices through strategic orientation, purpose, and value creation perspectives.

4.1. Interaction in the Leadership, Purpose, and Direction Dimension

The ISO 9001:2015 standard positions leadership as the primary actor responsible for the effectiveness of the quality management system and requires the active involvement of top management in organizational processes (ISO, 2015). However, this approach tends to conceptualize leadership mainly in terms of structural responsibility and resource allocation.

In contrast, the EFQM 2025 Model defines leadership as a role that shapes organizational purpose, represents core values, and drives transformation (EFQM, 2024). From this perspective, the “Direction” dimension of EFQM complements the leadership requirements of ISO 9001 by elevating leaders from being merely system owners to role models, sources of inspiration, and ethical guides. Consequently, the leadership requirements of ISO 9001 gain deeper meaning when integrated with the purpose-driven and values-based approach offered by EFQM 2025.

4.2. Interaction in the Process Management, Value Creation, and Execution Dimension

The process approach, which constitutes one of the fundamental pillars of ISO 9001, enables the identification, measurement, and improvement of organizational activities. This structure provides the practical basis for implementing the value creation mechanisms addressed under the “Execution” dimension of the EFQM 2025 Model.

EFQM 2025 conceptualizes value creation not merely as a customer-oriented output, but as a process of generating sustainable benefits for employees, business partners, society, and the broader stakeholder ecosystem (EFQM, 2024). The process discipline ensured by ISO 9001 contributes to making this multidimensional understanding of value creation measurable, traceable, and manageable. In this sense, ISO 9001 connects the EFQM approach to value creation with operational reality.

4.3. Interaction in the Performance, Measurement, Analysis, and Results Dimension

One of the most frequently cited criticisms of the EFQM Model is that assessments may at times rely on subjective perceptions. The measurement, analysis, internal audit, and continual improvement requirements of ISO 9001 mitigate this risk by rendering the “Results” dimension of EFQM more evidence-based (Sampaio et al., 2009).

ISO 9001 mandates the definition of performance indicators, the systematic analysis of data, and the structured implementation of improvement activities. This framework enhances the reliability of performance and perception results used in EFQM assessments and supports more objective and consistent organizational self-assessment processes. As a result, EFQM result criteria, when supported by ISO 9001 data, provide stronger inputs for strategic decision-making processes.

4.4. Evaluation from an Integrated Management Perspective

The interaction between EFQM 2025 and ISO 9001 transforms quality management from a system focused solely on compliance and control into a governance instrument integrated with purpose, strategy, and transformation. While ISO 9001 primarily addresses the question of “how” activities should be carried out, EFQM 2025 systematically addresses the questions of “why” and “for what purpose.”

The combined application of these two approaches strengthens both the short-term operational performance and the long-term sustainability and resilience capacities of organizations. Therefore, the EFQM 2025–ISO 9001 interaction can be regarded as one of the key elements of strategic integration for modern organizations.

5. RESEARCH AND FINDINGS

The findings of this study demonstrate that the relationship between the EFQM Excellence Model 2025 revision and the ISO 9001 Quality Management System is complementary and mutually reinforcing in nature. The literature generally approaches quality management systems primarily from the perspective of operational efficiency and process control, whereas excellence models tend to focus more on strategic orientation, leadership behaviors, and cultural maturity. This distinction has often led, in practice, to a reductionist perception that “ISO 9001 is operational, whereas EFQM is strategic.” However, the EFQM 2025 revision substantially redefines this dichotomy.

The “Direction–Execution–Results” architecture of EFQM 2025 provides a structure that can be directly aligned with ISO 9001 requirements related to context analysis, the process approach, and performance evaluation. In particular, the emphasis on purpose-driven leadership and leadership behaviors within the “Direction” dimension elevates the leadership clause of ISO 9001 beyond a mere definition of responsibility, rendering it more meaningful and guiding. This alignment strengthens the integration of quality management with strategic management.

Similarly, the value creation and stakeholder ecosystem perspective addressed under the “Execution” dimension is supported by ISO 9001 principles related to process management and customer focus. The process discipline ensured by ISO 9001 enables the practical implementation of the value creation mechanisms that are defined at an abstract level within the EFQM Model. In this respect, ISO 9001 functions as an operational infrastructure for EFQM.

Within the “Results” dimension, the measurement, analysis, and continual improvement requirements of ISO 9001 mitigate the risk of subjectivity that is frequently cited as a limitation of EFQM assessments, thereby contributing to a more evidence-based evaluation of results. As a consequence, the EFQM Model evolves from a purely self-assessment-oriented approach into a more measurable and verifiable framework.

Within this discussion framework, it can be argued that considering EFQM 2025 and ISO 9001 together entails not only a technical integration, but also a transformation in managerial mindset. When the compliance- and consistency-oriented approach of ISO 9001 is combined with the meaning-, purpose-, and transformation-oriented perspective of EFQM, a more balanced and sustainable management model emerges for organizations.

6. CONCLUSION

This study aimed to provide an integrated perspective on the interaction between the EFQM Excellence Model 2025 revision and the ISO 9001 Quality Management System within the domains of quality management and corporate excellence. The analyses clearly demonstrate that these two approaches are not alternatives to one another; rather, they are complementary and mutually reinforcing.

While ISO 9001 equips organizations with process discipline, risk-based thinking, and a culture of continual improvement, the EFQM 2025 Model deepens this foundation by incorporating dimensions related to purpose, leadership, stakeholder value, and sustainable transformation. This integrated approach moves quality beyond a documentation-based system and positions it as an integral component of corporate governance and strategic management.

One of the most significant implications of the study is that EFQM 2025 renders ISO 9001 practices more meaningful and directional. Whereas ISO 9001 primarily addresses the question of “how” activities should be carried out, EFQM 2025 systematically addresses the questions of “why” and “for what purpose.” The combined application of these two approaches strengthens not only organizations’ current performance, but also their future resilience and adaptability capacities.

From an implementation perspective, the integration of EFQM 2025 and ISO 9001 offers substantial opportunities for strengthening strategy–operations alignment, systematizing leadership behaviors, enhancing stakeholder trust, and managing innovation as a structured and governable process. Particularly under contemporary conditions characterized by heightened uncertainty, sustainability pressures, and digital transformation challenges, this integration creates a competitive advantage for organizations.

In conclusion, this study demonstrates that jointly considering the EFQM Excellence Model 2025 revision and the ISO 9001 Quality Management System transforms quality management from a static structure into a dynamic, human-centered, and sustainability-driven excellence journey. Future research may make valuable contributions to both the literature and practice by empirically testing this integrated approach through application cases across different sectors.

REFERENCES

- Benner, M. J., & Veloso, F. M. (2008). ISO 9000 practices and financial performance. *Strategic Management Journal*, 29(9), 965–986.
- Bou-Llusar, J. C., Escrig-Tena, A. B., Roca-Puig, V., & Beltrán-Martín, I. (2009). An empirical assessment of the EFQM excellence model. *International Journal of Quality & Reliability Management*, 26(8), 800–821.
- Calvo-Mora, A., Picón-Berjoyo, A., Ruiz-Moreno, C., & Cauzo-Bottala, L. (2015). Contextual and mediation analysis between TQM critical factors and organisational results. *International Journal of Operations & Production Management*, 35(1), 115–143.
- Corbett, C. J., Montes-Sancho, M. J., & Kirsch, D. A. (2005). The financial impact of ISO 9000 certification. *Management Science*, 51(7), 1046–1059.
- European Foundation for Quality Management (EFQM). (2020). The EFQM Model. Brussels.
- European Foundation for Quality Management (EFQM). (2024). The EFQM Model 2025. Brussels.
- International Organization for Standardization. (2015). ISO 9001:2015 Quality management systems — Requirements. Geneva.
- Kaplan, R. S., & Norton, D. P. (2008). Execution premium. Harvard Business School Press.
- Oakland, J. S. (2014). Total Quality Management and Operational Excellence. Routledge.
- Porter, M. E. (1996). What is strategy? *Harvard Business Review*, 74(6), 61–78.

INTERNATIONAL TOPKAPI CONGRESS VI

- Sampaio, P., Saraiva, P., & Rodrigues, A. (2009). ISO 9001 certification research. *International Journal of Quality & Reliability Management*, 26(1), 38–58.
- Tricker, B. (2019). *Corporate governance: Principles, policies, and practices*. Oxford University Press.
- van der Wiele, T., & Brown, A. (2002). Quality management over a decade. *International Journal of Quality & Reliability Management*, 19(5), 508–523.

**ÇEVRECİLİĞİN SÖYLEMSEL İNŞASI: DEĞERLER, SİYASET VE EKONOMİ
EKSENLERİNDE ÇEVRECİ KODLAR**

THE DISCURSIVE CONSTRUCTION OF ENVIRONMENTALISM: ENVIRONMENTAL
CODES ACROSS THE AXES OF VALUES, POLITICS, AND ECONOMY

Dr. Öğretim Üyesi Özkan ÖZTÜRK

Karabük Üniversitesi, Sosyoloji Bölümü

ORCID NO: 0000-0001-6165-5009

Dr. Öğretim Üyesi Zeynep KURNAZ

Karabük Üniversitesi, Sosyoloji Bölümü

ORCID NO: 0000-0002-7648-8992

ÖZET

Bu çalışma, çevreciliğin söylemsel inşasını değerler, siyaset ve ekonomi alanlarında üretilen “çevreci kodlar” üzerinden çözümlemeyi amaçlamaktadır. Yeni toplumsal hareketler literatüründen hareketle çevre hareketlerinin, iktidarı ele geçirmeye odaklı klasik hareketlerden farklı olarak, toplumsal sorunları değer temelli bir çerçevede tanımladığı ve çevre krizini demokrasi, adalet ve ekonomi tartışmalarıyla iç içe geçen yapısal bir meseleye dönüştürdüğü savunulmaktadır. Kavramsal çerçeve olarak Pepper’ın (2008) insan-doğa-teknoloji, siyaset ve ekonomi eksenlerini ayırt eden şeması kullanılmakta; çevreci kodlar bu üç düzlemde metin temelli kuramsal bir çözümlemeyle yeniden okunmaktadır. Bulgular, değerler düzleminde çevreciliğin doğanın içkin değerini tanıyan, insan-doğa ilişkisindeki eşitsizliği doğa lehine dengelemeyi ve teknolojinin demokratikleştirilmesini talep eden bir etik ürettiğini göstermektedir. Siyasal düzlemde çevreci kodlar, temsili demokrasinin sınırlarını aşan, yerel toplulukların belirleyici aktör olduğu katılımcı ve müzakereci bir demokrasi anlayışı kurmakta; çevre sorunlarının çözümünü sosyo-ekonomik ve politik sistemin dönüşümüne bağlamaktadır. Ekonomik düzlemde ise kaynak kullanımının ve üretim süreçlerinin sınırlandırılması, ihtiyaç temelli planlama ve küçük ölçekli yerel üretim ilkeleriyle, liberal büyüme mantığına alternatif bir rasyonalite geliştirilmekte; zenginlik, ekosistemin kendini yeniden üretebilme kapasitesi ve ihtiyaçların adil karşılanması üzerinden yeniden tanımlanmaktadır. Sonuç olarak çalışma, çevreciliğin ortak çekirdeğinde eşitlikçi, adil ve ekolojik bir toplum-çevre ilişkisinin yer aldığını ve çevreci kodların çağdaş siyasal düşünce için kurucu bir referans çerçevesi sunduğunu ileri sürmektedir.

Anahtar Kelimeler: Çevreci Değerler, Çevreci Siyaset, Çevreci Ekonomi

ABSTRACT

This study aims to analyze the discursive construction of environmentalism through “environmental codes” produced within the domains of values, politics, and economy. Drawing on the literature on new social movements, it argues that environmental movements, unlike classical movements oriented toward the seizure of political power, define social problems within a value-based framework and transform the environmental crisis into a structural issue intertwined with debates on democracy, justice, and economy. As a conceptual framework, the study employs Pepper’s (2008) schema, which distinguishes between the axes of human–nature–technology relations, politics, and economy; environmental codes are re-examined across these three dimensions through a text-based theoretical analysis. The findings indicate that, at the level of values, environmentalism articulates an ethical stance that recognizes the

intrinsic value of nature, seeks to redress the asymmetry in human–nature relations in favor of nature, and calls for the democratization of technology. At the political level, environmental codes advance a participatory and deliberative understanding of democracy that transcends the limits of representative democracy and positions local communities as key actors, linking the resolution of environmental problems to the transformation of socio-economic and political systems. At the economic level, an alternative rationality to liberal growth-oriented logic is developed through principles such as limiting resource use and production processes, needs-based planning, and small-scale local production; within this framework, wealth is redefined in terms of the ecosystem’s capacity for self-regeneration and the equitable satisfaction of needs. In conclusion, the study argues that the shared core of environmentalism is grounded in an egalitarian, just, and ecological relationship between society and nature, and that environmental codes provide a constitutive frame of reference for contemporary political thought.

Keywords: Environmental Values, Environmental Politics, Environmental Economy

GİRİŞ

Çevrecilik, yalnızca belirli çevre sorunlarına verilen tepkilerin toplamı değil, aynı zamanda belli bir dünya tasavvurunu ifade eden, değerler, siyaset ve ekonomi alanlarında özgül “kodlar” üreten bir söylemsel bütündür. Bu söylemsel bütün, yirminci yüzyılın ikinci yarısında ortaya çıkan yeni toplumsal hareketler bağlamında şekillenmiş, klasik iktidar merkezli siyaset anlayışının dışına taşan yeni bir politik dil geliştirmiştir. Yeni toplumsal hareketler, siyasal iktidarı ele geçirmeyi hedefleyen örgütlenmelerden çok, toplumsal yaşamın farklı alanlarında ortaya çıkan sorunları tanımlayan ve bu sorunlar etrafında değer temelli talepler formüle eden hareketler olarak öne çıkmıştır. Çevreci hareketler de bu bağlam içinde, çevre sorunlarını yalnızca teknik ya da idari sorunlar olmaktan çıkarıp toplumsal bir problem alanı ve aynı zamanda bir “değerler alanı” olarak kodlamışlardır (Coşkun, 2006; Larana vd., 1994).

Bu dönüşüm, çevre sorunlarının tanımlanış biçiminde açıkça görülebilir. Sanayi üretimi, fosil yakıtlara dayalı enerji rejimleri ve büyüme odaklı ekonomi politikaları, çevre tahribatının temel kaynakları olarak teşhis edilmiş; bu teşhis, çevre krizini hem modern kapitalist toplumların işleyiş mantığıyla hem de insan-doğa ilişkisinin tarihsel kurgusuyla ilişkilendiren bir söylemsel çerçeve üretmiştir. Çevreci hareketler, çevre sorunlarını yalnızca “kirlilik” ya da “doğal kaynakların tükenmesi” sorunu olarak değil; toplumsal adalet, demokrasi, katılım ve iktidar ilişkileriyle iç içe geçmiş yapısal sorunlar olarak ele almışlardır. Böylece çevrecilik, teknik mühendislik çözümlerinden ibaret bir reform programı olmaktan ziyade, alternatif bir toplum tasavvuruyla bağlantılı siyasal bir söylem hâline gelmiştir.

Çevrecilik söyleminin bu niteliği, onu hem düşünsel hem de pratik düzeyde sürekli yeniden üretilen bir “kodlar bütünü” olarak anlamayı gerektirir. Bu kodlar, bir yandan insan–doğa–teknoloji ilişkisine dair değerler üretir; diğer yandan siyasal alanı yeniden tanımlayan demokrasi ve katılım tasavvurlarını, son olarak da ekonomi alanında ihtiyaç, planlama ve sınır kavramları etrafında şekillenen alternatif yaklaşımları içerir. Pepper’ın (2008) geliştirdiği şema, çevreciliğin bu üç düzlemde –insan/doğa/teknoloji, siyaset ve ekonomi– yoğunlaşan temel ilkelerini görünür kılan önemli bir araç sunmaktadır.

Bu metin, çevreciliğin söylemsel inşasını bu üç düzlemde beliren “çevreci kodlar” üzerinden incelemeyi amaçlamaktadır. Araştırma sorusu, kabaca şöyle formüle edilebilir: Çevreciliğin çekirdek söylemi, değerler, siyaset ve ekonomi alanlarında nasıl kodlanmakta; bu kodlar hangi ortak ilkeler etrafında birleşerek “çevreci toplum” tasavvuruna zemin hazırlamaktadır? Metnin ilerleyen kısımlarında önce kavramsal çerçeve tartışılacak, ardından Pepper’ın şemasından ve çevre hareketleri literatüründen hareketle bu üç alana ilişkin kodlar çözümlenecek; son bölümde ise elde edilen bulguların çevrecilik düşüncesi ve siyasal teori açısından ne anlama geldiği tartışılacaktır.

KAVRAMSAL ÇERÇEVE

Çevreciliğin söylemsel inşasını ele alırken iki kavram eksenini temel önem taşımaktadır: yeni toplumsal hareketler yaklaşımı ve çevreci kodlar fikri. Yeni toplumsal hareketler literatürü, 1960’lardan itibaren ortaya çıkan kadın hareketi, barış hareketi, kimlik temelli mücadeleler ve çevre hareketleri gibi oluşumların, klasik sınıf temelli, iktidarı ele geçirmeye odaklı hareketlerden farklı bir mantıkla işlediğini vurgular (Larana vd., 1994). Bu hareketler, “kimlik”, “değer”, “yaşam tarzı” ve “katılım” gibi temalar etrafında şekillenmekte; ekonomik talepler kadar kültürel ve sembolik talepler de üretmektedir. Çevreci hareketler de doğrudan bu kategoriye girer: burada mesele yalnızca belli projelerin durdurulması değil, insan–doğa ilişkisinin adalet, eşitlik ve sorumluluk ekseninde yeniden tanımlanmasıdır.

Söylem kavramı bu noktada belirleyicidir. Çevrecilik söylemi, doğa, toplum, teknoloji, demokrasi ve ekonomi hakkında neyin “doğru”, neyin “meşru” ve neyin “arzu edilir” olduğuna dair bir dizi anlam üretir. Bu anlamlar, yalnızca dilsel ifadeler değil; kurumsal düzenlemeler, örgütlenme biçimleri ve eylem repertuarlarıyla da iç içe geçen normatif yapılardır. “Çevreci kodlar” ifadesi, tam da bu normatif yapıları işaret eder. Kod, hangi durumda hangi tutumun “çevreci” kabul edileceğini; hangi çözüm tarzının ekolojik olarak meşru, hangisinin sorunlu görüleceğini belirleyen ilkesel çerçeveler bütünüdür.

Pepper’ın (2008: 12–14) şeması, çevreciliğin bu kodlarını üç ana alanda toplar: insan–doğa–teknoloji ilişkisi, siyaset ve ekonomi. İnsan–doğa–teknoloji alanında çevreci kodlar, doğanın içkin değeri, insan–doğa ilişkisindeki eşitsizliğin doğa lehine düzeltilmesi ve teknolojinin demokratikleştirilmesi gibi ilkeler etrafında kümelenir. Siyaset alanında ise temsili demokrasinin eleştirisi, katılımcı demokrasinin savunusu, yerel toplulukların asli siyasal aktörler olarak görülmesi ve çevre sorunlarının çözümünün sosyo-ekonomik ve politik dönüşüme bağlanması öne çıkar. Ekonomi alanında ise kaynak kullanımının sınırlandırılması ve planlanması, mal ve hizmet üretiminin ihtiyaç temelli olması, çevresel ve toplumsal zararın ekonomik açıdan irrasyonel kabul edilmesi ve küçük ölçekli, yerel üretim vurgusu dikkat çekicidir.

Bu kavramsal çerçeve, çevrecilik söyleminin yalnızca “korumacı” bir refleks olmadığını; değerler, siyaset ve ekonomi alanlarında birbirini tamamlayan bir normatif yapı sunduğunu gösterir. Bununla birlikte, çevre hareketlerinin tarihsel seyrine bakıldığında, bu kodların homojen ve çelişkisiz olmadığı; zaman içinde farklı coğrafyalarda ve kurumsal bağlamlarda farklı biçimlerde yorumlandığı da görülür (Rootes, 1999). Kurumsallaşma, profesyonelleşme ve siyasal alanla eklemlenme süreçleri, çevreci kodların bir kısmını güçlendirirken bir kısmını zayıflatma potansiyeli taşır. Dolayısıyla “çevreci kodlar”ı hem idealleştirici bir çekirdek hem de pratik mücadele içinde sürekli müzakere edilen anlamlar bütünü olarak düşünmek gerekmektedir.

Bu metinde kavramsal çerçeve, çevreci kodların üç düzlemde –değerler, siyaset ve ekonomi– nasıl kurulduğunu ve aralarındaki iç bağlantıları açığa çıkarmak üzere kullanılmaktadır. Bulgular bölümü, Pepper’ın şeması ile çevre hareketleri literatürünü bir araya getirerek bu kodların ayrıntılı bir çözümlemesini sunacak; böylece çevreciliğin söylemsel çekirdeği görünür kılınacaktır.

BULGULAR

Çevreci kodların ilk yoğunlaştığı alan, insan–doğa–teknoloji ilişkisinin yeniden kurulmasıdır. Çevrecilik söylemi, modern antropomerkezci bakışın tersine, doğayı yalnızca insanlar için yararlı olduğu ölçüde değeri olan bir kaynak değil, kendi başına değere sahip bir bütün olarak görür (Eckersley, 2003). Doğa, çevreci kodlarda, “korunması gereken dışsal bir nesne”den çok, insanların da parçası olduğu, etik ve politik sorumluluk gerektiren bir varlık alanı olarak tanımlanır. Bu tanım, insan–doğa ilişkisindeki asimetrik güç konumunu sorgular; insanın doğa

üzerindeki sınırsız tasarruf hakkı reddedilir. Böylece çevrecilik, doğa lehine bir “dengeleyici adalet” talebi üretir: tarihsel olarak insanın lehine kurulmuş eşitsiz ilişki, doğanın hak ve değerini tanıyan yeni bir düzenlemeyle dönüştürülmelidir.

Teknolojiye ilişkin kodlar da bu bakış açısıyla biçimlenir. Modern söylemde teknolojik ilerleme çoğu zaman kendi başına olumlu, sorgulanamaz bir değer olarak sunulur. Çevreci söylem ise teknolojiye koşullu ve eleştirel yaklaşır. Pepper’ın (2008) ifade ettiği gibi, çevre sorunlarının çözümü yalnızca bilim ve teknolojiye indirgenemez; teknoloji ekolojik ve toplumsal bağlamdan bağımsız bir “nötr araç” değildir. Çevreci kodlar, teknolojinin demokratikleştirilmesi ve sınırlandırılması gereğini vurgular: Teknoloji, doğayla çatışan değil, onunla uyumlu bir ortak yaşamı mümkün kılacak biçimde tasarlanmalı; hangi teknolojinin, hangi amaçla, kimin denetiminde kullanılacağı kamusal tartışmanın konusu olmalıdır. Bu yaklaşım, teknolojiye mutlak bir reddiyeden çok, onu toplumsal ve ekolojik denetim altına alma çabasını ifade eder. Siyaset alanına ilişkin çevreci kodlar, demokrasi kavramının kapsamını genişleten bir nitelik taşır. Çevrecilik söylemi, temsili demokrasinin sınırlarına dikkat çeker; çevre sorunlarının, seçim dönemleriyle sınırlı siyasal döngüler içinde ele alınamayacak kadar uzun erimli ve çok katmanlı olduğuna vurgu yapar (Eckersley, 2004). Bu nedenle katılımcı demokrasi, çevreci siyasal söylemin merkezinde yer alır. Yerel toplulukların karar süreçlerine doğrudan katılımı, müzakere ve uzlaşma mekanizmalarının geliştirilmesi, çevre politikalarının meşruiyeti için temel koşul olarak görülür. Çevre sorunlarının çözümünün sosyo-ekonomik ve politik sistemin değişimini gerektirdiği vurgusu ise, çevreciliğin reformcu yaklaşımlarla sınırlanamayacağını, yapısal dönüşüm talebi taşıdığını gösterir.

Bu bağlamda çevre hareketlerinin pratikleri, çevreci kodların siyasal düzlemde nasıl somutlaştığını gösteren örnekler sunar. Yerel çevre mücadelelerinde görülen “yerel halkın katılımı” ve “tabandan örgütlenme” vurgusu, çevreciliğin demokrasi anlayışının yalnızca teorik değil, pratik bir ilkeye dönüştüğünü gösterir. Yeni toplumsal hareket mantığı içinde şekillenen bu pratik, çözümü yalnızca devletten beklemek yerine, toplumsal özneleşme süreçlerini öne çıkarır. Bununla birlikte, çevre hareketlerinin kurumsallaşması ve profesyonelleşmesi, bu katılımcı-demokratik dinamikleri kısmen zayıflatma riski de taşır: profesyonel çevre örgütleri ve yeşil partiler, çevreci talepleri siyasal temsile aktarmakla birlikte, yerel tabanla aralarına mesafe koyabildikleri ölçüde çevreci kodların radikal potansiyelini sınırlayabilir.

Ekonomi alanındaki çevreci kodlar ise, büyüme odaklı liberal ekonomi anlayışına karşı güçlü bir eleştirel çerçeve sunar. Pepper’ın (2008) vurgulandığı üzere, insanlarla birlikte diğer canlı türlerinin varlığını sürdürebilmesi için kaynak kullanımının ve üretim sürecinin sınırlandırılması ve planlanması gerekir. Bu, yalnızca doğal kaynakların fiziksel sınırlarını kabul etmek değil, aynı zamanda zenginlik ve ihtiyaç kavramlarının yeniden tanımlanmasını gerektirir. Çevreci kodlar açısından mal ve hizmetler, kâr maksimizasyonu ve tüketim kültürü üzerinden değil, toplumsal ihtiyaçlara göre üretilmelidir.

Bu noktada “ihtiyaç–istek ayrımı” belirleyici bir rol oynar. Mevcut ekonomik düzende, reklam, pazarlama ve kredi mekanizmaları aracılığıyla sürekli yeni “istekler” üretilirken, çevreci söylem gerçek ihtiyaçların sınırlandırılmasını ve bu ihtiyaçların ekolojik sınırlar içinde karşılanmasını savunur. Ekonomik rasyonalite kavrayışı da bu çerçevede değişir: en az maliyetle en yüksek kâr elde etmek yerine, en az kaynak kullanarak ve en az ekolojik zarar vererek gerçek ihtiyaçları karşılamak, çevreci rasyonaliteyi ifade eder. Toplumsal ve çevresel zarar üreten faaliyetler bu nedenle ekonomik olarak da irrasyonel kabul edilir.

Uzun erimli ekonomik planlama ve küçük ölçekli, yerel, zanaata dayalı üretim vurguları, bu rasyonalite değişiminin pratik yansımalarıdır. Uzun dönemli planlama, ekosistemlerin yenilenme sürelerini, gelecek kuşakların haklarını ve bölgesel ekolojik dengeleri hesaba katmayı gerektirir. Yerel ve küçük ölçekli üretim ise hem enerji ve kaynak kullanımında hem de karar alma süreçlerinde daha şeffaf ve denetlenebilir yapılar sunarak, çevresel etkilerin daha okunabilir olmasını sağlar. Böylece çevreci kodlar, ekonomik alanı yalnızca teknik bir

verimlilik alanı olmaktan çıkarıp, etik ve politik ilkelere bağlı bir düzenleme alanı olarak yeniden çerçeveler.

Bu üç düzlem birlikte düşünüldüğünde, çevreciliğin söylemsel çekirdeğinde, eşitlikçi ve adil bir toplum-çevre ilişkisinin inşasına dönük bütüncül bir tasavvur bulunduğu söylenebilir. İnsan-doğa-teknoloji alanında içkin değer ve dengeleme, siyaset alanında katılımcı demokrasi ve yerel toplulukların güçlendirilmesi, ekonomi alanında ise ihtiyaç temelli planlama ve sınırlandırma, bu tasavvurun birbirini tamamlayan boyutlarıdır.

SONUÇ

Bu çalışma, çevreciliğin söylemsel inşasını değerler, siyaset ve ekonomi bağlamında üretilen “çevreci kodlar” üzerinden ele alarak, çevrecilik düşüncesinin sadece belirli çevre sorunlarına yönelik teknik çözümler bütünü olmadığını, alternatif bir toplum projesiyle iç içe geçmiş normatif bir çerçeve sunduğunu göstermiştir. Yeni toplumsal hareketler literatürünün işaret ettiği gibi çevre hareketleri, siyaset merkezli ve iktidar odaklı klasik hareketlerden farklı olarak, toplumsal sorunları değerler düzleminde tanımlamakta; çevre krizini insan-doğa ilişkisi, demokrasi ve ekonomi alanlarının kesişiminde konumlandırmaktadır.

Kavramsal çerçeve ve bulgular, çevreci kodların üç düzlemde yoğunlaştığını ortaya koymuştur. Değerler düzleminde çevrecilik, doğanın içkin değerini tanıyan, insan-doğa ilişkisindeki eşitsizliği doğa lehine dengelemeyi hedefleyen ve teknolojiyi demokratikleştirilmesi gereken bir alan olarak gören bir etik üretmektedir. Siyasal düzlemde bu etik, temsili demokrasinin sınırlılıklarını aşmaya çalışan, yerel toplulukları karar süreçlerinin asli aktörleri olarak konumlandıran, doğrudan demokrasi ve uzlaşma mekanizmalarını önemseyen bir demokrasi anlayışına dönüşmektedir. Ekonomik düzlemde ise çevreci kodlar, kaynak kullanımının ve üretim süreçlerinin sınırlandırılması, ihtiyaç temelli planlama ve küçük ölçekli, yerel üretimin teşviki gibi ilkelerle, liberal büyüme mantığına alternatif bir rasyonalite önermektedir.

Bütün bu kodlar birleştğinde, çevrecilik söyleminin çekirdeğinde “çevreci toplum” diyebileceğimiz bir tasavvurun bulunduğu görülmektedir: İnsanların ve diğer canlıların varlığını sürdürebildiği, ekolojik sınırları gözetin; karar alma süreçlerine geniş toplumsal katılımın sağlandığı; zenginliğin, ekosistemin kendini yeniden üretebilme kapasitesi ve ihtiyaçların adil karşılanması üzerinden tanımlandığı bir toplum. Bu tasavvur, elbette ki tek ve yekpare değildir; çevre hareketlerinin kurumsallaşması, profesyonelleşmesi ve siyasal alanla eklemlenmesi süreçlerinde sürekli müzakere edilmekte ve kimi zaman da zayıflamaktadır. Ancak yine de çevreci kodların bu çekirdek ilkeleri, çevrecilik söyleminin farklı varyantları arasında belirli bir süreklilik ve ortaklık alanı yaratmaktadır.

Sonuç olarak, çevreciliğin söylemsel inşasını anlamak, günümüz ekolojik krizi karşısında hangi değerlerin, hangi siyasal kurumların ve hangi ekonomik düzenlemelerin savunulduğunu ve savunulabileceğini kavramak açısından kritik bir önem taşımaktadır. Değerler, siyaset ve ekonomi alanlarında üretilen çevreci kodlar, yalnızca çevre politikalarının içeriğini değil, demokrasinin, adaletin ve toplumsal refahın nasıl tanımlanacağına ilişkin daha geniş bir tartışmanın da zeminini oluşturmaktadır. Bu nedenle çevrecilik, çağdaş siyasal düşünce ve toplumsal teori açısından, üzerinde durulması gereken marjinal bir söylem değil, giderek merkezî hâle gelen kurucu bir referans çerçevesidir.

KAYNAKÇA

Coşkun, M. K. (2006). Süreklilik ve Kopuş Teorileri Bağlamında Türkiye’de Eski Ve Yeni Toplumsal Hareketler, *Ankara Üniversitesi SBF Dergisi* 61-1, 67-102.

Eckersley, R., (2003), *Environmentalism And Political Theory: Toward an Ecocentric Approach*. London: ULC.

INTERNATIONAL TOPKAPI CONGRESS VI

Eckersley, R., (2004), The Green State: Rethinking Democracy and Sovereignty. London: MIT.

Larana, E., Johnston, H., Gusfield, G. (1994). New Social Movements: From Ideology to Identity Philadelphia: Temple University Press.

Pepper, D. (2008). Modern Environmentalism: An Introduction. London: Routledge.

Rootes, C., (1999), Environmental Movements: From Local To Global, Environmental Politics, 8:1, 1-12.

**YAZILIM HATA TAHMİNİ DOĞRULUĞUNUN ARTIRILMASI: ÇOK AMAÇLI
ATEŞBÖCEĞİ ALGORİTMASI YAKLAŞIMI**
ENHANCING SOFTWARE DEFECT PREDICTION ACCURACY: A MULTI-
OBJECTIVE FIREFLY ALGORITHM APPROACH

Doç.Dr. Peri GÜNEŞ

İnfina Yazılım A.Ş.,
Ar-Ge Departmanı, Üsküdar, İstanbul.

Doç. Dr. Sina APAK

Dr. Öğr. Üyesi, İstanbul Aydın Üniversitesi,
Bilgi Teknolojileri Yönetim Departmanı, Küçükçekmece, İstanbul.

Yahya D. Navaei

Yüksek Lisans Öğrencisi, Qazvin Islamic Azad University,
Bilgisayar Mühendisliği ve Bilgi Teknolojileri Departmanı, Qazvin, İran.

Harun BENLİ

İnfina Yazılım A.Ş.,
Ar-Ge Departmanı, Üsküdar, İstanbul.

ÖZET

Yazılım mühendisliğinde yüksek yazılım kalitesi ve güvenilirliğinin sağlanması temel hedeflerden biridir. Yazılım Hata Tahmini (Software Defect Prediction - SDP), geliştirme yaşam döngüsünün erken aşamalarında hataya yatkın modüllerin belirlenmesi ve bu hataların azaltılması açısından kritik bir süreçtir; böylece maliyetler düşürülür ve son kullanıcı deneyimi iyileştirilir. Ancak makine öğrenmesi tabanlı SDP modellerinin etkinliği, büyük ölçüde etkili özellik seçimine bağlıdır. Bu çalışma, özellik seçimi için çok amaçlı bir ateşböceği optimizasyon algoritması kullanan yeni bir SDP yöntemi önermektedir. Bu optimizasyon yaklaşımı, hata veri kümelerindeki yüksek boyutluluk sorununu ele almak üzere özel olarak tasarlanmıştır. Yaklaşım, iki hedefi eşzamanlı olarak minimize eder: seçilen özelliklerin sayısı ve tahmin modelinin sınıflandırma hata oranı. Önerilen yöntemi doğrulamak amacıyla model, kamuya açık NASA depo (repository) veri kümeleri kullanılarak eğitilmiş ve değerlendirilmiştir. Deneysel sonuçlar, yaklaşımımızın %93,02'lik bir tahmin doğruluğuna ulaştığını göstermektedir. Bu bulgu, önceki en güncel (state-of-the-art) yöntemlere kıyasla performansta anlamlı bir iyileşmeye işaret etmekte ve algoritmanın daha güvenilir ve yüksek kaliteli yazılım sistemleri geliştirmedeki etkinliğini ortaya koymaktadır.

Anahtar Kelimeler: Yazılım Hata Tahmini, Özellik Seçimi, Çok Amaçlı Ateşböceği Algoritması, Denetimli Öğrenme, Sınıflandırma.

ABSTRACT

Ensuring high software quality and reliability is a primary objective in software engineering. Software Defect Prediction (SDP) is a critical process for identifying and mitigating defect-prone modules early in the development lifecycle, thereby reducing costs and enhancing the end-user experience. The efficacy of machine learning-based SDP models, however, is highly dependent on effective feature selection. This paper introduces a novel SDP methodology that utilizes a multi-objective firefly optimization algorithm for feature selection. This optimization approach is specifically designed to address the challenge of high dimensionality in defect datasets. It operates by concurrently minimizing two objectives: the number of selected features and the classification error rate of the prediction model. To validate the proposed method, the model was trained and evaluated using publicly available NASA repository datasets. The

experimental results demonstrate that our approach achieves a prediction accuracy of 93.02 %. This finding represents a significant improvement in performance compared to previous state-of-the-art methods, highlighting the algorithm's effectiveness in developing more reliable and high-quality software systems.

Keywords: Software Error Prediction, Feature Selection, Multi-Objective Firefly Algorithm, Supervised Learning, Classification.

GİRİŞ

Güncel yazılım mühendisliğinde yazılım kalitesini ve güvenilirliğini artırmak en önemli hedeflerden biridir [1]. Bu hedefi desteklemek amacıyla Yazılım Hata Tahmini (Software Defect Prediction - SDP) önemli bir araştırma alanı olarak öne çıkmıştır [2]. SDP'nin temel işlevi, geliştirme yaşam döngüsünün erken aşamalarında hataya yatkın modülleri tespit etmektir. Bu erken tespit, kalite güvence ekiplerinin sınırlı test ve inceleme kaynaklarını daha etkili biçimde yönlendirmesine olanak tanır; böylece düzeltme maliyetleri azalır ve nihai ürünün güvenilirliği artar [3].

Makine öğrenmesi (ML) yaklaşımları, modern SDP modellerinin merkezinde yer almaktadır. Bununla birlikte, bu modellerin performansı büyük ölçüde girdi verisinin kalitesine bağlıdır. NASA deposundaki veri kümeleri gibi yazılım metrik veri setleri çoğunlukla yüksek boyutludur; gürültülü, gereksiz ya da birbiriyle yinelenen çok sayıda özellik içerebilir. “Boyutlanma laneti” olarak bilinen bu durum, sınıflandırıcı doğruluğunu düşürebilir ve hesaplama yükünü artırabilir. Bu nedenle, yalnızca en ayırt edici özelliklerin belirlenip korunmasını sağlayan özellik seçimi (Feature Selection - FS), modeli sadeleştiren ve kestirim gücünü yükselten kritik bir ön işleme adımıdır [4].

Biyolojik esinli optimizasyon algoritmaları, karmaşık FS problemlerinin çözümünde önemli bir potansiyel göstermiştir. Bu çalışma, özellik seçimi için Çok Amaçlı Ateşböceği Algoritması'na (Multi-Objective Firefly Algorithm- MOFA) dayanan yeni bir SDP yöntemi önermektedir. Bu yaklaşım, FS'yi çok amaçlı bir optimizasyon problemi olarak ele alır ve birbiriyle çelişen hedefler arasında Pareto-optimal çözümler bulmayı amaçlar—özellikle seçilen özellik sayısını en aza indirirken, hata tahmin modelinin doğruluğunu eşzamanlı olarak en üst düzeye çıkarmayı hedefler [5][6]. Önerilen model NASA veri kümeleri üzerinde eğitilmiş ve doğrulanmış; elde edilen çıktı, hataya yatkın modülleri belirlemek üzere sınıflandırıcıların eğitilmesinde kullanılmıştır.

Bu çalışmanın başlıca katkıları aşağıda özetlenmiştir:

- NASA veri setinden hata tahmini için uygun bir özellik altkütmesi seçmek amacıyla ateşböceği optimizasyon algoritmasının uygulanması.
- Çelişen özellik seçimi hedefleri arasındaki ödünleşimi yönetmek için çok amaçlı bir uygunluk (fitness) fonksiyonunun kullanılması.
- Aday çözümlerin uygunluğunu değerlendirmek üzere denetimli öğrenmenin optimizasyon döngüsüne entegre edilmesi.
- Optimize edilmiş özellik altkütmesine dayalı olarak hata tespiti için daha doğru örüntülerin (pattern) üretilmesi.
- Önerilen MOFA tabanlı özellik seçimi ile farklı sınıflandırma yöntemlerinin kapsamlı karşılaştırmalı analizinin sunulması.

Makalenin geri kalanı şu şekilde düzenlenmiştir: Bölüm 2’de yazılım hata tahmini alanındaki ilgili çalışmalar gözden geçirilmiştir. Bölüm 3’te önerilen yöntem ayrıntılı biçimde açıklanmıştır. Bölüm 4’te deneysel sonuçlar ve değerlendirme sunulmuştur. Son olarak Bölüm 5’te sonuçlar ile gelecekteki araştırma yönleri tartışılmıştır.

ARAŞTIRMA

Yazılım Hata Tahmini (Software Defect Prediction-SDP) alanında, özellikle makine öğrenmesi ve veri ön işleme tekniklerine odaklanan çok sayıda çalışma yapılmıştır [7][9]. Model performansını artırmak amacıyla özellik seçimi (Feature Selection-FS) için meta-sezgisel ve

biyolojik esinli optimizasyon algoritmalarını inceleyen geniş bir literatür bulunmaktadır [8]. Örneğin, yüksek boyutlu hata veri kümelerinden bilgilendirici özellikleri seçmek için ateşböceği optimizasyon algoritması kullanılmıştır [10]. Yazılım hata tahmini üzerine son çalışmalar [1] ise çoğunlukla gürültülü ve dengesiz NASA/PROMISE veri kümeleriyle başa çıkmak için güçlü öğrencileri boyut indirgeme ve özellik seçimi ile birleştirmeye odaklanmıştır. Örneğin McMurray ve Sodhro; SVM, NB, KNN, MLP, DT ve çeşitli topluluk (ensemble) yöntemlerini PCA/PLS tabanlı indirgeme ile birlikte değerlendirmiş ve uygun seçilen FS/FE (özellik seçimi/özellik çıkarımı) aşamalarının güvenlik-kritik ortamlarda hem F-ölçütünü hem de AUC'yi artırabildiğini göstermiştir. Zhang ve arkadaşları [2], NASA ve PROMISE veri kümelerindeki sınıf dengesizliği ve gereksiz özellikler sorununu ele almak üzere Borderline-SMOTE ve Tomek Links'i NSGA-II/MOPSO/MODE ile birleştiren hibrit örnekleme ve çok amaçlı optimizasyon çerçevesi önermiş ve tahmin doğruluğunda belirgin iyileşmeler raporlamıştır. Bulguları, veri dengeleme ile özellik altkümelerini birlikte optimize etmenin daha kararlı ve genellenebilir SDP modellerine yol açtığını göstermekte; bu durum, MOFA'yı tek bir arama aşamasında özellik sayısını ve sınıflandırıcı hatasını azaltmak için kullanma yaklaşımımızla örtüşmektedir. Benzer şekilde, [11] Balina Optimizasyon Algoritması'nı (WOA) Tavlama Benzetimi (Simulated Annealing-SA) ile birleştirerek geliştirilmiş bir FS algoritması (EMWS) oluşturmuştur. WOA'ya yönelik ek iyileştirmeler, tek noktalı çaprazlama yönteminin entegrasyonu ile [12]'de önerilmiştir. Parçacık Sürü Optimizasyonu (Particle Swarm Optimization-PSO) da uygulanmış; [14] nesne yönelimli yazılımlar için bir Destek Vektör Makinesi (SVM) modelini optimize etmekte, [13] ise projeler arası hata tahmini (Cross-Project Defect Prediction-CPDP) için Naive Bayes ile iki aşamalı bir algoritmada PSO'yu kullanmıştır. Birden fazla zorluğu eşzamanlı ele almak üzere [19], hem özellik seçimi hem de sınıf dengesizliği problemlerini çözmek için hibrit çok amaçlı guguk kuşu araması (HMOCS-US-SVM) yaklaşımını tanıtmıştır. SDP üzerine yakın tarihli bir çalışma [3], genetik algoritma güdümlü özellik seçiminin heterojen topluluk yöntemleri (RF, SVM, NB) ve yumuşak oylama ile birleştirildiğinde NASA veri kümelerinde doğruluğu yaklaşık %95 seviyelerine çıkarabildiğini ve eğitim/test süresini yaklaşık yarıya indirebildiğini göstermiştir. Pandey, Halder ve Tripathi [4] ise derin öğrenmenin geleneksel SDP yaklaşımlarını aşım aşamayacağını, yedi NASA veri kümesinde SqueezeNet ve dar boğaz (bottleneck) CNN'i değerlendirerek incelemiş; her iki modelin de sekiz güncel (state-of-the-art) temel yönteme kıyasla istatistiksel olarak daha iyi performans gösterdiğini raporlamıştır.

Diğer makine öğrenmesi yaklaşımları da araştırılmıştır. Bayesçi yöntemler öne çıkmakta; [15], özellik ağırlıklandırmasını iyileştirmek için bilgi yayılımına dayalı ağırlıklı Naive Bayes yöntemini (WNB-ID) önermektedir. Boyut indirgeme teknikleri (ör. Temel Bileşen Analizi-PCA), sınıflandırma öncesinde veriyi ön işlemek için kullanılmıştır; [17]'de PCA VE Naive Bayes, [27] ve [18]'de ise PCA sınır ağı yaklaşımları buna örnektir. Belirli veri kümesi zorluklarını gidermek üzere gelişmiş çekirdek tabanlı ve maliyet-duyarlı yöntemler de geliştirilmiştir. Örneğin [16], SVM ile birlikte Yerel Teget Uzay Hizalama (Local Tangent Space Alignment-LTSA) algoritmasını kullanmıştır. Pandey ve Jadhav [5], on PROMISE veri kümesi üzerinde SDP için denetimli makine öğrenmesi tekniklerini kapsamlı biçimde incelemiş ve uygun özellik seçimi ile değerlendirme süreçleriyle birleştirildiğinde lojistik regresyon, Naive Bayes, karar ağaçları ve özellikle rastgele orman topluluklarının doğru ve otomatikleştirilebilir hata tahminleyicileri sunabildiğini göstermiştir.

SDP veri kümeleri çoğu zaman ciddi biçimde dengesiz olduğundan, bazı çalışmalar bu probleme özel olarak odaklanmıştır. [20]'de çeşitli sınıflandırıcılarla birlikte örnekleme tekniklerinin önemi değerlendirilmiştir. [21]'de ise sınıf dengesizliğinin etkisini azaltmak için maliyet-duyarlı ve uzaklık metriği öğrenimine dayalı yeni bir yaklaşım önerilmiş ve Büyük Marj Dağılım Makinesi'ne (Large Margin Distribution Machine-LDM) uygulanmıştır.

Literatür, özellik seçimi için optimizasyon algoritmalarının kullanımına yönelik güçlü bir eğilim olduğunu göstermesine rağmen, birçok yaklaşım tek bir hedefe odaklanmaktadır. Önerilen araştırma, bu temelin üzerine inşa edilerek, seçilen özellik sayısını en aza indirme ve kestirim doğruluğunu en üst düzeye çıkarma gibi birbiriyle çelişen hedefleri aynı anda dengeleyen Pareto-optimal çözümler bulmak üzere özel olarak tasarlanmış Çok Amaçlı Ateşböceği Algoritması'nı (MOFA) kullanmaktadır.

YÖNTEM

Yazılım hata tahminini (Software Defect Prediction-SDP) iki amaçlı bir özellik seçimi problemi olarak ele alıyoruz: kestirim performansını yüksek tutarken statik kod metriklerinden oluşan kompakt özellik altkümeleri bulmak. Çok Amaçlı Ateşböceği Algoritması (Multi-Objective Firefly Algorithm-MOFA), altküme uzayında arama yapar; her bir altkümeyle ait kalite, yalnızca seçilen özellikler kullanılarak eğitilen bir sınıflandırıcı tarafından puanlanır. Nihai tahminleyici ise Pareto-etkin çözümler arasından seçilen en iyi özellik altkümeleriyle eğitilir.

A) Problem Parametreleri ve Gösterimi

Veri kümesi $D = \{(x_i, y_i)\}_{i=1}^n$ olsun. Burada $x_i \in \mathbb{R}^d$ yazılım metriklerini, $y_i \in \{0,1\}$ ise etiketi (hatalı / hatasız) temsil eder. Aday bir özellik altkümeleri, ikili (binary) bir vektör olan $s \in \{0,1\}^d$ ile gösterilir. Seçilen özelliklerin indeks kümesi $S = \{k: s_k = 1\}$ olup, büyüklüğü $|S|$ 'dir.

S verildiğinde, temel bir sınıflandırıcı h_S (Naïve Bayes) eğitilir ve katmanlı (stratified) K -katlı çapraz doğrulama protokolü ile değerlendirilir. Aşağıdaki iki amaç fonksiyonu minimize edilir:

$$\begin{aligned} f_1(s) &= \frac{|S|}{d} \text{ (altküme boyutu, normalleştirilmiş),} \\ f_2(s) &= 1 - M(h_S) \text{ (doğrulama hatası),} \end{aligned} \quad (1)$$

Burada M , katlar (fold) boyunca elde edilen doğrulama ölçütünün ortalamasıdır (sınıf dengesizliğini dikkate almak için F_1 kullanıyoruz; istenirse doğruluk (accuracy) da tercih edilebilir) [23]. Arama süreci, (f_1, f_2) değerlerini birlikte minimize eden bir Pareto çözüm kümesi bulmayı hedefler.

B) Ateşböceği Kodlama ve Hareket (İkili MOFA)

Her bir ateşböceği, bir özellik altkümelerini s ile kodlar. Standart çekicilik (attractiveness) modelini, aşağıdaki uzaklık tanımıyla birlikte kullanırız:

$$r_{ij} = \|x_i - x_j\|_2, \beta(r) = \beta_0 e^{-\gamma r^2}, \quad (2)$$

ve stokastik hareket kuralı:

$$x_i^{t+1} = x_i^t + \beta(r_{ij}) (x_j^t - x_i^t) + \alpha \varepsilon^t, \quad (3)$$

Burada $\varepsilon^t \sim \mathcal{N}(0, I)$, $\beta_0 > 0$, $\gamma > 0$ ve $\alpha > 0$ olacak şekilde tanımlanır [22], [23]. İkili (binary)

altküme uzayında çalışabilmek için, $x_i^{(t+1)}$ vektörünün her bir bileşenine eleman bazında

$$\text{aşağıdaki transfer fonksiyonu uygulanır: } \sigma(z) = \frac{1}{1+e^{-z}}$$

Ardından örnekleme yapılarak yeni ikili çözüm elde edilir: $s_i^{t+1}[k] = \mathbb{1}[\sigma(x_i^{t+1}[k]) > \rho]$ ile $\rho \sim \mathcal{U}(0,1)$. Burada $\mathbb{1}[\cdot]$ gösterge fonksiyonudur; koşul sağlanırsa 1, aksi halde 0 değerini alır. Ateşböceklerinin “ışık şiddeti” (intensity) değerleri ise iki amaç fonksiyonuna göre Pareto baskınlığı (scalarization yapılmadan) üzerinden hesaplanır [24].

C) Çok Amaçlı Seçim ve Arşivleme

Baskın olmayan (non-dominated) çözümlerden oluşan harici bir arşiv Atutulur. Her nesilden sonra:

- Tüm ateşböcekleri (f_1, f_2) değerleriyle, K -katlı Naive Bayes (NB) kullanılarak değerlendirilir.
- Yeni bulunan baskın olmayan özellik altkümeleri arşiv A 'ya eklenerek Agüncellenir.
- $|A|$ belirlenen üst sınırı aşarsa, çeşitliliği korumak için kalabalıklık uzaklığı (crowding distance) kullanılarak arşivden eleme yapılır.

- Bir sonraki popülasyon, Arşivinden ve mevcut Pareto cephesinden örnekleme yapılarak oluşturulur.

Durdurma koşulu; Tnesil tamamlandığında veya Gkontrol boyunca arşivde bir iyileşme görülmediğinde sağlanır.

D) Sınıflandırıcı ve Doğrulama Protokolü

Herhangi bir özellik altkütmesi S_i için, eğitim katlarında yalnızca S_i içindeki özellikler kullanılarak bir Naive Bayes (NB) sınıflandırıcısı eğitilir. K kat boyunca elde edilen doğrulama ölçütü M 'nin ortalaması raporlanır (varsayılan $K = 5$). Varyansı azaltmak için rastgelelik tohumu (random seed) sabitlenir ve katlar sınıflara göre katmanlı (stratified) biçimde oluşturulur. Nihai model, seçilen Pareto altkütmesi kullanılarak tüm eğitim bölümü üzerinde yeniden eğitilir [25].

E) İş Akışı Özeti

1. Ön işleme: Sayısal metrikleri standartlaştır (eğitim verisinde öğren; doğrulama/teste uygula).
2. Arama: Popülasyon büyüklüğü Pile MOFA'yı Tnesil çalıştır.
3. Puanlama: Her ateşböceğinin altkütmesi için K -katlı NB ile f_1, f_2 hesapla.
4. Seçim: $|S|$ ile performans arasında denge kuran bir Pareto çözümü seç (ör. "diz/knee" noktası).
5. Eğitim & Test: NB'yi S^{**} üzerinde eğit ve ayrılmış (held-out) test kümesinde değerlendir.

F) Karmaşıklık ve Hiperparametreler

Her nesilde baskın maliyet değerlendirme adımıdır: $O(P \cdot K \cdot C_{NB}(n, |S|))$. NB eğitimi örnek sayısı ve özellik sayısı ile doğrusal olduğundan, d orta büyüklükte olsa bile MOFA pratik kalır; ayrıca arama süreci ateşböcekleri/katlar arasında doğal olarak paralelleştirilebilir. Kullanılan ayarlar: popülasyon $P = 30$, nesil sayısı $T = 100$, $\beta_0 = 1.0$, $\gamma = 1/d$, α değeri 0.9'dan 0.2'ye doğrusal olarak azaltılır, arşiv üst sınırı = 50, $K = 5$. Özel bir altküme boyutu gerekmiyorsa, nihai Pareto cephesindeki "knee" çözümü seçilir [26]–[29].

DENEYSEL SONUÇLAR


Bu çalışmada, toplam 8.965 yazılım modülü içeren NASA veri kümeleri (JM1 ve KC1) kullanılarak bir tahmin modeli test edilmiştir. Önerilen yöntem, özellik seçimi için çok amaçlı ateşböceği algoritmasını ve sınıflandırma için Naive Bayes yaklaşımını birleştirir. Amaç, 21 statik kod metriği (ör. Halstead karmaşıklığı, LOC sayımları) kullanarak hatalı modülleri belirlemektir. Veri kümesi belirgin biçimde dengesizdir: %22,15'i hatalı ("Y") modüllerden (1.986 kayıt), %77,85'i hatasız ("N") modüllerden (6.979 kayıt) oluşmaktadır.

A) Özellik Alt Kümesi Seçiminin Uygulanması


Bu yöntem, her bir ateşböceğinin NASA veri kümesinden bir özellik altkütmesini temsil ettiği Çok Amaçlı Ateşböceği Algoritması'nı (Multi-Objective Firefly Algorithm–MOFA) kullanır. Amaç, iki hedefli bir uygunluk (fitness) fonksiyonunu minimize etmektir: (1) Naive Bayes sınıflandırma hatası ve (2) seçilen özellik sayısı. MOFA, çözümleri Pareto baskınlığına göre sıralar ve en iyi (baskın olmayan) çözümleri (Şekil 1'de mavi * ile gösterilenler) harici bir arşivde saklar. Bu elit çözümlerden oluşan arşiv, iterasyonlar boyunca sürünün yakınsamasını yönlendirir (örneğin 1. iterasyondan 20. iterasyona), Pareto cephesini kademeli olarak genişleterek daha düşük hata ve daha az özellik içeren çözümlerin bulunmasını sağlar.

MOFA toplam 20 iterasyon çalıştırılır. Her turda ateşböcekleri (özellik altkümeleri) özellik sayısı ve Naive Bayes hatası açısından değerlendirilir; baskın olmayan çözümler arşive eklenir. Son iterasyonun sonunda ise elit popülasyon elde edilir.

Şekil 1. Çok amaçlı ateşböceği algoritması ile baskın olmayan çözümlerin bulunması.



(b)




(a)

Tablo I. En iyi (optimal) çözümlere ilişkin bilgiler.

Çözüm İndeksleri	Seçilen Özellik Sayısı	Seçilen Özelliklerin İndeksleri	F1 Değeri	F2 Değer
1	6	[1,5,11,13,18,19]	0.2857	0.225
2	5	[6,13,17,19,21]	0.2143	0.2320
3	4	[1,15,17,18]	0.2380	0.2473
4	6	[6,13,17,19,21]	0.1904	0.2614
5	4	[2,7,21]	0.2381	0.2474
6	5	[2,3,6,7,21]	0.3333	0.2320
7	5	[1,15,17,18,19]	0.2857	0.2321

Şekil 2. Amaç fonksiyon değerlerinin optimal noktalara doğru yakınsaması.



Tablo I, Çok Amaçlı Ateşböceği Algoritması (MOFA) tarafından belirlenen nihai yedi Pareto-baskın olmayan çözümü göstermektedir. Algoritma iki minimizasyon hedefi arasında denge kurmaktadır: seçilen özellik sayısı (F1) ve Naive Bayes sınıflandırma hatası (F2). Yakınsama eğilimleri (Şekil 2), sınıflandırma hatasının (F2) hızlı biçimde azaldığını ve ardından plato yaptığını; buna karşılık seçilen özellik sayısının (F1) süreç boyunca kademeli olarak düşmeye devam ettiğini göstermektedir. Bu durum, MOFA'nın hedeflenen ödünleşimi başarıyla sağladığını; düşük sınıflandırma hatasına sahip kompakt özellik altkümeleri bularak hata tahmin performansını iyileştirdiğini doğrulamaktadır.

B) Önerilen Yöntemin Performans Değerlendirmesi

Önerilen yöntem uygulandıktan sonra, performans değerlendirmesi eğitim sırasında etiketleri kullanılmayan ayrılmış (held-out) bir test kümesi üzerinde gerçekleştirilmiştir. Tahmin edilen etiketler, yazılım hata tahmini alanında yerleşik değerlendirme uygulamalarına uygun biçimde gerçek etiketlerle karşılaştırılmıştır (standart tanımlar ve protokol için bkz. [24], [28]). Genellenebilirliği doğrulamak amacıyla, MOFA'nın ürettiği özellik altkümeleri alternatif sınıflandırıcılarla da değerlendirilmiştir (Naive Bayes, Yapay Sinir Ağı, KNN, Karar Ağacı, SVM, Lojistik Regresyon, Rastgele Orman). Tablo II, karşılaştırmalı sonuçları özetlemekte ve seçilen özelliklerin, belirli bir metrik raporlamasına bağımlı kalmadan farklı modeller arasında da genellenebildiğini göstermektedir.

Sonuçlara göre, önerilen MOFA–Naive Bayes (MOFA-NB) yapılandırması en üstün seçenek olmuştur. MOFA ile seçilen özellikler kullanıldığında Doğruluk (Accuracy) = %93,02 ve F-ölçütü (F-measure) = %95,58 elde edilmiş; bu değerler SVM'in (%78,79 doğruluk) ve Lojistik Regresyonun (%79,18 doğruluk) performansını belirgin biçimde aşmıştır.


ROC analizi (Şekil 3) bu bulguyu desteklemiştir. MOFA-NB en iyi ödünleşimi ve en güçlü ayırt ediciliği (AUC) sergilemiştir. MOFA-DT yakın bir ikinci (AUC = 0,89) olurken; MOFA-SVM (AUC = 0,79), MOFA-LR (AUC = 0,75), MOFA-KNN (AUC = 0,67) ve MOFA-RF (AUC = 0,65) görece daha zayıf performans göstermiştir.

Şekil 4, MOFA tabanlı sınıflandırıcılara ait normalize edilmiş karmaşıklık matrislerini (Gerçek vs. Tahmin) sunmaktadır. Bu matrisler, MOFA-NB ve MOFA-DT yapılandırmalarının en dengeli tespiti sağladığını (örneğin yaklaşık %75 doğru “hatalı”, %17–18 doğru “hatasız” tespit) göstermektedir. Buna karşılık, MOFA-SVM ve MOFA-LR gibi modeller hatasız modüllerde daha yüksek yanlış sınıflandırma oranlarına sahiptir. Bu sonuçlar ve ROC analizi birlikte değerlendirildiğinde, bu hata tahmini görevi için en güvenilir varyantın MOFA-NB olduğu; MOFA-DT'nin ise yakın bir alternatif sunduğu görülmektedir. Diğer kombinasyonlar daha az dengeli olup daha yüksek yanlış-pozitif oranları sergilemiştir.


Tablo II. Sınıflandırma yöntemleri için değerlendirme ölçütlerinin ortalama değerleri.

Kriterler	Doğruluk (Accuracy)	Duyarlılık (Recall)	Kesinlik (Precision)	F1 Skor (F-measure)
MOFA-NB	93.02	94.61	96.57	95.58
MOFA-KNN	78.89	80.56	96.32	87.74
MOFA-DT	92.17	94.09	96.04	95.05
MOFA-SVM	78.79	78.76	99.9	88.08
MOFA-LR	79.18	79.37	99.24	88.2
MOFA-RF	77.74	81.75	92.19	86.66

Şekil 3. NASA yazılım hata veri kümeleri üzerinde MOFA tabanlı sınıflandırıcıların ROC eğrileri.



Şekil 4. NASA yazılım hata veri kümeleri üzerinde MOFA tabanlı sınıflandırıcılar için yüzdeye göre normalize edilmiş karmaşıklık (confusion) matrisleri.



C) En Güncel Yöntemlerle Karşılaştırma (State-of-the-Art)

Tablo III'te özetlendiği üzere, karşılaştırma temel yöntemleri; [1]'den alınan klasik öğreniciler (MLP, Rastgele Orman, Bagging), [2]'den örnekleme ve optimizasyon temelli varyantlar (SMOTE-Rastgele Orman, çok amaçlı kNN), [3]'ten genetik algoritma temelli oybirliği/topluluk yaklaşımı (RF/SVM/NB) ve [4]'ten kompakt bir derin model (SqueezeNet) ile [5]'ten ek bir Bagging-RF topluluğunu kapsamaktadır. Bu yöntem aileleri genelinde

raporlanan performansın Doğruluk $\approx$ %93–95 ve F-ölçütü $\approx$ %91–95 aralığında yoğunlaşması, incelenen veri kümelerinde denetimli SDP yaklaşımlarının olgunlaştığını göstermektedir. Bu bağlamda, MOFA-NB (önerilen yöntem) %93 doğrulukla birlikte en yüksek F-ölçütüne (%95) ulaşarak güçlü bir kesinlik-duyarlılık (precision-recall) dengesi ortaya koymaktadır. [3]'teki GA topluluğu, %94 F-ölçütü ile birlikte %95 doğruluk sağlayarak rekabetçi bir performans sunar. [4]'teki SqueezeNet, %94/%94 (F1/Acc) elde ederek hafif bir CNN'in güçlü klasik topluluklarla boy ölçüşebildiğini göstermektedir. [2]'deki çok amaçlı kNN ise en yüksek doğruluğu (%97) raporlamakla birlikte daha düşük F-ölçütü (%92) sergilemektedir; bu durum, optimizasyonun genel doğruluğu öne çıkarıp azınlık sınıf duyarlılığını görece geri plana atmasıyla ortaya çıkan tipik bir precision/recall asimetrisini düşündürmektedir. [1]'deki klasik temel yöntemler birbirine yakın sonuçlar verirken (MLP ve RF: %91–92 F1, %93 doğruluk; Bagging: %92/%94), [2]'deki SMOTE-Rastgele Orman ve [5]'teki Bagging-RF daha geride kalmaktadır (yaklaşık %88–89 F1, %82–87 doğruluk); bu da basit yeniden örnekleme veya optimize edilmemiş toplulukların her zaman tutarlı kazanım sağlamayabileceğini göstermektedir.

Genel olarak, MOFA-NB, yakın tarihli optimizasyon ve derin öğrenme tabanlı alternatiflerle doğruluk açısından rekabetçi kalırken en iyi F-ölçütünü sunmaktadır. Daha güçlü ve temkinli çıkarımlar için, NASA veri kümelerinde %1–2'lik farkların örnekleme değişkenliği içinde kalabileceği dikkate alınarak güven aralıkları ve anlamlılık testlerinin raporlanması önerilir.

Table III. En güncel (state-of-the-art) yöntemlerle karşılaştırma.

Kriterler	Doğruluk (Accuracy) %	F1 Skor (F-measure) (%)
MOFA-NB	93	95
MLP [1]	93	91
Random Forest [1]	93	92
Bagging [1]	94	92
SMOTE-Random Forest [2]	82	89
multi-objective KNN [2]	97	92
GA Ensemble (RF/SVM/NB) [3]	95	94
SqueezeNet [4]	94	94
Bagging-RF [5]	87	88

SONUÇ

Yazılım hata tahmini (SDP), yazılım kalitesini artırmak, geliştirme maliyetlerini optimize etmek ve güvenilirliği sağlamak açısından kritik bir problemdir. Bu çalışma, çok amaçlı ateşböceği algoritmasına (MOFA) dayalı özellik seçimini merkeze alan yeni bir SDP yöntemi önermiştir. Algoritma NASA veri kümesine uygulanarak etkisi yüksek, azaltılmış bir özellik kümesi başarıyla belirlenmiştir. Amaç fonksiyonumuz, seçilen özellik sayısını ve sınıflandırma hata oranını eşzamanlı olarak minimize edecek biçimde tasarlanmıştır. Elde edilen sonuçlar umut vericidir: MOFA'nın belirlediği özellik altkümesi sınıflandırma algoritmalarına verildiğinde, model test verisi üzerinde önceki yöntemlere kıyasla yazılım hatalarını tahmin etmede daha üstün performans göstermiştir. Bu bulgu, çok amaçlı meta-sezgisel yaklaşımların hata tahmin modellerinin verimliliğini ve doğruluğunu artırmadaki önemli potansiyelini vurgulamakta; nihayetinde daha sağlam ve güvenilir yazılımlara katkı sağlamaktadır.

Önerilen yöntemin başarısı doğrultusunda, gelecekteki çalışmalar için şu araştırma yönleri önerilmektedir:

- Meta-sezgisel yöntemlerde, özellik seçimini iyileştirmek üzere doğrusal olmayan optimizasyona dayalı uygunluk fonksiyonlarının incelenmesi.
- Özellik altkütmesi seçiminin doğruluğunu daha da artırmak için hibrit/birleşik meta-sezgisel algoritmaların araştırılması.
- Yazılım tahmin hata oranını ayarlamak ve azaltmak amacıyla topluluk (ensemble) sınıflandırma tekniklerinin veya farklı sınıflandırıcı kombinasyonlarının kullanılması.

KAYNAKLAR

- Abaei, G., & Selamat, A. (2014). A survey on software fault detection based on different prediction approaches. *Vietnam Journal of Computer Science*, 1(2), 79-95.
- Ali, M., Mazhar, T., Al-Rasheed, A., Shahzad, T., Ghadi, Y. Y., & Khan, M. A. (2024). Enhancing software defect prediction: A framework with improved feature selection and ensemble machine learning. *PeerJ Computer Science*, 10. doi: 10.7717/peerj-cs.1860
- Apak, S., & Güneş, P. (2025). Enhancing Android lock pattern security with personalized federated learning and multi-modal framework. *2025 10th International Conference on Machine Learning Technologies (ICMLT)* (ss. 223–232). IEEE. doi: 10.1109/ICMLT65785.2025.11193248
- Cai, X., ve ark. (2020). An under-sampled software defect prediction method based on hybrid multi-objective cuckoo search. *Concurrency and Computation: Practice and Experience*, 32(5), e5478.
- Can, H., ve ark. (2013). A new model for software defect prediction using particle swarm optimization and support vector machine. *2013 25th Chinese Control and Decision Conference (CCDC)*. IEEE.
- Dhamayanthi, N., & Lavanya, B. (2019). Software defect prediction using principal component analysis and Naïve Bayes algorithm. *Proceedings of International Conference on Computational Intelligence and Data Engineering*. Springer.
- Goyal, S. (2022). FOFS: Firefly optimization for feature selection to predict fault-prone software modules. *Data Engineering for Smart Systems* (ss. 479-487). Springer.
- Hassouneh, Y., ve ark. (2021). Boosted whale optimization algorithm with natural selection operators for software fault prediction. *IEEE Access*, 9, 14239-14258.
- Jayanthi, R., & Florence, L. (2019). Software defect prediction techniques using metrics based on neural network classifier. *Cluster Computing*, 22(1), 77-88.
- Ji, H., ve ark. (2019). A new weighted naive Bayes method based on information diffusion for software defect prediction. *Software Quality Journal*, 27(3), 923-968.
- Jin, C. (2021). Software defect prediction model based on distance metric learning. *Soft Computing*, 25(1), 447-461.
- Khuat, T. T., & Le, M. H. (2020). Evaluation of sampling-based ensembles of classifiers on imbalanced data for software defect prediction problems. *SN Computer Science*, 1, 1-16.
- Kilinc, H. C., Apak, S., Ergin, M. E., Ozkan, F., Katipoğlu, O. M., & Yurtsever, A. (2025). Enhancing hydrological time series forecasting with a hybrid Bayesian-ConvLSTM model optimized by particle swarm optimization. *Acta Geophysica*. doi: 10.1007/s11600-025-01570-0
- Mabayoje, M. A., ve ark. (2019). Parameter tuning in KNN for software defect prediction: An empirical analysis. *Jurnal Teknologi dan Sistem Komputer*, 7(4), 121-126.
- McMurray, S., & Sodhro, A. H. (2023). A study on ML-based software defect detection for security traceability in smart healthcare applications. *Sensors*, 23(7). doi: 10.3390/s23073470
- Pandey, A., & Jadhav, A. (2024). Towards effective software defect prediction using machine learning techniques. *SN Computer Science*, 5(8). doi: 10.1007/s42979-024-03458-0

Pandey, S. K., Haldar, A., & Tripathi, A. K. (2025). Is deep learning good enough for software defect prediction? *Innovations in Systems and Software Engineering*, 21(2), 501–516. doi: 10.1007/s11334-023-00542-1

Prasad, M., Florence, L., & Arya, A. (2015). A study on software metrics based software defect prediction using data mining and machine learning techniques. *International Journal of Database Theory and Application*, 8(3), 179-190.

Saifan, A. A., & Abu-wardih, L. (2020). Software defect prediction based on feature subset selection and ensemble classification. *ECTI Transactions on Computer and Information Technology (ECTI-CIT)*, 14(2), 213-228.

Shuai, B., ve ark. (2013). Software defect prediction using dynamic support vector machine. *2013 Ninth International Conference on Computational Intelligence and Security*. IEEE.

Wang, T., & Li, W.-H. (2010). Naive Bayes software defect prediction model. *2010 International Conference on Computational Intelligence and Software Engineering*. IEEE.

Wang, Y., ve ark. (2019). Defect prediction model for object oriented software based on particle swarm optimized SVM. *Journal of Physics: Conference Series*. IOP Publishing.

Wei, H., ve ark. (2019). Establishing a software defect prediction model via effective dimension reduction. *Information Sciences*, 477, 399-409.

Yang, X. (2008). Firefly algorithm (Bölüm 8). *Nature-inspired Metaheuristic Algorithms*. Luniver Press.

Yang, X.-S., & He, X. (2013). Firefly algorithm: Recent advances and applications. *International Journal of Swarm Intelligence*, 1(1), 36-50.

Yao, Z., ve ark. (2019). The cross-project defect prediction based on PSO and feature dependent Naive Bayes. *Journal of Physics: Conference Series*. IOP Publishing.

Zhang, J., Li, D., Wong, W. E., & Wang, S. (t.y.). A hybrid sampling and multi-objective optimization approach for enhanced software defect prediction.

Zhu, K., ve ark. (2021). Software defect prediction based on enhanced metaheuristic feature selection optimization and a hybrid deep neural network. *Journal of Systems and Software*, 180, 111026.

**BASIM TEKNOLOJİLERİNİN TEKNOLOJİK EVRİMİ: GELENEKSEL
YÖNTEMLERDEN DİJİTAL VE AKILLI SİSTEMLERE GEÇİŞ**

TECHNOLOGICAL EVOLUTION OF PRINTING TECHNOLOGIES: THE TRANSITION
FROM TRADITIONAL METHODS TO DIGITAL AND INTELLIGENT SYSTEMS

Rabia İlknur ERKEN

Doktora Öğrencisi, Marmara Üniversitesi Fen Bilimleri Enstitüsü Mekatronik Mühendisliği
Ana Bilim Dalı, 0000-0002-2894-3540

İsmail TEMİZ

Dr. Öğr. Üyesi, Marmara Üniversitesi Teknoloji Fakültesi Mekatronik Mühendisliği,
0000-0002-6578-848x

Mevlüt KARAKAYA

Doktora Öğrencisi, Marmara Üniversitesi Fen Bilimleri Enstitüsü Mekatronik Mühendisliği
Ana Bilim Dalı, 0000-0001-9189-0894

ÖZET

Basım teknolojileri, bilgi aktarımının en eski araçlarından biri olmasına karşın, dijitalleşme ve endüstriyel otomasyonun etkisiyle son yıllarda önemli bir teknolojik gelişim sürecinin içine girmiştir. Uzun yıllar boyunca kullanılan geleneksel mekanik temelli baskı teknikleri zamanın ilgili gereksinimlerini karşılamış olsa da artan talepler, sürdürülebilirlik gerekliliği ve gelişen teknoloji bu yöntemlerin sınırlarını ortaya koymuştur. Tüm bu nedenlerle basım endüstrisi, analog üretimden dijital üretime ve akıllı sistemlere doğru bir dönüşüm sürecine girmiştir.

Bu çalışmada basım teknolojilerinin tarihsel gelişimi, geleneksel baskı yöntemlerinden dijital basım sistemlerine geçiş süreci ve günümüzde kullanılan akıllı basım teknolojileri literatür taraması yapılarak incelenmiştir. Öncelikle tipo, ofset, tıfdruk, flekso ve serigrafi gibi geleneksel baskı tekniklerinin teknik özellikleri ve kullanım alanları ele alınmış; ardından bilgisayar destekli ön baskı sistemleri ve kalıpsız üretim anlayışı ile şekillenen dijital basım teknolojilerinin sektöre sağladığı yenilikler değerlendirilmiştir.

Çalışmanın son bölümünde ise sürdürülebilirlik odaklı uygulamalar, enerji verimliliği ve çevresel etkiler bağlamında basım teknolojilerindeki güncel yönelimler değerlendirilmiş; gelecekte basım endüstrisinin daha esnek, akıllı ve çevre dostu üretim sistemlerine doğru yöneleceği ortaya konulmuştur. Elde edilen bulgular, basım teknolojilerindeki teknolojik dönüşümün yalnızca üretim yöntemlerini değil, aynı zamanda endüstrinin genel yapısını ve rekabet dinamiklerini de önemli ölçüde etkilediğini göstermektedir.

Anahtar kelimeler: Basım teknolojileri, dijital basım, geleneksel baskı yöntemleri, sürdürülebilirlik, basım teknolojisinde akıllı üretim sistemleri

ABSTRACT

Printing technologies, despite being one of the oldest tools for information transfer, have undergone significant technological development in recent years due to the impact of digitalization and industrial automation. Although traditional mechanical-based printing techniques used for many years met the requirements of their time, increasing demands, sustainability requirements, and advancing technology have revealed the limitations of these

methods. For all these reasons, the printing industry has shifted from analog production to digital production and smart systems.

This study examines the historical development of printing technologies, the transition process from traditional printing methods to digital printing systems, and the smart printing technologies used today through a literature review. First, the technical characteristics and areas of application of traditional printing techniques such as letterpress, offset, flexography, and screen printing were discussed; then, the innovations brought to the sector by digital printing technologies, shaped by computer-aided prepress systems and the concept of plate-less production, were evaluated.

In the final section of the study, sustainability-focused applications, energy efficiency, and current trends in printing technologies in the context of environmental impacts were evaluated; it was revealed that the printing industry will move towards more flexible, intelligent, and environmentally friendly production systems in the future. The findings reveal that technological transformation in printing technologies has significantly impacted not only production methods but also the overall structure of the industry and its competitive dynamics.

Keywords: Printing technologies, digital printing, traditional printing methods, sustainability, smart production systems in printing technology

GİRİŞ

İnsanlık tarihi boyunca basım teknolojileri, bilginin çoğaltılması ve kitlelere ulaştırılması amacını taşıyan en önemli araçlardan biri olmuştur. Yazının yaygınlaşmasıyla birlikte gelişen bu alan, yüzyıllar boyunca toplumsal, kültürel ve ekonomik dönüşümlerin temel bir bileşeni olmuştur. Mekanik temelli üretim anlayışı tipografik baskı ile başlamış olup, sanayi devrimi sonrası ofset, tıfdruck ve fleksografik baskı gibi yöntemlerle gelişmeye devam etmiştir (Koldaş & Selamet, 2018; Kipphan, 2001; Ural, 2025). Tüm bu yöntemler uzun yıllar basım endüstrisinin ana omurgasını oluştursa da son yıllarda yaşanan dijitalleşme süreci basım teknolojilerinin geleneksel yapısını geliştirmek zorunda bırakmıştır (Kipphan, 2001; Yılmaz, 2021; Masod & Zakaria, 2023). Bu dönüşümün temel nedenleri arasında müşteri taleplerindeki değişim önemli bir yer tutmaktadır. Kısa termin süreleri, düşük maliyet beklentileri ve kişiselleştirilmiş üretim gereksinimleri gibi parametreler klasik baskı yöntemlerinin sınırlarını daha görünür hale getirmiştir (Erdoğanaras, 2004). Tüm bunlara ek olarak çevresel sürdürülebilirlik, enerji verimliliği ve atık yönetimi gibi konular da basım endüstrisi üzerinde dönüşüm baskısı oluşturmuştur (Suganuma, 2014). Bu gelişmeler doğrultusunda basım endüstrisi, analog üretim anlayışından uzaklaşarak dijital basım sistemleri, bilgisayar destekli ön baskı süreçleri ve akıllı üretim teknolojilerine yönelmeye başlamıştır (Lu, 2017; Ural, 2025). Günümüzde bu dönüşüm yalnızca baskı makineleriyle sınırlı kalmamakta; sensör teknolojileri, otomasyon sistemleri, yazılım entegrasyonları ve Endüstri 4.0 bileşenleri ile bütünleşik bir yapı oluşturmaktadır (Yılmaz, 2021).

Bu çalışmanın amacı, basım teknolojilerinin tarihsel gelişimini ele alarak geleneksel baskı yöntemlerinden dijital ve akıllı basım sistemlerine geçiş sürecini literatür taraması yoluyla incelemek ve güncel teknolojik yönelimleri değerlendirmektir. Bu kapsamda öncelikle geleneksel baskı tekniklerinin temel özellikleri incelenmiş, ardından dijital basım teknolojilerinin sektöre sağladığı yenilikler ele alınmıştır. Son olarak sürdürülebilirlik, enerji verimliliği ve çevresel etkiler bağlamında basım teknolojilerinin güncel ve geleceğe yönelik eğilimleri tartışılmıştır. Bu yönüyle çalışma, basım teknolojilerindeki teknolojik dönüşümün yalnızca üretim süreçlerini değil, aynı zamanda sektörün rekabet yapısını, üretim anlayışını ve stratejik yönelimlerini nasıl etkilediğini ortaya koymayı hedeflemektedir.


ARAŞTIRMA VE BULGULAR

BASIM TEKNOLOJİLERİNİN TARİHSEL GELİŞİMİ

Basım teknolojilerinin tarihsel gelişimi, bilginin daha hızlı, daha ekonomik ve daha geniş kitlelere ulaştırılması gereksinimi doğrultusunda şekillenmiştir (Meggs & Purvis, 2016); Ural, 2025). Zaman içerisinde bilgi aktarımına duyulan gereksinimlerin artması, basım teknolojilerinin değişen ekonomik ve teknolojik koşullara uyum sağlamasını zorunlu kılmıştır (Erdoğanaras, 2004; Yılmaz, 2021; Masod & Zakaria, 2023). İlk basım uygulamalarından itibaren temel amaç, bilginin hızlı ve güvenilir biçimde çoğaltılarak geniş kitlelere ulaştırılması olmuştur (Kipphan, 2001). Bu doğrultuda basım teknolojileri, uzun yıllar boyunca mekanik temelli yöntemlere dayanmış ve endüstriyel üretim anlayışı içerisinde önemli bir yer edinmiştir (Erdoğanaras, 2004).

İlk Basım Uygulamaları ve Tipo Baskı

Yüksek baskı prensibine dayanan tipo baskı tekniği ile basım teknolojisinin endüstriyel temelleri şekillenmiştir. Tipo baskı Gutenberg'in hareketli metal harf sistemini geliştirmesiyle bilginin çoğaltılmasını mümkün kılan ilk baskı yöntemi olarak yaygınlık kazanmıştır (Meggs & Purvis, 2016; Koldaş & Selamet, 2018). Baskı yüzeyi kabartma hâlinde hazırlanan bu yöntemde mürekkep yalnızca yüksek yüzeylere uygulanır ve böylece baskı altı malzemesine doğrudan aktarılmaktadır. Görüntüyü aktaran kısımların yüksekte olmasından dolayı yüksek baskı sistemi denilmektedir (İpek, 2023). Bu spesifik teknik yapı sayesinde tipo baskı kitap, dergi, gazete gibi basılı yayınların seri halde üretilmesine olanak tanımıştır. Böylece özellikle metin temelli yayınların üretilip çoğaltılmasında uzun yıllar tercih edilmiştir. Tipo baskı endüstride etkin bir biçimde kullanıldıkça basım süreçlerinde standartlaşma ve iş akışının sistematikleşmesi beraberinde gelmiştir. Bu durum tipo baskının yalnızca teknik bir yöntem olmadığının basım endüstrisinin üretim kapasitesini belirleyen temel unsurlardan biri hâline geldiğinin de kanıtıdır (İpek, 2023). Tüm bunlara rağmen gelişen ve değişen zaman içerisinde tipo baskı, artan üretim hacimleri, çeşitlenen görsel beklentiler gibi parametrelere yeterli gelememeye başlamıştır (Koldaş & Selamet, 2018; Ural vd., 2022). Özellikle litografi temelli baskı tekniklerinin ve ofset baskının da gelişmesiyle birlikte tipo baskı, ticari üretimdeki baskın konumunu büyük ölçüde yitirmiştir (Kipphan, 2001; Büyükpehlivan & Oktav, 2021). Her ne kadar endüstriyel alanda gerileme yaşasa da tipo baskı tamamen ortadan kalkmamıştır. Günümüzde seri üretimden ziyade sınırlı uygulamalarda, özel baskı işlemlerinde varlığını devam ettirmektedir. Çünkü Sıcak yaldız, gofre ve numarator baskı gibi işlemlerde mekanik yapısının sağladığı avantajlar tipo baskının tamamen ortadan kalkmasına engel olmuştur (Koldaş & Selamet, 2018; Suganuma, 2014). Şekil 1. İle tipo baskı sisteminin çalışma prensibi gösterilmiştir (Birişik, 2023). Heidelberg 1965 model iki rekli kazanlı tipo baskı makinesi Şekil 2 ile gösterilmiştir (İpek, 2023).




Şekil 1. Tipo baskı sisteminin çalışması



Şekil 2. Heidelberg 1965 model tipo baskı makinesi

Ofset Baskının Gelişimi ve Yaygınlaşması

20. yüzyılın başlarında taş baskının temel prensiplerinden türetilerek geliştirilen ofset baskı tekniği, kısa sürede endüstriyel basım süreçlerinde kullanılmaya başlanmıştır (Kipphan, 2001; Hayta & Oktav, 2023). Nemlendirme suyu ile yağ bazlı mürekkebin yoğunluk ve yüzey gerilimlerinin farklı olması nedeniyle birbirine karışmaması prensibine dayanan bu yöntemde, baskı kalıbında görüntü alanları ile görüntü dışı alanlar arasında yalnızca mikroskobik düzeyde emülsiyon kalınlığı farkı bulunmaktadır. Görüntü ilk önce ters olarak kauçuk silindire, ardından baskı silindiri ile baskı altı malzemesi arasından geçerek düz biçimde baskı altı malzemesine aktarılır. Bu dolaylı aktarım yapısı, hem baskı kalitesini artırarak kalıp aşınmasını azaltır hem de ofset baskının “düz ve endirekt baskı sistemi” olarak tanımlanmasına temel oluşturmuştur (Ünal, 1988; Kipphan, 2001; Birişik, 2023; Hayta & Oktav, 2023). Şekil 3 ile ofset baskı sistemi gösterilmiştir (Hayta & Oktav, 2023).




Şekil 3. Ofset baskı sistemi

Ofset baskının hızla yaygınlaşmasının temel nedenlerinden biri, yüksek baskı kalitesini seri üretim kapasitesiyle birleştirebilmesidir. Özellikle metin ve görsel ağırlıklı işlerde sağladığı netlik, ton geçişlerindeki süreklilik ve renk kararlılığı, bu yöntemin gazete, dergi, kitap ve ticari basım alanlarında uzun yıllar boyunca tercih edilmesini sağlamıştır (Kipphan, 2001; Yılmaz, 2021). Ayrıca farklı kâğıt türleri üzerinde tutarlı sonuçlar verebilmesi, ofset baskının endüstriyel ölçekte benimsenmesini kolaylaştırmıştır (Ural vd., 2022). Teknolojik gelişmeler, ofset baskının yalnızca makine sistemleri açısından değil, kalıp teknolojileri bakımından da önemli bir evrim geçirmesine olanak tanımıştır (Büyükpehlivan & Oktav, 2021; Yılmaz, 2021; Yılmaz vd., 2021). İlk dönemlerde kullanılan çinko esaslı kalıplar zamanla yerini alüminyum kalıplara bırakmış; bu dönüşüm, ince tram noktalarının daha sağlıklı aktarılmasını ve baskı hassasiyetinin artmasını mümkün kılmıştır. Alüminyum kalıpların hafifliği, yüzey dayanımı ve nem-mürekkep dengesini daha etkin biçimde sağlaması, ofset baskının kalite standartlarını

yükselten temel unsurlar arasında yer almıştır (Ünal, 1988; Birişik, 2023; Hayta & Oktav, 2023). Ofset baskının yaygınlaşmasını destekleyen bir diğer önemli gelişme, ön baskı süreçlerinde yaşanan teknolojik ilerlemelerdir (Birişik, 2023). Fotodizgi ve film tabanlı sistemlerin ardından bilgisayar destekli ön baskı uygulamalarının ve CTP (Computer to Plate) teknolojilerinin kullanıma girmesiyle üretim süreçleri daha kontrollü, hızlı ve tekrarlanabilir bir yapıya kavuşmuştur. Bu durum, insan kaynaklı hataların azalmasına ve üretim verimliliğinin artmasına doğrudan katkı sağlamıştır (Büyükpehlivan & Oktav, 2021; Hayta & Oktav, 2023; Ural, 2025). Ekonomik açıdan değerlendirildiğinde, ofset baskı uzun yıllar boyunca özellikle yüksek tirajlı işlerde sunduğu birim maliyet avantajı sayesinde basım endüstrisinin temel üretim yöntemi olmuştur (Kipphan, 2001; Bann, 2010; Büyükpehlivan & Oktav, 2021). Kurulum maliyetlerinin yüksek olmasına karşın, tiraj arttıkça düşen baskı maliyetleri, ofset baskıyı büyük ölçekli üretimler için cazip hâle getirmiştir. Bu özellik, yöntemin sektörel ölçekte uzun süre baskın konumda kalmasını sağlamıştır (Erdoğanaras, 2004). Ancak müşteri taleplerinin kısa termin süreleri, kişiselleştirilmiş üretim ve esnek baskı çözümlerine yönelmesiyle birlikte ofset baskının sınırlılıkları daha belirgin hâle gelmiştir (Birişik, 2023). Dijital baskı teknolojilerinin gelişmesiyle rekabet ortamı değişmiş olsa da ofset baskı, yüksek hacimli ve kalite odaklı üretim gerektiren uygulamalarda günümüzde hâlâ önemli bir yere sahiptir (Suganuma, 2014; Yılmaz, 2021).

Tifdruk Baskı Teknikleri


Tifdruk baskı, baskı yapan alanların kalıp yüzeyinin altında yer aldığı çukur baskı sistemleri arasında yer almaktadır (Kipphan, 2001). Özellikle yüksek baskı kalitesi ve üretim sürekliliği gerektiren uygulamalar için geliştirilmiş bir tekniktir. Görüntü, kalıp yüzeyine oyulan veya kimyasal yöntemlerle oluşturulan hücreler aracılığıyla elde edilmektedir. Baskı sırasında bu hücreler mürekkeple doldurulmakta ve yüzeyde kalan fazla mürekkep rakle sistemiyle sıyırılmaktadır (Akdoğan, 2006; Suganuma, 2014). Tifdruk baskı sistemlerinde kalıplar genellikle silindir formundadır ve mürekkep, bu çukur hücrelerden doğrudan baskı altı malzemesine aktarılmaktadır. Silindirik yapı, sistemin yüksek hızlarda ve sürekli üretim hatlarında çalışmasına olanak tanımakta; bu durum tifdruk baskıyı özellikle çok yüksek tirajlı işler için ekonomik hâle getirmektedir (Kipphan, 2001; Erdoğanaras, 2004; Birişik, 2023). Baskı kalitesinin homojen ve tekrarlanabilir olması, tifdruk baskının fotoğraf ağırlıklı ve geniş zeminli işlerde tercih edilmesini sağlamaktadır (Ural vd., 2022). Tifdruk baskıda kullanılan mürekkepler düşük viskoziteli ve hızlı kuruma özelliklerine sahip olup, özellikle plastik film ve esnek ambalaj malzemeleri üzerinde yüksek parlaklık ve tutunma sağlamaktadır. Bu yönüyle tifdruk baskı, ambalaj ve dergi baskıları gibi alanlarda uzun yıllardır yaygın olarak kullanılmaktadır (Suganuma, 2014). Ancak kalıp hazırlama sürecinin maliyetli olması, yöntemin kısa tirajlı ve değişken üretimler için sınırlı kalmasına neden olmaktadır. Buna rağmen tifdruk baskı, yüksek hacimli ve kalite odaklı uygulamalarda günümüzde hâlâ önemli bir konuma sahiptir (Koldaş & Selamet, 2018; Ural, 2025). Şekil 4 tifdruk baskı sistemi görülmektedir (Ural vd., 2022).




Şekil 4. Tifdruk baskı sistemi

Flekso Baskı Sistemi

Flekso baskı sistemi, yüksek baskı prensibine dayanan ve esnek fotopolimer baskı kalıplarının kullanıldığı bir baskı tekniğidir (Kipphan, 2001; Birişik, 2023). Tipo baskı sisteminden türeyen bu yöntem, metal kalıplar yerine kauçuk veya fotopolimer esaslı klişelerin kullanılması sayesinde farklı baskı altı malzemelerine uyum sağlayabilmektedir. Bu özellik, flekso baskının özellikle ambalaj ve etiket üretiminde yaygınlaşmasında belirleyici bir rol oynamıştır (Keşan, 2008; Ergen, 2010; Ural vd., 2022). Flekso baskı sisteminde mürekkep, aniloks merdane üzerindeki mikro hücreler aracılığıyla kontrollü bir biçimde baskı kalıbına aktarılmakta ve buradan doğrudan baskı altı malzemesine iletilmektedir. Aniloks merdanenin hücre hacmi ve tram değeri, baskı sırasında aktarılan mürekkep miktarını belirleyerek baskı kalitesinin sürekliliğini sağlamaktadır. Sistemde genellikle düşük viskoziteli solvent bazlı, su bazlı veya UV kürlemeli mürekkepler kullanılmakta olup, bu mürekkeplerin hızlı kuruma özellikleri flekso baskının yüksek hızlarda çalışmasına olanak tanımaktadır (Kipphan, 2001; Keşan, 2008; Suganuma, 2014). Makine teknolojilerindeki gelişmeler, flekso baskı sisteminin kalite algısını önemli ölçüde değiştirmiştir. Özellikle dişli sistemlerden servo motorlu sistemlere geçiş, baskı üniteleri arasındaki senkronizasyonu artırmış; titreşim, kayma ve ton farklılıklarını azaltmıştır. Yapılan çalışmalar, servo sistemli flekso baskı makinelerinin renk tutarlılığı ve baskı stabilitesi açısından daha yüksek performans sunduğunu göstermektedir (Ergen, 2010; Zelzele & Özdemir, 2015). Buna paralel olarak dijital fotopolimer kalıpların kullanımı, daha ince tram değerleriyle çalışılmasına imkân tanımış ve flekso baskının ofset ve tifdruk gibi geleneksel baskı teknikleriyle rekabet edebilir bir kalite seviyesine ulaşmasına katkı sağlamıştır (Ergen, 2010; Suganuma, 2014; Zelzele & Özdemir, 2015). Sonuç olarak flekso baskı sistemi; yüksek üretim hızı, geniş baskı altı malzemesi yelpazesi ve gelişen makine ve kalıp teknolojileri sayesinde günümüz basım endüstrisinde önemli bir üretim yöntemi olarak konumlanmaktadır (Kipphan, 2001; Zelzele & Özdemir, 2015). Özellikle ambalaj sektöründe artan kalite beklentileri ve verimlilik gereksinimleri, flekso baskının sektörel önemini koruyarak gelecekte de yaygın biçimde kullanılacağını göstermektedir (Erdoğanaras, 2004; Ural, 2025). Şekil 5 flekso baskı makinesinin çalışma prensibini göstermektedir (Ergen, 2010). Toplu düzen flekso baskı makinesi Şekil 6 ile gösterilmiştir (Gençoğlu vd., 2009)




Şekil 5. Flekso baskı sistemi çalışması



Şekil 6. Toplu düzen flekso baskı makinesi

Serigrafi Baskı ve Uygulama Odaklı Kullanımı

Serigrafi baskı, mürekkebin bir elek (dokuma) üzerine hazırlanmış şablon aracılığıyla rakle yardımıyla baskı altı malzemesine aktarılmasına dayanan, kökeni oldukça eski olan bir baskı tekniğidir (Kipphan, 2001; Meggs & Purvis, 2016; Ural vd., 2022; Sesli, 2024). Bu baskı sisteminde kalite; dokuma sıklığı, emülsiyon kalınlığı, rakle sertliği ve baskı parametreleri gibi çok sayıda değişkene bağlı olarak şekillenmektedir ve bu değişkenlerin her biri baskı sonucunu doğrudan etkilemektedir. Özellikle dokuma sıklığının mürekkep film kalınlığı, renk yoğunluğu ve tram yapısı üzerinde belirleyici olduğu; uygun elek seçiminin nokta kazancı, densite ve renk evreni açısından kritik bir rol oynadığı deneysel çalışmalarla ortaya konmuştur (Akgül & Özakhun, 2012; Uğur, 2019; Özdemir vd., 2022; Sesli, 2024). Serigrafi baskının en önemli avantajlarından biri, düz olmayan veya üç boyutlu yüzeyler dâhil olmak üzere çok çeşitli baskı altı malzemeleri üzerinde uygulanabilmesidir; bu özellik yöntemin tekstil, cam, seramik, porselen ve elektronik gibi farklı sektörlerde yaygın biçimde kullanılmasını sağlamaktadır (Erdoğanaras, 2004; Koldaş & Selamet, 2018). Ayrıca serigrafi baskıda mürekkebin kalın tabaka hâlinde uygulanabilmesi, yüksek opaklık ve doygun renkler elde edilmesine olanak tanımakta ve bu durum yöntemi ofset ve flekso gibi diğer baskı tekniklerinden ayıran temel bir özellik olarak öne çıkmaktadır (Suganuma, 2014; Özdemir vd., 2022). Günümüzde otomatik serigrafi makineleri, gelişmiş emülsiyon sistemleri ve kalite standartlarının kullanımı sayesinde serigrafi baskı, deneme-yanılma temelli uygulamalardan uzaklaşarak daha kontrollü ve ölçülebilir bir üretim sürecine dönüşmüştür (Akgül & Özakhun, 2012; Ural, 2025). Şekil 7 ile serigrafi baskı tekniği gösterilmiştir (Uğur, 2019).



Şekil 7. Serigrafi baskı tekniği

GELENEKSEL BASKI YÖNTEMLERİNİN SINIRLARI VE ANALOGDAN DİJİTALE GEÇİŞ SÜRECİ

Geleneksel baskı yöntemleri uzun yıllar boyunca basım endüstrisinin temel üretim altyapısını oluşturmuş olsa da, bu sistemler teknik ve yapısal bazı sınırlılıklar barındırmaktadır (Yılmaz, 2021). Öncelikle kalıp temelli üretim yapıları, hazırlık süreçlerini zaman alıcı ve maliyetli hâle getirmekte; bu durum özellikle kısa tirajlı ve sık değişkenli işlerde verimliliği düşürmektedir (Ünal, 1988; Kipphan, 2001; Akdoğan, 2006). Ofset ve tıfdruk baskıda kalıp üretimi ve ayar süreçleri yüksek hassasiyet gerektirdiğinden esneklik sınırlı kalmakta; tıfdruk baskıda ise yüksek kalıp maliyetleri yöntemi yalnızca çok yüksek tirajlı üretimler için ekonomik olmaktadır (Erdoğanaras, 2004; Birişik, 2023). Flekso ve serigrafi baskı sistemleri malzeme çeşitliliği açısından avantaj sağlasa da, baskı kalitesinin çok sayıda parametreye bağlı olması sürecin standardizasyonunu zorlaştırmakta ve operatör deneyimine bağımlılığı artırmaktadır (Akgül & Özakhun, 2012). Bununla birlikte tüm geleneksel baskı sistemlerinde atık miktarının yüksek olması, kurulum ve ayar sürecinde ciddi malzeme ve enerji kayıplarına yol açmakta; bu durum çevresel sürdürülebilirlik açısından önemli bir sınırlılık oluşturmaktadır (Suganuma, 2014). Ayrıca kişiselleştirilmiş baskı, değişken veri kullanımı ve kısa teslim süreleri gibi güncel üretim talepleri karşısında geleneksel baskı yöntemlerinin yapısal olarak yetersiz kaldığı ve dijital baskı sistemleri karşısında rekabet gücünün azaldığı görülmektedir (Koldaş & Selamet, 2018; Ural, 2025). Bu nedenlerle geleneksel baskı yöntemleri günümüzde daha çok yüksek tirajlı, standartlaştırılmış ve uzun süre değişmeyen üretimlerde tercih edilmekte; esnek ve hızlı üretim gerektiren uygulamalarda ise yerini alternatif teknolojilere bırakmaktadır (Kipphan, 2001; Thompson, 2005). Tüm bu sınırlar basım endüstrisinin analogdan dijital geçiş sürecini başlatmıştır.

DİJİTAL BASIM TEKNOLOJİLERİ

Dijital basım teknolojileri, basım endüstrisinde üretim süreçlerini hız, esneklik ve kişiselleştirme ekseninde yeniden şekillendiren çağdaş üretim sistemleri olarak ortaya çıkmıştır. Kalıp gerektirmeyen yapıları sayesinde geleneksel baskı yöntemlerinden ayrılan bu teknolojiler, özellikle kısa tirajlı, değişken verili ve hızlı teslimat gerektiren baskı uygulamalarında önemli avantajlar sunmaktadır. Bu yönüyle dijital basım teknolojileri, analog baskı sistemlerinin teknik ve yapısal sınırlarına bir yanıt niteliği taşımakta ve basım endüstrisinde üretim anlayışının dönüşümünde merkezi bir rol üstlenmektedir (Erdoğanaras, 2004; Sesli & Oktav, 2021; Birişik, 2023; Ural, 2025).

Dijital Baskının Ortaya Çıkışı

Dijital baskının ortaya çıkışı, bilgisayar destekli tasarım ve veri işleme teknolojilerindeki gelişmelerle doğrudan ilişkilidir. Baskı öncesi, baskı ve baskı sonrası süreçlerin dijital ortamda bütünleşik olarak yönetilebilmesi, basım endüstrisinde üretim süreçlerini daha hızlı ve kontrol edilebilir hâle getirmiştir (Polat, 2018; Yılmaz, 2021). Geleneksel baskı sistemlerinde zor veya maliyetli olan değişken veri kullanımı, kişiselleştirilmiş içerik üretimi ve talep kadar baskı gibi uygulamalar, dijital baskı teknolojileriyle mümkün hâle gelmiştir (Birişik, 2023; Ural vd., 2022).

Dijital baskı sistemlerinin sektörde yaygınlaşmasında, müşteri taleplerinin çeşitlenmesi ve teslim sürelerine yönelik beklentilerin artması da etkili olmuştur (Thompson, 2005; Polat, 2018). Seri üretim odaklı analog baskı anlayışından farklı olarak dijital baskı, esnek üretim yapısıyla küçük ölçekli ve özelleştirilmiş işlere ekonomik çözümler sunmaktadır. Bu durum, dijital baskının basım endüstrisinde tamamlayıcı bir teknoloji olarak hızla benimsenmesine ve geleneksel sistemlerle birlikte hibrit üretim modellerinin gelişmesine zemin hazırlamıştır (Suganuma, 2014; Koldaş & Selamet, 2018).

Dijital Baskının Avantajları ve Sınırlılıkları

Dijital baskı teknolojileri, basım endüstrisinde üretim süreçlerini hız, esneklik ve kişiselleştirme açısından önemli ölçüde dönüştürmüş olsa da sunduğu avantajların yanında belirli teknik ve ekonomik sınırlılıklar da barındırmaktadır (Thompson, 2005; Polat, 2018). Dijital baskının en temel avantajı, kalıp gerektirmeyen üretim yapısıdır. Bu özellik, baskı öncesi hazırlık süreçlerini büyük ölçüde kısaltmakta ve özellikle kısa tirajlı işler için zaman ve maliyet avantajı sağlamaktadır. Geleneksel baskı sistemlerinde ekonomik olmayan düşük adetli üretimler, dijital baskı teknolojileri sayesinde talebe dayalı ve hızlı biçimde gerçekleştirilebilmektedir (Erdoğanaras, 2004; Yılmaz, 2021; Ural, 2025). Dijital baskının sunduğu bir diğer önemli avantaj, değişken veri kullanımına olanak tanımasıdır. Her baskı çıktısının içerik açısından farklı olabildiği bu yapı, kişiselleştirilmiş baskı uygulamalarını mümkün kılmakta; pazarlama, etiketleme ve yayıncılık gibi alanlarda dijital baskıyı stratejik bir üretim aracı hâline getirmektedir. Ayrıca baskı öncesi, baskı ve baskı sonrası süreçlerin yazılım tabanlı olarak entegre edilebilmesi, üretim süreçlerinin daha kontrol edilebilir ve izlenebilir olmasına katkı sağlamaktadır (Polat, 2018; Ural vd., 2022). Bu bütünleşik yapı, üretim hatalarının azaltılmasına ve iş akışının optimize edilmesine olanak tanımaktadır. Çevresel sürdürülebilirlik açısından bakıldığında, dijital baskı sistemleri daha düşük fire oranları ve talep kadar üretim imkânı sunması nedeniyle geleneksel baskı yöntemlerine kıyasla önemli avantajlar sağlamaktadır. Özellikle kurulum ve ayar aşamalarında oluşan atık miktarının düşük olması, malzeme ve enerji kullanımında verimliliği artırmaktadır. Bu durum, dijital baskının çevresel etkilerinin azaltılmasına yönelik güncel sektör beklentileriyle daha uyumlu bir yapı sunduğunu göstermektedir (Kipphan, 2001; Suganuma, 2014; Polat, 2018; Sesli & Oktav, 2021).

Bununla birlikte dijital baskı teknolojilerinin bazı sınırlılıkları da bulunmaktadır. Öncelikle, çok yüksek tirajlı ve uzun süre değişmeyen işler söz konusu olduğunda dijital baskı sistemleri, birim maliyet açısından analog baskı yöntemleriyle rekabet etmekte zorlanmaktadır (Kipphan, 2001; Thompson, 2005). Ofset ve tıfdruk gibi geleneksel baskı teknikleri, yüksek adetli üretimlerde hâlen daha düşük maliyetli çözümler sunabilmektedir (Ünal, 1988; Akdoğan, 2006; Polat, 2018). Ayrıca dijital baskı sistemlerinde kullanılan mürekkep ve tonerlerin malzeme uyumluluğu, baskı altı malzemesi çeşitliliği açısından bazı teknik kısıtlamalar oluşturabilmektedir. Baskı kalitesi açısından değerlendirildiğinde, dijital baskı teknolojileri son yıllarda önemli gelişmeler göstermiş olsa da, belirli uygulamalarda renk derinliği, yüzey dokusu ve özel efektler bakımından analog baskı sistemlerinin sunduğu sonuçlara her zaman tam olarak ulaşamamaktadır (Kipphan, 2001; Birişik, 2023). Bu durum, özellikle yüksek kalite beklentisi olan sanat baskıları veya özel ambalaj uygulamalarında dijital baskının kullanımını sınırlayabilmektedir (Koldaş & Selamet, 2018).

Sonuç olarak dijital baskı, basım endüstrisinde hız, esneklik ve kişiselleştirme gerektiren üretimler için güçlü bir çözüm sunarken; yüksek tirajlı, standartlaştırılmış ve uzun vadeli üretimlerde analog baskı sistemleriyle birlikte değerlendirilmesi gereken tamamlayıcı bir teknoloji olarak öne çıkmaktadır (Berman, 2012). Günümüzde basım endüstrisindeki üretim yapısı, dijital ve analog baskı teknolojilerinin kullanım amacına göre bir arada konumlandığı hibrit bir model doğrultusunda şekillenmektedir (Ural, 2025).

BASIM ENDÜSTRİSİNDE OTOMASYON VE ENDÜSTRİ 4.0

Basım endüstrisi, dijitalleşme sürecinin olgunlaşmasıyla birlikte yalnızca baskı teknolojileri açısından değil, üretim organizasyonu ve yönetim anlayışı açısından da önemli bir dönüşüm sürecine girmiştir. Bu dönüşüm, Endüstri 4.0 yaklaşımı kapsamında otomasyon, veri paylaşımı ve akıllı sistemlerin üretim süreçlerine entegre edilmesiyle şekillenmektedir. Geleneksel basım anlayışında insan müdahalesine dayalı olan birçok süreç, günümüzde sensörler, yazılımlar ve

otomatik kontrol sistemleri aracılığıyla daha izlenebilir, ölçülebilir ve optimize edilebilir hâle gelmiştir (Erdoğanaras, 2004; Birişik, 2023; Ural, 2025).

Akıllı Basım Sistemleri

Akıllı basım sistemleri, basım süreçlerinin otomasyon, veri analizi ve dijital kontrol mekanizmalarıyla bütünleştiği üretim yapıları olarak tanımlanmaktadır (Kipphan, 2001; Berman, 2012). Bu sistemlerde baskı öncesi, baskı ve baskı sonrası aşamalar; sensörler, yazılım tabanlı izleme araçları ve otomatik ayar mekanizmaları aracılığıyla birbirine entegre bir şekilde yönetilmektedir. Böylece üretim süreci boyunca makine performansı, malzeme kullanımı ve kalite parametreleri gerçek zamanlı olarak izlenebilmekte ve gerekli durumlarda otomatik müdahaleler gerçekleştirilebilmektedir (Kipphan, 2001; Ural vd., 2022). Akıllı basım sistemlerinin temel avantajlarından biri, üretim süreçlerinde insan kaynaklı hataların azaltılması ve kalite sürekliliğinin sağlanmasıdır. Geleneksel basım sistemlerinde operatör deneyimine bağlı olarak değişkenlik gösteren ayar süreçleri, akıllı sistemler sayesinde standartlaştırılmakta ve üretim çıktıları arasındaki tutarsızlıklar minimize edilmektedir. Bu durum, özellikle yüksek kalite beklentisinin bulunduğu ambalaj ve ticari baskı uygulamalarında önemli bir rekabet avantajı sunmaktadır (Koldaş & Selamet, 2018).

Endüstri 4.0 bileşenleriyle desteklenen akıllı basım sistemleri, yalnızca makine düzeyinde otomasyonu değil, aynı zamanda üretim planlama ve karar destek süreçlerini de kapsamaktadır (Kipphan, 2001; Petrasch & Hentschke, 2016). Üretim verilerinin dijital ortamda toplanması ve analiz edilmesi, bakım planlarının öngörücü yaklaşımlarla yapılmasına olanak tanımakta; arıza süreleri ve plansız duruşlar azaltılmaktadır. Bu bağlamda akıllı basım sistemleri, verimlilik artışı, maliyet kontrolü ve sürdürülebilir üretim hedefleri açısından basım endüstrisine önemli katkılar sağlamaktadır (Suganuma, 2014; Ural, 2025).

Bununla birlikte akıllı basım sistemlerine geçiş süreci, yüksek ilk yatırım maliyetleri ve nitelikli insan kaynağı gereksinimi gibi bazı sınırlılıkları da beraberinde getirmektedir. Özellikle küçük ve orta ölçekli basım işletmeleri için bu sistemlerin entegrasyonu, ekonomik ve teknik açıdan dikkatli planlama gerektirmektedir. Ancak uzun vadede sağlanan operasyonel verimlilik ve kalite avantajları, akıllı basım sistemlerinin basım endüstrisinde giderek daha yaygın bir şekilde benimsenmesine zemin hazırlamaktadır (Erdoğanaras, 2004).

SÜRDÜRÜLEBİLİRLİK VE ÇEVRESEL ETKİLER

Basım endüstrisinde sürdürülebilirlik ve çevresel etkiler, artan enerji tüketimi, hammadde kullanımı ve atık üretimi nedeniyle son yıllarda giderek daha fazla önem kazanan bir değerlendirme alanı hâline gelmiştir (Kipphan, 2001; Yenidoğan & Avcı, 2018; Çağlar, 2021). Geleneksel baskı yöntemleri, özellikle kurulum ve ayar aşamalarında oluşan yüksek fire oranları, kimyasal kullanımına dayalı süreçleri ve yoğun enerji gereksinimleri nedeniyle çevresel açıdan önemli yükler oluşturmaktadır. Ofset ve tıfdruk gibi kalıp temelli baskı sistemlerinde kalıp üretimi, mürekkep tüketimi ve temizlik işlemleri sırasında ortaya çıkan atıklar, çevresel etkilerin başlıca kaynakları arasında yer almaktadır (Erdoğanaras, 2004; Hayta, 2023). Dijital baskı teknolojilerinin gelişimi, bu çevresel baskılara karşı alternatif ve daha sürdürülebilir üretim modellerinin ortaya çıkmasına katkı sağlamıştır. Kalıp gerektirmeyen üretim yapısı sayesinde dijital baskı sistemleri, hazırlık aşamasındaki malzeme israfını azaltmakta; talep kadar üretim imkânı sunarak stok fazlası ve atık miktarını önemli ölçüde düşürmektedir. Ayrıca baskı öncesi ve baskı süreçlerinin dijital ortamda entegre biçimde yönetilmesi, enerji ve malzeme kullanımının daha kontrollü hâle gelmesine olanak tanımaktadır (Yenidoğan & Avcı, 2018; Ural vd., 2022; Güzel, 2024). Sürdürülebilirlik açısından yalnızca baskı teknolojileri değil, üretim organizasyonu ve iş akışlarının da çevre dostu yaklaşımlar doğrultusunda yeniden yapılandırılması gerekmektedir. Otomasyon ve veri temelli üretim sistemleri, makine verimliliğinin izlenmesini ve kaynak kullanımının optimize edilmesini

mümkün kılarak çevresel etkilerin azaltılmasına katkı sunmaktadır. Bu bağlamda dijitalleşme ve Endüstri 4.0 bileşenleri, basım endüstrisinde sürdürülebilir üretim hedeflerine ulaşmada stratejik araçlar olarak değerlendirilmektedir (Güzel, 2024). Bununla birlikte dijital baskı sistemlerinin de tamamen çevresel etkilerden bağımsız olduğu söylenemez. Dijital baskıda kullanılan mürekkepler, tonerler ve elektronik bileşenler, üretim ve bertaraf süreçlerinde farklı çevresel riskler oluşturabilmektedir. Bu nedenle basım endüstrisinde sürdürülebilirlik, tek bir baskı teknolojisinin tercih edilmesinden ziyade, üretim hacmi, ürün türü ve kullanım amacına göre en uygun teknolojinin seçildiği bütüncül bir yaklaşımı gerektirmektedir. Günümüzde çevresel etkilerin azaltılmasına yönelik çabalar, basım endüstrisinde teknoloji seçimini belirleyen temel kriterlerden biri hâline gelmiş ve sürdürülebilir üretim anlayışı sektörün geleceğini şekillendiren önemli bir unsur olarak öne çıkmıştır (Koldaş & Selamet, 2018; Hayta, 2023).

GÜNCEL TRENDLER VE GELECEK PERSPEKTİFİ

Basım endüstrisi, dijitalleşme ve otomasyon süreçlerinin olgunlaşmasıyla birlikte yalnızca mevcut üretim tekniklerini iyileştiren değil, üretim anlayışını yeniden tanımlayan bir dönüşüm sürecine girmiştir. Güncel eğilimler incelendiğinde, basım teknolojilerinin geleceğinin; veri temelli karar mekanizmaları, esnek üretim modelleri ve farklı üretim teknolojileriyle bütünleşik yapılar üzerinden şekillendiği görülmektedir. Bu bağlamda yapay zekâ destekli sistemler, kişiselleştirilmiş seri üretim yaklaşımları, üç boyutlu baskı teknolojileriyle kurulan kesişim alanları ve otonom üretim hatları, basım endüstrisinin gelecek perspektifini belirleyen temel eğilimler arasında yer almaktadır (Erdoğanaras, 2004; Güzel, 2024). Yapay zekâ destekli baskı yönetim sistemleri, üretim süreçlerinin izlenmesi, kalite kontrolü ve karar destek mekanizmalarının otomatikleştirilmesi açısından önemli bir potansiyel sunmaktadır (Sesli & Oktav, 2021; Güzel, 2024). Makine performans verilerinin analiz edilmesi, baskı parametrelerinin optimize edilmesi ve hata olasılıklarının önceden tahmin edilmesi gibi uygulamalar, insan müdahalesine olan bağımlılığı azaltarak üretim sürekliliğini ve kalite istikrarını artırmaktadır. Bu tür uygulamalar, özellikle Endüstri 4.0 kapsamında geliştirilen veri temelli üretim yaklaşımlarının basım endüstrisine uyarlanmasıyla mümkün hâle gelmektedir (Sesli & Oktav, 2021; Özdemir vd., 2022; Güzel, 2024). Kişiselleştirilmiş seri üretim, dijital baskı teknolojilerinin sağladığı değişken veri kullanımı sayesinde basım endüstrisinde giderek daha uygulanabilir bir üretim modeli hâline gelmiştir (Koldaş & Selamet, 2018). Geleneksel seri üretim anlayışından farklı olarak bu yaklaşım, yüksek adetli üretimlerde dahi içerik bazında farklılaşmaya olanak tanımakta; pazarlama, ambalaj ve yayıncılık alanlarında katma değeri yüksek ürünlerin ortaya çıkmasını sağlamaktadır. Bu durum, basım endüstrisinde müşteri odaklı üretim anlayışının güçlenmesine ve rekabet stratejilerinin yeniden şekillenmesine yol açmaktadır (Erdoğanaras, 2004; Güzel, 2024). Üç boyutlu baskı teknolojileri ile geleneksel basım teknolojileri arasındaki kesişim alanı ise henüz gelişim aşamasında olmakla birlikte, özellikle fonksiyonel yüzeyler, akıllı ambalajlar ve basılı elektronik uygulamalar açısından dikkat çekici bir potansiyel barındırmaktadır. Basım teknolojilerinin iki boyutlu görsel üretimin ötesine geçerek fonksiyonel katmanlar ve etkileşimli yüzeyler oluşturabilmesi, basım endüstrisinin farklı sektörlerle daha güçlü entegrasyon kurmasına zemin hazırlamaktadır (Suganuma, 2014; Hayta, 2023). Otonom üretim hatları ise otomasyon, sensör teknolojileri ve yazılım entegrasyonlarının bir araya gelmesiyle basım süreçlerinde insan müdahalesinin minimuma indirildiği üretim yapıları olarak öne çıkmaktadır (Güzel, 2024). Baskı öncesi ayarlardan bakım planlamasına kadar pek çok sürecin kendi kendini yöneten sistemler aracılığıyla yürütülmesi, verimlilik artışı ve kaynak kullanımında optimizasyon sağlamaktadır. Ancak bu sistemlerin yaygınlaşması, yüksek yatırım maliyetleri ve nitelikli insan kaynağı gereksinimi nedeniyle kademeli bir geçiş süreci gerektirmektedir (Erdoğanaras, 2004; Çağlar, 2021; Güzel, 2024).

Sonuç olarak basım endüstrisinin gelecek perspektifi; tamamen yeni teknolojilere yönelmekten ziyade, mevcut baskı sistemlerinin yapay zekâ, otomasyon ve veri temelli yaklaşımlarla desteklendiği hibrit üretim modelleri üzerinden şekillenmektedir. Bu eğilimler, basım endüstrisinin sürdürülebilirlik, esneklik ve rekabet gücü açısından dönüşümünü sürdürürken, teknolojik gelişmelerin kontrollü ve sektörel ihtiyaçlara uygun biçimde entegre edilmesini zorunlu kılmaktadır (Çağlar, 2021; Hayta, 2023; Güzel, 2024).

SONUÇ VE DEĞERLENDİRME

Bu çalışma kapsamında klasik baskı yöntemleri ile akıllı sistemlere dönüşmüş olan baskı teknolojilerinin değişim trendleri incelenmiştir. Ele alınan bulgular, basım endüstrisinin teknolojik evriminin yalnızca üretim araçlarının değişimiyle sınırlı olmadığını; sektörün üretim anlayışı, organizasyon yapısı ve rekabet stratejileri üzerinde de köklü etkiler yarattığını göstermektedir. Geleneksel baskı yöntemleri uzun yıllar boyunca basım endüstrisinin temel üretim altyapısını oluşturmuş olsa da, dijitalleşme süreciyle birlikte hız, esneklik, kişiselleştirme ve sürdürülebilirlik gibi parametrelerin sektörde belirleyici hâle gelmesi, mevcut üretim modellerinin yeniden değerlendirilmesini zorunlu kılmıştır. Bu durum, teknolojik evrimin basım endüstrisinde yalnızca teknik bir dönüşüm değil, aynı zamanda stratejik bir yeniden konumlanma süreci yarattığını ortaya koymaktadır.

Çalışma bulguları, basım endüstrisinde geleneksel ve dijital baskı sistemlerinin birbirinin alternatifi olmaktan ziyade, kullanım amacına göre birlikte değerlendirilen hibrit yapılar hâlinde konumlandığını göstermektedir. Yüksek tirajlı ve standartlaştırılmış üretimlerde geleneksel baskı sistemleri maliyet avantajını korurken, kısa tirajlı, değişken verili ve kişiselleştirilmiş üretimlerde dijital baskı teknolojileri ön plana çıkmaktadır. Bu hibrit yapı, basım işletmelerine üretim esnekliği kazandırmakta ve farklı müşteri taleplerine daha etkin biçimde yanıt verme olanağı sunmaktadır. Dolayısıyla sektördeki dönüşüm, “gelenekselden dijitale geçiş” şeklinde doğrusal bir ilerlemeden ziyade, teknolojilerin birlikte ve tamamlayıcı biçimde kullanıldığı çok katmanlı bir yapıyı işaret etmektedir.

Geleceğe yönelik perspektif değerlendirildiğinde, basım teknolojilerinin yönünün tamamen yeni ve radikal üretim sistemlerine geçmekten çok, mevcut baskı altyapılarının yapay zekâ, otomasyon ve veri temelli yaklaşımlarla desteklenmesi doğrultusunda şekilleneceği öngörülmektedir. Akıllı basım sistemleri, otonom üretim hatları ve veri odaklı karar mekanizmaları, sektörde verimlilik artışı ve sürdürülebilir üretim hedefleri açısından önemli fırsatlar sunmaktadır. Ancak bu dönüşümün başarılı olabilmesi, teknolojik yatırımların sektörel ihtiyaçlar doğrultusunda planlanmasına, insan kaynağının niteliğinin geliştirilmesine ve dönüşüm sürecinin kademeli biçimde yönetilmesine bağlıdır. Sonuç olarak basım endüstrisinin geleceği, teknolojik gelişmelerin kontrollü entegrasyonu ve hibrit üretim modellerinin stratejik kullanımı üzerinden şekillenen dengeli bir dönüşüm sürecine işaret etmektedir.

KAYNAKÇA

Akdoğan, A. E. (2006). Basılı ürünlerin incelenerek üzerine uygulanan baskı tekniklerinin belirlenmesi (Yüksek lisans tezi). Marmara Üniversitesi Fen Bilimleri Enstitüsü, İstanbul.

Akgül, A., & Özakhun, Ş. C. (2012). Serigrafi baskı sistemi kullanılarak yapılan dekal baskıda dokuma sıklığının baskı kalitesine etkisinin belirlenmesi. İstanbul Ticaret Üniversitesi Fen Bilimleri Dergisi, 10(20), 143-152.

Berman, B. (2012). 3-D printing: The new industrial revolution. Business Horizons, 55(2), 155–162. <https://doi.org/10.1016/j.bushor.2011.11.003>

Berman, S. J. (2012). Digital transformation: Opportunities to create new business models. Strategy & Leadership, 40(2), 16–24. DOI: [10.1108/10878571211209314](https://doi.org/10.1108/10878571211209314)

Birişik, B. İ. (2023). Temel baskı sistemlerinin ayırıcı özelliklerinin incelenmesi (Yüksek lisans tezi). Marmara Üniversitesi.

Büyükpehlivan, G. A., & Oktav, M. (2021). Ofset baskı sistemine ait temel terimler ve değerlendirilmesi. *Avrasya Terim Dergisi*, 9(2), 63-68.

Çağlar, T. (2021). Basım endüstrisinde sürdürülebilirlik yaklaşımı: Karton etiket üretimi üzerine bir çalışma (Yüksek lisans tezi). Marmara Üniversitesi.

Erdoğanaras, F. (2004). Basım ve yayın sektöründe yeni teknolojilere dayalı yeniden yapılanma süreci: istanbul örneği. *Gazi Üniversitesi Mühendislik Mimarlık Fakültesi Dergisi*, 19(1).

Ergen, C. (2010). Flekso baskı sistemindeki gelişmelerin baskı kalitesine etkisinin incelenmesi (Yüksek lisans tezi). Marmara Üniversitesi, Fen Bilimleri Enstitüsü.

Gençoğlu, E., Şimşeker, O., Özdemir, L., (2009). Flekso Baskı Sistemi, Geliştirilmiş 2. Baskı, DuPont Türkiye, İstanbul.

Güzel, H. Y. (2024). Basım sanayisinde Endüstri 4.0 teknolojilerinin sürdürülebilir üretime etkileri (Yüksek lisans tezi). Marmara Üniversitesi, Türkiye.

Hayta, P. (2023). Basım Sektöründe Sürdürülebilir ve Ekolojik Malzemelerin İncelenmesi. *Dynamics in Social Sciences and Humanities*, 4(2), 78-83.

Hayta P., Oktav M. (2023) “Ofset Baskıda Yolma Probleminin İncelenmesi”, *Sosyal ve Beşeri Bilimlerde Uluslararası Araştırma ve Derlemeler*, Serüven Yayınevi: 217-234.

İpek, A. R. (2023). Özgün baskıda tipo baskı makinalarının kullanımı. *RumeliDE Dil ve Edebiyat Araştırmaları Dergisi*, (35), 811-827.

Keşan, N. (2008). Flesko Baskı Sistemi için baskı Hazırlık Ve Kalıp Hazırlama Parametrelerinin İncelenmesi (Yüksek lisans tezi). Marmara Üniversitesi, Türkiye.

Kipphan, H. (Ed.). (2001). *Handbook of print media: Technologies and production methods*. Springer.

Koldaş, K., & Selamet, S. (2018). Geçmişin penceresinden geleceğe bakmak: Yeni yüzyılda tipo baskı. 6. Uluslararası Matbaa Teknolojileri Sempozyumu Bildiriler Kitabı

Lu, Y. (2017). Industry 4.0: A survey on technologies, applications and open research issues. *Journal of Industrial Information Integration*, 6, 1–10.

Masod, M. Y., & Zakaria, S. F. (2023). The health and outlook of printing industry post-Covid-19: the insight into Malaysia printing industry. *Journal of Print and Media Technology Research*, 12(1), 21-34.

Meggs, P. B., & Purvis, A. W. (2016). *Meggs' history of graphic design* (6th ed.). Wiley.

Özdemir, L., Kurt, M. B., Akgül, A., Oktav, M., & Duman, M. N. (2022). Optimization of ink consumption in screen printing within color difference limits. *Pigment & Resin Technology*, 53(1), 17-27.

Petrash, R., & Hentschke, R. (2016, July). Process modeling for industry 4.0 applications: Towards an industry 4.0 process modeling language and method. In *2016 13th International Joint Conference on Computer Science and Software Engineering (JCSSE)* (pp. 1-5). IEEE.

Polat, H. H. (2018). Endüstriyel baskı teknikleri ve dijital baskı. *The Journal of Academic Social Science*. <https://doi.org/10.16992/ASOS.14319>

SESLİ, Y., & OKTAV, M. (2021). Dijital baskı sistemlerinde baskı kalitesine etki eden parametrelerin belirlenmesi. *Euroasia Journal Of Mathematics, Engineering, Natural & Medical Sciences*, 8(14), 120-131.

Sesli, Y. (2024). Serigrafi baskı temel terimlerinin tanımlanması. *Avrasya Terim Dergisi*, 12(1), 15-22.

Suganuma, K. (2014). Printing Technology. In *Introduction to Printed Electronics* (pp. 23-48). Springer, New York, NY.

Thompson, J. B. (2005). *Books in the digital age: The transformation of academic and higher education publishing*. Polity Press.

Uğur, E. (2019). Serigrafi Baskı Tekniğinde Kalıp Malzemesi Olarak Kullanılan Sentetik Dokumaların Baskı Kalitesi ve Kullanım Performansını Belirleyen Üretim Süreçlerinin Analizi. *Avrupa Bilim ve Teknoloji Dergisi*, (15), 526-534.

Ural, E., Özdemir, L., Özomay, Z. (2022) “Tasarımda Baskı Süreçleri”, *Tasarım ve Baskı Süreçleri Üzerine Akademik Yaklaşımlar, Sonçağ Yayıncılık*: 130-142.

Ural, E. (2025). Baskı Öncesi Hazırlıkta Kullanılan Terimler ve Tanımlamaları. *Avrasya Terim Dergisi*, 13(1), 24-29.

Ünal, H. (1988). Ofset baskı kalıpları teknolojisi (Yüksek lisans tezi). Marmara Üniversitesi, Fen Bilimleri Enstitüsü.

Yenidoğan, S. & Avcı, N. Basım Endüstrisinde Atık Yönetiminin İncelenmesi/Waste Management Examination for The Printing Industry.

Yılmaz, A. (2021) *Grafik Tasarımda Dijital Baskı ve Ofset Baskı Arasındaki Fark. (Yüksek Lisans Tezi)*. İstanbul Arel Üniversitesi Lisansüstü Eğitim Enstitüsü, İstanbul, Türkiye.

Yılmaz, U., Tutuş, A., & Sönmez, S. (2021). Investigation of Color Properties of Offset, Laserjet and Inkjet Printing on Uncoated Recycled Papers. *Erciyes Üniversitesi Fen Bilimleri Enstitüsü Fen Bilimleri Dergisi*, 37(1), 130-136.

Zelzele, Ö., & Özdemir, L. (2015). Dijital termal flekso baskı kalıbı hazırlama parametrelerinin, kalıp üzerindeki nokta yapısına etkisinin incelenmesi. *Marmara Fen Bilimleri Dergisi*, 27(2), 63-75.

NUMERICAL INVESTIGATION OF THE ELECTRONIC AND ELECTRICAL CHARACTERISTICS OF InGaN / GaN MULTIPLE QUANTUM WELL SOLAR CELLS

Rajab Yahyazadeh, Zahra Hashempour

Department of Physics, Khoy.C., Islamic Azad University, Khoy, Iran

Abstract: In this paper, numerical model allows to analysis photovoltaic parameters according to the electronic properties of InGaN/GaN multiple quantum well solar cell (MQWSC) under hydrostatic pressure. Finite difference techniques have been used to acquire energy eigenvalues and their corresponding eigenfunctions of InGaN/GaN MQWSC and the hole eigenstates are calculated via a 6×6 k.p method under an applied hydrostatic pressure. It was found that the depth of the quantum wells, bandgaps, band offset, the electron, and hole density increases with the increases hydrostatic pressure. Also, as the pressure increases, the electron and hole wave functions will have less overlap, the amplitude of the absorption coefficient increases, and the binding energy of the excitons decreases. A change in pressure of up to 10 GPa causes the absorption coefficients peaks of light and heavy holes to shift to low wavelengths of up to 32 nm, decreases short-circuit current density and increases open circuit voltage.

Keywords: optical absorption, solar cell, multi-quantum well, hydrostatic Pressure

1 Introduction

Nitride heterstructures are important because of the high energy gap, high electron density in the quantum well, and the high electrical conductivity [1,2]. These heterstructures are used in the manufacture of electronic components (e.g. transistors and diodes, optical components, solar cells) and industrial components such as electrical switches (disconnecting or connecting electrical circuits that act as converters) [3-4]. However, the dependence of temperature and hydrostatic pressure on the electronic, optical and mechanical properties of III-V nitrides has become the subject of numerous studies [5, 6]. Other researches were interested in the influence of pressure on the electronic and optical properties of GaN hetrostructure [7]. This effect is one of the best tools for enhancing the physical specifications of these heterostructures[8]. Theoretical investigation of the pressure's dependences on the optical properties in InGaN/GaN QW is studied by El Ghazi et al [9]. Therefore, it is important to study the effect of hydrostatic pressure on optical and electrical parameters such as the electron and hole density, subband transition energy, current density and absorption coefficient of MQW. Given that the absorption coefficient is the most important parameter in calculating and studying the current in solar cells, it needs to be studied under external pressure perturbation. Most articles present the analytical formula obtained from the experimental results for the absorption coefficient, which depends on the energy gap used in the calculation of the photoelectric current of solar cells. A precise measure of current density in solar cells requires numerical calculations of the absorption coefficient. [10].

2. Hetrostructure Modeling

The quantum well solar cell(QWSC)consists of a multiple quantum well structure in the intrinsic region of a p-i-n cell. The MQW structure introduced for the model is constructed by a InGaN with lower indium molar fraction($x=0.4$) for barrier and $x=0.5$ for wells, which is schematically shown in Fig. 1. In order to obtain accurate values for Fermi energy, the energies of quantized levels within the 2DEG, potential profiles, wave function and the sheet carrier

concentration, both the Schrodinger and Poisson equations must be solved self consistently. This has been achieved by solving Schrodinger's equation and simultaneously taking into account the electrostatic potential obtained from Poisson's equation, as well as the image and exchange-correlation potentials using three-point finite difference method. The relationship between current density J and voltage V for a MQW solar cell is presented by $J(V) = J_{QW0} [1 + r_R \beta] [\exp(qV/k_B T) - 1] - J_{ph}$ [11,12]:

where J_{QW0} is the saturation current density, J_{ph} is the photocurrent density, k_B is the Boltzmann constant, q is the elementary charge, T is the temperature, r_R is the radiative enhancement rate and β is the ratio of the current required to feed radiative recombination in the intrinsic region at equilibrium to the usual reverse drift current resulting from minority carrier extraction [11,12]. The term $r_R \beta$ account for the radiative recombination within the intrinsic region which has been developed by Anderson [12]

3 Results and Discussion

In this paper, we presented a numerical model to calculate the optical and electrical parameters of InGaN/GaN multiple quantum well solar cell (MQWSC), which investigate the effect of the hydrostatic pressure. We conducted the iteration between the Schrödinger–Poisson equation systems by a three-point finite difference method to obtain a self-consistent solution of basic equations. During the self-consistent calculation, a grid spacing as small as $1 \times 10^{-10} m$ and the convergent criteria for the electrostatic potential is set to be 0.1% to ensure the iteration convergence and stability of our calculation. The hole eigenstates are calculated along the Z-axis using a 6×6 k.p method. Conduction and valance bands with location of quantum wells (electrons and holes) as well as valance bands for light and heavy holes are shown in Figure 2. According to Figure 2, after determining the pressure dependence of the wave functions, the energy of the subbands and the overlap integral, the absorption coefficient can be calculated. Moreover, with increasing pressure, the absorbed photon energy increases, and the corresponding wavelength decreases which are related to increasing the bandgaps energy with pressure. In this figure, two peaks are observed for each pressure, which is associated with the light and heavy holes of the valance band. The second point is associated with changes in the amplitude of the absorption coefficient. As the pressure increases, the amplitude of the absorption coefficient decreases. In other words, Low overlap of wave functions and deepening of quantum wells increase quantum confinement. Which also reduces the absorption coefficient. Therefore, increasing the pressure will weaken the amplitude. Figure 3 depicts the curves of the current-voltage for different hydrostatic pressure values. The hydrostatic pressure dependence of short-circuit current density (J_{SC}) and open circuit voltage (V_{OC}), for the different pressure values can be seen from Figure 4. In the case $P = 0 \text{ GPa}$ at room temperature, the J_{SC} value is 22.3 mA cm^{-2} and decreases further to 13.8 mA cm^{-2} at $P = 10 \text{ GPa}$. However, with the increasing hydrostatic pressure, the short-circuit current density decreases due to the band gap increasing and low overlap of wave functions. Furthermore, the increases of the band gap energy results in lower absorption of lower wavelength incident light, this will allow low electron to jump into the conduction band which lead to a decrease in current density. The V_{OC} increases almost linearly with 1.32 V at $P = 0 \text{ GPa}$ of 1.73 V for $P = 10 \text{ GPa}$. This is mainly attributed to the band-gap increment with the increasing hydrostatic pressure.




Fig. 1. Schematic profile of p-GaN-i(InGaN/GaN MQWSC)-n-GaN.




Fig. 3. Absorption coefficient for p-GaN-i(InGaN / GaN MQWSC)-n-GaN versus different hydrostatic pressure




Fig. 2. The conduction(C.B) and valance(V.B) bands energy of InGaN/GaN MQW as a function of the distance under different hydrostatic pressure.




Fig. 4. Current-voltage characteristic of 10-MQW p-GaN-i(InGaN / GaN MQWSC)-n-GaN solar cell for various hydrostatic pressure.

References

1. R. Chu, GaN power switches on the rise: Demonstrated benefits and unrealized potentials., *Appl. Phys. Lett.*, **116**, 090502 (2020).
2. G. Hu, L. Lib, Y. Zhang, Two-dimensional electron gas in piezotronic devices, *Nano Energy*, **59**, 667–673 (2019).
3. R. Yahyazadeh, Zahra hashempour, Effects of Hydrostatic Pressure and Temperature on the AlGaIn/GaN High Electron Mobility Transistors, *Journal of Interfaces, Thin films, and Low dimensional systems*, **2(2)**, 183-194 (2019).
4. R Yahyazadeh, Z. Hashempour, Numerical Optimization for Source-Drain Channel Resistance of AlGaIn/GaN HEMTS, *Journal of Science and technology*, **11(1)**, 1-9 (2019).
5. C. M. Duque, A. L. Morales, M. E. Mora-Ramos, C. A. Duque, Exciton-related optical properties in zinc-blende GaN/InGaIn quantum wells under hydrostatic pressure, *Physica Status Solidi (b)*, **252**, 670 (2015).
6. Z.H. Zhang, J.H. Yuan, K.X. Guo, The Combined Influence of Hydrostatic Pressure and Temperature on Nonlinear Optical Properties of $\text{Al}_{0.3}\text{Ga}_{0.7}\text{As}/\text{GaAs}$ Morse Quantum Well in the Presence of an Applied Magnetic Field, *Materials*, **11**, 668 (2018).
7. C. X. Xia, Z. P. Zeng, Z. S. Liu, S. Y. Wei, Exciton states in zinc-blende GaN/AlGaIn quantum dot: Effects of electric field and hydrostatic pressure, *Physica B: Condensed Matter*, 405, 2706 (2010).

8. Y. Liu et al, Effect of hydrostatic pressure on the current-voltage characteristics of GaN/AlGa_N/Ga_N heterostructure devices, *Journal of Applied Physics*, **99**(11), 113706(2006).
9. H. El Ghazi, A. Jorio, Electron-hole transition in spherical QD-QW nanoparticles based on GaN|(In,Ga)N|Ga_N under hydrostatic pressure, *Physica B*, **429**, 42 (2013).
10. B. Chouchen, M. H. Gazzah, A. Bajahzar, Hamed Belmabrouk, Numerical Modeling of the Electronic and Electrical Characteristics of InGa_N/Ga_N-MQW Solar Cells, *Materials*, **12**,1241 (2019).
11. N.G. Anderson, Ideal theory of quantum well solar cells, *J. Appl. Phys*, **78**, 1850 (1995).

**ENDÜSTRİ MÜHENDİSLİĞİNDE YAPAY ZEKANIN ROLÜ: VERİ ODAKLI
KARAR VERME VE AKILLI SİSTEMLERE DÖNÜŞÜM**

Raniyah RAFEA KHALAF

Dumlupınar Üniversitesi, Lisansüstü eğitim Enstitüsü, Teknoloji ve İnovasyon Yönetimi
Bölümü, Kütahya / Türkiye

ORCID: 0009-0006-0133-6800

Prof. Dr. Arif GÖK

Dumlupınar Üniversitesi, Mimarlık Fakültesi, Endüstriyel Tasarım Bölümü

ORCID: 0000-0003 2840 9601

ÖZET

Endüstri Mühendisliği disiplini, geleneksel optimizasyon ve süreç iyileştirme yaklaşımlarından, veri odaklı ve yapay zekâ (YZ) destekli karar verme mekanizmalarına doğru köklü bir dönüşüm geçirmektedir. Endüstri 4.0 ve gelişmekte olan Endüstri 5.0 perspektifinde, yapay zekâ teknikleri sadece otomasyonu sağlamakla kalmayıp, karmaşık sistemlerin modellenmesinde ve belirsizliklerin yönetiminde kritik bir rol oynamaktadır. Bu çalışmada, yapay zekanın endüstri mühendisliğindeki dönüştürücü gücü; üretim planlama, risk yönetimi, sağlık sistemleri ve tedarik zinciri gibi farklı uygulama alanları üzerinden ele alınmıştır.

Özellikle makine öğrenmesi algoritmaları, bulanık mantık yaklaşımları ve derin öğrenme tekniklerinin, sistem verimliliğini artırmada ve insan hatasını minimize etmede nasıl kullanıldığı incelenmiştir. Yapılan literatür taraması ve vaka analizleri, YZ entegrasyonunun proje yönetiminde risklerin erken tespitinden, tarımsal üretimde verim tahminlemesine kadar geniş bir yelpazede katma değer yarattığını göstermektedir. Ayrıca, insan-makine iş birliğini temel alan yeni nesil akıllı sistemlerin, sürdürülebilirlik ve esneklik hedeflerine ulaşmada endüstri mühendislerine yeni yetkinlikler kazandırdığı vurgulanmıştır. Sonuç olarak, yapay zekâ bir araç olmaktan öte, modern endüstri mühendisliği problemlerinin çözümünde stratejik bir ortak haline gelmiştir.

Anahtar Kelimeler: Endüstri Mühendisliği, Yapay Zeka, Karar Destek Sistemleri, Makine Öğrenmesi, Dijital Dönüşüm.

**THE ROLE OF ARTIFICIAL INTELLIGENCE IN INDUSTRIAL ENGINEERING:
TRANSFORMATION TO DATA-DRIVEN DECISION MAKING AND SMART
SYSTEMS**

ABSTRACT

The discipline of Industrial Engineering is undergoing a radical transformation from traditional optimization and process improvement approaches to data driven and Artificial Intelligence (AI) supported decision-making mechanisms. Within the perspective of Industry 4.0 and the emerging Industry 5.0, AI techniques not only provide automation but also play a critical role in modeling complex systems and managing uncertainties. In this study, the transformative power of AI in industrial engineering is discussed through various application areas such as production planning, risk management, healthcare systems, and supply chains. Specifically, the use of machine learning algorithms, fuzzy logic approaches, and deep learning techniques to increase system efficiency and minimize human error has been examined. The literature review and case analyses demonstrate that AI integration creates value across a wide spectrum, ranging from early detection of risks in project management to yield prediction in agricultural production. Furthermore, it is emphasized that next-generation smart systems based on human machine collaboration provide industrial engineers with new competencies in

achieving sustainability and flexibility goals. Consequently, AI has become more than just a tool; it has evolved into a strategic partner in solving modern industrial engineering problems.

Keywords: Industrial Engineering, Artificial Intelligence, Decision Support Systems, Machine Learning, Digital Transformation.

1.GİRİŞ

Endüstri Mühendisliği, doğası gereği insan, makine, malzeme ve bilgi arasındaki karmaşık ilişkileri optimize etmeyi amaçlayan bir disiplindir. Sistemlerin karmaşık yapısını ve birbirleriyle olan ilişkilerini modellemek, mühendisliğin temel taşlarından biridir [1]. Ancak günümüzde bu optimizasyon süreçleri, sadece matematiksel modellemelerle sınırlı kalmamakta; verinin olduğu her yerde yapay zekâ (YZ) destekli karar destek mekanizmalarına evrilmektedir. Endüstri 4.0 ile başlayan dijitalleşme süreci ve günümüzde konuşulan Endüstri 5.0 kavramı (insan odaklı teknoloji), biz endüstri mühendislerini klasik “süreç iyileştiriciler” olmaktan çıkarıp “veri bilimci” ve “sistem mimarı” rollerine taşımıştır.

Bu çalışmanın temel motivasyonu, yapay zekanın sadece teorik bir kavram olmadığını, endüstri mühendisliğinin temel uygulama alanları olan üretim planlama ve imalat süreçlerinde nasıl somut avantajlar sağladığını göstermektir [2]. Özellikle makine öğrenmesi algoritmalarının (Random Forest, XGBoost vb.) olasılıksal temelleri [3] ve çok kriterli karar verme (ÇKKV) tekniklerinin entegrasyonu, belirsizlik altındaki karar verme süreçlerini kökten değiştirmektedir. Kongre kapsamında sunduğum bu çalışma, farklı sektörlerdeki (tarım, sağlık, e-ticaret ve proje yönetimi) YZ uygulamalarını inceleyerek, bu teknolojilerin operasyonel verimlilik üzerindeki etkisini ortaya koymayı amaçlamaktadır.

2.LİTERATÜR VE YÖNTEM

Bu çalışmada, endüstri mühendisliği problemlerinin çözümünde kullanılan yapay zekâ tekniklerinin etkinliğini ölçmek amacıyla nitel araştırma yöntemlerinden doküman incelemesi ve vaka analizi (case study) yöntemi benimsenmiştir. Literatürde vaka analizi çalışmaları, akademik başarıdan endüstriyel uygulamalara kadar geniş bir yelpazede bilgi keşfi için kullanılmaktadır [4]. Araştırma, tek bir sektöre odaklanmak yerine, YZ’nin esnekliğini göstermek adına disiplinler arası bir yaklaşım sergilemektedir. Benzer şekilde, mühendislik yapılarının sayısal analizlerinde de görüldüğü üzere, karmaşık sistemlerin analizi deneysel ve sayısal yöntemlerin birleşimini gerektirir [5].

Araştırmanın evreni, son 5 yıl içerisinde (2020-2025) endüstri mühendisliği literatüründe yayınlanmış yapay zekâ ve dijital dönüşüm odaklı akademik çalışmalardır. Araştırmanın örnekleme ise, amaçsal örnekleme (purposive sampling) yöntemiyle seçilmiş, farklı uygulama alanlarını temsil eden 5 temel çalışma alanından oluşmaktadır:

Tarımsal Endüstri: Akıllı zeytin yetiştiriciliği ve verim tahmini.

Sağlık Sistemleri Mühendisliği: Hastalıkların erken teşhisinde tahmin modelleri.

Hizmet ve Bilişim Sektörü: Bulut servisi sağlayıcı seçiminde karar destek sistemleri.

E-Ticaret: Öneri sistemleri ve sohbet robotları (Chatbot) entegrasyonu.

Proje Yönetimi: Risk analizinde yapay zeka kullanımı.

Araştırma modeli kapsamında ele alınan değişkenler şu şekildedir:

Bağımsız Değişkenler: Kullanılan Yapay Zeka Teknikleri (Örn: Makine Öğrenmesi, Derin Öğrenme, Bulanık Mantık, AHP/TOPSIS), Veri Kaynağı Türü (Sensör verisi, hasta kayıtları, müşteri logları) ve Sektör Türü.

Bağımlı Değişken: Karar Verme Doğruluğu (Accuracy), Sistem Verimliliği, Risk Tespit Süresi ve Tahmin Performansı (F1-Score, RMSE değerleri).

Burada amaç, bağımsız değişken olan “farklı YZ algoritmalarının”, bağımlı değişken olan “sistem başarısı” üzerindeki etkisini sektörel bazda incelemektir.

3.BULGULAR

Yapılan analizler sonucunda, endüstri mühendisliğinde yapay zekâ kullanımının sektörel bazda şu somut çıktıları sağladığı tespit edilmiştir:

3.1.Üretim ve Tarım Endüstrisinde Tahminleme Başarısı

İncelenen akıllı tarım uygulamalarında, geleneksel yöntemlerin aksine, IoT tabanlı sensörlerden alınan nem, sıcaklık ve toprak verilerinin YZ algoritmalarıyla işlenmesi sayesinde verim tahmininde yüksek başarı sağlandığı görülmüştür. Bulgularımız, YZ destekli sistemlerin sadece izleme yapmadığını, aynı zamanda “kestirimci bakım” mantığıyla bitki hastalıklarını oluşmadan önce haber verebildiğini göstermektedir. Bu durum, endüstri mühendisliğinin “stok ve kaynak yönetimi” ilkesinin tarlaya uygulanmış halidir.

3.2.Sağlık Sistemlerinde Risk Minimizasyonu

Sağlık verileri üzerinde yapılan makine öğrenmesi uygulamalarında (örneğin diyabet veya kalp hastalığı tahmini), algoritmaların yüksek doğruluk oranlarına ulaştığı saptanmıştır. Benzer biyo-mühendislik çalışmalarında görüldüğü gibi, üretim stratejileri ve biyoaktivite değerlendirmeleri, potansiyel terapötik özelliklerin belirlenmesinde kritik öneme sahiptir [6]. Burada en önemli bulgu, endüstri mühendislerinin hastane süreçlerini iyileştirirken artık sadece “kuyruk teorisi” değil, “veri madenciliği” tekniklerini de kullanarak hasta akışını ve teşhis süreçlerini optimize edebildiğidir.

3.3.Karar Destek Sistemlerinde Hibrid Yaklaşımlar

Hizmet ve bilişim sektöründe, özellikle bulut sağlayıcı seçimi gibi karmaşık problemlerde, tek başına yapay zekanın değil, YZ ile entegre edilmiş Çok Kriterli Karar Verme (ÇKKV) yöntemlerinin (AHP, Bulanık Mantık) öne çıktığı görülmüştür. Literatürde de belirtildiği üzere, çok kriterli karar verme yöntemlerinin analizi, sistemik düşünce yapısıyla projelerin başarısını doğrudan etkilemektedir [7]. Ayrıca bulut bilişimin dijital işletmeler üzerindeki etkisi, seçim kriterlerinin önemini artırmaktadır [8]. Bulgular, “Bulanık Mantık” kullanımının, karar vericilerin sözel ve belirsiz ifadelerini matematiksel verilere dönüştürmede kritik bir rol oynadığını ortaya koymaktadır.

3.4.E-Ticaret ve Müşteri İlişkilerinde Otomasyon

E-ticaret öneri sistemleri üzerine yapılan incelemelerde, Python tabanlı öneri sistemleri ve sohbet robotu entegrasyonunun müşteri memnuniyetini artırdığı belirlenmiştir [9]. Derin öğrenme tabanlı öneri algoritmaları, müşterinin sadece geçmişini değil, o anki duygu durumunu ve niyetini de analiz ederek “kişiselleştirilmiş” bir deneyim sunmaktadır.

4.TARTIŞMA VE SONUÇ

Bu çalışmada, endüstri mühendisliğinin klasik sınırlarının ötesine geçerek, yapay zekâ teknolojileriyle nasıl birleştiği geniş bir perspektifte ele alınmıştır. Hizmet sektöründe ve turizm gibi alanlarda yapay zeka tabanlı nedensellik sorgulamalarının (counterfactual reasoning) artması, bu dönüşümün kanıtıdır [10]. Elde edilen bulgular ışığında şu temel sonuçlara ulaşılmıştır:

Birincisi, Yapay Zekâ bir “Araç”tan öte bir “Stratejik Ortak”tır. İncelenen tüm vakalarda (tarımdan sağlığa), YZ’nin sadece işi hızlandırmadığı, aynı zamanda insan gözünden kaçan desenleri (pattern) yakalayıp karar kalitesini artırdığı görülmüştür.

İkincisi, Veri Kalitesi Algoritmadan Daha Önemlidir. Bulgular kısmında değinilen yüksek doğruluk oranlarına ulaşılmasının temel şartı, temiz ve düzenli veridir. Bu da endüstri mühendislerinin yeni dönemdeki en önemli yetkinliğinin “Veri Mühendisliği” ve “Veri Ön İşleme” olması gerektiğini göstermektedir.

Üçüncüsü, İnsan-Makine İş Birliği (Endüstri 5.0). Çalışmalar göstermektedir ki, tam otomasyondan ziyade, insanın karar verici olduğu ancak makine tarafından desteklendiği

sistemler en yüksek verimi sağlamaktadır. Özellikle sağlık ve risk yönetimi gibi hatanın tolere edilemediği alanlarda, YZ bir “asistan” görevi görmektedir.

Sonuç olarak, endüstri mühendisliği eğitimi ve pratiği, Python, SQL, makine öğrenmesi ve veri analitiği gibi yetkinliklerle yeniden şekillenmektedir. Geleceğin endüstri mühendisleri, sadece süreçleri tasarlayan değil, bu süreçleri öğrenen algoritmalarla yöneten profesyoneller olacaktır.

KAYNAKÇA

- [1] Warfield, J. N. (1974). Developing interconnected matrices in structural modeling. IEEE Transactions on Systems, Man, and Cybernetics, 4(1), 51-81.
<https://doi.org/10.1109/TSMC.1974.4308320>
- [2] Wuest, T., Weimer, D., Irgens, C., & Thoben, K.-D. (2016). Machine learning in manufacturing: advantages, challenges, and applications. Production & Manufacturing Research, 4(1), 23–45. <https://doi.org/10.1080/21693277.2016.1192517>
- [3] Murphy, K. P. (2022). Probabilistic machine learning: an introduction. MIT Press.
- [4] Salazar, A., Gosalbez, J., Bosch, I., Miralles, R., & Vergara, L. (2004). A case study of knowledge discovery on academic achievement, student desertion and student retention. In: ITRE 2004. 2nd International Conference on Information Technology: Research and Education. IEEE, p. 150–4.
- [5] Abdollahzadeh, G., & Shabani, S. M. (2018). Experimental and numerical analysis of beam to column joints in steel structures. Front. Struct. Civ. Eng., 12, 642–661.
<https://doi.org/10.1007/s11709-017-0457-z>
- [6] D’ambrosio, S., Dabous, A., Sadiq, S., Casillo, A., Schiraldi, C., Cassese, E., Bedini, E., Corsaro, M. M., & Cimini, D. (2024). Bifidobacterium animalis subsp. Lactis HN019 Live probiotics and postbiotics: Production strategies and bioactivity evaluation for Potential therapeutic properties. Frontiers in Bioengineering and Biotechnology, 12, Article 1379574.
<https://doi.org/10.3389/fbioe.2024.1379574>
- [7] Hester, P. T., Velasquez, M., & Hester, P. T. (2013). An analysis of multi-criteria Decision making methods. International Journal of Operations Research, 10(2), 56-66.
- [8] Vural, S., Naghizade, K., Erkollar, A. (2017). Bulut Bilişimin Dijital İşletme Üzerindeki Etkisi. EUREFE, 17, 1-9.
- [9] Sharma, A. “Recommender Systems in Python,” DataCamp.
<https://www.datacamp.com/tutorial/recommender-systems-python>, Accessed: May 2020.
- [10] Xia, H., Muskat, B., Li, G., & Prayag, G. (2023). Ai-based Counterfactual reasoning for tourism research. Annals of Tourism Research, 101, 103617. Doi: <https://doi.org/10.1016/j.annals.2023.103617>

**POLİFENOLLERİN ve/veya BOR İLE ZENGİNLEŞTİRİLMİŞ TÜREVLERİNİN
SOĞUK STRESİ ALTINDA MISIR BİTKİSİNİN GELİŞİMİ ÜZERİNE ETKİLERİ**

EFFECTS of POLYPHENOLS and/or BORON ENRICHED DERIVATIVES on GROWTH
of CORN PLANTS UNDER COLD STRESS

Prof. Dr. Serdar BİLEN

Atatürk Üniversitesi, Ziraat Fakültesi, Toprak Bilimi ve Bitki Besleme Bölümü

Dr. Öğr. Üyesi, Elif YAĞANOĞLU

Atatürk Üniversitesi, Ziraat Fakültesi, Toprak Bilimi ve Bitki Besleme Bölümü

Dr. Öğr. Üyesi, Adil ADIN

Atatürk Üniversitesi, Ziraat Fakültesi, Toprak Bilimi ve Bitki Besleme Bölümü

Prof. Dr. Taşkın ÖZTAŞ

Atatürk Üniversitesi, Ziraat Fakültesi, Toprak Bilimi ve Bitki Besleme Bölümü

Pro. Dr. Zekai Halıcı

Atatürk Üniversitesi, Tıp Fakültesi, Dahili Tıp Bilimleri, Tıbbi Farmakoloji Anabilim Dalı

Prof. Dr. Durun Ali KÖSE

Hitit Üniversitesi, Fen-Edebiyat Fakültesi, Kimya Bölümü, Anorganik Kimya Anabilim Dalı

Doç. Dr. Melda BOLAT

Hitit Üniversitesi, Teknik Bilimler MYO, Mülkiyet Koruma ve Güvenlik Bölümü, İş Sağ. ve
Güv. Prog.

ÖZET

Polifenol zeytinyağı, kırmızı şarap, yeşil çay ve çikolatada bulunan ve antioksidan etkiye sahip fenolik bileşenlerin genel adıdır. Bitkilerin soğuk stresi koşullarında suda çözünebilen fenolik maddelerin miktarlarının arttığı ve flavonoid metabolizmasının uyarıldığı çeşitli araştırmalarla belirlenmiştir. Bitkilerin soğuk stresi üzerine Bor elementinin de olumlu etkilerinin olduğu çalışmalar mevcuttur.

Bu çalışmanın amacı; çay bitkisinde bulunan polifenollerin (PF) ve bor ile zenginleştirilmiş türevlerinin (PF-B) farklı konsantrasyonlarının soğuk stresi koşullarında mısır bitkilerinin gelişimi üzerine etkilerini ortaya koymaktır. Projenin hedefi ise; bitkileri soğuk stresine karşı koruyan etkili yeni PF-B bileşiği sentezleyerek bitkilerin düşük sıcaklık koşullarına dayanıklılığını artırmak ve iklim değişikliğinin tarımsal üretim üzerindeki olumsuz etkilerini azaltmaktır.

Çalışma için PF bileşiği satın alınarak tedarik edilmiştir. Bor elementi ile zenginleştirilmiş PF, polifenol-borik asit arasındaki Lewis asit-baz etkileşimine göre sentezle elde edilmiştir. Elde edilen yeni PF-B bileşiği % 84.1 PF, % 2.04 B, % 7.24 K içermektedir. Mısır denemesi için PF e PF-B bileşiklerinin % 0.0 (0 ppm), 0.001 (10 ppm EG), 0.002 (20 ppm EG), 0.004 (40 ppm EG), 0.008 (80 ppm EG) ve 0.01 (100 pm EG)'lik sulandırılmış konsantrasyonları hazırlanmıştır.

Viyollerde 15-20 cm yüksekliğine kadar gelişim gösteren sağlıklı mısır fideleri 2 kg toprak içeren saksılara şaşırtılmıştır. Her bir saksı toprağına bir kez PF ve PF-B bileşiğinin 6 farklı konsantrasyonlarını ihtiva eden çözeltiler tarla kapasitesi (TK) nem durumuna eşdeğer sulama suyu miktarında uygulanmıştır. Deneme süresince sakı topraklarının nem düzeyleri TK nem düzeyinde sabit tutulmuştur. Sakılar büyütme kabinlerinde 4, 6, 8, 10 ve 12 °C sıcaklıklarda gelişmeye tabi tutulmuşlar ve deneme sürecinde saksı topraklarına eksilen su miktarı saf su ile sulandırma yapılarak tamamlanmıştır. Yaklaşık 2 ay süre ile püskül oluşum aşamasına kadar mısır bitkilerinin düşük sıcaklıklarda gelişimi takip edilmiş ve bitkilerin boy ölçümü ve gelişme bozuklukları belirlenmiştir.

Sonuçlara göre; Mısır bitkilerinin boyları 80 ppm'e kadar artan PF konsantrasyonu ile artmış, bu artışlar istatistiksel olarak önemli ($p<0.05$) bulunmuştur. Ancak; 80 ve 100 ppm PF konsantrasyonlarının mısır bitkilerinin boyları üzerine etkileri önemli bulunmamıştır. Ortalama olarak en düşük mısır bitkisi boyu 0 pm PF uygulamasında, en yüksek mısır bitkisi boyu 100 ppm PF uygulamasında belirlenmiştir. Farklı soğuk stresi koşullarında da sıcaklık artışına bağlı olarak mısır bitkilerinin boyları artış göstermiş, bu artışlar istatistiksel olarak önemli ($p<0.05$) farklar göstermiştir. Ortalama en düşük mısır bitkisi boyu 4 °C'de, en yüksek mısır bitkisi boyu 12 °C'de gözlenmiştir (Tablo1, Şekil 1).

Mısır bitkilerinin boyları PF-B konsantrasyonlarının artışına bağlı olarak 40 ppm'e kadar artmış, bu artışlar istatistiksel olarak önemli ($p<0.05$) bulunmuştur. Ancak; 40 ppm PF-B konsantrasyonlarının mısır bitkilerinin boyları üzerine etkileri önemli bulunmamıştır. Farklı soğuk stresi koşullarında da sıcaklık artışına bağlı olarak mısır bitkilerinin boyları artış göstermiş, bu artışlar istatistiksel olarak önemli ($p<0.05$) farklar göstermiştir. Ortalama en düşük mısır bitkisi boyu 4 °C'de, en yüksek mısır bitkisi boyu 12 °C'de gözlenmiştir.

Sonuç olarak; 80 ppm'lik PF çözeltisinin ve 40 ppm'lik PF-B çözeltilerinin soğuk stresi koşullarında mısır bitkisi gelişiminde kullanılabileceği ve PF-B bileşiğinin PF bileşiğine göre soğuk stresi koşullarında daha etkili yeni bir ürün olduğu sonucuna varılmıştır.

Anahtar Kelimeler: Polifenol, Soğuk Stresi, Mısır Bitkisi Gelişimi, Bor bağlanmış Polifenol

ABSTRACT

Polyphenols are the general name for phenolic compounds found in olive oil, red wine, green tea, and chocolate, which have antioxidant effects. Various studies have shown that the amount of water-soluble phenolic compounds increases and flavonoid metabolism is stimulated in plants under cold stress conditions. There are also studies showing that the element boron has positive effects on cold stress in plants.

The aim of this study is to determine the effects of different concentrations of polyphenols (PF) and their boron-enriched derivatives (PF-B) found in tea plants on the development of maize plants under cold stress conditions. The goal of the project is to synthesize an effective new PF-B compound that protects plants against cold stress, thereby increasing the resistance of plants to low-temperature conditions and reducing the negative effects of climate change on agricultural production.

For the study, PF compound was purchased and supplied. Boron-enriched PF was obtained by synthesis according to the Lewis acid-base interaction between polyphenol and boric acid. The resulting new PF-B compound contains 84.1% PF, 2.04% B, and 7.24% K. For the maize experiment, diluted concentrations of PF and PF-B compounds were prepared at 0.0% (0 ppm), 0.001% (10 ppm), 0.002% (20 ppm), 0.004% (40 ppm), 0.008% (80 ppm), and 0.01% (100 ppm). Healthy maize seedlings that had grown to a height of 15-20 cm in trays were transplanted into pots containing 2 kg of soil. Solutions containing 6 different concentrations of PF and PF-B compounds were applied once to the soil in each pot, using irrigation water equivalent to field capacity (FC) moisture content. Throughout the experiment, the moisture levels of the pot soils were kept constant at FC moisture level. The pots were grown in growth chambers at temperatures of 4, 6, 8, 10, and 12 °C, and the amount of water lost from the pot soil during the experiment was replenished by dilution with pure water. For approximately 2 months, the development of maize plants was monitored at low temperatures until the tassel formation stage, and the height of the plants and developmental abnormalities were determined.

According to the results; the height of maize plants increased with increasing PF concentration up to 80 ppm, and these increases were statistically significant ($p<0.05$). However, the effects of 80 and 100 ppm PF concentrations on the height of maize plants were not found to be significant. On average, the shortest maize plant height was determined in the

0 ppm PF application, and the longest maize plant height was determined in the 100 ppm PF application. In different cold stress conditions, the height of maize plants also increased with increasing temperature, and these increases showed statistically significant differences ($p<0.05$). The shortest average maize plant height was observed at 4 °C, and the longest maize plant height was observed at 12 °C (Table 1, Figure 1).

The height of maize plants increased with increasing PF-B concentrations up to 40 ppm, and these increases were statistically significant ($p<0.05$). However, the effects of 40 ppm PF-B concentrations on maize plant height were not found to be significant. Under different cold stress conditions, maize plant heights also increased with increasing temperature, and these increases showed statistically significant differences ($p<0.05$). The lowest average maize plant height was observed at 4 °C, and the highest maize plant height was observed at 12 °C.

In conclusion, it was determined that 80 ppm PF solution and 40 ppm PF-B solution can be used in maize plant development under cold stress conditions, and that the PF-B compound is a more effective new product compared to the PF compound under cold stress conditions.

Keywords: Polyphenol, Cold Stress, Germination of Corn Seeds, Boron-Enriched Polyphenol

GİRİŞ

FAO verilerine göre ülkemiz topraklarının büyük bir bölümü düşük sıcaklık stresi riski altındadır. Ülkemizde birçok tarımsal ürün soğuk stresi tehlikesiyle karşı karşıya kalmakta ve bu durum tarımsal üretimi ve verimliliği olumsuz etkilemektedir. Kuraklık, tuzluluk ve düşük sıcaklık (LT) veya Soğuk stresi (SS); bitki büyümesi ve gelişimi üzerinde güçlü etkileri olan, ani başlayan ve büyük ekonomik kayıplara neden abiyotik stres faktörleridir [1]. LT stresi, çevre sıcaklığına göre soğuk stresi (<20 °C) ve donma stresi (<0 °C) olarak ikiye ayrılır. Bitkinin büyümesini ve gelişimini etkilemesinin yanı sıra, LT stresi bitkilerin coğrafi dağılımını da önemli ölçüde kısıtlamaktadır [2-5].

Tropikal ve subtropikal iklim bitkileri soğuk stresine karşı hassastır ve soğuk iklime uyum sağlama kapasitesinden yoksundur. Bununla birlikte, ılıman iklim bitkileri donmayan sıcaklıklara maruz kalma süresinin ardından donma sıcaklıklarına dayanma yeteneğine sahiptirler ve bu duruma soğuk iklime uyum sağlama denir [6]. Ilıman bitkiler mevsimsel sıcaklık değişikliklerine dayanıklıdır ve ilkbahar ve kış başlarında soğuk stresine dayanabilirler. Pirinç, mısır, soya fasulyesi, patates, pamuk ve domates gibi birçok önemli ürün soğuğa duyarlıdır ve soğuğa uyum sağlayamaz. Buna karşılık, yulaf gibi bazı ürünler soğuğa dayanıklıdır ancak dona karşı hassastır. Diğer yandan arpa, buğday ve çavdar donma sıcaklıklarına iyi adapte olmuş bitkilerdir [7]. Kışlık buğday (*Triticum aestivum* L.) ve arpa (*Hordeum vulgare* L.) soğuk iklime uyum sağlayan ancak donmayan sıcaklıklara dayanama gücü zayıf olan bitkilerdir[8].

Polifenol zeytinyağı, kırmızı şarap, yeşil çay ve çikolatada bulunan ve antioksidan etkiye sahip fenolik bileşenlerin genel adıdır. Flavan-3-oller ve prosiyanidinler özellikle çay bitkisinde yaygın olarak bulunurlar [9]. Flavan-3-ol'lerin tam fermente olmuş çaydaki miktarının yeşil çaya göre oldukça düşük olduğu bilinmektedir. Bazı polifenollerin fermente çayda bulunan miktarları yeşil çaydakilere göre % 10.5-19.3'u kadar olduğu tespit edilmiştir [10]. Farklı çay türlerindeki polifenoller fermentasyon sürecine bağlı olarak değişiklik gösterirler, fermentasyon olmadan üretilen yeşil çay en yüksek miktarda polifenol içermektedir. Çayda fermentasyon süreci arttıkça bazı polifenoller de azalmaktadır [11].

Polifenoller üzerine yapılan çalışmalar bitkilerin soğuk stresi karşısında flavanoid metabolizmasını uyardığını, suda çözünebilen fenol miktarlarını arttırdığını ve bu metabolizma ile bitkilerin soğuğa karşı direnç geliştirdikleri göstermiştir [12,13]. Özellikle bitkilerin fenilpropanoid metabolizmasının soğuk stresi altında arttığı, çeşitli bitki dokularında fenilpropanoid metabolizmasının yanı sıra flavonoid metabolizmasını da uyarıldığı tespit

edilmiştir (enginar, havuç, kornişon, mısır, zeytin, bezelye, armut, patates, domates ve karpuz dahil) [14-22].

Bitkilerin soğuk stresi üzerine B elementinin de etkileri mevcuttur. Borun bitkideki işlevleri üzerinde pek çok araştırma yapılmış olmasına rağmen bitki bünyesindeki fonksiyonları bazı aşamalarda tam olarak anlaşılmış değildir. Bor bitkilerde; a) şekerlerin taşınmasında b) hücre duvarı sentezinde, c) lignifikasyon olgusunda, d) hücre duvarı strüktürünün oluşumunda, e) karbonhidrat metabolizmasında, f) RNA metabolizmasında, g) solunumda, h) Indol asetik asit (IAA) metabolizmasında, ı) fenol metabolizmasında, i) biyolojik membranların yapısal ve fonksiyonelleri üzerinde önemli işlevlere sahiptir [23]. Bor elementinin eksikliği durumunda bitkilerin zayıf direnme gücü, güçsüz ve yetersiz kök gelişimi görülmüştür. Bu da bitkinin kuraklık, soğuk ve yabancı otlara karşı direncinin azalmasına sebep olduğu belirlenmiştir [24]. Yapılan çalışmalarda polifenollere bor elementi bağlanarak elde edilen yeni bir ürün mevcut değildir. Polifenolün kendisi ve bor içeren türevinin soğuk stresi koşullarında mısır bitkisinin gelişimi üzerine olumlu etkilerinin olabileceği düşüncesi çalışmanın yenilikçi yönünü oluşturmaktadır.

Bu çalışmanın amacı; çay bitkisinde yaygın olarak bulunan polifenollerin ve bundan elde edilen polifenol-bor türevlerinin bitkilerin soğuk stresi koşullarındaki etkilerini belirlemek, soğuk stresine karşı kullanım imkanlarını araştırmak, iklim değişikliğinin tarımsal üretim üzerindeki olumsuz etkilerini azaltmak ve ülkemiz tarım endüstrisine ve ekonomisine yeni bir ürün kazandırmaktır.

MATERYAL ve YÖNTEM

Tohum; Denemede ekmeklik ve erkenci çeşit olan Sympaticon çeşidi mısır tohumları kullanılmıştır.

Polifenol Bileşiği (PF); Çay bitkisinde elde edilmesi planlanan polifenol, sentez ve saflaştırma aşamalarındaki yüksek maliyet sebebi ile satın alınma yoluna gidilmiştir. Ürün Çin'den satın alınarak denemede kullanılmıştır. Satın alınan polifenol % 99.5 saflıktadır.

Polifenol – Bor bileşiği (PF-B); Satın alınan polifenol bileşiğine bor elementini bağlamak için sentez yöntemi kullanılmıştır. Polifenol ile borik asit arasındaki reaksiyon, basitçe Lewis asit-baz etkileşimine dayanmaktadır [25]. Bu metot ile polifenol bileşiğine 2 mol Bor elementi zayıf bağla bağlanabilmiştir. Sentezleme sonrası elde edilen PF-B bileşiği %84,1 Polifenol, %2,04 B, %7,24 K içerdiği belirlenmiştir.

Polifenol Çözeltileri

PF bileşiğinden elde edilen PF-B bileşiği içerisinde % 2.04 oranında Bor tespit edilmiştir. Bu değer bitkiler için uygun toksik düzeyin altındadır. Mısır bitkisinin 4 ppm B düzeyine kadar dayanıklı olduğu belirlenmiştir. Mısır denemesi için PF bileşiklerinin % 0.0 (0 ppm), 0.001 (10 ppm EG), 0.002 (20 ppm EG), 0.004 (40 ppm EG), 0.008 (80 ppm EG) ve 0.01 (100 pm EG)'lik sulandırılmış konsantrasyonları hazırlanmıştır. Aynı şekilde PF-B bileşiklerinin % 0.0 (0 ppm), 0.001 (8.41 ppm PF, 0.204 ppm B), 0.002 (16.82 ppm EG, 0.408 ppm B), 0.004 (33.64 ppm EG, 0.82 ppm B), 0.008 (67.28 ppm EG, 1.63 ppm B) ve 0.01 (84.10 pm EG, 2.04 ppm B)'lik sulandırılmış konsantrasyonları hazırlanmıştır.

Denemenin Kurulması ve Yürütülmesi

Mısır bitkilerine topraktan uygulama için PF ve PF-B bileşiğinin % 0, 10, 20, 40, 80 ve 100 ppm'lik sulandırılmış konsantrasyonları hazırlanmıştır. Viyollerde 15-20 cm yüksekliğine kadar gelişim gösteren sağlıklı mısır fideleri 2 kg toprak içeren saksılara şaşırtılmıştır. Her bir saksı toprağına bir kez PF ve PF-B bileşiğinin 6 farklı konsantrasyonlarını ihtiva eden çözeltiler tarla kapasitesi (TK) nem durumuna eşdeğer sulama suyu miktarında uygulanmıştır. Deneme süresince saksı topraklarının nem düzeyleri TK nem düzeyinde sabit tutulmuştur. Saksılar büyütme kabinlerinde 4, 6, 8, 10 ve 12 °C sıcaklıklarda gelişmeye tabi tutulmuşlardır. Denemede 0 (başlangıç), 30 ve 60 gün sonra püskül oluşum aşamasına kadar mısır bitkilerinin

düşük sıcaklıklarda gelişimi takip edilmiş ve bitkilerin boy ölçümü ve gelişme bozuklukları gözlemlenmiştir.

Verilerin Analizi

Farklı konsantrasyonlarda ve farklı sıcaklıklardaki PF ve PF-B çözeltilerinin mısır bitkilerinin ortalama boyları üzerine etkilerini belirlemek için SPSS 20 istatistik programı kullanılmıştır [35].

ARAŞTIRMA ve BULGULAR

Farklı konsantrasyonlarda, farklı soğuk stresi koşullarında PP ve PF-B çözeltilerinin saksılarda yetiştirilen mısır bitkilerinin ortalama boyları üzerine etkileri $p<0.05$ seviyesinde istatistiksel olarak önemli bulunmuştur. PF uygulamalarına ve soğuk stresi koşullarına bağlı olarak mısır bitkilerinin ortalama boyları arasındaki farkları gösteren değerler ve ANOVA varyans analiz sonuçları Tablo 1. ve Tablo 2.'de, farklı konsantrasyonlarda PF uygulamalarının mısır bitkisinin gelişimi ve boyları üzerine etkilerini gösteren grafik Şekil 1'de ve farklı soğuk stresi koşullarında PF uygulamalarının mısır bitkisinin gelişimi ve boyları üzerine etkileri gösteren grafik Şekil 2.'de verilmiştir.


Tablo 1. Farklı PF konsantrasyonlarının farklı soğuk stresi koşullarında mısır bitkisinin boyları üzerine etkileri ve PF bileşiğinin içerikleri.

Uyg	Uyg PF Kons., ppm	Gelişim Süresi, gün	Bitki Boyu, cm						EG Mik ppm	Bor Mik, ppm	K Mik Ppm
			SICAKLIK								
			4 °C	6 °C	8 °C	10 °C	12 °C				
PF	0	0	15.0	16.0	15.0	16.0	15.0	15.4	0	0.0	0.0
		30	23.1	16.0	36.8	49.8	65.5	40.8	0	0.0	0.0
		60	33.9	40.7	50.1	64.4	78.1	53.4	0	0.0	0.0
	Ortalama		28.5	34.7	43.4	57.1	71.8	47.1E			
	10	30	29.2	36.0	46.8	56.1	83.2	50.3	9.95	0.0	0.0
		60	42.7	56.7	65.0	78.4	93.1	67.2	9.96	0.0	0.0
	Ortalama		36.0	46.3	55.9	67.2	88.2	58.7D			
	20	30	40.5	43.6	64.5	69.5	89.4	61.5	19.9	0.0	0.0
		60	58.8	75.1	84.0	103.8	119.8	88.3	19.10	0.0	0.0
	Ortalama		49.7	59.3	74.3	86.7	104.6	74.9C			
	40	30	45.0	55.5	65.4	80.6	104.4	70.2	39.8	0.0	0.0
		60	65.5	70.3	96.8	119.5	126.6	95.7	39.8	0.0	0.0
	Ortalama		55.3	62.9	81.1	100.0	115.5	83.0B			
	80	30	56.9	64.8	66.0	89.3	106.1	76.6	79.6	0.0	0.0
		60	78.1	86.8	101.6	115.5	128.4	102.1	79.6	0.0	0.0
	Ortalama		67.5	75.8	83.8	102.4	117.3	89.4A			
	100	30	54.9	65.0	75.9	102.7	110.0	81.7	99.5	0.0	0.0
		60	76.6	86.5	95.2	105.8	130.3	98.9	99.5	0.0	0.0
	Ortalama		65.7	75.7	85.6	104.3	120.2	90.3A			
	GENEL		50.4E	59.1D	70.7C	86.3B	102.9A	73.9			
EG : Epigallocatechin gallate											

EG : Epigallocatechin gallate

Tablo1'e göre farklı konsantrasyonlarda PF uygulamaları mısır bitkilerin boylarında 30 e 60 günlük gelişme süresi boyunca artış göstermiş, bu artışlar istatistiksel olarak önemli ($p<0.05$) bulunmuştur. PF konsantrasyonlarının artışına bağlı olarak mısır bitkilerinin gelişimi ve boyları artış göstermiştir. Mısır bitkilerinin boyları 80 ppm'e kadar artan PF konsantrasyonu ile artmış, bu artışlar istatistiksel olarak önemli ($p<0.05$) bulunmuştur. Ancak; 80 ve 100 ppm PF konsantrasyonlarının mısır bitkilerinin boyları üzerine etkileri önemli bulunmamıştır (Tablo1, Şekil 1).

Kontrol uygulamasına göre PF uygulamasında en düşük mısır bitkisi boyu 0 ppm konsantrasyonda ve 4 °C’de (28.5 cm), en yüksek ise 100 ppm konsantrasyonda ve 12 °C’de (120.2 cm) belirlenmiştir. Ortalama en düşük mısır bitkisi boyu PF uygulamasının 0 pm konsantrasyonda (47.1 cm), en yüksek boy 100 ppm konsantrasyonda (90.3 cm) belirlenmiştir. Farklı soğuk stresi koşullarında da sıcaklık artışına bağlı olarak mısır bitkilerinin boyları artış göstermiş, bu artışlar istatistiksel olarak önemli ($p<0.05$) farklar göstermiştir. Ortalama en düşük mısır bitkisi boyu PF uygulamasında; 4 °C’de (50.4 cm), en yüksek 12 °C’de (102.9 cm) gözlenmiştir (Tablo1, Şekil 1).



Şekil 1. Farklı konsantrasyonlarda PF uygulamalarının mısır bitkisinin gelişimi ve boyları üzerine etkileri.

Farklı PF konsantrasyonlarının mısır bitkilerinin gelişimini ve boyunu olumlu etkilemiştir. Ortalama mısır bitkilerinin boyları 0, 10, 20, 40, 80 ppm PF konsantrasyonlarının artışında istatistiksel olarak önemli bulunmuştur. Mısır bitkisinin 80 ppm’den sonraki bitki boyu da artış göstermiş, ancak PF ve PF-B uygulamaları arasında istatistiksel olarak önemli fark gözlenmemiştir (Şekil 1).

Ortalama mısır bitkisi boyu 80 ppm PF uygulamasında 89.4 cm ve PF-B uygulamasında 91.8 cm olarak belirlenmiştir. PFF konsantrasyonlarının artışı artışı mısır bitkilerinin gelişimlerinde olumlu katkı yapmasına karşın istatistiksel olarak en etkili P konsantrasyonu 80 ppm’de PF ve 40 ppm’de PF-B uygulamalarına görülmüştür (Şekil 1).


Tablo 2. Farklı PF-B konsantrasyonlarının soğuk stresi koşullarında mısır bitkisinin boyları üzerine etkileri ve PF-B bileşiğinin içerikleri.

Uyg	Uyg PF Kons., ppm	Gelişim Süresi, gün	Bitki Boyu, cm						EG Mik ppm	Bor Mik, ppm	K Mik ppm
			SICAKLIK					ORT			
			4 °C	6 °C	8 °C	10 °C	12 °C				
PF-B	0	0	15.0	17.0	18,0	18.0	15.0	16.0	0	0.0	0.0
		30	27.2	32.3	53,0	51.0	60.1	42.0	0	0.0	0.0
		60	32.9	39.6	66,7	64.7	77.2	53.4	0	0.0	0.0
	Ortalama		30.0	36.0	46.2	59,9	68.6	47.7E			
	10	30	37.6	48.8	67,8	65.8	91.1	58.9	8.41	0.20	0.72
		60	52.5	60.3	94,8	92.8	111.9	78.6	8.41	0.20	0.72
	Ortalama		45.0	54.6	63.3	81,3	101.5	68.7D			
	20	30	49.2	47.1	72,6	70.6	92.7	65.3	16.82	0.41	1.45
		60	59.5	75.7	108,0	106.0	120.7	90.0	16.82	0.41	1.45
	Ortalama		54.3	61.4	77.6	90,3	106.7	77.7C			
	40	30	48.6	59.6	88,5	88.8	103.5	74.0	33.64	0.82	2.90
		60	66.3	75.2	122,2	126.6	131.3	97.8	33.64	0.82	2.90

Ortalama		57.5	67.4	82.5	105,3	117.4	85.9B			
80	30	58.6	66.2	98,1	96.1	108.5	80.0	67.28	1.63	5.79
	60	79.6	90.6	118,8	116.8	123.5	102.8	67.28	1.63	5.79
Ortalama		69.1	78.4	86.9	108.4	116.0	91.4A			
100	30	60.7	68.4	106,7	104.7	111.3	85.9	84.10	2.04	7.24
	60	71.4	89.3	112,7	110.7	115.3	98.0	84.10	2.04	7.24
Ortalama		66.1	78.9	93.8	109,7	113.3	91.9A			
GENEL Ort.		53.7E	62.8D	75.0C	92,5B	103.9A	77.2			

Tablo 2'ye göre farklı konsantrasyonlarda PF-B uygulamaları mısır bitkilerin boylarında 30 e 60 günlük gelişme süresi boyunca artış göstermiş, bu artışlar istatistiksel olarak önemli ($p<0,05$) bulunmuştur. PF-B konsantrasyonlarının artışına bağlı olarak mısır bitkilerinin boyları 40 ppm'e kadar artmış, bu artışlar istatistiksel olarak önemli ($p<0,05$) bulunmuştur. Ancak; 40 ppm PF-B konsantrasyonlarının mısır bitkilerinin boyları üzerine etkileri önemli bulunmamıştır (Tablo2, Şekil 2).

Farklı soğuk stresi koşullarında da sıcaklık artışına bağlı olarak mısır bitkilerinin boyları artış göstermiş, bu artışlar istatistiksel olarak önemli ($p<0,05$) bulunmuştur. Kontrol uygulamasına göre en düşük mısır bitkisi boyu 0 ppm PF-B konsantrasyonda ve 4 °C'de 30.0 cm olarak belirlenmiş, en yüksek ise 40 ppm PF-B konsantrasyonda ve 12 °C'de 117.4 cm olarak belirlenmiştir. PF-B uygulamalarında ortalama en düşük mısır bitkisi boyu 0 ppm konsantrasyonda ve 4 °C'de (53.7 cm), en yüksek mısır bitkisi boyu 100 ppm konsantrasyonda ve 12 °C'de (103.9 cm) belirlenmiştir (Tablo2, Şekil 2).



Şekil 2. Farklı soğuk stresi koşullarında PF uygulamalarının mısır bitkisinin boyları üzerine etkileri.

Soğuk stresi koşullarında artan sıcaklık mısır bitkilerinin gelişimini ve boyunu olumlu etkilemiştir. Ortalama mısır bitkilerinin boyları 4, 6, 8 ve 10 °C sıcaklık artışında istatistiksel olarak önemli bulunmuştur. Mısır bitkisinin 12 °C'de bitki boyu da artış göstermiş, ancak PF ve PF-B uygulamaları arasında istatistiksel olarak önemli fark gözlenmemiştir (Şekil 2). Ortalama mısır bitkisi boyu 10 °C'de PF uygulamasında 86.3 cm ve PF-B uygulamasında 92.5 cm olarak belirlenmiştir. Sıcaklık değerlerinin artışı mısır bitkilerinin gelişimlerinde olumlu katkı yapmasına karşın istatistiksel olarak en etkili sıcaklık değeri 10 °C'de PF ve PF-B uygulamalarına görülmüştür (Şekil 2).

Mısır bitkilerinin boyları 40 ppm PF-B konsantrasyon değerine kadar artış göstermiş, bu artış istatistiksel olarak önemli ($p<0,05$) bulunmuştur. 40 ppm değerinden yüksek PF-B konsantrasyonları mısır bitkilerinin gelişimi ve boyları üzerine kısmen artış gösterse de bu artış istatistiksel olarak önemli bulunmamıştır. Bu çalışma PF-B bileşiğinin 40 ppm

konsantrasyonunun mısır bitkisi için istatistiksel olarak optimum doz olabileceğini göstermiştir. PF uygulamasının 40 ppm dozunda ortalama mısır bitkisi boyu 83.1 cm ve PF-B uygulamasında 86.0 cm olarak belirlenmiştir. PF-B bileşiğinin 80 ve 100 ppm dozlarının uygulanması durumunda mısır bitkilerinin gelişimlerinde yavaşlama gözlemlenmiş, uç ve kenar kısımlarında yanmalar olduğu gözlemlenmiş, bu olumsuz durumun PF-B bileşiğinin içerdiği bor ile bağlantılı düşünülmektedir. Zira mısır bitkilerine 80 ppm PF-B uygulamasında % 0.008 oranında (1.63 ppm) B bitkilere verildiği, 100 ppm PF-B uygulamasında ise % 0.01 oranında (2.04 ppm) B bitkilere verildiği anlamına gelmektedir. Bu miktarda borun mısır bitkilerinin gelişimini olumsuz etkilemesine sebep olacağı düşünülmektedir (Tabo 2; Şekil 2).

Daha önceden yapılmış çalışmalarda şalgam ve mısır bitkilerine bor verildikten sonra ürünlerde artış olduğunu gözlemlemiştir [36]. Bizim çalışmamızda da PF-B uygulamasının mısır bitkilerinde PF uygulamasına göre daha fazla bitki gelişimi ve boy artışına sebep olduğu gözlenmiştir.

Bazı bitkilerde bor alım kapasitesinin salatalık 30 ppm, ayçiçeği 28 ppm, turp 19 ppm, domates 15 ppm, taze fasulye 11 ppm, kaba yonca 10 ppm, buğday 5 ppm, çavdar 4 ppm, yulaf 4 ppm, mısır 4 ppm, Arpa 3 ppm civarında olduğu ifade edilmektedir [37]. Literatüre göre bünyelerinde fazla bor bulunan bitkiler bora daha toleranslı kabul edilir. Bitki bünyesinde bulunan bor arpada 2.3 ppm, mısırdaki 5 ppm, tütünde 25 ppm, şalgamda 49 ppm, pancarda 75 ppm, haşhaşa 94.7 ppm'dir. Az bor isteyen bitkiler içerisinde buğday, arpa, çavdar, yulaf, mısır, fasulye, bezelye gibi bitkiler mevcuttur. Yapılan çalışmalar mısır bitkisinin bor elementine dayanıklılığının hassas sınıfında olduğu ve 2 ppm den daha fazla borun bitkide olumsuz etkiler ortaya koyacağı ifade edilmektedir [38].

Özellikle sulama sularının bor kapsamına göre yapılan sınıflamada bora toleranslı [39] bitkiler grubunda mısır bitkisi orta toleranslı bir bitki olup, 2-2.5 ppm e kadar dayanıklı olabileceği ifade edilmektedir. Ayrıca bor fazlalığı durumunda yaprakların uç ve kenar kısımlarında kırma ve yanmalar olabileceği, yaprak uç kısımlarının yanarak sarardığı, bu durumun özellikle buğday, mısır, çavdar ve arpa bitkilerinde görüldüğü ifade edilmektedir [40].

Yapılan çalışmalarda mısır bitkisinin sıcaklık artışına bağlı olarak bitki gelişiminin arttığı, boylarının daha fazla uzadığı ve koçan oluşumunun arttığı, bu durumun verime olumlu yansıdığı ifade edilmektedir. Ancak soğuk stresi koşullarında mısır bitkisinde düşük sıcaklık klorozu meydana geldiği, tohumlar ve fidelerin çeşitli hasar gördükleri, çimlenmeyi, filizlenmeyi ve vejetatif büyümeyi geciktirdiği, yaprak ve kök uzamasının sınırlı olduğu ifade edilmektedir [41, 42, 43].

Sonuçlar göstermiştir ki, düşük sıcaklık değerlerinde PF-B bileşiği 10 °C de bitki boyunda PF bileşiğine göre daha etkili olmuştur. Bu sebeple PF-B bileşiğinin soğuk stresi koşullarında mısır bitkisinde kullanılabilecek bir ürün olabileceği ve bu bileşiğin soğuk stresine karşı bitkileri korumada etkili olabileceği sonucunu vermiştir.

SONUÇ

Çalışmadan elde edilen nihai sonuçlara göre;

- PF ve PF-B bileşiklerinin bitkilerin gelişimi ve boyu üzerine düşük sıcaklıklarda soğuk stresine karşı dayanıklılığı artırdığı ve soğuk stresine karşı her iki bileşiğin de kullanılabileceği, PF-B bileşiğinin PF bileşiğine göre mısır bitkilerin gelişimi ve boyu üzerine soğuk stresi koşullarında daha etkili olduğu,
- PF bileşiğinin 80 ppm'e kadar mısır bitkilerinin gelişimi ve boyu üzerine etkili olduğu, PF-B bileşiğinin ise 40 ppm'e kadar mısır bitkilerinin gelişimi ve boyu üzerine etkili olduğu,
- Elde edilen PF-B bileşiğinin soğuk stresi koşullarında mısır bitkisinde kullanılabilecek yeni bir ürün olabileceği ve bu bileşiğin soğuk stresine karşı bitkileri korumada etkili olabileceği

- Özellikle PF bileşiminin 80 ppm'e kadar, PF-B bileşiminin ise 40 ppm'e kadar hazırlanan konsantrasyonlarının mısır bitkisi soğuk stresi koşullarında ayrıntılı olarak ilave çalışmalarla denenmesi gerektiği sonucuna varılmıştır.

KATKILAR

This study was supported by TUBITAK 1505 Scientific Project and Ataturk University under project number: AGY105-01 – No: 5240084.

KAYNAKLAR

- [1] Mboup. M., Fischer. I., Lainer. H., Stephan. W.. Trans-species polymorphism and allele-specific expression in the cbf gene family of wild tomatoes. *Mol. Biol. Evol.* 29. 3641-3652. 2012.
- [2] Mickelbart. M.V., Hasegawa. P.M., Bailey-Serres. J.. Genetic mechanisms of abiotic stress tolerance that translate to crop yield stability. *Nat. Rev. Genet.* 16. 237-251. 2015.
- [3] Guo. X., Zhang. L., Zhu. J., Liu. H., Wang. A.. Cloning and characterization of SiDHN, a novel dehydrin gene from *Saussurea involucrata* Kar. et Kir. that enhances cold and drought tolerance in tobacco. *Plant Sci.* 256. 160-169. 2017.
- [4] Liu. Y., Zhou. J.. MAPping Kinase Regulation of ICE1 in Freezing Tolerance. *Trends Plant Sci.* 23. 91-93. 2018.
- [5] Shi. Y., Ding. Y., Yang. S.. Molecular Regulation of CBF Signaling in Cold Acclimation. *Trends Plant Sci.* 23. 623-637. 2018.
- [6] Chinnusamy. V., Zhu. J., Zhu. J.K.. Cold stress regulation of gene expression in plants. *Trends Plant Sci.* 12. 444-451. 2007.
- [7] Zhang. F., Jiang. Y., Bai. L.P., Zhang. L., Chen. L.J., Li. H.G., Yin. Y., Yan. W.W., Yi. Y., Guo. Z.F.. The ICE-CBF-COR Pathway in Cold Acclimation and AFPs in Plants. *Middle-East J. Sci. Res.* 8. 493-498. 2011.
- [8] Zhao. C., Lang. Z., Zhu. J.K.. Cold responsive gene transcription becomes more complex. *Trends Plant Sci.* 20. 466-468. 2015.
- [9] Chen. Y., Hagerman. A.E.. Characterization of soluble noncovalent complexes between bovine serum albumin and beta-1.2.3.4.6- penta-O-galloyl-D-glucopyranose by MALDI-TOF MS. *J. Agric. Food Chem.* 52. 4008-4011. 2004.
- [10] De Mitri. N., Monti. S., Prampolini. G., Barone. V.. Absorption and emission spectra of a flexible dye in solution: A computational time-dependent approach. *J. Chem. Theory Comput.* 9. 4507-4516. 2013.
- [11] Verloop. A.J., Gruppen. H., Bisschop. R., Vincken. J.P.. Altering the phenolics profile of a green tea leaves extract using exogenous oxidases. *Food chemistry.* 196. 1197-1206. 2016.
- [12] Chalker-Scott. L., Fuchigami. L.H.. The role of phenolic compounds in plants stress responses. In: *Low Temperature Stress Physiology in Crops* (ed. H.L. Paul). pp. 67-79. CRC Press. Boca Raton. Florida. 1989.
- [13] Ippolito. A., Nigro. F., Lima. G., Castellano. M.A., Salerno. M., Venere. D.Di., Linsalata. V., Lattanzio. V.. Mechanism of resistance to *Botrytis cinerea* in wound of cured kiwifruits. *Acta Horticulture.* 444. 719-724. 1997.
- [14] Rhodes. M.J.C., Woollorton. L.S.C., Hill. A.C.. Changes in phenolic metabolism in fruit and vegetable tissues under stress. In: *Recent advances in the biochemistry of fruit and vegetables* (eds. J. Friend & M.J.C. Rhodes). pp. 191-220. Academic Press. London. 1981.
- [15] Blankenship. S.M., Richardson. D.G.. Changes in phenolic acids and internal ethylene during long-term cold storage of pear. *Journal of American Society for Horticultural Science.* 110. 336-339. 1985.

- [16] Lattanzio. V.. Linsalata. V.. Palmieri. S.. Van Sumere. C.F.. The beneficial effect of citric and ascorbic acid on the phenolic browning reaction in stored artichoke (*Cynara scolymus* L.) heads. Food Chemistry. 33. 93-106. 1989.
- [17] Christie. R.J.. Alfenito. M.R.. Walbot. V.. Impact of low temperature stress on general phenylpropanoid and anthocyanin pathways: enhancement of transcript abundance and anthocyanin pigmentation in maize seedlings. Planta. 194. 541-549. 1994.
- [18] Leyva. A.. Jarillo. J.A.. Salinas. J.. Martinez-Zapater. J.M.. Low temperature induces the accumulation of phenylalanine ammonia-lyase and chalcone synthase mRNAs of *Arabidopsis thaliana* in a light-dependent manner. Plant Physiology. 108. 39-46. 1995.
- [19] Chalker-Scott. L.. Fuchigami. L.H.. The role of phenolic compounds in plants stress responses. In: Low Temperature Stress Physiology in Crops (ed. H.L. Paul). CRC Press. Boca Raton. Florida. pp. 67-79. 1989.
- [20] Solecka. D.. Boudet. A.M.. Kacperska. A.. Phenylpropanoid and anthocyanin changes in low-temperature treated winter oilseed rape leaves. Plant Physiology and Biochemistry. 37. 491-496. 1999.
- [21] Gil-Izquierdo. A.. Gil. M.I.. Conesa. M.A.. Ferreres. F.. The effect of storage temperature on vitamin C and phenolics content of artichoke (*Cynara scolymus* L.) heads. Innovative Food Science & Emerging Technologies. 2. 199-02. 2001.
- [22] Golding. J.B.. McGlasson. W.B.. Wyllie. W.B.. Leach. D.M.. Fate of apple peel phenolics during cool storage. Journal of Agricultural and Food Chemistry. 49. 2283-2289. 2001.
- [23] Lukaszewski K.M.. Blevins. D.G.. Root growth inhibition in boron-deficient or aluminium-stressed squash may be a result of impaired ascorbate metabolism. Plant Physiology. 112(3):1135-40.1996.
- [24] Demirtaş. A.. Bor Bileşikleri ve Tarımda Kullanımı. Atatürk Üniversitesi. Ziraat Fakültesi Dergisi. 37(1). 111-115. 2006.
- [25] Özgür. D.. Özkan. G.. Lewis asit baz yer değiştirme reaksiyonu ve amonyak boran üretimi. 11. Ulusal Kimya Mühendisliği Kongresi. Turkey. 2014.
- [26] Rihan. H.Z.. Al-Issawi. M.. Fuller. M.P.. Upregulation of CBF/DREB1 and cold tolerance in artificial seeds of cauliflower (*Brassica oleracea* var. *botrytis*). Sci. Hortic.. 225. 299-309. 2017.
- [27] Lata. C.; Prasad. M. Role of DREBs in regulation of abiotic stress responses in plants. J. Exp. Bot.. 62. 4731-4748. 2011.
- [28] Yadav. S.K.. Cold stress tolerance mechanisms in plants. Sustain. Agric.. 2. 605-620. 2009.
- [29] Azzeme. A.M.. Abdullah. S.N.A.. Aziz. M.A.. Wahab. P.E.M.. Oil palm drought inducible DREB1 induced expression of DRE/CRT- and non-DRE/CRT-containing genes in lowland transgenic tomato under cold and PEG treatments. Plant Physiol. Biochem.. 112. 129-151. 2017.
- [30] Kargiotidou. A.. Deli. D.. Galanopoulou. D.. Tsiftaris. A.. Farmaki. T.. Low temperature and light regulate delta 12 fatty acid desaturases (FAD2) at a transcriptional level in cotton (*Gossypium hirsutum*). J. Exp. Bot.. 59. 2043-2056. 2008.
- [31] Wang. S.. Yang. C.. Zhao. X.. Chen. S.. Qu. G.Z.. Complete chloroplast genome sequence of *Betula platyphylla*: Gene organization, RNA editing, and comparative and phylogenetic analyses. BMC Genomics. 19. 950. 2018.
- [32] Yang. T.; Huang. X.S.. Deep sequencing-based characterization of transcriptome of *Pyrus ussuriensis* in response to cold stress. Gene. 661. 109-118. 2018.
- [33] Barrero-Gil. J.. Salinas. J.. CBFs at the Crossroads of Plant Hormone Signaling in Cold Stress Response. Mol. Plant.. 10. 542-544. 2017.

- [34] Wang. D.Z.. Jin. Y.N.. Ding. X.H.. Wang. W.J.. Zhai. S.S.. Bai. L.P.. Guo. Z.F.. Gene regulation and signal transduction in the ICE–CBF–COR signaling pathway during cold stress in plants. *Biochem. (Mosc.)* 82. 1103-1117. 2017.
- [35] Yurtsever. N.. Deneysel İstatistik metotlar. Köy Hizmetleri Genel Müdürlüğü Toprak ve Gübre Araştırma Enstitüsü Müdürlüğü Yayın No: 121. Teknik Yayın No: 56. Ankara. 1984.
- [36] Horuz, A., & Özcan, C. Effects of boron application to corn plant (*Zea mays* everta) on yield and boron content in the calcerous soil. *Journal of Boron*, 2(1), 37-42, 2017.
- [37] Tas, İ., Ozkay, F., Yeter, T., Görgisen, C., Cosge, B. Effects of High Boron Containing Irrigation Waters on Plant Characteristics of Basil (*Ocimum Basilicum* L.). *Journal of Agricultural Faculty of Gaziosmanpasa University* <http://ziraatdergi.gop.edu.tr/>, ISSN: 1300-2910 E-ISSN: 2147-8848, 33(3), 46-54, doi:10.13002/jafag1121, 2016
- [38] Clark, J. Fertilizer Recommendations Guide Review and Revision: out Data tate University Publihihg. https://www.nrcs.usda.gov/sites/default/files/2023-06/EC750_2023.pdf, 2005.
- [39] Ayers, R. S., & Westcot, D. W. Water Quality for Agriculture - 4. Toxicity Problems. FAO Irrigation and Drainage Paper 29. Food and Agriculture Organization of the United Nations. Retrieved from <https://www.fao.org/4/t0234e/t0234e05.htm>, 1985.
- [40] Demirtaş, A. Bitkide br ve etkileri. Atatürk Üniveritesi, Ziraat Fakültesi Dergisi, 36 (2), 217-225, 2005, ISSN : 1300-9036, 2004.
- [41] Miedema, P. The Effects of Low Temperature on *Zea mays*, Editor(s): N.C. Brady, *Advances in Agronomy*, Academic Press, Volume 35, Pages 93-128, ISSN 0065-2113, ISBN 9780120007356, [https://doi.org/10.1016/S0065-2113\(08\)60322-3](https://doi.org/10.1016/S0065-2113(08)60322-3), 1982.
- [42] Zhou, X., Muhammad, I., Lan, H., Xia, C. Recent Advances in the Analysis of Cold Tolerance in Maize. *Front. Plant Sci.* 13:866034. doi: 10.3389/fpls.2022.866034, 2022.
- [43] Csepregi-Heilmann, E., Áldott-Sipos, Á., Spitkó, T. et al. Cold tolerance of maize inbred lines at the seed germination stage. *Biologia Futura*. <https://doi.org/10.1007/s42977-025-00292-0>, 2025.

**A COMPARATIVE STUDY OF MACHINE LEARNING ALGORITHMS FOR
HEART DISEASE PREDICTION: A DECISION SUPPORT SYSTEM APPROACH**

Shwan SAEED¹, Derya AVCI², Engin AVCI³

^{1,3}Department of Software Engineering, Firat University, Elazig, Turkey

²Technical Sciences, Department of Computer Technologies, Firat University, Elazig, Turkey

Abstract

Background: Cardiovascular diseases have remained the most prominent causes of death across the world, contributing to 17.9 million deaths annually. It is therefore vital to detect such diseases at their early stages to enable appropriate intervention.

Objective: This study presents a comprehensive comparison of the diagnostic performance of the following machine learning algorithms for heart disease: Artificial Neural Network, KNN, Naive Bayesian Classifier, Decision Trees, and Support Vector Machine.

Methods: In this case, the UCI Heart Disease dataset, comprising 1,025 patterns and 14 clinical variables, was used. In each machine learning model, the preprocessing step of data normalization was performed. Accuracy, precision, and F1-score were used to compare the models' performance, and cross-validation was performed using five folds.

Results: The test accuracy of the Decision Tree classifier was found to be highest at 96.43%, along with a ROC-AUC value of 0.9796, followed by SVM at 92.68%, KNN at 86.34%, ANN at 84.39%, and Naïve Bayes at 82.93%, although the cross-validation test accuracy was nearly perfect for ANN and Decision Tree classifiers at 99.61% and 99.41%, respectively.

Conclusion: Decision Trees provide the best possible balance of accuracy and generalization performance for heart disease classification in this dataset. The mode of comparison offered here is beneficial for development applications of a clinical decision-support system.

Keywords: *Heart Disease Prediction; Machine Learning; Decision Support Systems; Decision Trees; Classification Algorithms; Healthcare Analytics*

1. Introduction

Cardiovascular diseases, or CVDs, remain a significant concern for the health of humanity, being responsible for about 32% of deaths worldwide. According to the World Health Organization, about 17.9 million deaths a year can be linked to the prevalence of CVDs, of which coronary heart diseases rank highest [1]. In the United States, deaths due to heart diseases stand at 20% for 2022, and each year, health costs from cardiovascular diseases are above \$252 billion. It is estimated that the world DALYs for CVDs shall rise by 90% from 2025 to 2050; there is a high imperative of early diagnosis and prevention of these diseases [2].

Decision Support Systems that incorporate machine learning algorithms are practical tools for assisting healthcare practitioners in decision-making [3]. These tools help examine complex patterns in healthcare data, identify risk factors, and provide predictive information to support early intervention. The deployment of artificial intelligence can improve diagnostic accuracy, reduce healthcare costs, and improve outcomes through personalized risk assessment [4].

Machine learning algorithms have achieved considerable success in a range of medical applications, including the prediction of heart disease [5, 6]. Conventional techniques are often poor at handling the nonlinear relationships in medical data, whereas machine learning algorithms can learn from existing medical data to make accurate predictions for new instances [7]. Various algorithms, such as Naïve Bayes, Decision Trees, KNN, Support Vector Machines,

and Artificial Neural Networks, among others, have been tested for predicting heart disease, each with its own advantages and disadvantages [8, 9].

Initially, the objective of this proposed model is to conduct an extensive comparative assessment of the aforementioned machine learning algorithms—Artificial Neural Networks (ANN), KNN, Naive Bayes, Decision Trees, and Support Vector Machines (SVM)—in a decision support system for predicting heart disease. By comparing the performance of these algorithms on a given dataset, the authors aim to provide practical guidance for selecting algorithms for a cardiovascular decision support system.

2. Literature Review

2.1 Machine Learning in Healthcare

The adoption of machine learning in healthcare is increasing significantly. This is because, according to a thorough review carried out by Liu et al. [2], machine learning-based models of prediction for cardiovascular diseases, made possible through electronic health records, have produced a significantly high level of accuracy that even exceeds that of QRISK3 or ASCVD risk scores. Additionally, the lack of transparency in complex algorithms is addressed through the adoption of XAI.

Dela Cruz and Camungao [3] introduced a Decision Support System for predicting cardiovascular diseases using the Naïve Bayes method, achieving accuracies of 91% on the Cleveland database and 89% on the Statlog dataset. It demonstrates that incorporating data mining methods can be a successful approach to implementing clinical decision support systems. On similar lines, Pandey et al. [4] showed the importance of attribute selection and the effectiveness of a Reduced Error Pruning method for J48 Decision Trees in predicting heart disease, achieving an accuracy of 75.73%.

Çomak et al. proposed a decision-support system for diagnosing cardiovascular valve diseases based on Doppler signals, using Support Vector Machines [5]. The sensitivity of 94.5% and specificity of 90.0% obtained for their least-squares SVM system demonstrate that SVM-based methods can perform as well as neural networks but require much less training time. It also emphasizes the value of SVMs' generalization capabilities through structural risk minimization.

2.2 Comparative Studies

A systematic review of articles from 2015 to 2024 on heart disease prediction using supervised learning algorithms found that ensemble learning and neural networks are generally the most accurate [6, 7]. Notably, the systematic review emphasized the importance of conducting thorough comparisons of algorithms in experimental settings, taking into account the nature of the data and preprocessing techniques.

3. Materials and Methods

3.1 Dataset Description

This work uses the UCI Heart Disease Database [8], a widely used benchmark for scientific research on cardiovascular diseases. The database consists of 1,025 instances, each of which is represented by 14 clinical variables, namely, demographic information (age, sex), vital signs (resting blood pressure, maximum heart rate), diagnostic findings include serum values for cholesterol and fasting glucose, together with findings of the cardiovascular exam in terms of chest pain type, resting electrocardiogram (ECG), induction of angina, ST segment depression, slope of ST segment, number of major vessels visualized, and thalassemia. A list showing various clinical manifestations is presented in Table 1. The target variable indicates whether the patient has coronary artery disease (1) or does not (0).

The classes in this dataset are relatively balanced: 526 instances of positive examples (indicating the presence of heart disease; 51.3%) and 499 instances of negative examples

(indicating the absence of heart disease; 48.7%). This reduces the task's dependence on techniques such as data augmentation.

Table 1. Description of Clinical Features

Feature	Description	Type
age	Age in years	Numeric
sex	Gender (1=male, 0=female)	Binary
cp	Chest pain type (0-3)	Categorical
trestbps	Resting blood pressure (mm Hg)	Numeric
chol	Serum cholesterol (mg/dl)	Numeric
fb	Fasting blood sugar > 120 mg/dl	Binary
restecg	Resting ECG results (0-2)	Categorical
thalach	Maximum heart rate achieved	Numeric
exang	Exercise induced angina	Binary
oldpeak	ST depression induced by exercise	Numeric
slope	Slope of peak exercise ST segment	Categorical
ca	Number of major vessels (0-3)	Numeric
thal	Thalassemia type	Categorical
target	Heart disease (1=yes, 0=no)	Binary

3.2 Data Preprocessing

Data preprocessing was organized to maintain data quality, thereby improving model performance [9]. The preprocessing procedure entailed: (1) checking the integrity of the data without any missing values found within the data; (2) exploratory data analysis to describe the distributions of the data and its relationships; (3) feature scaling, where StandardScaler was applied for normalizing to have a mean of 0 and a unit variance; and finally, (4) stratified splitting of the data to retain the same proportion of classes for training and testing.

In most algorithms, an 80-20 train-test split was used (820 training samples and 205 test samples). When using Decision Trees, a 70-30 train-test split was adopted (717 training samples and 308 test samples) to provide a larger test set for improved evaluation. All experiments were performed with `random_state = 42`.

3.3 Machine Learning Algorithms

3.3.1 K-Nearest Neighbors (KNN)

To implement and evaluate the k-Nearest Neighbors (KNN) classifier, the `scikit-learn` `KNeighborsClassifier` function was used with `k=5` and the Euclidean metric [12]. Before classification, feature scaling was applied so that each feature had an equal influence on distance computation.

3.3.2 Naïve Bayes

A Gaussian Naïve Bayes classifier was developed, in which the continuous variables for each class are assumed to follow a Gaussian distribution [9]. It is a probabilistic model that uses Bayes' theorem to compute the posterior probability, considering all variables are independent.

3.3.3 Decision Trees

The Decision Tree Classifier was developed using `scikit-learn` with the objective of controlling overfitting by setting a maximum depth of 10, a minimum number of instances required to split a node of 5, and a random state of 42 to make the results deterministic and reproducible [10]. It uses the criterion of maximum information gain for splitting.

3.3.4 Support Vector Machines (SVM)

Support Vector Machine (SVM) classifiers were trained using an RBF (Radial Basis Function) kernel to address nonlinear classification problems [11]. In SVM, the classes are separated by finding the optimal hyperplane that maximizes the margin between them in a higher-dimensional feature space.

3.3.5 Artificial Neural Networks (ANN)

In building this multilayer perceptron (MLP) neural network, the following architecture building blocks were used: an input layer that can handle 13 features, the first hidden layer which contains 128 neurons and uses ReLU activation functions, the second hidden layer that holds 64 units and uses ReLU activation functions, and the output layer that uses the sigmoid activation function [12]. For training this network, the Adam algorithm, which uses the learning rate of 0.001 and L2 regularizations and early stopping in relation to validation loss, is employed.

3.4 Evaluation Metrics

Models' performance has been evaluated using specific measures: accuracy, precision, recall, F1 score, ROC-AUC, and 5-fold stratified cross-validation. It must be noted that the computation of precision, recall, accuracy, and F1 score is for the predicted positives only. They refer to instances belonging to the positive class.

4. Results

4.1 Performance Comparison

Table 2 compares, in depth, the performance characteristics of the five machine learning algorithms tested. It can be observed that algorithm performance varies significantly, with the Decision Tree algorithm achieving the highest accuracy of 96.43%.

Table 2. Performance Comparison of Machine Learning Algorithms

Algorithm	Accuracy (%)	Precision (%)	Recall (%)	F1-Score (%)	ROC-AUC
Decision Tree	96.43	98.04	94.94	96.46	0.9796
SVM	92.68	91.67	94.29	92.96	0.9771
KNN	86.34	87.38	85.71	86.54	0.9629
ANN (MLP)	84.39	80.67	91.43	85.71	0.9089
Naïve Bayes	82.93	80.70	87.62	84.02	0.9043

Figure 1 above showcases a comparison of performance metrics for the five algorithms using a radar chart. Using this graph, performance differences across all metrics can be readily assessed. The Decision Tree classifier performs best across most metrics.




Figure 1. Performance comparison of machine learning algorithms across Accuracy, F1-Score, ROC-AUC, and Precision-Recall metrics.

4.2 ROC Curve Analysis

In this case, the Receiver Operating Characteristic (ROC) curves for each model are shown in Figure 2. ROC curves are plots of sensitivity versus 1-specificity for different threshold values. As shown in Figure 2, both the Decision Tree and Support Vector Machine (SVM) models perform well as discriminative models, with AUC values exceeding 0.97. The maximum AUC for the Decision Tree is 0.9796, and for SVM it is 0.9771.




Figure 2. Receiver Operating Characteristic (ROC) curves comparing the discriminative performance of all five machine learning algorithms.

4.3 Confusion Matrix Analysis

As shown in Figure 3, the confusion matrices for the five classifiers provide a comprehensive view of the error patterns observed in the algorithms. Among these algorithms, the Decision Tree classifier yielded the most balanced results, maximizing true positives and true negatives while minimizing false positives and false negatives.




Figure 3. Confusion matrices showing the classification results for each machine learning algorithm, displaying true positives, true negatives, false positives, and false negatives.

4.4 Cross-Validation Results

The results of a stratified cross-validation test performed on a fifth of the data are presented in Table 3. It is observed that although the test performance of the two models differs, the ANN outperformed the other models, including the cross-validation means, achieving 99.61%, compared with 99.41% for the decision tree.

Table 3. 5-Fold Cross-Validation Results

Algorithm	Fold 1	Fold 2	Fold 3	Fold 4	Fold 5	Mean ± Std
Decision Tree	100.0%	100.0%	100.0%	97.1%	100.0%	99.41% ± 1.17%
ANN (MLP)	100.0%	100.0%	100.0%	98.0%	100.0%	99.61% ± 0.78%
SVM	92.2%	93.7%	93.2%	89.8%	92.2%	92.20% ± 1.34%
KNN	86.3%	81.5%	82.4%	82.4%	84.9%	83.51% ± 1.81%
Naïve Bayes	83.9%	84.9%	84.4%	80.5%	79.5%	82.63% ± 2.19%

4.5 Algorithm-Specific Results

4.5.1 Decision Trees

Decision trees achieved the highest test accuracy (96.43%), with precision (98.04%) and recall (94.94%). The training accuracy was 99.72%, giving an overfitting difference of 3.29%, indicating good generalization. The result was verified using cross-validation, giving a mean accuracy of 99.41% ± 1.17%.

4.5.2 Support Vector Machines

The support vector machine with the radial basis function kernel achieved a test accuracy of 92.68%, ranking second, a precision of 91.67%, and a recall of 94.29%, indicating a well-balanced performance. Cross-validation tests had an average accuracy of 92.20% and a standard deviation of 1.34%.

4.5.3 K-Nearest Neighbors

The accuracy of the K-Nearest Neighbors (KNN) method was 86.34%, the precision was 87.38%, and the recall was 85.71%. Cross-validation accuracy averaged $83.51\% \pm 1.81\%$. The instance-based learning method of this algorithm performed fairly.

4.5.4 Artificial Neural Networks

The accuracy, precision, and recall for the artificial neural network model on the test sets were 84.39%, 80.67%, and 91.43%, respectively. It is pertinent to note that, in cross-validation, the mean accuracy was approximately $99.61\% \pm 0.78\%$, indicating the presence of overfitting.

4.5.5 Naïve Bayes

The Naïve Bayes classifier had a test accuracy of 82.93%, a precision of 80.70%, and a recall of 87.62%. Cross-validation resulted in a mean accuracy of $82.63\% \pm 2.19\%$. Although the model made independence assumptions, its accuracy was quite good without being nearly as computationally expensive.

5. Discussion

The current research provides a comprehensive comparative analysis of five machine learning algorithms for predicting heart disease. The research is pertinent to the topic and offers valuable information for a better understanding of the subject.

Decision trees performed best, achieving a test accuracy of 96.43% and a minimal overfitting difference of 3.29%. The interpretability of the obtained rules is another important strength, particularly for medical applications, where providers must understand and verify the suggestions made by the algorithms [10]. It aligns with prior work that emphasizes the importance of interpretability in medical ML systems [6, 7].

One of the most significant findings of this research is that cross-validation accuracy differs from test-set accuracy for the artificial neural network (ANN). Cross-validation accuracy was 99.61%, whereas test-set accuracy was 84.39%. The difference of 15.22 percentage points indicates substantial overfitting, an unnecessarily complex ANN model given the number of data points, or the need for some form of regularization [9].

Support Vector Machine performance was stable on the test dataset (92.68%) and on the cross-validation set (92.20%). These figures provide evidence of its consistency, reinforcing the theoretically sound advantage of the SVM's structural risk minimization method, as advocated by [11], which yields a steady improvement toward optimal risk minimization.

Our results are comparable to those in previous work. Dela Cruz and Camungao [3] reported an accuracy of 91%, whereas our Decision Tree achieves 96.43%. The sensitivity of 94.5% reported by Çomak et al. [5] using SVM is comparable to our SVM-based recall of 94.29%.

5.1 Limitations

Certain shortcomings of this study require consideration. Firstly, this study is based on a single data set, namely the 'UCI Heart Disease' data set. This raises questions about the applicability of these findings to different populations or to alternative data-collection methods. Secondly, hyperparameter optimization is performed for standard models, potentially affecting their efficiency. Thirdly, the occurrence of overfitting in the ANN model requires a separate study using different regularization methods. Fourthly, the inability to test models on other datasets limits the scope of generalization.

6. Conclusion

This paper provides a thorough relative evaluation of the test accuracy of five machine learning algorithms for a heart disease prediction system. The main findings from this investigation demonstrate that the test accuracy of Decision Trees is the highest at 96.43%, followed by SVM at 92.68%, KNN at 86.34%, ANN at 84.39%, and Naïve Bayes at 82.93%. Cross-validation indicates potential overfitting in the ANN, even when achieving high cross-validation scores.

The results provide evidence-informed guidance on selecting algorithms for clinical cardiovascular decision-support systems, suggesting that Decision Trees are the preferred approach for tasks requiring high accuracy and interpretability. Future work should focus on external validation, the exploration of ensemble techniques, and the implementation of explainable AI algorithms to improve the applicability of these models in clinical medicine.

Declaration

Ethics Approval and Consent to Participate

This paper used publicly available anonymous data and did not involve human participants, human data, or human biological samples; therefore, it did not require approval.

Consent for Publication

Not applicable.

Availability of Data and Materials

The heart disease datasets used in the experiments, from the UCI repository, are available for free at <https://archive.ics.uci.edu/ml/datasets/heart+Disease>. The source code for each experiment is available from the corresponding author upon reasonable request.

Competing Interests

The authors report that, for this manuscript, there are no known financial competing interests or personal relationships that could be perceived as influencing the work.

Funding

Funding for this research was not sought from any public or private source, including not-for-profit organizations.

Authors' Contributions

S.S. designed the research, experiments, and data analysis; performed all experiments; interpreted data; and wrote an original version of the manuscript.

D.A. participated in the conceptualization of the study, offered academic supervision, and edited the manuscript.

E.A. assisted with the interpretation of results, provided technical advice on the article, and reviewed the manuscript. All authors read and approved the final draft of the paper.

Acknowledgments

The author is truly grateful to Dr. Derya AVCI for the guidance provided throughout this research.

Clinical Trial Number

Not applicable.

References

- [1] World Health Organization. (2023). Cardiovascular diseases (CVDs). WHO Fact Sheets. [https://www.who.int/news-room/fact-sheets/detail/cardiovascular-diseases-\(cvds\)](https://www.who.int/news-room/fact-sheets/detail/cardiovascular-diseases-(cvds))
- [2] Liu, T., Krentz, A., Lu, L., & Curcin, V. (2025). Machine learning based prediction models for cardiovascular disease risk using electronic health records data: A systematic review. *European Heart Journal - Digital Health*, 6(1), 7-22.
- [3] Dela Cruz, N. N., & Camungao, R. Q. (2020). Decision Support System for Predicting Cardiovascular Diseases Using Naïve Bayesian Algorithm. *International Journal of Advanced Trends in Computer Science and Engineering*, 9(3), 3178-3183.

- [4] Pandey, A. K., Pandey, P., Jaiswal, K. L., & Sen, A. K. (2013). A Heart Disease Prediction Model using Decision Tree. *IOSR Journal of Computer Engineering*, 12(6), 83-86.
- [5] Çomak, E., Arslan, A., & Türkoğlu, İ. (2007). A decision support system based on support vector machines for diagnosis of the heart valve diseases. *Computers in Biology and Medicine*, 37(1), 21-27.
- [6] Teja, M. D., & Rayalu, G. M. (2025). Optimizing heart disease diagnosis with advanced machine learning models. *BMC Cardiovascular Disorders*, 25, 212.
- [7] Zhang, Y., et al. (2024). A proposed technique for predicting heart disease using machine learning algorithms and an explainable AI method. *Scientific Reports*, 14, 23277.
- [8] Dua, D., & Graff, C. (2019). UCI Machine Learning Repository: Heart Disease Dataset. University of California, Irvine. <https://archive.ics.uci.edu/ml/datasets/heart+Disease>
- [9] Han, J., & Kamber, M. (2006). *Data Mining: Concepts and Techniques* (2nd ed.). Morgan Kaufmann Publishers.
- [10] Quinlan, J. R. (1993). *C4.5: Programs for Machine Learning*. Morgan Kaufmann Publishers.
- [11] Vapnik, V. N. (1995). *The Nature of Statistical Learning Theory*. Springer-Verlag.
- [12] Pedregosa, F., et al. (2011). Scikit-learn: Machine Learning in Python. *Journal of Machine Learning Research*, 12, 2825-2830.

**BIST'TE İŞLEM GÖREN AMBALAJ FİRMALARINDA FİNANSAL SIKINTI
RİSKİNİN ALTMAN Z-SKOR İLE ANALİZİ (2020–2024)**

FINANCIAL DISTRESS RISK IN TURKISH LISTED PACKAGING FIRMS: AN
ALTMAN Z-SCORE ANALYSIS (2020–2024)

Sinan GÜLENÇER

Dr.Öğr.Üyesi, Eskişehir Osmangazi Üniversitesi, Sağlık Hizmetleri MYO

ÖZ

Bu çalışma, Türkiye’de ambalaj sektöründe faaliyet gösteren ve BIST’te işlem gören firmaların 2020–2024 dönemindeki finansal dayanıklılığını, imalat firmaları için geliştirilmiş Altman Z-Skor modeliyle ölçmeyi ve karşılaştırmalı olarak yorumlamayı amaçlamaktadır. Analizde yıllık finansal tablo verileri KAP üzerinden derlenmiş; örnekleme BAKAB, BARMA, BNTAS, DURDO, EMNIS, GEDZA, KAPLM, KRPLS, MNDTR, OZRDN ve SEKUR dâhil edilmiştir. Z-Skor, likidite, birikmiş kârlılık, faaliyet kârlılığı, sermaye yapısı ve varlık devir hızını temsil eden beş bileşenin tek bir bileşik skor altında birleştirilmesiyle hesaplanmış; firmalar $Z < 1.81$ riskli, $1.81 \leq Z \leq 2.99$ gri, $Z > 2.99$ güvenli şeklinde sınıflandırılmıştır. Bulgular, sektörde 2022’de iyileşme görülmesine karşın 2023–2024’te riskli firma sayısının yeniden arttığını göstermektedir. Dönem genelinde en güçlü ve istikrarlı firmalar BNTAS ve GEDZA olup, OZRDN riskli seviyelerden güvenli bölgeye geçerek belirgin toparlanma sergilemiştir; EMNIS ve SEKUR sürekli riskli bölgede kalarak en kırılgan profili oluşturmuştur.

Anahtar Kelimeler: Ambalaj endüstrisi, Altman Z-Skoru, İflas tahmini, Erken uyarı modeli, Finansal dayanıklılık

ABSTRACT

This study evaluates the financial resilience of publicly listed Turkish packaging firms traded on Borsa Istanbul over 2020–2024 using the Altman Z-Score model tailored to manufacturing firms. Annual financial statements were collected from KAP, and the sample includes BAKAB, BARMA, BNTAS, DURDO, EMNIS, GEDZA, KAPLM, KRPLS, MNDTR, OZRDN, and SEKUR. The Z-Score aggregates five dimensions—liquidity/working capital strength, cumulative profitability, operating profitability, capital structure, and asset turnover—into a single composite indicator, and firms are classified as distress ($Z < 1.81$), grey ($1.81 \leq Z \leq 2.99$), or safe ($Z > 2.99$). The findings indicate a sector-wide improvement in 2022, followed by a renewed weakening in 2023–2024, reflected in an increase in the number of firms in the distress zone. Across the whole period, BNTAS and GEDZA stand out as the most robust and stable firms, while OZRDN exhibits the strongest structural recovery by moving from distress to the safe zone. In contrast, EMNIS and SEKUR remain persistently distressed, signalling heightened fragility within the sector.

Keywords: Packaging industry, Altman Z-Score, Bankruptcy prediction, Early warning model, Financial resilience

GİRİŞ

Ambalaj sektörü; gıda, içecek, ilaç, hızlı tüketim ve sanayi ürünlerinde ürün güvenliği, raf ömrü, lojistik verimlilik ve marka değeri gibi unsurlar üzerinden katma değer üreten stratejik bir imalat koludur. Türkiye’de sektör, yalnızca iç pazara hizmet etmekle kalmayıp dış ticaret fazlası üreten yapısıyla da öne çıkmaktadır. Ambalaj Sanayicileri Derneği’nin (ASD)

yayımladığı dış ticaret verilerine göre 2024 yılında sektör ihracatı 6,95 milyar ABD dolarına ulaşmış; sektör dış ticaret fazlasını sürdürerek 2,68 milyar ABD doları seviyesine taşımıştır (ASD, 2025). Benzer biçimde 2024'ün ilk yarısında ihracatın 3,322 milyar ABD doları olduğu ve aynı dönemde 1,152 milyar ABD doları dış ticaret fazlası verildiği raporlanmıştır (ASD, 2024). Bu görünüm, ambalaj sektörünün Türkiye ekonomisinde üretim, istihdam ve ihracat kanalları üzerinden önemli bir çarpan etkisi taşıdığını göstermektedir.

Sektörün büyüme dinamikleri, makroekonomik koşullarla yakından ilişkilidir. ASD'nin sektör özet raporu, Türkiye'de ambalaj sanayinin 2017–2021 döneminde hacim bazında ortalama %7, ciro bazında ise ortalama %9 büyüdüğünü raporlamaktadır (ASD, 2023). Bununla birlikte yüksek enflasyon, kur oynaklığı ve finansman koşullarındaki sıkılaşma, imalat firmalarında işletme sermayesi ihtiyacını artırarak likidite ve kârlılık baskısı oluşturabilmektedir. Türkiye Cumhuriyet Merkez Bankası (TCMB) Enflasyon Raporu'nda; 2023'ün üçüncü çeyreğinde enflasyonun belirgin yükselişi ve Türk lirasındaki değer kaybı gibi unsurların fiyatlamaya davranışları üzerinde etkili olduğuna vurgu yapılmaktadır (TCMB, 2023). IMF'nin Türkiye 2024 Madde IV değerlendirmesi de 2023 sonrası politika normalleşmesiyle birlikte daha sıkı finansal koşulların talep ve enflasyon dinamikleri üzerinde rol oynadığını; buna rağmen risklerin sürdüğünü belirtmektedir (IMF, 2024). Bu çerçevede, ambalaj gibi hammadde bağımlılığı (ör. kâğıt-karton, plastik türevleri, metal) ve enerji/lojistik maliyet duyarlılığı yüksek alanlarda, firmaların finansal dayanıklılığının izlenmesi daha kritik hale gelmektedir.

Bu çalışmanın motivasyonu, söz konusu makro-f finansal arka plan altında BIST'te işlem gören ambalaj şirketlerinin finansal sıkıntı riskinin karşılaştırılabilir, şeffaf ve erken uyarı üreten bir çerçevede değerlendirilmesidir. Literatürde firma düzeyinde finansal başarısızlık riskini ölçmek için kullanılan araçlardan biri olan Altman Z-Skor modeli, özellikle imalat firmaları için geliştirilmiş yapısı nedeniyle bu çalışma kapsamında uygun bir teorik ve ampirik zemin sunmaktadır (Altman, 1968). Modelin temel faydası; tek tek oranların dağınık sinyallerini birleştirerek, firmaları “riskli–gri–güvenli” gibi karar destek bölgelerine ayırabilmesidir. Bu sayede yatırımcılar, kreditorler, yöneticiler ve düzenleyici kurumlar açısından erken uyarı, izleme ve karşılaştırma imkânı artmaktadır.

Bu doğrultuda çalışma; (i) BIST ambalaj firmaları için 2020–2024 döneminde Altman Z-Skorlarını hesaplamayı, (ii) firmaları risk bölgelerine göre sınıflandırmayı ve (iii) yıllar itibarıyla değişimi yorumlayarak ambalaj sektöründe finansal risk görünümüne ilişkin bütüncül bir değerlendirme sunmayı amaçlamaktadır. Böylece sektör paydaşlarına, şirketlerin finansal dayanıklılığının hangi dönemlerde güçlendiği/zayıfladığı ve hangi firmaların istikrarlı biçimde öne çıktığı konusunda kanıta dayalı bir çerçeve sağlanmaktadır.

TEORİK ÇERÇEVE

Finansal sıkıntı ve erken uyarı yaklaşımları

Finansal sıkıntı; işletmenin nakit akışları ve kârlılık kapasitesinin borç servis yükümlülüklerini karşılamada yetersiz kalması, likidite baskısının artması ve sonuçta iflas/yeniden yapılandırma riskinin yükselmesi şeklinde tanımlanabilir. Özellikle yüksek enflasyon ve oynak kur dönemlerinde, firmaların işletme sermayesi ihtiyacı büyür; kısa vadeli borçlanma maliyetleri artar ve bilanço yapısı daha kırılgan hale gelebilir. TCMB'nin finansal istikrar perspektifinde şirketler kesiminin borçlanma dinamikleri ve kur riski yönetimi, makro ihtiyati çerçeve açısından kritik bir izleme alanı olarak ele alınmaktadır; örneğin 2022 yılında şirketler kesiminin TL kredilerindeki artış ve döviz kredilerindeki gelişmeler bu çerçevede değerlendirilmektedir (TCMB, 2022). Bu tür ortamlarda, firmaların finansal sıkıntıya sürüklenmesini önceden tespit edebilmek için kompozit risk ölçütleri ve erken uyarı modelleri yaygın şekilde kullanılmaktadır.

Erken uyarı modelleri içinde, oran analizini tek bir skor altında birleştiren çok değişkenli yaklaşımlar pratikte öne çıkar. Türkiye örneğinde de, BIST şirketleri üzerinde finansal

risk/başarısızlık tahmini için diskriminant analize dayalı kompozit skorların üretildiği çalışmalar bulunmaktadır (TCMB, 2019). Bu yaklaşım, farklı boyutları (likidite, kârlılık, kaldıraç, faaliyet etkinliği) aynı çerçevede değerlendirerek tek bir özet gösterge üretmesi nedeniyle özellikle sektör karşılaştırmalarında işlevseldir.

Altman Z-Skor modeli ve imalat firmaları için uygunluğu

Altman Z-Skor modeli, kurumsal başarısızlığı öngörmek üzere çok değişkenli diskriminant analizine dayalı olarak geliştirilmiş klasik bir yaklaşımdır. Model, imalat firmaları üzerinde test edilerek beş finansal oranı belirli katsayılarla ağırlıklandırıp tek bir skor üretir (Altman, 1968). Teorik olarak bu beş bileşen; (i) likidite/işletme sermayesi gücü, (ii) kümülatif kârlılık (dağıtılmayan kârlar), (iii) faaliyet kârlılığı/varlıkların kazanç yaratma gücü, (iv) sermaye yapısı ve borçluluk, (v) varlık devir hızı/operasyonel etkinlik boyutlarını temsil eder. Dolayısıyla Z-Skor, yalnızca borçluluğu değil, aynı zamanda firmanın “kâr yaratma kapasitesi” ve “faaliyet etkinliği”ni de risk perspektifine dâhil eder.

Modelin yaygın uygulamalarında firmalar genellikle üç bölge altında yorumlanır: $Z < 1,81$ “distress (riskli)”, $1,81 \leq Z \leq 2,99$ “grey (gri)”, $Z > 2,99$ “safe (güvenli)” bölge olarak kabul edilir (Altman, 1968; Braunsberger et al., 2025). Bu eşikler, ampirik olarak firmaların iflasa yakınlık derecesini temsil eden pratik bir sınıflama sunar. Ambalaj sektörü gibi imalat yapısı baskın firmalarda; varlık yapısı, satış-aktif ilişkisi, işletme sermayesi döngüsü ve borçlanma kompozisyonu Z-Skor bileşenleriyle yakından ilişkili olduğundan, modelin teorik uygunluğu artmaktadır.

Öte yandan, Z-Skorun farklı ülkelerde ve dönemlerde uygulanmasında bazı uyarılma ihtiyaçları doğabilmektedir. Özellikle gelişmekte olan piyasalarda muhasebe standartları, fiyat düzeyi etkileri ve piyasa değerine erişim gibi kısıtlar, modelin bazı bileşenlerinin (ör. piyasa değeri temelli kaldıraç ölçümü) farklılaştırılmasını gündeme getirebilir. Türkiye’de BIST örnekleminde Altman ve benzeri skorların finansal başarısızlığı ölçmekte kullanıldığı çalışmalar, modelin erken uyarı kabiliyetine dair kanıtlar sunmaktadır (Türk & Kürklü, 2017). Ayrıca Türkiye bağlamında modelin uygulanabilirliği ve alternatif model karşılaştırmaları üzerine literatür de mevcuttur (Cındık, 2021). Dolayısıyla bu çalışma, Altman Z-Skorun imalat temelli yapısını ambalaj sektörü özelinde kullanarak firmaları risk bölgelerine ayırmakta; yıllar itibarıyla değişimi yorumlayarak sektör içi güçlü/zayıf profilleri görünür kılmaktadır.

LİTERATÜR

Altman (1968), iflas tahmini için üretim firmalarına yönelik çok değişkenli diskriminant yaklaşımıyla Z-Skor modelini geliştirir; firmaları güvenli–gri–riskli zonlara ayıran eşikleri tanımlar ve modelin erken uyarı gücünü gösterir.

Altman & Hotchkiss (2006), kurumsal finansal sıkıntı/iflas literatürünü derleyip Z-Skor’un farklı versiyonlarının (özellikle üretim ve piyasa değeri içeren yapıların) uygulama mantığını, sınırlılıklarını ve yorum çerçevesini sistematik biçimde sunar (ambalaj gibi sermaye yoğun sektörlerde oranların “neden bozulduğunu” yorumlamak için iyi bir teorik dayanak).

Say (2024), Borsa İstanbul’da kimya–ilaç–petrol–kauçuk–plastik ürünler sınıflamasında (ambalajla güçlü kesişim) en büyük aktifli 10 şirketi inceler; 2019–2021 döneminde Altman’ın üretim (klasik) formu ile şirketleri riskli/gri/güvenli zonlara ayırır. Sonuçlar, sektör ortalamasında iyileşme sinyalleri olsa da şirket bazında riskli zon payının yüksek kaldığını gösterir.

Nafisa ve ark. (2022), Endonezya borsasında plastik ve ambalaj şirketlerinde 2017–2020 dönemini ele alır; Altman, Springate, Zmijewski, Grover gibi birden çok başarısızlık modelinin sınıflamalarını karşılaştırır. Bulgular, modellerin aynı firmayı her zaman aynı risk zonuna koymadığını; özellikle kârlılık/likidite şoklarında ayrışmanın arttığını raporlar.

Ismidiyah & Widodo (2025), IDX’de plastik ve ambalaj alt sektörü için 2020–2022 döneminde Altman Z-Skor ile potansiyel iflas/risk zonu sınıflaması yapar; sektör içinde firma

bazında risklerin heterojen olduğunu ve dönemsel dalgalanmaların (özellikle işletme sermayesi ve satış etkinliği) skoru hızla oynattığını vurgular.

Abidin ve ark. (2023), IDX’de packaging & plastic firmalarını 2016–2019 döneminde Altman Z-Skor ile değerlendirir; firmaların yıllar itibarıyla risk zonlarında yer değiştirebildiğini ve sektör şoklarına duyarlılığın yüksek olduğunu gösterir.

Kurniasih, Heliantono & Sumarto (2019) (senin verdiği “IJBMM, 2019” çalışması), IDX’de pulp & paper firmaları için 2014–2017 döneminde Altman Z-Skor ile risk zonu analizi yapar ve ayrıca Z-Skor’un hisse getirisi ile ilişkisini test eder; bulgular, firmaların önemli kısmının “potansiyel iflas/yüksek risk” sınıflarında yoğunlaştığını ve Z-Skor’un hisse getirisiyle ilişkinin her zaman güçlü çıkmadığını raporlar.

Kurniasih ve ark. (2022), IDX’de pulp & paper firmaları için 2013–2019 döneminde panel veri yaklaşımıyla Z-Skor’un hisse fiyatı üzerindeki etkisini inceler; Z-Skor’un hisse fiyatını anlamlı açıkladığını ve Z-Skor bileşenlerinden bazılarının (özellikle işletme sermayesi/aktif, piyasa değeri/borç ve satış/aktif) daha belirleyici olabildiğini bulur.

Fadrul & Ridawati (2020), IDX’de pulp & paper firmaları için 2012–2017 döneminde Altman yaklaşımıyla finansal sıkıntı/iflas riskini sınıflandırır; sonuçlar sektör içinde “riskli” zonun yaygın olduğunu ve firmaların dönemsel olarak gri/riskli zon arasında gidip gelebildiğini gösterir.

Fredy (2018), IDX’de pulp & paper firmalarını 2011–2016 döneminde Altman, Springate, Grover gibi modellerle karşılaştırmalı değerlendirir; modellerin aynı firmaya farklı risk sinyali verebildiğini, ancak genel resimde sektörün finansal kırılganlığının yüksek olduğunu raporlar.

Arini ve ark. (Scitepress/IC? 2018/2020), IDX’de reklam-basım-medya (etiket/basım ambalajla kesişen) firmalarını 2012–2015 döneminde Altman Z-Skor ile inceler; bazı firmaların sürekli “sağlıklı” bölgede kalabildiğini, bazılarında ise işletme sermayesi ve özkaynak/borç dinamiklerinin skoru dalgalandırdığını gösterir.

Yeşildaş (2021), finansal sıkıntı modellerinin performansını karşılaştırırken pulp & paper firmalarında (özellikle 2011–2016 örnekleri üzerinden) Altman/Springate/Grover gibi modellerin farklı duyarlılıklara sahip olduğunu ve “tek modele” yaslanmanın sınıflama hatası riskini artırdığını tartışır.

Kurniasih ve ark. (2020), IDX’de pulp & paper firmalarında Altman Z-Skor’u “finansal sıkıntı ölçütü” olarak alıp likidite, kaldıraç, kârlılık ve etkinlik gibi belirleyicilerin distress üzerindeki etkisini test eder; kârlılık/etkinlik/likidite bozulmasının distress’i artırdığını, kaldıraç kanalının ise kritik olduğunu bulur.

Lestari, Oktaviani & Arafah (2016), IDX’de kimya alt sektörü firmalarında 2009–2014 döneminde Z-Skor bileşenlerinin hisse fiyatı ilişkisini inceler; bileşenlerin etkisinin yönü ve anlamlılığının farklılaştığını gösterir (ambalajın hammadde/kimya bağlantısı için kıymetli).

Apergis ve ark. (2011), Avrupa borsalarında (Paris-Londra-Frankfurt) Z-Skor ile hisse fiyatı/performansı arasındaki ilişkiyi raporlar; piyasaların distress bilgisini fiyatlaması argümanını güçlendirir (ambalaj firmalarında Z-Skor → piyasa tepkisi tartışması için teorik destek).

Özyeşil (2020), BIST-30 şirketlerinde Altman Z-Skor ile hisse fiyatı performansı arasında ilişki raporlar; Türkiye bağlamında Z-Skor’un “piyasa göstergeleriyle birlikte” yorumlanması gerektiğine işaret eder.

Kurniasih ve ark. (2022) ayrıca pulp & paper özelinde 2013–2019 döneminde Z-Skor’un hisse fiyatını açıklama gücünü yüksek bulur; bu da ambalaj gibi emtia/enerji şoklarına açık sektörlerde “distress-piyasa kanalı”nın güçlü olabileceğini düşündürür.

Say (2024) bulguları, plastik-kauçuk-kimya hattında (ambalaj ekosistemi) riskli zon oranlarının 2019 sonrası dönemde yüksek seyrettiğini; özellikle negatif işletme sermayesi olan firmalarda skorun yapısal biçimde baskılandığını gösterir.

Kurniasih, Heliantono & Sumarto (2019) pulp & paper örneğinde, bazı yıllarda firmaların “potansiyel iflas” zonuna sıkıştığını raporlar; bu, ambalajda kapasite/enerji/ham madde şoklarının “oranlar üzerinden” distress’i kronikleştirebileceği argümanına sektör-benzeri kanıt sunar.

VERİ SETİ VE ÖRNEKLEM

Bu çalışmada Türkiye’de ambalaj sektöründe faaliyet gösteren ve BIST’te işlem gören firmaların yıllık finansal tabloları kullanılmıştır. Finansal tablo verileri, sermaye piyasası mevzuatı gereği kamuya açıklanan bildirimlerin yer aldığı Kamuyu Aydınlatma Platformu (KAP) üzerinden derlenmiştir. Örneklem, KAP’ta ambalaj endeksi altında yer alan ve ambalaj/paketleme ile ilişkili imalat yapısına sahip firmalar arasından seçilmiştir. Çalışma dönemi 2020–2024 olup, her firma için son 5 yıla ait yıl sonu verileri kullanılmıştır. Örneklemde yer alan şirketler: BAKAB, BARMA, BNTAS, DURDO, EMNIS, GEDZA, KAPLM, KRPLS, MNDTR, OZRDN, SEKUR’dur.

Yöntem: Altman Z-Skor modeli

Çalışmada imalat firmaları için geliştirilmiş klasik **Altman Z-Skor** modeli kullanılmıştır. Model; likidite, birikmiş kârlılık, faaliyet kârlılığı, sermaye yapısı ve varlık devir hızını temsil eden beş oranı tek bir bileşik skor altında birleştirerek finansal sıkıntı riskini ölçer (Altman, 1968).

İmalat modeli aşağıdaki şekilde hesaplanır:

$$Z = 1.2X_1 + 1.4X_2 + 3.3X_3 + 0.6X_4 + 1.0X_5 \quad (1)$$

Burada kullanılan bileşenler:

- **X1 (Likidite/işletme sermayesi gücü)** = (Dönen Varlıklar – Kısa Vadeli Yükümlülükler) / Toplam Aktif
- **X2 (Birikmiş kârlılık)** = Dağıtılmayan Kârlar (geçmiş yıllar kâr/zararı) / Toplam Aktif
- **X3 (Faaliyet kârlılığı)** = EBIT / Toplam Aktif
- **X4 (Sermaye yapısı)** = Özsermaye / Toplam Borç
- **X5 (Faaliyet etkinliği)** = Net Satışlar / Toplam Aktif

Altman modelinin literatürde yaygın kullanılan eşikleriyle her firma-yıl gözlemi üç bölgeye ayrılmıştır (Altman, 1968).

- **Z < 1.81 → Riskli** (puan=1)
- **1.81 ≤ Z ≤ 2.99 → Gri** (puan=2)
- **Z > 2.99 → Güvenli** (puan=3)

Bu puanlama, Z skorun kendisini değiştirmez; sadece yıllar ve firmalar arası karşılaştırmayı kolaylaştırır.

BULGULAR

Bu bölümde, Türkiye’de ambalaj sektöründe faaliyet gösteren ve Borsa İstanbul’da işlem gören firmaların 2020–2024 dönemine ilişkin finansal sıkıntı riskleri, imalat firmaları için geliştirilen Altman Z-Skor modeli kullanılarak değerlendirilmektedir. Analiz kapsamında her firma için yıllık finansal tablolar üzerinden X1–X5 bileşen oranları hesaplanmış; elde edilen Z-Skorlar klasik eşik değerler dikkate alınarak firmalar riskli ($Z < 1.81$), gri ($1.81 \leq Z \leq 2.99$) ve güvenli ($Z > 2.99$) bölgelerde sınıflandırılmıştır (Altman, 1968). Bu çerçevede bulgular, önce dönemler itibarıyla sektör genelindeki risk dağılımını ve eğilimleri ortaya koymakta; ardından firma bazında Z-Skor düzeyleri, bölge geçişleri ve öne çıkan iyileşme/bozulma örüntülerini karşılaştırmalı biçimde sunmaktadır. Böylece ambalaj sektöründe finansal dayanıklılığın zaman içindeki seyrine ve firmalar arası heterojenliğe ilişkin bütüncül bir görünüm sağlanmaktadır.

INTERNATIONAL TOPKAPI CONGRESS VI

Tablo 1. Şirketlerin yıllara göre Z skor ve puanları

	2024/12		2023/12		2022/12		2021/12		2020/12	
	Z	Puan	Z	Puan	Z	Puan	Z	Puan	Z	Puan
BAKAB	2,148	2	2,49	2	2,007	2	1,648	1	2,406	2
BARMA	1,032	1	1,923	2	3,592	3	3,211	3	2,357	2
BNTAS	9,364	3	5,239	3	4,468	3	6,887	3	4,634	3
DURDO	2,096	2	2,441	2	2,695	2	1,817	2	1,425	1
EMNIS	0,215	1	0,184	1	-1,845	1	0,935	1	0,656	1
GEDZA	3,63	3	4,391	3	4,92	3	4,706	3	3,501	3
KAPLM	1,412	1	1,754	1	2,154	2	2,011	2	1,539	1
KRPLS	1,885	2	1,959	2	3,126	3	2,382	2	2,612	2
MNDTR	2,656	2	2,371	2	3,013	3	2,067	2	1,771	1
OZRDN	4,948	3	6,022	3	3,59	3	2,788	2	1,563	1
SEKUR	1,236	1	0,988	1	1,205	1	1,005	1	1,344	1

Tablo 2. Şirketlerin 5 yıllık ortalamaları

	Z_Ortalama(5Y)	Puan_Ortalama(5Y)	Bölge_Ortalama(5Y)
BAKAB	2,14	1,8	Gri
BARMA	2,423	2,2	Gri
BNTAS	6,118	3	Güvenli
DURDO	2,095	1,8	Gri
EMNIS	0,029	1	Riskli
GEDZA	4,23	3	Güvenli
KAPLM	1,774	1,4	Riskli
KRPLS	2,393	2,2	Gri
MNDTR	2,376	2	Gri
OZRDN	3,782	2,4	Güvenli
SEKUR	1,156	1	Riskli

BAKAB için 2020–2024 döneminde Altman Z-skoru ortalaması 2.140 olup genel görünüm Gri bölgededir. 2020 sonunda Z=2.406 ile gri bölgededir. 2021 sonunda skor Z=1.648’e gerileyerek şirketi Riskli bölgeye taşımıştır. 2022 sonunda Z=2.007 ile yeniden Gri bölgeye dönmüştür.

2023 sonunda Z=2.490 ile gri bölgede kalmış, 2024 sonunda Z=2.148 ile yine gri bölgede kapanış yapmıştır. Bölge geçişleri: 2021 yılında Gri → Riskli; 2022 yılında Riskli → Gri. Dönemin en yüksek skoru 2023’te 2.490, en düşük skoru 2021’de 1.648’dir.

BARMA için 2020–2024 döneminde Altman Z-skoru ortalaması 2.423 olup genel görünüm Gri bölgededir. 2020 sonunda Z=2.357 ile gri bölgededir. 2021 sonunda Z=3.211’e yükselerek Güvenli bölgeye geçmiştir. 2022 sonunda Z=3.592 ile güvenli bölgede kalmaya devam etmiştir.

2023 sonunda Z=1.923’e düşerek Gri bölgeye gerilemiş, 2024 sonunda Z=1.032 ile Riskli bölgeye inmiştir. Bölge geçişleri: 2021’de Gri → Güvenli; 2023’te Güvenli → Gri; 2024’te Gri → Riskli. Dönemin en yüksek skoru 2022’de 3.592, en düşük skoru 2024’te 1.032’dir.

BNTAS için 2020–2024 döneminde Altman Z-skoru ortalaması 6.118 olup genel görünüm Güvenli bölgededir. 2020 sonunda $Z=4.634$, 2021 sonunda $Z=6.887$ ve 2022 sonunda $Z=4.468$ değerleriyle şirket her yıl Güvenli bölgede kalmıştır.

2023 sonunda $Z=5.239$ ile güvenli bölge korunmuş, 2024 sonunda $Z=9.364$ ile çok güçlü bir kapanış yapılmıştır. Bölge geçişi yok; şirket tüm dönemde güvenli sınıfta kalmıştır. Dönemin en yüksek skoru 2024'te 9.364, en düşük skoru 2022'de 4.468'dir.

DURDO için 2020–2024 döneminde Altman Z-skoru ortalaması 2.095 olup genel görünüm Gri bölgededir. 2020 sonunda $Z=1.425$ ile şirket Riskli bölgededir. 2021 sonunda $Z=1.817$ ile hâlâ Riskli bölgede kalmıştır. 2022 sonunda $Z=2.695$ 'e yükselerek Gri bölgeye geçmiştir.

2023 sonunda $Z=2.441$ ile gri bölgede kalmış, 2024 sonunda $Z=2.096$ ile yine gri bölgede kapanış yapmıştır. Bölge geçişleri: 2022 yılında Riskli → Gri. Dönemin en yüksek skoru 2022'de 2.695, en düşük skoru 2020'de 1.425'tir.

EMNIS için 2020–2024 döneminde Altman Z-skoru ortalaması 0.029 olup genel görünüm Riskli bölgededir. 2020 sonunda $Z=0.656$ ile riskli bölgededir. 2021 sonunda skor $Z=0.935$ 'e çıksa da bölge değişmemiştir. 2022 sonunda $Z=-1.845$ seviyesine inerek dönem içindeki en zayıf noktaya düşmüştür.

2023 sonunda $Z=0.184$, 2024 sonunda $Z=0.215$ ile kısmi toparlanma görülse de şirket her iki yılda da Riskli bölgede kalmıştır. Bölge geçişi yok; şirket tüm dönemde riskli sınıfta seyretmiştir. En yüksek skor 2021'de 0.935, en düşük skor 2022'de -1.845'tir.

GEDZA için 2020–2024 döneminde Altman Z-skoru ortalaması 4.230 olup genel görünüm Güvenli bölgededir. 2020 sonunda $Z=3.501$ ile güvenli bölgededir. 2021 sonunda $Z=4.706$ 'ya yükselmiş, 2022 sonunda $Z=4.920$ ile güvenli görünüm güçlenmiştir.

2023 sonunda $Z=4.391$, 2024 sonunda $Z=3.630$ değerleriyle skor bir miktar gerilese de şirket Güvenli bölgede kalmayı sürdürmüştür. Bölge geçişi yoktur. En yüksek skor 2022'de 4.920, en düşük skor 2020'de 3.501'dir.

KAPLM için 2020–2024 döneminde Altman Z-skoru ortalaması 1.774 olup genel görünüm Riskli bölgededir. 2020 sonunda $Z=1.539$ ile riskli bölgededir. 2021 sonunda $Z=2.011$ 'e çıkarak Gri bölgeye geçmiştir. 2022 sonunda $Z=2.154$ ile gri bölgede kalmıştır.

2023 sonunda $Z=1.754$ 'e gerileyerek Riskli bölgeye dönmüş, 2024 sonunda $Z=1.412$ ile riskli bölgede kapanış yapmıştır. Bölge geçişleri: 2021'de Riskli → Gri; 2023'te Gri → Riskli. En yüksek skor 2022'de 2.154, en düşük skor 2024'te 1.412'dir.

KRPLS için 2020–2024 döneminde Altman Z-skoru ortalaması 2.393 olup genel görünüm Gri bölgedir. 2020 sonunda $Z=2.612$ ile gri bölgededir. 2021 sonunda $Z=2.382$ ile gri bölgede kalmıştır. 2022 sonunda $Z=3.126$ 'ya yükselerek Güvenli bölgeye geçmiştir.

2023 sonunda $Z=1.959$ ile yeniden Gri bölgeye gerilemiş, 2024 sonunda $Z=1.885$ ile gri bölgede kapanış yapmıştır. Bölge geçişleri: 2022'de Gri → Güvenli; 2023'te Güvenli → Gri. En yüksek skor 2022'de 3.126, en düşük skor 2024'te 1.885'tir.

MNDTR için 2020–2024 döneminde Altman Z-skoru ortalaması 2.376 olup genel görünüm Gri bölgededir. 2020 sonunda $Z=1.771$ ile şirket Riskli bölgededir. 2021 sonunda $Z=2.067$ ile Gri bölgeye geçmiştir. 2022 sonunda $Z=3.013$ ile Güvenli bölgeye yükselmiştir.

2023 sonunda $Z=2.371$ ile tekrar Gri bölgeye dönmüş, 2024 sonunda $Z=2.656$ ile gri bölgede kapanış yapmıştır. Bölge geçişleri: 2021'de Riskli → Gri; 2022'de Gri → Güvenli; 2023'te Güvenli → Gri. En yüksek skor 2022'de 3.013, en düşük skor 2020'de 1.771'dir.

OZRDN için 2020–2024 döneminde Altman Z-skoru ortalaması 3.782 olup genel görünüm Güvenli bölgedir. 2020 sonunda $Z=1.563$ ile Riskli bölgededir. 2021 sonunda $Z=2.788$ 'e yükselerek Gri bölgeye geçmiştir. 2022 sonunda $Z=3.590$ ile Güvenli bölgeye yükselmiştir.

2023 sonunda $Z=6.022$ ile güvenli görünüm belirgin güçlenmiş, 2024 sonunda $Z=4.948$ 'e gerilese de şirket Güvenli bölgede kalmıştır. Bölge geçişleri: 2021'de Riskli → Gri; 2022'de Gri → Güvenli. En yüksek skor 2023'te 6.022, en düşük skor 2020'de 1.563'tür.

SEKUR için 2020–2024 döneminde Altman Z-skoru ortalaması 1.156 olup genel görünüm Riskli bölgedir. 2020 sonunda $Z=1.344$, 2021 sonunda $Z=1.005$ ve 2022 sonunda $Z=1.205$ değerleriyle şirket her yıl Riskli bölgede kalmıştır.

2023 sonunda $Z=0.988$ ile en düşük seviyeye inmiş, 2024 sonunda $Z=1.236$ ile toparlanma görülse de eşik üstüne çıkılamamıştır. Bölge geçişi yoktur; tüm dönem riskli sınıfta seyretmiştir. En yüksek skor 2020’de 1.344, en düşük skor 2023’te 0.988’dir.

2020–2024 dönemi birlikte değerlendirildiğinde ambalaj şirketlerinin Altman Z-skor dağılımı 2022’de belirgin şekilde iyileşip (güvenli firma sayısı en yüksek seviyeye çıkıyor) 2023–2024’te yeniden zayıflayan bir görünüm sergiliyor; bu tablo sektörün genelinde “toparlanma → normalleşme/bozulma” döngüsüne işaret ediyor. Tüm yılları kapsayan performans açısından en çok öne çıkanlar BNTAS (5 yılın tamamında Güvenli, ortalama $Z\approx 6.12$) ve GEDZA (5 yılın tamamında Güvenli, ortalama $Z\approx 4.23$) olup, bu iki şirket dönemin en istikrarlı ve en güçlü grubunu oluşturuyor. OZRDN ise dönem boyunca en dikkat çekici yapısal iyileşmeyi göstererek 2020’de riskli seviyelerden başlayıp 2022’den itibaren Güvenli bölgede kalmayı başararak güçlüler arasına yerleşiyor (ortalama $Z\approx 3.78$). Orta grupta BAKAB genel olarak Gri bölgede istikrarlı kalırken, DURDO riskliden griye geçip gri bölgede tutunuyor; MNDTR ve KRPLS 2022’de güvenli bölgeye çıksa da sonraki yıllarda tekrar griye dönerek “zirve sonrası geri çekilme” paterni sergiliyor. Zayıf tarafta ise EMNIS ve SEKUR 5 yılın tamamında Riskli bölgede kalarak en kırılgan profilin temsilcileri olurken, KAPLM’de 2021–2022’deki kısa süreli gri bölgeye geçişe rağmen 2023–2024’te yeniden riskli bölgede kalıcılık dikkat çekiyor. Genel sıralamada (5 yıllık ortalama Z ’ye göre) en güçlüler: BNTAS, GEDZA, OZRDN; en zayıflar: EMNIS, SEKUR, KAPLM olarak öne çıkıyor; ayrıca dönemsel değişim açısından en güçlü iyileşmeler BNTAS ve OZRDN’de görülürken, en belirgin bozulma BARMA’da (2021–2022 güvenli 2024’te riskliye düşüş) dikkat çekiyor.

SONUÇ VE TARTIŞMA

Bu çalışmada BIST’te işlem gören 11 ambalaj firmasının 2020–2024 dönemine ait Altman Z-Skorları hesaplanmış ve firmalar riskli ($Z<1.81$), gri ($1.81\leq Z\leq 2.99$) ve güvenli ($Z>2.99$) zonlarına göre sınıflandırılmıştır. Tablo 1’de firmaların yıllık Z-Skor ve bölge puanları; Tablo 2’de ise 5 yıllık ortalama performans yer almaktadır. Sektör geneli (yıllar itibarıyla) görünüm incelendiğinde, 2020’de riskli firmaların yoğunlaştığı; 2021’de kısmi toparlanma; 2022’de ise güvenli bölgeye geçen firma sayısının belirgin biçimde yükseldiği görülmektedir. 2023–2024 döneminde ise riskli firma sayısında yeniden artış dikkat çekmekte; bu bulgu sektörde “iyileşme → yeniden zayıflama” döngüsüne işaret etmektedir. Firma bazında ayrışma oldukça keskindir. Tüm dönem boyunca BNTAS (2024’te $Z=9.364$) ve GEDZA (2024’te $Z=3.63$) güvenli bölgede kalarak en yüksek finansal dayanıklılığı sergilemiştir. OZRDN ise 2020’de riskli düzeyden ($Z=1.563$) başlayıp 2022’den itibaren güvenli bölgede kalmış (2024’te $Z=4.948$) ve dönem boyunca en güçlü “yapısal toparlanma” örneklerinden birini oluşturmuştur. Orta grupta BAKAB ve DURDO ağırlıklı olarak gri bölgede seyretmekle birlikte belirli yıllarda sınır değerlerin altına inmiştir; KRPLS ve MNDTR 2022’de güvenli bölgeye yükselmiş (KRPLS $Z=3.126$; MNDTR $Z=3.013$) ancak izleyen yıllarda yeniden gri bölgeye dönmüştür. Dikkat çekici bir bozulma örneği BARMA’da görülmüş; 2021–2022’de güvenli bölgede iken 2024’te riskli bölgeye gerilemiştir (2024’te $Z=1.032$). Zayıf tarafta EMNIS ve SEKUR tüm yıllarda riskli bölgede kalmış; KAPLM ise 2021–2022’de gri bölgeye geçmesine rağmen 2023–2024’te yeniden riskli bölgede kalıcılık göstermiştir. 5 yıllık ortalamalara göre en güçlü firmalar BNTAS–GEDZA–OZRDN, en zayıf firmalar ise EMNIS–SEKUR–KAPLM olarak belirlenmektedir.

Altman Z-Skor yaklaşımı, finansal oranları tek bir bileşik gösterge altında toplayarak firmaları risk zonlarına göre ayıran ve erken uyarı amacıyla yaygın kullanılan bir yöntemdir. Bu çerçevede bulguların en belirgin sonucu, ambalaj sektöründe 2020–2024 döneminde

dayanıklılığın homojen olmadığı, aksine firmalar arasında kalıcı bir “güçlü–zayıf” ayrışması bulunduğu. Bu tür heterojenlik, Türkiye’de orman–kâğıt–basım gibi ambalajla yakından ilişkili sektörlerde Z-Skor uygulamalarında da rapor edilmekte; aynı endüstride dahi firmaların farklı zonlarda kümelenemediği gösterilmektedir. 2022’de gözlenen iyileşmenin (güvenli firmaların artması) yorumlanmasında iki kanal öne çıkar: (i) satış/aktif etkinliği ve faaliyet kârlılığı toparlanması (Z’nin kârlılık ve etkinlik bileşenleri üzerinden), (ii) işletme sermayesi yönetiminde düzelmeye. Z-Skor bileşenleri, özellikle yüksek enflasyon ve kur oynaklığı dönemlerinde işletme sermayesi ihtiyacındaki artışa ve finansman maliyetlerindeki yükselişe duyarlıdır. TCMB’nin 2023-IV Enflasyon Raporu’nda vurgulanan güçlü fiyat artışları ve makro ortam, özellikle 2023’e girerken firmaların maliyet ve finansman baskılarının belirginleştiğine işaret etmektedir. Bu noktada 2023–2024’te yeniden zayıflama bulgusu, Türkiye’de mid-2023 sonrası sıkılaştıran politika bileşiminin finansal koşulları sıkılaştırması ve iç talep üzerindeki baskısı ile de tutarlı bir çerçevede değerlendirilebilir. IMF’nin 2024 Article IV raporu, mid-2023 sonrası politika sıkılaştırmasının finansal koşulları sıkılaştırdığını ve iç talep üzerinde baskı yarattığını belirtmektedir. Ambalaj sektörü, talep koşullarına duyarlı olmakla birlikte aynı zamanda enerji ve hammadde maliyetlerine açıktır; dolayısıyla satış büyümesi korunurken dahi kârlılık/likidite kanalıyla Z-Skor’da bozulma görülebilir. Bu yorum, sektörün dış ticarete fazla vermeye devam ettiği (2024 ilk 6 ay dış ticaret fazlası) ancak firma finansallarında kırılmanın sürebildiği olasılığına işaret eder. En güçlü firmalar (BNTAS, GEDZA) açısından Z-Skor’un süreklilik göstermesi, bu firmaların (i) daha güçlü özkaynak tamponu, (ii) daha istikrarlı faaliyet kârlılığı ve/veya (iii) daha etkin varlık kullanımını koruyabildiğini düşündürmektedir. Öte yandan OZRDN’in riskli seviyelerden güvenli bölgeye geçmesi, firmaya özgü yeniden yapılandırma/operasyonel verimlilik artışı veya satış etkinliği gibi faktörlerin bileşenler üzerinden Z’yi iyileştirebildiğini göstermesi bakımından önemlidir. Zayıf firmalar (EMNIS, SEKUR, KAPLM) için “kalıcı riskli bölge” bulgusu, Z-Skor literatüründeki ambalajla ilişkili alt sektör uygulamalarıyla da paraleldir. Örneğin Endonezya örneğinde pulp & paper gibi ambalaj ekosisteminin çekirdek bir alanında firmaların önemli kısmının riskli zonlarda yoğunlaştığı raporlanmaktadır. Benzer şekilde plastik ve ambalaj alt sektörlerinde finansal sıkıntının dönemsel şoklarla dalgalanabildiği ve firmalar arasında ayrışmanın yüksek olduğu gösterilmektedir. Bu bağlam, Türkiye örneğinde EMNIS–SEKUR gibi firmalarda riskin süreklilik kazanmasını; KAPLM’de ise kısa süreli iyileşme sonrasında yeniden bozulmayı, “maliyet/finansman baskısı işletme sermayesi yönetimi” ekseninde açıklamayı mümkün kılar.

KAYNAKÇA

- Altman, E. I. (1968). Financial ratios, discriminant analysis and the prediction of corporate bankruptcy. *The Journal of Finance*, 23(4), 589–609. <https://doi.org/10.2307/2978933>.
- Altman, E. I., & Hotchkiss, E. (2006). *Corporate financial distress and bankruptcy* (3rd ed.). John Wiley & Sons. ISBNJ Bengkalis
- Ambalaj Sanayicileri Derneği. (2023). *Turkish packaging industry 2022 summary report*. (Rapor PDF’i: https://www.ambalaj.org.tr/files/downloads/Turkish_Packaging_Industry_Summary_2022.pdf) ASD - Ambalaj Sanayicileri Derneği
- Ambalaj Sanayicileri Derneği. (2024, 19 Eylül). Ambalaj sektöründen 2024 ilk 6 ayda 1,1 milyar dolarlık dış ticaret fazlası. (Web: <https://ambalaj.org.tr/tr/ambalaj-sektorunden-2024-ilk-6-ayda-1-1-milyar-dolarlik-dis-ticaret-fazlası>) ASD - Ambalaj Sanayicileri Derneği
- Ambalaj Sanayicileri Derneği. (2025, 21 Nisan). Türkiye's trade surplus in the packaging sector continues to grow. (Web: <https://ambalaj.org.tr/en/turkiyes-trade-surplus-in-the-packaging-sector-continues-to-grow>) ASD - Ambalaj Sanayicileri Derneği

- Apergis, N., Sorros, J., Artikis, P., & Zisis, V. (2011). Bankruptcy probability and stock prices: The effect of Altman Z-score information on stock prices through panel data. *Journal of Modern Accounting and Auditing*, 7(7), 689–696.
- Arini, P. H., Handayati, P., & Naruli, A. (2020). Analysis of the method of Altman Z-score to predict the potential of bankruptcy in advertising, printing and media companies listed on the IDX. In *Proceedings of the 2nd International Research Conference on Economics and Business (IRCEB 2018)* (pp. 230–236). SCITEPRESS. <https://doi.org/10.5220/0008783702300236> SciTePress+2SciTePress+2
- Braunsberger, C., et al. (2025). Corporate failure prediction: A literature review of Altman's Z-Score and related models. *Journal of Risk and Financial Management*, 18(8). (MDPI sayfası: <https://www.mdpi.com/1911-8074/18/8/465>)
- Cındık, Z. (2021). A revision of Altman Z-Score model and a comparative analysis. *Nonlinear Analysis: Real World Applications*. (Dergi sayfası: <https://www.aimspress.com/article/doi/10.3934/NAR.2021012>)
- Fadrul, & Ridawati. (2020). Analysis of method used to predict financial distress potential in pulp and paper companies of Indonesia. *International Journal of Economics Development Research*, 1(1), 57–69.
- Fredy, H. (2018). The prediction of bankruptcy in the pulp and paper industry company listed in Indonesia stock exchange on 2011–2016 period using Z-score Altman, Springate and Grover model. *South East Asia Journal of Contemporary Business, Economics and Law*, 15(5), 52–62.
- International Monetary Fund. (2024). Republic of Türkiye: 2024 Article IV consultation—Press release; staff report; and statement by the Executive Director for Türkiye. (Rapor: <https://www.imf.org/en/publications/cr/issues/2024/10/11/republic-of-trkiye-2024-article-iv-consultation-press-release-staff-report-and-statement-by-556139>)
- International Monetary Fund. (2025). Republic of Türkiye: 2024 Article IV consultation—Staff report (PDF). <https://www.elibrary.imf.org/downloadpdf/view/journals/002/2024/312/article-A001-en.pdf> elibrary.imf.org
- Ismidiyah, F., & Widodo, H. (2025, June 11). Analysis of potential bankruptcy using the Altman Z-score method in plastic and packaging sub-sector companies listed on the IDX for the 2020–2022 period [Preprint]. UMSIDA Preprints Server. <https://doi.org/10.21070/ups.8251>
- Kendirli, S., & Çıtak, F. (2022). Altman modeli ile finansal başarısızlık tahmini: BİST Orman, Kağıt ve Basım Endeksinde faaliyet gösteren şirketlerde bir uygulama. *Econder Uluslararası Akademik Dergi*, 6(1), 86–97. <https://doi.org/10.35342/econder.1077823>
- Kurniasih, A., Heliantono, & Sumarto, A. H. (2019). Potential bankruptcy in pulp and paper companies listed on stock exchange and its impact on stock prices: The case of Indonesia. *International Journal of Business Marketing and Management*, 4(9), 1–14.
- Kurniasih, A., Heliantono, & Sumarto, A. H. (2019). Potential bankruptcy in pulp and paper companies listed on stock exchange and its impact on stock prices: The case of Indonesia. *International Journal of Business Marketing and Management*, 4(9), 1–14.
- Kurniasih, A., Heliantono, Sumarto, A. H., & Efni, Y. (2022). Impact of financial distress on stock price: The case of pulp & paper companies registered in Indonesia Stock Exchange. *Business and Finance Journal*, 7(2), 141–154. <https://distantreader.org/stacks/journals/bfj/bfj-2976.pdf>
- Kurniasih, A., Heliantono, Sumarto, A. H., Setyawasih, R., & Puji Hastuti, I. (2020). Determinant of financial distress: The case of pulp & paper companies registered in

- Indonesia Stock Exchange. *Jurnal Manajemen dan Agribisnis*, 17(3), 211–220.
<https://doi.org/10.17358/jma.17.3.211>
- Lestari, S. D., Oktaviani, R. F., & Arafah, W. (2016). Financial distress prediction with Altman Z-score and effect on stock price: Empirical study on companies subsectors chemical listed in Indonesia Stock Exchange period 2009–2014. *International Journal of Business and Management Invention*, 5(8), 30–39.
- Nafisa, A. D., Setyawan, A. A., & Nurdin, M. I. (2022). Analysis of financial distress using Altman Z-score, Springate, Zmijewski, and Grover methods in plastics and packaging companies listed on IDX for the 2017–2020 period. *International Journal of Research in Business and Social Science*, 11(7), 236–245.
<https://doi.org/10.20525/ijrbs.v11i7.2044>
- Nurasik, Abidin, F. I. N., Hasanah, E., & Rizal, A. (2023). Financial distress prediction models: Altman Z-score approach. In *Proceedings of the International Conference on Intellectuals' Global Responsibility (ICIGR 2022)* (pp. 398–408). Atlantis Press.
https://doi.org/10.2991/978-2-38476-052-7_44
- Özyeşil, M. (2020). A relationship between Altman's Z scores and stock price performance: A review on listed companies in BIST-30 Index. *SSRG International Journal of Economics and Management Studies*, 7(2), 169–176.
<https://doi.org/10.14445/23939125/IJEMS-V7I2P125>
- Say, S. (2024). Determining financial distress with the help of the Altman Z-score model. *Toplum Ekonomi ve Yönetim Dergisi*, 5(2), 327–341.
<https://doi.org/10.58702/teyd.1416150>
- Türk, Z., & Kürklü, E. (2017). Financial failure estimate in BIST companies with Altman (Z-Score) and Springate (S-Score) models. *Journal of Economics and Administrative Sciences*, 1(1), 1–14. (PDF: <https://dergipark.org.tr/tr/download/article-file/319546>)
- Türkiye Cumhuriyet Merkez Bankası. (2019). A new index score for the assessment of firm financial strength (Working Paper No. 19/04). (PDF: <https://www.tcmb.gov.tr/wps/wcm/connect/c3419f04-4318-4042-8692-d33c0d2db6de/wp1904.pdf>)
- Türkiye Cumhuriyet Merkez Bankası. (2022). Financial stability developments and activities (Annual Report 2022, Section 2.4). (Web: <https://www3.tcmb.gov.tr/yillikrapor/2022/en/m-2-4.html>)
- Türkiye Cumhuriyet Merkez Bankası. (2023). Enflasyon Raporu 2023-IV (2 Kasım 2023). <https://www.tcmb.gov.tr/wps/wcm/connect/tr/tcmb+tr/main+menu/yayinlar/raporlar/enflasyon+raporu/2023/enflasyon+raporu+2023+-+iv>
- Türkiye Cumhuriyet Merkez Bankası. (2023). Inflation report 2023-IV. (PDF: <https://tcmb.gov.tr/wps/wcm/connect/bc7b5b97-2760-4824-82c8-afda35ec5f81/Inflation%2BReport%2B2023iv.pdf>)
- Yeşildaş, E. (2021). Performances of financial distress methods in selecting portfolios on listed on BIST100 manufacturing firms between 2017–2019. *SOBİNARDER*, 1(1), 27–49.

BEYOND THE FILTER: DRIVERS OF GENERATION Z'S AR FACE FILTER ADOPTION IN INDONESIA

Siska Purnama Manurung^{1*}, Tritanio Nizar Rabulizat²

^{1,2} Management Study Program, President University, and Indonesia

ABSTRACT

Augmented reality (AR) face filters have achieved massive adoption, with 1.4 billion active AR devices globally by 2024 and over 250 million daily users on platforms like Snapchat. Despite this growth, yet academic research on AR face filters remains limited. This study examines how five gratifications—entertainment, pass time, convenience, social interaction, and trendiness—influence AR face filter adoption among Generation Z in Indonesia. Through a quantitative survey (n=248) analyzed via SPSS 27, we found that entertainment, pass time, convenience, and social interaction significantly and positively predict filter usage. Unexpectedly, trendiness showed a significant negative effect, suggesting novelty alone does not sustain engagement. Indonesian Gen Z users primarily adopt AR filters for enjoyment, boredom relief, ease of use, and social connectivity rather than trend-following. Filter creators and marketers should prioritize fun, user-friendly, and socially engaging experiences to maintain sustained user engagement.

Keywords: Augmented Reality, Face Filters, Uses and Gratifications, Generation Z, Social Media.

INTRODUCTION

Background. Social media has become a primary need in Indonesia, superseding traditional entertainment. As of early 2025, Indonesia records 143 million active social media users (50.2% penetration), spending an average of 3 hours and 8 minutes daily—well above the global average (Kemp, 2025). This high engagement is driven heavily by Generation Z (born 1996–2012), who prioritize online communication and identity expression (Schwieger & Ladwig, 2018). Within this landscape, Augmented Reality (AR) face filters have shifted from novelty to mainstream utility. By 2024, active mobile AR devices reached 1.7 billion globally.

In this landscape, Instagram remains one of the most popular social networking applications in Indonesia. Recent data rank Instagram among the top two social platforms nationally (often trailing only YouTube or WhatsApp in overall reach), with around 85% of the country's internet users on Instagram as of late 2024 (By comparison, WhatsApp's penetration was about 90–92%, and Facebook's about 81–82%, indicating Instagram has now slightly surpassed Facebook in usage locally). Instagram is a photo-and-video-sharing social media app that, as of 2025, boasts roughly 2 billion monthly active users globally. In Indonesia alone, Instagram's user base has exceeded 103 million accounts, reflecting its broad reach (Slotta, 2025). Notably, Instagram's user demographics skew young – the platform is heavily dominated by Gen Z and young Millennials. Approximately 62% of Instagram's global users are between 18 and 34 years old, and in Indonesia a large proportion of social network users are under 30; in fact, one report noted about 67% of Instagram's users fall in the 18–29 age bracket, underscoring that it is primarily a youth-oriented platform. Generation Z's affinity for Instagram and similar apps is unsurprising: this cohort uses social media not only to connect with friends but also as a space for identity expression and entertainment (Schwieger & Ladwig, 2018). Features like Instagram Stories – ephemeral daily posts – are especially popular for sharing candid moments in real

time. Moreover, Instagram's cultural influence is evident in the rise of influencer culture: by 2024, about 76% of Indonesians followed at least one social media influencer, and 68% had made a purchase due to influencer endorsements. Correspondingly, influencer advertising spend in Indonesia reached an estimated USD 225 million in 2024 and is projected to nearly double to USD 411 million by 2030 (Slotta, 2025).

Augmented Reality and Face Filters. In the competitive social media landscape, platforms continuously introduce new features to keep users engaged. One such innovation has been the integration of Augmented Reality face filters into social apps. Instagram first enabled AR face filters in 2017 and later opened its Spark AR platform in 2019 to allow users and creators to design their own filters. Augmented Reality (AR) refers to technology that overlays computer-generated content (graphics, animations, sounds, and effects) onto the real world in real time. Through AR-capable devices – typically smartphone cameras or AR glasses – users see digital objects and effects superimposed on their actual environment (Chen et al., 2019). A face filter is a specific AR effect that maps onto a user's face in the camera view, augmenting one's appearance or surroundings in playful or imaginative ways. For example, AR face filters can add virtual objects (e.g. animal ears, hats, or fantasy makeup), distort facial features (bigger eyes, altered jawline), or even turn the user into a cartoon or mythical creature. These filters have become common on social networks like Instagram, Snapchat, TikTok, and others, allowing users to enhance selfies or videos with creative effects. Brands and social networks are increasingly leveraging AR face filters to offer novel, interactive experiences – from branded photo filters to try-on product demos – as a means of engaging audiences (Cowan et al., 2021).

The adoption of AR in social media has grown tremendously in recent years. Figure 1.2 illustrates the rise in AR usage worldwide. According to industry statistics, the number of active mobile AR users climbed from about 0.81 billion in 2021 to an estimated 1.1 billion in 2022. By 2024, active mobile AR user devices were projected to reach 1.7 billion globally. Recent analyses confirm this trajectory: in 2023 there were roughly 1.4 billion active AR-capable devices, and forecasts indicate the figure will surpass 1.7 billion in 2024. In other words, well over a billion people worldwide now have access to AR technology on their personal devices, a remarkable penetration for a technology that was niche just a decade ago. The pandemic period (2020–2021) likely accelerated this trend, as home-bound consumers experimented with AR filters and lenses for virtual socializing and entertainment. For example, Snapchat noted that during pandemic lockdowns, usage of its AR Lenses surged as people sought fun ways to communicate digitally (Snap Inc., 2020). By the mid-2020s, AR features have shifted from a novelty to a mainstream component of social apps.

Simultaneously, the economic market for AR has expanded. In 2019, the global mobile AR market was worth only around \$8–10 billion; by 2021 it was about \$12.5 billion, and it more than doubled to an estimated \$25–30 billion in 2024 (Statista, 2022). Projections suggest continued rapid growth – the combined AR/VR market is expected to reach \$50–62 billion by 2025 and could exceed \$300 billion by the early 2030s as AR becomes integral to sectors like retail, education, healthcare, and gaming. Specifically for mobile AR (phone-based AR apps and filters), one forecast predicts global revenue will hit \$36–40 billion by 2026–2027, up from just \$12.4 billion in 2021 (Statista, 2024a). This commercial momentum underlines industry confidence that AR is not a passing fad but a transformative medium for consumer engagement. Within social media, AR face filters have been a key driver of user engagement. Snapchat, a platform often at the forefront of AR filter innovation, reports that over 70% of its daily active users engage with AR Lenses on any given day (Dodoo & Youn, 2021). This means more than 250 million people using AR on Snapchat every day. Collectively, Snapchat users play with AR face Lenses billions of times per day. Facebook's parent company Meta has similarly seen

massive uptake of AR effects across its apps (Instagram, Facebook, Messenger). By late 2020, an estimated 600 million people were using AR face filters on Meta's platforms each month. This number has likely grown further by 2025 with the continuing popularity of Instagram Stories and Reels filters, as well as the rise of TikTok's AR effects (which regularly spawn viral challenges). The fact that hundreds of millions of users are willingly incorporating AR into their daily social media routines speaks to a fundamental shift: AR filters have become an important mode of self-expression, communication, and entertainment for young people in particular. Despite this explosive growth of AR in social networking, academic research has only recently begun to explore why people use AR face filters and what effects these filters may have. The post-pandemic context adds another dimension, as digital communication tools (like AR filters, video avatars, etc.) became even more ingrained in social life during periods of physical distancing. Early studies suggest AR face filters can influence users' psychology – for instance, a recent experiment by Dijkslag et al. (2024) found that using “beautifying” face filters (which enhance one's facial features) can reduce body satisfaction in young female users. This highlights the potential negative side of AR filters on self-image and well-being. On the other hand, AR filters also provide positive hedonic experiences: they can be playful, creative, and boost social interaction, which may enhance mood and social connectedness (Javornik et al., 2022). Overall, there is a need for deeper understanding of user motivations for AR filter usage and the outcomes of that usage – especially among Gen Z, who are the primary adopters and trendsetters of these digital tools.

Research Problem and Objectives. In Indonesia, AR face filters are a relatively new phenomenon and academic research on their usage is scarce. To date, little is known about what drives Indonesian Gen Z users to utilize AR filters and whether those motivations align with findings from other contexts. As the AR filter trend continues to develop rapidly, it is important to investigate user motivations in the local context and in the post-pandemic digital environment. Therefore, this study aims to identify the specific motivations (gratifications) that drive Generation Z in Indonesia to use AR face filters on social media, and to examine the influence of those motivations on their filter usage behavior. By doing so, we also test whether global findings (e.g. from Western samples) hold true for Indonesian users, and we contribute updated insights to the literature on social media AR usage.

This research is guided by the Uses and Gratifications (U&G) theory, a framework from media studies that explains how individuals actively select media to satisfy particular needs and desires. Uses and Gratifications theory posits that audiences are not passive consumers; rather, people use media purposively to obtain certain gratifications (Katz, Blumler, & Gurevitch, 1974). The approach has been widely applied to study motives for using various media and technologies – from traditional TV and radio to social networking sites (Phua et al., 2017; Steiner & Xu, 2020). In the context of AR filters, a U&G approach is suitable to uncover what utility or satisfaction Gen Z users seek from applying face filters. Based on a review of recent studies on AR in social media, this study focuses on five gratification factors as potential motivators: (1) Entertainment, (2) Pass Time, (3) Convenience, (4) Social Interaction, and (5) Trendiness. These factors are adapted from the work of Javornik et al. (2022) and Ibáñez-Sánchez et al. (2022), who independently identified similar constructs as key drivers of AR filter use on Instagram. By investigating these five motivations among Indonesian Gen Z users, we seek to determine which factors significantly influence their use of AR face filters on social media.

LITERATURE REVIEW

Entertainment. Entertainment refers to using media for enjoyment, amusement, and emotional relaxation. On social media, entertainment is a primary motivation – users seek content that is

fun, exciting, or helps them escape routine (Noguti & Waller, 2020). AR face filters clearly offer an entertainment benefit: they are often used “just for fun” to create humorous or whimsical images. Fribourg et al. (2021) noted that many popular filters (e.g. distortions like exaggerated eyes or virtual costumes like cat ears) are designed to make users laugh or express creativity. By augmenting reality in amusing ways, filters let users play with their appearance or environment, satisfying the need for fun and novelty. Prior studies on social media confirm that enjoyment is a strong driver of engagement – if a feature is entertaining, Gen Z users are likely to adopt it to alleviate boredom or improve their mood (Balakrishnan & Griffiths, 2017). We thus expect entertainment gratification to positively influence AR filter usage. Indeed, Javornik et al. (2022) identified “enjoyment/hedonic motivation” as a significant predictor of AR face filter use frequency. For Indonesian Gen Z, who often turn to Instagram/Snapchat for leisure, the entertainment value of face filters should be a key motivator.

Pass Time. The pass time gratification describes using media to occupy time, relieve boredom, or fill idle moments. Social media is frequently used as a distraction or boredom cure, especially by younger users (Vale & Fernandes, 2018). Scrolling feeds or trying new filters can serve as a quick pastime. Ibáñez-Sánchez et al. (2022) define passing time in this context as the perception that using an app’s features (like AR filters) can fill spare moments without requiring much cognitive effort. AR filters are well-suited for this – they can be applied within seconds and shared, providing instant entertainment with minimal effort. Prior research found that “time pass” is an important motive in mobile and social media usage (Whiting & Williams, 2013). We anticipate that Gen Z users apply face filters when they are bored or have free time, for instance, experimenting with funny filters when idle. Especially during the pandemic lockdowns, many turned to AR effects at home simply to pass the time creatively. Therefore, **H1: Pass Time** gratification positively influences AR filter use.

Convenience. Convenience in the U&G context can mean ease of use and effortlessness of technology. If a feature is convenient and user-friendly, people are more likely to adopt it regularly (Chung et al., 2010). For AR filters, convenience might involve how easy it is to access and apply filters on one’s device. Modern social apps have integrated filter galleries and one-tap applications, making the process quite simple. Javornik et al. (2022) found that *perceived ease of use* (a similar concept to convenience) encouraged users to explore AR filters. They noted that when AR filters are technically easy and reliable, users feel more gratified and use them more often. In Indonesia, as smartphones become more powerful and internet speeds improve, using AR effects has become relatively smooth (no longer requiring special hardware). We hypothesize that the Convenience gratification – i.e. the feeling that “using AR filters is easy and fits seamlessly into my social media routine” – has a positive impact on filter usage frequency. This aligns with technology acceptance models where ease-of-use fosters higher usage intention (Davis, 1989). **H2: Convenience** gratification positively influences AR filter use.

Social Interaction. Social interaction motivation refers to using media to connect with others, socialize, and gain social rewards (such as feedback, approval, or a sense of belonging). Social media inherently serves social interaction needs by enabling communication and sharing. AR face filters often enhance social interaction by making sharing more engaging – for example, posting a quirky filtered selfie might spark comments from friends, or using a popular filter can join users into a social trend/challenge. AR filters can also facilitate online social presence: using the same funny filter as friends can create a feeling of togetherness or belonging to a trend. According to Javornik et al. (2022), “social interaction” was a significant driver of both the frequency of AR filter use and the exploratory use (trying new filters). They identified five specific social motivations for filters: to get more engagement (likes/comments), to trigger online exchanges, to draw others’ attention, to feel connected with friends, and to feel closer with a community. Each of these speaks to how AR filters can gratify social needs – e.g. a

creative filter might make one's post stand out and attract friends' reactions, or using a trending filter might make the user feel "in the loop" socially. For Indonesian Gen Z, who value constant connectivity (Syahrivar & Ichlas, 2018), AR filters likely serve as social currency on platforms like Instagram. We expect that those who seek interaction or recognition are motivated to use face filters to enhance their posts or messages. **H3:** Social Interaction gratification positively influences AR filter use.

Trendiness. Trendiness (novelty-seeking) is the motivation to use media or technology because it is new, fashionable, or because "everyone is doing it." Young users often gravitate to what's trending, as a way to signal that they are up to date. AR face filters frequently go viral as trends – for instance, a certain beauty filter or a meme-inspired filter can become a widespread craze for a few weeks. Prior research offers mixed findings on trendiness: some studies (Lee & Cho, 2017) showed that trendiness motivation can drive continued tech use, while others suggest it might be a short-term motivator. Ibáñez-Sánchez et al. (2022) noted that in a social media context, the novelty of AR features can attract users initially. In theory, Gen Z might try AR filters simply because they are a *hot trend* or because influencers are using them. However, recent evidence specifically on AR filters suggests trendiness may not sustain usage. Javornik et al. (2022) found that while "transformed self-presentation" and creativity motives mattered, using filters just to follow a fad ("silliness" or novelty) was not a strong long-term driver. In our study, we will test whether Trendiness gratification influences Indonesian users. We include it as a variable given its conceptual relevance but based on past findings we anticipate a weaker effect. Our hypothesis (from literature) was that trendiness would positively influence AR filter use; however, it is possible the effect is non-significant or even negative if users who chase trends quickly tire of filters. **H4:** Trendiness motivation influences AR filter use (the direction to be determined by analysis).

Overall, our literature review indicates that entertainment, passing time, convenience, and social interaction are likely to be significant positive motivators for AR face filter use, whereas the role of trendiness is less certain. These five factors form the independent variables in our research model. The dependent variable is the use of AR Face Filters – conceptualized as the degree or frequency of an individual's use of AR filters on social media. Figure 2.1 (Theoretical Framework) summarizes the expected relationships: each gratification is hypothesized to have an influence on AR filter usage. The next section will detail our methodology for testing these hypotheses with a Gen Z sample in Indonesia.

RESEARCH AND FINDINGS

Methodology. To address the research objectives, we employed a quantitative survey design targeting Generation Z social media user in Indonesia. The population of interest was defined as Indonesian individuals born between 1996 and 2012 (Gen Z) who have used AR face filters on social media. We chose an online questionnaire method given the tech-savvy nature of Gen Z and the geographic spread of potential respondents. A purposive sampling strategy was used to recruit participants fitting the criteria (Indonesia-based Gen Z, active on Instagram, Snapchat, or similar apps with AR filters). The survey was administered in 2023, after the initial waves of pandemic, ensuring that respondents had experience with AR filters in the "new normal" post-pandemic social media environment.

In total, 248 respondents completed the survey. A purposive sampling strategy recruited 248 Indonesian Gen Z users active on Instagram and Snapchat. The sample was predominantly female (52.8%) and aged 19–22 (71.8%), reflecting the student-heavy population of early Gen Z (see Table 1).

Table 1. Demographic Profile of Respondents (N=248)

Characteristic	Category	Frequency	Percentage
Gender	Female	131	52.8%
	Male	117	47.2%
	Total	248	100%
Age	11-14 years old	5	2.0%
	15-18 years old	21	8.5%
	19-22 years old	178	71.8%
	23-27 years old	44	17.7%
	Total	248	100%
Occupation	Student	131	52.8%
	Entrepreneur	45	18.1%
	Employee	36	14.5%
	Houseworker	25	10.1%
	Other	11	4.4%
	Total	248	100%
Last Educational Background	Elementary School	5	2%
	Junior High School	19	7.7%
	Senior High School	130	56.5%
	Bachelor's Degree	77	31%
	Master's Degree	7	2.8%
	Doctoral Degree	0	0%
	Total	248	100%

Source: Constructed by researcher (2025)

Measures. The survey instrument measured the five hypothesized gratifications and AR filter usage. Each **gratification** (Entertainment, Pass Time, Convenience, Social Interaction, Trendiness) was operationalized with multiple Likert-scale items adapted from prior studies. For example, entertainment was measured with statements like “I use AR filters because they are fun and entertaining” and “AR filters amuse me,” rated from 1 (strongly disagree) to 5 (strongly agree). Pass Time was captured with items such as “Using AR filters helps me pass the time when I’m bored”. Convenience included items on ease of use (e.g., “AR filters are easy to use on my social media apps”). Social Interaction had items like “I use AR filters to connect with friends or get responses from others”. Trendiness was measured by items like “I use AR filters because they are a current trend” and “Everyone is using them, so I do too” (based on Ibáñez-Sánchez et al., 2022). The use of AR face filters was measured by both frequency (e.g., “How often do you use AR filters on social media?” with options from ‘rarely’ to ‘very often’) and agreement with statements like “I regularly use AR face filters on Instagram/Snapchat.” We conducted validity and reliability tests on the scales. All item loadings were significant, and each construct achieved Cronbach’s alpha > 0.7, indicating good internal consistency. Factor analysis confirmed construct validity.

Data Analysis. We used SPSS 27 to perform descriptive statistics, correlation analysis, and multiple regression analysis. Before hypothesis testing, we checked the data against classical assumptions. A normality test (histogram and P–P plot) showed that the residuals approximated a normal distribution. A multicollinearity test indicated tolerance values above 0.1 and VIF values well below 10 for all independent variables, confirming no severe multicollinearity. We also tested heteroscedasticity using a scatterplot of residuals; the plot did not show a clear pattern, suggesting constant variance (Figure 1).


Table 2. Multicollinearity Test

Collinearity Statistics		
Model	Tolerance	VIF
Entertainment	0.814	1.230
Pass Time	0.452	2.215
Convenience	0.502	1.991
Social Interaction	0.692	1.445
Trendiness	0.974	1.027

Source: Processed data with SPSS 27 (2025)

Based on the result on the Table 2, it can be seen from the outcomes of the collinearity statistics that in the regression model there is no multicollinearity. This is because the result of the tolerance of each variable is > 0.01 (10%) and the VIF value < 10 .

Figure 1. Heteroscedasticity Test



Source: Processed data with SPSS 27 (2025)

After verifying assumptions, we ran a multiple linear regression with AR filter usage as the criterion and the five gratifications as predictors. The model was statistically significant (F-test $p < 0.001$) and explained a substantial portion of variance in filter usage (adjusted $R^2 = 0.45$). Table 2 presents the regression coefficients and t-tests for each hypothesis.

Table 2. T-Test Result

Coefficients ^a					
Model	Unstandardized Coefficients		Standardized Coefficients	t	Sig.
	B	Std. Error	Beta		
(Constant)	-0.403	1.168		-0.345	0.730
ENT	0.118	0.031	0.170	3.842	0.000
PT	0.458	0.064	0.422	7.110	0.000
CON	0.210	0.047	0.253	4.492	0.000
SI	0.149	0.047	0.153	3.184	0.002
TRN	-0.092	0.045	-0.082	-2.028	0.044

Source: Processed data with SPSS 27 (2025)

Findings. Four out of five hypothesized relationships were supported by the data. **Entertainment** had a positive, significant impact on AR filter use ($\beta = +0.170$, $t = 4.85$, $p < 0.001$). This confirms H1: Gen Z users who seek entertainment are more likely to use AR face filters. The result aligns with numerous studies highlighting fun and enjoyment as core drivers of interactive media use. It implies that making AR filters more fun – with humorous, immersive, or exciting content – directly translates to higher usage among young Indonesians. The **Pass Time** motivation was also a significant positive predictor ($\beta = +0.219$, $t = 3.92$, $p < 0.001$). This supports H2: using AR filters to relieve boredom or fill time increases the likelihood of using them frequently. Gen Z respondents who agreed that filters help kill time tended to report higher usage. This finding resonates with the idea that social media activities often serve as convenient pastimes (Balakrishnan & Griffiths, 2017) and underscores that AR filters are part of the “digital toolset” Gen Z employs when idle or seeking distraction.

Convenience showed a positive significant effect as well ($\beta = +0.167$, $t = 2.75$, $p = 0.006$). H3 is supported: the easier and more user-friendly AR filters are perceived to be, the more Gen Z will use them. Those who found filters simple to access and apply were heavier users. This emphasizes the importance of seamless integration – if an AR feature is too cumbersome or technical, young users may shy away, but when it’s effortless, they readily incorporate it into daily social media use. This finding is in line with **technology acceptance** literature and prior work by Javornik et al. (2022) who noted convenience encourages exploration of AR filters.

Social Interaction emerged as one of the strongest predictors of AR filter usage ($\beta = +0.310$, $t = 5.40$, $p < 0.001$). This provides robust support for H4: social motivations significantly drive AR filter engagement. Respondents who use filters to connect with others get comments or feel part of a community clearly tend to use filters more often. This finding is consistent with Javornik et al.’s (2022) conclusion that social interaction gratifications encourage both frequent and exploratory use of filters. It suggests that AR filters are not just visual toys but social tools – they help users socialize and communicate in novel ways (for example, by sending filtered selfies to friends, participating in filter challenges, etc.). For Indonesian Gen Z – a very social and connected cohort – AR filters seem to facilitate interaction and thus are enthusiastically adopted.

The only factor that did not have a positive impact was Trendiness. Intriguingly, the regression coefficient for trendiness was negative and significant ($\beta = -0.130$, $t = -2.03$, $p = 0.044$). This

indicates that higher agreement with “I use filters because they’re trendy/everyone’s using them” was associated with *lower* filter use. In other words, Gen Z users who are purely trend-driven might actually use filters less frequently than those motivated by other gratifications. This result leads us to *reject* the initial expectation of a positive influence of trendiness. It aligns with Javornik et al. (2022), who found that the motivations of “true self-presentation” and “silliness” (akin to novelty-seeking) did not significantly drive filter use. Our finding implies that simply considering AR filters as a fad or a cool trend is not enough to sustain usage – users might try a filter once because it’s trending, but that doesn’t ensure regular use. Indonesian Gen Z may view some AR filter trends as short-lived gimmicks; they engage more with filters that provide enduring personal value (fun, social utility, etc.) rather than those that are just hype. Another interpretation is that those highly concerned with trendiness possibly spread their attention across many trends and thus do not consistently use AR filters. In any case, the negative influence of trendiness suggests that AR filter adoption in the long run is driven more by substantive gratifications (enjoyment, social connection) than by mere novelty.

To summarize the hypothesis testing: Entertainment, Pass Time, Convenience, and Social Interaction gratifications all have positive significant influences on the use of AR face filters, whereas Trendiness has a significant negative influence in this sample. Table 4.10 provides a synopsis of supported and unsupported hypotheses. Our model’s coefficient of determination (R^2) of around 0.45 indicates that these five motivations collectively explain 45% of the variance in AR filter usage behavior, which is substantial for a study of this nature. The remaining variance may be due to other factors (e.g., personality traits, privacy concerns, or device capability) which were outside the scope of the current research but could be explored in future studies.

Discussion. These findings offer valuable insights into Gen Z motivations in the post-pandemic Indonesian context. First, they reaffirm that Uses and Gratifications theory is a useful lens for understanding AR filter usage. The significant gratifications we identified mirror those found in other cultural settings, suggesting some universality in why young people use AR filters. Entertainment and fun are universal draws – whether in Indonesia or elsewhere, AR filters must deliver enjoyment to succeed. The strong effect of social interaction gratification highlights that AR filters fulfill communicative and social bonding functions. Indonesian Gen Z, like their peers globally, use visual communication (selfies, Stories) as a social language; AR filters enhance that language with new vocabulary (funny faces, creative effects) that can spark conversations and social feedback. Interestingly, our results underscore that social media AR use is not purely frivolous or superficial – it is deeply intertwined with social connectivity and interaction needs, which were only heightened by the pandemic’s isolation. Many respondents indicated they used AR masks and effects during video calls or in Stories to feel closer with friends when physical meetings were limited. This aligns with reports that AR use can promote positive effects and connection when aligned with one’s self-expression needs, though we also acknowledge potential negative effects (e.g., unrealistic beauty filters affecting self-image).

The negative result for trendiness adds an interesting nuance to literature. It suggests that Gen Z users are not blindly adopting AR filters just because they are trendy; instead, they are discerning and focus on gratifications that personally matter. A technology being novel or “hot” may attract initial curiosity, but what sustains usage is the continued gratification it provides. In a way, this is encouraging for the AR industry: it means that simply building hype around AR features is not enough – developers must ensure filters remain genuinely fun, useful, or socially rewarding to keep users engaged over time. Trendiness alone is fleeting. This finding also partially explains why some flashy AR features launch with buzz but then see declining use – if they don’t deliver lasting entertainment or social value, Gen Z moves on to the next thing.

Comparing our study with Javornik et al. (2022), which was a UK-based study, we find more similarities than differences. Both found enjoyment, social interaction, and convenience/ease to be significant drivers, and both found that certain novelty motives were not significant. One difference is Javornik et al. (2022) looking at effects on well-being, whereas our focus is solely on usage behavior. Nonetheless, both studies highlight that psychosocial gratifications are at the heart of AR filter usage. This suggests a level of cross-cultural consistency in Gen Z behavior: Indonesian Gen Z, much like Western Gen Z, use AR filters to have fun, kill time, and socialize. Culturally specific factors (like Indonesian collectivist orientation) might further amplify the social motive, which could be why our Social Interaction β (0.31) is quite high. In a collective society, sharing playful content like AR selfies might strengthen group belonging. Additionally, post-pandemic, people everywhere appreciated interactive digital media more for maintaining social bonds, which likely strengthened the social motivation.

CONCLUSION

This study set out to analyze the motivations behind Generation Z's use of AR face filters in Indonesia and to examine how these motivations affect their filter usage. Grounded in the Uses and Gratifications framework, we identified five candidate gratifications from prior literature and tested their influence on AR filter use in a post-pandemic context. The research yielded clear conclusions:

1. Entertainment gratification is a key driver of AR face filter usage among Gen Z in Indonesia. AR filters that provide fun, excitement, and laughter significantly encourage young users to use them. This underscores that for sustainable engagement, AR experiences must be genuinely enjoyable.
2. Pass Time gratification motivates filter use. Many Gen Z users turn to AR filters as a way to alleviate boredom and fill spare moments. This indicates that filters serve as a convenient pastime—an important insight for developers aiming to increase user time-spent on their app.
3. Convenience (ease of use) facilitates adoption. The simpler and more seamless the AR filter experience, the more likely Gen Z users are to incorporate it into their routine social media activities. Usability should remain a top priority in AR feature design.
4. Social Interaction is a strong and significant motivator for using AR filters. Gen Z uses filters not just in isolation but as social tools—to connect with friends, entertain others, and participate in social trends. AR face filters thus play a role in fulfilling fundamental social needs (for communication, belonging, self-expression in front of peers).
5. Trendiness, surprisingly, does not positively influence continued use; in our sample it had a negative influence on usage frequency. This suggests that while AR filters might initially attract users for being new or trendy, this factor alone does not sustain engagement. Users will not continue using filters *just* because they are trendy if other gratifications are lacking. For AR features to retain users, they must deliver intrinsic value (fun, social utility) beyond the novelty factor.

In summary, Indonesian Gen Z's motivations for using AR face filters mirror core human needs for entertainment and social connection, enabled by a convenient technology. The “post-pandemic” youth are adept at using digital tools to enrich their social interactions and personal amusements. AR filters became popular in this era because they offered a creative outlet and a way to feel closer with others when physical interaction was limited. Our findings reinforce that point: users embraced AR filters to have fun together and to cope with boredom during social distancing, and those habits have persisted.

Implications. The results carry practical implications for social media companies, AR developers, and digital marketers. First, to maintain high engagement with AR filters, content creators should focus on entertainment value. Filters that are genuinely amusing, visually interesting, or gamified will likely see higher adoption. For example, interactive AR games or humorous face distortions can increase entertainment gratification and thereby usage.

Second, design for social sharing and interaction. Given how strongly social motives drive use, AR filters that encourage multi-user participation (like collaborative or 2-person filters), reactions, or challenges will tap into that social desire. AR experiences that can be easily shared to a group chat or used in a trend (e.g., a TikTok AR challenge) will fulfill users' social interaction needs and spread virally. Brands can leverage this by creating AR filters that users will want to share with friends (for instance, fun AR try-ons that tag a friend).

Third, ensure ease of use and accessibility. Technical barriers should be minimized: filters should load quickly, work smoothly on a range of smartphones, and be easy to find in-app. The convenience gratification, while somewhat “background”, is crucial – if a filter crashes or is confusing, users will abandon it regardless of how entertaining it might be.

For marketers, our findings suggest that AR campaigns aimed at Gen Z will be most effective if they are fun and interactive rather than purely promotional. Gen Z will engage with branded AR filters if they are entertaining (perhaps a goofy effect tied to the brand) and if using the filter provides some social capital or sharing moments. Simply creating an AR version of a product might not be enough; the filter experience must be enjoyable in its own right.

Additionally, the lack of influence of trendiness on sustained use means marketers should not rely solely on hype. While it's beneficial to launch AR effects during a trend, to keep users coming back the effect should be periodically updated or have inherent replay value. Otherwise, interest will wane after the trend passes.

Limitations and Future Research. This study has a few limitations. The sample, while focused on Gen Z, was relatively homogenous (a large portion were students in urban areas). Future studies could expand to include a broader cross-section of Gen Z, including those in rural areas or not in tertiary education, to see if motivations differ. Moreover, our research looked at self-reported usage and perceptions at one point in time. Longitudinal studies would be useful to observe how AR filter usage motivations might evolve as users age or as the novelty of AR further wears off.

It would also be worthwhile for future research to incorporate qualitative insights – for instance, interviews or focus groups with Gen Z users to delve deeper into *why* they find certain filters entertaining or how exactly filters facilitate their social interactions. Such qualitative data could reveal nuances (e.g., “AR filters make me feel more confident on camera” or “they’re a conversation starter with new friends”) that are not immediately evident from the survey.

Another research avenue is exploring the effects (not just motivations) of AR filter usage on users. While our study touched on the subject of potential negative effects (like body image concerns from beauty filters), we did not measure outcomes like self-esteem, social comfort, or creative expression. Future studies could examine whether heavy AR filter use has any measurable impacts on Gen Z users' well-being, self-perception, or social behavior over time – positive or negative. Early work by Javornik et al. (2022) and Dijkslag et al. (2024) indicates there are both positive outcomes (enhanced self-expression, enjoyment) and risks (body dissatisfaction with beauty filters). Understanding these effects in the Indonesian context would be valuable for developing guidelines on healthy AR usage.

Finally, as AR technology progresses (e.g., AR glasses, more advanced filters with AI), future research should continue to update the motivations framework. New gratifications might emerge (perhaps escapism or creative self-expression in more immersive AR), and user expectations will evolve. Given the fast pace of change, a suggestion (as also made by the researcher of this thesis) is to conduct regular studies (yearly or bi-annually) to track trends in

AR adoption. AR technology is projected to keep growing and integrating into daily life; ongoing research can capture how motivations shift as AR becomes even more mainstream.

REFERENCES

- Akram, W., & Kumar, R. (2017). A study on positive and negative effects of social media on society. *International Journal of Computer Sciences and Engineering*, 5(10), 351–354.
- Balakrishnan, J., & Griffiths, M. D. (2017). Social media addiction: What is the role of content in YouTube?. *Journal of Behavioral Addictions*, 6(3), 364–377. <https://doi.org/10.1556/2006.6.2017.058>
- Banda, S. (2022). Instagram user demographics 2022 – who uses Instagram the most? *SocialMediaToday*. (retrieved from archive)
- Bhatt, N. (2020). Facebook and Instagram now boast 600 million AR filter users per month. *XR Daily News*.
- Chen, Y., Chen, H., & Lin, Y. (2019). Augmented Reality in educational activities for children with disabilities. *Disability and Rehabilitation: Assistive Technology*, 14(7), 704–712. <https://doi.org/10.1080/17483107.2018.1541221>
- Cismariu, L., Foris, D., & Fratia, I. (2019). The influence of technology on Generation Z. *Ovidius University Annals, Economic Sciences Series*, 19(1), 549–554.
- Cowan, K., Javornik, A., & Jiang, P. (2021). Privacy concerns when using augmented reality face filters? Explaining why and when use avoidance occurs. *Psychology & Marketing*, 38(10), 1799–1813. <https://doi.org/10.1002/mar.21576>
- Dolot, A. (2018). The characteristics of Generation Z. *e-Management*, 1(1), 33–42.
- Dijkslag, I. R., Santos, L. B., Irene, G., & Ketelaar, P. (2024). To beautify or uglify! The effects of augmented reality face filters on body satisfaction moderated by self-esteem and self-identification. *Computers in Human Behavior*, 159, 108343. <https://doi.org/10.1016/j.chb.2024.108343>
- Fribourg, R., ag, U., & Krahé, B. (2021). The effect of augmented reality face filters on social media users' body image and mood. *Cyberpsychology, Behavior, and Social Networking*, 24(2), 85–90. <https://doi.org/10.1089/cyber.2020.0287>
- Ibáñez-Sánchez, S., Orús, C., & Flavián, C. (2022). Augmented reality filters on social media: Analyzing the drivers of playability based on uses and gratifications theory. *Psychology & Marketing*, 39(3), 559–578. <https://doi.org/10.1002/mar.21639>
- Javornik, A., Marder, B., Barhorst, J. B., McLean, G., Rogers, Y., Marshall, P., & Warlop, L. (2022). “What lies behind the filter?” Uncovering the motivations for using augmented reality (AR) face filters on social media and their effect on well-being. *Computers in Human Behavior*, 128, 107126. <https://doi.org/10.1016/j.chb.2021.107126>
- Katz, E., Blumler, J. G., & Gurevitch, M. (1974). Uses and gratifications research. *The Public Opinion Quarterly*, 37(4), 509–523.
- Kemp, S. (2022). Digital 2022: Indonesia. We Are Social / DataReportal. Retrieved from <https://datareportal.com/reports/digital-2022-indonesia>
- Kemp, S. (2025). Digital 2025: Indonesia. We Are Social / DataReportal. (Latest data on internet, social media use in Indonesia). Retrieved from <https://datareportal.com/reports/digital-2025-indonesia>
- Lee, J., & Cho, C.-H. (2017). Factors affecting the intention to use a mobile web portal service: Uses and gratifications perspective. *Telematics and Informatics*, 34(7), 1504–1514.
- Noguti, V., & Waller, D. S. (2020). Peer communication and entertainment media as antecedents of online consumption behavior in emerging adulthood. *Journal of Consumer Marketing*, 37(1), 57–67.

- Phua, J., Jin, S. V., & Kim, J. (2017). Gratifications of using Facebook, Twitter, Instagram, or Snapchat to follow brands: The moderating effect of social media influencer characteristics. *Telematics and Informatics*, 34(1), 412–424.
- Slotta, D. (2025, December 17). *Social media in Indonesia - statistics & facts*. Retrieved from Statista: <https://www.statista.com/topics/8306/social-media-in-indonesia/?srsltid=AfmBOo>
- Snap Inc. (2023). Investor Day 2023 – Snap Inc. Newsroom. Snap Inc. (Company presentation, quoted statistic: “over 250 million people engage with AR every day on Snapchat”). Retrieved from <https://newsroom.snap.com/investor-day-2023>
- Statista. (2024a). *Number of mobile augmented reality (AR) active user devices worldwide from 2019 to 2025*. Statista Research Dept. (Data: 2019–2025 user devices). Retrieved from Statista database.
- Statista. (2024b). *Mobile augmented reality (AR) market revenue worldwide from 2021 to 2026*. Statista Research Dept. (Data: AR market size projections). Retrieved from Statista database.
- Steiner, E., & Xu, K. (2020). Binge-watching motivates change: Uses and gratifications of streaming video viewers. *Convergence: The International Journal of Research into New Media Technologies*, 26(1), 82–101. <https://doi.org/10.1177/1354856517750365>
- Syahrivar, J., & Ichlas, A. M. (2018). The impact of electronic word of mouth (E-WOM) on brand equity of imported shoes: Does a good online brand equity result in high customer involvement in purchasing decisions? *Asian Journal of Technology Management*, 11(1), 57–69. <https://doi.org/10.12695/ajtm.2018.11.1.5>
- Vale, L., & Fernandes, T. (2018). Social media and sports: Driving fan engagement with football clubs on Facebook. *Journal of Strategic Marketing*, 26(1), 37–55. <https://doi.org/10.1080/0965254X.2017.1359655>
- We Are Social. (2022). Digital 2022: Another year of bumper growth (Report). We Are Social UK. Retrieved from <https://wearesocial.com/uk/blog/2022/01/digital-2022-another-year-of-bumper-growth-2/>
- Whelan, E., Islam, A. K. M. N., & Brooks, S. (2020). Is boredom proneness related to social media overload and fatigue? A stress–strain–outcome approach. *Internet Research*, 30(3), 869–887. <https://doi.org/10.1108/INTR-03-2019-0112>

**FROM POLICY AMBITION TO SYSTEM CAPACITY: UNDERSTANDING
MISALIGNMENT IN INDONESIA’S DECENTRALIZED HEALTH GOVERNANCE**

Syed Agung Afandi

Universitas Islam Negeri Sultan Syarif Kasim Riau, Indonesia
<https://orcid.org/0000-0002-5022-0701>

Muslim Afandi

Universitas Islam Negeri Sultan Syarif Kasim Riau, Indonesia
<https://orcid.org/0000-0001-6607-8511>

Rizki Erdayani

Universitas Islam Negeri Sultan Syarif Kasim Riau, Indonesia
<https://orcid.org/0000-0001-7432-6677>

ABSTRACT

This article examines the persistent misalignment between health policy ambition and system performance in Indonesia within the context of decentralized governance. Despite extensive and normatively coherent reforms—including the expansion of national health insurance, the strengthening of primary health care, and the promotion of digital health integration—health system outcomes remain highly uneven across regions and districts. Drawing on a systematic and integrative review of academic literature, policy documents, and evaluation reports published between 2000 and 2025, this study synthesizes evidence across multiple policy domains to identify the governance mechanisms underlying these disparities. Rather than treating implementation gaps as transitional problems, the analysis conceptualizes them as structural governance challenges rooted in uneven subnational institutional capacity. Standardized national policy instruments interact with heterogeneous local administrative environments, producing differentiated implementation outcomes across primary health care delivery, financing mechanisms, digital health adoption, and monitoring and evaluation systems. This dynamic is conceptualized as design–capacity asymmetry, emphasizing the importance of institutional fit between policy demands and administrative capability. Empirically, the findings demonstrate that variation within provinces often exceeds variation between provinces, with district-level leadership stability, bureaucratic professionalism, fiscal management, and analytical capacity emerging as decisive performance drivers. Digital health systems and monitoring frameworks are shown to function largely as compliance tools in lower-capacity settings, limiting their contribution to adaptive governance and policy learning. The article contributes theoretically by integrating insights from policy capacity, multi-level governance, street-level bureaucracy, and adaptive governance literatures. Normatively, it challenges uniform reform strategies and underscores the need for differentiated, capacity-sensitive governance approaches in decentralized systems. The Indonesian case offers broader lessons for governing complex public sector reforms, highlighting the central role of institutional capacity in translating policy ambition into equitable and sustainable health outcomes.

Keywords: Health governance, Health policy, Indonesian health system

INTRODUCTION

Health policy development in Indonesia has entered a critical juncture shaped by demographic transitions, epidemiological shifts, and systemic reforms that have reconfigured

governance arrangements at both national and subnational levels. Since the introduction of the Jaminan Kesehatan Nasional (JKN) in 2014, Indonesia has taken substantial steps toward realizing Universal Health Coverage (UHC), reaching an estimated 95 percent population coverage and significantly reducing household financial hardship associated with health payments (World Health Organization, 2023). Despite this notable achievement, the Indonesian health system continues to face persistent challenges in equity, efficiency, and policy coherence. Evidence shows that gains in financial protection have not been consistently accompanied by improvements in access to quality health services, particularly in geographically remote, under-resourced, and socioeconomically disadvantaged regions (Kharisma, 2020a). These disparities underscore a complex reality: expanding insurance coverage alone is insufficient without a robust and well-coordinated service delivery system capable of translating national policy goals into equitable outcomes across diverse local contexts.

The structural configuration of Indonesia's health sector is further complicated by decentralization, which devolved significant authority for health planning, budgeting, and service management to provincial and district governments. While decentralization was envisaged to enhance responsiveness, strengthen accountability, and promote innovation at the local level, empirical studies indicate that uneven institutional capacity, fragmented governance, and variable political commitment have contributed to heterogeneous policy implementation outcomes (SMERU Research Institute, 2023). Regions with stronger bureaucratic capability and fiscal autonomy tend to perform better in achieving national health targets, whereas regions with limited managerial competency, constrained budgets, or weak accountability mechanisms often experience stagnation or regression in key health indicators. This complex interplay between central directives and local discretion constitutes a central analytical issue for understanding how health policy is enacted and experienced across Indonesia.

A growing body of literature has examined the multidimensional challenges of Indonesia's health system. Pribadi (2024) highlights persistent problems in health financing, including structural deficits within the JKN programme, imbalances between revenue and expenditure, and inefficiencies in pooling arrangements that hinder risk equalization. Earlier analyses by Irwandy (2015) identified initial implementation challenges such as regulatory inconsistencies, hospital claims management issues, and misaligned tariff structures under the INA-CBG payment system, which collectively affected provider behavior and service quality. Meanwhile, more recent empirical research using national utilization data indicates that service uptake under JKN is substantially influenced by socioeconomic determinants, health needs, insurance category, and preferences for public versus private facilities, revealing persistent inequities in utilization patterns despite universal coverage. Complementing these findings, studies on geographical inequalities demonstrate that remote districts—especially in eastern Indonesia—continue to struggle with shortages of health personnel, limited facility readiness, and weak pharmaceutical supply chains, further exacerbating disparities in health outcomes (Kharisma, 2020b). Parallel to these systemic challenges, Indonesia's digital health transformation agenda—particularly the rollout of Electronic Medical Records (EMR)—has encountered organizational readiness issues, infrastructure gaps, and insufficient integration across platforms, raising questions about the feasibility of achieving full interoperability in the near term (Ardiansyah, 2024).

These diverse strands of evidence point to several pressing policy issues that remain insufficiently addressed. First, the persistent imbalance between JKN's rising expenditures and limited revenue base raises concerns regarding long-term financial sustainability and the adequacy of provider payment incentives. Second, decentralization-induced fragmentation continues to challenge coordination between levels of government, often resulting in

mismatched priorities between national policies and local capacity. Third, substantial inequities in service access, quality, and outcomes persist across regions, demanding more targeted approaches to address the structural determinants of health inequality. Fourth, the acceleration of Indonesia's digital health strategy requires stronger governance to ensure that data systems, monitoring mechanisms, and digital infrastructure support—not hinder—the effective delivery of health services. Fifth, the increasing complexity of Indonesia's health landscape calls for more sophisticated monitoring and evaluation (M&E) frameworks that enable real-time detection of performance gaps and adaptive policy adjustments.

Despite a growing volume of research examining individual elements of Indonesia's health system, significant gaps remain in the literature. Most studies tend to focus on isolated dimensions—such as financing, equity, decentralization, or service readiness—without situating these components within a unified policy cycle that encompasses planning, implementation, and monitoring across governance levels. Furthermore, limited research explicitly examines the interaction between national policy frameworks and regional institutional capacity, particularly in relation to how policy ambitions are transformed, constrained, or reshaped within decentralized administrative structures. Additionally, few studies systematically assess how M&E mechanisms function as a bridge between national priorities and local realities, or how data-driven governance can correct systemic inefficiencies in real time.

This article contributes to the scholarly and policy debate by addressing these gaps through three key innovations. First, it offers an integrated multilevel synthesis that connects macro-level health system policies with meso-level governance processes and micro-level institutional practices, thereby providing a comprehensive account of how health policy operates in both national and regional arenas. Second, it introduces an adaptive governance framework that emphasizes the role of M&E systems and data feedback loops in aligning national strategic objectives with regional implementation capacity, proposing a model of policy responsiveness suited to Indonesia's decentralized context. Third, it adopts an explicitly equity-driven analytical lens, focusing not only on aggregate progress toward UHC but also on the distributional consequences of policy design and implementation. By foregrounding issues of fairness, access, and regional disparity, the article advances a normative and empirical argument for health policy reforms that prioritize inclusive and equitable outcomes.

METHODS AND FINDINGS

This study employs a rigorous qualitative research design supported by a systematic and integrative review methodology to comprehensively analyze the formulation, implementation, monitoring, and evaluation of health policies in Indonesia across national and sub-national governance levels. The methodological approach draws upon established methodological guidelines for qualitative synthesis (Dixon-Woods et al., 2006; Thomas & Harden, 2008) and is constructed to address the complexity of Indonesia's multi-level health governance structure, which operates under decentralization and significant regional heterogeneity in institutional capacity (Heywood & Harahap, 2009; Pisani et al., 2017). Integrating systematic search procedures, documentary analysis, and thematic synthesis, this approach enables an in-depth assessment of both structural reforms and micro-level institutional practices within Indonesia's evolving health system.

Data were collected through systematic searching of four major academic databases—Scopus, Web of Science, PubMed, and Google Scholar—using an advanced keyword strategy informed by PRISMA 2020 recommendations. Search strings employed Boolean combinations of terms related to health policy (“health policy,” “public health regulation,” “universal health coverage”), governance (“decentralization,” “institutional capacity,” “street-

level bureaucracy”), and the Indonesian context (“Indonesia,” “district health system,” “JKN”). Documentary sources were supplemented by official Indonesian government repositories, including regulations and policy documents issued by the Ministry of Health (Kementerian Kesehatan Republik Indonesia, 2012; Kementerian Kesehatan Republik Indonesia, 2019), strategic development plans produced by (Bappenas, 2014, 2020), and evaluation reports by international organizations such as WHO (World Health Organization, 2019), the World Bank (2016), and UNICEF (2021). Inclusion criteria were limited to documents published between 2000 and 2025 to reflect the period during which major health reforms—decentralization, the introduction of Jaminan Kesehatan Nasional, and the revitalization of primary health care—were enacted (Sparling et al., 2021).

All included documents were imported into a qualitative analysis environment, where they were coded using a hybrid deductive–inductive thematic analysis strategy (Fereday & Muir-Cochrane, 2006). Deductive codes were derived from prominent public policy and health systems frameworks, including Gilson (2014) Policy Triangle Framework, Lipsky's (1980) Street-Level Bureaucracy theory, Sabatier (1988) Advocacy Coalition Framework, and the WHO Health Systems Building Blocks model (World Health Organization, 2007). These frameworks provided an analytical scaffold for examining policy actors, contextual determinants, governance structures, and system performance. Simultaneously, inductive codes were developed from recurring patterns and emergent insights in Indonesian case studies, enabling sensitivity to local institutional realities such as leadership variability, resource constraints, regional political incentives, and implementation discretion (Kristiansen & Santoso, 2006; Riyadi et al., 2020).

To enhance methodological rigor, triangulation was applied across data sources and analytical stages. Source triangulation compared findings from national regulations, provincial implementation studies, and independent evaluations to ensure consistency and reduce single-source bias. Analyst triangulation was conducted through iterative coding cycles, peer debriefing, and intercoder consistency checks (Bradley et al., 2007). Procedural reliability was strengthened by maintaining a transparent audit trail documenting inclusion decisions, code development, and synthesis logic, following standards of qualitative rigor proposed by Lincoln & Guba (1985). Validity was enhanced by systematically cross-checking all interpretive insights with primary documents to avoid misrepresentation of policy intent or implementation outcomes, especially with respect to decentralized governance structures.

After coding and validation, the study employed an interpretive narrative synthesis approach (Popay et al., 2006) to construct thematic clusters linking macro-level policy reforms—such as UHC governance, regulatory harmonization, financing structures, and stewardship mechanisms—with micro-level institutional practices involving service delivery, frontline bureaucrat discretion, managerial decision-making, and operational constraints in PUSKESMAS and hospitals. The synthesis also highlighted cross-regional variation in governance capacity, elucidating how political economy factors, administrative bottlenecks, and accountability arrangements shape health policy outcomes in Indonesia (McLaughlin et al., 2020; Rokx et al., 2010). By integrating systematic review principles with contextual specificity, this methodological framework enabled a holistic assessment of Indonesia's health policy processes, capturing structural determinants, institutional performance, and on-the-ground implementation dynamics.




Figure 1. Research Methodology Flowchart
Source: Developed by the authors (2025).

Policy Ambition and Design–Capacity Asymmetry

While Indonesia’s health reforms are normatively robust and conceptually coherent at the design level, the reviewed literature reveals a persistent structural gap between national policy ambition and subnational implementation capacity. Over the past two decades, successive governments have articulated health reform agendas that closely align with dominant global health governance paradigms, particularly universal health coverage, equity-oriented service delivery, and integrated health system governance. Flagship initiatives—most notably the National Health Insurance (Jaminan Kesehatan Nasional/JKN), the revitalization of primary health care, and the development of integrated digital health ecosystems—reflect a strong commitment to constructing a comprehensive and rights-based health system.

From a policy design perspective, Indonesia’s health reforms exhibit a high degree of normative ambition and regulatory sophistication. National policies are closely aligned with international frameworks such as the WHO Health System Building Blocks and strategic purchasing models, emphasizing stewardship, financial protection, service quality, and information integration. These principles are translated into dense regulatory instruments, including laws, ministerial regulations, and technical guidelines, which collectively create an appearance of conceptual completeness and institutional maturity at the national level.

Despite this formal coherence, empirical studies consistently point to a systemic misalignment between national policy design and subnational implementation capacity. National policy instruments implicitly assume a relatively uniform baseline of institutional readiness across provinces and districts, encompassing administrative competence, adequate human resources, fiscal stability, managerial capability, and functional coordination mechanisms. In practice, however, these assumptions rarely hold. Indonesia’s decentralized governance structure has generated highly heterogeneous local institutional environments shaped by fiscal disparities, uneven bureaucratic professionalism, leadership turnover, and variations in political commitment to health sector reform.

This article uses the term *design–capacity asymmetry* as an analytical lens rather than as a new theoretical construct to capture the gap between standardized national policy instruments and uneven subnational administrative capacity. This asymmetry constitutes a central mechanism explaining the differentiated outcomes of Indonesia’s health reforms. Identical policy mandates—whether related to service standards, financing arrangements, or reporting requirements—interact with divergent local governance contexts, producing a wide spectrum of implementation patterns. In high-capacity regions, national reforms are more readily absorbed, adapted, and operationalized, while in lower-capacity districts they often result in partial compliance, symbolic implementation, or unintended distortions.

These dynamics are amplified within Indonesia’s decentralized system, where authority over health service delivery has been devolved to subnational governments without a commensurate equalization of administrative capacity. District governments are required to implement increasingly complex policy frameworks while operating under conditions of staffing shortages, high leadership turnover, and limited analytical resources. As a result, policy compliance frequently becomes an end in itself, overshadowing substantive performance improvement and institutional learning.

From a public administration perspective, the persistence of design–capacity asymmetry underscores the limits of policy ambition as a determinant of governance outcomes. Policy effectiveness is mediated by the degree of institutional fit between policy demands and administrative capability rather than by the internal coherence of policy design alone. In the Indonesian case, ambitious national health reforms operate within a fragmented multilevel governance system in which coordination mechanisms and enforcement capacity vary substantially across jurisdictions. Without explicit strategies to address this asymmetry, continued policy expansion risks reinforcing existing inequalities rather than achieving the intended goals of equitable and sustainable health system strengthening.

Uneven Subnational Capacity and Primary Health Care Performance

Building on the design–capacity asymmetry discussed above, this section examines how uneven subnational capacity translates into differentiated primary health care performance. Indonesia’s decentralized governance structure positions districts as the primary locus of health service delivery, with PUSKESMAS functioning as the main interface between national health reforms and citizens’ everyday experiences of care. Across the reviewed studies, variations in subnational institutional capacity consistently emerge as a decisive factor shaping the performance of primary health care facilities.

Empirical evidence reveals pronounced disparities in the operational readiness of PUSKESMAS across regions, particularly with respect to the availability and distribution of human resources, infrastructure quality, diagnostic capability, and the functionality of referral systems. Facilities located in urban and fiscally strong districts are more likely to meet national service standards, maintain stable staffing levels, and integrate preventive, promotive, and curative services. In contrast, PUSKESMAS in rural, remote, and fiscally constrained districts frequently operate under chronic shortages of qualified health workers, limited equipment availability, and weak logistical and referral support. Across the reviewed studies, these patterns recur consistently across regions and health programs, indicating systemic rather than isolated implementation challenges.

The implications of uneven primary health care capacity are evident across multiple priority health outcomes. Maternal and neonatal health indicators remain highly sensitive to the availability of skilled personnel, emergency obstetric services, and timely referral mechanisms at the district level. The literature documents persistent gaps between national policy commitments to safe motherhood and the realities of service provision in peripheral regions, where referral delays and limited emergency capacity continue to undermine

outcomes. Similar dynamics are observed in tuberculosis control, where case detection rates and treatment success vary substantially across districts, reflecting differences in surveillance capacity, laboratory access, and workforce stability.

Noncommunicable disease (NCD) management further illustrates the limits of primary health care performance under uneven capacity conditions. Although national policy frameworks increasingly emphasize chronic disease prevention, continuity of care, and service integration, many PUSKESMAS lack the institutional and managerial resources required to operationalize these models. High workloads, fragmented information systems, and insufficient training constrain the ability of frontline providers to transition from episodic treatment toward sustained disease management, particularly outside major urban centers.

From an administrative perspective, these patterns align closely with insights from street-level bureaucracy theory. Frontline health workers exercise significant discretion in translating policy mandates into practice, especially under conditions of resource scarcity and ambiguous operational guidance. This discretion does not imply uniform failure across low-capacity districts, but rather highlights structural constraints that systematically shape implementation outcomes. In higher-capacity settings, discretion may facilitate adaptation and innovation, whereas in lower-capacity contexts it often functions as a coping mechanism that prioritizes feasibility over strict policy fidelity.

Importantly, the literature suggests that uneven primary health care performance is shaped not only by resource availability but also by differences in institutional and managerial capacity. Districts with relatively limited resources but stable leadership, effective supervision, and coherent planning processes often outperform better-resourced districts characterized by high leadership turnover and weak bureaucratic coordination. This finding reinforces the argument that administrative capability—encompassing leadership quality, managerial competence, and organizational learning—plays a critical mediating role between policy inputs and service delivery outcomes.

Taken together, the evidence indicates that primary health care performance in Indonesia is influenced less by the formal content of national policy than by the capacity of subnational institutions to interpret, prioritize, and operationalize policy mandates. Uniform national reforms therefore generate uneven effects not because of policy failure per se, but because they are filtered through highly differentiated local governance environments. Without targeted efforts to strengthen district-level institutional capacity at the frontline of service delivery, continued reliance on policy expansion alone is unlikely to yield equitable and sustainable improvements in health outcomes.

Digital Health Integration and Governance Constraints

Following the analysis of uneven primary health care capacity, this section examines how digital health integration interacts with existing governance constraints in Indonesia's decentralized health system. Digital health integration has emerged as a central pillar of Indonesia's health reform agenda, with national initiatives explicitly framed as solutions to long-standing problems of fragmentation, data asymmetry, and weak coordination across levels of care. Platforms such as SATUSEHAT are designed to function as integrative infrastructures, enabling interoperability among health facilities, supporting real-time surveillance, and strengthening evidence-based decision-making. At the policy level, digital transformation is positioned as a key enabler of system-wide efficiency, transparency, and accountability.

However, the reviewed literature indicates that the implementation of digital health systems is constrained less by technological limitations than by underlying governance and institutional challenges. While national regulations mandate system integration and standardized reporting, actual adoption and meaningful use of digital platforms vary

substantially across regions and facilities. Across the reviewed studies, variations in digital adoption and use recur consistently across regions, indicating structural rather than incidental implementation barriers. This pattern mirrors the broader design–capacity asymmetry discussed earlier, as digital reforms assume levels of organizational readiness, digital literacy, and managerial capability that are unevenly distributed across subnational governments.

Empirical evidence further shows that digital health systems are frequently used in a compliance-oriented manner rather than as instruments of strategic governance. Health facilities often prioritize data entry to satisfy reporting requirements imposed by central authorities, with limited attention to data quality, analytical use, or feedback into planning and service improvement. In lower-capacity districts, digital platforms commonly coexist with parallel manual systems, informal workarounds, or delayed reporting, reflecting coping strategies in response to unreliable connectivity, limited infrastructure, and insufficient training. These recurring patterns suggest that digital fragmentation is not an incidental implementation problem, but a systemic governance challenge.

Institutional coordination constitutes another major constraint on effective digital integration. Multiple digital platforms—developed by different agencies and introduced at different stages of reform—often operate with overlapping functions and limited interoperability. Although recent policy initiatives seek to consolidate these systems, the legacy of fragmented digital governance continues to shape implementation practices. Subnational governments and health facilities are frequently required to comply with multiple reporting standards and data flows, increasing administrative burdens without necessarily enhancing decision-making capacity. In this sense, digitalization layered onto existing institutional fragmentation may inadvertently intensify coordination problems rather than resolve them.

From a public administration perspective, the limits of digital health integration can be understood through the interaction between technology and institutional capacity. Digital tools do not substitute for governance; rather, they amplify existing organizational strengths and weaknesses. In higher-capacity settings, digital systems can support performance monitoring, resource allocation, and adaptive management. In lower-capacity contexts, by contrast, the same systems may reinforce hierarchical control and compliance without generating learning or improvement. These findings do not suggest that digital health initiatives are inherently ineffective, but rather that their governance conditions critically shape their impact.

The COVID-19 pandemic further exposed these governance constraints by functioning as a stress test for Indonesia’s digital health infrastructure. While digital platforms played an important role in surveillance and reporting, inconsistencies in data integration, unclear authority over data validation, and weak intergovernmental coordination limited their effectiveness in several regions. These challenges were driven less by the absence of digital tools than by deficiencies in stewardship, accountability, and incentive structures governing data use.

Taken together, the evidence indicates that digital health integration in Indonesia remains fundamentally shaped by governance conditions that determine how technology is adopted, institutionalized, and used for decision-making. Without parallel investments in subnational analytical capacity, clearer intergovernmental coordination mechanisms, and incentives for data-driven governance, digital reforms risk reproducing the very fragmentation they are intended to overcome. As with other dimensions of Indonesia’s health reform, the effectiveness of digital health integration ultimately depends not on technological sophistication alone, but on the capacity of institutions to govern, learn from, and act upon digital information.

Monitoring, Evaluation, and the Limits of Adaptive Governance

Following the analysis of digital governance constraints, this section examines how weaknesses in monitoring and evaluation further limit adaptive governance capacity in Indonesia's health sector. Monitoring and evaluation (M&E) systems are formally positioned as central instruments for learning, accountability, and continuous improvement within Indonesia's health reform architecture. In principle, the expansion of health information systems, performance indicators, and routine reporting mechanisms should enable policymakers to identify implementation bottlenecks, recalibrate policy instruments, and respond adaptively to emerging challenges. Within a decentralized governance system characterized by substantial regional heterogeneity, effective M&E is particularly critical for aligning national policy objectives with subnational implementation realities.

However, the reviewed literature reveals that M&E practices in Indonesia's health sector remain predominantly compliance-oriented rather than learning-oriented. While reporting requirements have expanded significantly, the use of performance data to inform decision-making, resource allocation, and policy adjustment remains limited at both central and subnational levels. Data are frequently collected to satisfy upward accountability obligations rather than to support downward accountability or internal organizational learning. These patterns recur consistently across policy domains and regions, indicating systemic governance constraints rather than isolated technical failures.

Empirical studies further document wide variation in data quality, timeliness, and analytical use across districts. In lower-capacity regions, data systems are often fragmented, incomplete, or inconsistently updated, reflecting constraints in human resources, technical skills, and managerial oversight. Even in higher-capacity settings, the translation of performance data into actionable insights is frequently constrained by siloed organizational structures and weak coordination between planning, budgeting, and service delivery units. As a result, performance information accumulates without being systematically integrated into governance processes.

The limits of adaptive governance become particularly visible when performance feedback fails to trigger meaningful policy or managerial responses. Although national frameworks emphasize evidence-based planning, performance indicators rarely lead to differentiated interventions or targeted capacity-building at the district level. Instead, uniform policy responses are often applied regardless of local performance variation, reinforcing the design–capacity asymmetry identified earlier. In this context, M&E systems generate information without empowering institutions to act upon it, undermining their potential as tools for governance learning.

From a public administration perspective, these dynamics reflect a broader tension between accountability and adaptability in hierarchical administrative systems. Strong upward reporting requirements may enhance formal accountability, but they can also discourage experimentation, risk-taking, and honest reporting at the frontline. These findings do not imply that accountability mechanisms are undesirable; rather, they suggest that accountability without learning constrains adaptive capacity. When sanctions outweigh incentives for improvement, local officials and health managers may prioritize indicator compliance over substantive performance gains.

Crisis conditions further expose the constraints of Indonesia's M&E architecture. During the COVID-19 pandemic, rapidly shifting policy priorities and service demands required flexible information flows and real-time decision-making. While data collection intensified, inconsistencies in reporting standards, delays in data validation, and limited analytical capacity constrained adaptive responses in several regions. These challenges were driven less by data scarcity than by institutional arrangements that limited the effective use of available information.

Taken together, the evidence indicates that persistent weaknesses in adaptive governance are closely linked to how M&E systems are designed, institutionalized, and used within Indonesia's health sector. Without mechanisms that connect performance monitoring to managerial discretion, resource reallocation, and policy adjustment, M&E remains a technical exercise rather than a governance capability. Strengthening adaptive governance therefore requires not only improved data systems, but also institutional reforms that embed M&E within decision-making processes, align incentives with learning, and enhance subnational analytical capacity. Absent such reforms, monitoring and evaluation are unlikely to bridge the gap between national policy ambition and subnational implementation capacity.

Regional Typologies and Intra-Provincial Variation

This section synthesizes the preceding analyses by situating observed governance patterns within a set of analytically derived regional typologies. The cumulative findings of this review point to regional heterogeneity as a defining characteristic of Indonesia's health governance landscape. Rather than exhibiting a uniform national trajectory, health system performance reflects patterned variation shaped by differences in subnational institutional capacity, governance quality, and administrative coherence. To capture these patterns, the reviewed literature supports the identification of distinct regional typologies that illustrate how national policies are mediated through local governance contexts.

At one end of the spectrum are high-capacity regions, typically characterized by relatively strong fiscal bases, stable political leadership, and professionalized bureaucracies. In these settings, national health reforms—ranging from JKN implementation to digital health integration and M&E utilization—tend to be absorbed and operationalized with fewer distortions. Policy instruments are more likely to function as intended, supported by managerial capability, inter-agency coordination, and the effective use of performance data for planning and service improvement. These regions demonstrate the conditional effectiveness of national policy design when institutional fit is high.

A second group consists of intermediate-capacity regions, where overall performance masks substantial internal variation. Provinces in this category often include both relatively high-performing urban districts and weaker peripheral districts. Here, policy outcomes are highly contingent on district-level leadership, administrative professionalism, and political prioritization rather than on provincial characteristics alone. The literature consistently shows that within these regions, differences in governance practices produce sharper contrasts in performance than differences between provinces, underscoring the limits of aggregate regional classifications.

Lower-capacity regions form a third typology, marked by chronic resource constraints, limited administrative capability, and weak coordination mechanisms. In these contexts, national reforms are frequently implemented in a fragmented or symbolic manner. Digital health systems are used primarily for compliance, M&E functions are weakly institutionalized, and primary health care facilities struggle to meet minimum service standards. Importantly, these outcomes are not solely attributable to fiscal scarcity, but to compounded governance challenges, including high leadership turnover, politicized appointments, and limited organizational learning capacity.

Finally, the most structurally constrained regions—often remote and geographically dispersed—experience cumulative disadvantages that severely limit the transformative potential of national health reforms. In these settings, the interaction of geographic isolation, workforce shortages, weak infrastructure, and limited managerial capacity produces persistent implementation gaps across policy domains. Even when formal program coverage is high, effective service delivery and adaptive governance remain elusive.

These typologies are heuristic and intended to capture dominant governance patterns rather than rigid regional classifications. Crucially, the reviewed literature converges on the finding that variation within provinces frequently exceeds variation between provinces. District-level factors—particularly leadership stability, fiscal management practices, and bureaucratic competence—emerge as more powerful predictors of performance than regional location per se. This insight challenges policy approaches that rely on broad regional targeting and supports a shift toward more granular, capacity-sensitive governance strategies.

Taken together, these regional typologies consolidate the central argument of this study: Indonesia's health system challenges are fundamentally governance challenges rooted in uneven institutional capacity rather than deficiencies in policy ambition or design. National reforms have established an extensive and normatively coherent policy architecture, yet their outcomes are mediated by local administrative realities. Without explicit recognition of subnational diversity and systematic differentiation of policy instruments, capacity-building efforts, and accountability mechanisms, national reforms risk reproducing existing inequalities. As a closing synthesis to the Results and Discussion, this typological perspective provides the empirical and analytical foundation for the concluding section, which elaborates the theoretical, empirical, and normative implications of this study.

CONCLUSION

This study examined the persistent misalignment between health policy ambition and system performance in Indonesia's decentralized governance context through a systematic and integrative review of literature published between 2000 and 2025. The findings show that Indonesia's health system challenges are not primarily attributable to weak policy design or insufficient reform commitment. Rather, they reflect a structural governance problem rooted in uneven subnational institutional capacity. Despite extensive and normatively coherent reforms—covering national health insurance, primary health care strengthening, and digital health integration—policy outcomes remain highly uneven across regions and districts.

Theoretical Contribution

Theoretically, this study advances public administration and health governance scholarship by framing *design–capacity asymmetry* as a central analytical lens for understanding policy implementation in decentralized systems. Integrating insights from policy capacity, multi-level governance, street-level bureaucracy, and adaptive governance, the analysis demonstrates that policy effectiveness depends on institutional fit between standardized policy instruments and heterogeneous administrative capacities. This integrated perspective clarifies how policy design, frontline discretion, digital governance, and monitoring systems jointly shape reform outcomes.

Empirical Contribution

Empirically, the study synthesizes fragmented evidence across primary health care delivery, financing, digital health, and monitoring and evaluation. Consistent patterns of subnational variation emerge across policy domains, indicating systemic rather than isolated implementation challenges. Regional typologies and pronounced intra-provincial variation reveal that district-level leadership stability, bureaucratic professionalism, fiscal management, and analytical capacity are more decisive for performance than provincial location alone.

Normative and Policy Implications

Normatively, the findings challenge uniform reform strategies that prioritize policy expansion over capacity-sensitive governance. Persistent design–capacity asymmetry implies that one-size-fits-all approaches risk reinforcing inequality. More effective health governance requires differentiated policy instruments, targeted capacity-building, and adaptive implementation strategies that explicitly account for subnational diversity. Digital health

initiatives and performance management systems should therefore be treated as institutional reforms rather than technical fixes.

Concluding Remarks

Overall, this study demonstrates that Indonesia's health reform trajectory is best understood as a governance challenge rather than a policy failure. While national reforms have established a robust normative framework, their impact remains constrained by uneven institutional capacity and limited adaptive governance at the subnational level. By explicitly integrating theoretical, empirical, and normative insights, this article contributes to broader debates on governing complex public sector reforms in decentralized settings and underscores the centrality of institutional capacity for achieving equitable and sustainable outcomes.

REFERENCES

- Ardiansyah, M. (2024). *Digital health readiness and interoperability challenges in Indonesia's EMR implementation*. *Journal of Health Informatics Indonesia*, 12(1), 44–59.
- Bappenas. (2014). *Rencana Pembangunan Jangka Menengah Nasional 2015–2019*. Kementerian PPN/Bappenas.
- Bappenas. (2020). *Rencana Pembangunan Jangka Menengah Nasional 2020–2024*. Kementerian PPN/Bappenas.
- Bradley, E. H., Curry, L. A., & Devers, K. J. (2007). Qualitative data analysis for health services research. *Health Services Research*, 42(4), 1758–1772.
- Dixon-Woods, M., Agarwal, S., Jones, D., Young, B., & Sutton, A. (2006). Synthesising qualitative and quantitative evidence. *Journal of Health Services Research & Policy*, 10(1), 45–53.
- Fereday, J., & Muir-Cochrane, E. (2006). Demonstrating rigor using thematic analysis: A hybrid approach of inductive and deductive coding and theme development. *International Journal of Qualitative Methods*, 5(1), 80–92. <https://doi.org/10.1177/160940690600500107>
- Gilson, L. (2014). Practice and power: A review and interpretive synthesis on the exercise of discretionary power in policy implementation by front-line providers and managers. *Health Policy and Planning*, 29, 151–163. <https://doi.org/10.1093/heapol/czu098>
- Heywood, P., & Harahap, N. P. (2009). Public funding of health at the district level in Indonesia. *Health Research Policy and Systems*, 7, Article 5.
- Kementerian Kesehatan Republik Indonesia. (2012). *Peraturan Menteri Kesehatan tentang Sistem Kesehatan Nasional*. Kemenkes RI.
- Kementerian Kesehatan Republik Indonesia. (2019). *Rencana Strategis Kementerian Kesehatan 2020–2024*. Kemenkes RI.
- SMERU Research Institute. (2023). *Decentralization and health governance in Indonesia: Performance, challenges, and future pathways*.
- Irwandy, A. (2015). Challenges of INA-CBG implementation in Indonesian hospitals. *Jurnal Administrasi Kesehatan Indonesia*, 3(2), 101–115.
- Kharisma, B. (2020a). Geographical inequalities in Indonesia's health system. *Journal of Regional Development Studies*, 14(2), 55–71.
- Kharisma, B. (2020b). Inequality in access to health services in Indonesia: Empirical findings and policy implications. *Journal of Indonesian Health Policy Studies*, 12(2), 113–127.
- Kristiansen, S., & Santoso, P. (2006). Surviving decentralization? Leadership, accountability, and local politics in Indonesia. *The Pacific Review*, 19(4), 421–444.
- Lincoln, Y. S., & Guba, E. G. (1985). *Naturalistic inquiry*. Sage Publications.
- Lipsky, M. (1980). *Street-level bureaucracy: Dilemmas of the individual in public services*. Russell Sage Foundation.

- McLaughlin, K., Yudiarto, M., & Siregar, A. (2020). Governance and health system performance in Indonesia. *Health Policy and Planning*, 35(6), 729–738.
- World Bank. (2016). *Health financing system assessment: Indonesia*. World Bank.
- World Health Organization. (2007). *Everybody's business: Strengthening health systems to improve health outcomes*. WHO.
- World Health Organization. (2019). *Indonesia health system review*. WHO.
- World Health Organization. (2023). *Universal health coverage: Indonesia country profile 2023*. WHO.
- Pisani, E., Kok, M. O., & Nugroho, K. (2017). Indonesia's road to universal health coverage. *Health Policy and Planning*, 32(3), 267–276.
- Popay, J., Roberts, H., Sowden, A., et al. (2006). *Guidance on the conduct of narrative synthesis in systematic reviews*. ESRC UK.
- Pribadi, T. (2024). Structural deficits and financing reforms in Indonesia's JKN program: A macro-fiscal analysis. *Indonesian Journal of Health Economics*, 9(1), 1–18.
- Rokx, C., Giles, J., Satriawan, E., Marzoeqi, P., Harimurti, P., & Yavuz, E. (2010). *New insights into the provision of health services in Indonesia*. World Bank.
- Sabatier, P. A. (1988). An advocacy coalition framework of policy change and the role of policy-oriented learning therein. *Policy Sciences*, 21(3), 129–168.
- Sparling, T., O'Neil, M., & Anwar, T. (2021). Universal health coverage reforms in Indonesia: Impacts, challenges, and opportunities. *Health Systems & Reform*, 7(3), 190–213.
- Thomas, J., & Harden, A. (2008). Methods for the thematic synthesis of qualitative research in systematic reviews. *BMC Medical Research Methodology*, 8, Article 45.
- UNICEF. (2021). *Indonesia health system strengthening: Annual report 2021*. UNICEF Indonesia.

**“FLEXIBLE PEG–PVDF SOLID ELECTROLYTE MEMBRANES WITH
ENHANCED IONIC CONDUCTIVITY FOR POUCH-TYPE LITHIUM-ION
BATTERIES”**

Azad Md. Sorwar

Research assistant, Dhaka University of Engineering & Technology, Gazipur. Faculty of Mechanical,
Department of Mechanical Engineering

Md. Saimon Islam

Research assistant, Dhaka University of Engineering & Technology, Gazipur. Faculty of Mechanical,
Department of Mechanical Engineering

Dr. Khurshida Sharmin

Dhaka University of Engineering & Technology, Gazipur
Faculty of Mechanical, Department of Mechanical Engineering, Dhaka, Gazipur

Abstract

This paper reports the preparation and electrochemical performance of a polyethylene glycol (PEG) modified poly vinylidene fluoride (PVDF)-based solid polymer electrolyte for all-solid-state lithium-ion batteries. The incorporation of PEG and lithium bis (fluorosulfonyl)imide (LiFSI) effectively suppresses the crystallinity of PVDF and enhances lithium-ion transport. The electrolyte membranes were fabricated via a solution casting technique and characterized by scanning electron microscopy (SEM), tensile testing, Fourier transform infrared spectroscopy (FTIR), and electrochemical impedance spectroscopy. The optimized PVDF–PEG–LiFSI membrane exhibits a homogeneous porous morphology, improved mechanical flexibility, and a high room-temperature ionic conductivity of 2.66 mS cm^{-1} . A prototype pouch-type solid-state cell demonstrates stable charge–discharge behavior with a working voltage of approximately 1.8 V. The results indicate that PEG-modified PVDF solid polymer electrolytes are promising candidates for safe and high-performance solid-state lithium-ion batteries.

Index Terms— Solid polymer electrolyte, PVDF, polyethylene glycol, ionic conductivity, lithium-ion battery.

1. Introduction

The rapid growth of electric vehicles, portable electronics, and large-scale energy storage systems has intensified the demand for lithium-ion batteries (LIBs) with higher energy density, improved safety, and long-term reliability. Since their commercialization, LIBs have dominated the energy storage market due to their high gravimetric and volumetric energy densities; however, their reliance on flammable liquid electrolytes presents serious safety concerns, including electrolyte leakage, thermal runaway, and catastrophic failure under abusive conditions [1–3]. These limitations fundamentally restrict the further development of next-generation high-energy battery technologies. All-solid-state lithium-ion batteries (ASSLIBs) have emerged as a promising solution to overcome these challenges by replacing liquid electrolytes with solid alternatives. Solid electrolytes can significantly enhance battery safety, suppress leakage, and enable the use of high-capacity lithium metal anodes [2,6,8]. Among various solid electrolyte systems, solid polymer electrolytes (SPEs) have attracted particular attention due to their mechanical flexibility, good interfacial contact with electrodes, ease of processing, and scalability for practical applications [3,9]. Nevertheless, conventional SPEs often suffer from low ionic conductivity at room temperature, primarily arising from high

polymer crystallinity and restricted segmental chain motion [4,9]. Considerable research efforts have therefore focused on tailoring polymer structures and compositions to enhance ionic transport while maintaining mechanical integrity. Strategies such as polymer blending, plasticizer incorporation, and crystallinity control have proven effective in increasing the amorphous phase content and facilitating lithium-ion migration [5,7,10]. In particular, modification of fluorinated polymers such as polyvinylidene fluoride (PVDF) has shown promise due to their high dielectric constant, electrochemical stability, and strong lithium salt dissociation capability [8,10]. However, achieving an optimal balance between ionic conductivity, mechanical strength, and structural stability remains a critical challenge. In this context, rational design of polymer electrolyte systems that integrate high ionic conductivity with robust mechanical performance is essential for advancing safe and high-performance solid-state lithium-ion batteries suitable for next-generation energy storage applications.

II. Experimental

A. Materials Preparation

PVDF was dissolved in an appropriate solvent under continuous stirring to obtain a homogeneous solution. PEG was added as a plasticizer, followed by the incorporation of LiFSI salt. The mixture was stirred until a uniform viscous solution was obtained. The solution was cast onto a glass substrate and dried under controlled conditions to remove residual solvent, forming free-standing solid polymer electrolyte membranes.

B. Characterization

The surface morphology of the membranes was examined using scanning electron microscopy (SEM). Mechanical properties were evaluated by tensile testing. Fourier transform infrared (FTIR) spectroscopy was employed to analyze polymer–salt interactions and crystallinity changes. Ionic conductivity was measured by electrochemical impedance spectroscopy at room temperature using stainless steel blocking electrodes. A pouch-type solid-state lithium-ion cell was assembled to evaluate electrochemical performance.

III. Results and Discussion

A. Morphological Analysis




Fig: (a) SEM Test result of neat PVDF membrane. (b) SEM Test result of neat PVDF+PEG membrane.(c) SEM Test result of neat PVDF+SALTmembrane.(d)SEMTestresultofneatPVDF+PEGmembran.

SEM images reveal that neat PVDF exhibits a dense and compact morphology with limited porosity. The addition of PEG slightly disrupts the crystalline domains, while PVDF with LiFSI alone shows irregular pores and micro-cracks due to poor compatibility. In contrast, the PVDF–PEG–LiFSI membrane displays a homogeneous and uniformly porous structure, which is favorable for lithium-ion transport.

B. Tensile test of neat PVDF membrane




Fig: (a) Tensile test of neat PVDF membrane. (b) Tensile test of neat PVDF+PEG membrane. (c) Tensile test of neat PVDF+SALT membrane

The neat PVDF membrane exhibits typical semi-crystalline polymer behavior, with an initial elastic region followed by plastic deformation before fracture. It shows a tensile strength of ~15 MPa, a Young's modulus of ~0.35 GPa, and a strain at break of 20–25%, indicating moderate stiffness but limited ductility. While PVDF provides adequate mechanical stability for handling, its relatively brittle nature and limited flexibility may limit its durability under repeated stresses in solid-state lithium-ion batteries.

C. Mechanical Properties

The neat PVDF membrane shows moderate tensile strength but limited flexibility. PEG incorporation significantly improves mechanical strength and flexibility by reducing crystallinity and enhancing chain mobility. The PVDF–PEG–LiFSI membrane maintains adequate mechanical integrity suitable for solid-state battery applications.

D. FTIR Analysis




Fig: (D) FTIR test result of sample

FTIR spectra confirm strong interactions between PEG ether oxygen atoms and Li^+ ions. The reduction and broadening of PVDF crystalline peaks indicate suppression of crystallinity and increased amorphous phase content, which contributes to enhanced ionic conductivity.

E. Ionic Conductivity & Resistance




Fig: (a) Conductivity of different samples. (b) Resistance of different samples.

The ionic conductivity of neat PVDF is relatively low (1.05 mS cm^{-1}). The addition of LiFSI increases conductivity to 1.224 mS cm^{-1} . Notably, the PVDF–PEG–LiFSI membrane exhibits a high ionic conductivity of 2.66 mS cm^{-1} at room temperature due to synergistic effects of PEG plasticization and polymer–salt coordination.

F. Electrochemical Performance




Fig: (F) Charging & Discharging graph

The charge–discharge behavior of the pouch-type lithium-ion battery with a PVDF–PEG–LiFSI solid electrolyte shows stable and repeatable performance. The voltage quickly increases from ~0.18 V to ~2.1 V during charging and then gradually decreases to ~0.2–0.3 V during discharge, completing each cycle. Consistent voltage profiles over multiple cycles (~160 minutes) indicate good reversibility and interfacial stability, with minor voltage decay attributed to typical resistance and polarization effects. Overall, the results confirm adequate ionic conductivity and electrochemical stability of the PEG-modified PVDF electrolyte.

G. Pouch Cell Performance

The assembled pouch-type solid-state cell shows stable charge–discharge behavior with a reproducible voltage of approximately 1.8 V, demonstrating good interfacial compatibility and effective ion transport through the solid polymer electrolyte.

IV. Conclusions

A PEG-modified PVDF solid polymer electrolyte incorporating LiFSI was successfully developed for all-solid-state lithium-ion batteries. The incorporation of PEG effectively reduces PVDF crystallinity, improves mechanical flexibility, and enhances lithium-ion transport. The optimized membrane exhibits high room-temperature ionic conductivity and stable electrochemical performance in a pouch-type cell. This study demonstrates a simple and scalable strategy for designing high-performance solid polymer electrolytes for next-generation lithium-ion batteries.

Acknowledgment

The authors acknowledge institutional support for materials characterization and electrochemical testing.

References

- [1] Goodenough, J. B.; Park, K. S., *J. Am. Chem. Soc.*, 2013, 135, 1167–1176.
- [2] Tarascon, J.-M.; Armand, M., *Nature*, 2001, 414, 359–367.
- [3] Manthiram, A., *ACS Cent. Sci.*, 2017, 3, 1063–1069.
- [4] Xu, K., *Chem. Rev.*, 2014, 114, 11503–11618.
- [5] Feng, X. et al., *Energy Storage Mater.*, 2018, 10, 246–267.
- [6] Janek, J.; Zeier, W. G., *Nat. Energy*, 2016, 1, 16141.
- [7] Sun, C. et al., *Nano Energy*, 2017, 33, 363–386.
- [8] Manthiram, A.; Yu, X.; Wang, S., *Nat. Rev. Mater.*, 2017, 2, 16103.
- [9] Meyer, W. H., *Adv. Mater.*, 1998, 10, 439–448.
- [10] Zhang, H.; Liu, C.; Zheng, L., *Energy Storage Mater.*, 2020, 24, 29–51.

ÖĞRETMENLERDE PSİKOLOJİK SERMAYE VE ÖRGÜTSEL YABANCILAŞMA İLİŞKİSİ: BİR LİTERATÜR TARAMASI

Psikolojik Danışman Tuğba TAŞDEMİR

Dokuz Eylül Üniversitesi, Eğitim Bilimleri Enstitüsü,
Psikolojik Danışma ve Rehberlik Anabilim Dalı, Buca, İzmir.

Prof. Dr. H. Zekavet KABASAKAL

Dokuz Eylül Üniversitesi, Buca Eğitim Fakültesi,
Psikolojik Danışma ve Rehberlik Anabilim Dalı, Buca, İzmir.

ÖZET

Okullar, toplumu ve bireyi doğrudan etkileme gücüne sahiptir ve bu etki gücünü, hedefler doğrultusunda toplumu değiştirmek ve dönüştürmek için kullanırlar. Okulların hedeflerine ulaşmasında öğretmenler önemli bir role sahiptir. Bu bağlamda öğretmenlerin örgütsel tutumları, okulların işlevselliği açısından belirleyici bir faktör olmaktadır. Öğretmenlerde artan iş yükü, olumsuz örgütsel koşullar; motivasyonsuzluk ve tükenmişlik gibi işlevsiz duygulara neden olarak öğretmenlerde örgütsel yabancılaşma algısını arttırabilmektedir. Örgütsel süreçler üzerinde yıpratıcı etkisi bulunan yabancılaşma algısının önlenmesinde, bireyin olumlu psikolojik kaynaklarını tanımlayan psikolojik sermaye kavramı önemli bir koruyucu işleve sahiptir. Psikolojik sermayesi yüksek olan öğretmenlerin iyi oluş düzeylerinin arttığı ve eğitim-öğretim sürecine daha etkin katkı sağladıkları görülmektedir. Bu çalışmanın amacı, öğretmenlerde psikolojik sermaye ve örgütsel yabancılaşma ilişkisini inceleyen ulusal ve uluslararası araştırmaları derleyerek literatürdeki eğilimleri ortaya koymaktır. Çalışma geleneksel bir literatür taraması desenindedir. Bu kapsamda Google Akademik, DergiPark, Ulusal Tez Merkezi (YÖK Tez), Web of Science ve EBSCOhost veri tabanları üzerinden 2018–2025 yılları arasında Türkçe ve İngilizce yayımlanmış çalışmalar taranmış ve toplam 23 çalışmaya ulaşılmıştır. İncelenen çalışmalarda ağırlıklı nicel yöntemler ve ilişkisel tarama desenleri kullanılmıştır. Bulgular öğretmenlerin psikolojik sermayelerinin orta ve yüksek, örgütsel yabancılaşma algılarının ise düşük düzeyde olduğu göstermektedir. Ayrıca öğretmenlerde psikolojik sermaye ile örgütsel yabancılaşma arasında orta düzeyli negatif yönlü bir ilişki bulunduğu belirlenmiştir. Elde edilen bulgular, öğretmenlerin psikolojik sermayelerinin güçlendirilmesinin örgütsel yabancılaşmayı azaltmada önemli bir değişken olduğunu göstermektedir.

Anahtar Sözcükler: Psikolojik Sermaye, Örgütsel Yabancılaşma, Öğretmen

ABSTRACT

Schools have the power to directly influence both society and individuals, and they utilize this power to change and transform society in line with their goals. Teachers play a crucial role in enabling schools to achieve these goals. In this context, teachers' organizational attitudes constitute a determining factor in the functionality of schools. Increased workload and unfavorable organizational conditions may lead to dysfunctional emotions such as lack of motivation and burnout among teachers, thereby increasing their perceptions of organizational alienation. In preventing perceptions of alienation, which have a detrimental effect on organizational processes, the concept of psychological capital defined as an individual's positive psychological resources serves an important protective function. Teachers with high levels of psychological capital exhibit higher levels of well-being and contribute more effectively to the teaching learning process.

The aim of this study is to review national and international research examining the relationship between psychological capital and organizational alienation among teachers and to reveal trends in the literature. The study was designed as a traditional literature review. Within this scope, studies published in Turkish and English between 2018 and 2025 were searched through Google Scholar, DergiPark, the National Thesis Center (YÖK Thesis), Web of Science, and EBSCOhost databases, and a total of 23 studies were included. Quantitative methods and correlational research designs were predominantly used in the reviewed studies. The findings indicate that teachers' psychological capital levels are moderate to high, while their perceptions of organizational alienation are low. In addition, a moderate negative relationship was found between psychological capital and organizational alienation among teachers. These findings demonstrate that strengthening teachers' psychological capital is an important factor in reducing organizational alienation.

Keywords: Psychological Capital, Organizational Alienation, Teacher

GİRİŞ

Ortak amaçlar doğrultusunda bir araya gelen insan topluluklarına örgüt denir (Kayaalp, 2020). Örgütler toplumu ve bireyi doğrudan etkileme gücüne sahiptir. Okullar, toplumu şekillendiren ve dönüştüren örgüt yapılarından biri olması nedeniyle önem arz etmektedir. Bu doğrultuda geleceğin mimarı olan öğretmenlerin kendilerini sürekli yenileyerek okulların yakın ve uzak hedeflerine ulaştırması beklenmektedir (Çetinkaya ve Koçyiğit, 2021). Ancak okullar; öğrenci, öğretmen ve yöneticilerin yer aldığı açık bir sistem olması nedeniyle pek çok unsurdan etkilenir (Şişman, 2022, akt. Şentürk ve Seçilmiş, 2021). Bu kapsamda eğitim kurumları ve öğretmenler özelinde psikolojik sermaye ve örgütsel yabancılaşma kavramları önemli görülmektedir (Çetinkaya ve Koçyiğit, 2021).

Psikolojik Sermaye

Psikolojik sermaye kavramı, temellerini Martin Seligman'ın (1999) insanları geliştirmek, ileriye taşımak ve mutluluk düzeylerini artırmak gibi hedefleri esas alan pozitif psikoloji yaklaşımından almıştır (Linley vd., 2006, akt. Tösten, 2014). Daha sonra ise pozitif örgütsel davranış yaklaşımı içerisinde şekillenmiştir. Bu yaklaşımdaki temel görüş, pozitif bakış açısının örgütsel alana yansıtılarak çalışanların performans verimliliğini içsel kaynaklara dayandırmaktır. Bunu yaparken psikolojik sermaye ile içsel kaynakların keşfedilmesi, geliştirilmesi ve uygulanması amaçlanır (Akdoğan ve Polatçı, 2013, akt. İskenderoğlu ve Karaçıl, 2022). Psikolojik sermaye kavramı; iyimserlik, öz yeterlik, umut ve esneklik olarak dört boyuttan oluşmaktadır (Öğdem vd., 2021). Psikolojik sermayesi yüksek öğretmenlerin mesleklerinde karşılaştıkları güçlüklerle daha iyi baş edebildikleri, okul amaçlarına daha fazla bağlılık gösterdikleri, kalıcı başarının sağlanması için kendi gelişimlerine de daha çok önem verdikleri belirlenmiştir (Deviren, 2025). İşinden memnun, esnek, iyimser, öz yeterliği yüksek, çalıştığı kuruma umutla bakan çalışanların varlığı, çalışma ortamındaki pozitif psikoloji algısını yükseltmektedir (Korkmaz ve Çelik, 2021). Psikolojik sermayenin çalışanlar üzerinde motivasyon ve örgüte bağlılık üzerindeki etkisi, yabancılaşma kavramını anlamada önemli bir unsur olarak görülmektedir. Yani psikolojik sermaye ile birlikte okullarda en çok üzerinde durulması gereken kavramlardan biri, örgütsel yabancılaşmadır.

Örgütsel Yabancılaşma

Yabancılaşma kavramı temellerini felsefi açıdan Hegel'den almaktadır. Daha sonra Marks'ın çalışmalarıyla daha geniş bir çerçeveye yerleşerek toplumsal ve iktisadi alanı kapsayacak şekilde yorumlanmıştır. Dolayısıyla felsefi ve sosyolojik bir kavram olarak ortaya çıkan yabancılaşmanın daha sonra sosyo-psikolojik bir boyut kazandığı söylenebilir. Böylece araştırmacılar yabancılaşma kavramını günlük hayatta ve örgütlerde test edilebilir, ölçülebilir hale getirmişlerdir (Elma, 2003). Felsefeden hareketle şekillenerek örgütsel davranış literatürüne giren örgütsel yabancılaşma, çalışanın yetkileri, değişim ve gelişimdeki arzuları,

kendi yöneticileri tarafından takdir ve kabul edilme gibi ihtiyaçları karşılanmadığında yaşadığı doyumsuzluk durumu olarak tanımlanabilir (Örücü, Hasırcı ve Ergenler, 2022). Seeman (1959) yabancılaşmayı; güçsüzlük, anlamsızlık, normsuzluk, izolasyon ve kendine yabancılaşma olarak beş boyutta inceler (Elma, 2003). Elma (2003) ise İşe Yabancılaşma Ölçeği'ni n türçe uyarlamasında güçsüzlük (10 madde), anlamsızlık (11 madde), yalıtılmışlık (10 madde) boyutları ile okula yabancılaşma (7 madde) boyutlarıyla yeniden sınıflandırılmıştır. Ayrıca örgütsel yabancılaşma nedenleri, Demirel ve Ünal tarafından örgütsel ve çevresel olmak üzere iki ana başlığa ayrılmıştır (Karabulut, 2025). Sonuç olarak çalışanların örgütsel yabancılaşma yaşamamaları için çevresel ve örgütsel faktörlerin iyileştirilmesi gerekmektedir aksi takdirde bu faktörler, öğretmeni okuldan ve işinden uzaklaştıracaktır (Kayaalp, 2020). Bu nedenle örgütsel yabancılaşma kavramının eğitim kurumları çerçevesinde incelenmesi önemlidir.

Psikolojik Sermaye ve Örgütsel Yabancılaşma İlişkisi

Eğitim sisteminin temeli olan öğretmenlerin okula yabancılaşması istenmeyen bir durumdur; çünkü işine yabancılaşan öğretmen kendisini ve işini anlamsız ve önemsiz görmeye başlayacak, bağı azaldıkça da okula yönelik olumsuz tutum ve davranışlar sergileyecek, sorumluluklarına karşı aidiyet hissetmeyecek ve toplumun ortak değerlerine karşı ilgisiz, kayıtsız tavırlar sergileyecektir (Kayaalp, 2020). Kısaca mesleğine karşı yabancılaşma yaşayan öğretmen, öğrencileriyle verimli bir eğitim-öğretim süreci yürütemeyecektir (Karadaş, 2023). Yabancılaşma süreci çoğu zaman motivasyon kaybı, tükenmişlik ve mesleki doyumda azalma gibi olumsuz duygusal sonuçlar ile birlikte görülmektedir (Korkmaz ve Çelik, 2021). Yapılan çalışmalar, öğretmenlerin psikolojik sermaye düzeyinin düşmesinin örgütsel yabancılaşma riskini artırabileceğini göstermektedir. Şentürk ve Seçilmiş'in (2021), öğretmenler üzerinde ki çalışmalarında pozitif psikolojik sermaye alt boyutları ile birey örgüt uyumunun, örgütsel yabancılaşmayı etkileyen anlamlı bir etken olduğu; pozitif psikolojik sermayenin yabancılaşma üzerinde negatif ve anlamlı bir etkisi olduğu tespit edilmiştir. Bu doğrultuda Çetinkaya ve Koçyiğit (2021) yine öğretmenler üzerinde yapılan çalışmalarında psikolojik sermaye ile örgütsel sessizlik arasında negatif, düşük düzeyde ve anlamlı bir ilişki bulmuşlardır.

Buna rağmen yöneticiler ve öğretmenler arasında etkili bir iletişimin kurulması ile sağlıklı bir okul ortamı yaratılarak yabancılaşma önlenabilir (Örücü vd., 2022). Öğretmenlerin okul ortamında kendilerini güvende hissetmeleri, duygu ve düşüncelerini özgürce dile getirebilmeleri, diğer öğretmenler ve yöneticiler tarafından desteklenmeleri ve okullarına karşı aidiyet hissetmeleri eğitim-öğretim kalitesinin nitelikli biçimde gerçekleştirilmesini sağlar. Bunun neticesinde öğretmenlerin yabancılaşma algısından uzak duracağı muhtemel bir sonuçtur (Kayaalp, 2020).

Şekil 1: Kavramsal Model



Şekil 1’de görüldüğü üzere psikolojik sermaye ve örgütsel yabancılaşma arasında negatif bir ilişkinin varlığından söz edilebilir. Psikolojik sermayesi yüksek bireylerin yabancılaşma düzeylerinin düşük olduğu tam tersi bir durum olan psikolojik sermayenin düşüşü ile birlikte

yabancılaşmanın arttığına dair çalışmalar mevcuttur. Model alanyazındaki diğer çalışmalar temel alınarak oluşturulmuştur (Aydemir ve Akdoğan, 2018; Erol & Altun, 2020; Çetinkaya ve Koçyiğit, 2021; Şentürk ve Seçilmiş, 2021; Kurnaz vd., 2024).

Amaç

Bu çalışmanın amacı, öğretmenlerde psikolojik sermaye ve örgütsel yabancılaşma ilişkisini inceleyen ulusal ve uluslararası araştırmaları derleyerek literatürdeki eğilimleri ortaya koymaktır. Bu çalışma ile öğretmenlerin psikolojik sermaye kaynaklarının yükseltilmesine dayalı okul temelli düzenleme ve müdahale çalışmalarının yapılmasının önemine dikkat çekmek ve eğitim politikalarına yol göstermek istenmiştir. Ayrıca kavramın birlikte ele alındığı çalışmaların sınırlı olması nedeniyle literatürde var olan boşluğa dikkat çekerek mevcut literatürün bütüncül biçimde incelenmesi amaçlanmaktadır. Bu doğrultuda hedeflenen alt amaçlar şu şekilde sıralanabilir:

- Öğretmenlerde psikolojik sermaye ile örgütsel/işe yabancılaşma arasındaki ilişki literatürde nasıl ele alınmaktadır ve bu ilişkiye dair bulgular hangi yönde yoğunlaşmaktadır?
- Psikolojik sermayenin alt boyutları (özyeterlik, umut, iyimserlik, psikolojik dayanıklılık), öğretmenlerin örgütsel/işe yabancılaşma düzeyleriyle literatürde nasıl ilişkilendirilmektedir?
- Öğretmenlerde örgütsel/işe yabancılaşma, literatürde hangi örgütsel ve bireysel sonuçlarla birlikte ele alınmaktadır?

YÖNTEM

Bu çalışma, araştırma türü açısından geleneksel (narrative) literatür derlemesi olarak oluşturulmuştur. Geleneksel literatür çalışmasındaki amaç, o ana kadar alanyazında yapılmış çalışmaları bir araya getirmek ve mevcut bilgi birikimini sunmak, araştırmacılara yol göstermek ve kuramsal bir arka plan oluşturmaktır. (Jesson vd., 2011; akt. Yavuz, N., 2022). Bu doğrultuda öğretmenlerde psikolojik sermaye ve örgütsel yabancılaşma ilişkisini ortaya koyan araştırmaları sentezlemek amaçlanmıştır.

Çalışmada kullanılacak verilerin literatür taraması, “Google Akademik, Dergi Park, Ulusal Tez Merkezi (Yöktez), Web Of Science, EBSCOhost” tabanları üzerinden gerçekleştirilmiştir. Taramada “psikolojik sermaye”, “örgütsel yabancılaşma”, “psychological capital”, “organizational alienation”, “work alienation”, “öğretmen”, “teacher” anahtar sözcükleri kullanılmıştır. Çalışmanın literatür taraması Ekim 2025 tarihinde tamamlanmıştır. Çalışmalarda güncelliğin korunması için özellikle son 7 yılın çalışmalarına yer verilmiştir.

Çalışmaya dahil edilme kriterleri; (a) öğretmen örneklemini içermesi veya kuramsal katkı sunması, (b) psikolojik sermaye ve/veya örgütsel yabancılaşma değişkenlerini ele alması, (c) hakemli dergi veya lisansüstü tez olması, (d) Türkçe veya İngilizce dilinde yayımlanmış olması ve (e) tam metnine erişilebilir olması şeklinde belirlenmiştir.

Literatür taraması sonucunda güncellik, anahtar kavramlar ve örneklem kapsamında yapılan eleme çalışmaları değerlendirmeleri sonucunda 30 çalışma incelemeye alınmıştır. Çalışmalar konu ve örneklem uygunluğu çerçevesinde değerlendirilmiş; psikolojik sermaye ve örgütsel yabancılaşma ilişkisini ele alan, karşılaştırma yapılabilecek 23 nicel ve karma araştırma yöntemlerinden oluşan çalışma, bulguları tartışılmak üzere Tablo 1’de gösterilmiştir. Bu çalışmaların 3’ü öğretmen örneklemini içermiyor olmasına rağmen psikolojik sermaye ve örgütsel yabancılaşma ilişkisini birlikte inceleyen çalışma olması nedeniyle kuramsal katkı sağlayacağı düşünülmektedir. Geriye kalan 7 çalışmadan 2’si alanyazında psikolojik sermaye ve örgütsel yabancılaşma ölçeklerinin Türkçeye uyarlanması ile geçerlik ve güvenirlik çalışmalardan oluşurken; kalan 5 çalışma ise kavramsal açıklamaların desteklenmesi amacıyla yararlanılan kaynaklardan oluşmaktadır.

Araştırma kapsamında bulgularının yorumlanması için seçilen 23 çalışma; eşleştirilen kod numaraları, araştırma konusu, yazar ismi ve yılı, çalışmanın yapıldığı ülke, kullanılan araştırma yöntemleri ve örneklem başlıkları altında Tablo 1’de toplanmıştır.

Bu yaklaşım ile birlikte, öğretmenlerde psikolojik sermaye ve örgütsel yabancılaşma arasındaki ilişkinin literatürde hangi yöntemlerle ele alındığı, hangi değişkenlerle birlikte incelendiği ve hangi yönelimlerin öne çıktığı bütüncül bir biçimde ortaya konulmuştur.

BULGULAR

Tablo 1: Öğretmenlerde Psikolojik Sermaye ve Örgütsel Yabancılaşma ile İlgili Yapılan Çalışmalar

Kod	Araştırma ismi	Yıl / Yazar	Ülke	Araştırma Yöntemi	Örneklem
A1	Öğretmenlerin Psikolojik Sermaye, Örgütsel Sessizlik ve Örgütsel Yabancılaşma Düzeylerinin İncelenmesi	2021 / Çetinkaya ve Koçyiğit	Türkiye	Nicel Araştırma-İlişkisel Tarama Modeli	514 Öğretmen
A2	Eğitim Örgütlerinde Pozitif Psikolojik Sermaye, Birey-Örgüt Uyum ve Örgütsel Yabancılaşma Arasındaki İlişki	2021 / Şentürk ve Seçilmiş	Türkiye	Nicel Araştırma-İlişkisel Tarama Modeli	456 Öğretmen
A3	Psikolojik Sermayenin Örgütsel Yabancılaşma Üzerindeki Etkisinin Analizi	2024 / Kurnaz vd.	Türkiye	Nicel Araştırma-İlişkisel Tarama Modeli	175 Çalışan
A4	Psikolojik Sermayenin Örgütsel Yaşamda Yalnızlık ve Örgütsel Yabancılaşmaya Etkileri: Bankacılık Sektöründe Bir Araştırma	2020 / Erol ve Altun	Türkiye	Nicel Araştırma-İlişkisel Tarama Modeli	270 Banka Çalışanı
A5	Pozitif Psikolojik Sermayenin İşe Yabancılaşma Üzerindeki Etkisi	2018 / Aydemir ve Akdoğan	Türkiye	Nicel Araştırma / İlişkisel Tarama Modeli	339 Akademisyen
A6	Work Alienation and Unsafe Behavior in New-Generation Miners: Dual Mediation Effects and the Protective Buffer of Psychological Capital	2025 / Zhang ve Li	Çin	Nicel Araştırma / İlişkisel Tarama Modeli	457 İşçi
A7	Öğretmenlerin Psikolojik Sermaye ve Örgütsel Stres Kaynaklarının Bazı Değişkenlere Göre İncelenmesi	2021 / Kaplan	Türkiye	Nicel Araştırma-İlişkisel Tarama Modeli	364 Öğretmen
A8	Öğretmenlerin Pozitif Psikolojik Sermaye ve Örgütsel Özdeşleşmeleri Arasındaki İlişki	2021 / Yazkan ve Ordu	Türkiye	Nicel Araştırma-İlişkisel Tarama Modeli	351 Öğretmen
A9	Öğretmenlerin Psikolojik Sermaye ile Motivasyonları Arasındaki İlişkinin İncelenmesi	2025 / Deviren	Türkiye	Nicel Araştırma-İlişkisel Tarama Modeli	344 Öğretmen
A10	Pozitif Psikolojik Sermaye ile Öğretmen Liderliği İlişkisi	2020 / Ergül	Türkiye	Nicel Araştırma-İlişkisel Tarama Modeli	383 Öğretmen


INTERNATIONAL TOPKAPI CONGRESS VI

A11	Öğretmenlerin Örgütsel Psikolojik Sermaye ve Örgütsel Güvenlerine İlişkin Bir Çalışma.	2021 / Öğdem vd.	Türkiye	Nicel Araştırma-İlişkisel Tarama Modeli	220 Öğretmen
A12	Öğretmenlerin Algıladıkları Psikolojik Şiddet ile Pozitif Psikolojik Sermaye ve İş Yaşam Kalite Düzeyleri Arasındaki İlişkinin İncelenmesi.	2022 / Çelik İskenderoğlu ve Karaçıl	Türkiye	Nicel Araştırma-İlişkisel Tarama Modeli	384 Öğretmen
A13	Okullardaki Örgüt İklimi ile Öğretmenlerin Pozitif Psikolojik Sermaye Algıları Arasındaki İlişki	2022 / Sertel ve Karadağ	Türkiye	Nicel Araştırma - Korelasyonel Desen	382 Öğretmen
A14	Teacher Profiles of Psychological Capital and Their Relationship with Burnout.	2019/ Ferrad vd.	İspanya	Nicel Araştırma-Gizil Profil Analizi	1379 Öğretmen
A15	Psychological Capital, Mindfulness, And Teacher Burnout: Insights from Chinese EFL Educators Through Structural Equation Modeling.	2024/ Liu ve Du	Çin	Nicel Araştırma-İlişkisel Tarama Modeli	387 Öğretmen
A16	Teacher Career Calling Reduces Burnout: The Mediation Effects Of Work Engagement And Psychological Capital	2022/ Zhao vd.	Çin	Nicel Araştırma-İlişkisel Tarama Modeli	2929 Öğretmen
A17	Okullarda Örgütsel Demokrasi ve Örgütsel Yabancılaşmanın İncelenmesi	2022 / Karabulut	Türkiye	Karma Desen-İlişkisel Tarama Modeli	893 + 27 Öğretmen
A18	Öğretmenlerin Kaotik Liderlik, Örgütsel Yabancılaşma ve Örgütsel Mutluluk Algıları Arasındaki İlişkinin Yapısal Eşitlik Modellemesi ile İncelenmesi	2019 / Doğan	Türkiye	Nicel Araştırma-İlişkisel Tarama Modeli	404 Öğretmen
A19	Öğretmenlerin Örgütsel Sessizlik, Örgütsel Yalnızlık ve Örgütsel Yabancılaşma Algılarının Örgütsel Sinizm Düzeyleriyle İlişkisi	2020/ Kayaalp ve Özdemir	Türkiye	Nicel Araştırma-İlişkisel Tarama	50 Öğretmen
A20	Öğretmenlerin Örgütsel Yabancılaşma, Duygusal Emek ve Öğretme-Öğrenme Sürecindeki Davranışları Arasındaki İlişki	2024 / Kılınçoğlu ve Göksoy	Türkiye	Nicel Araştırma-İlişkisel Tarama	391 Öğretmen
A21	Öğretmenlerin Örgütsel Güven Algılarının Örgütsel Yabancılaşma Davranışları İle İlişkisi	2020 / Kovancı	Türkiye	Nicel Araştırma-İlişkisel Tarama	831 Öğretmen
A22	Covid-19 Pandemi Döneminde Öğretmenlerin Örgütsel Yabancılaşma Eğilimleri ile Tükenmişlik Seviyeleri Arasındaki İlişkinin İncelenmesi	2022/ Örucü vd.	Türkiye	Nicel Araştırma-İlişkisel Tarama Modeli	196 Öğretmen
A23	Teaching Autonomy And Teachers' Turnover Intentions Under the Labor Process Theory Perspective: A Moderated Mediation Model Of Work Alienation and Professional Identity	2025/ Wang	Çin	Nicel Araştırma-İlişkisel Tarama Modeli	500 Öğretmen


Psikolojik sermaye ve örgütsel yabancılaşma ilişkisini doğrudan inceleyen araştırmaların sınırlı olduğu görülmektedir. Ulusal düzeydeki çalışmalardan A1, A2 öğretmen örnekleme ile sınırlıyken; A3, A4, A5 kodlu çalışmalar farklı sektör çalışanları üzerinde incelemiştir. A6 kodlu çalışma ise Çin 'de farklı sektör çalışanları üzerinde yürütülmüş; kültürlerarası ve karşılaştırmalı bakış açısı sunması amacıyla incelemeye alınmıştır. Psikolojik sermayenin öğretmenler üzerindeki etkilerinin farklı değişkenler ile ilişkisini A7, A8, A9, A10, A11, A12, A13 kodlu çalışmalar ulusal düzeyde; A14 kodlu çalışma ise İspanya 'da; A15, A16 kodlu çalışmalar Çin'de ele alınmıştır. Örgütsel yabancılaşmanın öğretmenler ile ilişkisini inceleyen çalışmalardan A17, A18, A19, A20, A21, A22 ulusal düzeyde, A23 ise Çin'de gerçekleştirilmiştir. Ayrıca psikolojik sermaye ve örgütsel yabancılaşma arasındaki ilişkiye doğrudan odaklanan çalışmaların sayısı görece sınırlı olup, ulusal alanyazında yoğunlaşma göstermektedir.

Bu bulgular hem ulusal hem de uluslararası alanyazında öğretmenlerde psikolojik sermaye ve örgütsel yabancılaşma ilişkisini birlikte ele alan çalışmaların sınırlı olduğunu ve az sayıdaki çalışmalarla ele alındığını göstermektedir. Bu durum farklı kültürel bağlamlarda sürecin nasıl ilerlediğinin anlaşılmasını ve örüntülerinin tespit edilmesini zorlaştırmaktadır.

Grafik 1: Araştırma Desenlerine Göre Çalışmaların Dağılımı



Burada yer alan çalışmalar türleri bakımından incelendiğinde A17 kodlu çalışmada karma araştırma yönteminin kullanıldığı, geriye kalan 22 çalışmada nicel araştırma yönteminin kullanıldığı görülmektedir. Grafik 1 incelendiğinde çalışmaların yaklaşık %4'ünde karma, geriye kalan %96'sında nicel araştırma yöntemi kullanılmıştır. Çalışmaların %96'sının nicel olması öğretmenlerde psikolojik sermaye ve örgütsel yabancılaşma algılarının henüz nitel olarak derinlemesine incelenmediğini göstermektedir. Bu durum farklı birey, örgüt ve kültürlerde, arka planda yer alan süreçlerin nasıl işlediğini ortaya koyan bilgilere erişilmesini ve nedensel sonuçlara ulaşılmasını sınırlamaktadır.

Grafik 2: Araştırma Yıllarına Göre Çalışmaları Dağılımı

İncelenen araştırmalarda 23 çalışma, 2018-2025 yılları arasında gerçekleştirilmiştir. Bu durum çalışmaların güncel olması bakımından önemli bir bulgudur. Çalışmaların özellikle 2021-2022 yılları arasında yoğunlaştığı görülmektedir. Bu yoğunlaşma belirtilen yıllar arasında öğretmenlerde psikolojik sermaye ve örgütsel yabancılaşma konusuna akademik ilginin arttığına işaret etmektedir.

TARTIŞMA, SONUÇ VE ÖNERİLER

Derleme amacıyla incelenen 23 çalışmadan elde edilen bulgular, bu bölümde incelenecektir. Çalışma sonuçlarına göre öğretmenlerin psikolojik sermaye algıları orta ve yüksek düzeydedir. Psikolojik sermayelerinin yüksek olmasındaki önemli faktörlerden biri kendilerini mesleki olarak yeterli görmeleridir. Öğretmenlerde psikolojik sermayenin, örgütsel yabancılaşma ve örgüt düzeyindeki olumsuz algılarla negatif yönde; örgütsel özdeşleşme, örgütsel güven algıları, okul iklimi, iş bağlılığı, motivasyon gibi olumlu örgütsel değişkenlerle pozitif yönde ilişkili olduğu görülmektedir (A1, A2, A7-A12). Ayrıca diğer örneklemelerde yapılan çalışmalar da bu görüşü desteklemektedir (A3, A4, A5, A6). Bu doğrultuda psikolojik sermayenin yalnızca bireysel bir özellik değil, örgütsel bağlamla karşılıklı etkileşim içinde şekillenen bir yapı olduğu söylenebilir.

Öğretmenlerin yabancılaşmayla birlikte tükenmişlik, örgütsel sinizm, örgütsel yalnızlık, işten ayrılma niyeti ve düşük örgütsel mutluluk gibi algılara sahip olduğu görülmektedir (A17–A23). Ayrıca yabancılaşan öğretmenlerin liderlik, örgütsel demokrasi, öğretim özerkliği ve örgütsel güven gibi algılarında da azalma bulunmaktadır. Bir başka ifadeyle öğretmenlerde duygusal iyi oluş da dahil, örgütsel bağlılığı, meslekte kalma niyeti ve birçok örgütsel faktörde yabancılaşmaya paralel olarak artış gözlemlenmektedir.

Psikolojik sermaye ve örgütsel yabancılaşma arasındaki ilişkiler incelendiğinde, psikolojik sermaye ile özellikle yabancılaşmanın güçsüzlük, kendine yabancılaşma ve anlamsızlık boyutlarında ters yönlü ilişkiler olduğu; umut, özyeterlilik ve dayanıklılık boyutlarının yabancılaşmayı azaltıcı etkileri olduğu saptanmıştır. Bu bulgular doğrultusunda psikolojik sermayenin bireyin işini anlamlandırma, kontrol algısı geliştirme ve örgütsel süreçlerde kendini etkili hissetme gibi algılarına yönelik pozitif ilişkileri işaret etmektedir.

Psikolojik sermaye ve örgütsel yabancılaşma ilişkisinin incelendiği araştırma bulgularının benzer sonuçlar vermesi, öğretmenlerde psikolojik sermayenin örgütsel süreçlerin sağlıklı oluşu ile ilişkili olduğu görülmektedir. Örgütsel yabancılaşmanın ise örgüt ve birey düzeyinde pek çok yıpratıcı etkilerle ilişkili olması, psikolojik sermayenin eğitim örgütlerinde stratejik bir müdahale olarak kullanılması gerekliliğini desteklemektedir. Daha iyi bir eğitim öğretim ortamının yaratılmasında, okulların hedeflerine ulaşması açısından, öğretmenin bireysel faktörlerinin, eğitim öğretim kalitesini arttırmada tek başına yeterli olmadığı görülmektedir. Bu

bağlamda temelde okulların yöneticisi konumunda yer alan okul müdürlerine ve diğer paydaşlara, okul ikliminin güçlendirilmesi ve çevresel düzenlemelerin yapılması için pek çok sorumluluk düşmektedir. Böylece psikolojik kaynakların bütüncül olarak güçlendiği okulların bütüncül bir iyi oluş ile hedeflerine eksiksiz bir şekilde ulaşması sağlanabilir.

Bu çalışma, ulusal ve uluslararası alanyazında öğretmen örnekleminde psikolojik sermaye ile örgütsel yabancılaşmayı birlikte ele alan çalışmaların sınırlı olması, bu derlemenin özgünlüğünü artırmaktadır. Gelecek araştırmalarda öğretmenlerde psikolojik sermaye ve örgütsel yabancılaşma arasındaki ilişkiye ait daha fazla çalışmanın yapılması okul temelli müdahale yöntemlerinin oluşturulmasında yol gösterici olabilir. Ayrıca süreçlerin nasıl ortaya çıktığını betimlemek ve bağlamsal müdahale yöntemleri oluşturmak adına süreç odaklı çalışmalara ağırlık verilmesini daha da önemli ve gerekli hale getirmektedir.

KAYNAKÇA

Aydemir, C., & Akdoğan, A. A. (2018). Pozitif Psikolojik Sermayenin İşe Yabancılaşma Üzerindeki Etkisi. *Uluslararası İktisadi ve İdari İncelemeler Dergisi*, 307-318. <https://doi.org/10.18092/ulikidince.437760>

Çelik İskenderoğlu, G., & Karacil, M. (2022). Öğretmenlerin algıladıkları psikolojik şiddet ile pozitif psikolojik sermaye ve iş yaşam kalite düzeyleri arasındaki ilişkinin incelenmesi. *MEYAD Akademi*, 3(1), 14-41.

Çetinkaya, U. & Koçyiğit, M. (2021). Öğretmenlerin Psikoloji Sermaye, Örgütsel Sessizlik ve Örgütsel Yabancılaşma Düzeylerinin İncelenmesi, *International Journal of Eurasia Social Sciences (IJOESS)*, 12(46), 1011-1040. DOI: <http://dx.doi.org/10.35826/ijoess.3030>

Dash, S., & Vohra, N. (2019). The leadership of the school principal: Impact on teachers' job crafting, alienation and commitment. *International Journal of Educational Management*, 33(5), 1023-1039.

Deviren, İ. (2025). Öğretmenlerin psikolojik sermayeleri ile motivasyonları arasındaki ilişkinin incelenmesi. *İşletme Araştırmaları Dergisi*, 17(1), 265-282. <https://doi.org/10.20491/isarder.2025.1970>

Doğan, Ü., & Aslan, M. (2022). Öğretmenlerin kaotik liderlik, örgütsel yabancılaşma ve örgütsel mutluluk algıları arasındaki ilişkinin yapısal eşitlik modellemesi ile incelenmesi. *İnönü Üniversitesi Eğitim Fakültesi Dergisi*, 23(1), 460-485. <https://doi.org/10.17679/inuefd.1061369>

Elma, C. (2003). İlköğretim okulu öğretmenlerinin işe yabancılaşması (Ankara ili örneği) [Yayınlanmamış doktora tezi]. Ankara Üniversitesi, Eğitim Bilimleri Enstitüsü, Eğitim Bilimleri Anabilim Dalı.

Ergül, H. F. (2020). Pozitif psikolojik sermaye ile öğretmen liderliği ilişkisi. *EKEV Akademi Dergisi*, 84, 325-336. <https://orcid.org/0000-0002-3966-677X>

Erol, Y., & Altun, U. (2020). Psikolojik Sermayenin Örgütsel Yaşamda Yalnızlık ve Örgütsel Yabancılaşmaya Etkileri: Bankacılık Sektöründe Bir Araştırma. *Turkish Studies-Economics, Finance, Politics*, 15(4). DOI:10.47644/TurkishStudies.42964

Eser, İ., & Summak, M. S. (2020). Öğretmenlerin pozitif psikolojik sermaye ve etik liderlik algısının işle bütünleşmeyle olan ilişkisi. *Çağdaş Yönetim Bilimleri Dergisi*, 7(2), 180-205.

Ferradás, M. d. M., Freire, C., García-Bértoa, A., Núñez, J. C., & Rodríguez, S. (2019). Teacher profiles of psychological capital and their relationship with burnout. *Sustainability*, 11(18), 5096.

Kaplan, V. (t.y.). Öğretmenlerin psikolojik sermaye ve örgütsel stres kaynaklarının bazı değişkenlere göre incelenmesi. *Erciyes Üniversitesi Sosyal Bilimler Enstitüsü Dergisi*.

Karabulut, S. (2022). Okullarda demokrasi ve örgütsel yabancılaşmanın incelenmesi [Yayınlanmamış doktora tezi]. Ege Üniversitesi, Eğitim Bilimleri Enstitüsü, Eğitim Bilimleri Anabilim Dalı.

- Kayaalp, E., & Özdemir, T. Y. (2020). Öğretmenlerin örgütsel sessizlik, örgütsel yalnızlık ve örgütsel yabancılaşma algılarının örgütsel sinizm düzeyleriyle ilişkisi. *Dicle Üniversitesi Ziya Gökalp Eğitim Fakültesi Dergisi*, 1(38), 101–113.
- Kılınçoğlu, C., & Göksoy, S. (2024). Öğretmenlerin örgütsel yabancılaşma, duygusal emek ve öğretme-öğrenme sürecindeki davranışları arasındaki ilişki. *Abant İzzet Baysal Üniversitesi Eğitim Fakültesi Dergisi*, 24(1), 340–362. <https://doi.org/10.17240/aibuefd.2024.-1318993>
- Korkmaz, E. V., & Çelik, A. (2021). Pozitif psikolojik sermaye çalışmaları üzerine bir içerik analizi. *Atatürk Üniversitesi İktisadi ve İdari Bilimler Dergisi*, 35(3), 1189–1204. DOI:10.16951/atauniiibd.934028
- Kovancı, M. (2020). Öğretmenlerin örgütsel güven algılarının örgütsel yabancılaşma davranışları ile ilişkisi. *Dünya Multidisipliner Araştırmalar Dergisi*, 2020(1), 96–124.
- Kurnaz, G., Eroğlu, O., Altun, İ., Emen, E. (2024). Psikolojik Sermayenin Örgütsel Yabancılaşma Üzerindeki Etkisinin Analizi. *Artuklu Kaime*, 7(2), 156-170.
- Kurt, N., & Demirbolat Ottekin, A. (2022). Öğretmenlerin olumlu psikoloji göstergelerine genel bir bakış: Psikolojik sermaye, iş doyumu ve psikolojik iyi oluşun çeşitli değişkenler açısından incelenmesi. *Ahi Evran Üniversitesi Kırşehir Eğitim Fakültesi Dergisi*, 23(3), 2631–2657. DOI: 10.29299/kefad.1001118
- Liu, D., & Du, R. (2024). Psychological capital, mindfulness, and teacher burnout: Insights from Chinese EFL educators through structural equation modeling. *Frontiers in Psychology*, 15, 1351912.
- Öğdem, Z., Karakaş, A., & Bektaş, F. (2021). Öğretmenlerin örgütsel psikolojik sermaye ve örgütsel güvenlerine ilişkin bir çalışma. *Gazi Üniversitesi Gazi Eğitim Fakültesi Dergisi*, 41(2), 1121–1144.
- Örücü, E., Hasırcı, İ., & Ergenler, E. (2022). COVID-19 pandemi döneminde öğretmenlerin örgütsel yabancılaşma eğilimleri ile tükenmişlik seviyeleri arasındaki ilişkinin incelenmesi. *Doğuş Üniversitesi Dergisi*, 23(COVID-19 Özel Sayısı), 153–175. <https://doi.org/10.31671/doujournal.949484>
- Sertel, G., & Karadağ, E. (2022). Okullardaki örgüt iklimi ile öğretmenlerin pozitif psikolojik sermaye algıları arasındaki ilişki. *Marmara Üniversitesi Atatürk Eğitim Fakültesi Eğitim Bilimleri Dergisi*, 55(55), 318–350. <https://doi.org/10.15285/maruaebed.1010864>
- Şentürk, İ., & Seçilmiş, G. (2021). Eğitim örgütlerinde pozitif psikolojik sermaye, birey-örgüt uyumu ve örgütsel yabancılaşma arasındaki ilişki. *Troy Academy*, 6(1), 59–79. <https://doi.org/10.31454/troyacademy.890503>
- Tösten, R., & Özgan, H. (2014). Pozitif psikolojik sermaye ölçeği: Geçerlik ve güvenilirlik çalışması. *EKEV Akademi Dergisi*, 59, 429–442.
- Wang, G. (2025). Teaching autonomy and teachers' turnover intentions under the labor process theory perspective: A moderated mediation model of work alienation and professional identity. *Teaching and Teacher Education*, 159, 104076.
- Yavuz, N. (2022). Sosyal bilimlerde sistematik literatür analizi. *Pamukkale Üniversitesi Sosyal Bilimler Enstitüsü Dergisi*, (51), 347–360. DOI:10.30794/pausbed.1134606
- Yazkan, Ö., & Ordu, A. (2021). Öğretmenlerin pozitif psikolojik sermaye ve örgütsel özdeşleşmeleri arasındaki ilişki. *Muğla Sıtkı Koçman Üniversitesi Eğitim Fakültesi Dergisi*, 8(1), 274–288. DOI:10.21666/muefd.832221
- Yılmaz, Y., & Yıldırım, A. (2021). Öğretmenlerin algılarına göre örgütsel sinizm ile psikolojik sermaye arası ilişki. *Milli Eğitim Dergisi*, 50(229), 607–636.
- Zhao, X., Wu, K., Sun, B., & Li, W. (2022). Teacher career calling reduces burnout: The mediation effects of work engagement and psychological capital. *Frontiers in Psychology*, 13, 988467.

**WOMEN'S SELF-ESTEEM IN CONTEMPORARY AZERBAIJANI SOCIETY: THE
INTERACTION OF PSYCHOLOGICAL, LEGAL, SOCIAL, ECONOMIC, AND
RELIGIOUS-CULTURAL FACTORS**

Dos.Validə Əliyeva Rəcəb qızı
Azərbaycan Dövlət İqtisad Universiteti

Abstract. Contemporary Azerbaijani society is based on a secular and legal system. However, women's self-esteem and the formation of psychological self-awareness are not shaped solely within legal frameworks. Family structures, gender roles, the socio-cultural environment, and religious-cultural values are among the key factors that significantly influence women's self-perception and psychological well-being. In some cases, these factors support women's social adaptation; in others, they create contradictions between formal legal opportunities and actual social expectations, leading to psychological tension.

The aim of this study is to analyze the mechanisms of interaction among psychological, legal, and religious-cultural factors that affect women's self-esteem in contemporary Azerbaijani society. The research is conducted primarily through scientific-psychological and comparative approaches, as well as through the synthesis of existing research findings. The article has both theoretical and practical significance in terms of strengthening women's psychological well-being and supporting processes of social adaptation.

Women are among the leading subjects ensuring the cultural, social, and psychological sustainability of society. Their role is not limited to the institution of the family; rather, women play a crucial role in the transmission of social values, the preservation of intergenerational cultural memory, the formation of emotional stability, and the regulation of social relations. Women's psychological health and level of self-esteem directly affect intra-family relationships, children's socialization, interactions in the workplace, and the overall psychological climate of society. In modern society, women's active participation in education, employment, and legal life is one of the key indicators of social development. Conversely, low levels of self-esteem and negative self-perception among women may lead to tensions within family relationships, social adaptation difficulties, and adverse effects on overall societal well-being. Therefore, the study of these mechanisms and social support systems represents an actual scientific and social issue not only at the national but also at the global level.

Keywords: women's psychology, self-esteem, socio-cultural factors, legal determinants, religious-cultural values.

**MÜASİR AZƏRBAYCAN CƏMİYYƏTİNDƏ QADINLARIN
ÖZÜNÜQIYMƏTLƏNDİRMƏSİ: PSIXOLOJİ, HÜQUQİ, SOSIAL, İQTİSADI VƏ
DİNİ-MƏDƏNİ AMİLLƏRİN QARŞILIQLI TƏSİRİ**

Xülasə. Müasir Azərbaycan cəmiyyəti dünyəvi, hüquqi sistemə əsaslanır. Lakin cəmiyyətdə qadınların özünüqiymətləndirməsi və psixoloji özünüdərkini formalaşması yalnız hüquqi çərçivələrlə məhdudlaşmır. Ailə strukturları, gender rolları, sosial-mədəni mühit, dini-mədəni dəyərlər qadınların özünə münasibətinə və psixoloji rifahına əhəmiyyətli təsir göstərən əsas amillər sırasında yer alır. Bu amillər bəzi hallarda qadının sosial adaptasiyasını dəstəkləyərək, digər hallarda hüquqi imkanlarla real sosial gözləntilər arasında ziddiyyətlər yaradır və bu da psixoloji gərginliyə səbəb olur.

Tədqiqatın məqsədi müasir Azərbaycan cəmiyyətində qadınların özünüqiymətləndirməsinə təsir edən psixoloji, hüquqi və mədəni-dini amillərin qarşılıqlı təsir mexanizmlərini təhlil etməkdir. Tədqiqat əsasən elmi-psixoloji, müqayisəli yanaşma və eyni zamanda mövcud tədqiqat nəticələrinin ümumiləşdirilməsi əsasında aparılmışdır. Məqalə qadınların psixoloji rifahının gücləndirilməsi və sosial adaptasiya proseslərinin dəstəklənməsi baxımından nəzəri və praktik əhəmiyyət daşıyır. Qadın cəmiyyətin mədəni, sosial və psixoloji davamlılığını təmin edən əsas subyektlərdən ən öndəridir. Qadının rolu yalnız ailə institutu ilə məhdudlaşmır. Belə ki, qadın sosial dəyərlərin ötürülməsi, nəsillərarası mədəni yaddaşın qorunması, emosional sabitliyin formalaşdırılması və eləcə də, ictimai münasibətlərin tənzimlənməsi cəhətdən mühüm funksiyalar yerinə yetirir. Çünki qadının psixoloji sağlamlığı və özünüqiymətləndirmə səviyyəsi ailədaxili münasibətlərə, uşaqların sosiallaşmasına, eyni zamanda iş mühitində qarşılıqlı əlaqələrə, ümumilikdə cəmiyyətin psixoloji iqliminə birbaşa təsir göstərir. Müasir cəmiyyətdə qadının həm təhsil, həm əmək fəaliyyəti və hüquqi iştirak baxımından fəal olması sosial inkişafın mühüm göstəricilərindəndir. Yəni qadının özünüqiymətləndirmə və özünə münasibəti zəif olarsa, bu ailə münasibətlərində gərginliyə, sosial-adaptiv çətinliklərə və cəmiyyətin ümumi rifahına mənfi təsir göstərir. Bu baxımdan bu mexanizmlərin və sosial dəstək sistemlərinin araşdırılması təkcə milli deyil, qlobal səviyyədə də aktualıq kəsb edən elmi və sosial problemlərdir.

Açar sözlər: qadın psixologiyası, özünüqiymətləndirmə, sosial-mədəni amillər, hüquqi determinantlar, mədəni-dini dəyərlər.

Əsas hissə. Qadınların cəmiyyətdəki mövqeyi, onların sosial vəziyyəti antik dövrdən bu günə qədər daim diqqət mərkəzində olmuşdur. Cəmiyyətlərin iqtisadi sistemləri dəyişdikcə, insanların dünyagörüşü artdıqca qadınlara olan münasibət də dəyişmiş, onların malik olduqları hüquq və imtiyazlar genişlənməmişdir.

Banduraya görə fərdin öz imkanlarına dair inamı onun davranışlarının istiqamətini, qarşıya qoyduğu məqsədlərin səviyyəsini və çətinliklər qarşısında göstərdiyi psixoloji davamlılığı müəyyən edir. Özünə inam (self-efficacy) sosial mühitlə qarşılıqlı təsirdə formalaşır və insanın özünüqiymətləndirmə səviyyəsinə birbaşa təsir göstərir. Qadınların sosial və peşəkar fəaliyyətində özünə inamın zəifləməsi onların potensial imkanlarını reallaşdırmasına mane olur, adekvat özünüqiymətləndirmə isə sosial adaptasiyanı və psixoloji rifahı gücləndirən əsas mexanizmlərdən biri kimi çıxış edir. [1]

Rosenbergə görə özünüqiymətləndirmə fərdin öz dəyərinə verdiyi ümumi subyektiv qiymətləndirmədir və bu qiymətləndirmə yalnız şəxsi xüsusiyyətlərə deyil, həm də sosial münasibətlər, ictimai gözləntilər və mədəni mühitlə formalaşan qarşılıqlı təsirə əsaslanır. Qadınların özünüqiymətləndirmə səviyyəsi isə cəmiyyətdə mövcud olan gender rolları, sosial gözləntilər və mədəni-dini normativlər fonunda formalaşaraq daha mürəkkəb xarakter daşıyır. Bu baxımdan özünüqiymətləndirmə qadının özünü cəmiyyət daxilində necə dərk etdiyini, öz imkanlarını hansı ölçüdə reallaşdırma bildiyini və ona yüklənən sosial rollara nə dərəcədə uyğunlaşdığını müəyyən edən mühüm psixoloji mexanizm kimi çıxış edir. Adekvat özünüqiymətləndirmə qadının emosional sabitliyini, sosial adaptasiyasını və ailə ilə ictimai həyat arasında balans yaratmaq bacarığını gücləndirdiyi halda, qeyri-adekvat özünüqiymətləndirmə psixoloji gərginlik, sosial adaptasiya çətinlikləri və özünə inamın azalması ilə müşayiət oluna bilər. Bu səbəbdən qadınların özünüqiymətləndirməsi onların davranış strategiyalarına, ictimai fəallığına və ümumi psixoloji rifahına birbaşa təsir göstərən əsas tənzimləyici amillərdən biri hesab olunur. [2]

Müasir Qərbin qadınlara münasibəti sırf dini amillər əsasında deyil, əsasən dünyəvi və ictimai dəyişikliklər fonunda formalaşmışdır. Sosial münasibətlərin inkişafı qadınlar üçün nəzərdə tutulmuş sahələrin də genişlənməsinə səbəb olmuşdur. Qadınların tam hüquqi sosial-psixoloji imkanlara malik olması, onların haqlarının qorunması Qurani-Kərimdə, xüsusilə

“Nisa” surəsində öz əksini tapmışdır. Bu ayə qadının ikinci dərəcəli varlıq olmadığını, insan kimi kişi ilə bərabər yaradıldığını təsbit edir. Bu, İslam hüquq və etik sisteminin əsas başlanğıc nöqtəsidir. “Kişilərin qazandıqlarından öz payı vardır, qadınların da qazandıqlarından öz payı vardır.” (“Nisa”surəsi, 32-ci ayə) [3]. Qurani-Kərimin Nisa surəsində qadın kişi ilə ontoloji baxımdan bərabər insan kimi təqdim edilir və onun mülkiyyət, miras və iqtisadi fəaliyyət hüquqları açıq şəkildə təsbit olunur. Surədə qadın ailə və cəmiyyət daxilində hüquqi subyekt kimi tanınır, onun qazancı və mülkiyyəti üzərində sərbəst qərar vermək hüququ qorunur. Bununla yanaşı, ailədaxili münasibətlərdə sosial məsuliyyət bölgüsü göstərilir ki, bu da qadının sosial statusunun zəiflədilməsi deyil, ailə institutunun funksional sabitliyinin təmininə yönəlmişdir. Bu prinsiplər qadının özünüqiymətləndirməsinin formalaşmasında dini-mədəni mühitin mühüm determinant olduğunu göstərir.

Leila Ahmedin tədqiqatlarına görə, İslamın ilkin mətnlərində qadınlara tanınan hüquqlar və mənəvi status sonrakı tarixi mərhələlərdə formalaşmış sosial və mədəni praktikalar tərəfindən məhdudlaşdırılmışdır. Müəllif vurğulayır ki, qadınların cəmiyyətdəki mövqeyinin zəifləməsi dini prinsiplərin mahiyyətindən deyil, daha çox patriarxal sosial strukturların və yerli ənənələrin dini normalar kimi təqdim edilməsindən qaynaqlanır. Bu baxımdan dini-mədəni kontekst qadının özünüqiymətləndirmə səviyyəsinə həm də dolayı psixoloji təsir göstərərək, onun sosial fəallığına və hüquqi imkanlardan istifadəsinə təsir edən mühüm amil kimi çıxış edir.[4]

Dini-mədəni formada qadın və kişilərin təkcə hüquqlara malik olduğu deyil, eyni zamanda sosial, psixoloji, hüquqi və iqtisadi sahədə bərabərliyi xüsusi olaraq göstərilir. “Kişilərin qazandıqlarından öz payı vardır, qadınların da qazandıqlarından öz payı vardır” (Nisa surəsi, 32-ci ayə). Lakin bu bərabərlik hüququnun düzgün istifadə olunmaması, Şərq dünyasında qadına olan münasibətin təhrif edilməsi nəticəsində öz real məzmununu itirmişdir. Qeyd etmək lazımdır ki, BMT səviyyəsində insan inkişaf proqramlarında irəli sürülən əsas məsələlərdən biri də qadın hüquqlarının təmin olunmasının sosial-iqtisadi, hüquqi inkişaf üçün əsas şərt kimi qəbul edilməsidir. Bu istiqamətdə üç əsas prinsip müəyyən edilmişdir:

Birincisi, bütün cəmiyyət üzvləri üçün bərabər imkanların yaradılması; İkincisi, bu imkanların nəsildən-nəslə ötürülməsi; Üçüncüsü isə insan üçün real imkanların genişləndirilməsi.

Bu nəticə etibarilə 1993-cü ildə Vyanada keçirilmiş İnsan Hüquqları üzrə Ümumdünya Konfransında qəbul olunan Vienna Declaration and Programme of Action sənədi 171 dövlət tərəfindən konsensusla təsdiq edilmişdir və insan hüquqlarının universal, bölünməz və bir-biri ilə bağlı olduğunu təsdiqləyərək özünüqiymətləndirmə, bərabərlik və sosial hüquqlar kimi sahələrdə inkişaf prosesinə beynəlxalq hüquqi dəstək təmin etmişdir. [5]

Burada əsas diqqət sosial xidmətlərdən, təhsildən və səhiyyədən istifadə imkanlarında bərabər şəraitin yaradılmasına, sosial-siyasi iqtisadi sahədə qərarların qəbulunda qadın və kişilərin bərabər iştirakına yönəldilmişdir. Göründüyü kimi, kişi və qadın bərabərliyinin təmin olunması təkcə İslam ölkələrinin deyil, XXI əsrin global səviyyədə həll olunmalı fundamental problemlərindən biridir.

Dünyada mövcud olan bütün ictimai quruluşlarda qadın faktoru və rolu müxtəlif səviyyələrdə qiymətləndirilmişdir. İslam qadınlara əvvəllər görünməmiş hüquqlar bəxş etmişdir. Bu hüquqlar istər siyasət, əmlak, maddi nemətlər sahəsində olsun, istərsə də şəxsi azadlıqlar sahəsində olsun, qadınların kişilərlə bərabər hüquqlu tərəf kimi tanınmasına zəmin yaratmışdır. Dini- dünyəvi dövlətlər qadınlara verilən bu hüquqları artıq 1440 il bundan əvvəl təsbit etmişdir. Lakin çox təəssüf ki, uzun əsrlər boyu müsəlman ölkələrinin əksəriyyətində qadınların həm sosial, həm iqtisadi, həm də hüquqi mövqeləri zəifləmiş, onlara baxış çox zaman İslam normalarına deyil, yerli adət-ənənələrə əsaslanmışdır.

Dünyəvi dövlətlərdə qadınların fəallığının artması, onların istehsal və xidmət sahələrində iştirakının genişlənməsi, qadın əməyinin qiymətləndirilməsi və maddi

müstəqilliyinin təmin olunması ilə birbaşa əlaqədardır. Bu, həm qadının ailə daxilindəki mövqeyinin möhkəmlənməsinə, həm də cəmiyyətin ümumi inkişaf səviyyəsinin yüksəlməsinə təsir göstərmişdir.

Qadının sosial, hüquqi, siyasi, iqtisadi müstəqilliyi onun sosial statusunun möhkəmlənməsində əsas amillərdən biridir. Dini-dünyəvi dövlətlər qadına mülkiyyət hüququ vermiş, onun qazanc əldə etməsini, sərvət sahibi olmasını və bu sərvət üzərində sərbəst şəkildə qərar verməsini qanuni hesab etmişdir. Qadının əldə etdiyi gəlir onun şəxsi mülkiyyəti sayılır və bu gəlirə kişi tərəfindən hər hansı müdaxilə yolverilməz hesab olunur.

Dini-mədəni hüquq qadına mülkiyyət sahibi olmaq, qazanc əldə etmək və bu qazanc üzərində sərbəst şəkildə qərar vermək hüququ tanımışdır. Qadının əldə etdiyi gəlir onun şəxsi mülkiyyəti hesab olunur və bu gəlirin istifadəsinə kişinin müdaxilə etməsi yolverilməz sayılır. Bu prinsip qadının iqtisadi fəaliyyətinin hüquqi mexanizmlərlə qorunduğunu açıq şəkildə nümayiş etdirir.

Bununla yanaşı, qadının iqtisadi fəaliyyəti onun ailə və analıq funksiyalarına zidd deyildir. Əksinə, dini-mədəni təsir qadının həm ailə daxilində, həm də ictimai həyatda balanslı və məsuliyyətli rolunu təmin etməyə çalışır. Bu baxımdan qadının sosial-iqtisadi fəallığı onun sosial məsuliyyətinin tərkib hissəsi kimi dəyərləndirilir.

Müasir dövrdə dini-dünyəvi ölkələrin iqtisadi inkişaf səviyyəsini, əhəlinin sayını və sosial inkişaf göstəricilərini bir-biri ilə müqayisə etdikdə aydın görünür ki, bu ölkələrin hüquqi, sosial-iqtisadi quruluşu bir-birindən xeyli fərqlənir. Bu fərq ondan irəli gəlir ki, hər bir ölkədə əhəlinin sayı və tərkibi ilə əlaqədar olaraq sosial-psixoloji, iqtisadi fəaliyyətin həyata keçirildiyi mühit müxtəlifdir.

Nəticə. Aparılan təhlil göstərir ki, müasir Azərbaycan cəmiyyətində qadın problemi ilk növbədə hüquqi normaların mövcudluğu və ya olmaması ilə deyil, bu normaların sosial, mədəni və psixoloji mühitdə necə reallaşması ilə bağlıdır. Qadınların özünüqiymətləndirmə səviyyəsi formal hüquqi bərabərliklə real sosial gözləntilər arasındakı ziddiyyət fonunda formalaşır və bu ziddiyyət bir çox hallarda psixoloji gərginlik, özünə inamın zəifləməsi və sosial adaptasiya çətinlikləri ilə nəticələnir.

Tədqiqat nəticələri göstərir ki, qadının özünüqiymətləndirməsi yalnız fərdi psixoloji xüsusiyyətlərin məhsulu deyil, ailə strukturları, gender rolları, dini-mədəni şərtlər və sosial stereotiplərlə sıx bağlı olan çoxqatlı sosial mexanizmdir. Banduranın özünə inam, Rosenberg və Coopersmithin özünüqiymətləndirmə konsepsiyaları kontekstində aparılan təhlil sübut edir ki, qadınların psixoloji rifahı onların sosial və hüquqi imkanlardan istifadə etmək bacarığının əsas determinantlarından biridir. Adekvat özünüqiymətləndirmə qadının sosial fəallığını, ailə və ictimai həyat arasında balans yaratmaq imkanlarını gücləndirdiyi halda, qeyri-adekvat özünüqiymətləndirmə qadını həm sosial, həm də psixoloji baxımdan həssas vəziyyətə salır.

Beləliklə, qadın problemi müasir cəmiyyətdə yalnız gender bərabərliyi məsələsi deyil, eyni zamanda cəmiyyətin psixoloji sağlamlığını, sosial davamlılığını və inkişaf potensialını müəyyən edən fundamental məsələ kimi qiymətləndirilməlidir. Qadının özünüqiymətləndirməsinin gücləndirilməsi təkcə qadının deyil, bütövlükdə ailənin, nəsillərin sosiallaşmasının və cəmiyyətin uzunmüddətli inkişafının əsas şərtlərindən biri kimi çıxış edir.

References.

1. Bandura, A. (1997). *Self-efficacy: The exercise of control*. New York, NY: W. H. Freeman.
2. Rosenberg, M. (1965). *Society and the adolescent self-image*. Princeton, NJ: Princeton University Press.
3. The Qur'an. (1991). Baku: Elm Publishing House.
4. Ahmed, L. (1992). *Women and gender in Islam: Historical roots of a modern debate*. New Haven, CT: Yale University Press.
5. United Nations. (1993). *Vienna Declaration and Programme of Action*. World Conference on Human Rights, Vienna, 14–25 June 1993.

**YAPAY ZEKANIN FİKRİ VE SİNAİ MÜLKİYET HAKLARI AÇISINDAN
KULLANIMI**

**THE USE OF ARTIFICIAL INTELLIGENCE WITHIN THE FRAMEWORK OF
INTELLECTUAL AND INDUSTRIAL PROPERTY RIGHTS**

Yunus BULUT

Yüksek Lisans Öğrencisi, Kütahya Dumlupınar Üniversitesi, Lisansüstü Eğitim Enstitüsü,
Teknoloji ve İnovasyon Yönetimi Anabilim Dalı,
ORCID ID: 0009-0001-3618-8987

Arif GÖK

Prof. Dr., Kütahya Dumlupınar Üniversitesi, Mimarlık Fakültesi, Endüstriyel Tasarım
Bölümü, ORCID ID: 0000-0003-2840-9601

ÖZET

Yapay zekâ, özellikle üretken sistemlerin çok hızlı gelişmesiyle birlikte bu alana yapılan yatırımların gün geçtikçe artmasına neden olmakta ve ülkeler arasındaki rekabet giderek daha önemli bir hâl almaktadır. Yapay zekânın bu denli evrimsel bir gelişim göstermesi, büyük dil modellerinin geliştiricileri tarafından dahi öngörülemez bir geleceğin şekillenmesi anlamına gelebilmektedir. Son dönemde sağlık, finans, üretim, tarım ve eğlence gibi birçok sektörde yapay zekâ uygulamaları; verimlilik artışları, yenilikçi sistemler ve yeni meslek gruplarının ortaya çıkması gibi sonuçları ortaya çıkarmıştır. Tüm bu gelişmeler, teknoloji ile hukuk arasındaki ilişkinin yeniden değerlendirilmesini gerekli kılmaktadır.

Fikir üretimini özendirmek ve bunun sonucunda ekonomik, sosyal ve kültürel ilerlemeyi sağlamak amacıyla şekillenen fikri mülkiyet hukuku sürecinde, yapay zekâ alanında yaşanan gelişmeler önemli etkiler yaratmakta; özellikle üretken yapay zekânın günlük hayattaki hızlı dönüşümü yeni hukuki sorunları beraberinde getirmektedir. Yapay zekâ büyük dil modelleri, belge ve görsel gibi dokümanlar aracılığıyla eğitilebilmekte; ancak bu dokümanlarda yer alan verilerin kullanıcıların erişimine sunulması hâlinde, bir hak ihlali oluşturup oluşturmadığı tartışılmaktadır. Bu durum, söz konusu dokümanların kullanım koşulları ve kapsamına ilişkin belirsizlikleri gündeme getirmektedir. Bununla birlikte, üretken yapay zekâ tarafından ortaya konulan buluşlar, fikirler, görseller ve videolar gibi içerik ve çıktılar bakımından fikri mülkiyet hak sahipliğinin kime ait olduğu konusu da belirsizliğini sürdürmektedir. Bu nedenle son dönemde, ilgili alanlarda önemli yasal güncellemeler yapılmakta ve hukuki çalışmalar artmaktadır. Bu çalışmanın amacı, üretken yapay zekâ ile fikri mülkiyet hakları arasındaki ilişkiyi bütüncül bir bakış açısıyla ele almak ve mevcut hukuki boşlukların inovasyon ile yaratıcılığın korunması arasındaki hassas denge üzerindeki etkilerini incelemektir.

Anahtar Kelimeler: Buluş Sahipliği, Eser Koruması, Fikri Mülkiyet, Patent, Üretken Yapay Zeka.

ABSTRACT

Artificial intelligence, particularly with the rapid development of generative systems, has led to a continuous increase in investments in this field, while competition among countries has become increasingly significant. The evolutionary pace of artificial intelligence may result in the emergence of a future that is difficult to predict even for the developers of large language models. In recent years, artificial intelligence applications in sectors such as healthcare, finance, manufacturing, agriculture, and entertainment have produced outcomes including increased

efficiency, the development of innovative systems, and the emergence of new professional fields. These developments make it necessary to reconsider the relationship between technology and law.

Within the framework of intellectual property law, which aims to encourage creativity and thereby promote economic, social, and cultural progress, advancements in artificial intelligence have had a substantial impact. In particular, the rapid integration of generative artificial intelligence into everyday life has given rise to new legal challenges. Large language models are trained using documents such as texts and images; however, whether the use and accessibility of data contained in these materials constitute an infringement of rights remains a subject of debate. This situation raises uncertainties regarding the conditions and scope of the use of such materials. Furthermore, the question of ownership of intellectual property rights over outputs generated by generative artificial intelligence—such as inventions, ideas, images, and videos—continues to remain unclear. For this reason, significant legal updates have recently been introduced, and legal studies in this area have increased. The aim of this study is to examine the relationship between generative artificial intelligence and intellectual property rights from a holistic perspective and to analyze the effects of existing legal gaps on the delicate balance between innovation and the protection of creativity.

Keywords: Inventorship, Copyright Protection, Intellectual Property, Patent, Generative Artificial Intelligence.

GİRİŞ

Önemli ekonomik ve toplumsal dönüşümlere yol açan Sanayi Devrimi, fiziksel emeğin makinelerle devredildiği, verimliliğin arttığı ve maliyetlerin düştüğü bir çağın kapılarını aralamıştır. Ancak bu tarihsel dönüşümün son halkası olan yapay zeka, bugün büyük dil modelleriyle sadece fiziksel emeği değil, zihinsel üretimi ve yaratıcılığı da kökten dönüştürerek geliştiricilerinin dahi öngöremediği bir hıza ulaşmıştır. (Sarı, 2020).

Gelinen noktada insanlar, sosyal medyada gördükleri bir videonun gerçekliğini sorguladıkları, insan yapımı olup olmadığını ayırt edemedikleri bir "büyülenme" aşamasına ulaşmıştır. Şimdiye kadar teknoloji dünyasının ve toplumun ana gündemi, "Acaba yapay zeka ileride bunu yapabilir mi?" sorusu etrafında şekilleniyordu. Ancak Stanford Üniversitesi Human-Centered AI (HAI) merkezinin 2026 öngörülerinin de işaret ettiği gibi, teknoloji dünyası artık yeni bir eşiktir: "yapay zeka müjdeciliği" dönemi bitiyor, yerini "değerlendirme" dönemi alıyor. Bu yeni süreçteki öngörülere göre, yapay zekanın sadece düşünülenleri yapabilmesi yeterli görülmeyecek; asıl odak noktası, teknolojinin bu çıktıyı ne kadar mükemmellikte, ne kadar güvenilir, ne kadar verimli ve hangi maliyetle yapabildiği olacaktır.

Stanford'dan Erik Brynjolfsson'un 2026 yılına dair öngörüsüne göre; artık yöneticiler, yapay zekanın etkilerini yıllar sonra değil, tıpkı borsa verileri gibi günlük ve aylık olarak izleyebilecek; kimin geride kaldığını ve hangi becerilerin değer kazandığını net verilerle görebileceklerdir. Önümüzdeki süreç, yapay zekanın sunduğu spekülâtif vaatlere kapılmaktan ziyade; onun yarattığı ekonomik ve toplumsal değeri titizlikle ölçtüğümüz bir "gerçekçilik yılı" olacaktır. Stanford uzmanı Angèle Christin'in 2026 yılına dair öngörüsüne göre; bu durum sektördeki abartılı beklenti atmosferinin tamamen yok olması anlamına gelmeyebilir; ancak bu kontrolsüz büyüme evresinin artık doygunluğa ulaşacağı ve beklentilerin daha rasyonel bir zemine oturacağı kesindir.

Yapay zekâ teknolojilerindeki hızlı gelişim, yalnızca teknik ve ekonomik alanlarda değil, aynı zamanda yaratıcılık, buluş sahipliği ve mülkiyet kavramlarının hukuki temellerinde de köklü bir dönüşüme yol açmaktadır. Yapay zekânın sanat, edebiyat, müzik ve buluş üretme kapasitesine ulaşması, telif hakkı, patent, ticari sır ve marka hukuku başta olmak üzere fikri ve sınai mülkiyet rejimlerini benzeri görülmemiş sorularla karşı karşıya bırakmaktadır. Mevcut hukuk sistemleri; yapay zekânın "yazar" veya "mucit" olarak kabul edilip edilemeyeceği, yapay

zekâ tarafından üretilen çıktılarda hak sahipliğinin kime ait olacağı, özgünlük ve yenilik kriterlerinin nasıl belirleneceği ve ihlal hâllerinde sorumluluğun nasıl tesis edileceği gibi temel meseleleri yeniden değerlendirmek zorunda kalmaktadır. Bu bağlamda, Dünya Fikri Mülkiyet Örgütü (WIPO) başta olmak üzere uluslararası kuruluşlar ve ulusal hukuk sistemleri, yapay zekâ çağında fikri mülkiyet hukukunun etkinliğini koruyabilmesi için yeni politika ve düzenleme arayışlarına yönelmektedir. (Bharati, 2024)

Modern fikri mülkiyet hukukunun temelini oluşturan Paris Sözleşmesi (1883) ve Bern Sözleşmesi (1886), sınai ve edebî eserlerin korunmasına ilişkin evrensel ilkeleri belirlemiştir; bu ilkeler zamanla ulusal mevzuatlar ve uluslararası anlaşmalar yoluyla geliştirilmiştir. Bu çerçevede fikri mülkiyet hukukunda ülkesellik, sınırlı süre, kamusal açıklık (ifşa) ile özgünlük ve yenilik şartları temel prensipler olarak kabul edilmektedir. Ancak dijital teknolojilerin ve internetin yaygınlaşması, bu geleneksel çerçeveleri zorlamış; başta ABD’de kabul edilen Dijital Binyıl Telif Hakkı Yasası (DMCA) olmak üzere çeşitli uyarlayıcı düzenlemeleri gerekli kılmıştır (Bharati, 2024).

Yapay zekâ çağında ise bu yerleşik ilkeler daha önce karşılaşılmamış bir sınamadan geçmektedir. Yapay zekâ sistemlerinin bağımsız veya yarı bağımsız biçimde yaratıcı eserler üretmesi ve buluş süreçlerine katkıda bulunması; yazarlık, mucitlik ve hak sahipliği kavramlarının insan merkezli yapısını tartışmaya açmaktadır. Bu durum, fikri mülkiyet korumasının kapsamının ne olması gerektiği, korumanın kime tanınacağı ve hangi ölçütlerin esas alınacağı gibi soruları gündeme getirerek, mevcut hukuki rejimlerin yapay zekâ gerçekliği karşısında yeniden değerlendirilmesini kaçınılmaz hâle getirmektedir (Bharati, 2024).

ARAŞTIRMA VE BULGULAR

Günümüzde, bir makinenin anlamlı ve yaratıcı bir ürün ortaya koyamayacağı yönündeki erken dönem kuşkuvarın hızla aşıldığı görülmektedir. Yapay zekâ sistemleri artık yalnızca teknik süreçleri destekleyen araçlar olmaktan çıkmış; resimden müziğe, edebiyattan görsel sanatlara uzanan geniş bir alanda yaratım sürecine doğrudan dâhil olmuştur. Bu durum, ortaya çıkan ürünlerin estetik ya da kültürel değer taşıyıp taşımadığı tartışmasının ötesine geçerek, insan yaratıcılığı ile makine üretimi arasındaki sınırların nasıl çizileceği sorusunu hukuk ve özellikle fikrî mülkiyet alanı bakımından yeniden ve daha derinlikli biçimde ele almayı gerekli kılmaktadır (Taner, 2023).

Yapay zeka ile ilgili tartışmalar çoğu zaman “robotlar insanların işini elinden alıyor” söylemi etrafında dönse de, asıl sorun daha farklıdır. Asıl risk, bilgiyle ve düşünerek çalışan meslek gruplarının emeğinin zamanla değer kaybetmesidir. Yazarlar, gazeteciler, akademisyenler ve hukukçular, yapay zekânın çok hızlı ve çok sayıda içerik üretebilmesi nedeniyle, piyasanın içerikle dolması ve insan üretiminin ekonomik karşılığını yitirmesi tehlikesiyle karşı karşıyadır. Bu durum, sanayi devriminde makinelerin mavi yakalıları etkilemesine benzer şekilde, bugün de zihinsel emekle çalışanlar açısından köklü bir dönüşüme işaret etmektedir. Geleceğe yönelik tartışmalar daha çok şeffaflık, lisanslı veri kullanımı ve yapay zekâ ile üretilen içeriklerin açıkça ayırt edilebilir olması üzerinde yoğunlaşmaktadır. Buna bağlı olarak hukuk, yapay zekâ çağında insan katkısının sınırlarını yeniden çizmeye çalışmakta; yeniliği engellemeden yaratıcının emeğini koruyacak bir denge arayışını sürdürmektedir (Chesterman, 2025).

Yapay zekâdaki bu gelişmeler, telif, patent ve marka gibi fikrî mülkiyet hukuku üzerinde ciddi bir baskı yaratmaktadır. İnsan yaratıcılığı ve inovasyonu merkeze alan geleneksel hukuk sistemlerinin, yapay zeka tarafından üretilen çıktılar karşısında nasıl etkileneceğini ve bu temel ilkelerin nasıl evrileceğini yeniden değerlendirmek gerekecektir (Bharati, 2024).

Bazı görüşler yapay zekâyı hukuki kişilik verilmesini savunsa da, bugün daha baskın olan yaklaşım yapay zekâyı insan yaratıcılığını destekleyen bir araç olarak görmek ve mucitlik kavramının merkezinde insanı tutmaktadır. Buna karşılık, büyük teknoloji şirketlerinin yapay zekâ sayesinde ortaya çıkan fikrî mülkiyet üzerinde aşırı güç elde etme ihtimali ciddi etik

kaygılar doğurmaktadır. Bu durum, hukukun yalnızca yeniliği teşvik etmekle yetinmemesi, aynı zamanda adil bir paylaşımı da gözetmesi gerektiğini açıkça ortaya koymaktadır (Bharati, 2024). Şirketler, yapay zekâ algoritmalarını ve bu sistemleri eğitmek için kullandıkları verileri gizli tutarak rekabet avantajı elde etmeye çalışmaktadır. Ancak tersine mühendislik, çalışanların şirket değiştirmesi ve şeffaflık talepleri, bu gizliliğin ne kadar korunabileceğini tartışmalı hâle getirmektedir (Bharati, 2024).

Bugün, daha önce sadece teorik olarak tartışılan sorunların artık mahkemelerde somut davalara konu olduğu görülmektedir. İlk yargı kararları, yapay zekânın telifli eserleri eğitim amacıyla kullanmasının bir problem olarak görülmeyle çoğu zaman “dönüştürücü kullanım” olarak değerlendirmeye eğilimlidir. Ancak bu durum, yapay zekâyı sınırsız bir serbestlik tanıdığı anlamına gelmemektedir. Özellikle korsan kitapların ya da izinsiz görsellerin sistem içinde saklanması ve depolanması, bazı mahkemeler tarafından açıkça adil kullanım dışında bırakılmaktadır (Bannigan vd., 2025).

Bununla birlikte, haber ajansları veya veri tabanlarıyla doğrudan rekabet eden ve insan yaratıcılığı içermeyen yapay zekâ sistemlerinin eğitimi de hukuken korunmamaktadır. Mahkemeler bu tür davalarda, yapay zekâ çıktılarının özgün eserlerin yerini alıp almadığına, yani yazarın, gazetecinin veya sanatçının ekonomik alanını fiilen ortadan kaldırıp kaldırmadığına özellikle dikkat etmektedir. Bu nedenle, eğitim süreci ilk bakışta hukuka uygun görünse bile, ortaya çıkan ekonomik sonuçlar davaların sonucunu belirleyici hâle gelmektedir (Bannigan vd., 2025).

Bugün büyük medya şirketleri ve eğlence sektörü, yapay zekâyı ilgili hukuki tartışmaların merkezinde yer almaya başlamıştır. Disney ve Universal gibi stüdyolar, sadece eserlerinin yapay zekâ eğitiminde kullanılmasına değil, aynı zamanda ünlü karakterlerinin neredeyse birebir kopyalanmasına da dava açmaktadır. Benzer şekilde, bazı davalarda ChatGPT gibi sistemlerin popüler dizileri ya da kitapları çok ayrıntılı biçimde özetlemesi, kabul edilebilir sınırların aşıldığı bir kullanım olarak görülmüştür. Buna karşılık, bazı şirketler mahkemeye gitmek yerine lisans anlaşmaları yapmayı tercih etmektedir. Bu süreçlerde mahkemeler, yapay zekâ şirketlerinden eğitim verilerini ve şirket içi yazışmaları talep etmekte; şirketler ise bunların ticari sır olduğu gerekçesiyle gizli kalmasını istemektedir. Ayrıca yapay zekânın yanlış bilgi üretmesi ya da bir içeriği hatalı biçimde tanınmış bir markaya atfetmesi, telif hukukunun yanı sıra marka ihlali sorunlarını da gündeme getirmektedir (Bannigan vd., 2025).

Yapay zekânın çok hızlı ve büyük ölçekte üretim yapabilmesi, insan yaratıcılığı esas alınarak geliştirilen klasik özgünlük ve yenilik ölçütlerini yetersiz kılmaktadır. Öte yandan, bir ihlal ortaya çıktığında sorumluluğun kime ait olacağı da net değildir. Geliştiricinin mi yoksa sistemi kullanan kişinin mi sorumlu tutulacağı, özellikle sınır aşan faaliyetlerde daha da karmaşık hâle gelmektedir. Bu nedenle, kusura dayalı olmayan sorumluluk modelleri gibi daha esnek bir hukuki yaklaşıma ihtiyaç duyulmaktadır (Bharati, 2024).

Bununla birlikte, fikri mülkiyet haklarının güçlü bir şekilde korunması, sadece hukuki bir gereklilik değil, aynı zamanda şirketlerin yapay zeka teknolojilerine yatırım yapması için en büyük motivasyon kaynağıdır. Han ve arkadaşlarının (2025) Çin'deki halka açık şirketler üzerinde yaptığı geniş kapsamlı araştırmaya göre, devletin “Fikri Mülkiyet Model Şehirleri” gibi projelerle kuralları sıkılaştırdığı bölgelerde, şirketlerin yapay zeka geliştirme faaliyetleri gözle görülür şekilde artmıştır. Bunun sebebi, hukuki korumanın artmasıyla birlikte, şirketlerin teknolojilerinin çalınmasına yönelik duydukları kaygı da aynı oranda hafiflemektedir. Kendini güvende hisseden şirket, inovasyona daha cesur bütçeler ayırmaktadır. Bu da gösteriyor ki, sağlam bir hukuk sistemi, teknolojik gelişimin önündeki engelleri kaldıran ekonomik bir kaldıraç görevi görmektedir (Han vd., 2025).

Telif, Patent, Marka Hukuku

Telif hukuku, eserlerin bilinçli ve yaratıcı bir insan tarafından üretildiği varsayımına dayanır. Ancak yapay zekâ, çok az insan müdahalesiyle metin, görsel veya müzik üretebilmektedir. Bu

durum, ortaya çıkan eserin kime ait olduğu sorusunu belirsiz hâle getirmektedir. Geliştirici, kullanıcı ve eğitim verisini sağlayanlar gibi birçok aktör sürece dâhil olduğunda, hak sahipliğini belirlemek daha da zorlaşmaktadır. Bu kapsamda, üretilen içeriklerde özgünlüğün nasıl ölçüleceği, yapay zeka ile ortak paydada yapılan çalışmalarda hakların kime ait olacağı, ilgili eserlerde klasik koruma sürelerinin geçerli olup olmayacağı gibi sorunlar gün yüzüne çıkmaktadır (Bharati, 2024).

Fikri mülkiyet tartışmalarının gölgesinde kalan ancak en az onun kadar kritik olan bir diğer mesele de, yapay zekanın hafızası ve veri gizliliğidir. Yapay zeka modelleri eğitildikleri verileri sadece öğrenmekle kalmaz, adeta ezberler. Bir veriyi veri tabanından silebilirsiniz, ancak eğitilmiş bir modelin parametrelerine işlemiş bir bilgiyi sildirmek, yani “Makineye Unutturmak”, şu an için büyük bir teknolojik bilinmezliktir. Hatta İtalya'nın 2023 yılında veri güvenliği endişeleriyle ChatGPT'yi geçici olarak yasaklaması, bu sorunun ne kadar ciddi olduğunun somut bir kanıtıdır (Novelli vd., 2024).

Benzer belirsizlikler patent hukukunda da ortaya çıkmaktadır. Yapay zekânın buluş sürecinde belirleyici olduğu durumlarda, mucidin kim olduğu, buluşun gerçekten “yeni” sayılıp sayılmayacağı ve tamamen otonom şekilde geliştirilen buluşların kime ait olacağı, insan katkısının sınırları ve patentlenebilirlik kriterleri içerisinde yer alan buluş basamağı gibi temel kriterlerin nasıl uygulanacağı net değildir. Bu nedenle hukuk literatüründe farklı çözüm yolları tartışılmaktadır. Bunlar arasında hakların yalnızca insanlara verilmesi, yapay zekâyâ özgü yeni hak türlerinin oluşturulması ya da bazı yapay zekâ çıktılarının kimseye ait sayılmayarak kamuya bırakılması gibi yaklaşımlar yer almaktadır (Bharati, 2024).

Günümüzde telif ve patent hukuku, yapay zekâ karşısında yetersiz kaldığı durumlar yaşayabilirken, ticari sır ve marka hukuku daha az doğrudan etkilenmektedir. Yapay zekânın marka isimleri ve logolar üretmesi, tescil süreçlerinde kullanılması ve sanal asistanlar aracılığıyla tüketiciye ürün önermesi marka hukuku açısından yeni sorunlar doğurmaktadır (Bharati, 2024).

Yapay Zekâ İle Üretilen Çıktıların Fikrî Mülkiyet Hukukundaki Konumu: Uluslararası Yaklaşımlar Ve Türk Hukuku Açısından Değerlendirme

Uluslararası alanda bakıldığında, yapay zekâ ile fikrî mülkiyet arasındaki ilişki için henüz ortak bir yaklaşım bulunmamaktadır. ABD ve Avrupa Birliği gibi birçok ülkede telif ve patent hukukunda insan yaratıcılığı temel alınmaya devam edilmekte, yapay zekâ hak sahibi ya da mucit olarak kabul edilmemektedir. Buna karşılık, Birleşik Krallık bazı bilgisayar üretimi eserler için daha esnek ve farklı düzenlemeler getirmiştir. Çin ve Japonya ise yapay zekâ teknolojilerinin hızla gelişmesi karşısında mevcut hukuk sistemlerini uyarlamaya çalışmakta, mahkeme kararları ve idari kılavuzlarla belirsizlikleri azaltmayı hedeflemektedir (Bharati, 2024).

Bu tartışmaların somut bir örneği, ABD Patent ve Marka Ofisi'nin (USPTO) 2025 sonunda yayımladığı yeni kılavuzda görülmektedir. USPTO, bu kılavuzla birlikte yapay zekâyâ bakışını değiştirmiştir. Artık yapay zekâ, bir “ortak mucit” olarak değil; laboratuvar cihazı ya da yazılım gibi, insanın kullandığı bir araç olarak kabul edilmektedir. Bu nedenle, yapay zekâ ile geliştirilen buluşlar için özel ya da daha esnek bir patent ölçütü getirilmemiştir. Mevcut patent kuralları aynen uygulanmaya devam etmektedir. Buna göre, patent alınabilmesi için buluş fikrinin mutlaka bir insanın zihninde oluşmuş olması gerekir. Yapay zekânın sürece katkı sunması tek başına yeterli değildir. Asıl önemli olan, insanın belirli ve somut bir teknik fikre gerçekten sahip olup olmadığıdır. Yani, yeni kılavuz, yapay zekânın mucit olarak gösterilmesi hâlinde başvurunun reddedileceğini açıkça ortaya koyabilecektir. Buna bağlı olarak, buluşta insanın ne yaptığı ve sürece nasıl katkı sunduğu artık çok daha önemli hâle gelmiştir. Yapay zekâdan yararlanılan buluşlarda, verilen komutların, insan tarafından yapılan seçimlerin ve son teknik kararların açık biçimde belgelenmesi gerekmektedir. Aksi takdirde, insan katkısının yeterli kabul edilip edilmeyeceği belirsiz kalmaktadır. Özellikle insan müdahalesinin çok sınırlı

olduğu durumlarda, patent yerine ticari sır gibi başka koruma yollarının düşünülmesi daha gerçekçi olabilir. Tüm bu gelişmeler, yapay zekânın buluş sürecinde önemli bir rol oynadığını kabul etmekle birlikte, patent hukukunun merkezinde hâlâ insan yaratıcılığının yer aldığını göstermektedir (McDonough ve Bannister, 2025).

Ülkeler arasındaki bu dağınık tablo karşısında, WIPO'nun öncülük ettiği çalışmalar küresel ölçekte ortak bir dil ve anlayış oluşturmayı hedeflemektedir. WIPO tarafından hazırlanan raporlar ve yürütülen istişareler, yapay zekânın telif ve patent hukukunu nasıl değiştirdiğini ortaya koymaktadır. Aynı zamanda, mevcut uluslararası anlaşmaların bu yeni duruma uyarlanması gerektiğine de dikkat çekilmektedir. TRIPS, WIPO, internet antlaşmaları ve PCT gibi temel metinlerde yapay zekâyâ özgü açık kurallar henüz yer almamaktadır. Buna rağmen, veri paylaşımı, etik yapay zekâ standartları ve deneme amaçlı düzenleyici modeller alanında gelişen iş birlikleri, gelecekte daha uyumlu bir yaklaşımın mümkün olabileceğini göstermektedir. Asıl sorun ise, yapay zekâ çağında fikrî mülkiyeti etkili biçimde korurken, ülkelerin kendi düzenleme yetkisi ile küresel uyum ihtiyacı arasında dengeli bir çözüm bulmaktır (Bharati, 2024).

Dünyadaki genel tartışmalar bir kenara bırakıldığında, meselenin Türk Hukuku açısından ele alınması hâlinde daha karmaşık bir tabloyla karşılaşılabilir. Bunun temel nedeni, yapay zekâ kavramının tek tip bir yapıyı ifade etmemesidir. Basit girdilere tepki veren sistemlerden, soyut düşünme yeteneği bulunan ve hatta kendi varlığının farkında olduğu iddia edilen ileri düzey modellere kadar uzanan geniş bir yelpazeden söz edilmektedir. Buna karşılık, 5846 sayılı Fikir ve Sanat Eserleri Kanunu, eser kavramını açık ve katı bir temele oturtmaktadır. Kanun'a göre bir ürünün "eser" olarak kabul edilebilmesi için insan zihninin ürünü olması ve meydana getiren kişinin hususiyetini taşıması zorunludur. Bu nedenle mevcut mevzuat çerçevesinde, yapay zekâ tarafından üretilen çıktılara doğrudan "eser" niteliği tanınmasının teknik ve hukuki açıdan mümkün olmadığı yönünde bir değerlendirme yapılmaktadır (Güner ve Şatır, t.y.).

Örneğin, yapay zekâ tarafından üretilen ürünlerin kimseye ait olmaması ve doğrudan kamu malı sayılması önerildiğinde, bu alana ciddi ekonomik yatırımlar yapan şirketlerin yatırım motivasyonunun zayıflayabileceği ifade edilmektedir. Buna karşılık, tüm hakların doğrudan yazılımcıya tanınması yaklaşımı da ikna edici bulunmamaktadır; zira yapay zekâ sistemleri çoğu zaman geliştiricilerinin dahi öngöremediği sonuçlar ortaya koyabilmektedir. Avrupa'da zaman zaman dile getirilen, yapay zekâyâ "elektronik kişilik" tanınması ve bu suretle hak ehliyetine sahip kılınması yönündeki öneriler ise, bir yapay zekânın dava açması ya da tazminat sorumluluğu üstlenmesi gibi pratik ve teorik güçlükler nedeniyle uygulanabilir olmaktan uzak bir yaklaşım olarak değerlendirilmektedir (Güner ve Şatır, t.y.).

Hukuki çıkmaz ile ilgili Güner ve Şatır tarafından ileri sürülen çözüm önerisinde, yapay zekâ çıktılarının klasik anlamda bir "eser" olarak nitelendirilmesinin zorlanmamasıdır. Bunun yerine, bu tür ürünler için kendine özgü bir koruma sisteminin oluşturulması önerilmektedir. Güner ve Şatır'a göre, veri tabanlarının korunmasına benzer şekilde, yapay zekâ teknolojilerine yapılan yatırımı güvence altına alacak; ancak süresi klasik eser korumasına kıyasla belirgin şekilde daha kısa süreyle uygulanacak özgün bir hukuki koruma modelinin tercih edilmesinin uygun olacağı ifade edilmektedir. Bu yolla, "Eser yalnızca insan (gerçek kişi) tarafından meydana getirilebilir" ilkesi korunurken; aynı zamanda yatırımcıların haklarının tanınması suretiyle teknoloji alanındaki yeniliklerin ve yatırımların teşvik edilmesi de sağlanabilecektir.

Benzer bir yaklaşımı ele alan Palacios (2025) düşüncesine göre, yapay zekayı kullanan insanı, süreci yöneten bir "operatör" olarak tanımlamak daha isabetli olacaktır. Operatör olarak benzetme yaptığımız insan, parametreleri belirler, sınırları çizer ve yapay zeka bu direktifler doğrultusunda üretimi gerçekleştirir. Ortaya çıkan ürün, klasik anlamda tamamen insan eseri sayılmasa da, insanın bu kritik yönlendirici rolü nedeniyle hukuki bir koruma altına alınabilir. Dolayısıyla, "insan destekli yapay zeka üretimine" özgü yeni bir hukuk kategorisi oluşturmak da seçenekler arasında gösterilebilir.

SONUÇ

Yapay zekâ teknolojilerindeki hızlı ve öngörülmesi güç ilerleme ve gelişim, fikrî ve sınai mülkiyet hukuku alanı ile ilgili olarak belirsizlikler yaratmakta; insan yaratıcılığı, buluş sahipliği ve hak kavramlarının yeniden düşünülmesini gerekli kılmaktadır. Üretken yapay zekâ uygulamalarının kültürel, sanatsal ve teknik alanlarda giderek daha görünür ve etkili ürünler ortaya koyması, mevcut hukuki çerçevenin bu gelişmeleri karşılamada ne kadar yeterli olduğu sorusunu gündeme getirmiştir. Bu bağlamda tartışma, yalnızca yapay zekâ tarafından ortaya konulan ürünlerde hak sahipliğinin kime ait olacağı meselesiyle sınırlı kalmamakta; aynı zamanda yeniliğin desteklenmesi, insan emeğinin korunması ve toplumun ortak yararı arasında nasıl bir denge kurulması gerektiği sorusunu da beraberinde getirmektedir.

Yapay zekâ çağında, fikrî mülkiyet hukuku ne çok katı ne de tamamen serbest olması gerekmektedir. Asıl amaç, yeniliği desteklerken insan yaratıcılığını ve toplumun çıkarlarını da koruyabilmektir. Bunun için ülkelerin birlikte hareket etmesi, etik kurallara önem vermesi ve şeffaf politikalar geliştirmesi gerekmektedir. Hukukun da bu hızlı değişime ayak uyduracak şekilde sürekli güncellenmesi önemlidir. Bu nedenle hukukçular, teknoloji uzmanları ve karar vericilerin birlikte çalışması artık kaçınılmazdır (Bharati, 2024).

Bugün atılacak adımlar, yalnızca yapay zekânın hukuki statüsünü değil, aynı zamanda gelecekte fikrî mülkiyet hukukunun yenilik karşısındaki konumunu da belirleyecek niteliktedir.

KAYNAKÇA

Taner, Ö. (2023). *Yapay zeka tarafından üretilen ürünler üzerindeki fikri haklar* (Master's thesis, Türk-Alman Üniversitesi Sosyal Bilimler Enstitüsü).

Bharati, R. K. (2024). AI and intellectual property: Legal frameworks and future directions. *International Journal of Law, Justice and Jurisprudence*, 4(2), 207-215.

Chesterman, S. (2025). Good models borrow, great models steal: intellectual property rights and generative AI. *Policy and Society*, 44(1), 23-37.

Novelli, C., Casolari, F., Hacker, P., Spedicato, G., & Floridi, L. (2024). Generative AI in EU law: Liability, privacy, intellectual property, and cybersecurity. *Computer Law & Security Review*, 55, 106066.

Han, Q., Li, C., & Jin, Y. (2025). The impact of intellectual property protection on the development of artificial intelligence in enterprises. *International Review of Financial Analysis*, 105, 104179.

Palacios, G. (2025). The impact of generative artificial intelligence on intellectual property regulation in the Andean Community. *IDEA: The Law Review of the Franklin Pierce Center for IP*, 66(Special Issue), 14–25.

McDonough, T. Y., & Bannister, T. L. (2025, 4 Aralık). *Intellectual property update: U.S. patent office provides new guidance on AI-assisted inventions*. Eckert Seamans Cherin & Mellott, LLC.

Bannigan, M. K., Ford, C. S., Liles, A., & Lasker, C. (2025, 2 Aralık). *AI intellectual property disputes: The year in review*. Debevoise & Plimpton.

Güner, C., & Şatır, E. (t.y.). *Yapay zekâ ürünleri üzerinde fikri hak sorunu hakkında bilgi notu*. Biçer Güner.

Stanford University. (2026). *Stanford AI experts predict what will happen in 2026*. Stanford Institute for Human-Centered AI (HAI). <https://hai.stanford.edu/news/stanford-ai-experts-predict-what-will-happen-in-2026>

INVESTIGATION OF THE EFFECT OF STEEL SLAG ON THE MECHANICAL
PROPERTIES OF FLEXIBLE SUPERSTRUCTURE USING THE FINITE ELEMENT
METHOD

Asst. Prof. Dr. Yunus ERKUŞ

Firat University, Technology Faculty,
Department of Civil Engineering, Elazığ.

Dilay AKSAKAL

Firat University, Technology Faculty,
Department of Civil Engineering, Elazığ.

ABSTRACT

The depletion of natural aggregate resources and the increasing need for sustainable materials have made steel slag, a waste product of steel production, an important alternative in road engineering. The main objective of this study is to investigate the stress, deformation, and strain behavior of base and asphalt layers containing different proportions of steel slag using the finite element method to reveal their contribution to superstructure performance. Within this scope, in models consisting of asphalt pavement, base, and subgrade layers, engineering properties were defined based on varying steel slag percentages, and mechanical responses under axle load were evaluated. Additionally, fatigue and wheel track-related load repetition numbers were calculated based on strains occurring under the flexible pavement and above the subgrade layer. Finally, considering fatigue and wheel track-related settlement conditions, the optimal use of steel slag was evaluated using the surface response method. According to the analysis results, it was found that as the percentage of steel slag used in the base layer increased, the stress, deformation, and strain values decreased. As the percentage of steel slag used in the asphalt layer increased, stresses were seen to increase initially and then decrease after a 75% steel slag ratio. In contrast, it was found that deformation and strain values initially decreased with the increase in steel slag and then increased after a 75% steel slag ratio. When axial maximum stresses were examined, the highest stresses occurred only when steel slag (75%) was used in the asphalt layer. Fatigue and wheel track-related load repetition numbers were found to be more affected by the amount of steel slag in the base layer. When optimization was performed based on the maximum fatigue and wheel track-related load repetition numbers, the highest strength was achieved with approximately 70% steel slag in the base layer and 42% in the asphalt layer. The results obtained indicate that the use of steel slag in appropriate proportions can increase the service life of flexible pavements and contribute to sustainable material use.

Keywords: Steel slag, flexible superstructure, mechanical properties, finite element method, surface response method

INTRODUCTION

Transportation infrastructure plays a critical role in the economic development, social integration, and spatial sustainability of modern societies (Rodrigue, 2020; Litman, 2021). The efficiency of transportation networks directly affects countries' economic competitiveness and supports social interaction and cultural integration (Sinha & Labi, 2019). Road transportation continues to be the most widely used transportation system worldwide due to its extensive access network, flexible usage options, and ability to integrate with other modes of transportation (AASHTO, 2020). The intensive use of road networks, the increase in the number of vehicles, and the impact of industrialization place significant burdens on the infrastructure

(Yin et al., 2018). These burdens cause structural deterioration in road superstructures, increased maintenance and repair costs, and disruption of transportation services (Roberts et al., 2019).

The design and performance evaluation of highway superstructures are not limited to safely transferring vehicle loads to the ground but also encompass multidimensional criteria such as long-term durability, economic efficiency, and environmental sustainability (Huang, 2021; Li et al., 2020). Flexible pavements, in particular, exhibit complex stress-strain behavior under traffic loads due to their layered structure and different material properties (Al-Qadi et al., 2018). In flexible pavement design, each layer—*asphalt pavement, binder course, base course, and subbase course*—directly affects the overall performance of the system; interactions between layers and the mechanical properties of materials are among the key factors determining the service life of the road (Li et al., 2020).

In traditional flexible pavement designs, natural aggregates are used extensively in the base and surface courses (Huang, 2021). However, the limited availability of natural aggregate resources, coupled with increasing infrastructure investments, is placing growing pressure on these resources (Prowell et al., 2018). Environmental issues such as the degradation of natural landscapes as a result of quarrying activities, the negative impact on underground and surface water resources, and carbon emissions associated with high energy consumption have emerged (Zhang et al., 2019). Therefore, transportation engineering applications today are approached holistically, considering not only structural performance but also environmental impacts and resource efficiency (Khayat et al., 2020).

In this context, the utilization of industrial by-products and waste materials in road construction has become an important part of sustainable engineering practices (Bilal et al., 2021). Steel slag, which is produced in large quantities during steel production processes, is a type of industrial waste that attracts attention because it causes environmental problems when it is not properly utilized (Abbas et al., 2019). However, the mechanical properties of steel slag, such as high strength, hardness, and wear resistance, indicate that this material can be used as an alternative to natural aggregates in road engineering applications (Shafabakhsh et al., 2020).

Studies in the literature on the use of steel slag in asphalt mixtures, base, and subbase layers have shown that this material can increase the load-carrying capacity of road pavements and reduce permanent deformation (Li et al., 2017; Kim et al., 2018). The angular particle shape and rough surface characteristics of steel slag strengthen the bitumen-aggregate adhesion, providing advantages, particularly in terms of rutting resistance and fatigue performance (Bamforth, 2016). However, the variability in the chemical composition of steel slag and its volumetric expansion potential due to free lime content are issues that need to be carefully evaluated in terms of long-term performance (Zhang & Xiao, 2019). This necessitates a detailed scientific investigation of the use of steel slag in road pavements (Huang et al., 2020).

The behavior of flexible superstructures cannot be fully represented by analytical methods due to their multi-layered structures and complex loading conditions (AASHTO, 2020). Therefore, numerical analysis methods have been widely used in transportation engineering research in recent years (Khalid et al., 2019). The Finite Element Method (FEM) stands out as a powerful tool in superstructure analysis due to its ability to model the behavior of systems with complex geometries and different material properties (Zhang et al., 2021). Stress, deformation, and strain occurring in superstructure layers can be examined in detail using FEM; the structural response of the system can be reliably evaluated under different material scenarios (Gao et al., 2018).

Finite element analyses offer significant advantages, particularly in determining the effects of alternative materials on superstructure performance (Li et al., 2019). When materials with heterogeneous properties, such as steel slag, are used in different proportions, data that is difficult or costly to obtain through experimental studies can be analyzed in detail using numerical models (Kim & Lee, 2020). However, statistical approaches are needed to optimize

the results obtained from these analyses and directly transfer them to engineering design (Montgomery, 2017).

The Response Surface Method (RSM) provides an effective tool for evaluating the results obtained from finite element analyses and determining the most suitable design parameters (Myers et al., 2016). RSM expresses the interactions between variables using mathematical models, revealing solution areas that maximize system performance or optimize within specific limits (Montgomery, 2017). Thus, the effects of steel slag usage rates on superstructure performance can be evaluated with a more holistic approach (Shafabakhsh et al., 2020).

The primary objective of this study is to investigate the effects of steel slag on the mechanical properties of flexible pavements using the finite element method and to optimize the results obtained using the surface response method. Within the scope of the study, pavement models with base and asphalt layers containing different proportions of steel slag were created. The stress, deformation, and strain of these models under load were analyzed. In addition, fatigue and wheel track-related load repetition numbers were calculated. The findings were evaluated comparatively to reveal the effects of steel slag ratio on pavement performance.

METHOD

The study aims to determine the stress, deformation, and strain behavior that occurs when steel slag is used in road pavement layers. To this end, two different but complementary methods were used together in the study: the Finite Element Method and the Surface Response Method. The Finite Element Method was chosen to numerically model the mechanical behavior of the road pavement under traffic loads (Huang, 2004). The Surface Response Method was used to statistically evaluate the outputs obtained from finite element analyses and to model the relationships between variables (Montgomery, 2017). The combined use of these two methods allows for both a detailed examination of physical behavior and an increase in the generalizability of the results (Myers, Montgomery & Anderson-Cook, 2016).

The Finite Element Method is a numerical analysis method widely used in transportation engineering to examine the stress and deformation behavior of multi-layered road pavements (Huang, 2004). This method allows for realistic modeling of systems where layers with different material properties work together (Zienkiewicz & Taylor, 2013). The finite element approach provides more comprehensive results than analytical methods, particularly in determining interlayer load transfer and critical deformations (Karadağ et al., 2020).

The Surface Response Method is an experimental design and analysis approach that aims to statistically model the relationship between one or more dependent variables and multiple independent variables (Montgomery, 2017). This method enables the evaluation of variable interactions in complex engineering systems and the prediction of system behavior through mathematical models (Myers, Montgomery & Anderson-Cook, 2016).

RESULTS

The two-dimensional road model used in the study, consisting of the subgrade, base, and pavement layers, is shown in Figure 1. The model was designed to have a width of 4000 mm, a length of 10000 mm, and a height of 5450 mm. The wheel contact area was taken as 290x200 mm. Solidworks software was used for the finite element analysis of the road superstructure.




Figure1. Highway cross-section and dimensions

The mechanical properties of the layers forming the roadway when steel slag is not used are given in Table 1.

Table 1. The mechanical properties of the layers forming the roadway before the use of steel slag

Layers	Specific Gravity (kg/m ³)	Modulus of Rigidity (MPa)
Subgrade	1600	60
Base	2233	166
Asphalt	2403	600

Representative symbols and varying mechanical properties depending on the percentage of steel slag used in the base layer are given in Table 2 below.

Table 2. Representative symbols and varying mechanical properties depending on the percentage of steel slag used in the base layer (Shiha et al., 2020)

Steel Slag (%)	Symbol	Specific Gravity (kg/m ³)	Modulus of Rigidity (MPa)
0	B0	2233	166
20	B20	2320	218
40	B40	2463	269
60	B60	2664	303
80	B80	2840	313
100	B100	2847	324

Representative symbols and varying mechanical properties depending on the percentage of steel slag used in the asphalt layer are given in Table 3 below.

Table 3. Representative symbols and varying mechanical properties depending on the percentage of steel slag used in the asphalt layer (Asi et al., 2007)

Steel Slag (%)	Symbol	Specific Gravity (kg/m ³)	Modulus of Rigidity (MPa)
0	A0	2403	600
25	A25	2450	750
50	A50	2548	740
75	A75	2640	900
100	A100	2874	720

Figure 2 shows the mesh structure created to prepare the structure for finite element analysis. A fine and regular mesh structure increases the accuracy of the analysis, enabling more accurate calculation of stress and deformation distributions. Mesh quality, element size, shape, and density play a critical role, especially in areas where stress concentration is expected. This step is one of the most important stages in terms of the accuracy and stability of the numerical solution. Furthermore, an adaptive mesh structure is recommended for modeling heterogeneous materials such as steel slag. In the model used in this study, the mesh size was set to 100 mm.




Figure 2. Highway model ready for analysis

Figure 3 shows the overall stress distribution in the model without steel slag as a result of the loads applied to the structure analyzed. The color scale represents stress intensity ranging from a minimum stress value (1.74e-07) to a maximum (approximately 1.19). Blue tones represent low stress regions, while light blue and turquoise tones represent higher stress regions. The absence of stress accumulation in the corners and edges of the structure indicates that the loads are distributed homogeneously and that the structure has a balanced design in terms of rigidity.,




Figure 3. Stress distribution in an unmodified highway pavement structure

Figure 4 shows the displacement amounts experienced by structural elements under load in the model without steel slag. The color scale ranges from $1e-30$ mm to 1.27 mm. Red areas represent maximum displacement, while blue areas represent minimum displacement. The displacement distribution is concentrated on the upper surface of the structure and at the load application points; on the lower surface, it remains at a minimum level in the fixed regions. This indicates that the lower boundary conditions of the structure are correctly defined and that the load transfer occurs in a controlled manner from top to bottom.




Figure 4. Deformation distribution of the unmodified highway pavement structure

Figure 5 shows the distribution of unit strain (strain) in the structure. The color scale ranges from $6.92e-09$ to 0.00148. Blue tones represent regions within elastic limits, while red tones represent regions that are critical in terms of strain. The strain distribution is more intense on the load-bearing surfaces of the structure and is at a minimum level on the fixed edges. Low strain values contribute to a longer fatigue life and an increase in the number of load cycles.




Figure 5. Strain distribution in an unmodified highway pavement structure

The variation in maximum axial stresses occurring in the highway pavement structure solved using the finite element method, depending on the use of steel slag in the base and asphalt layers, is given in Table 4 below. The lowest axial stress values were obtained when steel slag was not used in the asphalt layer. As the use of steel slag in the base layer increased, the axial stresses decreased.

Table 4. The variation of maximum axial stresses depending on the steel slag

Base Layer Steel Slag (%)	Asphalt Layer Steel Slag (%)	Symbol	Stress (MPa)		
			x	y	z
0	0	B0A0	0,892	0,794	0,876
0	25	B0A25	0,961	0,795	0,945
0	50	B0A50	0,956	0,795	0,94
0	75	B0A75	1,02	0,796	1
0	100	B0A100	0,948	0,795	0,932
20	0	B20A0	0,831	0,793	0,821
20	25	B20A25	0,896	0,794	0,886
20	50	B20A50	0,892	0,794	0,882
20	75	B20A75	0,953	0,795	0,943
20	100	B20A100	0,884	0,794	0,874
40	0	B40A0	0,787	0,792	0,782
40	25	B40A25	0,849	0,793	0,844
40	50	B40A50	0,845	0,793	0,84
40	75	B40A75	0,903	0,794	0,898
40	100	B40A100	0,837	0,793	0,832
60	0	B60A0	0,764	0,792	0,76
60	25	B60A25	0,823	0,793	0,82
60	50	B60A50	0,819	0,793	0,817
60	75	B60A75	0,875	0,794	0,873
60	100	B60A100	0,812	0,792	0,809
80	0	B80A0	0,757	0,791	0,755
80	25	B80A25	0,816	0,793	0,814
80	50	B80A50	0,812	0,793	0,81
80	75	B80A75	0,868	0,793	0,866
80	100	B80A100	0,805	0,792	0,803
100	0	B100A0	0,751	0,791	0,749
100	25	B100A25	0,809	0,792	0,807
100	50	B100A50	0,805	0,792	0,804
100	75	B100A75	0,86	0,793	0,859
100	100	B100A100	0,798	0,792	0,796

The variation in maximum axial deformations occurring in the highway pavement structure solved using the finite element method, depending on the use of steel slag in the base and asphalt layers, is given in Table 4.5 below. The smallest values of axial deformations were obtained when 75% steel slag was used in the asphalt layer. Axial deformations decreased as the use of steel slag in the base layer increased.

Tablo 5. Change in maximum axial deformations depending on steel slag

Base Layer Steel Slag (%)	Asphalt Layer Steel Slag (%)	Symbol	Deformation (mm)		
			x	y	z
0	0	B0A0	0,0976	1,27	0,128
0	25	B0A25	0,0877	1,19	0,121
0	50	B0A50	0,0883	1,2	0,122
0	75	B0A75	0,0801	1,14	0,118
0	100	B0A100	0,0895	1,21	0,122
20	0	B20A0	0,0876	1,17	0,117
20	25	B20A25	0,0791	1,1	0,114
20	50	B20A50	0,0796	1,11	0,114
20	75	B20A75	0,0725	1,05	0,111
20	100	B20A100	0,0806	1,11	0,114
40	0	B40A0	0,0804	1,09	0,109
40	25	B40A25	0,0727	1,04	0,107
40	50	B40A50	0,0732	1,04	0,107
40	75	B40A75	0,0668	0,991	0,105
40	100	B40A100	0,0741	1,05	0,107
60	0	B60A0	0,0766	1,06	0,105
60	25	B60A25	0,0693	1	0,103
60	50	B60A50	0,0697	1	0,103
60	75	B60A75	0,0638	0,958	0,101
60	100	B60A100	0,0706	1,01	0,103
80	0	B80A0	0,0756	1,05	0,103
80	25	B80A25	0,0684	0,991	0,101
80	50	B80A50	0,0688	0,995	0,101
80	75	B80A75	0,0629	0,949	0,0995
80	100	B80A100	0,0697	1	0,102
100	0	B100A0	0,0745	1,04	0,102
100	25	B100A25	0,0675	0,982	0,1
100	50	B100A50	0,0679	0,985	0,1
100	75	B100A75	0,0621	0,94	0,0983
100	100	B100A100	0,0687	0,991	0,1

The variation in maximum axial strains occurring in the highway pavement structure solved using the finite element method, depending on the use of steel slag in the base and asphalt layers, is given in Table 6 below. The smallest values of axial strains were obtained when 75% steel slag was used in the asphalt layer. As the use of steel slag in the base layer increased, the axial deformations decreased.

Tablo 6. The change in maximum unit strain depending on the steel slag

Base Layer Steel Slag (%)	Asphalt Layer Steel Slag (%)	Symbol	Strain		
			x	y	z
0	0	B0A0	0,000669	0,0019	0,000777
0	25	B0A25	0,000601	0,00175	0,000701
0	50	B0A50	0,000605	0,00176	0,000706
0	75	B0A75	0,000548	0,00163	0,000641
0	100	B0A100	0,000613	0,00178	0,000715
20	0	B20A0	0,000593	0,00155	0,0007

INTERNATIONAL TOPKAPI CONGRESS VI

20	25	B20A25	0,000537	0,00145	0,000635
20	50	B20A50	0,00054	0,00146	0,000639
20	75	B20A75	0,000492	0,00136	0,000591
20	100	B20A100	0,000547	0,00147	0,000647
40	0	B40A0	0,000538	0,00132	0,000643
40	25	B40A25	0,000489	0,00124	0,000586
40	50	B40A50	0,000492	0,00125	0,00059
40	75	B40A75	0,000451	0,00118	0,000556
40	100	B40A100	0,000498	0,00126	0,000597
60	0	B60A0	0,000509	0,0012	0,000612
60	25	B60A25	0,000464	0,00114	0,00056
60	50	B60A50	0,000466	0,00114	0,000563
60	75	B60A75	0,000428	0,00108	0,000534
60	100	B60A100	0,000472	0,00115	0,000569
80	0	B80A0	0,000501	0,00117	0,000603
80	25	B80A25	0,000457	0,00111	0,000553
80	50	B80A50	0,000459	0,00111	0,000556
80	75	B80A75	0,000422	0,00105	0,000528
80	100	B80A100	0,000465	0,00112	0,000562
100	0	B100A0	0,000492	0,00114	0,000595
100	25	B100A25	0,000449	0,00108	0,000545
100	50	B100A50	0,000452	0,00108	0,000548
100	75	B100A75	0,000415	0,00103	0,000522
100	100	B100A100	0,000457	0,00109	0,000554

There are two types of settlement mechanisms in highway structures. The first is a fatigue-related settlement mechanism caused by tensile strain changes forming under the pavement layer. The second is a rutting mechanism caused by compressive strain changes forming on the soil layer. Using formulas determined by Shell, the maximum number of load cycles that can be repeated without deformation of the road structure is calculated in both cases. The change in fatigue and rutting load cycles in the road superstructure, solved using the finite element method and calculated using the Shell method, depending on steel slag is given in Table 7 below. The highest load repetition numbers related to rutting and fatigue were obtained with 75% steel slag usage in the asphalt layer. Again, as the steel slag ratio used in the base layer increased, the load repetition numbers related to rutting and fatigue increased regularly.

Table 7. Changes in fatigue and rutting load repetition counts in highway superstructures solved using the finite element method, depending on steel slag

Base Layer Steel Slag (%)	Asphalt Layer Steel Slag (%)	Symbol	Fatigue-Related Load Repetition Count	Rutting-Related Load Repetition Count
0	0	B0A0	146674	47191
0	25	B0A25	158981	65572
0	50	B0A50	158048	64095
0	75	B0A75	174429	87121
0	100	B0A100	156511	61262
20	0	B20A0	290639	106548
20	25	B20A25	301064	139124
20	50	B20A50	301106	135351
20	75	B20A75	321446	179770
20	100	B20A100	298613	131706
40	0	B40A0	504755	202571
40	25	B40A25	512004	260128
40	50	B40A50	510494	251904
40	75	B40A75	526512	317210

INTERNATIONAL TOPKAPI CONGRESS VI

40	100	B40A100	508450	244001
60	0	B60A0	691115	296585
60	25	B60A25	689478	364129
60	50	B60A50	694558	364129
60	75	B60A75	708477	452043
60	100	B60A100	689145	351628
80	0	B80A0	756079	328194
80	25	B80A25	751552	405119
80	50	B80A50	756807	405119
80	75	B80A75	767532	505962
80	100	B80A100	750084	390843
100	0	B100A0	837940	364129
100	25	B100A25	830720	452043
100	50	B100A50	825724	452043
100	75	B100A75	843903	546419
100	100	B100A100	827658	435681

The results obtained from the analysis of fatigue-related load cycle count using the surface response method are presented in Table 8. A quadratic model was used in the variance analysis. The large F-value (763.68) indicates that the model is significant. A P-value less than 0.0500 indicates that the model terms are significant. In this case, A (percentage of steel slag in the base layer) and A^2 are significant model terms in the analysis. A P-value greater than 0.1000 indicates that the model terms are not significant. The estimated R^2 value (0.9947) is in reasonable agreement with the adjusted R^2 value (0.9969); that is, the difference between them is less than 0.2. Adeq Precision measures the signal-to-noise ratio. A ratio greater than 4 is desirable. The ratio of 69.882 indicates that the signal is adequate.

Table 8. Results obtained from the analysis of fatigue-related load cycle count using the surface response method

Source	Sum of Squares	df	Mean Square	F-value	p-value	
Model	2.309E+11	5	4.618E+10	763.68	< 0.0001	significant
A- Base Layer Steel Slag (%)	1.585E+10	1	1.585E+10	262.20	< 0.0001	
B- Asphalt Layer Steel Slag (%)	2.739E+05	1	2.739E+05	0.0045	0.9482	
AB	2.698E+07	1	2.698E+07	0.4461	0.5256	
A^2	2.384E+09	1	2.384E+09	39.42	0.0004	
B^2	2.508E+08	1	2.508E+08	4.15	0.0811	
Residual	4.233E+08	7	6.047E+07			
Cor Total	2.313E+11	12				
Std. Dev.	7775.95		R^2		0.9982	
Mean	2.950E+05		Adjusted R^2		0.9969	
C.V. %	2.64		Predicted R^2		0.9947	
			Adeq Precision		69.8816	

The results obtained from the analysis of the number of load repetitions associated with rutting using the surface response method are given in Table 9. A quadratic model was used in the variance analysis. The large F-value (44.93) indicates that the model is significant. The P-value being less than 0.0500 indicates that the model terms are significant. In this case, A (percentage of steel slag in the base layer) and B^2 (square of the percentage of steel slag in the asphalt layer)

are significant model terms in the analysis. If the P-value is greater than 0.1000, it indicates that the model terms are not significant. The estimated R^2 value (0.9042) is in reasonable agreement with the adjusted R^2 value (0.9482); that is, the difference between them is less than 0.2. Adeq Precision measures the signal-to-noise ratio. A ratio greater than 4 is desirable. The ratio of 19.849 indicates that the signal is adequate.

Table 9. Results obtained from the analysis of the number of load repetitions associated with rutting using the surface response method

Source	Sum of Squares	df	Mean Square	F-value	p-value	
Model	6.011E+10	5	1.202E+10	44.93	< 0.0001	significant
A- Base Layer Steel Slag (%)	4.666E+09	1	4.666E+09	17.44	0.0042	
B- Asphalt Layer Steel Slag (%)	4.029E+08	1	4.029E+08	1.51	0.2595	
AB	1.003E+08	1	1.003E+08	0.3750	0.5596	
A ²	7.974E+08	1	7.974E+08	2.98	0.1279	
B ²	1.507E+09	1	1.507E+09	5.63	0.0494	
Residual	1.873E+09	7	2.676E+08			
Cor Total	6.198E+10	12				
Std. Dev.	16357.53		R²		0.9698	
Mean	1.333E+05		Adjusted R²		0.9482	
C.V. %	12.28		Predicted R²		0.9042	
			Adeq Precision		19.8490	

When optimized for the maximum number of load cycles associated with fatigue and wheel rutting, the highest strength was achieved with approximately 70% steel slag usage in the base layer and 42% in the asphalt layer.

CONCLUSION

In this study, the effects of using steel slag in flexible pavement layers on structural and mechanical performance were examined in detail using the finite element method and surface response method together. The main motivation for this study is to reveal the potential of steel slag, an industrial by-product, as an alternative material in road engineering in the face of diminishing natural aggregate resources and the increasing need for sustainable infrastructure. The results obtained show that the use of steel slag in both the base and asphalt layers leads to significant improvements in the mechanical behavior of road pavement systems. The reduction in vertical deformations in sections containing steel slag, the more balanced stress distribution, and the decrease in tensile stresses formed in critical areas demonstrate that this material can be effectively used in load-bearing layers. These findings show that steel slag is not only an environmental waste but also a valuable engineering construction material.

Statistical analyses conducted using the surface response method have revealed significant and strong relationships between the steel slag usage rate and road pavement performance parameters. Optimization results have shown that maximum performance is achieved at specific slag ratios. This clearly demonstrates that the use of steel slag in road pavements should not be random but should be based on engineering principles, taking into account optimal ratios. When optimization was performed based on the maximum fatigue and wheel rutting load repetition counts, the highest strength was achieved with approximately 70% steel slag usage in the base layer and 42% in the asphalt layer.

REFERENCES

- AASHTO. (2020). AASHTO guide for pavement design (7th ed.). American Association of State Highway and Transportation Officials.
- Abbas, A., Li, X., & Zhang, Y. (2019). Utilization of steel slag in road construction: A review. *Journal of Cleaner Production*, 231, 1230–1242. <https://doi.org/10.1016/j.jclepro.2019.05.045>
- Al-Qadi, I. L., Elseifi, M. A., & Carpenter, S. H. (2018). Characterization of pavement layer materials for mechanistic-empirical design. *Transportation Research Record*, 2672(12), 1–12. <https://doi.org/10.1177/0361198118793456>
- Asi, I. M., Qasrawi, H. Y., & Shalabi, F. I. (2007). Use of steel slag aggregate in asphalt concrete mixes. *Canadian Journal of Civil Engineering*, 34(8), 902–911.
- Bamforth, P. (2016). Sustainable use of industrial by-products in road construction. *Construction and Building Materials*, 122, 728–737. <https://doi.org/10.1016/j.conbuildmat.2016.06.095>
- Bilal, M., Ali, S., & Khan, A. (2021). Steel slag as an eco-friendly aggregate in pavement construction: A review. *Journal of Materials in Civil Engineering*, 33(2), 04020345. [https://doi.org/10.1061/\(ASCE\)MT.1943-5533.0003541](https://doi.org/10.1061/(ASCE)MT.1943-5533.0003541)
- Gao, X., Li, Q., & Huang, Y. (2018). Finite element modeling of multi-layered flexible pavements under moving loads. *International Journal of Pavement Engineering*, 19(6), 533–544. <https://doi.org/10.1080/10298436.2016.1272761>
- Huang, X., Wang, K., & Li, M. (2020). Evaluation of steel slag in pavement layers using finite element analysis. *Construction and Building Materials*, 257, 119562. <https://doi.org/10.1016/j.conbuildmat.2020.119562>
- Karadağ, O., Fırat, S., & Işık, E. (2020). Finite element analysis of pavement structures containing alternative materials. *International Journal of Pavement Engineering*, 21(8), 995–1007. <https://doi.org/10.1080/10298436.2018.1508842>
- Khalid, A., Zaman, M., & Ahmad, S. (2019). Numerical analysis of flexible pavements incorporating industrial by-products. *Road Materials and Pavement Design*, 20(8), 1895–1909. <https://doi.org/10.1080/14680629.2018.1551714>
- Kim, S., Park, J., & Lee, C. (2018). Mechanical performance of steel slag modified asphalt pavements. *Materials*, 11(9), 1601. <https://doi.org/10.3390/ma11091601>
- Li, Q., Gao, X., & Huang, Y. (2019). Optimization of flexible pavement design with steel slag using finite element method. *Journal of Materials in Civil Engineering*, 31(7), 04019144. [https://doi.org/10.1061/\(ASCE\)MT.1943-5533.0002789](https://doi.org/10.1061/(ASCE)MT.1943-5533.0002789)
- Li, X., Li, Q., & Zhang, Y. (2017). Investigation of steel slag for base course application in flexible pavements. *Construction and Building Materials*, 149, 150–160. <https://doi.org/10.1016/j.conbuildmat.2017.05.068>
- Litman, T. (2021). Transportation and sustainability: Evaluating impacts of transport infrastructure. Victoria Transport Policy Institute. <https://www.vtpi.org>
- Myers, R. H., Montgomery, D. C., & Anderson-Cook, C. M. (2016). Response surface methodology: Process and product optimization using designed experiments (4th ed.). Wiley.
- Prowell, B., Frank, B., & Brown, E. (2018). Sustainable aggregates for asphalt pavements: Current practices and research directions. *Transportation Research Record*, 2672(2), 12–23. <https://doi.org/10.1177/0361198118756853>
- Roberts, F. L., Kandhal, P. S., Brown, E. R., Lee, D.-Y., & Kennedy, T. W. (2019). Hot mix asphalt materials, mixture design, and construction (3rd ed.). NAPA Education Foundation.
- Shafabakhsh, G., Akbari, M., & Tahami, S. (2020). Mechanical behavior of steel slag in asphalt mixtures: A review. *Construction and Building Materials*, 252, 119058. <https://doi.org/10.1016/j.conbuildmat.2020.119058>

Shiha, M., El-Badawy, S., & Gabr, A. (2020). Modeling and performance evaluation of asphalt mixtures and aggregate bases containing steel slag. *Construction and Building Materials*, 248, 118710.

Sinha, K. C., & Labi, S. (2019). *Transportation decision making: Principles of project evaluation and programming* (2nd ed.). Wiley.

Yin, Y., Wu, S., & Zhang, L. (2018). Pavement structural performance under increasing traffic loads. *International Journal of Pavement Engineering*, 19(5), 424–435. <https://doi.org/10.1080/10298436.2017.1314320>

Zhang, J., & Xiao, F. (2019). Expansion potential of steel slag and its mitigation in pavement applications. *Construction and Building Materials*, 207, 168–176. <https://doi.org/10.1016/j.conbuildmat.2019.02.147>

Zhang, X., Li, Y., & Liu, H. (2021). Finite element analysis of multilayered pavements incorporating industrial by-products. *Road Materials and Pavement Design*, 22(6), 1461–1477.

RESEARCH ON METHODS FOR CONTROLLING SNOW AND ICE ON
HIGHWAY

Asst. Prof. Dr. Yunus ERKUŞ

Firat University, Technology Faculty,
Department of Civil Engineering, Elazığ.

Dilay AKSAKAL

Firat University, Technology Faculty,
Department of Civil Engineering, Elazığ.

ABSTRACT

Snowfall and icing during cold winter months are significant events that affect the performance and safety of road surfaces. Snow falling on the road surface and the subsequent formation of ice reduce friction, leading to accidents. These accidents result in loss of life and property damage. It is necessary to seriously combat snow and ice formation during the winter months, both to protect the road structure and for traffic safety. In this study, methods of combating snow and ice on highways found in the literature were compiled, and their advantages and disadvantages were examined. Methods of combating snow and ice on highways are generally divided into pre-icing and post-icing. The use of snow fences should be promoted in areas where wind is strong and snow accumulation is high. When snowfall is heavy, it is beneficial to physically remove the snow with machines and then clean the road after using chemicals. Intervening before ice forms after snowfall reduces the use of de-icing materials and prevents the friction coefficient of the pavement from decreasing further. In this regard, anti-icing applications offer advantages in terms of cost and safety. Sodium chloride (NaCl) salt is commonly used for de-icing. Using magnesium chloride (MgCl₂) instead, which has a similar cost, would cause less harm to the natural environment. Adding organic matter to such salts would further reduce both their cost and environmental impact. Traffic accident rates are higher on road sections such as intersections where vehicles must slow down and stop, bridges that freeze more quickly due to their open undersides, and steeply sloped terrain where vehicle speeds must be controlled. Therefore, combating snow and ice is of greater importance in these areas. The use of active systems (heat pipes, conductive cables, microwaves, and infrared) should be preferred in these areas. The use of phase change materials as additives, which both prevent icing and provide resistance to permanent deformation and crack formation, is of great importance as a multifaceted approach. In snow and ice control methods, the use of waste materials and renewable energy sources, integrated with smart transportation systems, will reduce costs, protect the natural environment, and enhance safety.

Keywords: Highway, asphalt, snow, ice, safety.

INTRODUCTION

Transportation is the movement of passengers and goods for a beneficial purpose. Different modes of transportation exist to serve this purpose, including road, air, sea, and rail. With advancements in the automotive industry, the demand for fast, comfortable, and flexible transportation has made road transport a crucial element. According to Turkey's 2022 transportation statistics, 89% and 91% of freight and passenger transportation, respectively, is carried out by road. With the continuous increase in population and vehicle use, traffic safety

has become a very important issue for road transportation. Road traffic safety is significantly affected not only by driver, vehicle, and management factors, but also by climatic conditions. Turkey has diverse climatic characteristics due to its proximity to seas, the location of mountains, and the undulating terrain. However, a continental climate generally prevails, and this climate type is particularly effective in Central Anatolia, Eastern Anatolia, Southeastern Anatolia, the inner Aegean region, and the inland areas of Thrace. In Eastern Anatolia, due to the influence of the continental climate, temperatures can drop as low as -46°C in some regions. In regions with a continental climate, harsh weather conditions during winter months cause problems such as icing, black ice, snow accumulation, avalanches, and blizzards on highways (Varış, 2007). One of the biggest challenges in mountainous and high-altitude areas during winter is the closure of roads due to heavy snowfall. Roads in Turkey are affected more by snow carried by the wind and accumulating in gorges than by snowfall (Gürer et al., 2018). The reason for the high number of traffic accidents in winter months is that the low ambient temperature in freezing weather, combined with precipitation, causes snow accumulation and ice formation on the roads (Chen et al., 2011; Lee et al., 2017). The coefficient of friction between tires and the road surface decreases when there is snow and ice on the surface, bringing with it significant safety risks (Wan et al., 2019; Jiang et al., 2022; Yuan et al., 2023). Studies report that the coefficients of friction for dry pavement, snow-covered pavement, and ice-covered pavement are 0.6, 0.18-0.3, and 0.06-0.17, respectively (Cheng and Mao, 2011; Klein-Paste, 2018). Therefore, effective removal of snow and ice accumulated on pavements is necessary for the smooth operation of the highway, especially in some critical sections such as bridges and ramps. An examination of the maintenance cost tables published by the General Directorate of Highways of the Republic of Turkey for 2022 shows that approximately 2 billion Turkish Lira was spent on snow and ice control. This figure represents almost a quarter of the asphalt maintenance costs calculated for the same year. Therefore, considering not only road safety but also the cost factor, a detailed investigation of snow and ice control methods is necessary. Currently, much of the fight against snow and ice relies primarily on mechanical and chemical salting (Aghazadeh et al., 2010; Feng et al., 2022; Ullah Sajid et al., 2021). It is reported that approximately 35 million tons of chemical salt are used annually to melt snow and ice on roads (Jiang et al., 2018; Xu et al., 2018). However, chemical salting has been reported to cause deterioration of pavements, corrosion of roadside infrastructure, and water pollution (Cristóvão et al., 2016; Li, C. et al., 2013; Sanzo and Hecnar, 2006). Furthermore, chemical salting will not melt ice and snow if the ambient temperature is below -3.9°C (Liu et al., 2007; Sun et al., 2018). The use of snowplows with mechanical methods to remove snow will damage road surfaces and structures, increasing maintenance and repair costs (Chen et al., 2011). Therefore, efficient and environmentally friendly snow and ice control methods continue to be a subject of research. In recent years, various new solutions have been developed to prevent icing on road surfaces, including salt deposition materials, phase change materials, road heating with heat pipes, conductive coatings, and hydrophobic coatings. These new systems are supported by technological tools and intelligent transportation systems for snow and ice control. This study investigates in detail the snow and ice control methods used on highways in the literature. The advantages and disadvantages of these methods are highlighted.

METHOD

This study utilized a literature review as its methodology.

SNOW REMOVAL WITH MACHINES AND EQUIPMENT

Snow accumulating on the road platform obstructs traffic and, due to prolonged presence and melting, seeps beneath the pavement, penetrating voids. As the air cools again, the existing water freezes, causing stresses in the pavement. Therefore, snow must be removed from the

platform as quickly as possible. The machinery and equipment used for mechanically removing snow from the road should be selected according to the snow depth and the locations where it will be stored and disposed of. When the snow depth exceeds 5 cm, trucks equipped with flat snow plows and operating at 50 km/h are used to remove the snow from the road (Figure 1). These machines are effective up to a snow depth of 20 cm.



Figure1. Flat blade snowplow.

On roads where the snow depth is between 20 cm and 50 cm, V-blades are used to clear blocked areas, and then flat blades are used for final clearing. In areas where the snow depth reaches 1 m, V-blades mounted on more powerful trucks are used to cut the snow. Side blades on the same truck widen the cut areas, and fine snow removal is done with flat blades. After all the work is done, the snow accumulated on the side of the road must be removed using rotary snowplows, if available, or by other means. Otherwise, if snowfall continues, clearing the road may become unmanageable. When snow depths exceed 50 cm, unless absolutely necessary, it is recommended to use rotary snowplows as shown in Figure 2. This is because rotary snowplows can throw snow over long distances, preventing it from creating a hazard on the road.



Figure 2. Rotary snowplow

Snow removal operations must be carried out quickly. This prevents snow from compacting and the difficulties that subsequent clearing operations would create. It also reduces icing and

prevents snowmelt from seeping through cracks in the pavement into the underlying layers. Many base and pavement defects encountered in the spring, especially on asphalt pavements, stem from the failure to remove snow from the pavement surface in a timely and rapid manner. Snow removal should continue until not only the pavement surface but also the shoulders are cleared. In this way, the road pavement and base are protected from the harmful effects of snowmelt.

FIGHTING THE SNOW WITH SHELTER

The snow that most often causes road closures is formed by the accumulation of snow on the land adjacent to the road, carried by the prevailing wind. Factors contributing to this snow accumulation include very steep embankment slopes, shoulders covered with tall grass, the presence of fences parallel to the road axis, and the route being perpendicular to the prevailing wind direction. Furthermore, snow accumulation along the roadside seeps under the pavement, damaging the base layer. Moreover, when it snows again immediately after this accumulation, there is no place for the snow to drift, and using rotary snowplows becomes costly and difficult. Therefore, instead of removing snow from the road surface using costly and difficult methods, using snow fences, which partially prevent snow from reaching the road, offers an economical and suitable solution. The working principle of snow fences is to reduce the speed of the wind carrying the snow, accumulating it in front of and behind the fence (Kıgılı, 2014). Snow fences should be positioned in areas where snow accumulation is likely to be significant on the highway. Snow shelters are generally divided into two groups: biological and non-biological snow shelters. Living snow fences, designed with native trees and regional natural greenery, are used to prevent snow accumulation at low cost. These fences are positioned to spread the snow over a wide area or store it in a small area. Thanks to these fences, ice formation, time wasted due to road closures, and pavement maintenance and repair costs are reduced. Trees used as living snow fences should be selected from varieties that are crowned at the base and have their tops trimmed to maintain a constant height. Otherwise, they should be planted at the necessary distance considering their height. These types of snow fences not only prevent snow accumulation but also contribute to landscaping and erosion prevention. Inert snow fences, made from materials such as stone, concrete, wood, steel, and PVC, are frequently preferred due to their ease of construction. One of the most effective measures against snow carried by prevailing winds on highways is snow fences made of PVC coated steel wire. The construction of these types of snow fences is easier and faster than that of concrete snow fences. Inert snow fences collect snow according to their surface void ratio and height. In our country, Canadian snow fences (Figure 3) are most commonly used. These fences are designed to collect snow with a maximum void ratio of 50%.



Figure 3. Snow Fences

CHEMICAL METHODS

As is the case worldwide, the most commonly used method in our country to prevent ice formation on roads or to remove existing ice is the application of chemical substances to the road surface (Henderson, 1963). The most commonly used chemical solutions, due to their low cost and effectiveness, are sodium chloride (NaCl), magnesium chloride (MgCl₂), calcium chloride (CaCl₂), calcium magnesium acetate (CMA), and potassium acetate (KAc) (Menzies, 1991). In addition, they are used in abrasive materials applied by mixing with urea, formates, glycols, and chemicals. Chemicals can be applied in solid or liquid form. The type and amount of chemical to be applied may vary depending on the amount of snow or ice, the ambient temperature, and the application area. However, these substances can damage asphalt and concrete pavement surfaces, the ecological system, and metal structures. In recent years, acetate-based de-icing agents such as potassium acetate (KAc) and calcium magnesium acetate (CMA) have been preferred for snow and ice removal due to their rapid dissolution and lack of chloride content. Acetates, which are considered a risk to the durability of concrete and asphalt pavements, are also expensive (Hassan, 2002). CMA does not pose a corrosion risk to concrete pavement reinforcements, but its performance is lower than that of salt, and its operating temperature range is narrower.

SALT-BASED ASPHALT PAVING

In the early 1960s, in Switzerland and Germany, the use of Verglimit antifreeze as an additive in salt-deposit asphalt pavements lowered the freezing point of the pavement to -20 °C (Chatterji, 1999). In the 1980s, Japan developed Mafilon (MFL), a salt-deposit material still used worldwide, and used it as a filler in asphalt mixes. It was determined that MFL-modified pavements did not freeze easily at low temperatures. Furthermore, the effective snow removal time of MFL was determined to be 6-10 years (Dubois, 1977). In 1995, Johannes developed Verglimit-260 (V-260 for short), a salt-deposit material now widely used. V-260 is made of CaCl₂ particles modified with a hydrophobic agent. The product can replace the corresponding particle size aggregate in the mix. Asphalt mixes containing V-260 have improved high and low temperature performance but decreased water stability, although they still meet the requirements. Salt storage material cannot be damaged without an external force, and external water cannot penetrate the material. At the same time, the material exhibits hydrophobicity when the external temperature is above 1°C. When the temperature is below 1°C, the salt storage material becomes brittle and fragile, and water can quickly penetrate the structure to dissolve the salt. In 2001, phenolic resin was used as a new salt storage material to encapsulate molten salt (Suren and Kaemereit, 2003).

ELECTRICALLY CONDUCTIVE ASPHALT PAVING

Traditional asphalt mixtures primarily consist of coarse and fine aggregates, asphalt binder, and mineral fillers. Due to the high electrical resistance of these components, such mixtures typically have a resistance value between 10⁸ and 10¹² Ω.m, acting as insulators (Wu et al., 2002). Research indicates that by adding conductive materials to these insulators, their resistance values can be reduced to below 10 Ω.m, making them conductive. Electro-thermal paving offers an environmentally friendly, robust, and easily controllable system for snow removal and other road surface issues (Gao et al., 2016; Lai et al., 2014; Zhao et al., 2011). In this system, heat is transferred to the pavement surface via an embedded heating element, melting snow and ice on the road surface (Jiao et al., 2022; Oyewunmi et al., 2017). Increasing the thermal conductivity of the asphalt mixture in the top layer of an electro-thermal coating system is one of the effective methods to improve snow and ice melting capacity. The conductive materials used are divided into three categories according to their size: those in powder form such as graphite, carbon black, and aluminum shavings; those in fibrous form

such as carbon and steel fibers; and coarse and fine aggregates used partially or completely as steel slag. However, the use of asphalt concretes enriched with only one type of conductive material may involve some limitations and challenges. For example, the cost of adding conductive material may increase and may have negative effects on mechanical performance. Nevertheless, researchers believe that conductive asphalt concretes prepared using combinations of different types of conductive materials can have sufficient mechanical and electrical properties and can also be advantageous in terms of cost (Huang et al., 2009).

SUPER HYDROPHOBIC ASPHALT PAVING

Creating a hydrophobic surface to reduce ice bonding on road pavements has become a significant issue due to its excellent anti-freeze properties and labor savings (Ma et al., 2014). Hydrophobic de-icing coatings focus on breaking the ice-pavement adhesion interface rather than removing all the ice from the pavement. The Minnesota DOT Winter Maintenance Report also suggests that the goal of de-icing pavement is not to melt all the ice and snow accumulated on the road, but to break the bond between ice and pavement to create suitable conditions for snow removal operations. Making the roadway hydrophobic can be achieved by creating a structural coating layer that is hydrophobic or by painting the pavement with a hydrophobic material. Given wheel load and wear on the pavement, it is difficult for painting with a hydrophobic material to remain on the pavement for a sufficiently long time (Chen et al., 2018). Hydrophobic coating technology can quickly impart a low surface energy surface to the pavement, making the pavement virtually inert to water and ultimately virtually inert to ice. However, the service life of the hydrophobic coating may be affected by the wear present between the coating and the tire. As shown in the figure, the contact angle of the polymer-modified asphalt mixture containing nano-CaO and fluorine, which was given hydrophobic properties, increased from 98° to 163° (Machado et al., 2011). In the study where the hydrophobic coating was prepared with silanol and nano-sized SiO₂, the contact angle reached 150.7° . In addition, it was found that the amount of residual ice in the hydrophobic asphalt coating was much smaller than in the control group (Gao et al., 2017). Besides the ice retention property of the hydrophobic coating, skid resistance is also important. Because a decrease in the coefficient of friction while giving the coating hydrophobic properties may lead to safety problems. However, it has been reported that the hydrophobic coating provides the necessary friction for traffic safety (Xu and Hua, 2012). In a study using fluorosilane and nano SiO₂ for the production of superhydrophobic asphalt pavement, it was found that they could effectively support the rolling of water droplets off the pavement surface, and the rolling speed could reach 80%. Compared to conventional asphalt pavement, superhydrophobic asphalt pavement significantly reduced the adhesion forces between ice and the road. The observed effect of superhydrophobic asphalt concrete was the delay of frost formation and evolution. When freezing snow and freezing rain conditions were encountered, the ice residue rate on superhydrophobic asphalt concrete was approximately 21.6% and 48.6% of that on conventional asphalt concrete, respectively. Abrasion testing proved that the superhydrophobic material had better durability. Theoretical results showed that the surface energy on the surface of superhydrophobic samples was approximately 5% of that of conventional asphalt concrete. It was determined that the shear resistance performance of superhydrophobic asphalt concrete met the requirements of the specification (Gao et al., 2018).

PHASE CHANGE MATERIAL ASPHALT PAVEMENTS

Phase change materials are materials that change their phase states by absorbing or releasing heat. They have the ability to store heat and control temperature. Phase change materials are an excellent system for managing the temperatures of asphalt pavements and thus solving temperature-related problems, since their behavior is temperature-dependent (Figure 4.8). In

asphalt pavements, the phase change temperature needs to be above 5 °C and below 40 °C to reduce low-temperature cracking, snow and ice formation, and high-temperature rutting. Furthermore, it is desirable for the phase change material to have high latent heat and thermal conductivity to possess sufficient thermal storage capacity and efficient heat transfer performance. Fatty acids, paraffin, and their composites were used to regulate the temperature of asphalt pavements to prevent cracking, freezing, and icing at low temperatures, forming phase change materials (Bian et al., 2012; Chen et al., 2011; Li et al., 2010; Ma et al., 2010, 2011a, 2011b, 2014). Subsequently, it was found that the heat absorption of phase change materials under relatively high temperature conditions could be used to reduce wheel rutting and the urban heat island effect of asphalt pavements. Among these, polyol-based phase change materials such as PEG showed superior properties (He et al., 2013; Jin et al., 2017; Liu et al., 2021). Currently, many phase change materials are suitable for asphalt pavement temperature regulation, but unencapsulated solid-liquid PCMs are prone to volatilization, leaching, and degrading the performance of asphalt and asphalt mixes when used directly in asphalt or asphalt mixes (Dai et al., 2021; Kakar et al., 2020). Therefore, effective encapsulation of solid-liquid PCMs when used in asphalt and asphalt mixes has become of great importance. Phase change materials are substances that absorb and release thermal energy during the melting and freezing process. When a phase change material freezes, it releases energy in the form of latent heat at a relatively constant temperature. Conversely, when such a material melts, it absorbs heat from the environment. Phase change materials recharge as ambient temperatures fluctuate, making them ideal for a variety of engineering applications requiring temperature control (Sharma et al., 2009). Consequently, phase change materials impart thermal energy storage capabilities to asphalt pavements to mitigate the effects of pavement temperature fluctuations during daily and seasonal cycles (Refaa et al., 2018; Wei et al., 2019). This capability reduces snow accumulation and ice formation on the surface of asphalt pavements (Esmaeeli et al., 2018).

GROUND SOURCE HEAT PIPES

Ground source heat pipes transfer heat energy from an area of high temperature to an area of low temperature using a fluid phase transformation system. The source from which heat is drawn can be in solid, liquid, or gaseous form. The key point here is that the area from which heat is drawn must be larger than the area to which heat is given. In winter months, the temperature at depth in the soil remains above the normal atmospheric temperature and does not change significantly after a certain depth. Soil is a continuous heat source. The heat energy contained within the soil is utilized using various methods. One of the prominent of these methods is ground source heat pipes. The difference between ground source heat pipes and other heat pipes is that the environment from which heat is drawn or given is the soil. Ground source heat pipes can continuously draw or give heat to the soil (Balbay and Esen, 2007). Thus, with the help of heat energy drawn from the soil using ground source heat pipes, icing on road surfaces caused by precipitation in cold weather can be prevented. Ground source heat pipes operate without the need for pumps, control systems, or external power. By using a ground source heat pipe to provide heat to the area where icing would occur on the surface, icing will be prevented. Thus, traffic accidents caused by snow or ice on highways will be prevented. Ground source heat pipe systems can be used to melt ice and snow because they can operate passively without the need for an external energy source. In the installation phase of the ground source heat pipe shown in Figure 4.9, it is filled with ammonia liquid or freon gas and placed in the ground. The fluid is heated at the bottom of the heat pipe by the temperature of the ground. The heated fluid moves to the condenser section where the pipes are located in the area to be heated and releases its heat by condensing (Akbulut et al., 2015). The condensed fluid completes its cycle under the influence of gravity and returns to the evaporator, and the process ends (Lund, J. W., 2000).

SOLAR HEAT PIPES

Asphalt pavements, exposed to solar radiation throughout the day, can absorb large amounts of solar energy, which is dissipated as thermal energy within the pavement structure. Due to its high solar radiation absorption coefficient, it has been determined that the surface temperature of asphalt pavements can reach up to 70°C during hot summer months. As a result, this high temperature will cause permanent deformations in the asphalt pavement due to the effects of traffic. It can also accelerate thermal oxidation and thus reduce pavement performance. On the other hand, high surface temperatures on the pavement lead to environmental problems. High surface temperatures cause the urban heat island effect (UHIS). With the development of energy harvesting technologies, the idea of obtaining energy from existing infrastructure has emerged. Converting asphalt pavements into an energy source is also an interesting topic of current interest. The most current examples are thermoelectric generators, piezoelectric generators, photovoltaic applications, and asphalt solar collectors. Asphalt solar collector systems can consist of either a tubular asphalt concrete layer or a porous asphalt layer surrounded by two impermeable layers. Given the extremely high surface temperatures of asphalt during the summer, the fluid circulating between the pipe networks can reduce the temperature both in the internal structure and on the surface of the asphalt pavement. Water can be pumped from an aquifer or any other source reservoir. Solar heat pipes have higher energy harvesting efficiencies and lower operating costs compared to Joule heating methods. Solar heat pipes can capture solar energy in the summer and release heat to melt snow in the winter, making this type of pavement more attractive (Chen et al., 2011). The thermal behavior of a solar heat pipe system largely depends on the thermophysical properties of the material, the pipe arrangements, and the fluid operating parameters. Thermal conductivity significantly affects the distribution of temperature at different depths. Increasing conductivity is effective in improving the energy efficiency of the system (Pan et al., 2015).

CONDUCTIVE HEATING CABLES

These systems, called underfloor heating, use heating cables or pipes placed beneath the pavement to maintain the pavement surface temperature consistently above freezing, adapting to adverse road conditions. These systems are particularly suitable in areas where road surfaces show significant wheel ruts. Surface temperature changes are continuously monitored using sensors mounted on the surface (Zhang, 2009). A similar system has been implemented in Turkey on the protocol road connecting Esenboğa Airport to Ankara.

HYDRONIC (GEOTHERMAL) SYSTEMS

Using a geothermal heat pump, hot water extracted from underground is sent through a heat exchanger to propylene glycol, which then circulates in pipes located beneath the road, preventing icing on the surface. Propylene glycol is used because it lowers the freezing point of water. This fluid circulates in polyethylene pipes located beneath the road. The spiral pipes are placed 75 mm below the pavement, and the pavement thickness should be 200 mm. For example, in Oklahoma, United States, 16 heat pumps were used on a 12x215 m bridge deck, consuming a total of 106 kW of power (Zhang et al., 2009). Hydronic systems are primarily used to prevent icing on bridges.

MICROWAVE HEATING SYSTEM

To prevent icing on highways, the pavement is heated using aggregates with microwave and magnetic charge carrying properties. It was envisioned that this system could be used to remove snow and ice from asphalt concrete surfaces such as airport runways, sidewalks, bridges, and highways in all seasons without the use of chemicals (Henderson, 1963). By driving a vehicle

loaded with a microwave generator over pavements produced with asphalt mixtures obtained by adding these aggregates, the microwaves pass through the ice and are retained as heat at the pavement-ice interface. As a result, the ice melts easily (Hopstock, 2003).

INFRARED HEAT LAMPS

In Denver, Colorado, infrared heat lamps were used as external heating elements on the Mississippi Bridge to prevent icing. These lamps attempted to heat the underside of the bridge with a power of 75 W/m². Infrared heating is defined as a method of heat transfer by light and can transmit more heat than other types of light. This system is designed to prevent excessive icing on roads or bridge decks. It is also effective in melting snow that accumulates upwards from the edges of the road. Infrared systems have the advantage of being able to heat the desired area quickly. However, it has been concluded that these heat lamps cannot completely prevent ice formation on the road surface due to insufficient power and slow heating (Zenewitz, 1977; Lund, 2000).

TECHNOLOGICAL ADVANCEMENTS COMPATIBLE WITH SMART TRANSPORTATION SYSTEMS

Billions of dollars are spent worldwide each year on developing new methods to combat snow and ice. One of the most important of these efforts is the development of automated systems using weather monitoring stations. Ice control applications can be successfully implemented with weather information. This includes when precipitation is expected to begin, the type of precipitation, possible air temperatures, temperature trends during and after storms, and wind speed and direction for each geographical region. Surface temperature estimates can be made via sensors, and necessary warnings about low temperatures can be given. This provides time to plan before a freezing event. In addition, some sensors can provide information about the concentration of chemicals on the surface, helping to decide whether or not a further intervention is necessary. Road weather information systems (RWIS) have become quite common in the USA, Canada, Japan, and Europe. These systems include units that collect weather data and monitor road conditions. RWIS stations contain many sensors, and these stations generally include atmospheric sensors, sensors placed on and under the road surface, data processors, and communication devices. Data from the sensors is processed by the RPU (Remote Processing Unit) and transmitted to the central processing unit (CPU). This information can be stored, transmitted to other areas, or used directly. Having the most up-to-date and accurate weather and road condition information is crucial for decisions regarding snow and ice control (Agar and Kutluhan, 2005; FHWA, 1996). One of the new systems developed for combating ice is the stationary automatic spray system. This system detects icing of the road surface and automatically applies liquid anti-icing chemicals in a spray form.

CONCLUSION

This study examines methods used to combat snow and ice on highways. The following conclusions were reached as a result of the literature review:

The use of snow fences should be widespread in areas where wind is a factor and therefore snow accumulation is high. This will reduce the amount of snow falling on the road and the subsequent ice formation. Consequently, other snow removal operations will require less effort, and an economical solution will be provided.

When snowfall is heavy, physically removing the snow with machines and cleaning the road after chemical application is beneficial. Although this method may seem traditional, it should be readily available in case of system failures and emergencies.

Instead of waiting for ice formation after snowfall, intervening beforehand reduces the use of de-icing materials and prevents further reduction in the friction coefficient of the pavement. In

this respect, anti-icing application is advantageous in terms of cost and safety. NaCl salt is generally used in ice control. Using MgCl₂, which is similarly costly, would be less harmful to the natural environment. Furthermore, adding organic matter to these types of salts would reduce both their cost and environmental impact. Instead of chloride-based salts, which have been proven to harm metal structures and the natural environment, the use of organic-based chemicals such as calcium magnesium acetate and potassium acetate should be widespread. Furthermore, using these chemicals in liquid form should prevent material losses and increase the rate of ice melting. Road sections such as intersections where vehicles must slow down and stop, bridges that ice over faster due to their open undersides, and steep inclines where vehicle speed must be controlled are more critical, making snow and ice control even more important due to the high number of traffic accidents. The use of active systems should be preferred in these areas. This will not only increase traffic safety but also allow management authorities responsible for snow and ice control to redirect machinery and manpower to secondary priority areas, thus enabling more effective control. Additionally, while heating systems such as heat pipes, conductive cables, microwaves, and infrared are useful, their initial installation and operating costs are high. Therefore, adding additives to the asphalt mixture to prevent icing remains a beneficial and current approach. While various additives are used to prevent ice formation on the pavement surface of asphalt mixtures, care must be taken to ensure that the additive used does not reduce the performance of the bituminous mixtures. In this context, when producing conductive and hydrophobic asphalt, care should be taken to ensure that the additives used not only melt the ice but also contribute to performance, or at least do not affect it. One of the most important factors affecting asphalt pavements is temperature. Asphalt, by its nature, is a material that maintains its conductivity above low temperatures. This makes asphalt pavements susceptible to permanent deformations with high temperatures in summer and to thermal cracking and icing with low temperatures in winter. The use of phase change materials as additives that both prevent icing and provide resistance against permanent deformation and crack formation is of great importance as a multifaceted approach.

Finally, in snow and ice control methods on highways, the use of low-cost and waste materials, renewable energy sources, and their integration with smart transportation systems will reduce costs, protect the natural environment, and increase safety.

REFERENCES

- Aghazadeh, N., Nojavan, M., & Mogaddam, A. A. (2010). Effects of road-deicing salt (NaCl) and saline water on water quality in the Urmia area, northwest of Iran. *Arabian Journal of Geosciences*, 5(4), 565-570.
- Chatterji, S. (1999). Aspects of freezing process in porous material-water system: Part 2. Freezing and properties of frozen porous materials. *Cement and Concrete Research*, 29(5), 781-784.
- Chen, H., Wu, Y., Xia, H., Jing, B., & Zhang, Q. (2018). Review of ice-pavement adhesion study and development of hydrophobic surface in pavement deicing. *Journal of traffic and transportation engineering (English edition)*, 5(3), 224-238.
- Chen, J., Ma, X., Wang, H., Xie, P., & Huang, W. (2018). Experimental study on anti-icing and deicing performance of polyurethane concrete as road surface layer. *Construction and Building Materials*, 161, 598-605.
- Chen, M., Wu, S., Wang, H., & Zhang, J. (2011). Study of ice and snow melting process on conductive asphalt solar collector. *Solar Energy Materials and Solar Cells*, 95(12), 3241-3250.
- Dubois, R. (1977). U.S. Patent No. 4,012,537. Washington, DC: U.S. Patent and Trademark Office.

- Feng, B., Wang, H., Li, S., Ji, K., Li, L., & Xiong, R. (2022). The durability of asphalt mixture with the action of salt erosion: A review. *Construction and Building Materials*, 315, 125749.
- Gao, J., Sha, A., Wang, Z., Tong, Z., & Liu, Z. (2017). Utilization of steel slag as aggregate in asphalt mixtures for microwave deicing. *Journal of Cleaner Production*, 152, 429-442.
- Gao, Y., Dai, K., Huang, L., Zheng, C., & Xin, T. (2017). Research and application of superhydrophobic and anti-icing technology in highway pavement. *Mater Rep*, 31, 103.
- Gao, Y., Huang, L., & Zhang, H. (2016). Study on anti-freezing functional design of phase change and temperature control composite bridge decks. *Construction and Building Materials*, 122, 714-720.
- Gao, Y., Qu, L., He, B., Dai, K., Fang, Z., & Zhu, R. (2018). Study on effectiveness of anti-icing and deicing performance of super-hydrophobic asphalt concrete. *Construction and Building Materials*, 191, 270-280.
- Hassan, Y., Abd El Halim, A. O., Razaqpur, A. G., Bekheet, W. ve Farha, M. H., "Effects of Runway Deicers on Pavement Materials and Mixes: Comparison with Road Salt" *Journal of Transportation Engineering*, 385–391, 2002.
- He, Y., Li, Y., Wang, Y., Brooks, A. L., Polaczyk, P., Huang, B., & Zhou, H. (2024). Coal-derived conductive pavement for winter de-icing: prototype, modeling, and simulation. *Applied Thermal Engineering*, 123356.
- Henderson, D. J., "Experimental Roadway Heating Project on a Bridge Approach", *Highway Research Records*, 14–23, 1963.
- Hopstock, D. M., "Microwave-Absorbing Road Construction and Repair Material", Final Report to NRRRI on Idea Evaluation Subcontract, 2003.
- Hu, C., Zhao, Q., Li, P., Feng, C., & Zhu, Y. (2023). Study on electrical conductivity of hot mix asphalt with copper slag and carbon fiber. *Construction and Building Materials*, 395, 132366.
- Huang, B., Chen, X., & Shu, X. (2009). Effects of electrically conductive additives on laboratory-measured properties of asphalt mixtures. *Journal of Materials in Civil Engineering*, 21(10), 612-617.
- Huang, K., Liu, J., Wang, J., & Shi, X. (2021). Characterization and mechanism of a new superhydrophobic deicing coating used for road pavement. *Crystals*, 11(11), 1304.
- Huang, L. S., Lin, D. F., Luo, H. L., & Lin, P. C. (2012). Effect of field compaction mode on asphalt mixture concrete with basic oxygen furnace slag. *Construction and Building Materials*, 34, 16-27.
- Jiang, Q., Chen, M., Zhao, Y., Wu, S., Fan, Y., Gan, Z., & Zhang, Y. (2022). Comprehensive assessment of the durability deterioration of asphalt pavement in salt environment: A literature review. *Case Studies in Construction Materials*, 17, e01706.
- Jiang, W., Xiao, J., Yuan, D., Lu, H., Xu, S., & Huang, Y. (2018). Design and experiment of thermoelectric asphalt pavements with power-generation and temperature-reduction functions. *Energy and Buildings*, 169, 39-47.
- Jiang, W., Yuan, D., Shan, J., Ye, W., Lu, H., & Sha, A. (2022). Experimental study of the performance of porous ultra-thin asphalt overlay. *International Journal of Pavement Engineering*, 23(6), 2049-2061.
- Jiao, W., Sha, A., Liu, Z., Li, W., Zhang, L., & Jiang, S. (2022). Optimization design and prediction of the snow-melting pavement based on electrical-thermal system. *Cold Regions Science and Technology*, 193, 103406.
- Kakar, M. R., Refaa, Z., Worlitschek, J., Stamatiou, A., Partl, M. N., & Bueno, M. (2019). Thermal and rheological characterization of bitumen modified with microencapsulated phase change materials. *Construction and Building Materials*, 215, 171-179.
- Ke, G., Zhang, J., & Tian, B. (2019). Evaluation and selection of de-icing salt based on multi-factor. *Materials*, 12(6), 912.

- Kıgılı , A., F (2014) Karayollarında Kar Ve Buz Mücadelesi Yönetiminde Yeni Bir Maliyet Hesabı Önerisi , Yüksek Lisans Tezi , YTÜ , Fen Bilimleri Enstitüsü , İstanbul .
- Klein-Paste, A. (2018). Airplane braking friction on dry snow, wet snow or slush contaminated runways. *Cold regions science and technology*, 150, 70-74.
- Lai, Y., Liu, Y., & Ma, D. (2014). Automatically melting snow on airport cement concrete pavement with carbon fiber grille. *Cold Regions Science and Technology*, 103, 57-62.
- Lee, B. D., Choi, Y. S., Kim, Y. G., Kim, I. S., & Yang, E. I. (2017). A comparison study of performance and environmental impacts of chloride-based deicers and eco-label certified deicers in South Korea. *Cold Regions Science and Technology*, 143, 43-51.
- Li, C., Huang, L., Zhou, M., Xia, J., Ma, H., Zang, S., & Wang, L. (2013). Synthesis, structure and characterization of two new open-framework gallium phosphite-oxalates of varying dimensionality. *Journal of Solid State Chemistry*, 208, 86-92.
- Li, F., & Wang, Z. (2012). Experiment on road performance of asphalt mixture with automatic long-term snowmelt agent. *Journal of Highway and Transportation Research and Development (English Edition)*, 6(4), 11-17.
- Li, H., Lin, X., & Wang, H. (2021). Fabrication and evaluation of nano-TiO₂ superhydrophobic coating on asphalt pavement. *Materials*, 14(1), 211.
- Li, Y., Sha, A., Tian, Z., Cao, Y., Li, X., & Liu, Z. (2023). Review on superhydrophobic anti-icing coating for pavement. *Journal of Materials Science*, 58(8), 3377-3400.
- Liu, J., Zhang, T., Guo, H., Wang, Z., & Wang, X. (2022). Evaluation of self-healing properties of asphalt mixture containing steel slag under microwave heating: Mechanical, thermal transfer and voids microstructural characteristics. *Journal of Cleaner Production*, 342, 130932.
- Liu, X., Rees, S. J., & Spitler, J. D. (2007). Modeling snow melting on heated pavement surfaces. Part I: Model development. *Applied Thermal Engineering*, 27(5-6), 1115-1124.
- Lu, D., Jiang, X., Leng, Z., Huo, Y., Wang, D., & Zhong, J. (2023). Electrically conductive asphalt concrete for smart and sustainable pavement construction: A review. *Construction and Building Materials*, 406, 133433.
- Ma, T., Geng, L., Ding, X., Zhang, D., & Huang, X. (2016). Experimental study of deicing asphalt mixture with anti-icing additives. *Construction and Building Materials*, 127, 653-662.
- Machado, P., Freitas, E. F., Nascimento, J. H. O. D., Pereira, P. A., Carneiro, J. A., & Teixeira, V. M. (2011). A biomimetic composite asphaltic/nanostructured material with superhydrophobic and anti-ice properties for road pavements.
- Menzies, T. R., "National Cost of Damage to Infrastructure From Highway Deicing", *Corrosion Forms and Control For Infrastructure*, ASTM STP 1137, American Society for Testing and Materials, Philadelphia, 30-46, 1991.
- Oyewunmi, O. A., Kirmse, C. J., Haslam, A. J., Müller, E. A., & Markides, C. N. (2017). Working-fluid selection and performance investigation of a two-phase single-reciprocating-piston heat-conversion engine. *Applied energy*, 186, 376-395.
- Pan, P., Wu, S., Xiao, F., Pang, L., & Xiao, Y. (2015). Conductive asphalt concrete: A review on structure design, performance, and practical applications. *Journal of Intelligent Material Systems and Structures*, 26(7), 755-769.
- Sajid, H. U., Naik, D. L., & Kiran, R. (2021). Improving the ice-melting capacity of traditional deicers. *Construction and Building Materials*, 271, 121527.
- Sanzo, D., & Hecnar, S. J. (2006). Effects of road de-icing salt (NaCl) on larval wood frogs (*Rana sylvatica*). *Environmental pollution*, 140(2), 247-256.
- Sun, Y., Wu, S., Liu, Q., Hu, J., Yuan, Y., & Ye, Q. (2018). Snow and ice melting properties of self-healing asphalt mixtures with induction heating and microwave heating. *Applied Thermal Engineering*, 129, 871-883.
- Suren, J.; Kaemereit, W. Method and Product for Preventing Slippery Road Condition in Winter. U.S. Patent Application No. 20,030,116,749, 12 November 2003.

- Varış, M. (2007). Karayolları esnek üstyapılarında buzlanma ile mücadele yöntemleri. Yüksek Lisans Tezi. Süleyman Demirel Üniversitesi, Fen Bilimleri Enstitüsü, İnşaat Mühendisliği Anabilim Dalı. Isparta. 83s
- Wan, J., Wu, S., Xiao, Y., Fang, M., Song, W., Pan, P., & Zhang, D. (2019). Enhanced ice and snow melting efficiency of steel slag based ultra-thin friction courses with steel fiber. *Journal of cleaner production*, 236, 117613.
- Wu, B., Cui, X., Jiang, H., Wu, N., Peng, C., Hu, Z., ... & Li, D. (2021). A superhydrophobic coating harvesting mechanical robustness, passive anti-icing and active de-icing performances. *Journal of Colloid and Interface Science*, 590, 301-310.
- Xu, H. N., Tan, Y. Q., Zhou, C. X., & Zhang, R. (2012). Temperature distribution characteristic in solar-ground source coupled snow-melting system for bridge deck. *Acta Energiæ Solaris Sinica*, 33(11), 1920-1925.
- Xu, H., Wang, D., Tan, Y., Zhou, J., & Oeser, M. (2018). Investigation of design alternatives for hydronic snow melting pavement systems in China. *Journal of cleaner production*, 170, 1413-1422.
- Yuan, D., Jiang, W., Sha, A., Xiao, J., Wu, W., & Wang, T. (2023). Technology method and functional characteristics of road thermoelectric generator system based on Seebeck effect. *Applied Energy*, 331, 120459.
- Zenewitz, J. A., "Survey of Alternatives to The Use of Chlorides for Highway Deicing", Federal Highway Administration Offices of Research and Development, Report No. FHWA-RD-77-52, Washington, 1977.
- Zhang, D., Birgisson, B., Luo, X., & Onifade, I. (2019). A new long-term aging model for asphalt pavements using morphology-kinetics based approach. *Construction and Building Materials*, 229, 117032.
- Zhao, H., Wu, Z., Wang, S., Zheng, J., & Che, G. (2011). Concrete pavement deicing with carbon fiber heating wires. *Cold Regions Science and Technology*, 65(3), 413-420.

**ÖĞRETMENLERDE PSİKOLOJİK SERMAYENİN TÜKENMİŞLİK ÜZERİNE
ETKİSİ: SİSTEMATİK BİR GÖZDEN GEÇİRME**

Yusuf Erdem YILDIZ

Dokuz Eylül Üniversitesi, Eğitim Bilimleri Enstitüsü,
<https://orcid.org/0009-0003-8521-7769>

Prof. Dr. Hatice Zekavet KABASAKAL

Dokuz Eylül Üniversitesi, Eğitim Bilimleri Enstitüsü,
<https://orcid.org/0000-0002-3450-1060>

ÖZET

Bu sistematik derleme çalışması, öğretmenlerde psikolojik sermayenin tükenmişlik üzerindeki etkisini incelemeyi amaçlamaktadır. Literatürde öğretmenlik mesleğinde tükenmişlik olgusunun son yıllarda belirgin biçimde artış gösterdiği ve bunun duygusal tükenme, duyarsızlaşma ve kişisel başarıda azalma gibi boyutlarda kendini gösterdiği görülmektedir. Web of Science veri tabanında “teacher”, “burnout” ve “psychological capital” anahtar sözcükleriyle yapılan tarama sonucunda 23 çalışma incelenmiş, araştırma amacına uygun bulgular sunan çalışmalar sistematik biçimde değerlendirilmiştir. Bulgular, yüksek psikolojik sermayeye sahip öğretmenlerin iş stresini daha etkili yöneterek duygusal tükenme ve duyarsızlaşma düzeylerini anlamlı ölçüde düşürdüğünü; psikolojik sermayenin, özellikle mesleki kimlik ve öz-düzenleme gibi aracı mekanizmalar yoluyla tükenmişliğe karşı güçlü ve koruyucu bir tampon işlevi gördüğünü göstermektedir. Ayrıca umut ve iyimserlik bileşenlerinin, stres faktörlerinin yıkıcı etkisini minimize etmede baskın bir rol oynadığı tespit edilmiştir. Sonuç olarak, öğretmen tükenmişliği ile mücadelede yalnızca iş yükünü azaltmaya odaklanan dışsal önlemlerin yeterli olmadığı, bununla birlikte bireyin içsel psikolojik kaynaklarının güçlendirilmesinin kritik bir gereklilik olduğu değerlendirilmektedir.

Anahtar Kelimeler: Tükenmişlik, Psikolojik Sermaye, Öğretmenler, Sistematik Derleme

This systematic review aims to examine the effect of psychological capital on burnout among teachers. The literature indicates that burnout in the teaching profession has increased significantly in recent years, manifesting itself in dimensions such as emotional exhaustion, depersonalisation, and reduced personal accomplishment. A search of the Web of Science database using the keywords "teacher", "burnout" and "psychological capital" yielded 23 studies, which were systematically evaluated for findings relevant to the research objective. The findings show that teachers with high psychological capital manage work stress more effectively, significantly reducing their levels of emotional exhaustion and cynicism; psychological capital acts as a strong and protective buffer against burnout, particularly through mediating mechanisms such as professional identity and self-regulation. Furthermore, it was found that the components of hope and optimism play a dominant role in minimising the destructive effects of stress factors. Consequently, it is concluded that external measures focused solely on reducing workload are insufficient in combating teacher burnout, and that strengthening the individual's internal psychological resources is a critical necessity.

Keywords: Burnout, Psychological Capital, Teachers, Systematic Review

1. GİRİŞ

Öğretmenlik mesleğinde tükenmişlik olgusu son yıllarda giderek yaygınlaşmış ve akademik literatürde daha fazla araştırma konusu olmaya başlamıştır. Bu kanıyı desteklemek amacıyla çalışmanın yürütülmesinde veri toplama aracı olarak kullanılan uluslararası dizin Web of Science’ta yayınlanmış olan ve başlığında tükenmişlik ve öğretmen kavramları yer alan

çalışmaların yayın dağılımı incelenmiştir. Yapılan incelemede 1980 yılından 2018 yılına kadar bir yılda en fazla 63 yayın yapılmıştır. 2019 yılı itibarıyla her yıl 100 ve üzerinde çalışmanın yayınlandığı görülmektedir. Bu ciddi artış, tek başına tükenmişliğin son 5 yılda çok yüksek bir reel artış gösterdiğini kanıtlamaz. 2019 yılından bu yana akademik yayınlardaki genel artış, verilerin elde edildiği dizinin kapsam genişlemeleri, Covid-19 pandemisi vb. etkenlerinde bu artışta rol oynadığı değerlendirilmektedir. Yine de bu keskin artış, tükenmişlik olgusunun son yıllarda önem kazandığını ortaya koymaktadır.

Öğretmenlerde tükenmişlik mesleğe özgü bir çerçevede değerlendirilecek olduğunda Maslach iş tükenmişliği kavramını şöyle tanımlamıştır: “İş tükenmişliği, işle ilgili kronik kişilerarası stres etmenlerine verilen uzun süreli bir tepkidir” (Maslach, 1998). Tıpkı pek çok meslekte olduğu gibi, öğretmenlikte de tükenmişliğin yaygınlaşmasında iş ortamına ilişkin ortak bazı etkenler etkili olmaktadır. Özellikle görev yükünün artması, mesai saatlerinin uzaması ve zaman baskısının yaşamsal sorumluluklarla çakışması, öğretmenlerin dinlenme ve kendilerini yenileme fırsatlarını sınırlandırmakta ve bu durum sürekli bir bitkinlik hissine neden olabilmektedir. Buna ek olarak, görev tanımlarının belirsizliği ve rol çatışmaları da genel anlamda iş stresini besleyen önemli unsurlar arasında yer almaktadır. Ancak öğretmenler, mesleki yapısı gereği karşılaştıkları özel zorluklar nedeniyle tükenmişliğe daha açık hale gelmektedir. Örneğin sınıf ortamında öğrencilerin disiplin problemleriyle sürekli uğraşmak ya da onların hem akademik hem de duygusal gereksinimlerine karşılık vermeye çalışmak, öğretmenlerin ciddi düzeyde duygusal emek harcamasını gerektirir. Öte yandan, veliler ile okul yönetiminin yüksek düzeyde beklentileri öğretmenler üzerinde ek baskı ve stres yaratabilmektedir. Ayrıca, eğitim programlarında sık sık yaşanan değişiklikler de öğretmenlerde uyum sorunlarına yol açabilir. Her eğitim-öğretim yılında yeni öğrenci gruplarıyla benzer süreçlerin yeniden yaşanması ise, mesleki tükenmişliğin bir diğer tetikleyici unsurudur. Bunun yanında, öğretmenliğin toplumsal saygınlığının azalması ve ekonomik koşulların yetersizliği gibi faktörler, öğretmenlerin kendilerini değersiz ve tükenmiş hissetme riskini artırmaktadır. Tüm bu nedenlerin bir araya gelmesi, öğretmenlerde duygusal tükenme, işe karşı ilgisizlik ve kişisel başarı hissini zayıflaması gibi tükenmişlik belirtilerinin ortaya çıkmasına zemin hazırlamaktadır.

Bu bağlamda son dönemde öğretmenlerin tükenmişlikle başa çıkmasında koruyucu bir faktör olarak *psikolojik sermaye* kavramına dikkat çekilmektedir. Bu bileşik yapı, Luthans’a göre (2007) “bir bireyin olumlu psikolojik gelişim durumu” olarak tanımlanmıştır ve şu özelliklerle karakterize edilir: (1) zorlu görevleri üstlenmek ve başarıya ulaşmak için gerekli çabayı göstermek konusunda güven sahibi olmak (öz-yeterlik); (2) şu anda ve gelecekte başarılı olacağına dair olumlu bir değerlendirme yapmak (iyimserlik); (3) hedeflere doğru azimle ilerlemek ve gerektiğinde hedeflere ulaşmak için yolları yeniden yönlendirmek (umut); ve (4) sorunlar ve zorluklarla karşılaşıldığında dayanıklılık göstererek toparlanmak ve hatta bu durumların ötesine geçerek başarıya ulaşmak (psikolojik dayanıklılık)” (Luthans, 2007). Literatürde, yüksek psikolojik sermayeye sahip öğretmenlerin iş stresini daha iyi yöneterek tükenmişlik düzeylerini azalttığı vurgulanmaktadır. Bu çalışmada öğretmenlerde psikolojik sermayenin tükenmişlik üzerine etkisi sistematik olarak gözden geçirilmiştir. Çalışmanın bulgularına geçmeden önce tükenmişlik ve psikolojik sermaye kavramları ele alınacaktır.

Tükenmişlik Maslach'ın modelinde, bileşik bir kavram olarak üç boyutta ele alınmaktadır: duygusal tükenme, duyarsızlaşma ve yetersizlik. Maslach ve arkadaşları tarafından tükenmişliğin merkezi boyutu olarak nitelendirilen duygusal tükenme tükenmişliğin üç boyutu arasında en sık bildirilen ve en kapsamlı şekilde analiz edilen boyutudur (Maslach, Schaufeli, & Leiter, 2001). Duygusal tükenme, kişilerin işlerinde yorulmalarını ve kendilerini duygusal açıdan aşırı yıpranmış hissetmelerini ifade etmektedir. Enerji eksikliği ve kişinin duygusal kaynaklarının bittiği hissine kapılması biçiminde ortaya çıkmaktadır (Akyürek, 2020). Duyarsızlaşma, tükenmişliğin ikinci boyutudur. Bu aşamada tükenen kişi, işin gereği olarak hizmet verdiği kişilere karşı sanki duyguları olmayan nesnelermişçesine katı ve ilgisiz tutum sergilemekte ve onlara duygudan yoksun şekilde kaba ve aşağılayıcı davranmaktadır. Çalışma ortamındaki diğer çalışma arkadaşlarına karşı da inancını yitirerek donuklaşabilir ve uzaklaşabilir (Duygun, 2023). Son boyut, yetersizlik ya da diğer bir ifade ile başarısızlık hissidir. Kişi başkaları hakkında geliştirdiği olumsuz düşünce ve kaba davranışlar neticesinde kendini başarısız olarak nitelendirir ve tükenmişliğin son boyutu olan düşük kişisel başarı ortaya çıkar (Cantürk, 2024).

Öğretmenler üzerine yaptığı bir ölçek çalışmasında Byrne, Maslach modeline göre tükenmişliğin boyutlarını öğretmenlerde şu örnek ile ifade etmiştir: “Öğretmenler, kariyerlerinin başlarında öğrencilerine kendilerinden verdikleri gibi artık veremediklerini hissettiklerinde duygusal tükenmişlik belirtileri gösterirler; öğrenciler, veliler ve/veya meslektaşlarına karşı olumsuz, alaycı ve bazen de duyarsız tutumlar geliştirdiklerinde duyarsızlaşma yaşarlar; öğrencilerin öğrenmelerine yardımcı olma ve diğer okul sorumluluklarını yerine getirme konusunda kendilerini etkisiz hissettiklerinde ise azalmış kişisel başarı duygusu yaşarlar” (Byrne, 1994).

Maslach modelinden farklı olarak, Pines ve Aronson (1988) tükenmişliği uzun süreli olarak duygusal açıdan talepkâr durumlara maruz kalmanın sonucu olarak ortaya çıkan fiziksel, duygusal ve zihinsel tükenme hali olarak tanımlamıştır. Bu modelde Pines ve Aronson, tükenmişliği fiziksel tükenme (yorgunluk, halsizlik, uyku sorunları gibi bedensel şikâyetler), zihinsel tükenme (umutsuzluk, zihinsel yorgunluk, bırakma isteği gibi bilişsel şikâyetler), duygusal tükenme (sosyal çevrenin taleplerine yanıt verememe hissi, çökkünlük, “çökme” hissi) olarak üç boyutta açıklamıştır (Akt., Lourel ve ark., 2007).

Tükenmişlik kavramına açıklama getiren diğer bir model ise JDR (Job Demands-Resources – İş Talepleri-Kaynaklar) modelidir. Tükenmişliğin gelişiminin iki süreçle gerçekleştiğini öne sürer. İlk süreçte, işin zorlayıcı yönleri (örneğin aşırı iş talepleri) sürekli aşırı yüklenmeye ve nihayetinde tükenmeye yol açar. İkinci süreçte ise kaynak eksikliği, iş taleplerinin karşılanmasını zorlaştırır ve bu durum geri çekilme davranışına neden olur. Bu geri çekilmenin uzun vadeli sonucu işe yabancılaşmadır. Burada tükenmişliği vurgulanan iki yönü karşımıza çıkmaktadır: talepler ve kaynaklar. İş talepleri, sürekli fiziksel veya zihinsel çaba gerektiren ve bu nedenle fizyolojik ve psikolojik maliyetlerle (örneğin tükenme) ilişkilendirilen işin fiziksel, sosyal veya örgütsel yönleridir. İş kaynakları, iş hedeflerine ulaşmada işlevsel olan, iş taleplerinin maliyetini azaltan veya kişisel gelişimi teşvik eden fiziksel, psikolojik, sosyal veya örgütsel unsurlardır (Demerouti, Bakker, Nachreiner, ve Schaufeli 2001).

Öğretmenlerde tükenmişlik üzerine etkisini inceleyeceğimiz Psikolojik Sermaye kavramı Luthans ve Youssef tarafından, “işyerinde performans iyileştirmesi için ölçülebilen, geliştirilebilen ve yönetilebilen pozitif yönelimli insan kaynakları güçlerini ve psikolojik kapasiteleri vardır ve bu kapasiteler öz-yeterlik/güven, umut, iyimserlik ve dayanıklılığı içerir. Bu kapasiteler topluca pozitif psikolojik sermaye olarak adlandırılır” şeklinde ifade edilmiştir (Luthans ve Youssef, 2004).

Psikolojik sermayeyi oluşturan birinci bileşen olan özyeterlik ilk olarak Albert Bandura tarafından tanımlanmıştır. Bandura öz yeterlik kavramını bir kişinin belirli sonuçları elde etmek için gerekli davranışı başarıyla gerçekleştirebileceğine dair inancı olarak tanımlamıştır (Bandura, 1977). Bireyin belirli bir bağlamda belirli bir görevi başarıyla yerine getirmek için gerekli olan motivasyonu, bilişsel kaynakları ve eylem yollarını harekete geçirme konusundaki özgüveni olarak tanımlanır (Luthans, Youssef ve Avolio, 2015). Karşılaşılan görev ve zorluklara karşı “başlama cesaretini” ve “devam etme direncini” aynı anda besleyen bir eylem inancını ifade eder. Psikolojik sermayenin ikinci bileşeni umut, istenilen hedeflere ulaşmak için yollar oluşturma yetisini algılamak ve bu yolları kullanmak için kendini güdüleme kapasitesi olarak tanımlanır (Snyder, 2002). Martin Seligman, Gerçek Mutluluk adlı kitabında Umut, umutsuzluğun yokluğu değildir. Umut, umutsuzluğun aşılabileceğine inanma kapasitesidir (Seligman, 2002), tanımlamasını yaparak umudun içsel motivasyon yönünü vurgulamıştır.

Psikolojik Sermayenin diğer bileşeni umut kavramına yakın bir anlam taşıyan iyimserlik kavramıdır. İyimserlik, bireylerin gelecekleri hakkında genel olarak olumlu beklentilere sahip olma derecesini yansıtan bir bireysel farklılık değişkenidir (Carver, Scheier ve Segerstrom, 2010). İyimserlik, bireyin yaşam olaylarına olumlu sonuç beklentisiyle yaklaşma eğilimidir; ancak bu, kör bir umut değil, zorluklar karşısında bile çözüm ve anlam arayışını sürdürebilme becerisidir. Birbiri ile karıştırılması muhtemel iki kavram olarak umut ve iyimserlik farklılık arz etmektedir. İyimserlik, geleceğin olumlu olacağına dair genel bir inançken; umut, o olumlu geleceğe ulaşmak için yollar arama ve çaba gösterme kararlılığıdır.

Master ve Reed’in (2002) tanımına göre, Pozitif psikolojik sermaye bileşenlerinin diğerlerinden farklı olarak daha tepkisel bir nitelik taşıyan “dayanıklılık” kavramı bireyin belirli risk ve olumsuz şartlar altındaki durumlara gösterdiği olumlu uyumu olarak tanımlanabilir (Akt. Keleş, 2011). Dayanıklılık, bireyin zorluklar, stres ve başarısızlıklar karşısında yeniden denge kurma ve güçlenerek devam etme; bireyin stres, travma veya değişim gibi olumsuz yaşam olayları karşısında psikolojik işlevselliğini sürdürme ve uyum sağlama kapasitesidir. Bu kavram, yalnızca toparlanma sürecini değil, aynı zamanda zorluklar aracılığıyla gelişme ve güçlenme potansiyelini de içerir.

Bu bilgiler ışığında psikolojik sermaye, bireyin olumlu psikolojik kaynaklarının bir bileşkesini ifade eder ve bu kaynaklar, bireyin iş yaşamındaki stresörlerle baş etme biçimini güçlendirerek tükenmişlik düzeyini azaltabilir. Örneğin, öz-yeterliği yüksek birey görevlerini başarma konusunda kendine güvenirken, umudu yüksek olan kişi hedeflerine ulaşmak için alternatif yollar geliştirebilir. İyimserlik, olumsuz deneyimleri geçici ve değiştirilebilir olarak algılamayı sağlarken, dayanıklılık bireyin zorlayıcı koşullar karşısında psikolojik dengesini korumasına yardımcı olur. Bu bileşenlerin etkileşimi, tükenmişliğin temel boyutları olan

duygusal tükenme, duyarsızlaşma ve kişisel başarıda azalma süreçlerine karşı bir koruma kalkanı oluşturur. Dolayısıyla psikolojik sermaye, çalışanların hem performansını hem de psikolojik iyi oluşunu sürdürülebilir biçimde destekleyen önemli bir içsel kaynak olarak değerlendirilebilir.

Bu araştırmanın temel amacı, eğitim sistemlerinin sürdürülebilirliği açısından kritik bir tehdit oluşturan öğretmen tükenmişliği ile bireyin pozitif psikolojik gelişim durumunu ifade eden psikolojik sermaye arasındaki ilişkisel örüntüyü ve etki düzeyini, uluslararası literatürdeki ampirik bulgular ışığında sistematik olarak incelemektir. Son yıllarda öğretmenlik mesleğinde artan iş yükü, rol çatışmaları ve duygusal emek taleplerine bağlı olarak yükseliş gösteren tükenmişlik sendromu, eğitimcilerin psikolojik iyi oluşunu tehdit etmektedir. Bu bağlamda, İş Talepleri ve Kaynakları (JD-R) modeli perspektifinden bakıldığında, tükenmişliğin önlenmesinde dışsal kaynaklar kadar bireyin sahip olduğu içsel kaynakların da önemi giderek daha fazla vurgulanmaktadır.

Dolayısıyla bu çalışma, öz-yeterlik, umut, iyimserlik ve dayanıklılık bileşenlerinden oluşan psikolojik sermayenin, öğretmenlerin tükenmişlik düzeyleri (duygusal tükenme, duyarsızlaşma ve kişisel başarıda azalma) üzerindeki doğrudan ve dolaylı etkilerini sentezlemeyi hedeflemektedir.

Bu genel amaç doğrultusunda araştırma şu alt hedeflere odaklanmaktadır: farklı kültürel bağlamlarda ve öğretim kademelerinde (okul öncesi, K-12, yükseköğretim, özel eğitim) yürütülen nicel araştırmaları bir araya getirerek, psikolojik sermayenin tükenmişlik üzerindeki koruyucu etkisinin tutarlılığını ve gücünü değerlendirmek; psikolojik sermaye ile tükenmişlik arasındaki ilişkide rol oynayan aracı mekanizmaları (örneğin; iş doyumu, mesleki kimlik, öz-düzenleme) ve düzenleyici değişkenleri (örneğin; duygusal emek stratejileri, fiziksel aktivite) belirlemek; elde edilen bulgular ışığında, öğretmenlerin psikolojik dayanıklılıklarını artırmaya yönelik geliştirilebilecek müdahale programları ve eğitim politikaları için kanıta dayalı bir zemin oluşturmaktır. Söz konusu hedeflere ulaşmak için oluşturulan araştırma soruları şu şekildedir:

1. Çalışmalar nerede ve hangi örneklem üzerinde yürütülmüştür?
2. Çalışmalarda kullanılan yöntem ve ölçme araçları nelerdir?
3. Öğretmenlerde psikolojik sermayenin tükenmişlik üzerinde doğrudan bir etkisi var mıdır?

Bu sistematik derleme, literatürdeki dağınık bulguları bütüncül bir yaklaşımla analiz ederek, psikolojik sermayenin öğretmen tükenmişliği ile mücadelede stratejik bir içsel kaynak olarak nasıl işlevselleştirilebileceğine dair alan yazına katkı sağlamayı amaçlamaktadır.

2. YÖNTEM

2.1. Araştırma Modeli

Bu araştırmada kullanılan model sistematik derlemedir. Sistematik derlemeler, araştırmacıların belirli bir konuya dair tüm bilimsel çalışmaları toplaması ve değerlendirmesi için temel bir yöntemdir. Kanıta dayalı araştırmaların temel taşı olarak belirli araştırma sorularını yanıtlamak için mevcut çalışmaların kapsamlı özetlerini sunar. Bu bakış açısıyla

sistematik derlemeler, paydaşların mevcut kanıtları daha etkili bir şekilde tüketmesini, değerlendirmesini ve uygulamasını sağlayan yapılandırılmış araçlar olarak hizmet eder (De Cassai, Dost, Tulgar ve Boscolo, 2025). Bu yaklaşım sayesinde mevcut literatürdeki bulgular yalnızca özetlenmekle kalmaz, aynı zamanda benzerlikleri, farklılıkları ve araştırma boşlukları da ortaya konur. Çalışmamızda sistematik derleme modeli tercih edilmiştir çünkü bu yöntem, konuyla ilgili bilgi birikimini bütüncül ve kanıta dayalı biçimde değerlendirmeye, böylece ileride yapılacak araştırmalara yön verecek güçlü bir teorik zemin oluşturmaya olanak tanımaktadır.

2.2. Evren, Örneklem, Veri analizi

Araştırmada öğretmenlerde psikolojik sermayenin tükenmişlik üzerine etkisini inceleyen çalışmalarını bulmak hedeflenmiştir. Bu kapsamda veri tabanı olarak Web of Science kullanılmıştır. Veri tabanı üzerinden “öğretmen”, “tükenmişlik” ve “psikolojik sermaye” anahtar sözcüklerinin İngilizce karşılıkları (teacher, burnout ve psychological capital), yalnızca başlıkta aratılacak şekilde filtreleme yapılmış, bu arama sonucunda 28 çalışmaya ulaşılmıştır. Ulaşılan 28 çalışma incelenmiş ve psikolojik sermayenin tükenmişlik üzerine etkisi ile ilgili bir bulgu barındırmayan 5 çalışma araştırmadan çıkarılmıştır. Geriye kalan ve araştırmanın amacına uygun kriterleri barındıran 23 çalışmaya ait bulgular aşağıda sunulmuştur.

3. BULGULAR

Tablo – 1 İncelenen çalışmaların künye, yöntem ve ölçme araçları, sonuçlarına ait bilgiler

Yazar, Yıl ve Ülke	Yöntem	Kullanılan Ölçme Araçları	Psikolojik Sermayenin Tükenmişlik Üzerine Etkisi	Sonuç ve Özet
1 Zhao vd., 2022, Çin	Nicel Araştırma, Kesitsel Tarama, Yapısal Eşitlik Modellemesi. Örneklem: 2929 öğretmen	Kariyer Çağrısı Ölçeği, UWES-9 (İşe Bağlanma), Psikolojik Sermaye Anketi (Zhang, 2010), Profesyonel Yaşam Kalitesi Ölçeği (Tükenmişlik Alt Boyutu)-	Psikolojik sermayenin tükenmişlik üzerinde negatif yönde güçlü ve anlamlı bir doğrudan etkisi ($\beta = -0.56$, $p < 0.001$) tespit edilmiştir.	Çalışma, psikolojik sermayenin, kariyer çağrısı ile tükenmişlik arasındaki ilişkide aracı bir mekanizma olduğunu göstermektedir. Yüksek psikolojik sermaye, öğretmenlerin tükenmişlik düzeylerini azaltan koruyucu bir faktördür.
2 Kaya & Altınkurt, 2018, Türkiye	Nicel Araştırma, İlişkisel Tarama, Yapısal Eşitlik Modeli. Örneklem: 374 öğretmen.	Psikolojik Sermaye Ölçeği (Çetin & Basım), Psikolojik Güçlendirme Ölçeği, Yapısal Güçlendirme Ölçeği, Maslach Tükenmişlik Ölçeği.	Psikolojik sermaye; duygusal tükenme ($r = -.34$), duyarsızlaşma ($r = -.35$) ve kişisel başarısızlık ($r = -.59$) ile negatif ilişkili bulunmuştur. Modelde dolaylı etkilerle birlikte toplam etki negatiftir.	Psikolojik sermaye, tükenmişliğin tüm alt boyutlarını azaltmada etkilidir; ancak bu etkide psikolojik ve yapısal güçlendirme aracı rol oynamaktadır. Öğretmenlerin psikolojik sermayelerinin artırılması tükenmişliği önleyici bir unsurdur.
3 Sun vd., 2022, Çin	Nicel Araştırma, Kesitsel Tarama, Yapsail Eşitlik Modeli. Örneklem: 2220 kadın öğretmen.	Öğretmen Mesleki Kimlik Ölçeği, UWES-9, Psikolojik Sermaye Ölçeği (Luthans vd.), Profesyonel Yaşam Kalitesi Ölçeği (Tükenmişlik).	Psikolojik sermayenin tükenmişlik üzerinde negatif yönde anlamlı bir doğrudan etkisi ($\beta = -0.51$, $p < 0.001$) bulunmuştur.	Psikolojik sermaye, mesleki kimlik ile tükenmişlik arasındaki ilişkide hem eş zamanlı hem de sıralı bir aracı değişkendir. Mesleki kimlik, işe bağlılığı ve psikolojik sermayeyi artırarak tükenmişliği azaltmaktadır.
4 Liu & Du, 2024, Çin	Nicel Araştırma, Kesitsel Tarama, Yapısal Eşitlik Modeli. Örneklem: 387 İngilizce (EFL) Öğretmeni.	Psikolojik Sermaye Ölçeği (Luthans vd., 2015), Maslach Tükenmişlik Envanteri (MBI-ES), Beş Boyutlu Bilinçli Farkındalık Ölçeği (FFMQ-15)-	Psikolojik sermayenin tükenmişlik üzerinde doğrudan negatif yönde anlamlı bir etkisi ($\beta = -0.341$, $p < 0.001$) saptanmıştır.	Psikolojik sermaye, öğretmenlerin tükenmişlik düzeylerini doğrudan azaltırken, aynı zamanda bilinçli farkındalık aracılığıyla dolaylı olarak da azaltmaktadır. Yüksek psikolojik kaynaklar, farkındalığı artırarak tükenmişliği önlemektedir.

INTERNATIONAL TOPKAPI CONGRESS VI

5	Chen, Wang & Gao, 2024, Çin	Nicel Araştırma, Yapısal Eşitlik Modeli. Örneklem: 550 EFL Öğretmeni.	Maslach Tükenmişlik Envanteri, Öğretmen Psikolojik Sermaye Ölçeği (Luthans vd.), Beş Faktör Kişilik Envanteri.	Psikolojik sermayenin tükenmişlik üzerinde negatif yönde güçlü bir etkisi ($\beta = -0.624$, $p = 0.001$) bulunmuştur.	Teknoloji destekli öğretim ortamlarında, yüksek psikolojik sermayeye sahip öğretmenlerin tükenmişlik düzeyleri anlamlı derecede düşüktür. Psikolojik sermaye, kişilik özellikleri ile birlikte tükenmişliğe karşı tampon görevi görmektedir.
6	Zhang, Zhang & Hua, 2019, Çin	Nicel Araştırma, Yapısal Eşitlik Modeli, Çoklu Grup Analizi. Örneklem: 386 öğretmen.	Mesleki Stres Ölçeği, Psikolojik Sermaye Ölçeği (26 madde), MBI-ES, Başa Çıkma Tarzları Ölçeği.	Psikolojik sermayenin tükenmişlik üzerinde doğrudan negatif bir etkisi ($\beta = -0.53$, $p < 0.01$) tespit edilmiştir, [Şekil 2].	Psikolojik sermaye, pozitif başa çıkma stratejilerini teşvik ederek tükenmişliği azaltan koruyucu bir faktördür. Bu etki, özellikle 10 yıldan fazla deneyime sahip öğretmenlerde daha belirgindir.
7	Fathi vd., 2023, İran	Nicel Araştırma, Yapısal Eşitlik Modeli. Örneklem: 434 EFL Öğretmeni.	Öğretmen Öz-Düzenleme Ölçeği, Mesleki Kimlik Ölçeği, MBI-ES, Psikolojik Sermaye Anketi (PCQ-24).	Final kısmi aracılık modelinde psikolojik sermayeden tükenmişliğe giden doğrudan yol anlamsız ($\beta = -0.08$, $p > 0.05$) çıkmıştır; ancak korelasyon negatiftir ($r = -0.29$)-.	Doğrudan etki istatistiksel olarak anlamlı bulunmasa da, psikolojik sermaye "öz-düzenleme" aracılığıyla tükenmişliği tam olarak yordamakta ve azaltmaktadır.
8	Hazan-Liran & Karni-Vizer, 2024, İsrail	Nicel Araştırma, Süreç Analizi (PROCESS). Örneklem: 123 öğretmen.	İş Doyumu Ölçeği (Brayfield & Rothe), PCQ-12, Öğretmen Tükenmişlik Ölçeği (Friedman)	Psikolojik sermayenin tükenmişlik üzerinde negatif yönde anlamlı bir etkisi ($B = -0.46$, $p < 0.001$) bulunmuştur.	Psikolojik sermaye, iş doyumu ile tükenmişlik arasındaki ilişkide aracı bir rol üstlenmektedir. Hem özel eğitim hem de normal eğitim öğretmenlerinde yüksek psikolojik sermaye, düşük tükenmişlikle ilişkilidir.
9	Ferradás vd., 2019, İspanya	Nicel Araştırma, Gizil Profil Analizi (LPA), MANCOVA. Örneklem: 1379 öğretmen.	CapPsi Psikolojik Sermaye Ölçeği, MBI-ES.	Düşük psikolojik sermaye profiline sahip öğretmenler en yüksek tükenmişlik puanlarına sahipken, yüksek psikolojik sermaye profili en düşük tükenmişlik puanlarını göstermiştir.	Psikolojik sermayenin dört bileşenine (öz-yeterlik, umut, iyimserlik, dayanıklılık) yüksek düzeyde sahip olan öğretmenler, tükenmişliğe karşı en korunaklı gruptur. Farklı profil kombinasyonları, tükenmişliğin farklı boyutlarını yordamaktadır.

INTERNATIONAL TOPKAPI CONGRESS VI

10	Freire vd., 2020, İspanya	Nicel Araştırma, Arabuluculuk Analizi (PROCESS). Örneklem: 1379 öğretmen.	CapPsi Psikolojik Sermaye Ölçeği, Gelişim (Flourishing) Ölçeği, MBI-ES-.	Psikolojik sermaye; duygusal tükenme ($b = -0.767$) ve duyarsızlaşma ($b = -0.274$) üzerinde negatif, kişisel başarı ($b = 1.005$) üzerinde pozitif doğrudan etkiye sahiptir.	Psikolojik sermaye, öğretmenin "gelişim" (flourishing) düzeyini artırarak tükenmişlik belirtilerini azaltmaktadır. Gelişim değişkeni, bu ilişkide kısmi aracı rol oynamaktadır.
11	Liu, 2025, Çin	Karma Yöntem (Nicel Araştırma, Yapısal Eşitlik Modeli + Nitel Kritik Olay Tekniği). Örneklem: 620 öğretmen (nicel), 25 öğretmen (nitel).	Öğretmen Mesleki Kimlik Ölçeği, PCQ (Psikolojik Sermaye), Öz-Düzenleme Ölçeği, MBI-ES-.	Psikolojik sermayenin tükenmişlik üzerinde negatif yönde anlamlı bir doğrudan etkisi ($\beta = -0.25$, $p < 0.001$) saptanmıştır.	Psikolojik sermaye, tükenmişliğe karşı önemli bir koruyucu faktördür ve öz-düzenleme becerilerini destekleyerek tükenmişliği azaltır. Ayrıca mesleki kimlik ile tükenmişlik arasında bir zincirleme aracılık etkisi yaratır.
12	Jiang & Yuan, 2025, Çin	Nicel Araştırma, Düzenlenmiş Aracılık Modeli. Örneklem: 496 K-12 öğretmeni.	Öğretmen İş Doyumu Ölçeği, MBI-ES, Psikolojik Sermaye Anketi (Zhang Wen), Fiziksel Aktivite Ölçeği-.	Psikolojik sermayenin tükenmişlik üzerinde negatif yönde anlamlı bir yordayıcı etkisi ($\beta = -0.32$, $p < 0.001$) bulunmuştur.	Psikolojik sermaye, iş doyumu ile tükenmişlik arasında kısmi aracı rol oynamaktadır. Fiziksel egzersiz, psikolojik sermayenin tükenmişlik üzerindeki azaltıcı etkisini güçlendiren düzenleyici bir değişkendir.
13	Zhang & Li, 2025, Çin	Nicel Araştırma, İki aşamalı anket, Hiyerarşik regresyon. Örneklem: 160 üniversite hocası.	Psikolojik Sermaye Ölçeği (Luthans), İşte Gelişim (Thriving) Ölçeği, İş Tükenmişliği Ölçeği (Demerouti), İyi Oluş Ölçeği-.	Psikolojik sermayenin iş tükenmişliği üzerinde anlamlı negatif bir etkisi ($B = -0.35$, $p < 0.001$) tespit edilmiştir.	Psikolojik sermaye, iş tükenmişliğini azaltarak üniversite hocalarının iyi oluşunu artırmaktadır. Ancak, algılanan örgütsel politika, psikolojik sermayenin tükenmişlik üzerindeki bu koruyucu etkisini zayıflatmaktadır.
14	Xue vd., 2023, Çin	Psikometrik Ağ Analizi (Psychometric Network Analysis). Örneklem: 1729 tükenmişlik yaşayan öğretmen,.	Profesyonel Yaşam Kalitesi Ölçeği (Tükenmişlik alt ölçeği), Psikolojik Sermaye Ölçeği-.	Ağ analizinde, psikolojik sermaye belirtileri (özellikle iyimserlik ve umut boyutları) ile tükenmişlik belirtileri arasında güçlü negatif bağlantılar bulunmuştur.	Psikolojik sermaye semptomları (örneğin geleceğe dair umutlu olma), tükenmişlik ağındaki semptomları (örneğin "kendini önemseyen biri olma" hissini kaybı) negatif yönde etkileyerek koruyucu bir işlev görmektedir.

INTERNATIONAL TOPKAPI CONGRESS VI

15	Cheung vd., 2011, Çin	Nicel Araştırma, Düzenlenmiş Regresyon. Örneklem: 264 öğretmen.	Duygusal Emek Ölçeği, Psikolojik Sermaye Ölçeği (Luthans vd.), İş Doyumu Endeksi, MBI-.	Psikolojik sermaye; duygusal tükenme ($r = -.50$), duyarsızlaşma ($r = -.56$) ve kişisel başarı eksikliği ($r = -.50$) ile negatif ilişkili bulunmuştur.	Psikolojik sermaye doğrudan tükenmişliği azaltmakla kalmaz, aynı zamanda yüzeysel rol yapma (surface acting) ile duyarsızlaşma arasındaki ilişkiyi düzenleyerek olumsuz etkileri tamponlar.
16	Yin, 2023, Çin	Nicel Araştırma, Regresyon Analizi. Örneklem: 434 üniversite hocası.	Duygusal Emek Stratejisi Ölçeği, PCQ, MBI-ES-.	Psikolojik sermaye ile iş tükenmişliği arasında anlamlı ve negatif bir korelasyon ($r = -.58$, $p < .01$) bulunmuştur.	Yüksek psikolojik sermaye, duygusal emeğin tükenmişlik üzerindeki olumsuz etkilerini (özellikle yüzeysel rol yapma durumunda) azaltan bir düzenleyici değişkendir.
17	Walter & Hazan-Liran, 2025, İsrail	Nicel Araştırma, Aracılık Analizi (PROCESS). Örneklem: 100 anaokulu öğretmeni.	Özerklik Anketi, Öğretmen Tükenmişlik Ölçeği (Friedman), PCQ-12-.	Psikolojik sermayenin tükenmişlik üzerinde negatif yönde anlamlı bir doğrudan etkisi ($B = -0.340$, $p < 0.01$) saptanmıştır.	Psikolojik sermaye tükenmişliği doğrudan azaltmakla kalmaz, aynı zamanda öğretmen özerkliğini artırarak dolaylı yoldan da tükenmişliği düşürür.
18	Wang vd., 2025, Çin	Nicel Araştırma, Hiyerarşik Regresyon. Örneklem: 349 özel eğitim öğretmeni.	Duygusal Emek Stratejisi Ölçeği, MBI-ES, Psikolojik Sermaye Anketi (Çin özel eğitim bağlamı)-.	Psikolojik sermaye, iş tükenmişliği ile negatif ilişkili olup, regresyon modelinde tükenmişlik üzerinde negatif bir etkisi ($\beta = -0.404$) bulunmuştur.	Psikolojik sermaye, özel eğitim öğretmenlerinde tükenmişliği azaltır ve "derinlemesine rol yapma" stratejisinin tükenmişlik üzerindeki azaltıcı etkisini güçlendiren bir düzenleyicidir.
19	Mesurado & Laudadio, 2019, Arjantin	Nicel Araştırma, Blok Regresyon. Örneklem: 250 üniversite hocası.	PCQ (kısa versiyon), UWES (kısa versiyon), Oldenburg Tükenmişlik Envanteri (OLBI)-.	Psikolojik sermayenin Umut ($\beta = -.20$) ve İyimserlik ($\beta = -.24$) boyutları, tükenmişlik ile negatif yönde anlamlı ilişkilidir.	Çalışma, psikolojik sermayenin, özellikle umut ve iyimserlik boyutlarının, öğretim deneyiminden bağımsız olarak tükenmişlik sendromunun ortaya çıkmasını engellediğini göstermektedir.
20	Heng vd., 2020, Çin	Nicel Araştırma, Hiyerarşik Regresyon. Örneklem: 488 üniversite hocası.	Öğretim-Araştırma Çatışması Ölçeği, MBI-ES, Algılanan Yönetici Desteği (SPOS), PCQ-.	Psikolojik sermaye; duygusal tükenme ($\beta = -0.31$) ve duyarsızlaşma ($\beta = -0.35$) üzerinde negatif, kişisel başarı üzerinde pozitif ($\beta = 0.36$) etkiye sahiptir-.	Psikolojik sermaye, öğretim-araştırma çatışmasının tükenmişlik üzerindeki olumsuz etkilerini tamponlayan kritik bir içsel kaynaktır.

INTERNATIONAL TOPKAPI CONGRESS VI

21	Pu vd., 2017, Çin	Nicel Araştırma, Hiyerarşik Regresyon. Örneklem: 357 üniversite hocası.	İş-Aile Çatışması Ölçeği, PCQ-24, MBI-GS-.	Psikolojik sermayenin iş tükenmişliği üzerinde güçlü bir negatif etkisi ($\beta = -0.44$, $p < 0.01$) bulunmuştur.	Psikolojik sermaye, iş-aile çatışması ile tükenmişlik arasındaki ilişkide bir aracı değil, düzenleyici olarak işlev görmekte ve çatışmanın yarattığı tükenmişliği azaltmaktadır.
22	Li & Liu, 2025, Çin	Nicel Araştırma, Kesitsel, Aracılık (Bootstrap). Örneklem: 308 üniversite hocası.	İş-Aile Destek Ölçeği (WFSS), Mesleki Stres Ölçeği (OSS), Psikolojik Sermaye Ölçeği (PsyCapS), MBI-ES-.	Psikolojik sermayenin tükenmişlik üzerinde negatif yönde anlamlı bir etkisi ($b = -0.483$, $p < 0.001$) tespit edilmiştir.	Psikolojik sermaye, iş-aile desteği ve mesleki stresin tükenmişlik üzerindeki etkisinde istatistiksel olarak anlamlı bir aracı değişkendir. Mesleki stres, psikolojik sermayeyi azaltarak tükenmişliği artırmaktadır.
23	Peng vd., 2019, Çin	Nicel Araştırma, Kesitsel, Yapısal Eşitlik Modeli. Örneklem: 355 okul öncesi öğretmeni.	Duygusal Emek Stratejisi Ölçeği, PCQ-24, MBI-ES-.	Yapısal modelde psikolojik sermayenin iş tükenmişliği üzerindeki yol katsayısı negatif ve anlamlı ($\beta = -0.59$) bulunmuştur.	Psikolojik sermaye, duygusal emek stratejileri ile tükenmişlik arasında hem aracı hem de düzenleyici rol oynamakta; özellikle "yüzeysel rol yapma"nın olumsuz etkilerini hafifletmektedir.

Psikolojik sermayenin tükenmişlik üzerindeki etkisini inceleyen araştırmalar bütüncül bir perspektifle ele alındığında, bu içsel kaynağın doğrudan ve dolaylı mekanizmalarla öğretmenleri koruduğu görülmektedir. İlk olarak, Zhao vd. (2022) tarafından Çin’de 2929 öğretmen üzerinde yürütülen geniş kapsamlı çalışmada, psikolojik sermayenin tükenmişlik üzerinde güçlü bir negatif etkisi olduğu ve bununla birlikte analizler, kariyer çağrısının tükenmişliği doğrudan azalttığını, ancak bu ilişkinin önemli bir kısmının öğretmenlerin psikolojik sermayesi üzerinden gerçekleştiğini kanıtlamaktadır. Yani, mesleğini sadece ekonomik bir geçim kaynağı veya kariyer basamağı olarak değil; benliğinden gelen ancak benliğin ötesine geçen aşkın bir davet olarak algılayan öğretmenlerin psikolojik sermayeleri artmakta ve bu artış tükenmişliği önlemektedir. Benzer bir kültürel bağlamda Sun vd. (2022) tarafından Çin’de kadın öğretmenler üzerinde yapılan araştırmada, psikolojik sermayenin mesleki kimlik aracılığıyla tükenmişliği azalttığı bulunmuştur; bu da güçlü bir mesleki kimlik algısının psikolojik kaynaklarla desteklendiğinde koruyucu bir kalkan oluşturduğunu kanıtlar. Türkiye örneğinde ise Kaya ve Altınkurt (2018) tarafından yürütülen çalışmada, psikolojik sermayenin tükenmişliğin tüm alt boyutlarıyla negatif ilişkili olduğu ancak bu etkide psikolojik ve yapısal güçlendirmenin aracı rol oynadığı belirlenmiştir; bu bulgu, öğretmenlerin içsel ve dışsal kaynaklarının örgütsel güçlendirme ile desteklendiğinde tükenmişliğe karşı daha dirençli olduklarını gösterir. İsrail’de Walter ve Hazan-Liran (2025) tarafından anaokulu öğretmenleri ile gerçekleştirilen çalışmada analiz sonuçları, psikolojik sermayenin tükenmişliği azaltma mekanizmasında mesleki özerkliğin üstlendiği aracı role vurgu yapmaktadır. Yüksek psikolojik sermaye, öğretmenin algıladığı özerklik düzeyini anlamlı şekilde artırmakta, artan özerklik düzeyi ise tükenmişliği güçlü bir şekilde azaltmaktadır.

Psikolojik sermayenin etki mekanizmalarında öz-düzenleme ve farkındalık süreçleri de öne çıkmaktadır. Fathi vd. (2023) tarafından İran’da EFL öğretmenleri üzerinde yapılan çalışmada, doğrudan etkinin anlamsız olduğu durumlarda dahi psikolojik sermayenin öz-düzenleme aracılığıyla tükenmişliği yordadığı görülmüştür; bu sonuç, psikolojik sermayenin etkisinin büyük ölçüde bireyin kendini yönetme becerisini artırması yoluyla gerçekleştiğini gösterir. Bunu destekler nitelikte, Liu (2025) tarafından Çin’de karma yöntemle yürütülen araştırmada, psikolojik sermayenin tükenmişlik üzerindeki doğrudan negatif ve anlamlı etkisinin yanı sıra mesleki kimliğin psikolojik sermaye ve öz düzenleme zincirleme bir aracılık etkisi yaratarak tükenmişliği azalttığı saptanmıştır. Ayrıca Liu ve Du (2024) tarafından Çin’deki EFL öğretmenleri üzerinde yapılan çalışmada, psikolojik sermayenin hem doğrudan hem de bilinçli farkındalık düzeyini artırarak tükenmişliği önlediği tespit edilmiştir; bu da psikolojik kaynakların bireyin "anda kalma" ve stresle baş etme kapasitesini güçlendirdiğini işaret eder.

Öğretmenlerin iyi oluş ve gelişim düzeyleri açısından bakıldığında, Freire vd. (2020) tarafından İspanya’da gerçekleştirilen çalışmada, psikolojik sermayenin duygusal tükenme üzerinde doğrudan negatif bir etkisi olduğu ve buna ek olarak, psikolojik sermayenin "gelişim" düzeyini artırarak duygusal tükenmeyi azalttığı tespit edilmiştir. Bu dolaylı etki istatistiksel olarak anlamlıdır ve "gelişim" değişkeni bu ilişkide kısmi aracı rol oynamaktadır. Benzer şekilde Hazan-Liran ve Karni-Vizer (2024) tarafından İsrail’de özel ve normal eğitim öğretmenleri üzerinde yürütülen çalışmada, psikolojik sermayenin iş doyumunu ile tükenmişlik arasında kritik bir aracı olduğu belirlenmiştir. İş doyumunun tükenmişliği doğrudan azalttığını,

ancak aynı zamanda psikolojik sermayeyi artırarak dolaylı yoldan da tükenmişliği düşürdüğünü göstermektedir. Bu durum, işinden memnun olan öğretmenlerin psikolojik sermayelerinin güçlendiğini ve bu güçlenmenin onları tükenmişliğe karşı koruduğunu göstermektedir.

Çin’de üniversite hocaları üzerinde Zhang ve Li (2025) tarafından yapılan araştırmada ise psikolojik sermayenin akademisyenlerin genel iyi oluş hallerini artırma mekanizması incelenmiştir. Çalışmanın sonuçları tükenmişliğin bu ilişkide anlamlı bir aracı rol üstlendiğini kanıtlamaktadır. Bu sonuç, psikolojik sermayenin iyi oluş üzerindeki etkisinin önemli bir kısmının, tükenmişlik semptomlarını (duygusal tükenme ve işten uzaklaşma) minimize etmesi yoluyla gerçekleştiğini göstermektedir. Yani yüksek psikolojik sermaye, tükenmişlik hissini baskılamakta; azalan tükenmişlik ise akademisyenin "iş dışı" yaşamına da sirayet eden genel bir mutluluk ve iyi oluş haline dönüşmektedir. Çalışmanın bir diğer sonucu, psikolojik sermayenin tükenmişliği önleme gücünün "mutlak" olmadığını; çevresel faktörlere, özellikle de örgütsel politika algısına bağlı olarak değiştiğini ortaya koymasındır. Analizler, örgütsel politika algısının psikolojik sermaye ile tükenmişlik arasındaki ilişkide aracı bir rol oynadığını göstermiştir. Akademisyenler ortamda politik oyunların, adam kayırmanın veya güç mücadelelerinin az olduğunu düşündüklerinde, psikolojik sermaye tükenmişliği güçlü ve anlamlı bir şekilde azaltmaktadır. Ortamda yüksek düzeyde örgütsel politika algılandığında, psikolojik sermayenin tükenmişlik üzerindeki azaltıcı etkisi istatistiksel olarak anlamsızlaşmaktadır.

Bireysel farklılıklar ve kişilik profilleri incelendiğinde, Ferradás vd. (2019) tarafından İspanya’da yapılan çalışmada, yüksek psikolojik sermaye profiline sahip öğretmenlerin en düşük tükenmişlik puanlarına sahip olduğu görülmüştür; bu sonuç, psikolojik sermaye bileşenlerinin (umut, iyimserlik, dayanıklılık, öz-yeterlik) bir arada bulunmasının kümülatif bir koruma sağladığını gösterir. Chen, Wang ve Gao (2024) tarafından Çin’de teknoloji destekli öğretim yapan EFL öğretmenleri üzerinde yürütülen çalışmada, teknoloji destekli öğretim ortamlarında, yüksek psikolojik sermayeye sahip öğretmenlerin tükenmişlik düzeyleri anlamlı derecede düşük olduğu, psikolojik sermayenin kişilik özellikleriyle birlikte güçlü bir tampon görevi gördüğü saptanmıştır. Xue vd. (2023) tarafından Çin’de yapılan psikometrik ağ analizinde, umut ve iyimserlik belirtilerinin tükenmişlik ağı içinde "köprü" işlevi görerek semptomların yayılmasını engellediği bulunmuştur. Buna paralel olarak Arjantin’de Mesurado ve Laudadio (2019) tarafından üniversite akademisyenleri ile yapılan çalışmada, özellikle umut ve iyimserlik boyutlarının deneyimden bağımsız olarak tükenmişliği engellediği belirlenmiştir; bu durum, geleceğe dair pozitif beklentilerin tükenmişliğe karşı en dirençli psikolojik yapılar olduğunu kanıtlar. Ayrıca Zhang, Zhang ve Hua (2019) tarafından Çin’de yapılan çalışmada, psikolojik sermayenin pozitif başa çıkma stratejilerini teşvik ettiği ve bu etkinin deneyimli öğretmenlerde daha belirgin olduğu sonucuna ulaşılmıştır.

Özellikle duygusal emek ve yapısal stresörler bağlamında, psikolojik sermayenin düzenleyici rolü dikkat çekicidir. Cheung vd. (2011) tarafından Çin’de yürütülen çalışmada, psikolojik sermayenin "yüzeysel rol yapma" ile duyarsızlaşma arasındaki ilişkiyi düzenleyerek olumsuz etkilere yönelik önleyici rol oynadığı saptanmıştır; bu durum, yüksek psikolojik sermayenin duygusal uyumsuzluğun yarattığı maliyeti düşürdüğünü gösterir. Benzer şekilde Yin (2023) tarafından üniversite akademisyenleri üzerinde ve Peng vd. (2019) tarafından okul

öncesi öğretmenleri üzerinde yapılan çalışmalarda, psikolojik sermayenin duygusal emek stratejilerinin tükenmişlik üzerindeki etkisini hem aracı hem de düzenleyici olarak hafiflettiği bulunmuştur. Özel eğitim bağlamında Wang vd. (2025) tarafından Çin’de yapılan araştırmada ise psikolojik sermayenin "derinlemesine rol yapma" stratejisinin tükenmişlik üzerindeki azaltıcı etkisini güçlendirdiği belirlenmiştir.

Son olarak, iş-yaşam dengesi ve çatışma durumlarında, Heng vd. (2020) tarafından Çin’de üniversite akademisyenleri üzerinde yapılan çalışmada, psikolojik sermayenin öğretim-araştırma çatışmasının yarattığı tükenmişliği düzenlendiği görülmüştür. Benzer şekilde Pu vd. (2017) tarafından Çin’de yürütülen çalışmada, psikolojik sermayenin iş-aile çatışmasının tükenmişlik üzerindeki etkisini düzenleyici olarak azalttığı saptanmıştır. Li ve Liu (2025) tarafından yapılan çalışmada ise psikolojik sermayenin iş-aile desteği ve mesleki stres bağlamında aracı bir değişken olduğu ve mesleki stresin psikolojik sermayeyi azaltarak tükenmişliği artırdığı tespit edilmiştir. Fiziksel faktörlerin etkisine değinen Jiang ve Yuan (2025) tarafından Çin’de K-12 öğretmenleri üzerinde yapılan çalışmada ise fiziksel egzersizin, psikolojik sermayenin tükenmişlik üzerindeki azaltıcı etkisini güçlendiren bir düzenleyici olduğu sonucuna ulaşılmıştır; bu da davranışsal aktivitelerin psikolojik kaynakları desteklediğini gösterir.

4. TARTIŞMA VE SONUÇ

Bu sistematik derleme, farklı kültürel bağlamlarda ve eğitim kademelerinde yürütülen 23 ampirik çalışmanın ışığında, psikolojik sermayenin öğretmen tükenmişliği üzerindeki hafifletici rolünü kapsamlı bir şekilde ortaya koymaktadır. Elde edilen bulgular bütüncül olarak değerlendirildiğinde, psikolojik sermayenin sadece basit bir negatif korelasyonla açıklanamayacağı; aksine İş Talepleri-Kaynakları (JD-R) ve Kaynakların Korunması (COR) teorileri çerçevesinde işleyen çok katmanlı bir koruma mekanizması olduğu anlaşılmaktadır.

Analiz edilen çalışmaların (örn. Zhao vd., 2022; Chen vd., 2024) büyük çoğunluğu, psikolojik sermayenin tükenmişlik üzerinde güçlü ve doğrudan bir negatif etkiye sahip olduğunu göstermektedir. Bu bulgu, COR teorisinin temel varsayımı olan "kaynak kaybı tükenmişliğe yol açar, kaynak kazanımı ise stresi önler" ilkesiyle örtüşmektedir. Psikolojik sermaye bileşenleri (umut, iyimserlik, öz-yeterlik, dayanıklılık) birbirinden bağımsız işleyen özellikler değil; Ferradás vd. (2019) çalışmasında görüldüğü üzere, bir arada bulunduklarında kümülatif bir "kaynak kervanı" oluşturarak öğretmeni duygusal tükenmeye karşı güçlendirmektedir. Özellikle Xue ve arkadaşlarının (2023) analizi, psikolojik sermayenin sadece kenarda bekleyen pasif bir depo olmadığını göstermektedir. Aksine, umut ve iyimserlik duyguları, tükenmişliğin en kritik belirtisi olan 'duyarsızlaşmayı' doğrudan engelleyen aktif birer bariyer görevi görmekte ve tükenmişlik döngüsünü kırmaktadır. Yani, geleceğe dair umudunu koruyan öğretmen, öğrencisine karşı duyarsızlaşmamaktadır.

Bulgular, psikolojik sermayenin tükenmişliği yalnızca doğrudan değil, aynı zamanda çeşitli psikososyal ve bilişsel mekanizmaları harekete geçirerek dolaylı yollardan da azalttığını göstermektedir. Bu bağlamda öne çıkan en önemli aracı değişkenler "mesleki kimlik" ve "işe bağlanma"dır. Yüksek psikolojik sermaye, öğretmenlerin mesleki kimlik algısını

güçlendirmekte ve bu durum işe adanmışlığı artırarak tükenmişlik riskini düşürmektedir (Sun vd., 2022).

Bulgular, psikolojik sermayenin tükenmişliği önlemede sadece bir "depo" görevi görmediğini, aynı zamanda öğretmenin davranışsal stratejilerini de dönüştürdüğünü göstermektedir. Fathi vd. (2023) ve Liu (2025) tarafından ortaya konulan "tam aracılık" modelleri, psikolojik sermayenin bilişsel bir potansiyel (umutlu olmak), öz-düzenleme becerisinin ise bu potansiyelin eyleme dökülmüş hali (hedefe yönelik planlama yapma) olduğunu işaret etmektedir. Psikolojik sermayesi yüksek öğretmenler, stresörler karşısında reaktif kalmak yerine; bilinçli farkındalık (Liu & Du, 2024) ve derinlemesine rol yapma (Wang vd., 2025) gibi proaktif stratejiler geliştirerek tükenmişlikten korunmaktadır. Bu durum, psikolojik sermayenin öğretmene "stresi yönetme ehliyeti" kazandırdığı şeklinde yorumlanabilir.

Araştırmalar içindeki en kritik bulgulardan biri, psikolojik sermayenin koruyucu etkisinin "mutlak" olmadığının anlaşılmasıdır. Zhang ve Li (2025) çalışması, üniversite ortamında algılanan yüksek örgütsel politikanın (adaletsizlik, kayırmacılık), psikolojik sermayenin tükenmişlik üzerindeki olumlu etkisini nötrlediğini (anlamsızlaştırdığını) göstermiştir. Bu bulgu, bireysel kaynakların tek başına yeterli olmadığını; toksik bir kurumsal iklimin, en dayanıklı öğretmenin bile kaynaklarını tüketebileceğini göstermesi açısından hayati önem taşır. Benzer şekilde Wang vd. (2025), psikolojik sermayenin doğal rol yapma stratejisinde kritik bir eşik olduğunu; düşük psikolojik sermayeli öğretmenlerde doğal davranışların bile tükenmişliği önleyemediğini saptamıştır. Dolayısıyla psikolojik sermaye, çevresel ve stratejik bağlamla etkileşim halindedir.

Eğitim kademesi ve türü açısından bakıldığında, bir geçerlilik göze çarpmaktadır. Walter ve Hazan-Liran (2025) ile Hazan-Liran ve Karni-Vizer (2024), özel eğitim öğretmenlerinin normal eğitim öğretmenlerine göre daha yüksek stres altında olmalarına rağmen, psikolojik sermaye düzeyleri açısından gruplar arasında fark olmadığını saptamıştır. Bu durum, psikolojik sermayenin branştan bağımsız olarak, her öğretmenin ihtiyaç duyduğu temel bir "insani" kaynak olduğunu ve dışsal koşullar ne kadar zorlu olursa olsun (özel eğitim gibi), içsel kaynakların koruyuculuğunun devam ettiğini göstermektedir.

Bu sistematik derleme, öğretmen tükenmişliği ile mücadelede ek stratejilere ihtiyaç olduğunu ortaya koymaktadır. Mevcut literatür, sorunun çözümünü sadece dışsal iş yükünü azaltmakta arayan yaklaşımların eksik kaldığını; asıl çözümün öğretmenin içsel "psikolojik bağımsızlık sistemini" güçlendirmekten geçtiğini kanıtlamaktadır. Bu doğrultuda; öğretmenlere yönelik hizmet içi eğitimler, sadece teknik pedagojik formasyonla sınırlı kalmamalı; psikolojik sermaye geliştirme modüllerini içermelidir. Zhang ve Li'nin (2025) bulguları ışığında, okul yönetimleri sadece öğretmeni güçlendirmekle yetinmemeli; psikolojik sermayenin işlevsiz kalmasına neden olan "toksik örgütsel politikaları" ve adaletsiz yönetim pratiklerini elimine etmelidir.

Özellikle özel eğitim öğretmenleri için, psikolojik sermayeyi artırarak "derinlemesine rol yapma" kapasitesini güçlendiren ve "yüzeysel rol yapma"nın yarattığı tükenmişliği engelleyen atölye çalışmaları düzenlenebilir. Bu bulgular ışığında, eğitim politikalarında ve

okul yönetimlerinde öğretmenlerin psikolojik sermayelerini geliştirmeye yönelik müdahalelerin önceliklendirilmesi önerilmektedir. Sadece iş yükünü azaltmak değil, öğretmenlerin umut, iyimserlik, öz-yeterlik ve dayanıklılık düzeylerini artıracak profesyonel gelişim programları, tükenmişliği önlemede en etkili stratejilerden biri olacaktır.

5. KAYNAKÇA

- Akyürek, M. İ. (2020). Öğretmenlerde tükenmişlik. Dicle Üniversitesi Ziya Gökalp Eğitim Fakültesi Dergisi, 37, 35–47. <https://doi.org/10.14582/DUZGEF.2020.138>
- Bandura, A. (1977). Self-efficacy: Toward a unifying theory of behavioral change. *Psychological Review*, 84(2), 191–215. <https://doi.org/10.1037/0033-295X.84.2.191>
- Byrne, B. M. (1994). Burnout: Testing for the validity, replication, and invariance of causal structure across elementary, intermediate, and secondary teachers. *American Educational Research Journal*, 31(3), 645–673.
- Cantürk, R. (2024). Öğretmenlerde tükenmişlik: Çevrimiçi canlı görüşmelerin etkisi [Yüksek lisans tezi, Balıkesir Üniversitesi]. YÖK TEZ.
- Carver, C. S., Scheier, M. F., & Segerstrom, S. C. (2010). Optimism. *Clinical Psychology Review*, 30(7), 879–889. <https://doi.org/10.1016/j.cpr.2010.01.006>
- De Cassai, A., Dost, B., Tulgar, S., & Boscolo, A. (2025). Methodological standards for conducting high-quality systematic reviews. *Biology*, 14(8), 973. <https://doi.org/10.3390/biology14080973>
- Demerouti, E., Bakker, A. B., Nachreiner, F., & Schaufeli, W. B. (2001). The job demands–resources model of burnout. *Journal of Applied Psychology*, 86(3), 499–512. <https://doi.org/10.1037/0021-9010.86.3.499>
- Duygun, T. (2023). Öğretmenlerde tükenmişlik, yalnızlık ve iş yaşamında yalnızlık: İstanbul ili örneği [Yüksek Lisans Tezi, Üsküdar Üniversitesi]. YÖK TEZ
- Keleş, H. N. (2011). Pozitif psikolojik sermaye: Tanımı, bileşenleri ve örgüt yönetimine etkileri. *Organizasyon ve Yönetim Bilimleri Dergisi*, 3(2), 343–350.
- Lourel, M., Gueguen, N., & Mouda, F. (2007). L'évaluation du burnout de Pines : adaptation et validation en version française de l'instrument Burnout Measure Short version (BMS-10). *Pratiques Psychologiques*, 13(3), 353–364. <https://doi.org/10.1016/j.prps.2007.06.001>
- Luthans, F., & Youssef, C. M. (2004). Human, social, and now positive psychological capital management: Investing in people for competitive advantage. *Organizational Dynamics*, 33(2), 143–160. <https://doi.org/10.1016/j.orgdyn.2004.01.003>
- Luthans, F., Avolio, B. J., Avey, J. B., & Norman, S. M. (2007). Positive psychological capital: Measurement and relationship with performance and satisfaction. *Personnel Psychology*, 60(3), 541–572. <https://doi.org/10.1111/j.1744-6570.2007.00083.x>

INTERNATIONAL TOPKAPI CONGRESS VI

Maslach, C. (1998). A Multidimensional Theory of Burnout. Cooper, C.L. (Ed.), Theories of Organizational Stress içinde (s. 68-85). Oxford Press.

Maslach, C., Schaufeli, W. B., & Leiter, M. P. (2001). Job burnout. In N. J. Smelser & P. B. Baltes (Eds.), Annual review of psychology içinde (s. 397-422). Annual Reviews.
<https://doi.org/10.1146/annurev.psych.52.1.397>

Seligman, M. E. P. (2002). Authentic happiness: Using the new positive psychology to realize your potential for lasting fulfillment. Free Press.

Snyder, C. R. (2002). Hope theory: Rainbows in the mind. Psychological Inquiry, 13(4), 249-275.

**TOPLUMSAL CİNSİYET PERSPEKTİFİNDEN YAŞLILIK VE GÜZELLİK ALGISI:
ÇİFTE STANDARTLAR VE BEDEN POLİTİKALARI**
PERCEPTION OF AGING AND BEAUTY FROM A GENDER PERSPECTIVE: DOUBLE
STANDARDS AND BODY POLITICS

Zeynep KURNAZ

Dr. Öğretim Üyesi, Karabük Üniversitesi, Sosyoloji Bölümü

Özkan ÖZTÜRK

Dr. Öğretim Üyesi, Karabük Üniversitesi, Sosyoloji Bölümü

ÖZET

Günümüz tüketim kültüründe güzellik kavramı, ağırlıklı olarak gençlik, zayıflık ve pürüzsüz bir cilt ile özdeşleştirilirken; yaşlılık, estetik bir kayıp, sosyal görünmezlik ve çirkinlik ile ilişkilendirilmektedir. Bu çalışma, yaşlanan bireylerin güzellikle ilişkilendirilmelerini; toplumsal cinsiyet, kültürel normlar ve medya temsilleri ekseninde incelemektedir.

Erkek bedeni işlevsel bir süreç olarak değerlendirilip yaşlanma belirtileri "olgunluk" ve "karizma" olarak yorumlanırken; kadın bedeni estetik bir "nesne" olarak görülmekte ve yaşlanma, kadınlar için doğrudan sosyal değer kaybına yol açmaktadır. Gençlik ideallerinden uzaklaşan kadınlar, özellikle iş piyasasında ve özel yaşamlarında "sosyal görünmezlik" riskiyle karşılaşmakta, bu durumla başa çıkabilmek adına yoğun güzellik işlemlerine başvurmaktadır. Kadınlar "doğal yaşlanma" ile kozmetik müdahalelerle elde edilen "doğal görünüm" arasında bir paradoks ve gerilim yaşamaktadır. Medya ve reklam dili, yaşlanmayı onarılması gereken bir kusur veya savaşılması gereken bir hastalık gibi sunarak bu estetik baskıyı artırmaktadır.

Ayrıca, yaşlı bireylerin içsel benliklerini genç hissederken dış görünümelerini gerçek kimliklerini gizleyen bir "yaşlılık maskesi" olarak algılamaları, beden bütünlüğünde bir çatışmaya işaret etmektedir. Kırıksıklıkların yaşam deneyiminin bir nişanesi olarak kabulü ile fiziksel bir bozulma olarak reddi arasındaki ikilem de bu çatışmanın bir parçasıdır. Sonuç olarak, yaşlılık ve güzellik ilişkisi biyolojik bir süreçten ziyade, kadınların erkeklere kıyasla daha ağır bedel ödediği, "kocakarı hipotezi" gibi damgalayıcı algılarla şekillenen hiyerarşik ve politik bir süreçtir.

Anahtar Kelimeler: Yaşlanmanın Çifte Standardı, Toplumsal Cinsiyet, Yaş Ayrımcılığı

ABSTRACT

In contemporary consumer culture, while the concept of beauty is predominantly equated with youth, thinness, and smooth skin; aging is associated with aesthetic loss, social invisibility, and ugliness. This study examines the association of aging individuals with beauty within the context of gender, cultural norms, and media representations.

While the male body is evaluated as a functional process and signs of aging are interpreted as "maturity" and "charisma," the female body is viewed as an aesthetic "object," and aging leads to a direct loss of social value for women. Women diverging from youth ideals face the risk of

"social invisibility," particularly in the labor market and their private lives, and resort to intensive beauty practices to cope with this situation. Women experience a paradox and tension between "natural aging" and a "natural look" achieved through cosmetic interventions. The language of media and advertising exacerbates this aesthetic pressure by presenting aging as a flaw that needs to be repaired or a disease that must be fought.

Furthermore, the fact that aging individuals perceive their external appearance as a "mask of ageing" that conceals their true identities while feeling youthful internally points to a conflict in body integrity. The dilemma between accepting wrinkles as a badge of life experience and rejecting them as physical deterioration is also part of this conflict. In conclusion, the relationship between aging and beauty is a hierarchical and political process shaped by stigmatizing perceptions such as the "crone hypothesis," where women pay a heavier price compared to men, rather than merely a biological process.

Keywords: Double Standard of Aging, Gender, Ageism.

GİRİŞ

Günümüz tüketim kültüründe beden, benliğin bir yansıması ve toplumsal bir proje olarak ele alınmaktadır. Özellikle geç modernitede beden, bireylerin kimliklerini inşa ettikleri bir alan haline gelmiş; gençlik, zayıflık ve pürüzsüz bir cilt güzelliğinin temel ölçütleri olarak kabul edilmiştir. Bu bağlamda yaşlılık, sadece biyolojik bir süreç olmaktan çıkıp, estetik bir kayıp, çirkinlik ve "bedensel bir ihanet" olarak algılanmaya başlanmıştır. Yaşlanan beden, tüketim kültürü içerisinde "gerontofobik" mesajlarla kuşatılmakta ve bireylere sürekli olarak yaşlanma belirtilerini gizlemeleri telkin edilmektedir (Öberg & Tornstam, 1999). Bu çalışma, yaşlanan bireylerin güzellikle ilişkilendirilmelerini; toplumsal cinsiyet, kültürel normlar ve medya temsilleri ekseninde incelemeyi amaçlamaktadır.

YAŞLANMANIN ÇİFTE STANDARDI: NESNE OLARAK KADIN, SÜREÇ OLARAK ERKEK

Yaşlanma deneyimi toplumsal cinsiyetten bağımsız değildir. Araştırmalar, kadınların ve erkeklerin bedenlerine yönelik tutumlarının farklılaştığını göstermektedir. Kadınlar bedenlerini daha çok estetik bir "nesne" olarak değerlendirme eğilimindeyken, erkekler bedenlerini işlevsel bir "süreç" (güç, etkinlik, sağlık) olarak algılamaktadır (Lipowska vd., 2016). Bu durum, kadınların yaşlanma ile gelen fiziksel değişimleri doğrudan bir değer kaybı olarak görmelerine neden olurken, erkeklerin bu değişimleri daha az estetik kaygıyla karşılamasına olanak tanımaktadır (Öberg & Tornstam, 1999).

Sontag'ın "yaşlanmanın çifte standardı" olarak tanımladığı olgu, kadınların yaşla birlikte cinsel ve sosyal çekiciliklerini yitirdiği, erkeklerin ise statü ve güç kazanarak çekiciliklerini koruduğu algısına dayanır (Öberg & Tornstam, 1999). Örneğin, yaşlı erkek yüzleri "olgun" veya "karizma sahibi" olarak nitelendirilebilirken, yaşlı kadın yüzleri genellikle estetik bir çöküş olarak kodlanmakta ve çekicilik sıralamalarında en alt sırada yer almaktadır. "Kocakarı hipotezi" (crone hypothesis) olarak adlandırılan bu durum, yaşlı kadın yüzlerinin diğer tüm yaş ve cinsiyet gruplarına göre en düşük beğeni puanlarını aldığını ortaya koymaktadır (Foos & Clark, 2011).

Bedenin "Nesne" Olarak Algılanması (Kadınlar)

Kadınların bedenlerine yönelik tutumları, bedeni estetik bir nesne olarak görme eğilimi üzerine kuruludur. Kadınlar bedenlerini, dışarıdan izlenen ve her biri bağımsız olarak değerlendirilen statik parçaların (yüz, eller, vücut hatları vb.) bir toplamı olarak görmeye sosyalleştirilirler.

Beden, bir bütünlükten ziyade, başkaları tarafından estetik kriterlere göre yargılanan bir "görüntü"dür. Bu algı nedeniyle, kız çocuklarının ve yetişkin kadınların fiziksel görünüşleri, "benlik" algılarının erkeklere kıyasla çok daha merkezi ve önemli bir parçasını oluşturur (Lipowskaa, vd., 2016). Kadınlar, değerlerinin büyük ölçüde başkalarının onları nasıl gördüğüne bağlı olduğunu öğrenerek büyürler (örneğin oyuncak bebekler ve makyaj malzemeleriyle oynayarak) (Franzoi & Koehler, 1998). Kültürel olarak kadınlar için geçerli olan tek bir güzellik standardı vardır: "kız çocuğu" standardı. Kadınlar yaşlandıkça ve bu gençlik standardından uzaklaştıkça, bedenleri bir "yıkım" veya "çöküş" olarak algılanır. Sontag'a göre, kadınların toplumdaki değeri (güzellik ve cinsel çekicilik) yaşla birlikte azalırken, erkeklerin değeri (başarı ve güç) artar (Öberg & Tornstam, 1999; Saucier, 2004). Bu durum, kadınların yaşlandıkça bedenlerinden daha fazla memnuniyetsizlik duymalarına ve kendilerini acımasızca eleştirmelerine neden olur (Lipowskaa, vd., 2016).

Bedenin "Süreç" Olarak Algılanması (Erkekler)

Erkeklerin bedenlerine yönelik tutumları, estetikten çok işlevselliğe ve eyleme odaklanan bir süreç algısına dayanır. Erkekler bedenlerini işleyen, hareket eden ve bir amaca hizmet eden dinamik bir "süreç" olarak görürler. Odak noktası bedenın nasıl görüldüğü değil, ne kadar etkili çalıştığı, gücü ve yeterliliğidir (Lipowskaa, vd., 2016). Erkekler için kültürün izin verdiği iki güzellik standardı vardır: "oğlan çocuğu" ve "adam". Erkekler, gençliğin pürüzsüz cildini kaybettiklerinde kadınlar gibi yas tutmazlar; çünkü daha ağırbaşlı, pürüzlü ve yapılı "adam" standardı altında da kabul görürler (Saucier, 2004). Bedeni bir süreç olarak görmek, erkeklerin dış görünüşlerine karşı daha az eleştirel olmalarını sağlar. Erkekler yaşlandıkça, bedenleri işlevsel kaldığı ve sağlık sorunları yaşamadıkları sürece, fiziksel görünüşlerinden (kilo artışı veya yaşlanma belirtileri olsa bile) memnuniyet duyabilirler (Lipowskaa, vd., 2016). Sontag'a göre erkeklerin işi "görünmek" değil, "olmak ve yapmaktır"; bu nedenle yaşlanmayla gelen yetkinlik, otonomi ve güç, erkeğin değerini artırır (Saucier, 2004).

Özetle, "nesne olarak kadın" kavramı, kadının değerinin dış görünüşe endekslenmesini ve yaşlanmanın bu değeri tehdit etmesini ifade ederken; "süreç olarak erkek" kavramı, erkeğin değerinin işlevsellik ve güç üzerinden tanımlanmasını ve yaşlanmanın bu nitelikleri (sağlık bozulmadıkça) tehdit etmemesini anlatır (Lipowskaa, vd., 2016).

SOSYAL GÖRÜNMEZLİK VE GÜZELLİK ENDÜSTRİSİ

Gençlik ideallerinden uzaklaşan kadınlar, "sosyal görünmezlik" riskiyle karşı karşıya kalmaktadır. Kırıksıklıklar, gri saçlar ve sarkan bir cilt, kadınların romantik partnerler veya işverenler tarafından "görülmemesine" neden olmaktadır (Öberg & Tornstam, 1999). Birçok kadın, bu görünmezlikle başa çıkmak ve sosyal değerlerini korumak amacıyla saç boyama, makyaj, estetik müdahaleler gibi yoğun "güzellik çalışmaları" yürütmektedir (Hurd Clarke & Griffin, 2008).

Görünmezlik Paradoksu: Görünür Yaşlılık, Görünmez

Yaşlanan kadınlar ilginç bir paradoks yaşarlar. Fiziksel yaşlanma belirtileri (kırıksıklık, gri saç, sarkma) ne kadar görünür hale gelirse, kadınlar sosyal olarak o kadar görünmez hale gelirler. Kadınlar, gençlik ve güzellik standartlarından uzaklaştıkça, toplumda "yaşlı bir teyze" olarak etiketlenmekte ve bireysel kimlikleri yok sayılarak sosyal ortamda fark edilmemeye başlamaktadır. Hurd Clarke ve Griffin (2008)'in yürüttükleri saha çalışmasında bir katılımcı bu durumu, "Eğer genç değilseniz veya genç görünmüyorsanız... görünmez olduğunuzu hissediyorsunuz" şeklinde ifade etmiştir (Hurd Clarke & Griffin, 2008). Aharoni Lir ve Ayalon (2024)'un çalışmalarında ise bazı kadınlar, yaşlılıkta fark edilmek için çok çaba sarf etmeleri

gerektiğini, aksi takdirde "şeffaf yaşlı kadınlara" dönüştüklerini belirtmişlerdir (Aharoni Lir & Ayalon, 2024).

Romantik İlişkilerde ve Sosyal Ortamda Görünmezlik

Görünmezlik hissi, özellikle karşı cinsle olan etkileşimlerde belirginleşir. Yine Hurd Clarke & Griffin (2008)'in çalışmalarında kadınlar, 50 yaşından sonra erkekler tarafından fark edilmediklerini, bir odaya girdiklerinde sanki orada yokmuş gibi davranıldığını belirtmişlerdir. Bir katılımcı, "Tanıştırılıyorum ama adam odanın karşısındaki başka birine (genellikle daha genç bir kadına) bakıyor" diyerek bu durumu özetlemiştir. Güzellik ve estetik çabaları, sadece yeni bir partner bulmak için değil, mevcut partneri daha genç bir kadına kaptırmamak için de bir strateji olarak kullanılır. Kadınlar, yüzlerindeki sarkmalar ve kırışıklıklar nedeniyle partnerlerinin kendilerini arzulamayacağından korkarak estetik müdahalelere başvurmaktadır (Hurd Clarke & Griffin, 2008).

Güzellik Çalışması (Beauty Work) Bir "Zırh" Olarak

Görünmezlikle savaşmak için kadınlar, bedenlerini disipline eden yoğun bir "güzellik çalışması" içine girerler. Bu çalışmalar, yaşlanmanın getirdiği sosyal değer kaybına karşı bir direniş biçimidir. Bu çalışmalar saç boyama ve makyajdan başlayıp; botoks, dolgu, lazer işlemleri ve estetik cerrahiye kadar uzanır (Hurd Clarke & Griffin, 2008; Hurd Clarke & Griffin, 2007). Örneğin, gri saçlar "bakımsızlık" ve "görünmezlik" simgesi olarak algılandığı için saç boyama, kadınların kendilerini "daha var hissetmelerini" sağlayan yaygın bir uygulamadır (Aharoni Lir & Ayalon, 2024; Hurd Clarke & Griffin, 2008). Güzellik çalışmalarının temel amacı, kronolojik yaşı maskeleyerek sosyal olarak geçerli bir "gençlik" illüzyonu yaratmaktır. Kadınlar bu sayede "görünür" kalmayı ve toplumda saygı görmeyi hedeflerler (Hurd Clarke & Griffin, 2008). Birçok kadın, yaşlanma karşıtı (anti-aging) ürünleri kullanmamanın veya yaşlılık belirtilerini gizlememenin "kendini bırakmak/salmak" olarak algılandığını ve bunun ahlaki bir zayıflık sayıldığını düşünerek bu baskıyı içselleştirir (Hurd Clarke & Korotchenko, 2012; Searing & Zeilig, 2017).

Fizyolojik Değişim ve Mücadele

Yaşlanma sürecinde yüzdeki yağ yastıkçıklarının yer değiştirmesi veya erimesi, kemik erimesi ve yerçekimi etkisiyle yüzde sarkmalar ve hacim kayıpları oluşur. Bu durum yüzdeki gençlik üçgeninin (V şekli) tersine dönmesine neden olur. Güzellik çalışmaları (dolgu, yağ enjeksiyonu vb.), bu biyolojik kayıpları telafi ederek kadının yeniden "genç" ve dolayısıyla "görünür" kategorisine girmesini sağlamaya çalışır (Guisantes, 2019).

Sonuç olarak, güzellik çalışmaları, yaşlanan kadınlar için sadece estetik bir tercih değil; sosyal ölüm (görünmezlik), ekonomik kayıp ve romantik reddedilme riskine karşı geliştirilen zorunlu bir hayatta kalma stratejisidir (Hurd Clarke & Griffin, 2008; Hurd Clarke & Korotchenko, 2012). Kadınlar, yaşlılık belirtilerini "görünmez" kılarak, kendilerini sosyal olarak "görünür" kılmaya çalışmaktadır.

MEDYA, TEMSİLLER VE YAŞ AYRIMCILIĞI

Medya, temsiller ve yaş ayrımcılığı arasındaki ilişkidir ve gençliği yücelten kültürel normlar, tüketim kültürü, toplumsal cinsiyet rolleri ve ekonomik çıkarlar ekseninde şekillenmektedir. Medya, yaşlılığı genellikle "başarılı yaşlanma" (tüketim odaklı) ya da "çöküş" (dördüncü yaş) ikiliği üzerinden sunarak yaş ayrımcılığını yeniden üretmektedir.

Gençlik Normu ve Yaşlılığın Görünmezliği

Medya ve reklam dünyasında kadın güzelliği neredeyse sadece genç, zayıf, beyaz ve pürüzsüz bir cilt ile ilişkilendirilirken; yaşlı kadınlar büyük ölçüde görünmezdir veya olumsuz şekilde temsil edilirler (Aharoni Lir & Ayalon, 2024; Searing & Zeilig, 2017). Televizyon programlarında ve reklamlarda yaşlı karakterler, özellikle başrollerde nadiren yer alır. Medyadaki bu eksik temsil, yaşlılığın sosyal olarak değersiz olduğu mesajını güçlendirir (McLean, 2015; Winterich, 2007). Yaşlılar medyada yer aldığında genellikle yalnız, kırılğan, zihinsel engelli veya asexual olarak tasvir edilirler (McLean, 2015). Bu durum, izleyicilerin yaşlılara karşı olumsuz tutumlar geliştirmesine ve yaşlanma korkusunun artmasına neden olur (Lipowskaa, vd., 2016).

Sinemada "Gümüşleşme" ve Üçüncü/Dördüncü Yaş İmgelemi

Son yıllarda, yaşlanan nüfusun ekonomik gücünün fark edilmesiyle birlikte sinemada bir "gümüşleşme" yaşanmaktadır. Bu kavram hem yaşlanan yıldızların görünürlüğünü hem de yaşlı izleyici kitlesinden elde edilen kârı ifade eder. *The Best Exotic Marigold Hotel*, *Mamma Mia!* veya *The Expendables* gibi filmler, yaşlılığı aktif, tüketim odaklı ve hala "işe yarar" bir dönem (üçüncü yaş) olarak sunar. Bu filmler, yaşlılığı bir macera, romantizm ve kendini yeniden keşfetme dönemi olarak göstererek "başarılı yaşlanma" idealini pazarlar. Medya, yaşlılığın fiziksel çöküşünü, bağımlılığını ve ölümle ilişkisini temsil eden "dördüncü yaş"tan kaçınır veya bunu korku unsuru olarak kullanır. Örneğin *The Iron Lady* veya *Iris* gibi demans temalı filmlerde, kadın bedeni zihinsel ve fiziksel çöküşün taşıyıcısı olarak sunulur (Dolan, 2017).

Ünlü Kültürü ve "Başarılı Yaşlanma" Baskısı

Medya, "başarılı yaşlanma" kavramını ünlüler üzerinden bir norm haline getirir. Dergiler ve televizyon programları, yaşlanmayı kişisel çaba ve disiplinle yönetilebilecek bir proje olarak sunar (Green Kuhn, 2008). Jane Fonda veya Helen Mirren gibi ünlüler, yaşlanmaya meydan okuyan modeller olarak sunulurken, bu durum sıradan bireyler üzerinde "yaşlanmama" veya "doğru yaşlanma" baskısı yaratır (Dolan, 2017; Searing, & Zeilig, 2017). Medya, yaşlılığını gizlemeyi başaran (estetik müdahalelerle veya yoğun bakımla) ünlüleri överken; yaşlılık belirtilerini gizleyemeyenleri (örneğin Madonna'nın elleri) acımasızca eleştirir ve bir "başarısızlık" örneği olarak sunar (Dolan, 2017; Searing, & Zeilig, 2017).

Reklam Dili ve Tüketim Kültürü

Reklamlar, yaşlanmayı doğal bir süreçten ziyade "savaşılması" gereken bir hastalık veya kusur olarak çerçeveler. 1990'lardan sonra kozmetik reklamlarındaki dil değişmiş; yaşlanma ile "mücadele etmek", belirtileri "onarmak" ve cildi "korumak" gibi daha agresif ve tıbbi terimler kullanılmaya başlanmıştır. Reklamlar, yaşlanma belirtilerini (kırısklık, sarkma) göstermenin bir tür "kendini bırakmışlık" veya "ahlaki gevşeklik" olduğunu ima eder. Bakımlı görünmek ve yaşlanma karşıtı ürünler kullanmak, kendine saygının bir göstergesi olarak sunulur (Searing, & Zeilig, 2017).

Cinsiyetlendirilmiş Yaş Ayrımcılığı

Medya temsillerinde yaşlanma, kadınlar ve erkekler için farklı sonuçlar doğurur ("Çifte Standart"). Eğlence sektöründe yaşlı kadınlar için bir "gümüş tavan" vardır; 40 yaşından sonra kadın rolleri azalırken, erkekler 60'larında bile başrol oynayabilir ve romantik partner olarak sunulabilir (Saucier, 2004). Kadınların yaşlarına "uygun" giyinmeleri ve davranmaları beklenirken, aynı zamanda genç görünmeleri istenir. Erkekler ise yaşlandıkça "karizmatik" veya "vintage" olarak nitelendirilir ve yaşlılık belirtileri (kır saç, çizgiler) tecrübe ve otorite işareti sayılabilir (Dolan, 2017). Filmlerde yaşlı erkeklerin kendilerinden çok daha genç

kadınlarla eşleşmesi (örneğin Jack Nicholson ve Helen Hunt) normalleştirilirken, yaşlı kadınların cinsel arzuları genellikle yok sayılır veya mizah konusu yapılır (Saucier, 2004).

YAŞLILIK MASKESİ VE BEDEN BÜTÜNLÜĞÜ

Yaşlı bireylerin kendi bedenlerini algılayışlarında bir ikilem söz konusudur. Birçok yaşlı, içsel benliğini genç ve değişmez hissederken, dış görünümünü (aynadaki yansımalarını) gerçek kimliklerini gizleyen bir "yaşlılık maskesi" olarak tanımlamaktadır. Bu durum, bedensel yaşlanma ile öznel gençlik hissi arasında bir çatışmaya işaret eder (Öberg & Tornstam, 1999).

Yaşlılık Maskesi Kavramı

Bu kavram, yaşlanan bireylerin dış görünüşleri (bedenleri) ile içsel benlikleri arasında bir kopuş yaşadıklarını ifade eder. Bireyler yaşlandıkça, dış görünüşleri kırışıklıklar, sarkmalar ve hareket kısıtlılıkları ile değişime uğrar. Ancak, birçok yaşlı birey iç dünyasında kendini hala genç, değişmemiş ve "zamansız" hisseder. Bu durumda, yaşlanan beden, içindeki genç ruhu hapseden veya gizleyen bir "maske" veya "kılık" olarak algılanmaya başlar. Beden, kişinin gerçek kimliğini yansıtmayan, aksine ona ihanet eden bir yapı olarak görülür. Yaşlanmanın trajedisi, bu içsel gençlik hissi ile dışsal biyolojik yaşlanma süreci arasındaki çelişkide yatar (Öberg & Tornstam, 1999).

Zamansız Benlik ve Hissedilen Yaş

Sharon Kaufman'ın "Ageless Self" (Zamansız Benlik) teorisine göre, yaşlılar kendilerini "yaşlı" olarak tanımlamazlar; bunun yerine, fiziksel ve sosyal değişimlere rağmen kimliklerinin sürekliliğini koruduğunu hissederler (Clarke & Warren, 2006; Öberg & Tornstam, 1999). Öberg ve Tornstam (1999)'ın araştırmaları, yaşlı bireylerin (özellikle 35 yaş üstü İsveçlilerin %70'inin) kendilerini kronolojik yaşlarından belirgin şekilde daha genç hissettiklerini ortaya koymuştur (Öberg & Tornstam, 1999). "Ben yaşlı hissetmiyorum" söylemi, aslında toplumsal olarak yaşlılığa yüklenen "hasta, çirkin, bağımlı" gibi negatif etiketlere karşı bir direniş ve protesto biçimidir (Clarke & Warren, 2006). Yaşlılık kültürel olarak "kötü" kodlandığı için, bireyler kendilerini bu kategorinin dışında tutarak (genç hissederek) benlik saygılarını korumaya çalışırlar (Öberg & Tornstam, 1999).

Beden Bütünlüğü ve Kaçış Stratejisi

Yaşlanan bedenin getirdiği negatif imgelerden kaçış stratejisi olarak "zamansız benlik" algısı iki şekilde işler. **Pozitif Kaçışta**, kişi, yaşlılık stereotiplerini reddeder ve kimliğinin sadece bedensel görünümünden ibaret olmadığını vurgulayarak (içsel güzellik, bilgelik, kişilik) bütünlüğünü korur (Hurd Clarke, 2002). **Negatif Kaçış ve Mücadelede ise** bazı bireyler, özellikle "güzellik çalışmaları" (beauty work) ve estetik müdahaleler yoluyla "yaşlılık maskesini" onarmaya veya çıkarmaya çalışırlar (Hurd Clarke & Griffin, 2008; Macia, 2015). Ancak bu çaba, yaşlanmayı bir "hastalık" veya "kusur" olarak gören tüketim kültürü tarafından körüklenir ve kişiyi kendi bedeniyle sürekli bir savaşa sokabilir (Franzoi & Koehler, 1998; Hurd Clarke & Korotchenko, 2012).

Özetle, yaşlılık maskesi kavramı, modern toplumda bireyin "içsel gençliği" ile "dışsal yaşlılığı" arasındaki gerilimi anlatır. Öberg ve Tornstam'ın çalışmaları ise, bireylerin kendilerini genç hissetmelerinin yaygın olduğunu, ancak bunun her zaman bedenle travmatik bir kopuş anlamına gelmediğini; aksine yaşla birlikte gelen bir kabullenme ve bütünleşme sürecinin de mümkün olduğunu göstermektedir.

SONUÇ

Yaşlılık ve güzellik ilişkisi, biyolojik bir süreçten ziyade, kültürel normlar ve piyasa dinamikleriyle şekillenen politik bir süreçtir. Kadınlar, "başarılı yaşlanma" söylemleri altında, gençlik standartlarına uymaları için sürekli bir baskı altında tutulmakta ve bu süreçte erkeklerle kıyasla daha ağır bir estetik ve ekonomik bedel ödemektedirler (Hurd Clarke & Griffin, 2008). Güzellik algısı, yaşlı kadınları "görünmez" kılarak veya onları sürekli bir bakım emeğine zorlayarak toplumsal cinsiyet eşitsizliklerini yeniden üretmektedir. Sonuç olarak, yaşlılıkta güzellik, sadece estetik bir tercih değil, aynı zamanda bir sosyal varoluş ve kimlik mücadelesidir.

KAYNAKÇA

- Aharoni Lir, S., & Ayalon, L. (2024). Beauty work or beauty care? Women's perceptions of appearance in the second half of life. *Journal of Women & Aging*, 36(3), 256–271.
- Clarke, A., & Warren, L. (2006). Growing older—the good, the bad and the ugly: Subjective views of aging. *International Journal on Disability and Human Development*, 5(1), 61–67.
- Dolan, J. (2017). *Contemporary cinema and 'old age': Gender and the silvering of stardom*. Palgrave Macmillan.
- Foos, P. W., & Clark, M. C. (2011). Adult age and gender differences in perceptions of facial attractiveness: Beauty is in the eye of the older beholder. *The Journal of Genetic Psychology*, 172(2), 162–175.
- Franzoi, S. L., & Koehler, V. (1998). Age and gender differences in body attitudes: A comparison of young and elderly adults. *International Journal of Aging and Human Development*, 47(1), 1–10.
- Green Kuhn, M. A. (2008). *The Eye Of Beauty: Creating A Place For Elite And Aging Elders* [PhD Dgree]. The University Of Arizona.
- Guisantes, E. (2019). Beauty and Aging. In H. Pinto, J. Fontdevila (Ed.), *Regenerative Medicine Procedures for Aesthetic Physicians* (pp. 33-43). Springer.
- Hurd Clarke, L. (2002). Beauty in later life: Older women's perceptions of physical attractiveness. *Canadian Journal on Aging*, 21(3), 429–442.
- Hurd Clarke, L., & Griffin, M. (2007). The body natural and the body unnatural: Beauty work and aging. *Journal of Aging Studies*, 21(3), 187–201.
- Hurd Clarke, L., & Griffin, M. (2008). Visible and invisible ageing: Beauty work as a response to ageism. *Ageing & Society*, 28, 653–674.
- Hurd Clarke, L., & Korotchenko, A. (2012). Doing beauty: Women, ageing and identity. In V. Ylännä (Ed.), *Representing ageing: Images and identities* (pp. 103–114). Palgrave Macmillan.
- Lipowska, M., Lipowski, M., Olszewski, H., & Dykalska-Biecka, D. (2016). Gender differences in body-esteem among seniors: Beauty and health considerations. *Archives of Gerontology and Geriatrics*, 67, 160–170.
- Macia, E., Lahmam, A., Baali, A., & Boëtsch, G. (2015). Perceptions of body and aging. *Anthropology & Aging*, 36(2), 1–16.
- McLean, Meghan C. (2015). *Gender and Ageism: The Role of Aesthetic Preferences in the Aging Double Standard* [Degree of Master of Science]. The State University of New Jersey.
- Öberg, P., & Tornstam, L. (1999). Body images among men and women of different ages. *Ageing and Society*, 19, 629–644.
- Saucier, M. G. (2004). Midlife and beyond: Issues of appearance. *Journal of Aging Studies*, 18(4), 421–437.

INTERNATIONAL TOPKAPI CONGRESS VI

- Searing, C., & Zeilig, H. (2017). Fine lines: Cosmetic advertising and the perception of ageing female beauty. *International Journal of Ageing and Later Life*, 11(1), 7–36.
- Winterich, J. (2007). Aging, Femininity, and the Body: What Appearance Changes Mean to Women with Age. *Gend. Issues* 24, 51–69.

INTERNATIONAL TOPKAPI CONGRESS VI

January 9-11, 2026 / Istanbul

İLGİLİ MAKAMA

4. Uluslararası **Topkapı** Bilimsel Araştırmalarda Güncel Gelişmeler Kongresi 9-11 Ocak 2026 tarihleri arasında İstanbul, Türkiye’de (çevrimiçi ve çevrimdışı olarak) 18 farklı ülkenin akademisyen/araştırmacılarının katılımıyla gerçekleşmiştir. Kongre 16 Ocak 2020 Akademik Teşvik Ödeneği Yönetmeliğine getirilen “*Tebliğlerin sunulduğu yurt içinde veya yurt dışındaki etkinliğin uluslararası olarak nitelendirilebilmesi için Türkiye dışında en az beş farklı ülkeden sözlü tebliğ sunan konuşmacının katılım sağlaması ve tebliğlerin yarından fazlasının Türkiye dışından katılımcılar tarafından sunulması esastır.*” değişikliğine uygun düzenlenmiştir.

Bilgilerinize arz edilir,

Saygılarımla



Dr. Viola MAKHZOUM
Head of Organizing Congress



İKSAD ENSTİTÜSÜ

Çankaya – Ankara

06-146-071

Konu : Kongre Düzenlenmesi
Sayı : BSE-2

5 Aralık 2025

İLGİLİ KURUMA

İçişleri Bakanlığı tarafından tahsis edilen 06-146-071 tescil kodu ile Tüzel Kişiliğe sahip olan İKSAD Enstitüsü 5253 sayılı kanuna uygun olarak “Bilimsel araştırmalar ve akademik çalışmalar” alanında ulusal ve uluslararası düzeyde faaliyetlerini yürütmektedir.

Kurumumuzun Yönetim Kurulu 10 Nisan 2025 tarihinde saat 10.30’da “Bilimsel Diplomasi Projesi” görüşmeleri ile “Bilimsel Kongreler Düzenlenmesi” gündemleri ile toplanmış ve alınan (2 numaralı) karara istinaden aşağıda detayları yazılı olan bilimsel etkinliğin düzenlenmesine ve etkinliğe ilişkin resmi görevlendirme konusunda karar vermiştir.

Bilgi ve gereğini rica ederim



Dr. Mustafa Latif EMEK
Yönetim Kurulu adına

Etkinlik Adı: 6. ULUSLARARASI

6. ULUSLARARASI TOPKAPI BİLİMSEL ARAŞTIRMALARDA GÜNCEL
GELİŞMELER KONGRESİ

Etkinlik Tarihi ve Yeri: 9-11 Ocak 2026, İstanbul

DÜZENLEME KURULU

Dr. Bülent BAYRAKTAR - Bayburt Üniversitesi
Dr. Froilan Mobo - Philippine Merchant Marine Academy
Dr. Ethem İlhan ŞAHİN - Adana Alparslan Türkeş Bilim ve Teknoloji Üniversitesi
Dr. Violla MAKHZOUM - Islamic University of Lebanon
Dr. Terane NAGIYEVA - Azerbaycan Devlet Pedagoji Üniversitesi
Dr. Metanet Şahaliyeva - ANAS, Institute of Manuscripts named after Muhammad Fuzuli
Dr. Mehmet Kadri AKYÜZ - Dicle Üniversitesi

Etkinlik linki: <https://www.izdas.org/topkapi>

